

SURVEY
Scale 1:625

- NOTE:**
- 1 No vehicle crossing or stockpiling of material on vegetation buffer.
 - 2 All existing vegetation will be retained outside the construction site.
 - 3 Clean sediments from footpaths, driveways & roads daily.
 - 4 Roof drainage via sealed pipeline to street gutter on roof completion.
 - 5 All sediment retaining structures to be cleaned on reaching 50% storage capacity.
 - 6 All sedimentation control structures to be inspected & maintained by site manager daily.

GENERAL NOTES

- 1 ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF COUNCIL, THE BUILDING CODE OF AUSTRALIA AND CURRENT AUSTRALIAN STANDARDS.
- 2 ALL DIMENSIONS AND LEVELS TO BE CONFIRMED PRIOR TO CONSTRUCTION.
- 3 REPORT ANY DISCREPANCIES TO THE DESIGNER.
- 4 DO NOT SCALE OFF THESE DRAWINGS.
- 5 THESE PLANS ARE TO BE READ TOGETHER WITH THE ENGINEERS DRAWINGS AND SPECIFICATIONS.
- 6 SCALES APPLY TO SHEET SIZE SHOWN IN THE TITLE.
- 7 THE BUILDER IS TO CHECK ALL FLOOR, CEILING AND ROOF LEVELS TO ENSURE THAT THE FINISHED ROOF HEIGHT DOES NOT EXCEED THE DA APPROVED RL & HEIGHT LIMIT.
- 8 A REGISTERED SURVEYOR IS TO SET OUT THE BUILDINGS, & CONFIRM ALL LEVELS.

- EXISTING SHRUB/ TREE TO REMAIN
- EXISTING SHRUB/ TREE TO BE REMOVED

- WASTE BIN DURING CONSTRUCTION ONLY
- 1.8m SQ x 1.2m HIGH SHADE CLOTH LINED AREA WITH LID AND STAR PICKETS DURING CONSTRUCTION ONLY

THIS PROPERTY IS AFFECTED BY BUSHFIRE.
Construction to comply with the Bushfire Level detailed in the approved DA and in accordance with PBP 2019 & AS 3959-2018



A	04/07/25 - EXTERNAL COLOURS, CARPARKING ETC.
ISSUE	DETAILS



SORENSEN
DESIGN & PLANNING

S

CONTACT DETAILS
Ph: (02) 4984 9955
E: reception@sorensendesign.com.au
W: www.sorensendesign.com.au


Suite 5/10 Yacaaba Street
Nelson Bay NSW 2315

PROJECT: PROPOSED DETACHED DWELLING AT LOT 5; DP 1241629 41 MILL CREEK ROAD, STROUD
CLIENT: MEANS
TITLE: SITE PLAN
FILE 2503682 DATE: 4/07/2025 SHEET: 1 OF 6
THESE PLANS ARE SUBJECT TO COPYRIGHT



GROUND FLOOR PLAN

1:100



MEZZANINE FLOOR PLAN

THIS PROPERTY IS AFFECTED BY BUSHFIRE.
Construction to comply with the Bushfire Level
detailed in the approved DA and in accordance
with PBP 2019 & AS 3959-2018



A	04/07/25 - EXTERNAL COLOURS, CARPARKING ETC.
ISSUE	DETAILS

SORENSEN
DESIGN & PLANNING



CONTACT DETAILS
Ph: (02) 4984 9955

E: reception@sorensendesign.com.au
W: www.sorensendesign.com.au

Suite 5/10 Yacaaba Street
Nelson Bay NSW 2315


PROJECT: **PROPOSED DETACHED DWELLING**
AT LOT 5; DP 1241629
41 MILL CREEK ROAD, STROUD

CLIENT: **MEANS**

TITLE: **FLOOR PLANS**

FILE: **2503682** DATE: **4/07/2025** SHEET: **2** OF **6**

THESE PLANS ARE SUBJECT TO COPYRIGHT



NORTH ELEVATION
1:100 ALL LEVELS ASSUMED

MATERIALS LEGEND

ROOF - COLORBOND 'CUSTOM ORB' METAL ROOF SHEETING

SELECT HORIZONTAL JAMES HARDIE CLADDING


WINDOWS AND DOORS - ALUMINIUM FRAMED

COLORBOND 'QUAD' GUTTER & FASCIA

COLORBOND - DUNE
WINDOWS, GARAGE DOOR,
DOWNPIPES, POSTS

COLORBOND - JASPER
WALL SHEETING

COLORBOND - BASALT
ROOF SHEETING, GUTTER & FASCIA



SOUTH ELEVATION
1:100 ALL LEVELS ASSUMED

THIS PROPERTY IS AFFECTED BY BUSHFIRE.
Construction to comply with the Bushfire Level
detailed in the approved DA and in accordance
with PBP 2019 & AS 3959-2018



SORENSEN
DESIGN & PLANNING



CONTACT DETAILS
Ph: (02) 4984 9955

E: reception@sorensendesign.com.au
W: www.sorensendesign.com.au

Suite 5/10 Yacaaba Street
Nelson Bay NSW 2315


PROJECT: **PROPOSED DETACHED DWELLING**
AT LOT 5; DP 1241629
41 MILL CREEK ROAD, STROUD

CLIENT: **MEANS**


TITLE: **ELEVATIONS**

FILE: **2503682** DATE: **4/07/2025** SHEET: **3** OF **6**

THESE PLANS ARE SUBJECT TO COPYRIGHT





EAST ELEVATION
1:100 ALL LEVELS ASSUMED



WEST ELEVATION
1:100 ALL LEVELS ASSUMED

MATERIALS LEGEND



SECTION A-A
1:100 ALL LEVELS ASSUMED

THIS PROPERTY IS AFFECTED BY BUSHFIRE.
Construction to comply with the Bushfire Level
detailed in the approved DA and in accordance
with PBP 2019 & AS 3959-2018



SORENSEN
DESIGN & PLANNING



CONTACT DETAILS
Ph: (02) 4984 9955

E: reception@sorensendesign.com.au
W: www.sorensendesign.com.au

Suite 5/10 Yacaaba Street
Nelson Bay NSW 2315

PROJECT: **PROPOSED DETACHED DWELLING**
AT LOT 5; DP 1241629
41 MILL CREEK ROAD, STROUD

CLIENT: **MEANS**

TITLE: **ELEVATIONS & SECTION A-A**

FILE: **2503682**

DATE: **4/07/2025**

SHEET: **4** OF **6**

THESE PLANS ARE SUBJECT TO COPYRIGHT

A3

BASIX™ Certificate

Building Sustainability Index
www.planningportal.nsw.gov.au/development-and-assessment/basix

Single Dwelling

Certificate number: 1799079S

This certificate confirms that the proposed development will meet the NSW government's requirements for sustainability, if it is built in accordance with the commitments set out below. Terms used in this certificate, or in the commitments, have the meaning given by the document entitled "BASIX Definitions" dated 10/09/2020 published by the Department. This document is available at www.planningportal.nsw.gov.au/definitions

Secretary
Date of issue: Tuesday, 10 June 2025
To be valid, this certificate must be submitted with a development application or lodged with a complying development certificate application within 3 months of the date of issue.



Project summary		
Project name	2503682 - Means	
Street address	41 MILL CREEK Road STROUD 2425	
Local Government Area	Mid-Coast Council	
Plan type and plan number	Deposited Plan DP1241629	
Lot no.	5	
Section no.	-	
Project type	dwelling house (detached)	
No. of bedrooms	1	
Project score		
Water	✔ 44	Target 40
Thermal Performance	✔ Pass	Target Pass
Energy	✔ 71	Target 70
Materials	✔ -24	Target n/a

Certificate Prepared by	
Name / Company Name: The Trustee for Sorensen Design & Planning Trust	
ABN (if applicable):	

BASIX Department of Planning, Housing and Infrastructure www.basix.nsw.gov.au Version: 4.03 / EUCALYPTUS_03_01_0 Certificate No.: 1799079S Tuesday, 10 June 2025 page 1/12

Description of project

Project address		Assessor details and thermal loads	
Project name	2503682 - Means	NatHERS assessor number	n/a
Street address	41 MILL CREEK Road STROUD 2425	NatHERS certificate number	n/a
Local Government Area	Mid-Coast Council	Climate zone	n/a
Plan type and plan number	Deposited Plan DP1241629	Area adjusted cooling load (MJ/ m²·year)	n/a
Lot no.	5	Area adjusted heating load (MJ/ m²·year)	n/a
Section no.	-		
Project type		Project score	
Project type	dwelling house (detached)	Water	✓ 44 Target 40
No. of bedrooms	1	Thermal Performance	✓ Pass Target Pass
		Energy	✓ 71 Target 70
Site details		Materials	✓ -24 Target n/a
Site area (m²)	3892		
Roof area (m²)	108		
Conditioned floor area (m²)	116.04		
Unconditioned floor area (m²)	12.87		
Total area of garden and lawn (m²)	170		
Roof area of the existing dwelling (m²)	0		

BASIX Department of Planning, Housing and Infrastructure www.basix.nsw.gov.au Version: 4.03 / EUCALYPTUS_03_01_0 Certificate No.: 1799079S Tuesday, 10 June 2025 page 2/12

Schedule of BASIX commitments

The commitments set out below regulate how the proposed development is to be carried out. It is a condition of any development consent granted, or complying development certificate issued, for the proposed development, that BASIX commitments be complied with.

Water Commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
Landscape			
The applicant must plant indigenous or low water use species of vegetation throughout 170 square metres of the site.	✓	✓	
Fixtures			
The applicant must install showerheads with a minimum rating of 3 star (> 7.5 but <= 9 L/min) in all showers in the development.		✓	✓
The applicant must install a toilet flushing system with a minimum rating of 3 star in each toilet in the development.		✓	✓
The applicant must install taps with a minimum rating of 3 star in the kitchen in the development.		✓	
The applicant must install basin taps with a minimum rating of 3 star in each bathroom in the development.		✓	
Alternative water			
Rainwater tank			
The applicant must install a rainwater tank of at least 2000 litres on the site. This rainwater tank must meet, and be installed in accordance with, the requirements of all applicable regulatory authorities.	✓	✓	✓
The applicant must configure the rainwater tank to collect rain runoff from at least 100 square metres of the roof area of the development (excluding the area of the roof which drains to any stormwater tank or private dam).		✓	✓
The applicant must connect the rainwater tank to: • all toilets in the development		✓	✓
• the cold water tap that supplies each clothes washer in the development		✓	✓

BASIX Department of Planning, Housing and Infrastructure www.basix.nsw.gov.au Version: 4.03 / EUCALYPTUS_03_01_0 Certificate No.: 1799079S Tuesday, 10 June 2025 page 3/12

Water Commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
• at least one outdoor tap in the development (Note: NSW Health does not recommend that rainwater be used for human consumption in areas with potable water supply.)		✓	✓

BASIX Department of Planning, Housing and Infrastructure www.basix.nsw.gov.au Version: 4.03 / EUCALYPTUS_03_01_0 Certificate No.: 1799079S Tuesday, 10 June 2025 page 4/12

Thermal Performance and Materials commitments		Show on DA plans	Show on CC/CDC plans & specs	Certifier check
Do-it-yourself Method				
General features				
The dwelling must be a Class 1 dwelling according to the National Construction Code, and must not have more than 2 storeys.	✓	✓	✓	
The conditioned floor area of the dwelling must not exceed 300 square metres.	✓	✓	✓	
The dwelling must not contain open mezzanine area exceeding 25 square metres.	✓	✓	✓	
The dwelling must not contain third level habitable attic room.	✓	✓	✓	
Floor, walls and ceiling/roof				
The applicant must construct the floor(s), walls, and ceiling/roof of the dwelling in accordance with the specifications listed in the table below.	✓	✓	✓	
The applicant must adopt one of the options listed in the tables below to address thermal bridging in metal framed floor(s), walls and ceiling/roof of the dwelling.	✓	✓	✓	
The applicant must show through receipts that the materials purchased for construction are consistent with the specifications listed in the tables below.			✓	
Construction	Area - m ²	Additional insulation required	Options to address thermal bridging	Other specifications
floor - concrete slab on ground, conventional slab.	103.87	nil;not specified	nil	
floor - above habitable rooms or mezzanine, particle board; frame: timber - untreated softwood...	25	nil;not specified	nil	

BASIX Department of Planning, Housing and Infrastructure www.basix.nsw.gov.au Version: 4.03 / EUCALYPTUS_03_01_0 Certificate No.: 1799079S Tuesday, 10 June 2025 page 5/12

Construction	Area - m²	Additional insulation required	Options to address thermal bridging	Other specifications
external wall: framed (metal clad); frame: light steel frame.	all external walls	3.00 (or 3.50 including construction) with one of the measures to address thermal bridging;not specified + reflective foil in the cavity	• Install reflective foil outside the frame to create a minimum 20 mm reflective airspace between frame and veneer, or • Install continuous insulation layer with at least R0.3 on the inside or outside of the frame	wall colour: Medium (solar absorptance 0.48-0.7)
internal wall: plasterboard; frame: timber - untreated softwood.	160	not specified	nil	
ceiling and roof - flat ceiling / pitched roof, framed - metal roof, light steel frame.	108	ceiling: 4.5 (up), roof: foil/sarking with one of the measures to address thermal bridging;ceiling: fibreglass batts or roll; roof: foil/ sarking.	• Install additional R0.5 (up) (or R5 (up) including the additional insulation), or • Install continuous ceiling insulation layer with at least R0.13 above or below the ceiling joists or the bottom chords of the trusses, or • Install two layers of insulation immediately on top of each other, with the top layer of at least R0.5 oriented to cover the ceiling joists or bottom chords of the trusses	roof space ventilation: unventilated; roof colour: medium (solar absorptance 0.48-0.59); 0.5 to ≤ 1.0% of ceiling area uninsulated
Note • Insulation specified in this Certificate must be installed in accordance with the ABCB Housing Provisions (Part 13.2.2) of the National Construction Code.				
Note • If the additional ceiling insulation listed in the table above is greater than R3.0, refer to the ABCB Housing Provisions (Part 13.2.3 (6)) of the National Construction Code.				
Note • In some climate zones, insulation should be installed with due consideration of condensation and associated interaction with adjoining building materials.				
Note • Thermal breaks must be installed in metal framed walls and applicable roofs in accordance with the ABCB Housing Provisions of the National Construction Code.				

BASIX Department of Planning, Housing and Infrastructure www.basix.nsw.gov.au Version: 4.03 / EUCALYPTUS_03_01_0 Certificate No.: 1799079S Tuesday, 10 June 2025 page 6/12



A	04/07/25 - EXTERNAL COLOURS, CARPARKING ETC.	<div><div>SORENSEN</div><div>DESIGN & PLANNING</div></div>	PROJECT: PROPOSED DETACHED DWELLING AT LOT 5; DP 1241629 41 MILL CREEK ROAD, STROUD		
			CLIENT: MEANS		
		<div><div>S</div><div>CONTACT DETAILS Ph: (02) 4984 9955</div><div>E: reception@sorensendesign.com.au W: www.sorensendesign.com.au</div><div>Suite 5/10 Yacaaba Street Nelson Bay NSW 2315</div></div>	TITLE: BASIX		
ISSUE			FILE 2503682 DATE: 4/07/2025 SHEET: 5 OF 6		
DETAILS			THESE PLANS ARE SUBJECT TO COPYRIGHT		

Thermal Performance and Materials commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
Ceiling fans			
The applicant must install at least one ceiling fan in at least one daytime habitable space, such as living room.	✔	✔	✔
• The minimum number and diameter of ceiling fans in a daytime habitable space must be installed in accordance with the ABCB Housing Provisions (Part 13.5.2) of the National Construction Code .	✔	✔	✔

BASIX

Department of Planning, Housing and Infrastructure

www.basix.nsw.gov.au

Version: 4.03 / EUCALYPTUS_03_01_0

Certificate No.: 1799079S

Tuesday, 10 June 2025

page 7/12

Thermal Performance and Materials commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
Glazed windows, doors and skylights			
The applicant must install the windows, glazed doors and shading devices described in the table below, in accordance with the specifications listed in the table. Relevant overshadowing specifications must be satisfied for each glazed window and door.	✔	✔	✔
The dwelling may have 1 skylight (<0.7 square metres) which is not listed in the table.	✔	✔	✔
The following requirements must also be satisfied in relation to each window and glazed door:	✔	✔	✔
• The applicant must install windows and glazed doors in accordance with the height and width, frame and glazing types listed in the table.	✔	✔	✔
• Each window and glazed door must have a U-value no greater than that listed and a Solar Heat Gain Coefficient (SHGC) within the range listed. Total system U values and SHGC must be calculated in accordance with National Fenestration Rating Council (NFRC) conditions.		✔	✔
The applicant must install the skylights described in the table below, in accordance with the specifications listed in the table. Total skylight area must not exceed 3 square metres (the 3 square metre limit does not include the optional additional skylight of less than 0.7 square metres that does not have to be listed in the table).	✔	✔	✔

Glazed window/door no.	Maximum height (mm)	Maximum width (mm)	Frame and glass specification	Shading device (Dimension within 10%)	Overshadowing
North facing					
W01	790.00	1730.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
W02	790.00	1730.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
East facing					
W03	790.00	1730.00	aluminium, single glazed (U-value: ~2.5, SHGC: 0.22 - 0.27)	none	not overshadowed

BASIX

Department of Planning, Housing and Infrastructure

www.basix.nsw.gov.au

Version: 4.03 / EUCALYPTUS_03_01_0

Certificate No.: 1799079S

Tuesday, 10 June 2025

page 8/12

Glazed window/door no.	Maximum height (mm)	Maximum width (mm)	Frame and glass specification	Shading device (Dimension within 10%)	Overshadowing
W04	790.00	590.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
South facing					
W05	790.00	590.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
W06	790.00	1730.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
W07	790.00	1730.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
W08	790.00	1730.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
W09	790.00	1730.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
West facing					
W10	790.00	1730.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
W11	790.00	1730.00	aluminium, single glazed (U-value: <=2.5, SHGC: 0.22 - 0.27)	none	not overshadowed
W12	2100.00	820.00	timber, single glazed (U-value: <=3.0, SHGC: 0.27 - 0.33)	none	not overshadowed

BASIX

Department of Planning, Housing and Infrastructure

www.basix.nsw.gov.au

Version: 4.03 / EUCALYPTUS_03_01_0

Certificate No.: 1799079S

Tuesday, 10 June 2025

page 9/12

Energy Commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
Hot water			
The applicant must install the following hot water system in the development, or a system with a higher energy rating: electric boosted solar with a performance of 15 to 20 STCs or better.	✔	✔	✔
Cooling system			
The applicant must install the following cooling system, or a system with a higher energy rating, in at least 1 living area: 3-phase airconditioning; Energy rating: EER 3.0 - 3.5		✔	✔
The applicant must install the following cooling system, or a system with a higher energy rating, in at least 1 bedroom: 3-phase airconditioning; Energy rating: EER 3.0 - 3.5		✔	✔
Heating system			
The applicant must install the following heating system, or a system with a higher energy rating, in at least 1 living area: 3-phase airconditioning; Energy rating: EER 3.0 - 3.5		✔	✔
The applicant must install the following heating system, or a system with a higher energy rating, in at least 1 bedroom: 3-phase airconditioning; Energy rating: EER 3.0 - 3.5		✔	✔
Ventilation			
The applicant must install the following exhaust systems in the development: At least 1 Bathroom: individual fan, ducted to façade or roof; Operation control: manual switch on/off		✔	✔
Kitchen: individual fan, ducted to façade or roof; Operation control: manual switch on/off		✔	✔
Laundry: natural ventilation only, or no laundry; Operation control: n/a		✔	✔
Artificial lighting			
The applicant must ensure that a minimum of 80% of light fixtures are fitted with fluorescent, compact fluorescent, or light-emitting-diode (LED) lamps.		✔	✔
Natural lighting			
The applicant must install a window and/or skylight in 1 bathroom(s)/toilet(s) in the development for natural lighting.	✔	✔	✔

BASIX

Department of Planning, Housing and Infrastructure

www.basix.nsw.gov.au

Version: 4.03 / EUCALYPTUS_03_01_0

Certificate No.: 1799079S

Tuesday, 10 June 2025

page 10/12

Energy Commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
Other			
The applicant must install a fixed outdoor clothes drying line as part of the development.		✔	
The applicant must install a fixed indoor or sheltered clothes drying line as part of the development.		✔	

BASIX

Department of Planning, Housing and Infrastructure

www.basix.nsw.gov.au

Version: 4.03 / EUCALYPTUS_03_01_0

Certificate No.: 1799079S

Tuesday, 10 June 2025

page 11/12

Legend
In these commitments, "applicant" means the person carrying out the development.
Commitments identified with a ✔ in the "Show on DA plans" column must be shown on the plans accompanying the development application for the proposed development (if a development application is to be lodged for the proposed development).
Commitments identified with a ✔ in the "Show on CC/CDC plans and specs" column must be shown in the plans and specifications accompanying the application for a construction certificate / complying development certificate for the proposed development.
Commitments identified with a ✔ in the "Certifier check" column must be certified by a certifying authority as having been fulfilled, before a final occupation certificate (either interim or final) for the development may be issued.

BASIX

Department of Planning, Housing and Infrastructure

www.basix.nsw.gov.au

Version: 4.03 / EUCALYPTUS_03_01_0

Certificate No.: 1799079S

Tuesday, 10 June 2025

page 12/12



CONTACT DETAILS
Ph: (02) 4984 9955

E: reception@sorensendesign.com.au
W: www.sorensendesign.com.au

Suite 5/10 Yacaaba Street
Nelson Bay NSW 2315

PROJECT: **PROPOSED DETACHED DWELLING
AT LOT 5; DP 1241629
41 MILL CREEK ROAD, STROUD**

CLIENT: **MEANS**

TITLE: **BASIX**

FILE: **2503682**

DATE: **4/07/2025**

SHEET: **6** OF **6**

THESE PLANS ARE SUBJECT TO COPYRIGHT