PROPOSED RESIDENTIAL DEVELOPMENT AT LOT G (NO. 9) MILLER ROAD, CHESTER HILL, NSW

GENERAL NOTES

- 1. THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ARCHITECTURAL, LANDSCAPE AND OTHER CONSULTANTS DRAWINGS AND SPECIFICATIONS AND WITH OTHER SUCH WRITTEN INSTRUCTION AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE ENGINEERS BEFORE PROCEEDING
- ALL DIMENSIONS ARE IN MILLIMETERS & ALL LEVELS ARE IN METERS, UNO (UNLESS
- NO DIMENSION SHALL BE OBTAINED BY SCALING THE DRAWINGS
- EXISTING SERVICES LOCATIONS SHOWN INDICATIVE ONLY. IT IS THE CONTRACTORS RESPONSIBILITY TO LOCATE & LEVEL ALL EXISTING SERVICES PRIOR TO
- ALL BALCONIES AND ROOFS TO BE DRAINED AND TO HAVE SAFETY OVERFLOWS IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARDS. ALL EXTERNAL SLABS TO BE WATERPROOFED
- DURING EXCAVATION WORK, THE STRUCTURE SHALL BE MAINTAINED IN A STABLE AND NO PART SHALL BE OVERSTRESSED.
- ALL WORK IS TO BE UNDERTAKEN IN ACCORDANCE WITH THE DETAILS SHOWN ON THE DRAWINGS & SPECIFICATION.
- EXISTING SERVICES WHERE SHOWN HAVE BEEN PLOTTED FROM SUPPLIED DATA AND SUCH THEIR ACCURACY CAN NOT BE GUARANTEED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH THE LEVEL OF ALL EXISTING SERVICE PRIOR TO THE COMMENCEMENT OF WORK
- ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACK FILLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE LOCAL COUNCIL.
- ALL TRENCH BACK FILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL.
- ON COMPLETION OF STORMWATER INSTALLATION, ALL DISTURBED AREAS MUST BE RESTORED TO ORIGINAL CONDITION, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL AND GRASSED AREAS AND ROAD PAVEMENTS, UNLESS DIRECTED
- 12. CONTRACTOR TO OBTAIN ALL AUTHORITY APPROVALS UNLESS DIRECTED OTHERWISE.

 13. LOCATION OF DOWNPIPES AND FLOOR WASTES ARE INDICATIVE ONLY. DOWN PIPE AND FLOOR WASTE SIZE, LOCATION AND QUANTITY TO BE DETERMINED BY BUILDER & IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARD.
- 14. ANY DISCREPANCIES OR OMISSIONS SHALL BE REFEREED TO THE DESIGN ENGINEER FOR RESOLUTION.
- 15. ALL PITS OR GRATES IN TRAFFICABLE ARES TO BE HEAVY DUTY. ALL GRATES TO HAVE CHILD PROOF LOCKS
- ALL GUTTERS WILL BE FITTED WITH LEAF GUARDS AND SHOULD BE INSPECTED AND CLEANED TO ENSURE LEAF LITTER CANNOT ENTER THE DOWNPIPES
- 17. ENSURE ALL DRAINAGE WORKS ARE AWAY FROM TREE ROOTS.

IMPORTANT NOTES

- ALLOW FOR EMERGENCY OVERFLOW SPLITTER SYSTEM AWAY FROM BUILDING FOR ALL TRAPPED AREAS AND ROOF GUTTER SYSTEM.
- DRIVEWAY GRADES LEVELS TO COMPLY WITH COUNCIL'S ISSUED ALIGNMENT LEVELS (WHERE APPLICABLE), FLOOD ENGINEER'S REQUIREMENTS AND TO COMPLY WITH AUSTRALIAN STANDARDS INCLUDING AS2890: TRAFFIC ENGINEER TO BE CONSULTED WHERE REQUIRED.
- EX. LEVELS HAVE BEEN INTERPOLATED / ASSUMED BASED ON PROVIDED SURVEY INFORMATION; THESE NEED TO BE CONFIRMED ON SITE PRIOR TO CONSTRUCTION AND AUSSIE STRUCTURAL ENGINEERS NOTIFIED OF ANY INCONSISTENCIES WITH WHAT HAS BEEN SHOWN ON THESE SET OF DRAWINGS IMMEDIATELY REFER ARCHITECTURAL/LANDSCAPE ARCHITECTURAL DRAWINGS FOR FINAL INTERNAL LEVELS AND LANDSCAPING RL'S.
- IF THESE LEVELS ARE NOT CONSISTENT WITH THE LEVELS SHOWN ON THESE DRAWINGS, CONTACT AUSSIE STRUCTURAL ENGINEERS IMMEDIATELY TO RESOLVE INCONSISTENCIES WITH THE ARCHITECT/LANDSCAPE ARCHITECT.
- SEWER PEG-OUT TO BE CONDUCTED BY CONTRACTOR PRIOR TO COMMENCEMENT OF ANY WORKS AND AUSSIE STRUCTURAL ENGINEERS TO BE NOTIFIED OF ANY CLASH IMMEDIATELY.
- ADEQUATE ACCESS TO BE PROVIDED TO THE RWT AS PER MANUFACTURER'S REQUIREMENTS. ALLOW MIN. 2% FALL AWAY FROM BUILDING AT ALL ENTRIES.
- SYDNEY WATER TO BE NOTIFIED OF WORKS IN PROXIMITY TO THEIR ASSETS AND NECESSARY APPROVALS TO BE OBTAINED BY DEVELOPER PRIOR TO CONSTRUCTION.
- PIT SURFACE LEVELS SHOWN ON THESE SET OF DRAWINGS MUST BE CHECKED BY CONTRACTOR PRIOR TO CONSTRUCTION AGAINST LANDSCAPE AND ARCHITECTURAL LEVELS AND AUSSIE STRUCTURAL ENGINEERS TO BE NOTIFIED IMMEDIATELY SHOULD ANY DISCREPANCIES BE IDENTIFIED FOR AN ALTERNATIVE DESIGN.
- PROVIDE AGG LINES TO ALL LANDSCAPE AREAS AND CONNECT IT TO THE NEAREST PROPOSED STORMWATER DRAINAGE SYSTEM BY GRAVITY: THESE HAVE NOT BEEN SHOWN ON THE PLANS IN ALL AREAS FOR CLARITY OF THE PLANS; CONTACT AUSSIE STRUCTURAL ENGINEERS IMMEDIATELY FOR ANY CLARIFICATIONS PRIOR TO CONSTRUCTION.
- WORKS PROPOSED IN PROXIMITY OF EX. TREES TO REMAIN MUST BE CONDUCTED USING NON-DESTRUCTIVE HAND DIGGING METHODS: ARBORIST TO BE CONSULTED AND TO APPROVE THE PROPOSED WORKS.
- REFER ARCHITECTURAL/LANDSCAPE ARCHITECTURAL DRAWINGS FOR FINAL DETAILS OF PROPOSED RETAINING WALLS. REFER ARCHITECTURAL DRAWINGS FOR FINAL INTERNAL LEVELS. DRIVEWAY PROFILE AND NUMBER AND LOCATION OF DOWNPIPES AND LANDSCAPING
- RAINWATER TANKS TO BE PLUMBED INTO THE HOUSEHOLD WATER SUPPLY SYSTEM SO THAT ITS WATER IS AUTOMATICALLY USED FOR NON-POTABLE PURPOSES - WORKS INCLUDING RE-USE TO BE AS PER BASIX REQUIREMENTS.
- PROVIDE CLEAN-OUT PIT TO CHARGED LINES AT LOWEST POINT IN THE LINE
- AGG LINES TO ALL RETAINING WALLS AND FOOTINGS TO BE PROVIDED AND CONNECTED TO THE NEAREST PROPOSED STORMWATER DRAINAGE SYSTEM BY GRAVITY.
- ALL CRATES AND LIDS TO BE HINGED TYPE AND FITTED WITH CHILDPROOF LOCKS LIDS WITHIN TRAFFICABLE AREAS TO BE ALSO BIKE SAFE, HEAVY DUTY.
- ADEQUATE ACCOUSTIC MEASURES TO BE PROVIDED FOR PIPEWORK RUNNING WITHIN

DRAINAGE REQUIREMENTS

- D1. ALL WORKMANSHIP AND MATERIAL SHALL BE IN ACCORDANCE WITH CURRENT EDITIONS OF AS2870, AS/NZS 2032 INTALL OF PVC PIPES AND AS/NZS 3500 PLUMBING &
- D2. PLUMBING TRENCHES SHALL BE SLOPED AWAY FROM THE HOUSE AND SHALL BE BACKFILLED WITH CLAY IN THE OP 300mm WITHIN 1.5m OF THE HOUSE. THE CLAY USED FOR BACKFILLING SHALL BE COMPACTED. WHERE PIPES PASS UNDER THE FOOTING SYSTEM. THE TRENCH SHALL BE BACKFILLED WITH CLAY OR CONCRETE TO RESTRICT THE INGRESS OF WATER BENEATH THE FOOTING SYSTEM.
- D3. DRAINAGE SHALL BE CONSTRUCTED TO AVOID WATER PONDING AGAINST OR NEAR THE
- ECAVATION NEAR THE EDGE OF THE FOOTING SYSTEM SHALL BE BACKFILLED IN SUCH A WAY AS TO PREVENT ACESS OF WATER TO THE FOUNDATION.
- WATER RUN-OFF SHALL BE COLLECTED AND CHANNELLED AWAY FROM THE HOUSE
- PENETRATIONS OF THE EDGE BEMS AND FOOTING BEAMS ARE TO BE AVOIDED, BUT WHERE NECESSARY SHALL BE SLEEVED TO ALLOW FOR MOVEMENT.
- D7. CONNECTION OF STORMWATER DRAINS AND WASTE DRAINS SHALL BE INCLUDED


RAINWATER TANK INFORMATION


- RAINWATER TANK TO COLLECT RAIN RUNOFF FROM AT LEAST AS PER BASIX SQUARE METERS OF ROOF AREA
- PROPOSED RAINWATER TANK SIZE AS PER SUPPLIERS SPECIFICATIONS
- RAINWATER TANKS SHALL BE CONNECTED TO MAINS WATER SUPPLY AS BACKUP.
- PUMPS SHALL PROVIDE MINIMUM 150kPa PRESSURE
- RAINWATER TANK TO BE CONNECTED AS PER BASIX REQUIREMENTS.
- A SIGN TO BE INSTALLED STATING "NOT FOR HUMAN CONSUMPTION".
- TANKS TO BE PLUMBED TO TOP-UP FROM THE POTABLE WATER SUPPLY DURING DRY PERIODS WHEN THE TANKS ARE 80% EMPTY.
- NO DIRECT CROSS-CONNECTION WITH THE SYDNEY WATER POTABLE SUPPLY AND AN AIR GAP MAINTAINED ABOVE THE OVERFLOW IN THE TANK.
- ANY OPENINGS SHALL BE MESHED OR SEALED TO PREVENT MOSQUITOS BREEDING AND ENTRY OF ANIMALS OR FOREIGN MATTER.
- RAINWATER TANKS TO BE CLEANED OUT EVERY 6 MONTHS.
- ALL DOWNPIPES TO BE SEALED TO UNDERSIDE OF FIRST FLOOR GUTTER AS DRAINAGE SYSTEM IS CHARGED TO FACILITATE PROPOSED ABOVE GROUND REUSE TANK.
 - THIS SYSTEM TO BE DESIGNED WITH A 'FIRST FLUSH' DIVERSION TO REMOVE ROOF CONTAMINANTS
- REUSE WATER TO BE DIRECTED TO THE FOLLOWING: A. MINIMUM 1 OUTDOOR GARDEN TAP
 - B. ALL CISTERNS (TOILETS)
 - C. COLD WATER SERVICE TO THE CLOTHES WASHER.





EROSION AND SEDIMENT CONTROL NOTES


- THESE NOTES ARE TO BE READ IN CONJUNCTION WITH EROSION AND SEDIMENT CONTROL DETAILS IN THIS DRAWING SET.
- THE CONTRACTOR SHALL IMPLEMENT ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES AS NECESSARY AND TO THE SATISFACTION OF THE RELEVANT LOCAL AUTHORITY PRIOR TO THE COMMENCEMENT OF AND DURING CONSTRUCTION. NO DISTURBANCE TO THE SITE SHALL BE PERMITTED OTHER THAN IN THE IMMEDIATE AREA OF THE WORKS AND NO MATERIAL SHALL BE REMOVED FROM THE SITE WITHOUT THE RELEVANT LOCAL AUTHORITY APPROVAL, ALL EROSION AND SEDIMENT CONTROL DEVICES TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH STANDARDS OUTLINED IN NSW DEPARTMENT OF HOUSING'S "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTIONS".
- PLACE STRAW BALES LENGTH WISE IN A ROW AS PARALLEL AS POSSIBLE TO THE SITE CONTOURS, UNO. BALE ENDS TO BE TIGHTLY BUTTED. BALES ARE TO BE PLACED SO THAT STRAWS ARE PARALLEL TO THE ROW. BALES ARE TO BE PLACED 1.5M TO 2M DOWNSLOPE FROM THE TOP OF THE DISTURBED BATTER, UNO.
- COUNCIL APPROVED FILTER FABRIC TO BE ENTRENCHED 150MM DEEP UPSLOPE TOWARDS DISTURBED SURFACE. FABRIC TO BE A MINIMUM SF2000 OR BETTER. FIX FABRIC TO POSTS WITH WIRE TIES OR AS RECOMENDED WITH MANUFACTURER'S SPECIFICATIONS. FABRIC JOINTS TO HAVE A MINIMUM OF 150MM OVERLAP. WIRE TO BE STRUNG BETWEEN POSTS WITH FILTER FABRIC OVERLAP TO PREVENT SAGGING.
- STABALISED ENTRY/EXIT POINTS TO REMAIN INTACT UNTIL FINISHED DRIVEWAY IS COMPLETE. CONSTRUCTION OF ENTRY/EXIT POINTS TO BE MAINTAINED AND REPAIRED AS REQUIRED SO THAT IT'S FUNCTION IS NOT COMPROMISED. CONSTRUCTION OF ENTRY/EXIT POINT TO BE IN
- ACCORDANCE WITH THE DETAIL CONTAINED WITHIN THIS DRAWING SET.
 ALL DRAINAGE PIPE INLETS TO BE CAPPED UNTIL: DOWNPIPES CONNECTED & PITS CONSTRUCTED AND PROTECTED WITH SILT BARRIER
- PROVIDE AND MAINTAIN SILT TRAPS AROUND ALL SURFACE INLET PITS UNTIL CATCHMENT IS
- REVEGETATED OR PAVED. THE CONTRACTOR SHALL REGULARLY MAINTAIN ALL FROSION AND SEDIMENT CONTROL DEVICES AND REMOVE ACCUMULATED SILT FROM SUCH DEVICES SUCH THAT MORE THAN 60% OF THEIR CAPACITY IS LOST. ALL THE SILT IS TO BE PLACED OUTSIDE THE LIMIT OF WORKS. THE PERIOD
- FOR MAINTAINING THESE DEVICES SHALL BE AT LEAST UNTIL ALL DISTURBED AREAS ARE REVEGETATED AND FURTHER AS MAY BE DIRECTED BY THE SUPERINTENDENT OR COUNCIL. THE CONTRACTOR SHALL IMPLEMENT DUST CONTROL BY REGULARLY WETTING DOWN (BUT NOT SATURATING) DISTURBED AREA.
- LAY 300 WIDE MINIMUM TURF STRIP ON 100 TOPSOIL BEHIND ALL KERB AND GUTTER WITH 1000 LONG RETURNS EVERY 6000 AND AROUND STRUCTURES IMMEDIATELY AFTER BACKFILLING AS PER THE RELEVANT LOCAL AUTHORITY SPECIFICATION.
- THE CONTRACTOR SHALL GRASS SEED ALL DISTURBED AREAS WITH AN APPROVED MIX AS SOON AS PRACTICABLE AFTER COMPLETION OF EARTHWORKS AND REGRADING.
- REVEGETATE ALL TRENCHES IMMEDIATELY LIPON COMPLETION OF BACKFILLING
- PROVIDE AND MAINTAIN SILT TRAPS AROUND ALL SURFACE INLET PITS UNTIL CATCHMENT IS REVEGETATED OR PAVED. TOPSOIL SHALL BE STRIPPED AND STOCKPILED OUTSIDE HAZARD AREAS SUCH AS DRAINAGE LINES. THIS TOPSOIL SHALL BE RESPREAD LATER ON AREAS TO BE REVEGETATED AND STABILISED ONLY, (I.E. ALL FOOTPATHS, BATTERS, SITE REGARDING AREAS, BASINS AND CATCHDRAINS). TOPSOIL SHALL NOT BE RESPREAD ON ANY OTHER AREAS UNLESS SPECIFICALLY INSTRUCTED BY THE SUPERINTENDENT. IF THEY ARE TO REMAIN FOR LONGER THAN ONE MONTH STOCKPILES SHALL BE PROTECTED FROM EROSION BY COVERING THEM WITH A MULCH AND HYDROSEEDING AND, IF NECESSARY, BY LOCATING BANKS OR DRAINS DOWNSTREAM OF A STOCKPILE TO RETARD SILT LADEN RUNOFF.
- WHEN ANY DEVICES ARE TO BE HANDED OVER TO COUNCIL THEY SHALL BE IN CLEAN AND STABLE CONDITION.











						Ğ
						[
						(E
A	ISSUED FOR DA	01.05.23				Į Į
ISSUE	DESCRIPTION	DATE	ISSUE	DESCRIPTION	DATE	,

COPYRIGHT. ALL RIGHTS RESERVED. THESE DRAWINGS, PLANS AND SPECIFICATIONS AND THE COPYRIGHT ARE THE PROPERTY OF AUSSIE STRUCTURAL ENGINEERS AND MUST NOT BE USED, REPRODUCED OR COPIED WHOLLY OR IN PART WITHOUT THE WRITTEN PERMISSION OF AUSSIE STRUCTURAL ENGINEERS.



AUSSIE STRUCTURAL ENGINEERS PTY LTD

ABN 96 619 616 625 Mobile: 0416 747 645

Email: design@aussieseng.com 31 COBHAM STREET, KINGS PARK NSW 2148.

PROPOSED RESIDENCE LOT G (NO. 9) MILLER ROAD CHESTER HILL, NSW FOR - IMRAN

M MODERN DESIGN

BUILDER


STORMWATER NOTES SCALE: 1:100, 1:20 U.N.O. DRAWN BY: CHECK BY: R.V. C.V. JOB NUMBER:


230327MD-H

PAGE

SSUE:

1 OF 3





31 COBHAM STREET, KINGS PARK NSW 2148.

230327MD-H

Α

THE WRITTEN PERMISSION OF

DATE

DATE

ISSUE

DESCRIPTION

ISSUE

DESCRIPTION

AUSSIE STRUCTURAL ENGINEERS.