
PROPOSED DEVELOPMENT (No.57-61) BOURKE STREET, NORTH PARRAMATTA STORMWATER MANAGEMENT PLANS





GENERAL NOTES

THESE PLANS SHALL BE READ IN CONJUNCTION WITH OTHER RELEVANT CONSULTANTS' PLANS, SPECIFICATIONS, CONDITIONS OF DEVELOPMENT CONSENT AND CONSTRUCTION CERTIFICATE 2. REQUIREMENTS. WHERE DISCREPANCIES ARE FOUND ACOR CONSULTANTS (CC) MUST BE CONTACTED IMMEDIATELY FOR VERIFICATION WHERE THESE PLANS ARE NOTED FOR DEVELOPMENT APPLICATION 2 PURPOSES ONLY, THEY SHALL NOT BE USED FOR OBTAINING A 3. CONSTRUCTION CERTIFICATE NOR USED FOR CONSTRUCTION PURPOSES 4 SUBSOIL DRAINAGE SHALL BE DESIGNED AND DETAILED BY THE 3 STRUCTURAL ENGINEER. SUBSOIL DRAINAGE SHALL NOT BE CONNECTED INTO THE STORMWATER SYSTEM IDENTIFIED ON THESE 5. PLANS UNLESS APPROVED BY ACOR CONSULTANTS (CC) 6. STORMWATER CONSTRUCTION NOTES ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH AS/NZS 3500 (CURRENT EDITION) AND THE REQUIREMENTS OF THE LOCAL 7. COUNCIL'S POLICIES AND CODES THE MINIMUM SIZES OF THE STORMWATER DRAINS SHALL NOT BE 2 8. LESS THAN DN90 FOR CLASS 1 BUILDINGS AND DN100 FOR OTHER CLASSES OF BUILDING OR AS REQUIRED BY THE REGULATORY AUTHORITY 9. THE MINIMUM GRADIENT OF STORMWATER DRAINS SHALL BE 1%, UNLESS NOTED OTHERWISE COUNCIL'S TREE PRESERVATION ORDER IS TO BE STRICTLY ADHERED TO. NO TREES SHALL BE REMOVED UNTIL PERMIT IS OBTAINED PUBLIC UTILITY SERVICES ARE TO BE ADJUSTED AS NECESSARY AT 5 THE CLIENT'S EXPENSE ALL PITS TO BE BENCHED AND STREAMLINED. PROVIDE STEP IRONS FOR ALL PITS OVER 1.2m DEEP MAKE SMOOTH JUNCTION WITH ALL EXISTING WORK VEHICULAR ACCESS AND ALL SERVICES TO BE MAINTAINED AT ALL 8 TIMES TO ADJOINING PROPERTIES AFFECTED BY CONSTRUCTION SERVICES SHOWN ON THESE PLANS HAVE BEEN LOCATED FROM INFORMATION SUPPLIED BY THE RELEVANT AUTHORITIES AND FIELD INVESTIGATIONS AND ARE NOT GUARANTEED COMPLETE NOR CORRECT. IT IS THE CLIENT & CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL PRIOR TO CONSTRUCTION 10. ANY VARIATION TO THE WORKS AS SHOWN ON THE APPROVED DRAWINGS ARE TO BE CONFIRMED BY ACOR CONSULTANTS (CC) PRIOR TO THEIR COMMENCEMENT

RAINWATER RE-USE SYSTEM NOTES

- RAINWATER SUPPLY PLUMBING TO BE CONNECTED TO OUTLETS WHERE REQUIRED BY BASIX CERTIFICATE (BY OTHERS)
- TOWN WATER CONNECTION TO RAINWATER TANK TO BE TO THE SATISFACTION OF THE REGULATORY AUTHORITY. THIS MAY **REQUIRE PROVISION OF**
 - 2.1. PERMANENT AIR GAP
 - BACKFLOW PREVENTION DEVICE 2.2.
- NO DIRECT CONNECTION BETWEEN TOWN WATER SUPPLY AND THE RAIN WATER SUPPLY
- AN APPROVED STOP VALVE AND/OR PRESSURE LIMITING VALVE AT THE RAINWATER TANK
- PROVIDE APPROPRIATE FLOAT VALVES AND/OR SOLENOID VALVES TO CONTROL TOWN WATER SUPPLY INLET TO TANK IN ORDER TO ACHIEVE THE TOP-UP INDICATED ON THE TYPICAL DETAIL
- ALL PLUMBING WORKS ARE TO BE CARRIED OUT BY LICENSED PLUMBERS IN ACCORDANCE WITH AS/NZS3500.1 NATIONAL PLUMBING AND DRAINAGE CODE
- PRESSURE PUMP ELECTRICAL CONNECTION TO BE CARRIED OUT BY A LICENSED ELECTRICIAN
- ONLY ROOF RUN-OFF IS TO BE DIRECTED TO THE RAINWATER TANK SURFACE WATER INLETS ARE NOT TO BE CONNECTED
- PIPE MATERIALS FOR RAINWATER SUPPLY PLUMBING ARE TO BE APPROVED MATERIALS TO AS/NZS3500 PART 1 SECTION 2 AND TO BE CLEARLY AND PERMANENTLY IDENTIFIED AS 'RAINWATER'. THIS MAY BE ACHIEVED FOR BELOW GROUND PIPES USING IDENTIFICATION TAPE (MADE IN ACCORDANCE WITH AS2648) OR FOR ABOVE GROUND PIPES BY USING ADHESIVE PIPE MARKERS (MADE IN ACCORDANCE WITH AS1345)
- 10. EVERY RAINWATER SUPPLY OUTLET POINT AND THE RAINWATER TANK ARE TO BE I ABEI ED 'RAINWATER' ON A METALLIC SIGN IN ACCORDANCE WITH AS1319
- 11. ALL INLETS AND OUTLETS TO THE RAINWATER TANK ARE TO HAVE SUITABLE MEASURES PROVIDED TO PREVENT MOSQUITO AND VERMIN ENTRY

OSD CAL ON-SITE ON-SITE EROSIO EROSION EASEME STORMV STORMV

2.

3.

4

5.

6

NORTH PARRAMATTA LOTS 23, 24, 25 & 38 in I

OCOPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified holly or in part without written permission from ACOR Consultants (CC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants oduced or copied w

TIMES

IMPORTANT: THE CONTRACTOR

IS TO MAINTAIN A CURRENT SET

OF "DIAL BEFORE YOU DIG" DRAWINGS ON SITE AT ALL

							Client
I	D	RE-ISSUED FOR DEVELOPMENT APPROVAL	25.11.22	RH	BK	North	BARRY RUSH &
I	С	RE-ISSUED FOR DEVELOPMENT APPROVAL & UPDATED TO SUIT CLIENTS COMMENTS	21.02.22	RH	BK		
	В	ISSUED FOR DEVELOPMENT APPROVAL	14.01.22	RH	BK		& ASSOCIATES
I	A	ISSUED FOR CLIENT REVIEW & COMMENT	23.11.21	RH	BK	1 4 1 9	PTY LTD
I	Issue	Description	Date	Drawn	Approved	$ \setminus /$	
	1 0	1cm at full size					



PARRAMATTA COUNCIL REQUIREMENTS

SITE AREA (m²) 1937.5

ON-SITE DETENTION REFER TO SHEET C4 FOR THE UPPER PARRAMATTA RIVER CATCHMENT TRUST ON-SITE DETENTION DRAINAGE CALCULATIONS

RAINWATER REUSE PROVIDE RAINWATER REUSE TANK AS REQUIRED BY BASIX. RAINWATER REUSE VOLUME PROVIDED = 27m³

WATER QUALITY 4 x SPEL FILTERS PROVIDED TO SATISFY WATER QUALITY MEASURES, REFER TO SHEETS C10 & C11 STORMWATER QUALITY REPORT

SITE DISCHARGE TO PROPOSED EASEMENT AT REAR OF SITE. REFER TO SHEET C2.


DESIGN HAS BEEN PREPARED IN ACCORDANCE WITH PARRAMATTA COUNCIL DESIGN & DEVELOPMENT GUIDELINES, UPPER PARRAMATTA RIVER CATCHMENT TRUST, AR&R AND AS/ANZS 3500


SHEET INDEX							
COVER SHEET & NOTES	SHEET C1						
STORMWATER MANAGEMENT PLAN	SHEET C2						
STORMWATER MANAGEMENT DETAILS SHEET No.1	SHEET C3						
OSD CALCULATION SHEET & MAINTENANCE SCHEDULE	SHEET C4						
ON-SITE DETENTION CHECKLIST SHEET 1 OF 2	SHEET C5						
ON-SITE DETENTION CHECKLIST SHEET 2 OF 2	SHEET C6						
EROSION & SEDIMENT CONTROL PLAN	SHEET C7						
EROSION & SEDIMENT CONTROL NOTES & DETAIL SHEET	SHEET C8						
EASEMENT DRAINAGE ALIGNMENT PLAN	SHEET C9						
STORMWATER QUALITY REPORT SHEET 1 OF 2	SHEET C10						
STORMWATER QUALITY REPORT SHEET 2 OF 2	SHEET C11						

DEVELOPMENT APPLICATION ISSUE NOT FOR CONSTRUCTION

DRAWINGS MUST BE PRINTED IN COLOUR

ELOPMENT	Drawing Title COVER SHEET & NOTES							
	Drawn	Date	Scale A1	Q.A. Check	Date			
Brown St (drainage easement only)	RH	NOV 21	AS NOTED	BAK 18	18.02.22			
	Designed	Project No.		Dwg. No.	Issue			
P 35290	ВК	CC210	392	C1	D			





ELOPMENT	STORMWATER MANAGEMENT DETAILS SHEET No.1				
Brown St (drainage easement only)	Drawn RH	Date NOV 21	Scale A1 AS NOTED	Q.A. Check BAK 1	Date 8.02.22
DP 35290	Designed BK	Project No. CC210	392	Dwg. No. C3	Issue D

Form B1 ¹	DRAINAGE DES			SUB/DA			
No	JRAINAGE DES			306/ <i>D</i> A			
Project:	CC210392	Location:	57-6	1 BOURKE STREE	ET, NTH P	ARRAMATTA	_
Designed By:	RH	Company:	ACOR CO	NSULTANTS (CC)	Pty. Ltd	Phone: (02) 43	24 3499
SITE AREA	0.1937	ha *See Se	ection 3.4.	3 for dual occup	bancy		[A]
•	ment draining thro	-			=_	0 ha	[AA]
See Section 4.1. Basic storage vo	3 for assessment o blume	f external flo 470 x [A]	ows. 0.193	7	=	91.04 m³	[B]
Basic Discharge		0.1937			=	0.0155 m³/s	[C]
Area of site drai	ned to storage		_		=	0.1782 ha	[D]
•	ch as possible and i			f			
	thout written Coun		_			02 0/	[6]
[D]/[A] + [0.1782]/[0.1937] x 100		-	92 %	[E]
	Of contributing are SD adjustment chai		sing [F] ar	ad	-	510.88 72.01 l/s/ha	[F]
	n litres/second/ha		511g [i], ai			72.01 1/3/118	[0]
Determine PSD	= [G] x [D]	72.01	_x	0.1782	=_	12.83 l/s	[H]
Maximum head	to orifice center				=_	<u>1.3</u> m	[K]
Weir flow to sto	orage Q ^{Wein}	^r =CL(H ^{Weir})	1.5	_H Weir	=_	0.15 m	[I]
Select orifice dia	ameter: d=(0.46	$4 \times Q/\sqrt{h}$	⁵ =(0.464>	<[H]/√[K]) ^{0.5}	=_	0.072 m	[1]
Maximum disch	arge				=_	12.83 l/s	[L]
Head for high ea	arly discharge				=_	<u>1.2</u> m	[M]
High early disch	arge {[L]×√[i	M]/[K] }	(min 75	5% of [L])	=_	12.33 l/s	[N]
Approximate m	ean discharge = ([L]] + [N])/2			=	12.58 l/s	[P]
Average dischar	ge/ha = [P]/[D]	= 12.58	_/0.178	32	=_	70.60 l/s/ha	[Q]
	SD adjustment cha		sing [Q]				
	al storage volume p				=_	<u>518.33</u> m³/ha	
	SSR = [R] x [D]	-			=_	<u>92</u> m ³	[S]
Primary storage	proportion =	[S]	x	%	-	m³	[T]
,							
, ,	age proportion =	[S]	x	%	-	m³	[U]

¹ Revised for third edition to include flow from upstream and revised by pass flows

Upper Parramatta River Catchment Trust

OSD STORMWATER MAINTENANCE SCHEDULE

MAINTENANCE ACTION	FREQUENCY	RESPONSIBILITY	PROCEDURE
Drainage Control Pit (DCP)			
Inspect and remove any blockage of orifice	Six monthly	Owner	Remove grate and screen to inspect orifice. See plan for location of DCP
Check attachment of orifice plate to wall of pit (gaps less than 5mm)	Annually	Maintenance Contractor	Remove grate and screen. Ensure plate mounted securely, tighten fixings if required. Seal gaps as required.
Check orifice diameter correct and retains sharp edge	Five yearly	Maintenance Contractor	Compare diameter to design (see Work-As- Executed) and ensure edge is not pitted or damaged
Inspect screen and clean	Six monthly	Owner	Remove grate and screen if required to clean it.
Check attachment of screen to wall of pit	Annually	Maintenance Contractor	Remove grate and screen. Ensure screen fixings secure. Repair as required
Check screen for corrosion	Annually	Maintenance Contractor	Remove grate and examine screen for rust or corrosion, especially at corners or welds.
Inspect flap valve and remove any blockage	Six monthly	Owner	Remove grate. Ensure flap valve moves freely and remove any blockages or debris.
Check attachment of flap valve to wall of pit	Annually	Maintenance Contractor	Remove grate. Ensure fixings of valve are secure
Check flap valve seals against wall of pit	Annually	Maintenance Contractor	Remove grate. Fill pit with water and check that flap seals against side of pit with minimal leakage.
Inspect overflow weir and remove any blockage	Six monthly	Maintenance Contractor	Remove grate and open cover to ventilate underground storage if present. Ensure weir clear o blockages.
Inspect DCP walls (internal and external, if appropriate) for cracks or spalling	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Inspect DCP sump and remove any sediment / sludge	Six monthly	Owner	Remove grate and screen. Remove sediment / sludge build-up and check orifice and flap valve clear.
Inspect grate for damage or blockage	Six monthly	Owner	Check both sides of grate for corrosion (especially corners and welds) damage or blockage.
Inspect return pipe from storage and remove any blockage	Six monthly	Maintenance Contractor	Remove grate and screen. Ventilate underground storage if present. Check orifice and remove any blockages in outlet pipe. Flush outlet pipe to confirm it drains freely. Check for sludge / debris on upstream side of return line.
Storage			
Inspect pit and remove any sediment / sludge in pit	Six monthly	Maintenance Contractor	Remove grate and screen. Remove sediment / sludge build-up.
Inspect internal tank walls (and external, if appropriate) for cracks or spalling	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Inspect and remove any debris / litter / mulch etc. blocking grates	Six monthly	After storm event	Remove blockages from grate and check if pit blocked.
Inspect tank storage are and remove debris / mulch / litter etc. likely to block screens / grates.	Six monthly	Maintenance Contractor	Remove debris and floatable material likely to be carried to grates.
Compare storage volume to volume approved (Rectify if loss > 5%)	Annually	Maintenance Contractor	Compare actual storage available with Work-as- Executed plans. If volume loss is greater than 5%, arrange for reconstruction to replace the volume lost Council to be notified of the proposal.
Inspect storages for subsidence near pits.	Annually	Maintenance Contractor	Check along drainage lines and at pits for subsidence likely to indicate leakages.

COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants (CC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants Pt

						Client
D	RE-ISSUED FOR DEVELOPMENT APPROVAL	25.11.22	RH	BK	North	BAI
С	RE-ISSUED FOR DEVELOPMENT APPROVAL & UPDATED TO SUIT CLIENTS COMMENTS	21.02.22	RH	BK		
В	ISSUED FOR DEVELOPMENT APPROVAL	14.01.22	RH	BK		& A
A	ISSUED FOR CLIENT REVIEW & COMMENT			BK		PTY
Issue	Description	Date	Drawn	Approved		
1 0	1cm at full size 10cm					

ARRY RUSH & ASSOCIATES

rchitect





ELOPMENT	OSD CALCULATION SHEET & MAINTENANCE SCHEDULE					
Brown St (drainage easement only)	Drawn RH	Date NOV 21	Scale A1 AS NOTED	Q.A. Check BAK 18	Date 3.02.22	
P 35290	Designed BK	Project No. CC210	392	Dwg. No. C4	Issue D	

B9. OSD DETAILED DESIGN SUBMISSION This form is to be completed by the stormwater designer and submitted to Council design plant's and any necessary attachments. PROJECT ADDRESS: PROJECT APPLICANT: OSD DESIGNER DETAILS: Company Name: ACOR CONSULTANTS (CC) PTY LTD Address: SUITE 2.01, 4 ILYA AVENUE, ERINA NSW 2250 Telephone No: (02) 43243499 Fax No:	Yes No Yes No Yes / No		OBD DETAILED DESIGN CHECK Image: State of the state of th
Upper Parramatta River Catchment Trust		°2	Upper Parramatta River Catchment Trus

						С
D	RE-ISSUED FOR DEVELOPMENT APPROVAL	25.11.22	RH	BK	North	۱ د
С	RE-ISSUED FOR DEVELOPMENT APPROVAL & UPDATED TO SUIT CLIENTS COMMENTS	21.02.22	RH	BK		15
В	ISSUED FOR DEVELOPMENT APPROVAL	14.01.22	RH	BK		2
A	NIL ISSUE	-	-	-		F
Issue	Description	Date	Drawn	Approved		
1 0	1cm at full size 10cm					1

& ASSOCIATES



rmwater Detention Handbook

LIST

	DESIC		RE	JNCIL /IEW
a ware recent areas	YES	NO	YES	NO
isly	1997 - 19	<	-	Richard and American
r event				
in carly - 110 Analysis AC ATTS ANY - 112 - 2017 AC ATTS	_ N/A	0-	1	ngan and
ions?	NI/A	in va Heztovina Vicensi	1 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201 - 201	
year	N/A	Concernance Concernance	I manta de altra de a	bergen and
	N/A	CONSIGNATION OF THE OWNER		
2010-00-00-00-00-00-00-00-00-00-00-00-00-	a.e.e	1 6 / 1 ADR 140	1.400-t- 1.5. S. S.	male with
ARI				
ermined,	N/A			
vent				
lated				
on an				
d SCP	1	100000 (CONE 1016 (d	18	-1
y affect		Contraction of the second	an a	
d	- D' TOLOR			
hich		100-15 (P-10-1) 1		y
8 65 5 , 36" (N R R R R	Frite at C Anton			Lan Land
t?			UNTERPORT OF STAT	200 Bel 200
J.Y.,	HADCHER SH		20000	
62	And the contract of	10 - 20 - 10	and the second s	Neille Nill mus Neille Charles is
				1
	All and the second	152 HE HADREDHE	2	
?				
been				
en	-7		and a country of a	
NAME AND A		-0-0.08	10-11 - 14 Is -	Long the second second
22_1 100000	baum inte			
than	1			
nted).	Caller Sciences	en anter for tillerad (en	Sale_ata prosport	l Rajoverski Stra Parina
nd	\checkmark			
	<u> 1975 - 198</u>	2005-000-1-0008-1-1-2 	the state of	668.200.200.200 2000-200-200-200-200 2000-200-200-20
ve been	10/20/2020	nera Antonija, A.J.		
	\checkmark		and the second s	707762 (Long-2009
	36-1 - To d	11 - 545 5-		allene and a
	/			
djoining		gen my amarta	some y	
djoining t the				

LOPMENT	Drawing Title OSD CHECKLIST SHEET 1 OF 2				
rown St (drainage easement only)	Drawn RH	Date NOV 21	Scale A1 AS NOTED	Q.A. Check BAK 18	Date 3.02.22
2 35290	Designed BK	Project No. Dwg. No. CC210392 C5		-	lssue D

125

	lention	Handboo	ok				This page last updated December 1999 ${ m B.9-4}$ On-site Stormwater L	etention	Handbo	ok
Where there is more than one OSD system, Questions 18 to 26 a answered separately for each OSD storage system.	ire to b	De						DESIG	<u></u>	
OSD Storage system identifier							21. If an above ground/landscaped storage is specified, answer	YES	NO	3 67
ITEM	DESIG	nan amin san	RE	UNCIL VIEW			Q21(a) to Q21(g), otherwise move to Q22. 21(a) The first 10%-20% of storage is provided in an area able to tolerate frequent inundation(refer Section 4.2.7)			
 The design explicitly shows how all the drained area grades to the storage, including roof gutter overflows (refer Section 6.2) If YES, see Plan No C2. 	YES	NO	YES	NO			21(b) Where the depth of ponding exceeds 600 mm, consideration has been given to whether there are steep drops, and/or a need for steps or 'walk-in' 'walk-out' batters, etc. when deciding if fencing and/or warning signs are required (Refer Sections 4.2.7 & 6.2)		e	1 22000
If NO, see calculations in Attachment E showing how all drainage system components (including all roof gutters, downpipes, collecting pits and pipe systems, etc) have 100 year ARI capacities with 50% blockage factor			- 90/84 F				21(c) The landscaping treatment within the storage area is such that it does not limit storage volumes or provide a significant source of debris loading 21(d) The minimum surface slope is consistent with Section 4.2.7			
19. The invert level of storage is not less than ground level (or top of kerb) at point of connection to external stormwater system	\checkmark						21(e) Subsoil drainage is provided in areas subject to frequent ponding and around the outlet (refer Section 4.2.7)		ko "-las" in	T
If YES, see Plan No. <u>C2.& C3</u> If NO, see explanatory notes in Attachment F	inguarqui Pitali Ingun Quarqui Pitali		anger to and the			Õ	21(f) If the design includes a retaining wall, has it been structurally checked?	And the second second second		
 20. The discharge control pit design is consistent with the principles shown in Figures 4.3, 7.10 and/or 7.11 20(a) The DCP has an open grating type lid (for ease of inspection) 	$\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{\mathbf{$	- <u></u>					 21(g) Does the system have the correct storage? If YES, see stage-storage calculations in Attachment G 22. If a driveway/car-park storage is specified, answer Q22(a) to 			
20(b) The DCP minimum dimensions are consistent with Section 4.2.3 20(c) The floor of the DCP has a localised sump adjacent to the orifice		nan an Arthur III. S					Q22(c), otherwise move to Q23 22(a) The maximum depth is less than or equal to 200mm (refer Section	Bouter Bart (
with level at least 150 mm below the return pipe, (refer Section 4.2.8) 20(d) The return pipe from the storage is at least 150 mm in diameter (refer Section 4.2.8).							4.2.7) 22(b) The minimum transverse slope is 0.7% (refer Section 4.2.7) 22(c) The system has the correct storage	ta kana Arini Prantista in Arini	100.00 00400. 1077-00-0	
20(e) The return pipe flap valve is consistent with Figure 4.3 20(f) If an orifice control is specified, is it consistent with the requirements set out in Section 4.2.3?							If YES, see stage-storage calculations in Attachment G 23. If a structural/underground storage is specified, answer Q 23(a)			
If YES, see: Plan No. C2.& C3 for stainless steel plate specification, thickness and fixing to pit wall							to Q 23(f), otherwise move to Q24 23(a) The dimensions of openings are consistent with Section 4.2.8 23(b) The storage floor has a minimum slope of 0.7% (refer Section 4.2.8)			Territoria
20(g) The overflow weir is fitted with a basket (refer Section 6.3). There is a surface grate above the basket to facilitate inspection and maintenance 20(h) The high early discharge (HED) characteristics are consistent with	00.050.000						23(c) There are sufficient access points for flushing purposes (refer Section 4.2.8)	× ✓		
the requirements set out in Section 4.2.3 If YES, see: Plan No. C2.&C3 for height of discharge to storage			and the second s		*	-	23(d) There are sufficient grated openings for ventilation purposes (refer Section 4.2.8) 23(e) All access points have light weight covers			
relative to permissible site discharge (PSD) Accompanying weir calculations in Attachment E		1	<u></u>			the second second	23(f) The system has the correct storage			t
Plan Noshowing majority of site drainage system connecting to the DCP & the volume of the DCP is small compared to the volume of the storage		2		10.000 - EFP 0 - Charles	p.		If YES, see stage-storage calculations in Attachment G 24. The distribution of storage minimises inconvenience (refer Section 5.1.4)			
20(i) The screen design is consistent with Section 4.2.5 If YES, see: Plan No. C.2. & C.3 for screen type, area and orientation			2. 0.2.0. 0.0000000				25. The Drainage Design Summary sheet has been completed (refer Appendix B1) If YES, see completed sheet in Attachment H			
Plan No. <mark>C2.& C3.</mark> for fabrication note re aperture orientation Plan No.C2.& C3. for fixing and handle details			ville dates for the				26. The Drainage Design Summary sheet details are consistent with the design plans			1
Plan No.2. & C3. showing how all inflows to the DCP are on the upstream side of the screen protecting the orifice					5					
20(j) The outlet pipe from the DCP has a capacity at least twice the PSD (refer Section 4.2.4)	\checkmark					2				
If YES, see calculations in Attachment E Upper Parramatta River Catchment Trust	17. 23. (n 17. 2007 1 1	i (PON)er Sonigi Sinonaet of P	972.079. 4.795.2				Upper Parramatta River Catchment Trust			

rchitect

COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants (CC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants PC).

						Client
D	RE-ISSUED FOR DEVELOPMENT APPROVAL 2			BK	North	
С	RE-ISSUED FOR DEVELOPMENT APPROVAL & UPDATED TO SUIT CLIENTS COMMENTS	21.02.22	RH	BK		DARI
В	ISSUED FOR DEVELOPMENT APPROVAL	14.01.22	RH	BK		& AS
A	NIL ISSUE	-	-	-		PTY LT
Issue	Description	Date	Drawn	Approved		
1 0	10cm		Ì	Ĩ		

RY RUSH & SSOCIATES




ACOR Consultants (CC) Pty Ltd Project Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia T +61 2 4324 3499 CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS | DEVELOPMENT | DE

	DESI	GNER	COU	NCIL /IEW
	YES	NO	YES	NO
swer	Provide the second second			
tolerate	-			
n has teps or arning				
hat it Iebris	let- Xietzi			
Concentration (har "-land" in d	-	196. HTT 197 197 197 197 197 197 197 197 197 197
nding				
lly	and the second second second			
			7-7-7-F0 14 P1 P2	5-5 U (345.24)
Mary Tages of Version				()
a) to	Titlen R.C.R.A.			
Section				
		in the second se		()
207. 200 (C)	Annour a comp		SALK AND	
	2-2-2-2-2-2-2-2-2-2-2-2-2-2-2-2-2-2-2-	WY RIDER O	Contracting where the state	1.3 = 0 d'(-0.00)
r Q 23(a)	1			
8	V.			
on 4.2.8)		and the second second		a Balt ALBERT
er	<			
s (refer	\	Contract to D. Property		
nen officially (or surphy)	\checkmark		72,91,00,000 (0.00)	0 00%(1994), 20 8 4 5%/04/6
C NE CEN /CORRE	. V			
ter program and the				
Section	\checkmark			
(refer				<u>18.8-02.7-1,-78</u>
		angeroore	73	
t with the	<			
	1			

MENT	Drawing Title OSD CHECKLIST SHEET 2 OF 2					
drainage easement only)	Drawn RH	Date NOV 21	Scale A1 AS NOTED	Q.A. Check BAK 18	Date 3.02.22	
	Designed BK	Project No. CC210	392	Dwg. No. C6	lssue D	

25



EROSION AND SEDIMENT CONTROL NOTES

GENERAL INSTRUCTIONS

- THIS SOIL AND WATER MANAGEMENT PLAN IS TO BE READ 7. IN CONJUNCTION WITH OTHER ENGINEERING PLANS RELATING TO THIS DEVELOPMENT
- CONTRACTORS WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE GUIDELINES OF "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION", DEPT OF HOUSING, 1998 (BLUE BOOK)
- ALL SUBCONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN REDUCING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE AREAS.

LAND DISTURBANCE INSTRUCTIONS

- DISTURBANCE TO BE NO FURTHER THAN 5 (PREFERABLY 2) METRES FROM THE EDGE OF ANY ESSENTIAL ENGINEERING ACTIVITY AS SHOWN ON APPROVED PLANS. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE ZONES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- ACCESS AREAS ARE TO BE LIMITED TO A MAXIMUM WIDTH OF 10 METRES THE SITE MANAGER WILL DETERMINE AND MARK THE LOCATION OF THESE ZONES ON-SITE. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE BOUNDARIES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS
- ENTRY TO LANDS NOT REQUIRED FOR CONSTRUCTION OR 6 ACCESS IS PROHIBITED EXCEPT FOR ESSENTIAL THINNING OF PLANT GROWTH
- WORKS ARE TO PROCEED IN THE FOLLOWING SEQUENCE: INSTALL ALL BARRIER AND SEDIMENT FENCING. A)
- WHERE SHOWN ON THE PLAN B) CONSTRUCT THE STABILISED SITE ACCESS
- CONSTRUCT DIVERSION DRAINS AS REQUIRED C)
- INSTALL MESH AND GRAVEL INLETS FOR ANY D) ADJACENT KERB INLETS
- INSTALL GEOTEXTILE INLET FILTERS AROUND ANY E) ON-SITE DROP INLET PITS.
- CLEAR SITE AND STRIP AND STOCKPILE TOPSOIL IN F) LOCATIONS SHOWN ON THE PLAN
- UNDERTAKE ALL ESSENTIAL CONSTRUCTION G) WORKS ENSURING THAT ROOF AND/OR PAVED AREA STORMWATER SYSTEMS ARE CONNECTED TO PERMANENT DRAINAGE AS SOON AS PRACTICABLE
- GRADE LOT AREAS TO FINAL GRADES AND APPLY H) PERMANENT STABILISATION (LANDSCAPING) WITHIN 20 DAYS OF COMPLETION OF CONSTRUCTION WORKS
- REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER THE PERMANENT LANDSCAPING HAS BEEN COMPLETED.
- ENSURE THAT SLOPE LENGTHS DO NOT EXCEED 80 METRES WHERE PRACTICABLE. SLOPE LENGTHS ARE DETERMINED BY SILTATION FENCING AND CATCH DRAIN SPACING
- ON COMPLETION OF MAJOR WORKS LEAVE DISTURBED LANDS WITH A SCARIFIED SURFACE TO ENCOURAGE WATER INFILTRATION AND ASSIST WITH KEYING TOPSOIL LATER

SITE MAINTENANCE INSTRUCTIONS

- THE SITE SUPERINTENDENT WILL INSPECT THE SITE AT LEAST WEEKLY AND AT THE CONCLUSION OF EVERY STORM EVENT TO:
- ENSURE THAT DRAINS OPERATE PROPERLY AND A) TO EFFECT ANY NECESSARY REPAIRS.
- B) REMOVE SPILLED SAND OR OTHER MATERIALS FROM HAZARD AREAS, INCLUDING LANDS CLOSER THAN 5 METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS ESPECIALLY WATERWAYS AND PAVED AREAS.
- C) REMOVE TRAPPED SEDIMENT WHENEVER THE DESIGN CAPACITY OF THAT STRUCTURE HAS BEEN EXCEEDED
- ENSURE REHABILITATED LANDS HAVE D) EFFECTIVELY REDUCED THE EROSION HAZARD AND TO INITIATE UPGRADING OR REPAIR AS NECESSARY
- CONSTRUCT ADDITIONAL EROSION AND/OR E) SEDIMENT CONTROL WORKS AS MIGHT BECOME NECESSARY TO ENSURE THE DESIRED PROTECTION IS GIVEN TO DOWNSLOPE LANDS AND WATERWAYS, MAKE ONGOING CHANGES TO THE PLAN WHERE IT PROVES INADEQUATE IN PRACTICE OR IS SUBJECTED TO CHANGES IN CONDITIONS ON THE WORK-SITE OR ELSEWHERE IN THE CATCHMENT
- F) MAINTAIN EROSION AND SEDIMENT CONTROL STRUCTURES IN A FULLY FUNCTIONING CONDITION UNTIL ALL FARTHWORK ACTIVITIES ARE
- COMPLETED AND THE SITE IS REHABILITATED THE SITE SUPERINTENDENT WILL KEEP A LOGBOOK MAKING ENTRIES AT LEAST WEEKLY, IMMEDIATELY BEFORE FORECAST RAIN AND AFTER RAINFALL. ENTRIES WILL INCLUDE:
- THE VOLUME AND INTENSITY OF ANY RAINFALL A) EVENTS.
- THE CONDITION OF ANY SOIL AND WATER B) MANAGEMENT WORKS
- THE CONDITION OF VEGETATION AND ANY NEED TO C) IRRIGATE THE NEED FOR DUST PREVENTION STRATEGIES.
- D) ANY REMEDIAL WORKS TO BE UNDERTAKEN F)
- THE LOGBOOK WILL BE KEPT ON-SITE AND MADE
- AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. IT WILL BE GIVEN TO THE PROJECT MANAGER AT THE CONCLUSION OF THE WORKS.


SEDIMENT CONTROL INSTRUCTIONS

- SEDIMENT FENCES WILL BE INSTALLED AS SHOWN ON THE WASTE CONTROL INSTRUCTIONS 9 PLAN AND ELSEWHERE AT THE DISCRETION OF THE SITE SUPERINTENDENT TO CONTAIN SOIL AS NEAR AS POSSIBLE TO THEIR SOURCE
- SEDIMENT FENCES WILL NOT HAVE CATCHMENT AREAS 10. EXCEEDING 900 SQUARE METRES AND HAVE A STORAGE DEPTH OF AT LEAST 0.6 METRES
- SEDIMENT REMOVED FROM ANY TRAPPING DEVICES WILL BE RELOCATED WHERE FURTHER POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS CANNOT OCCUR
- 12. STOCKPILES ARE NOT TO BE LOCATED WITHIN 5 METRES OF HAZARD AREAS INCLUDING AREAS OF HIGH VELOCITY FLOWS SUCH AS WATERWAYS, PAVED AREAS AND DRIVEWAYS
- WATER WILL BE PREVENTED FROM DIRECTLY ENTERING 13 THE PERMANENT DRAINAGE SYSTEM UNLESS THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR WATER HAS BEEN TREATED BY AN APPROVED DEVICE
- 14. TEMPORARY SEDIMENT TRAPS WILL REMAIN IN PLACE UNTIL AFTER THE LANDS THEY ARE PROTECTING ARE COMPLETELY REHABILITATED.
- 15 ACCESS TO SITES SHOULD BE STABILISED TO REDUCE THE LIKELIHOOD OF VEHICLES TRACKING SOIL MATERIALS ONTO PUBLIC ROADS AND ENSURE ALL-WEATHER ENTRY/EXIT

SOIL EROSION CONTROL INSTRUCTIONS

- 16. EARTH BATTERS WILL BE CONSTRUCTED WITH AS LOW A GRADIENT AS PRACTICABLE BUT NO STEEPER, UNLESS OTHERWISE NOTED, THAN:
 - 2(H):1(V) WHERE SLOPE LENGTH LESS THAN 12 METRES
 - 2.5(H):1(V) WHERE SLOPE LENGTH BETWEEN 12 AND 16 METRES.
 - 3(H):1(V) WHERE SLOPE LENGTH BETWEEN 16 AND 20 METRES.
 - 4(H):1(V) WHERE SLOPE LENGTH GREATER THAN 20 METRES
- ALL WATERWAYS, DRAINS, SPILLWAYS AND THEIR 17 OUTLETS WILL BE CONSTRUCTED TO BE STABLE IN AT LEAST THE 1:20 YEAR ARI, TIME OF CONCENTRATION STORM EVENT.
- 18. WATERWAYS AND OTHER AREAS SUBJECT TO CONCENTRATED FLOWS AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUNDCOVER C-FACTOR OF 0.05 (70% GROUND COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION. FLOW VELOCITIES ARE TO BE LIMITED TO THOSE SHOWN IN TABLE 5-1 OF "MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION", DEPT OF HOUSING 1998 (BLUE BOOK). FOOT AND VEHICULAR TRAFFIC WILL BE PROHIBITED IN THESE AREAS.
- STOCKPILES AFTER CONSTRUCTION ARE TO HAVE A 19. MAXIMUM GROUND-COVER C-FACTOR OF 0.1 (60% GROUND-COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION.
- ALL LANDS, INCLUDING WATERWAYS AND STOCKPILES, 20. DURING CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.15 (50% GROUND COVER) WITHIN 20 WORKING DAYS FROM INACTIVITY EVEN THOUGH WORKS MAY CONTINUE LATER.
- 21 FOR AREAS OF SHEET FLOW USE THE FOLLOWING GROUND COVER PLANT SPECIES FOR TEMPORARY COVER: JAPANESE MILLET 20 KG/HA AND OATS 20 KG/HA
- 22. PERMANENT REHABILITATION OF LANDS AFTER CONSTRUCTION WILL ACHIEVE A GROUND-COVER C-FACTOR OF LESS THAN 0.1 AND LESS THAN 0.05 WITHIN 60 DAYS NEWLY PLANTED LANDS WILL BE WATERED. REGULARI Y UNTIL AN EFFECTIVE COVER IS ESTABLISHED AND PLANTS ARE GROWING VIGOROUSLY, FOLLOW-UP SEED AND FERTILISER WILL BE APPLIED AS NECESSARY REVEGETATION SHOULD BE AIMED AT RE-ESTABLISHING 23
- NATURAL SPECIES, NATURAL SURFACE SOILS SHOULD BE REPLACED AND NON-PERSISTANT ANNUAL COVER CROPS SHOULD BE USED


- ACCEPTABLE BINS WILL BE PROVIDED FOR ANY 24 CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHING, LIGHTWEIGHT WASTE MATERIALS AND LITTER. CLEARANCE SERVICES WILL BE PROVIDED AT LEAST WEEKLY, DISPOSAL OF WASTE WILL BE IN A MANNER APPROVED BY THE SITE SUPERINTENDENT.
- 25. ALL POSSIBLE POLLUTANT MATERIALS ARE TO BE STORED WELL CLEAR OF ANY POORLY DRAINED AREAS, FLOOD PRONE AREAS, STREAMBANKS, CHANNELS AND STORMWATER DRAINAGE AREAS. STORE SUCH MATERIALS IN A DESIGNATED AREA UNDER COVER WHERE POSSIBLE AND WITHIN CONTAINMENT BUNDS.
- ALL SITE STAFF AND SUB-CONTACTORS ARE TO BE 26. INFORMED OF THEIR OBLIGATION TO USE WASTE CONTROL FACILITIES PROVIDED
- ANY DE-WATERING ACTIVITIES ARE TO BE CLOSELY 27. MONITORED TO ENSURE THAT WATER IS NOT POLLUTED BY SEDIMENT, TOXIC MATERIALS OR PETROLEUM PRODUCTS
- 28. PROVIDE DESIGNATED VEHICULAR WASHDOWN AND MAINTENANCE AREAS WHICH ARE TO HAVE CONTAINMENT BUNDS



CC210392

C8

D




COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified

						Client
D	RE-ISSUED FOR DEVELOPMENT APPROVAL			BK	North	BARRY
С	RE-ISSUED FOR DEVELOPMENT APPROVAL & UPDATED TO SUIT CLIENTS COMMENTS			BK		
В	ISSUED FOR DEVELOPMENT APPROVAL	14.01.22	RH	BK		& ASSO
A	NIL ISSUE			-		PTY LTD
Issue	Description	Date	Drawn	Approved		
1	1 Crm at full size 10cm					

RUSH & CIATES





1 INTRODUCTION

A CATCHMENT BASED WATER QUALITY MODEL WAS DEVELOPED TO ASSESS THE STORMWATER RUNOFF QUALITY IN ACCORDANCE WITH THE WATER SENSITIVE URBAN DESIGN (WSUD) REQUIREMENTS OF PARRAMATTA DEVELOPMENT CONTROL PLAN PART 3.3.6 AND APPENDIX 7. IN THIS REGARD WE REFER TO THE PRESCRIBED TARGETS TABLED FOLLOWING: TABLE 1 - STORMWATER POLLUTANT REDUCTION TARGETS

STORMWATER POLLUTANT	REDUCTION TARGETS
GROSS POLLUTANT	90%
TOTAL SUSPENDED SOLIDS (TSS)	85%
TOTAL PHOSPHORUS (TP)	60%
TOTAL NITROGEN (TN)	45%

2 STUDY METHODOLOGY

THE OBJECTIVES OF THIS REPORT ARE TO:

- ASSESS THE RUNOFF QUALITY FOR THE UNTREATED POST DEVELOPED SCENARIO AND IDENTIFY STORMWATER QUALITY CONTROLS LIKELY TO IMPACT ON RUNOFF QUALITY.
- ASSESS THE STORMWATER QUALITY FOR THE POST DEVELOPED SCENARIO INCLUDING THE MEASURES PROPOSED TO MEET THE POLLUTANT REMOVAL TARGETS

THE REPORT IS BASED ON THE APPLICATION OF MUSIC SOFTWARE (MODEL FOR URBAN STORMWATER IMPROVEMENT CONCEPTUALISATION). IN THIS REGARD THE MODEL IS DEFINED

AS FOLLOWS:

- A STORMWATER QUALITY MODEL TO CONVERT RAINFALL AND EVAPOTRANSPIRATION INTO RUNOFF.
- ESTIMATION OF STORMWATER FLOW AND POLLUTION GENERATION BY SIMULATING THE PERFORMANCE OF STORMWATER TREATMENT DEVICES INDIVIDUALLY AND AS PART OF A TREATMENT TRAIN.

THE MODEL DEFINES WATER QUALITY PROFILES FOR BOTH TREATED AND UNTREATED POST DEVELOPED SCENARIOS. THE TREATED POST DEVELOPED MODEL INCLUDES PARAMETERS WHICH REPRESENT THE WATER QUALITY MEASURES.

COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified

						Client
D	RE-ISSUED FOR DEVELOPMENT APPROVAL	25.11.22	RH	BK	North	BARRY RUSH &
С	NIL ISSUE	-	-	-		
В	NIL ISSUE	-	-	-		& ASSOCIATES
A	NIL ISSUE	-	-	-		PTY LTD
Issue	Description	Date	Drawn	Approved		
1 0	1cm at full size		ļ			

STORMWATER QUALITY REPORT

3 STORMWATER QUALITY MODELLING

3.1 GENERAL

THE FOLLOWING PARAMETERS WERE ASSESSED FOR THE HYDROLOGICAL MODELLING ASSOCIATED WITH THE CATCHMENT.

- RAINFALL/RUNOFF AND EVAPOTRANSPIRATION
- SUB CATCHMENT DIVERSIONS. •
- LAND USE (PERVIOUS AND IMPERVIOUS) •

3.2 RAINFALL/RUNOFF AND EVAPOTRANSPIRATION

THE MUSIC MODEL WAS FORCED WITH 6 MINUTE RAINFALL DATA FROM THE PARRAMATTA NORTH (MASONS DRIVE) GAUGE (ID 066124) FOR THE PERIOD 25 DECEMBER 1984 TO 30 DECEMBER 2007.

DAILY AVERAGE PET VALUES WERE NOT AVAILABLE FOR STATION ID 066124 AND WERE SOURCED FROM THE BUREAU OF METEOROLOGY FOR THE NEIGHBOURING PROSPECT RESERVOIR GAUGE (ID 067019). THE DETAILS ARE SUMMARISED IN TABLE 3.1 AND 3.2

TABLE 3.1 - DETAILS OF DAILY RAINFALL DATA							
STATION	NAME	PERIOD	TIMESTEP				
066124	PARRAMATTA NORTH (MASONS DRIVE)	25/12/1984-30/12/2007	6 min				

TABLE 3.	TABLE 3.2 - SUMMARY OF POTENTIAL EVAPOTRANSPIRATION (PET)							
JAN	FEB	MAR	APR	MAY	JUN			
170.5	131.6	120.9	87	62	48			
JUL	AUG	SEP	OCT	NOV	DEC			
51	77.5	108	136.4	155	173.6			

3.3 CATCHMENT DEFINITION

IDENTIFIED IN TABLE 3.3.

TABLE 3.3

SUB CATCHME

ROOF TO RV

AREA TO OS

4 MUSIC MODEL

TABLE 4.1

RAINFALL THE

SOIL STORAGE

SOIL INITIAL S

FIELD CAPACI

INFILTRATION

INFILTRATION

INITIAL DEPTH

DAILY RECHA

DAILY BASEFL

DAILY DEEP S



THE POST DEVELOPED CATCHMENT CHARACTERISTICS ARE

- POST DEVELOPMENT SUB CATCHMENT DETAILS						
ENT ID	SUB CATCHMENT AREA (ha)	% IMPERVIOUS AREA	% PERVIOUS AREA			
WT	0.072	100	0			
)SD	0.122	47	53			

THE MUSIC MODEL IS BASED ON A 6 min RAINFALL-RUNOFF MODEL IN CONJUNCTION WITH REPRESENTATIVE BASEFLOW AND STORMFLOW EVENT MEAN CONCENTRATIONS (EMCs).

4.1 WATER QUALITY PARAMETERS

THE ADOPTED VALUES OF VARIOUS MUSIC RAINFALL AND RUNOFF PARAMETERS IN ACCORDANCE WITH NSW MUSIC MODELLING GUIDELINES 2015 FOR MEDIUM CLAY ARE SUMMARISED IN TABLE 4.1.

- ADOPTED MUSIC RAINFALL/RUNOFF PARAMETERS					
PARAMETER	VALUE				
IMPERVIOUS AREA PROPERTIES					
RESHOLD (mm/DAY)	1.5 (0.3 ROOFS)				
PERVIOUS AREA PROPERTIES					
GE CAPACITY (mm)	94				
STORAGE (% OF CAPACITY)	25				
CITY (mm)	70				
N CAPACITY COEFFICIENT - a	135				
N CAPACITY EXPONENT - b	4				
GROUNDWATER PROPERTI	ES				
H (mm)	10				
ARGE RATE (%)	10				
LOW RATE (%)	10				
SEEPAGE RATE (%)	0				

Project SENIORS DEVELOPMENT	Drawing Title STORMWATER QUALITY REPORT SHEET 1 OF 2				
57-61 Bourke Street & 10 Brown St (drainage easement only)	Drawn RH	Date NOV 21	Scale A1 AS NOTED		Date 8.02.22
NORTH PARRAMATTA LOTS 23, 24, 25 & 38 in DP 35290	Designed BK	Project No. CC210	392	Dwg. No. C10	lssue D

4.1 WATER QUALITY PARAMETERS CONT.

STORMWATER QUALITY IS CHARACTERISED USING EVENT MEAN CONCENTRATION (EMCs) UNDER STORM AND BASE FLOW CONDITIONS. THE VALUE OF WATER QUALITY PARAMETERS ADOPTED IN THIS STUDY IS SUMMARISED IN TABLE 4.2

TABLE 4.2 - ADOPTED MUSIC WATER QUALITY PARAMETERS								
LAND-USE CATEGORY		Log ₁₀ TSS	og₁₀TSS (mg/L)		Log₁₀TP (mg/L)		Log₀ TN (mg/L)	
		STORM FLOW	BASE FLOW	STORM FLOW	BASE FLOW	STORM FLOW	BASE FLOW	
	MEAN	2.15	1.20	-0.60	-0.85	0.30	0.11	
RESIDENTIAL	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12	
GENERAL URBAN	MEAN	2.20	1.10	-0.45	-0.82	0.42	0.32	
	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12	
	MEAN	1.30	1.10	-0.89	-0.82	0.30	0.32	
ROOFS	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12	

4.2 STORMWATER TREATMENT MEASURES

THE PROPOSED STORMWATER TREATMENT MEASURES INCLUDED

IN THE POST DEVELOPED MODEL ARE AS FOLLOWS:

- 27,000 LITRE RAINWATER TANK (REUSED FOR IRRIGATION)
- 4 x SPELFILTERS (FULL HEIGHT)

THE SCHEMATIC LAYOUT FOR THE POST DEVELOPED MUSIC

MODEL IS DEPICTED IN FOLLOWING FIGURE 1




FIGURE 1 - MUSIC MODEL SCHEMATIC

5 RESULTS & CONCLUSION

BASED ON THE FOREGOING AND THE RESULTS DEPICTED IN TABLE 5.1, THE PROPOSED STORMWATER QUALITY TREATMENT MEASURES MEET THE REQUIRED TARGETS OF THE CITY OF PARRAMATTA. REFER TO CC210392_20221123.SQZ AS PREPARED BY ACOR CONSULTANTS (CC) PTY LTD FOR FURTHER INFORMATION.

TABLE 5.1 - TREATMENT TRAIN EFFECTIVENESS

	Sources	Residual Load	% Reduction
Flow (ML/yr)	1.18	0.803	31.7
Total Suspended Solids (kg/yr)	120	12.9	89.3
Total Phosphorus (kg/yr)	0.261	0.0584	77.6
Total Nitrogen (kg/yr)	2.57	1.04	59.4
Gross Pollutants (kg/yr)	32.2	0	100

COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants (CC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants Pty Ltd.

						Client
D	RE-ISSUED FOR DEVELOPMENT APPROVAL	25.11.22	RH	BK	North	BARRY RUSH &
С	NIL ISSUE	-	-	-		
В	NIL ISSUE	-	-	-		& ASSOCIATES
A	NIL ISSUE	-	-	-		PTY LTD
Issue	Description	Date	Drawn	Approved		
1 0	1cm at full size 10cm		<u> </u>			



hitect

57-61 Bourke Street & 10 Brown St (drainage easement only) NORTH PARRAMATTA LOTS 23, 24, 25 & 38 in DP 35290

STORMWATER QUALITY REPORT SHEET 2 OF 2							
Drawn	Date	Scale A1	Q.A. Check	Date			
RH	NOV 21	AS NOTED		3.02.22			
Designed	Project No.		Dwg. No.	Issue			
BK	CC210	392	C11	D			