

# **ACTIVITY DETERMINATION**

**Project No. BGXWX** 

Conflict of Interest <sup>1</sup>						
In this matter:						
<ol> <li>I have declared any possible conflict of interests (real, potential or perceived) to the Chief Executive Officer, Land &amp; Housing Corporation.</li> <li>I do not consider I have any personal interests that would affect my professional judgement.</li> </ol>						
<ol> <li>I will inform the Chief Executive Officer, Land &amp; Housing Corporation as soon as I become aware of a possible conflict of interest.</li> </ol>						
Signed						
NameEmma Nicholson Dated9 August 2023						

Having regard to the Determination Recommendation Report, the Statement of Compliance and the Review of Environmental Factors for this project addressing matters under Part 5 of the *Environmental Planning and Assessment Act 1979*, I determine that the activity proceed as described below and subject to the identified requirements set out in **Schedule 1**.

SITE IDENTIFICATION						
STREET ADDRESS						
Unit/Street No	Street or property name					
26 and 69-73	Rose Crescent and Bourke Street					
Suburb, town or locality		Postcode				
North Parramatta		2151				
Local Government Area(s)	Real property description (Lot	and DP)				
City of Parramatta	Lots 2, 3 & 4 in DP 215342					
ACTIVITY DESCRIPTION						
Provide a description of the activity Demolition of 3 existing bedsits containing a total of 13 dwellings and associated structures,						
removal of trees, and the construction of 14 independent living seniors housing units comprising 6 x one bedroom and 8 x two bedroom units, with associated landscaping and fencing, at-grade parking for 11 cars, and consolidation into a single lot						

 Conflict of interest includes actual and potential. A conflict of interest includes pecuniary i.e. financial interests to you or a related party or non-pecuniary i.e. benefits to relatives, friends, business associates and personal causes, etc. This includes "related persons" as defined in the Property, Stock and Business Agency Act 2002.

elle. Signed.

Dated....9 August 2023

Emma Nicholson Acting Head of Policy and Innovation Land and Housing Corporation

# SCHEDULE 1

# **Recommended Identified Requirements**

## PART A – Standard Identified Requirements

### THE DEVELOPMENT

The following identified requirements are to ensure that the **seniors housing** activity is carried out in accordance with the plans / documents and any amendments arising from the Review of Environmental Factors under Part 5 of the Environmental Planning & Assessment Act 1979, Section 171 of the Environmental Planning and Assessment Regulation 2021 and the requirements of State Environmental Planning Policy (Housing) 2021

1. The development shall be carried out substantially in accordance with the following plans / documents and as modified below by any of the undermentioned identified requirements:

Title / Name:	Drawing No / Document Ref	Revision / Issue:	Date Idd mm ysaadu	Prepared by:
Architectural Plans		/ issue:	[dd.mm.yyyy]:	
Coversheet	A01 of A17	Rev B	08.12.2022	Barry Rush & Associates Pty Ltd
Site Analysis Plan	A02 of A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Existing Site Plan	A02 of A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Site / Ground Floor Plan	A04 of A17	Rev B	29.11.2022	Barry Rush & Associates Pty Ltd
First Floor Plan	A05 of A17	Rev B	29.11.2022	Barry Rush & Associates Pty Ltd
Roof Plan	A06 of A17	Rev B	29.11.2022	Barry Rush & Associates Pty Ltd
Elevations	A07 of A17	Rev B	29.11.2022	Barry Rush & Associates Pty Ltd
Sections	A07 of A17	Rev B	29.11.2022	Barry Rush & Associates Pty Ltd
Exterior Colour Schedule	A09 Of A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Demolition Plan	A10 of A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Block Analysis Plan	A10 01 A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Shadow Diagrams – Mid	A12 of A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Winter		NevA	23.03.2022	Barry Rusin & Associates Fty Etd
Views from the Sun	A13 of A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Diagrams				
Streetscape Perspectives	A14 of A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Areas of Excavation and Fill	A15 of A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Landscape Data Plan	A16 of A17	Rev A	23.03.2022	Barry Rush & Associates Pty Ltd
Cross Ventilation	A17 of A17	Rev A	08.12.2022	Barry Rush & Associates Pty Ltd
Diagram				
Landscape Plans				
Landscape Plan	LA1 Sheet 1	Rev E	07.12.2022	Greenland Design Pty Ltd
Landscape details and	LA2 Sheet 2	Rev E	07.12.2022	Greenland Design Pty Ltd
Specification				
Civil/Stormwater Plans				
Cover sheet & notes	CC210393C - C1 -	D	08.03.2023	ACOR Consulting Pty Ltd

Title / Name:	Drawing No / Document Ref	Revision / Issue:	Date [dd.mm.yyyy]:	Prepared by:
	А			
Stormwater Management Plan	CC210393C C2 - A	D	08.03.2023	ACOR Consulting Pty Ltd
Stormwater Management Details Sheet No. 1	CC210393C C3 - A	D	08.03.2023	ACOR Consulting Pty Ltd
OSD Calculation Sheet and Maintenance Schedule	CC210393C C4 - A	D	08.03.2023	ACOR Consulting Pty Ltd
OSD Checklist – Sheet 1 of 2	CC210393C C5	D	08.03.2023	ACOR Consulting Pty Ltd
OSD Checklist Sheet 2 of 2	CC210393C C6	D	08.03.2023	ACOR Consulting Pty Ltd
Erosion & Sediment Control Plan	CC210393C C7	D	08.03.2023	ACOR Consulting Pty Ltd
Erosions and Sediment Control Notes and Detail	CC210393C C8	D	08.03.2023	ACOR Consulting Pty Ltd
Stormwater Quality Report Sheet 1 of 2	CC210393C C9	D	08.03.2023	ACOR Consulting Pty Ltd
Stormwater Quality Report Sheet 2 of 2	CC210393C C10	D	08.03.2023	ACOR Consulting Pty Ltd
BASIX and NatHERS	•	•		
BASIX	BASIX Certificate No 1275784M_04		31.05.2022	Building Sustainability Assessments
NatHERS Summary Certificate	Certificate No 0007711750		16.05.2022	Building Sustainability Assessments
Supporting Reports				
Arboricultural Impact Assessment	E314	С	10.06.2022	Creative Planning Solutions
BCA Design Compliance Assessment Report	P220035 (3)		06.06.2022	BCA Vision
Geotechnical Investigation and Acid Sulfate Soil Assessment	21/1342		May 2021	STS Geotechnics Pty Ltd
Waste Management Plan		1	02.06.2022	Barry Rush & Associates Pty Ltd
Traffic Impact Assessment	220214		June 2022	Apex Engineers
Acoustic Report			12.05.2022	DK Acoustics Pty Ltd
Access Report			15.03.2022	Accessibility Solutions
Flood Investigation Report	CC210393_FIA		17.03.2023	ACOR Consulting Pty Ltd

- 2. All building work is to be undertaken in accordance with the National Construction Code and referenced Australian Standards.
- 3. All commitments listed in the BASIX certificate and stamped plans shall be implemented.
- 4. All construction documentation and building work are to be certified in accordance with Section 6.28 of the *Environmental Planning and Assessment Act* 1979.
- 5. The land the subject of this determination shall be consolidated into a single lot. The plan of consolidation shall be lodged at the NSW Land Registry Services and shall be registered prior to the occupation of the development. A copy of the registered plan shall be provided to the Land & Housing Corporation.

### **OPERATIONAL MATTERS**

The following Identified Requirements relate to the use of the site and are to ensure that the activity and its operation do not interfere with the amenity of the surrounding area.

#### Stormwater Run-off

6. Stormwater shall be collected within the site and conveyed in a pipeline to the appropriate gutter or drain under the control of City of Parramatta Council substantially in accordance with the approved concept stormwater drainage plans.

- 7. Alterations to the natural surface contours or surface absorption characteristics of the site shall not impede, increase or divert natural surface water runoff so as to cause a nuisance to adjoining property owners.
- 8. All driveways shall be graded in such a manner as to provide continuous surface drainage flow paths to the appropriate points of discharge.
- 9. To prevent water from entering buildings, surface waters shall be collected and diverted clear of the buildings by a sub-surface / surface drainage system.

#### Vehicular Access & Parking

- 10. Concrete vehicular crossings and laybacks shall be provided at the entrances / exits to the property at both frontages. The crossing and layback from Rose Crescent shall be constructed in accordance with City of Parramatta Council standard requirements for residential crossings. The crossing and layback from Bourke Street shall be constructed in accordance with Councils Standard Drawing numbers DS9 and DS10 for heavy duty vehicular crossings. Council shall be provided with plans for the crossings and laybacks together with the payment of any council inspection fees.
- 11. Particular care shall be taken in the location of vehicular crossings and/or laybacks to avoid poles, pits etc. The cost of any necessary adjustments to utility mains and services associated with the construction of the layback(s)/driveway(s) shall be borne by the Land & Housing Corporation. Obsolete gutter layback(s) shall be constructed as kerb and gutter, foot-paving and grassed verge in accordance with City of Parramatta council's Standard Plan No. DS1. The reinstatement of kerb and footpath works must be completed prior to the occupation of the development.

Note: It is recommended that discussions be held with the relevant authorities before construction works commence.

12. Car parking spaces and driveway(s) shall be constructed of concrete or other approved hard surface materials. The car parking spaces must be clear of obstructions and columns, permanently line marked and provided with adequate manoeuvring facilities. The design of these spaces must comply with AS 2890.1.

#### Site Works

- 13. All soil erosion and sediment control measures required to be put in place prior to the commencement of demolition / construction works shall be maintained during the entire period of the works and until all the disturbed areas are restored by turfing, paving or revegetation. Soil erosion and sediment control measures shall be designed in accordance with the guidelines set out in the Blue Book *Managing Urban Stormwater: Soils and Construction* (4th edition, Landcom, 2004).
- 14. An appropriately qualified person shall design any retaining walls or other methods necessary to prevent the movement of excavated or filled ground, including associated stormwater drainage measures.

#### **Building Siting**

15. All buildings shall be sited well clear of any easements affecting the site. The builder shall ascertain if any easements do exist and, and if they do, obtain full details of such prior to construction commencing.

#### Smoke Detection System(s)

- 16. Smoke detection systems shall be installed throughout the building(s) in accordance with requirements of Clause E2.2a of the Building Code of Australia. Detectors and alarms shall comply with AS 3786 and AS 1670 and must be:
  - i. connected to a permanent 240V power supply; and
  - ii. provided with a battery backup to activate the alarm unit in the event of failure of the permanent power supply.

#### Site Soil Contamination

17. If the site is identified as being potentially affected by soil contamination, it shall be inspected by a suitably qualified person to identify any contaminated or hazardous material present. A proposal for remediation shall be prepared, which may include preparation of a Remedial Action Plan, and remediation shall be carried out in accordance with the proposal. A Validation Report, prepared in accordance with Environment Protection Authority requirements, shall be obtained from a qualified expert on completion of the remediation work to verify that the site is suitable for the intended residential use. A copy of the Validation Report shall be provided to the Land & Housing Corporation on completion of the remediation works.

#### Landscaping

- 18. Landscaping shall be carried out substantially in accordance with the approved Landscape Plan(s) and maintained for a period of 12 months by the building contractor. City of Parramatta Council shall be consulted in relation to the planting of any street trees.
- 19. All scheduled plant stock shall be pre-ordered prior to commencement of construction or 3 months prior to the commencement of landscape construction works, whichever occurs sooner, for the supply to the site on time for installation. The builder shall provide written confirmation of the order to City of Parramatta Council and provide a copy to the Land & Housing Corporation.

#### Tree Removal

20. Removal of trees within the boundaries of the site is to be carried out in accordance with the trees shown for removal on the approved landscape plan and Arboricultural Impact Assessment report and no other trees shall be removed without further approval(s).

#### Fencing

21. All front fencing and gates shall be constructed wholly within the boundaries of the site. Any gates associated with the fencing shall swing inwards towards the site.

#### **Provision of Letterbox Facilities**

22. Suitable letterbox facilities shall be provided in accordance with Australia Post specifications.

#### **Public Liability Insurance**

23. A valid public liability insurance policy of at least \$10M shall be maintained throughout the demolition / construction works by the building contractor.

#### PRIOR TO ANY WORK COMMENCING ON THE SITE

The following Identified Requirements are to be complied with prior to any work commencing on the site.

#### **Disconnection of Services**

- 24. All services that are required to be disconnected shall be appropriately disconnected and made safe prior to commencement of the demolition / construction works. The various service authorities shall be consulted regarding their requirements for the disconnection of services.
- 25. All existing services within the boundary to remain live shall be identified, pegged and made safe.

#### Demolition

- 26. The builder shall notify the occupants of premises on either side, opposite and at the rear of the site a minimum of two days prior to demolition. Such notification shall be clearly written on an A4 size paper giving the date demolition will commence and be placed in the letterbox of every premise (including every unit in a multi-unit residential building or mixed use building). The demolition shall not commence prior to the date that is stated in the notice letter.
- 27. Prior to the demolition, a Work Plan shall be prepared by a competent person(s) in accordance with AS 2601 and shall be submitted to the Land & Housing Corporation. The Work Plan shall outline the identification of any hazardous materials (including surfaces coated with lead paint), method of demolition, the precautions to be employed to minimise any dust nuisance and the disposal methods for hazardous materials.
- 28. If buildings to be demolished are determined as, or suspected of, containing asbestos cement, a standard commercially manufactured sign containing the words 'DANGER ASBESTOS REMOVAL IN PROGRESS', and measuring not less than 400mm x 300mm, shall be erected in a prominent visible position on the site for the duration of the demolition works.

#### Note:

Any buildings constructed before 1987 is assumed to contain asbestos.

#### **Utilities Service Provider Notification**

29. The demolition / construction plans shall be submitted to the appropriate water utility's office (e.g. Sydney Water office) to determine whether or not the development will affect the utility's sewer and water mains, stormwater drains and any easements.

#### Note:

If the development complies with water utility's requirements, the plans will be stamped indicating that no further requirements are necessary.

#### **Council Notification**

30. City of Parramatta Council shall be advised by the building contractor in writing, of the date it is intended to commence work, including demolition. A minimum period of 5 working days notification shall be given.

#### Site Safety

- 31. A sign shall be erected in a prominent position on the site:
  - (a) showing the name, address and telephone number of the responsible Land & Housing Corporation officer for the work, and
  - (b) showing the name of the principal contractor (if any) and the telephone number on which that person may be contacted during and outside working hours, and
  - (c) stating that unauthorised entry to the site is prohibited.

The sign shall be maintained while the work is being carried out but shall be removed when the work has been completed.

#### Note:

This requirement does not apply in relation to building work that is carried out inside an existing building that does not affect the external walls of the building.

32. A minimum 1.8m high security fence or Class A / Class B (overhead) hoarding must be erected between the work site and any public place prior to demolition / construction. Access to the site shall be restricted to authorised persons only and the site shall be secured against unauthorised entry when demolition / construction work is not in progress or the site is otherwise unoccupied.

#### Note:

Approval from the relevant roads authority may be required under Section 138 of the Roads Act 1993 where a Class A or B hoarding encroaches onto the footpath of / or a public thoroughfare within a classified road.

33. No building or demolition materials are to be stored on the footpath or roadway.

#### Site Facilities

- 34. The following facilities shall be installed on the site:
  - (a) Toilet facilities shall be provided at the rate of 1 toilet for every 20 persons, or part thereof, employed at the site. Each toilet shall be a standard flushing toilet and shall be connected to a public sewer. If connection to a public sewer is not practicable, to an accredited sewerage management facility provided by City of Parramatta Council or if this is also not practicable to some other council approved management facility.
  - (b) Adequate refuse disposal methods and builders storage facilities. Builders' wastes, materials or sheds shall not be placed on any property other than that to which this activity relates.
- 35. Access to the site shall only be provided via an all-weather driveway on the property and shall not be provided from any other site.

#### **Protection of Trees**

36. Trees and other vegetation that are to be retained on site shall be protected prior to the commencement of works and for the duration of the construction period in accordance with the details provided in the Arboricultural Impact Assessment report.

#### Waste Management

37. A final Waste Management Plan shall be prepared and submitted to the Land & Housing Corporation by the building contractor prior to the commencement of demolition / construction. The plan shall detail the amount of waste material and the destination of all materials, recyclable and non-recyclable.

#### PRIOR TO ANY CONSTRUCTION WORK COMMENCING ON SITE

The following Identified Requirements are to be complied with prior to any construction works occurring on the site, excluding demolition.

#### Service Authority Clearances

38. A compliance certificate, or other evidence, shall be obtained from Sydney Water, confirming service availability prior to work commencing.

#### Note:

Payment of water and/or sewer service charges and/or a notice of requirements for works to be carried out during construction / prior to occupation may be applicable prior to issue of the compliance certificate.

- 39. A written clearance from an electricity supply authority stating that electrical services are available to the site, or that arrangements have been entered into for the provision of services to the site, shall be obtained prior to work commencing.
- 40. A certificate from an approved telecommunications carrier certifying that satisfactory arrangements have been made for the provision of underground telephone services, to the site and to each dwelling, shall be obtained prior to work commencing.
- 41. Where the site is to be connected to reticulated gas, a certificate from an approved gas carrier certifying that satisfactory arrangements have been made for the provision of underground gas services, to the site and to each dwelling, shall be obtained prior to work commencing.

#### Stormwater Disposal

- 42. A detailed stormwater drainage plan(s), substantially in accordance with the approved concept stormwater drainage plan(s), shall be prepared and submitted to the Land & Housing Corporation. Any on-site detention system shall be designed in accordance with the relevant catchment authority's requirements (e.g. the Upper Parramatta River Catchment Trust On-site Detention Handbook) and/or City of Parramatta Council's drainage code.
- 43. Where a drainage easement is required, proof of lodgement of the plan of the drainage easement at the NSW Land Registry Services shall be submitted to the Land & Housing Corporation prior to commencement of works. Registration of the plan of easement shall be completed prior to occupation of the development and a copy of the registered plan shall be provided to the Land & Housing Corporation.

#### **DURING DEMOLITION AND CONSTRUCTION WORKS**

The following Identified Requirements are to be complied with whilst demolition and construction works are occurring on the site.

#### Landfill

- 44. Where site filling is required, a minimum of 95% standard compacting shall be achieved and certified by a NATA registered Soils Laboratory.
- 45. Land fill materials must satisfy the following requirements:
  - i. Shall be Virgin Excavated Natural Matter (VENM);
  - ii. Shall be free of slag and hazardous, contaminated, putrescible, toxic or radio-active matter; and
  - iii. Shall be free of industrial waste and building debris.

#### Heritage

- 46. Historic and indigenous archaeological sites and relics are protected under the *Heritage Act* 1977 and *National Parks and Wildlife Act* 1974, respectively. Should any relics be uncovered during the course of the approved works, work must cease immediately in the affected area. Subsequently, in cases where historical or indigenous items have been uncovered, the Department of Planning and Environment must be contacted.
- 47. All workers / contractors on the site shall be informed of their obligations, under the Heritage Act and *National Parks and Wildlife Act 1974*, that it is illegal to disturb, damage or destroy a relic without the prior approval of the Department of Planning and Environment.

#### Demolition

48. Any existing structures identified for demolition shall be demolished prior to commencement of the construction of the activity.

- 49. Demolition shall be carried out in accordance with the appropriate provisions of AS 2601.
- 50. Where materials containing asbestos are to be removed, demolition shall be carried out by a licensed contractor(s) that has a current SafeWork NSW accreditation in asbestos removal.
- 51. Removal of asbestos-based thermal, or acoustic insulation such as sprayed asbestos and asbestos-based lagging and including friable asbestos boards, shall be carried out in accordance with the National Occupational Health and Safety Commission's Code of Practice for the Safe Removal of Asbestos, 2<sup>nd</sup> Edition [NOHSC:2002 (2005)].
- 52. Hazardous and intractable waste, including all asbestos laden waste arising from the demolition process shall be removed and disposed of in accordance with the requirements of SafeWork NSW.
- 53. Documentary evidence, in the form of tip receipts from an approved Waste Management Facility, shall be obtained by the demolition contractor and submitted to the Land & Housing Corporation demonstrating the appropriate disposal of the asbestos waste.
- 54. Demolition procedures shall maximise the reuse and recycling of demolished materials in order to reduce the environmental impacts of waste disposal.
- 55. During demolition, the public footpath and the public road shall not be obstructed by any vehicles. The public road and footpath shall be swept (not hosed) clean of any material, including clay, soil and sand.
- 56. All vehicles leaving the site with demolition materials shall have their loads covered and vehicles shall not track soil and other material onto the public roads and footpaths. The footpath shall be suitably protected against damage when plant and vehicles access the site. All loading of vehicles with demolished materials shall occur on site.

#### Survey Reports

57. Survey reports shall be submitted by the building contractor to the Land & Housing Corporation prior to the placement of the footings / slab and on completion of the dwellings to verify the correct position of the structures in relation to the allotment boundaries.

#### Hours of Demolition / Construction / Civil Work

58. Demolition / construction / Demolition / construction / civil work shall only occur on the site between the hours of 7.00am to 5.00pm Monday to Saturday with no work permitted on Sundays or public holidays.

#### **Excavation & Backfilling**

59. All excavations and backfilling associated with the demolition or erection of building(s) shall be executed safely and in accordance with appropriate professional standards. All such work shall be guarded and protected to prevent it from being dangerous to life or property.

#### **Pollution Control**

- 60. Any noise generated during the carrying out of the activity shall not exceed the limits specified in the July 2009 Interim Construction Noise Guidelines published by the former Department of Environment and Climate Change.
- 61. No fires shall be lit, or waste materials burnt, on the site.
- 62. No washing of concrete forms or trucks shall occur on the site.

- 63. Any contamination / spills on the site during construction works shall be actively managed and reported immediately to the appropriate regulatory authorities to minimise any potential damage to the environment.
- 64. Dust generation during demolition / construction shall be controlled using regular control measures such as on site watering or damp cloth fences.
- 65. All vehicles transporting loose materials and travelling on public roads shall be secured (i.e. closed tail gate and covered) to minimise dust generation.
- 66. Non-recyclable waste and containers shall be regularly collected and disposed of at a licensed landfill or other disposal site in accordance with details set out in the final Waste Management Plan.

#### Impact of Construction Works

- 67. The Land & Housing Corporation shall bear the cost of any necessary adjustments to utility mains and services.
- 68. Care shall be taken to prevent any damage to adjoining properties. The building contractor shall be liable to pay compensation to any adjoining owner if, due to demolition/construction works, damage is caused to such adjoining property.

#### **Termite Protection**

69. To protect buildings from subterranean termite, termite barriers installed in accordance with AS 3660.1, shall be placed on the underside and in penetrations of the concrete slab floor.

In addition, a durable notice must be permanently fixed inside the meter box indicating:

- (a) the method of protection;
- (b) the date of installation of the system;
- (c) where a chemical barrier is used, its life expectancy as listed on the National Registration Authority label; and
- (d) the need to maintain and inspect the system on a regular basis.

#### PRIOR TO OCCUPATION OF THE DEVELOPMENT

The following Identified Requirements are to be complied with prior to the occupation of the development.

#### General

70. The occupation of the development shall not commence until all the Identified Requirements of this determination have been complied with.

#### **Council Infrastructure Damage**

71. The cost of repairing any damage caused to City of Parramatta Council assets in the vicinity of the site as a result of demolition / construction works shall be met in full by the building contractor.

#### Stormwater Drainage

- 72. Prior to occupation, a Work As Executed Plan shall be prepared by the building contractor clearly showing all aspects of the constructed stormwater drainage system, including any onsite detention system. The plan shall demonstrate general compliance with the approved concept stormwater drainage plan(s) and shall include:
  - sufficient levels and dimensions to verify the constructed storage volumes; and

- location and surface levels of all pits; and
- invert levels of the internal drainage lines, orifice plates fitted and levels within the outlet control pits; and
- finished floor levels of all structures; and
- verification that any required trash screens have been installed; and
- locations and levels of any overland flow paths; and
- verification that any drainage lines are located wholly within easements, where applicable.

The Work-As-Executed Plan information shall be shown on the final civil works drawings.

A positive covenant and restriction-as-to-user shall be placed over the onsite detention system in accordance with City of Parramatta Council's on-site detention policy to ensure that the system will be adequately maintained. The positive covenant and restriction-as-to-user shall be registered at NSW Land Registry Services prior to occupation. A copy of the registered restriction-as-to-user shall be provided to the Land & Housing Corporation and City of Parramatta Council.

#### PART B – Additional Identified Requirements

#### **Specific Requirements for Seniors Housing**

73. The independent living units shall comply with the accessibility and useability standards referenced in section 85 and set out in Schedule 4 of State Environmental Planning Policy (Housing) 2021.

#### Note:

This requirement does not apply to the provisions set out under sections 2, 7-13 and 15-20 of Schedule 4 for an independent living unit, or part of such a unit, that is located above the ground floor.

- 74. Only the following kinds of people shall be accommodated in the approved development:
  - (a) seniors or people who have a disability; or
  - (b) people who live within the same household with seniors or people who have a disability; or
  - (c) staff employed to assist in the administration and provision of services to the seniors housing development.

A restriction as to user shall be registered against the title of the property, prior to occupation, in accordance with Section 88E of the Conveyancing Act 1919 limiting the use of any accommodation to the kinds of people referred to above and that the dwellings cannot be subdivided.

#### Note:

It should be noted that 'seniors', as defined in the Housing SEPP, are any of the following:

- (a) people aged 60 or more years,
- (b) people who are resident at a facility at which residential care (within the meaning of the Aged Care Act 1997 of the Commonwealth) is provided, and
- (c) people who have been assessed as being eligible to occupy housing for aged persons provided by a social housing provider.
- 75. Pathway lighting shall be designed to provide a minimum of 20 lux at ground level and be located to avoid glare for pedestrians and adjacent dwellings.
- 76. Access to, and within, the site shall be provided in accordance with AS 1428.1 so that a person using a wheelchair can use common areas and common facilities associated with the activity.
- 77. A 1.5m wide concrete footpath across the site frontage, connecting to the existing footpath system in Bourke Street shall be constructed in accordance with City of Parramatta Council's specifications to provide an accessible pathway from the site to the nearest bus stop on Bourke Street.

#### Note:

The responsible officer at City of Parramatta council shall be contacted regarding council's specifications and any necessary approvals.

78. Entry doors to units shall to be provided with door viewers to enable residents to view approaches to their units without the need to open the door.

#### Site Specific Requirements

- 79. All works shall be supervised and recorded by a Project Arborist experienced in tree protection on construction sites. Supervision shall commence with installation of tree protection measures until completion of landscaping and removal of tree protection barriers. The Project Arborist shall supervise and monitor any excavation, machine trenching or compacted fill placement within the TPZ of retained trees throughout construction.
- 80. Tree Protection to be installed as shown on the Tree Location & Protection Plan Specification at Appendix 2 to the AIA and in accordance with Section 4.3 of AS4970-2009 and Appendix 5 to the Arboricultural Impact Assessment by Creative Planning Solutions dated 10 June 2022.
- 81. A detailed root mapping investigation is to be undertaken for Tree 1 (*Jacaranda mimosifolia*) by a suitably qualified Arborist with minimum AQF5 qualifications to identify the location and presence of tree roots to be impacted by the proposed building works and determine whether the proposed extent of hard surfacing requires modification to enable this tree to be retained in a healthy and viable condition following completion of construction. Should root mapping require adjustment to the hard surface treatments then this is to be documented by the building contractor and confirmed in the Crown Certification.

#### **Requirements Resulting from Council Comments**

- 82. A detailed survey of the stormwater easement and pipe system must be prepared by a registered surveyor. The survey is to include the pipe location relative to the easement, invert of the pipe, pipe diameter, and any existing pits that are proposed to be utilised. A copy of the detailed survey must be provided to the Crown Certifier prior to construction.
- 83. Full engineering construction details of the stormwater system, including OSD structures, pipe networks and calculations as per following points, shall be submitted for the approval of the Crown Certifier prior to release of the applicable Crown Certificate for any work on the site. This includes:
  - a) The stormwater drainage detail design shall be prepared by a Registered Stormwater Design Engineer and shall be generally in accordance with the following Stormwater Plans approved by this consent and with Council's Stormwater Disposal Policy, Council's Design and Development Guidelines, The Upper Parramatta River Catchment Trust On Site Detention Hand book 3<sup>rd</sup> Edition, the relevant Australian Standards and the National Construction Code.
    - (i) "Stormwater Management Plan", Drawing No C1-C10 Issue D, dated 08/03/2023, prepared by ACOR consultants (CC) Pty Ltd.
  - b) A Site Storage Requirement of 470 m3/ha and a Permissible Site Discharge of 80 L/s/ha (when using 3rd edition of UPRCT's handbook)
  - c) Adequate grate(s) to be provided so the OSD tank storage area can be inspected from outside for silt and debris, and to ensure adequate cross ventilation within the tank. If any grates are sealed, suitably designed ventilation shall be provided.
  - d) The orifice shall be centred over the centre of the outlet.
  - e) The orifice shall be adjusted for the flowrate from the SFC to ensure the PSD for the site has not been exceeded. The SFC outlet (underdrain) shall drain directly to the overflow pit.
  - f) Certificate from registered structural engineer certifying the structural adequacy of the OSD tank structure.

- 84. SPEL Filters SF.29-EMC water quality treatment devices must be installed to manage surface runoff water to Bourke Street to satisfy section 3.3.6.1 of *Parramatta City Council Development Control Plan 2011*. Details of the proposed devices and their location must accompany the application for the applicable Crown Certificate to the satisfaction of the Crown Certifier.
- 85. Prior to the commencement of any works on site, the applicant must submit a Construction and Traffic Management Plan to the satisfaction of the Crown Certifier. The following matters must be specifically addressed in the Plan:
  - a) Construction Management Plan for the Site. A plan view of the entire site and frontage roadways indicating:
    - Dedicated construction site entrances and exits, controlled by a certified traffic controller, to safely manage pedestrians and construction related vehicles in the frontage roadways,
    - (ii) Turning areas within the site for construction and spoil removal vehicles, allowing a forward entry and egress for all construction vehicles on the site,
    - (iii) The locations of proposed Work Zones in the egress frontage roadways,
    - (iv) Location of any proposed crane standing areas,
    - (v) A dedicated unloading and loading point within the site for all construction vehicles, plant and deliveries,
    - (vi) Material, plant and spoil bin storage areas within the site, where all materials are to be dropped off and collected,
    - (vii) The provisions of an on-site parking area for employees, tradesperson and construction vehicles as far as possible,
    - (viii) A detailed description and route map of the proposed route for vehicles involved in spoil removal, material delivery and machine floatage and a copy of this route is to be made available to all contractors, and
    - (ix) A detailed description of locations that will be used for layover for trucks waiting to access the construction site.
  - b) Written concurrence from Council's Traffic and Transport Services in relation to installation of a proposed 'Works Zone' restriction in the egress frontage roadways of the development site.

Application fees and kerbside charges for 6 months (minimum) are to be paid in advance in accordance with the Council's Fees and Charges. The 'Works Zone' restriction is to be installed by Council once the applicant notifies Council in writing of the commencement date (subject to approval through Parramatta Traffic Committee processes). Unused fees for kerbside charges are to be refunded once a written request to remove the restriction is received by Council.

- c) Traffic Control Plan (s) for the site:
  - (i) All traffic control devices installed in the road reserve shall be in accordance with the NSW Transport Roads and Maritime Services publication 'Traffic Control Worksite Manual' and be designed by a person licensed to do so (minimum RMS 'red card' qualification) The main stages of the development requiring specific construction management measures are to be identified and specific traffic control measures identified for each.
  - (ii) Approvals shall be obtained from City of Parramatta Council for any temporary road closures or crane use from public property.
- d) Where applicable, the plan must address the following:
  - (i) Evidence of Roads and Maritime Services concurrence where construction access is provided directly or within 20 m of an Arterial Road.
  - (ii) A schedule of site inductions shall be held on regular occasions and as determined necessary to ensure all new employees are aware of the construction management obligations.
  - (iii) Minimising construction related traffic movements during school peak periods.

The Construction and Traffic Management Plan shall be prepared by a suitably qualified and experienced traffic consultant and be certified by this person as being in accordance with the requirements of the abovementioned documents and the requirements of this condition.

- 86. Prior to the applicable Crown Certificate, the building must be designed and certified by a registered structural engineer to ensure the building does not fail due to floodwater forces, debris and buoyancy effects from flooding in events up to the Probable Maximum Flood (PMF) from the easement.
- 87. Prior to the issue of the applicable Crown Certificate, the Crown Certifier shall ensure that no floor levels are below the PMF flood level of RL53 AHD, identified in the Flood Investigation Report (March 2023) and that appropriate flood mitigation controls are implemented to ensure that no flooding in the easement affects the development.
- 88. Foundations adjacent to the existing 450mm diameter drainage pipe, within the 2m wide drainage easement, must be constructed in accordance with Council's Code, "Foundation Requirements for Structures Adjacent to Council Stormwater Drainage Easements Parramatta City Council Code E-3". The engineering details must accompany an application for the applicable Crown Certificate.
- 89. Driveway grades, including transitions, must comply with Australian Standard 2890.1 to prevent the underside of the vehicles scraping. Where the geometric change in grade exceeds 18%, the gradients of the driveway and ramps shall be checked using the method at Appendix C in AS2890.1:2004 and adjustments will be made to accommodate suitable transition lengths. Details are to be provided with the applicable Crown Certificate.
- 90. The landscaping works and fencing to be installed within the easement for drainage must be compatible with the overland flow function of the easement as described in the Flood Investigation Report by ACOR Consulting Pty Ltd dated 17.03.2023.
- 91. A 200mm wide grated drain, incorporating heavy duty removable galvanized grate is to be located within the site at the intersection of the driveway and Council's footway on Bourke Street to collect all surface water flowing down the driveway. The drainage line from the grated drain shall be connected to the street stormwater system, either separately or via the main site outlet.
- 92. An application for street numbering must be lodged with Council for approval, prior to the issue of the application Crown Certificate.

#### Note:

Notification of all relevant authorities of the approved street numbers must be carried out by Council.

93. An evacuation report and procedure shall be prepared by an appropriate consulting engineer. This report is to demonstrate how the occupants of the development will egress the site in the early stages of a storm event, together with how they will seek refuge in a peak stormwater event. The report shall be submitted to the Crown Certifier prior to the issue of the applicable Crown Certificate. A copy of the report shall be attached to the applicable Crown Certificate prior to occupation, and forwarded to Council for their records.

#### **Requirements Resulting from Adjoining Occupier Comments**

94. The building contractor is to contact the landowner of 24 Rose Crescent prior to ordering boundary fencing to ensure the fencing materials and colours are satisfactory.

#### **ADVISORY NOTES**

- i. Approval of this development activity does not imply or infer compliance with Section 23 of the Disability Discrimination Act 1992. Refer to AS 1428.1 and the Building Code of Australia for detailed guidance.
- *ii.* Information regarding the location of underground services may be obtained from Dial Before You Dig at *www.1100.com.au* or by dialing 1100.



# **Decision Statement**

SITE IDENTIFICATION		
STREET ADDRESS		
Unit/Street No.	Street or property name	
26 and 69-73	Rose Crescent and Bourke Street	
L		
Suburb, town or locality		Postcode
North Parramatta		2151
Local Government Area(s)	Real property description (Lot a	nd DP)
City of Parramatta	Lots 2, 3 & 4 in DP 215342	
ACTIVITY DESCRIPTION		
Provide a description of the activ	ity	

Demolition of 3 existing bedsits containing a total of 13 dwellir

Demolition of 3 existing bedsits containing a total of 13 dwellings and associated structures, removal of trees, and the construction of 14 independent living seniors housing units comprising 6 x one bedroom and 8 x two bedroom units, with associated landscaping and fencing, at-grade parking for 11 cars, and consolidation into a single lot

The Land & Housing Corporation (LAHC) has proposed the above activity under the provisions of *State Environmental Planning Policy (Housing) 2021* (Housing SEPP) which requires determination under Part 5 of the *Environmental Planning & Assessment Act 1979* (EP&A Act). This Decision Statement relates to the Review of Environmental Factors (REF) for the above activity prepared under Part 5 of the EP&A Act and the *Environmental Planning and Assessment Regulation 2021*.

Based on the REF document, a decision to proceed with the proposed activity has been made. This decision included consideration of the following:

### Significant Impact on the Environment

- The proposed activity is not likely to have a significant impact on the environment and therefore an EIS is not required.
- The proposed activity will not be carried out in a declared area of outstanding biodiversity value and is not likely to significantly affect threatened species, populations or ecological communities, or their habitats or impact biodiversity values, meaning a SIS and/or BDAR is not required.

Reasons for the Decision

 Following an assessment of the proposed activity and associated environmental impacts within the REF it was decided that the proposed seniors housing development will have economic and social benefits and any minor short-term impacts on the environment or surrounding properties can be appropriately mitigated. • The proposed seniors housing development will assist LAHC in providing new, fit for purpose housing in the North Parramatta area which will assist in addressing the existing and growing demand for social housing in City of Parramatta local government area.

#### Mitigation Measures

• Mitigation measures are required to minimise or manage environmental impacts and are detailed throughout the REF and specifically within Section **7**. All mitigation measures are detailed as Identified Requirements within the Activity Determination. Additional mitigation measures, detailed in the Activity Determination have been imposed to minimise the impact on the surrounding environment, ensure appropriate site safety and to ensure legislative compliance.

Signed....

9 August 2023

Emma Nicholson Acting Head of Policy and Innovation Land and Housing Corporation Department of Planning & Environment

# DA PLANS **SENIORS HOUSING DEVELOPMENT** 26 ROSE CRESCENT AND 69-73 BOURKE STREET, NORTH PARRAMATTA LOTS 2, 3 & 4 in DP 215342 **DEVELOPMENT DATA**

February 2022			BSA	Reference: 18084
Building Sustainability Ass enquiries@buildingsustair		www.		: (02) 4962 3439 ainability.net.au
	Important	Note		
The following specification was the Assessor Certificate. If the Assessor and NatHERS certific BCA provisions for building sea In NSW both BASIX & the BCA v - Thermal construction in accor - Thermal breaks for Class 1 dv - Floor insulation for Class 1 dv - Building sealing in accordanc	used to achieve proposed constr ates will no long aling & ventilatio ariations must be dance with Vol wellings in accor vellings as per F	e the thermal ruction varies ler be valid. In are complie complied with Section J1.2 dance with P Part 3.12.1.5(a	to those detaile Assessments a d with at const in particular the or Vol 2 Part art 3.12.1.2(c) a)(ii), (iii) & (e) d	ed below than the ssume that the ruction. e following: 3.12.1.1 & 3.12.1.4(d) or (c), (d) & (e)
Thermal Performa	ance Specificat	ons (does n	ot apply to ga	rage)
External Wall Construction	•			Added Insulation
Cavity Brick	R0.74	to inside face	e of masonry ur	nder plasterboard
Reverse Brick Veneer				R2.0
Internal Wall Construction				Added Insulation
Brick (internal to units)				none
Cavity Brick (common area wa	alls) R0.7	4 to inside fa	ce of masonry	under plasterboard
Cavity Brick (party walls)			ee ei maooniy (	none
Ceiling Construction				Added Insulation
Plasterboard		R3 5	to ceilings adia	cent to roof space
	ır (Solar Absorpi		to coningo aaja	Added Insulation
Metal	Any	ancej		oil + R1.0 blanket
metai				
Floor Construction	Covering			Added Insulation
Concrete As drawn (if not r	0	ues used)		None
				None
Windows Glass and frame	e tvpe	U value	SHGC Rang	ge Area sq m
Performance glazing Type A		2.90	0.40 - 0.48	Units 1,3,5 only
• • •		2.90	0.46 - 0.56	Units 1,3,5 only
Performance glazing Type B		4.30	0.40 - 0.50	Units 2,4,6,9 only
Performance glazing Type A				
Performance glazing Type B		4.30	0.48 - 0.58	Units 2,4,6,9 only All other glazing
Performance glazing Type A		5.40	0.44 - 0.54	
Performance glazing Type B	va hifalda aaaam	5.40	0.52 - 0.64	All other glazing
Type A windows are awning windov Type B windows are double hung w			•	
	-			
Skylights Glass and frame	e type U	SHGC Area	a sq m	Detail
U and SHGC values are according SHGC is within the range specified		e products may	/ be used if the U	value is lower & the
Shade elements			(eaves, veran	dahs, awnings etc)
All shade elements modelled a	is drawn			
Ceiling Penetrations		(d	ownlights, exha	aust fans, flues etc)
Modelled as drawn and/or to co	omply with the ve	entilation and	sealing require	ments of the BCA
			<u> </u>	
Ducting is modelled at 150mm.	No insulation lo	osses from de	ownlighting hav	e been modelled.
Additional Notes	No insulation lo	osses from de	ownlighting hav	





DRAWING SCHEDULE

# I FGFND

LEG	END				REFER
AGL AN. AL. BOE BR	ADJUSTABLE GLAZED LOUVRES ANODISED ALUMINIUM BRICK ON EDGE BROOM CUPBOARD	P PR1 PR2 PVC	PANTRY PAINTED RENDER COLOUR 1 PAINTED RENDER COLOUR 2 PHOTOVOLTAIC CELLS	<b>ARCHITECTURAL</b> COVER SHEET SITE ANALYSIS PLAN EXISTING SITE PLAN SITE/ GROUND FLOOR PLAN	REFER A01 A02 A03 A04
CC CL CP CT DP F1 F2 F3 FAL FB1	COLOURED CONCRETE COLOUR CLOTHES LINE CONCRETE PAVING BROOM FINISH CARPET CERAMIC TILE DOWNPIPE FENCE 1000mm HIGH METAL PALISADE FENCE FENCE 1800mm HIGH COLORBOND METAL FENCE FENCE 1500/1800mm HIGH SLATTED METAL FENCE FIXED ALUMINIUM LOUVRES FACE BRICK COLOUR 1	R REF RHD RL SWT SB SC SHR SMC SMC STC	ROBE REFRIGERATOR LOCATION RANGEHOOD RELATIVE LEVEL RAINWATER TANK KITCHEN SINK STAIR BALUSTRADE STEEL COLUMN SHOWER STANDING SEAM METAL CLADDING STEEL TROWEL CONCRETE FINISH	FIRST FLOOR PLAN ROOF PLAN ELEVATIONS SECTIONS EXTERIOR COLOUR SCHEDULE DEMOLITION PLAN BLOCK ANALYSIS PLAN SHADOW DIAGRAMS MID WINTER VIEWS FROM SUN DIAGRAM STREETSCAPE PERSPECTIVES	A05 A06 A07 A08 A09 A10 A11 A12 A13 A14 A15
FB2 FCL FFL G GD HP HR HT HWU LB LN MC MDR MSB NBN	FACE BRICK COLOUR 2 FINISHED CEILING LEVEL FINISHED FLOOR LEVEL GATE GRATED STRIP DRAIN HOTPLATE HANDRAIL GARDEN HOSE TAP HOT WATER UNIT LETTERBOXES - RECESSED INTO WALL LINEN CUPBOARD METAL CLADDING METAL DECK ROOF MAIN SWITCH BOARD NBN CONNECTION	SWP T TOF TOK TOW TOP TPZ UBO VJ VTY WA WC WM WO	STORMWATER PIT LAUNDRY TUB TOP OF FENCE TOP OF KERB TOP OF WALL TOP OF PARAPET TREE PROTECTION ZONE UNDER BENCH OVEN VERTICAL JOINT VANITY SUN AWNING TOILET SUITE WASHING MACHINE WALL OVEN	AREAS OF EXCAVATION AND FILL LANDSCAPE DATA PLAN CROSS VENTILATION DIAGRAM <b>CIVIL</b> COVER SHEET & NOTES STORMWATER MANAGEMENT PLAN STORMWATER MANAGEMENT DETAILS SHEET N OSD CALCULATION SHEET & MAINTENANCE SCH OSD CHECKLIST SHEET 1 OF 2 OSD CHECKLIST SHEET 2 OF 2 EROSION & SEDIMENT CONTROL PLAN EROSION & SEDIMENT CONTROL PLAN EROSION & SEDIMENT CONTROL NOTES & DETA STORMWATER QUALITY REPORT SHEET 1 OF 2	A16 A17 C1 C2 No1 C3 HEDULE C4 C5 C6 C7



LOCKED BAG 5022 PARRAMATTA NSW 2124 PHONE No 1800 738 718 https://www.dpie.nsw.gov.au/land-and-housing-corporation

AOOBarry Rush & Associates Pty Ltd Architects. Nominated Architect: Barry John Rush ARB Registration No 3753 Suite 25A, 2 Beattie Street, Balmain, NSW Phone: (02) 9555 8028 Email: info@barryrush.com.au www.barryrush.com.au

В	08/12/22	DA AMENDMENTS
А	23/03/22	DA PLAN ISSUE
EV	DATE	NOTATION/AMENDMENT
	DO NOT	SCALE DRAWINGS. CHECK ALL DIMENSIONS FIGURED DIMENSIONS TAKE PRECEDENCE.

 $\overline{}$ 

Job Reference	
Locality / Suburb	
Street Address	
Lot & DP	
Site Area	
Existing Lots	
Proposed GFA	
No. of Dwellings	

HY-DA-000

HY-DA-100

EL-DA-000

EL-DA-100

LA 1 OF 2

LA 2 OF 2

S 1 OF 4

S 2 OF 4

S 3 OF 4

S 4 OF 4

3

3

3

(E)

(E

1

1

-

	Control		Requirement	Proposed
HEIGHT	Parramatta Council-LEP		9m	7.8m to top of roof
	Housing	g SEPP	9.5m	7.8m to top of roof
FSR	Parramatta (	Council-LEP	0.5:1	0.49:1 (1085 m²)
	Housing	g SEPP	0.5:1	0.49:1 (1085 m²)
PARKING	Housing	g SEPP	1 per 5 dwellings = 2.8	3 car spaces
	Housing SEPP	non accessible site	0.5 x (no. 1 Beds) = 3 1 x (no. 2 Beds) = 8 TOTAL 11 car spaces	11 car spaces (including 3 accessible)
	Parramatta Street Council		5-7m Consistent with prevailing setback on the street.	Bourke St - 5.2min Rose Cr - 4.4 min
SETBACK DCP		Side	3m Except where buildings. primarily address side boundary then 4.5m	3m
		Rear	15% of the length of the site	n/a
LANDSCAPING	Housing SEPP		35 m <sup>2</sup> er Dwelling 490 m <sup>2</sup>	762 m²
DEEP SOIL	Housing SEPP		15 334 m² 65 at rear 217m²	342 m² 15.3 179 m² 52
SOLAR ACCESS	Housing SE	PP	70% for 2hrs in Mid-Winter = 12	100%

LAHC\* - development data for LAHC new housing supply. For details refer to Current version of LAHC Design Requirements. GFA\* - gross floor area calculated as per the Housing SEPP AREA\* - dwelling floor area includes internal walls but excludes external walls POS\* - private open space

WELLINGS					SOLAR A	CCESS
Number	Type*	Beds	Area (m²)	POS*	LIVING	POS
1	Ground	2	75	22	6 hr	4 hr
2	First	2	75	11	6 hr	6 hr
3	Ground	2	75	23	6 hr	4 hr
4	First	2	75	11	6 hr	6 hr
5	Ground	2	75	23	6 hr	4 hr
6	First	2	75	11	6 hr	6 hr
7	Ground	2	75	73	6 hr	4 hr
8	First	2	75	11	6 hr	6 hr
9	Ground	1	60	85	3 hr	3 hr
10	First	1	60	11	3 hr	2 hr
11	Ground	1	56	47	6 hr	4 hr
12	First	1	56	11	6 hr	6 hr
13	Ground	1	56	81	6 hr	4 hr
14	First	1	56	11	6 hr	6 hr

~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	· · · · · · · · · · · · · · · · · · ·			
	ARCHITECT	CIVIL	BUSINESS PARTNER:	PROJECT:
	BARRY RUSH & ASSOCIATES PTY LTD			SENIORS DEVELOPMENT
	PH (02) 9555 8028	PH (02) 4324 3499		26 ROSE CRESCENT AND
	PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 8753 9000	HYDRAULIC CONSULTANT MARLINE NEWCASTLE PTY LTD PH (02) 4925 9300 FAX (02) 4926 3811		69-73 BOURKE STREET
	LANDSCAPE CONSULTANT	ELECTRICAL CONSULTANT		NORTH PARRAMATTA
IONS ON SITE. CE.	GREENLAND DESIGN PTY LTD PH 0403 164 198	MARLINE NEWCASTLE PTY LTD PH (02) 4925 9300 FAX (02) 4926 3811		LOTS 2, 3 & 4 in DP 215342

HYDRAULIC

COVER SHEET

SITE SERVICES

ELECTRICAL

LANDSCAPE

SURVEY

BY:

COVER SHEET

SITE RETICULATION

LANDSCAPE PLAN

**DETAIL & CONTOUR SURVEY** 

**DETAIL & CONTOUR SURVEY** 

**DETAIL & CONTOUR SURVEY** 

LONGITUDINAL SECTIONS

LONGITUDINAL SECTIONS

DATE: 23/04/2021

LANDSCAPE DETAILS AND SPECIFICATION

TSS TOTAL SURVEYING SOLUTIONS

**REFERENCE** No

B

A

Α

(B)

B ·

SB <

B

B.

Δ

Α

Α

Δ

Α

Α

C

SC

C C

C

C :

C

( C

C

C S

( C





0007711750 16 May 2022 sessor Gavin Chambers 6 Rose Crescent 69 arramatta, NSV




BGXWX
North Parramatta
26 Rose Crescent & 69-73 BOURKE Street
Lots 2, 3 & 4 in DP 215342
2228.7 m <sup>2</sup>
3
1085 m²
8 x 2 Bed + 6 x 1 Bed = 14 Dwellings

	T	STATUS: DA			
	DATE: 2/05/22	SCALE:	PROJ:		
		ZIUSIZZ STAGE:	1:100 DRAWN:	- CHECKED:	BGXWX NOMINATED ARCHITECT:
		STAGE:	MB	BR	13R
FILE:	PLOTTED:	TYPE:	SHEET:		REV:
DA0a Cover_Demo_Block_SAnal	vsis_Finishes_CrossV Rose.dwg 8/12/2022 10:45 AM	A	<b>A0</b>	1	B




DETERMINED by the NSW Land and Housing Corporation on: 9 August 2023











DETERMINED by the NSW Land and Housing Corporation on:


9 August 2023

	ADJUSTABLE GLAZED LOUVRES
AGL	
	ANODISED ALUMINIUM
BOE	BRICK ON EDGE
BR	BROOM CUPBOARD
CC	COLOURED CONCRETE COLOUR
CL	CLOTHES LINE
CP	CONCRETE PAVING BROOM FINISH
CPT	CARPET
- · ·	CERAMIC TILE
CT	
DP	DOWNPIPE
F1	FENCE 1000mm HIGH METAL PALISADE FENCE
F2	FENCE 1800mm HIGH COLORBOND METAL FENCE
F3	FENCE 1500/1800mm HIGH SLATTED METAL FENCE
FAL	FIXED ALUMINIUM LOUVRES
FB1	FACE BRICK COLOUR 1
FB2	FACE BRICK COLOUR 2
FCL	
FFL	FINISHED FLOOR LEVEL
G	
GD	
HP	
HR	HANDRAIL
HT	GARDEN HOSE TAP
HWU	
LB	LETTERBOXES - RECESSED INTO WALL
LN	LINEN CUPBOARD
MC	METAL CLADDING
MDR	METAL DECK ROOF
MSB	MAIN SWITCH BOARD
NBN	NBN CONNECTION
Р	PANTRY
PR1	PAINTED RENDER COLOUR 1
PVC	PHOTOVOLTAIC CELLS
R	ROBE
REF	REFRIGERATOR LOCATION
RHD	RANGEHOOD
RL	RELATIVE LEVEL
RW	RETAINING WALL
RWT	RAINWATER TANK
S	KITCHEN SINK
SB	STAIR BALUSTRADE
	STEEL COLUMN
SC	
SHR	SHOWER
SMC	STANDING SEAM METAL CLADDING
STC	STEEL TROWEL CONCRETE FINISH
SWP	STORMWATER PIT
Т	LAUNDRY TUB
TOF	TOP OF FENCE
TOK	TOP OF KERB
TOW	TOP OF WALL
TOP	TOP OF PARAPET
TPZ	TREE PROTECTION ZONE
UBO	UNDER BENCH OVEN
VJ	VERTICAL JOINT
VTY	VANITY
ŴA	SUN AWNING
WC	TOILET SUITE
WM	WASHING MACHINE
WO	WALLOVEN

	STATUS: DA				
ELEVATIONS		date: <b>2/05/22</b>	scale: 1:100	PROJ: –	PROJECT NO. BGXWX
		STAGE:	DRAWN: MB	CHECKED: BR	NOMINATED ARCHITECT:
FILE: DA A04e Plans elevations sections Rose Cr P Par	PLOTTED: amatta.dwg 29/11/2022 5:11 PM	TYPE: A	SHEET: A07	,	REV: B



	ARCHITECT	CIVIL	BUSINESS PARTNER:	PROJECT:
	BARRY RUSH & ASSOCIATES PTY LTD			SENIORS DEVELOPMENT
	PH (02) 9555 8028	PH (02) 4324 3499		
	PROJECT MANAGER	HYDRAULIC CONSULTANT		26 ROSE CRESCENT AND
	LAND & HOUSING CORPORATION PH (02) 8753 9000	MARLINE NEWCASTLE PTY LTD PH (02) 4925 9300 FAX (02) 4926 3811		69-73 BOURKE STREET
	LANDSCAPE CONSULTANT	ELECTRICAL CONSULTANT		NORTH PARRAMATTA
ons on site.	GREENLAND DESIGN PTY LTD PH 0403 164 198	MARLINE NEWCASTLE PTY LTD		LOTS 2.3 & 4 in DP 215342




	LOCKED BAG 5022
NOW	PARRAMATTA NSW 2124
NSW	PHONE No 1800 738 718
COVEDNMENT	https://www.dpie.nsw.gov.au/land-and-housi

	Barry Rush & Associates Pty Ltd			
	Architects. Nominated Architect: Barry John Rush ARB Registration No 3753	А	23/03/22	Γ
	Suite 25A, 2 Beattie Street, Balmain, NSW	REV	DATE	
ing-corporation	Phone: (02) 9555 8028 Email: info@barryrush.com.au www.barryrush.com.au		DO NOT S	SC F

SENIORS DEVELOPMENT 26 ROSE CRESCENT AND AND & HOUSING CORPORATION ARLINE NEWCASTLE PTYLITD 69-73 BOURKE STREET DA PLAN ISSUE NORTH PARRAMATTA GREENLAND DESIGN PTYLTD ARLINE NEWCASTLE PTYL SCALE DRAWINGS, CHECK ALL DIMENSIONS ON SITE FIGURED DIMENSIONS TAKE PRECEDENCE. LOTS 2, 3 & 4 in DP 215342

			STATUS: DA				
EXTERIOR COLOUR SCHE			DATE: 2/05/22	SCALE: NTS		PROJECT No. BGXWX	
			STAGE:	DRAWN:	CHECKED:	NOMINATED ARCHITECT:	
				мв	BR	BR	
	FILE	PLOTTED:	TYPE:	SHEET:		REV:	
	DA Rose Cr N Parramatta Feb2022 Cover demo e	c.10Wg2/2022 11:33 AM	A	A09		Α	

# DETERMINED by the NSW Land and Housing Corporation on:






LOCKED BAG 5022 PARRAMAITA NSW 2124 PHONE No 1800 738 718 https://www.dpie.nsw.go


				PH (02) 9555 8028 PH (02) 9555 8028	ACOR CONSULTANTS PTY LTD PH (02) 4324 3499	
d				PROJECT MANAGER	HYDRAULIC CONSULTANT	
	A 23/03/22		DA PLAN ISSUE	PH (02) 8753 9000	MARLINE NEWCASTL PH (02) 4925 9300 FAX (02) 4926 3	
	REV	DATE	NOTATION/AMENDMENT	LANDSCAPE CONSULTANT	ELECTRICAL CONSULTANT	
n.au		DO NOT !	SCALE DRAWINGS, CHECK ALL DIMENSIONS ON SITE. FIGURED DIMENSIONS TAKE PRECEDENCE.	GREENLAND DESIGN PTY LTD PH 0403 164 198	MARLINE NEWCASTLI PH (02) 4925 9300 FAX (02) 4926 30	

9.August 2023


DETERMINED by the NSW Land and Housing Corporation on:




9AM 21ST JUNE




10AM 21ST JUNE




11AM 21ST JUNE




12NOON 21ST JUNE



1PM 21ST JUNE



2PM 21ST JUNE



3PM 21ST JUNE




Grey area indicates shadows cast by proposed development

 $\square$ Shadows cast by existing buildings on site

Pink area indicates shadows cast by neighboring properties

LOCKED BAG 5022 PARRAMATIA NSW 2124 PHONE No 1800 738 718 PHONE No 1800 738 718	arry Rush & Associates Pty Ltd chitects. Nominated Architect: Barry John Rush 83 Registration No 3753 ine 25A, 2 Beatelis Street, Balmain, NSW one: (CJ 955 5022 Email; Info@barryrush.com.au Wabryrush.com.au	A 23/03/22 DA PLAN ISSUE DATE NOTATION/AMENDMENT DO NOT SCALE DRAWINGS. CHECK ALL DIMENSIONS ON SITE.	PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 8753 9000 LANDSCAPE CONSULTANT GREENLAND DESIGN PTY LTD	ACOR CONSULTANTS PTY LTD PH (02) 4324 3499 HYDRAULIC CONSULTANT		reouton SENIORS DEVELOPMENT 26 ROSE CRESCENT AND 69-73 BOURKE STREET NORTH PARRAMATTA LOTS 2, 3 & 4 in DP 215342
------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	-------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------	-----------------------------------------------------------------------	--	---------------------------------------------------------------------------------------------------------------------------------






Bourke St 24


			STATUS: DA				
MID WINTER	5	DATE: 2/05/22	SCALE: N.T.S.	PROJ:	PROJECT No. BGXWX		
		stage:	DRAWN:	CHECKED:	NOMINATED ARCHITECT:		
FILE:	PLOTTED:	A	A12		A		

0 5 10 20 SCALE FOR PRINTING PURPOSE ONLY 40MM






10AM 21ST JUNE



11AM 21ST JUNE




12NOON 21ST JUNE





2PM 21ST JUNE



3PM 21ST JUNE



					ARCHITECT	CIVIL CONSULTANT	BUSINESS PARTNER:	PROJECT:
					BARRY RUSH & ASSOCIATES PTYLTD	ACOR CONSULTANTS PTYLTD		SENIORS DEVELOPMENT
	with the mark the same				PH (02) 9555 8028	PH (02) 4924 3499		
	Barry Rush & Associates Pty Ltd				PROJECT MANAGER	HYDRAULIC CONSULTANT		26 ROSE CRESCENT AND
	Architects. Nominated Architect: Barry John Rush	А	23/03/22	DA PLAN ISSUE	LAND & HOUSING CORPORATION	MARLINE NEWCASTLE PTYLTD		69-73 BOURKE STREET
	ARB Registration No 3753 Suite 25A, 2 Beattie Street, Balmain, NSW	REV	DATE	NOTATION/AMENDMENT		PH (02) 4925 9300 FAX (02) 4926 3811		NORTH PARRAMATTA
	Phone: (02) 9555 8028 Email: info@barryrush.com.au		Brite			ELECTRICAL CONSULTANT		
.gov.au/land-and-housing-corporation	www.barryrush.com.au		DO NO	T SCALE DRAWINGS. CHECK ALL DIMENSIONS ON SITE. FIGURED DIMENSIONS TAKE PRECEDENCE.		MARLINE NEWCASTLE PTYLTD		LOTS 2.3 & 4 in DP 215342
				FIGURED DIMENSIONS TAKE FRECEDENCE.	PH 0403 164 198	PH (02) 4925 9300 FAX (02) 4926 3811		



	VIEWS FROM SUN DIAGRAMS			STATUS: DA					
				SCALE: N.T.S.		PROJECT NO. BGXWX			
			STAGE:	DRAWN: MB	CHECKED: BR	NOMINATED ARCHITECT:			
	HLE: A12-A14 SHADOWS 3D.dwg	PLOTTED: 14/02/2022 11:30 AM	A	A13		REV: A			

0<u>510</u>20 40MM SCALE FOR PRINTING PURPOSE ONLY



BOURKE STREET - STREETSCAPE PERSPECTIVE



ROSE CRESCENT - STREETSCAPE PERSPECTIVE




LOCKED BAG 5022 PARRAMATTA NSW 2124 PHONE No 1800 738 718 https://www.dpie.nsw.gov.


	Barry Rush & Associates Pty Ltd
	Architects. Nominated Architect: Barry John Rush ARB Registration No 3753
	Sulte 25A, 2 Beattle Street, Balmain, NSW
au/land-and-housing-corporation	Phone: (02) 9555 8028 Email: Info@barryrush.com.au www.barryrush.com.au


				ARCHITECT	CIVIL CONSULTANT	BUSINESS PARTNER:	PROJECT:
				BARRY RUSH & ASSOCIATES PTY LTD PH (02) 9555 8028	PH (02) 4924 3499		SENIORS DEVELOPMENT
ŀ	_			PROJECT MANAGER	HYDRAULIC CONSULTANT		26 ROSE CRESCENT AND
	A	23/03/22	DA PLANISSUE	LAND & HOUSING CORPORATION	MARLINE NEWCASTLE PTY LTD PH (02) 4925 9300 FAX (02) 4926 3811		69-73 BOURKE STREET
Į.	REV	DATE	NOTATION/AMENDMENT	LANDSCAPE CONSULTANT	ELECTRICAL CONSULTANT		NORTH PARRAMATTA
		DO NOT	SCALE DRAWINGS. CHECK ALL DIMENSIONS ON SITE. FIGURED DIMENSIONS TAKE PRECEDENCE.	GREENLAND DESIGN PTY LTD PH 0403 164 198	MARLINE NEWCASTLE PTY LTD PH (02) 4925 9300 FAX (02) 4926 3811		LOTS 2, 3 & 4 in DP 215342



9 August 2023









	ARCHITECT	CIVIL	BUSINESS PARTN
	BARRY RUSH & ASSOCIATES PTY LTD PH (02) 9555 8028	ACOR CONSULTANTS PTY LTD PH (02) 4324 3499	
	111 (02) 3333 0020	PH (02) 4324 3499	4
	PROJECT MANAGER	HYDRAULIC CONSULTANT	
	LAND & HOUSING CORPORATION PH (02) 8753 9000	MARLINE NEWCASTLE PTY LTD PH (02) 4925 9300 FAX (02) 4926 3811	
	LANDSCAPE CONSULTANT	ELECTRICAL CONSULTANT	1
ONS ON SITE.	GREENLAND DESIGN PTY LTD PH 0403 164 198	MARLINE NEWCASTLE PTY LTD	





scale 1:25





Plant Schedule								
ID Qty		Common Name	Botanical Name	Size	Mature Height	Mature Spread	Native (N)	
Trees								
CalKing	8	Bottlebrush	Callistemon 'Kings Park Special'		3 - 6m	2.0 - 3.5m	N	
GorAxi	6	Gordonia	Gordonia axillilaris	75Litre	4 - 6m	3.5 - 6m		
SteSin	3	Firewheel Tree	Stenocarpus sinuatus	75Litre	15 - 20m	5 - 10m	N	
TriLus	5	Water Gum	Tristaniopsis laurina 'Luscious'	75Litre	6 - 8m	3.5 - 6m	N	
WatGre	7	Green Avenue	Waterhousia 'Green Avenue'	75Litre	13 - 15m	6 - 10m	N	
Shrubs								
AcaGree	57	Green Mist	Acacia cognata 'Green Mist'	200mm	1.0 - 1.5m	0.8 - 1.0m	N	
AlpCae	54	Native Ginger	Alpinia caerulea	200mm	0.9 - 1.5m	0.9 - 1.2m	N	
CalEnd	29	Scarlet Bottlebrush	Callistemon citrinus 'Endevour'	200mm	3 - 5m	2.0 - 3.5m	N	
CallAll	25	All Aglow Bottle Brush	Callistemon 'All Aglow'	200mm	1.5 - 2.0m	1.0 - 1.5m	N	
CalLit	49	Little John	Callistemon "Little John"	200mm	0.9 - 1.5m	0.9 - 1.2m	N	
CorAlb	65	White Correa	Correa alba	200mm	0.9 - 1.5m	0.9 - 1.2m	N	
CosEve	17	Evening Glow Mirror Plant	Coprosma 'Evening Glow'	200mm	1.2 - 1.5m	0.9 - 1.2m	N	
DorExc	25	Gymea Lily	Doryanthes excelsa	200mm	1.5 - 2m	1.2 - 2.0m	N	
GreHon	19	Honey Gem Grevillea	Grevillea 'Honey Gem'	200mm	3.0 - 4.0m	2.0 - 3.0m	N	
SyzRes	69	Resilience Lilly Pilly	Syzygium 'Resilience'	200mm	2 - 3m	1.2 - 2.0m	N	
WesFru	7	Jervis Gem	Westringia fruticosa 'Jervis Gem'	200mm	0.8 - 1.2m	0.8 - 1.2m	N	
Ground C	overs							
LomSha	211	Shara Mat Rush	Lomandra longifolia 'Shara'	150mm	0.45 - 0.55m	0.5 - 0.6m	N	
DicEme	106	Emerald Falls Dichondra	Dichondra 'Emerald Falls'	150mm	0.0 - 0.3m	0.9 - 1.2m	N	
DiaTas	79	Flax Lily	Dianella tasmanica 'Tasred'	150mm	0.4 - 0.5m	0.4 - 0.5m	N	
CasCou	84	Cousin It	Casuarina 'Cousin It'	150mm	0.10 - 0.15m	0.8 - 1.0m	N	
SenTri	32	Trident Blue	Senecio Trident Blue	150mm	0.2 - 0.3m	0.5 - 1.0m	N	
DiaBla	9	Flax Lily	Dianella tasmanica 'Blaze'	150mm	0.4 - 0.5m	0.4 - 0.6m	N	
HypGol	27	Gold Nuget	Hymenosporum flavum 'Gold Nuget'	150mm	0.10 - 0.15m	0.8 - 1.0m	N	
MyoYar	152	Carpet Spreading Myoporum	Myoporum parvifolium 'Yareena'	150mm	0.05 - 0.1m	0.8 - 1.0m	N	
HarMee	86	Meema	Hardenbergia violacea "Meema"		0.4 - 0.6m	1.5 - 2.0m	N	
PenRub	122	Purple Fountain Grass	Pennisetum 'Rubrum'	150mm	1 - 1.5m	0.5 - 0.9m	N	
JunUsi	JunUsi 214 Tussock Rush Juncus usitatus		Juncus usitatus	150mm	0.5 - 0.7m	0.8 - 1.0m	N	
DiaLit	51	Spreading Flax Lily	Dianella revoluta 'Little Rev'	150mm	0.3 - 0.45m	0.3 - 0.6m	N	
BanBir	45	Birthday Candle	Banksia spinulosa 'Birthday Candle'	150mm	0.45 - 0.6m	0.9 - 1.2m	N	
GrePoor	89	Royal Mantle Grevillea	Grevillea 'Poorinda Royal Mantle'	150mm	0-0.1m	2.0 - 3.0m	N	

GREENLAND DESIGN												
TWELVE MONTHS MAINTENANCE SCHEDULE		Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Plant Care												
Monitoring												
Pruning as required												
Deadhead /tip pruning												
Slow release fertilise												
Rapid suluble fertilise as required												
Cut back perenials and grasses												
Watering as required												
Garden Bed												
Edging												
Remove weeds and herbicide spraying as required												
Top up mulch as required												
Dead foliage removal												
Pest Management												
Monitoring and herbicide spraying as required												
Turfed Area												
Fertilise												
Make good turf as required												
Winter clean up												
Remove dead foliage and pruning as required												




LOCKED BAG 5022 PARRAMATTA NSW 2124 PHONE No 1800 738 718 https://www.dpie.nsw.gov.au/land-and-housing-corporation

NOMINATED ARCHITECT: Barry Rush & Associates Pty Ltd B 16/02/2022 DA Suite 25A, 2 Beattie Street, Balmain, NSW, 2041 Phone: (612) 9555 8028 Fax: (612) 9810 0161 Email: info@barryrush.com.au

www.barryrush.com.au

E 07/12/2022 DA D 02/05/2022 DA C 21/03/2022 DA 20/01/2022 SKETCH NOTATION/AMENDMENT DATE DO NOT SCALE DRAWINGS. CHECK ALL DIMENSIONS O FIGURED DIMENSIONS TAKE PRECEDENCE.



#### **SPECIFICATION NOTES** PLANTING MATERIALS

Planting Mix:

Planting mix for tree pit backfill shall be "Organic Garden Mix" consisting of 50% Black Soil

- 20% Coarse Sand
- 30% Organic Material

as available from Australian Native Landscapes, Phone: [02] 9450 1444, or approved equivalent. Samples shall be provided to the Superintendent prior to ordering or delivery to site. Any material delivered to site, that is rejected by the Superintendent, shall be removed by the contractor at his own expense. Minimum depths of mix to all planting bed areas is as specified on details. Mulch:

Mulch to garden bed:

Mulch shall mean hardwood mulch (25mm grade), free from material derived from Privet, Willow, Poplar, Coral trees, or other noxious weeds. Any mulch exceeding the 25mm grade shall be rejected / removed from the site. Graded hardwood mulch to be supplied by Australian Native Landscapes Pty Ltd Phone (02) 9450 1444, or approved equivalent.

Spread mulch so that after settling, it is: • smooth and evenly graded between design surface levels;

- flush with adjacent finished levels;
- of the required depths (75mm); and

• sloped towards the base of plant stems in plantation beds, but not in contact with the stem (not closer than 50mm in the case of gravel mulches).

Place after the preparation of the planting bed, planting and all other work.

## Plant Material:

All plant material must be true to the species. No substitutes will be allowed. All plants shall be free of fungus and insect damage. All plants shall be healthy, well shaped, not soft or force grown and not root bound.

Plants are available from Andreasens Green wholesale nursery, contact Darren (02) 8777 4713, email darren@andreasensgreen.com.au or approved equivalent. Tured areas:

All new turfed areas are to be selected weed free Soft Leaf Buffalo. Turf shall be laid neatly butted with staggered joins, flush with adjacent surfaces and have even running falls to all drainage points.

All new turfed area shall have a minimum 150mm depth of weed free top soil, placed and levelled prior to turfing.

## PREPARATION AND HARDWORKS

Excavating for Spot Planting To planting areas, excavate a hole for each plant large enough to provide not less than twice the depth and twice the diameter than the root ball of species to be planted.

## Staking

Use durable hardwood, straight, free from knots or twists, pointed at one end. Drive stakes into the ground a minimum one third of their length, avoiding damage to the root system.


• 75 Litre trees in 2 x 38x38x1800mm Hardwood Stake with double Nylon tie TIES: Provide a 50mm wide Nylon webbing tie per stake, fixed securely to the stakes, one tie at half the height of the main stem and the other as necessary to stabilise the plant.

## Concrete Edge

MATERIALS: Concrete to be off white colour.


INSTALLATION: Supply and install 150 x 100mm (width) reinforced flush concrete kerb to locations as approved on site by the Superintendent. Provide flexible joints at maximum 3 metre intervals in colour to match concrete. Lightly expose aggregate through rinsing / sponging. Tool finish exposed edges with 10mm pencil round to prevent chipping.

	ARCHITECT		PROJECT:
	BARRY RUSH & ASSOCIATES PTY LTD PH (02) 9555 8028		SENIORS DEVELOPMENT
	PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 8753 9000		26 ROSE CRESCENT AND 69-73 BOURK
	LANDSCAPE CONSULTANT		NORTH PARRAMATTA
ON SITE.	GREENLAND DESIGN PTY LTD PH 0403 164 198		LOTS 2,3 & 4 IN DP 215342



				DA						
	LANDSCAPE DETAILS AND		DATE: <b>07/12/2022</b>	scale: 1:100	PROJ:	PROJECT NO. BGXWX				
KE STREET	SPECIFICATION		stage: DA	DRAWN: CL	CHECKED: GD	LANDSCAPE ARCH				
	FILE: 2509		TYPE	sheet: 2 of 1	2	REV:				

# PROPOSED DEVELOPMENT (No.26) ROSE CRESCENT & (No. 69-73) BOURKE STREET, NORTH PARRAMATTA STORMWATER MANAGEMENT PLANS



#### **GENERAL NOTES**

- THESE PLANS SHALL BE READ IN CONJUNCTION WITH OTHER RELEVANT CONSULTANTS' PLANS, SPECIFICATIONS, CONDITIONS OF DEVELOPMENT CONSENT AND CONSTRUCTION CERTIFICATE REQUIREMENTS. WHERE DISCREPANCIES ARE FOUND ACOR CONSULTANTS (CC) MUST BE CONTACTED IMMEDIATELY FOR VERIFICATION WHERE THESE PLANS ARE NOTED FOR DEVELOPMENT APPLICATION 2 PURPOSES ONLY, THEY SHALL NOT BE USED FOR OBTAINING A CONSTRUCTION CERTIFICATE NOR USED FOR CONSTRUCTION PURPOSES SUBSOIL DRAINAGE SHALL BE DESIGNED AND DETAILED BY THE 3 STRUCTURAL ENGINEER. SUBSOIL DRAINAGE SHALL NOT BE CONNECTED INTO THE STORMWATER SYSTEM IDENTIFIED ON THESE PLANS UNLESS APPROVED BY ACOR CONSULTANTS (CC) STORMWATER CONSTRUCTION NOTES ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH AS/NZS 3500 (CURRENT EDITION) AND THE REQUIREMENTS OF THE LOCAL COUNCIL'S POLICIES AND CODES THE MINIMUM SIZES OF THE STORMWATER DRAINS SHALL NOT BE 2 LESS THAN DN90 FOR CLASS 1 BUILDINGS AND DN100 FOR OTHER CLASSES OF BUILDING OR AS REQUIRED BY THE REGULATORY AUTHORITY THE MINIMUM GRADIENT OF STORMWATER DRAINS SHALL BE 1%, UNLESS NOTED OTHERWISE COUNCIL'S TREE PRESERVATION ORDER IS TO BE STRICTLY ADHERED TO. NO TREES SHALL BE REMOVED UNTIL PERMIT IS OBTAINED PUBLIC UTILITY SERVICES ARE TO BE ADJUSTED AS NECESSARY AT 5 THE CLIENT'S EXPENSE ALL PITS TO BE BENCHED AND STREAMLINED. PROVIDE STEP IRONS FOR ALL PITS OVER 1.2m DEEP MAKE SMOOTH JUNCTION WITH ALL EXISTING WORK
  - VEHICULAR ACCESS AND ALL SERVICES TO BE MAINTAINED AT ALL 8 TIMES TO ADJOINING PROPERTIES AFFECTED BY CONSTRUCTION
  - SERVICES SHOWN ON THESE PLANS HAVE BEEN LOCATED FROM INFORMATION SUPPLIED BY THE RELEVANT AUTHORITIES AND FIELD INVESTIGATIONS AND ARE NOT GUARANTEED COMPLETE NOR CORRECT. IT IS THE CLIENT & CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL PRIOR TO CONSTRUCTION
  - 10 ANY VARIATION TO THE WORKS AS SHOWN ON THE APPROVED DRAWINGS ARE TO BE CONFIRMED BY ACOR CONSULTANTS (CC) PRIOR TO THEIR COMMENCEMENT

#### **RAINWATER RE-USE SYSTEM NOTES**

- RAINWATER SUPPLY PLUMBING TO BE CONNECTED TO OUTLETS WHERE REQUIRED BY BASIX CERTIFICATE (BY OTHERS)
- TOWN WATER CONNECTION TO RAINWATER TANK TO BE TO THE 2. SATISFACTION OF THE REGULATORY AUTHORITY. THIS MAY **REQUIRE PROVISION OF** 
  - 2.1. PERMANENT AIR GAP
  - BACKFLOW PREVENTION DEVICE 22
- NO DIRECT CONNECTION BETWEEN TOWN WATER SUPPLY AND THE 3. RAIN WATER SUPPLY
- AN APPROVED STOP VALVE AND/OR PRESSURE LIMITING VALVE AT 4 THE RAINWATER TANK
- PROVIDE APPROPRIATE FLOAT VALVES AND/OR SOLENOID VALVES 5. TO CONTROL TOWN WATER SUPPLY INLET TO TANK IN ORDER TO ACHIEVE THE TOP-UP INDICATED ON THE TYPICAL DETAIL
- 6. ALL PLUMBING WORKS ARE TO BE CARRIED OUT BY LICENSED PLUMBERS IN ACCORDANCE WITH AS/NZS3500.1 NATIONAL PLUMBING AND DRAINAGE CODE
- PRESSURE PUMP ELECTRICAL CONNECTION TO BE CARRIED OUT BY 7. A LICENSED ELECTRICIAN
- ONLY ROOF RUN-OFF IS TO BE DIRECTED TO THE RAINWATER TANK 8. SURFACE WATER INLETS ARE NOT TO BE CONNECTED
- 9. PIPE MATERIALS FOR RAINWATER SUPPLY PLUMBING ARE TO BE APPROVED MATERIALS TO AS/NZS3500 PART 1 SECTION 2 AND TO BE CLEARLY AND PERMANENTLY IDENTIFIED AS 'RAINWATER'. THIS MAY BE ACHIEVED FOR BELOW GROUND PIPES USING IDENTIFICATION TAPE (MADE IN ACCORDANCE WITH AS2648) OR FOR ABOVE GROUND PIPES BY USING ADHESIVE PIPE MARKERS (MADE IN ACCORDANCE WITH AS1345)
- 10. EVERY RAINWATER SUPPLY OUTLET POINT AND THE RAINWATER TANK ARE TO BE LABELED 'RAINWATER' ON A METALLIC SIGN IN ACCORDANCE WITH AS1319
- ALL INLETS AND OUTLETS TO THE RAINWATER TANK ARE TO HAVE 11 SUITABLE MEASURES PROVIDED TO PREVENT MOSQUITO AND VERMIN ENTRY

OCOPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified y or in part without written permission from ACOR Consultants (CC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOF

TIMES

DIAL BEFORE

YOU DIG

www.1100.com.au

IMPORTANT: THE CONTRACTOR

IS TO MAINTAIN A CURRENT SET

OF "DIAL BEFORE YOU DIG" DRAWINGS ON SITE AT ALL

						Client
D	D UPDATED TO SUIT COUNCILS COMMENTS			BK	North	
С	UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN & COUNCILS COMMENTS		RH	BK		BARRY RU
В	UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN		RH	BK		
Α	ISSUED FOR DEVELOPMENT APPROVAL		RH	BK	1 4 1 9	PTY LTD
Issue	Description	Date	Drawn	Approved	$1 \setminus  $	
1	0 1cm at full size 10cm	_			$\cup$	

SH & TES





9 August 2023



2229

### PARRAMATTA COUNCIL REQUIREMENTS

SITE AREA (m<sup>2</sup>)

**ON-SITE DETENTION** REFER TO SHEET C4 FOR THE UPPER PARRAMATTA RIVER CATCHMENT TRUST ON-SITE DETENTION DRAINAGE CALCULATIONS

RAINWATER RELISE PROVIDE RAINWATER REUSE TANK AS REQUIRED BY BASIX. RAINWATER REUSE VOLUME PROVIDED = 30m<sup>3</sup>

SITE DISCHARGE TO EXISTING STORMWATER PIT IN BOURKE STREET REFER TO SHEET C2

DESIGN HAS BEEN PREPARED IN ACCORDANCE WITH PARRAMATTA COUNCIL DESIGN & DEVELOPMENT GUIDELINES, UPPER PARRAMATTA RIVER CATCHMENT TRUST, AR&R AND AS/ANZS 3500

### SHEET INDEX

- COVER SHEET & NOTES
- STORMWATER MANAGEMENT PLAN
- STORMWATER MANAGEMENT DETAILS SHEET No.1
- OSD CALCULATION SHEET & MAINTENANCE SCHEDULE
- OSD CHECKLIST SHEET 1 OF 2
- OSD CHECKLIST SHEET 2 OF 2
- **EROSION & SEDIMENT CONTROL PLAN**
- **FROSION & SEDIMENT CONTROL NOTES & DETAIL SHEET**
- STORMWATER QUALITY REPORT SHEET 1 OF 2
- STORMWATER QUALITY REPORT SHEET 2 OF 2


SHEET C2 SHEET C3 SHEET C4 SHEET C5 SHEET C6 SHEET C7 SHEET C8 SHEET C9 SHEET C10


SHEET C1

### DEVELOPMENT APPLICATION ISSUE NOT FOR CONSTRUCTION

### DRAWINGS MUST BE PRINTED IN COLOUR

SIDENTIAL	Drawing Title	SHEET	& NOTE	S	
l	Drawn	Date	Scale A1	Q.A. Check	Date
IT &	RH	NOV 21	AS NOTED	BAK 07	7.02.22
EET	Designed	Project No.		Dwg. No.	Issue
	ВК	CC210	393	C1	D





7	This page last updated Ju	ne 2004	B.1-1	On-Site Stormwater De	tent	ion Handbook	
Form B1 <sup>1</sup> No.	DRAINAGE DESI	GN SUM	MARY	SUB/DA			
Project:	CC210393	Location:	26 ROSE	CRESCENT & 69-73 BOUF	RKE	STREET	_
Designec 334	RH	Company:	ACOR CON	SULTANTS (CC) Pty. Lt	td	Phone: (02) 432	24 3499
SITE AREA	0.2229	ha *See Se	ection 3.4.3	for dual occupancy			[A]
	hment draining throu 1.3 for assessment of volume	-	ws. 0.2229		=_ _	0 ha 104.76 m <sup>3</sup>	[AA] [B]
Basic Discharge		0.2229			_	0.0178 m <sup>3</sup> /s	[C]
Area of site dra (Must be as mu	ained to storage uch as possible and n vithout written Counc				_	0.1899 ha	[D]
[D]/[A] + [	0.1899 ]/[	0.2229	] x 100		=_	85%	[E]
Storage per ha	. Of contributing area	a = [B]/[D]			=_	551.67	[F]
	PSD adjustment char in litres/second/ha (		sing [F], and	1	=_	64.83 l/s/ha	[G]
Determine PSD	) = [G] x [D]	64.83	x	0.1899	=_	12.31 l/s	[H]
Maximum head	d to orifice center				=_	<u>0.92</u> m	[K]
Weir flow to st	orage Q <sup>Weir</sup>	=CL(H <sup>Weir</sup> )	1.5	<sub>H</sub> Weir	=_	0.16 m	[1]
Select orifice d	iameter: d=(0.464	$1 \times Q/\sqrt{h}$	5 =(0.464×[	H]/√[K]) <sup>0.5</sup>	=_	0.077 m	[1]
Maximum disc	harge				=_	12.31 l/s	[L]
Head for high e	early discharge				=	<u>0.77</u> m	[M]
High early disc	harge {[L]×√[№	/]/[K] }	(min 75%	6 of [L])	=_	11.26 l/s	[N]
Approximate n	nean discharge = ([L]	+ [N])/2			=_	11.79 l/s	[P]
Average discha	arge/ha = [P]/[D] =	= 11.79	/ 0.1899	)	=	62.07 l/s/ha	[Q]
	PSD adjustment char nal storage volume p		sing [Q]		=_	<u>569.50</u> m³/ha	[R]
Determine fina	al SSR = [R] x [D] =	= 569.50	x 0.1899	)	=_	<u>108                                    </u>	[S]
Primary storag	e proportion =	[S]	x	%	_	m³	[T]
Secondary stor	rage proportion =	[S]	x	%	_	m³	[U]
Tertiary storag	e proportion =	[S]	x	%	_	m <sup>3</sup>	[V]
Check [T] + [U]	+ [V] = [S]					m³	

### OSD STORMWATER MAINTENANCE SCHEDULE

MAINTENANCE ACTION	FREQUENCY	RESPONSIBILITY	PROCEDURE
Drainage Control Pit (DCP)			
Inspect and remove any blockage of orifice	Six monthly	Owner	Remove grate and screen to inspect orifice. See plan for location of DCP
Check attachment of orifice plate to wall of pit (gaps less than 5mm)	Annually	Maintenance Contractor	Remove grate and screen. Ensure plate mounted securely, tighten fixings if required. Seal gaps as required.
Check orifice diameter correct and retains sharp edge	Five yearly	Maintenance Contractor	Compare diameter to design (see Work-As- Executed) and ensure edge is not pitted or damaged
Inspect screen and clean	Six monthly	Owner	Remove grate and screen if required to clean it.
Check attachment of screen to wall of pit	Annually	Maintenance Contractor	Remove grate and screen. Ensure screen fixings secure. Repair as required
Check screen for corrosion	Annually	Maintenance Contractor	Remove grate and examine screen for rust or corrosion, especially at corners or welds.
Inspect flap valve and remove any blockage	Six monthly	Owner	Remove grate. Ensure flap valve moves freely and remove any blockages or debris.
Check attachment of flap valve to wall of pit	Annually	Maintenance Contractor	Remove grate. Ensure fixings of valve are secure
Check flap valve seals against wall of pit	Annually	Maintenance Contractor	Remove grate. Fill pit with water and check that flap seals against side of pit with minimal leakage.
Inspect overflow weir and remove any blockage	Six monthly	Maintenance Contractor	Remove grate and open cover to ventilate underground storage if present. Ensure weir clear of blockages.
Inspect DCP walls (internal and external, if appropriate) for cracks or spalling	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Inspect DCP sump and remove any sediment / sludge	Six monthly	Owner	Remove grate and screen. Remove sediment / sludge build-up and check orifice and flap valve clear.
Inspect grate for damage or blockage	Six monthly	Öwner	Check both sides of grate for corrosion (especially corners and welds) damage or blockage.
Inspect return pipe from storage and remove any blockage	Six monthly	Maintenance Contractor	Remove grate and screen. Ventilate underground storage if present. Check orifice and remove any blockages in outlet pipe. Flush outlet pipe to confirm it drains freely. Check for sludge / debris on upstream side of return line.
Storage			
Inspect pit and remove any sediment / sludge in pit	Six monthly	Maintenance Contractor	Remove grate and screen. Remove sediment / sludge build-up.
Inspect internal tank walls (and external, if appropriate) for cracks or spalling	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Inspect and remove any debris / litter / mulch etc. blocking grates	Six monthly	After storm event	Remove blockages from grate and check if pit blocked.
Inspect tank storage are and remove debris / mulch / litter etc. likely to block screens / grates.	Six monthly	Maintenance Contractor	Remove debris and floatable material likely to be carried to grates.
Compare storage volume to volume approved (Rectify if loss > 5%)	Annually	Maintenance Contractor	Compare actual storage available with Work-as- Executed plans. If volume loss is greater than 5%, arrange for reconstruction to replace the volume lost Council to be notified of the proposal.
Inspect storages for subsidence near pits.	Annually	Maintenance Contractor	Check along drainage lines and at pits for subsidence likely to indicate leakages.

<sup>i</sup> Revised for third edition to include flow from upstream and revised by pass flows

#### Upper Parramatta River Catchment Trust

RIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified duced or copied wholly or in part without written permission from ACOR Consultants (CC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants Pty Ltd by ACOR Consultants

		Client				
D	UPDATED TO SUIT COUNCILS COMMENTS	08.03.23	RH	BK	North	BARRY RUSH &
С	UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN & COUNCILS COMMENTS	08.12.22	RH	BK		
В	B UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN		RH	BK		& ASSOCIATES
A	A ISSUED FOR DEVELOPMENT APPROVAL		RH	BK		PTY LTD
Issue	Description	Date	Drawn	Approved		1
1 0	10m till size 10cm	_				1

chitect



IERS DEVEL

9 August 2023

ESIDENTIAL	Drawing Title OSD CALCULATION SHEET & MAINTENANCE SCHEDULE							
	Drawn	Date	Scale A1	Q.A. Check	Date			
NT &	RH	NOV 21	AS NOTED	BAK 07	7.02.22			
REET	Designed	Project No.		Dwg. No.	Issue			
	вк	CC210	393	C4	D			

9 August 2023

This page last updated December 1999 B.9-1 On-site Stormwater Detention Handbook B9. OSD DETAILED DESIGN SUBMISSION		This page last updated December 1999 B.9-2 OSD DETAILED DESIGN
This form is to be completed by the stormwater designer and submitted to Council together with the design plants and any necessary attachments.         PROJECT ADPRESS:       28 ROSE CRESCENT & 69-73 BOURKE STREET, PARAMATTA         PROJECT ADPRLICAT:       BARRY RUSH & ASSOCIATES PTV LTD         OSD DESIGNER DETAILS:       Company Name:         Company Name:       COCONSULTANTS (CC) PTV LTD         Address:       SUITE 2.01, 4 ILYA AVENUE, ERINA NSW 2250         Telephone No:       (02) 43243499         Cacreditation organisation:		ITEM 1. A Stormwater Concept Plan (SCP) has been approv (refer Section 4.1) 2. The site (whole or partly) is defined as floodprone in if YES, see Plan No

D	UPDATED TO SUIT COUNCILS COMMENTS	08.03.23	RH	BK	North	BAR
С	UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN & COUNCILS COMMENTS	08.12.22	RH	BK		
В	UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN	27.04.22	RH	BK		& AS
А	ISSUED FOR DEVELOPMENT APPROVAL	07.02.22	RH	BK		PTY LT
Issue	Description	Date	Drawn	Approved		
1 .0	1cm at full size					

C COPYRIGHT O eproduced o



SERS INFRASTRUCTURE PLAN

Kein

.

ormwater Detention Handbook

### KLIST

	DESIC		COUNCIL REVIEW				
a wara posili kane	YES	NO	YES	NO			
usly		<	in months to say				
ir event		L					
2012 - 1995 - 10 Million 2017 - 1995 - 10 Million			and the second second	1.000000000000000000000000000000000000			
	N/A	6= 192-192-1 6= 192-192-1	1				
tions?		t as reproved	Na 264-91 (2006) 10-1-11-12-01				
year	N/A	NOTE LIFE Y	in the second	<u></u>			
ycai	N/A						
	acr. cr-082		Lating to Bally and	2502			
ARI							
ermined,	N/A	er en Paul					
vent							
dated							
on an							
d SCP		CONTRACTOR BILL	18. 1993 A ACPU A	-1			
y affect			the standard and				
d							
hich	-D' TOLONT	1 1 1 1 1 1 1 1	<u>1999 - 1997 (1997)</u>	<u></u>			
9.65 a , DC 19. KH	The second second		-	L N			
CONT 01 CO 196000 1005	Same and		UNTERPETION JOIN	and the second			
d?	HADOLES ST						
62		101000-001-0000- 01-07-00-00-0	and the second	Neige XII man			
1997,040 - 5 a case V				hy on the second s			
NA 10 270900.5		MARINE PROPERTY.					
?	eputation of Actions proceeding of Actions		v m premier national and the	<u>, 11, 1997 (11, 1</u>			
been							
			dilicoconto in a				
en	$\checkmark$						
	arrayart 2-1		0 <sub>21</sub> 0				
than							
inted).	Zalas "Auflinium sel	Partic Artilland, Inc.	Sultana and a sub-	) Representation			
nd	$\checkmark$		Concession of the second				
5. 257 games - 278 - 4.11 V		LICENCE AND LICENCE					
ive been	$\checkmark$						
)				Allenter and and			
idjoining	$\checkmark$						
	Parent and the						
t the							

SIDENTIAL	Drawing Title OSD CI SHEET	HECKLIS 1 OF 2	T		
I IT &	Drawn RH	Date NOV 21	Scale A1 AS NOTED	Q.A. Check BAK 07	Date 7.02.22
REET	Designed BK	Project No. CC210	393	Dwg. No. C5	lssue D

22

## ON-SITE DETENTION CHECKLIST - SHEET 2 OF 2

Õ

This page last updated December 1999 $\mu_{0}$ $\mu_{0}$ On-site Stormwater Detention Han	This page last updated December 1999	<b>B</b> 9-3	<b>On-site Stormwater Detention Handl</b>	000
-------------------------------------------------------------------------------------------	--------------------------------------	--------------	-------------------------------------------	-----

Where there is more than one OSD system, Questions 18 to 26 are to be answered separately for each OSD storage system.

OSD Storage system identifier.....

ITEM	DESIG	NER	COUNCIL REVIEW	
	YES	NO	YES	NC
<ol> <li>The design explicitly shows how all the drained area grades to the storage, including roof gutter overflows (refer Section 6.2)</li> </ol>	$\checkmark$			
If YES, see Plan No				and all the second second
If NO, see calculations in Attachment E showing how all drainage system components (including all roof gutters, downpipes, collecting pits and pipe systems, etc) have 100 year ARI capacities with 50% blockage factor				
19. The invert level of storage is not less than ground level (or top of kerb) at point of connection to external stormwater system.	$\checkmark$			
If YES, see Plan No.	Carlo and Carlos and			CONT OF GAMES
If NO, see explanatory notes in Attachment F	No. 1 There a S		- Juliov - A	
<ol> <li>The discharge control pit design is consistent with the principles shown in Figures 4.3, 7.10 and/or 7.11</li> </ol>	$\checkmark$			
20(a) The DCP has an open grating type lid (for ease of inspection)	$\checkmark$	10,000		
20(b) The DCP minimum dimensions are consistent with Section 4.2.3	Carl	A THE ADDRESS		
20(c) The floor of the DCP has a localised sump adjacent to the orifice with level at least 150 mm below the return pipe, (refer Section 4.2.8)	$\checkmark$			
20(d) The return pipe from the storage is at least 150 mm in diameter (refer Section 4.2.8)	$\checkmark$		27 SE 9, SI 1, P	66 97 (
20(e) The return pipe flap valve is consistent with Figure 4.3	$\checkmark$			
20(f) If an orifice control is specified, is it consistent with the requirements set out in Section 4.2.3?	$\checkmark$	The state of the		875.2009.V
If YES, see: Plan No. C2.&C3 for stainless steel plate specification, thickness and fixing to pit wall		-		
20(g) The overflow weir is fitted with a basket (refer Section 6.3). There is a surface grate above the basket to facilitate inspection and maintenance				
20(h) The high early discharge (HED) characteristics are consistent with the requirements set out in Section 4.2.3	$\checkmark$			
If YES, see: Plan No. C2.&C3 for height of discharge to storage relative to permissible site discharge (PSD)				
Accompanying weir calculations in Attachment E	Construction Construction	anne sterre and	17	Ball 1072- 1073
Plan Noshowing majority of site drainage system connecting to the DCP & the volume of the DCP is small compared to the volume of the storage		2000 - 2000 - 200 - 200 - 200 		9990-04-
20(i) The screen design is consistent with Section 4.2.5			anger of the second	
If YES, see: Plan No.C2.&C3 for screen type, area and orientation				
Plan No. <mark>C2.&amp; C3</mark> for fabrication note re aperture orientation				
Plan No C2 & C3. for fixing and handle details		8	and the second second	
Plan NoC2.&C3. showing how all inflows to the DCP are on the upstream side of the screen protecting the orifice				
20(j) The outlet pipe from the DCP has a capacity at least twice the PSD (refer Section 4.2.4)	$\checkmark$			
If YES, see calculations in Attachment E			c	

Upper Parramatta River Catchment Trust

ITEM	DESIG	NER		INCIL /IEW
The second s	YES	NO	YES	NC
21. If an above ground/landscaped storage is specified, answer				
Q21(a) to Q21(g), otherwise move to Q22.	Solita, Mar. 1 Mar. 400			2011 2 100
21(a) The first 10%-20% of storage is provided in an area able to tolerate frequent inundation(refer Section 4.2.7)		E 62.53	a dana di Sila Bana da ana di Arti di	
A REAL PROPERTY OF A REAL PROPER		- ALTROLLATION IN		- 14- 14 18-15 - 14- 14-18-15
21(b) Where the depth of ponding exceeds 600 mm, consideration has been given to whether there are steep drops, and/or a need for steps or 'walk-in' 'walk-out' batters, etc. when deciding if fencing and/or warning signs are required (Refer Sections 4.2.7 & 6.2)				
21(c) The landscaping treatment within the storage area is such that it does not limit storage volumes or provide a significant source of debris loading			u dan Franke, in mi	
21(d) The minimum surface slope is consistent with Section 4.2.7		n Testans (n. )		1
21(e) Subsoil drainage is provided in areas subject to frequent ponding and around the outlet (refer Section 4.2.7)				
21(f) If the design includes a retaining wall, has it been structurally checked?				
21(g) Does the system have the correct storage?		, ROACE DEC. NO.	The last of the last	en de la composition de la composition Notas de la composition de la compositio
If YES, see stage-storage calculations in Attachment G				
22. If a driveway/car-park storage is specified, answer Q22(a) to Q22(c), otherwise move to Q23				
22(a) The maximum depth is less than or equal to 200mm (refer Section 4.2.7)		7.00 Million .	V operation	
22(b) The minimum transverse slope is 0.7% (refer Section 4.2.7)	100 C - 10 - 10			
22(c) The system has the correct storage				
If YES, see stage-storage calculations in Attachment G		nt willings		anna dha
23. If a structural/underground storage is specified, answer Q 23(a) to Q 23(f), otherwise move to Q24				
23(a) The dimensions of openings are consistent with Section 4.2.8	<b>V</b> .		Contraction of the local division of the loc	
23(b) The storage floor has a minimum slope of 0.7% (refer Section 4.2.8)		Parks and the		24 Delic JU
23(c) There are sufficient access points for flushing purposes (refer Section 4.2.8)			1.01000-0-	and the second second
23(d) There are sufficient grated openings for ventilation purposes (refer Section 4.2.8)				0.07-18-
23(e) All access points have light weight covers				. Tere Mari
23(f) The system has the correct storage		enalished Berrilla-ad		on Menselation
If YES, see stage-storage calculations in Attachment G				and the second
<ol> <li>The distribution of storage minimises inconvenience (refer Section 5.1.4)</li> </ol>		warmed parts		
25. The Drainage Design Summary sheet has been completed (refer Appendix B1)			and the last	
If YES, see completed sheet in Attachment H			74	
26. The Drainage Design Summary sheet details are consistent with the design plans	$\checkmark$		1	

Upper Parramatta River Catchment Trust

sultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, mn ion from ACOR consultants (CC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants (LC) Pty Ltd. ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants (LC) Pty Ltd. ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (LC) Pty Ltd. ACOR CONSULTANT (LC) Pty Ltd. ACOR CONSULTANT (LC) Pty Ltd. ACOR CONSULTANT (LC) HT of this design and plan is the property of ACOR Cons ed or copied wholly or in part without written permission

						oliont
D	UPDATED TO SUIT COUNCILS COMMENTS	08.03.23	RH	BK	North	BARRY RUSH &
С	C UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN & COUNCILS COMMENTS 0		RH	BK		
В	UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN			BK		& ASSOCIATES
Α	A ISSUED FOR DEVELOPMENT APPROVAL			BK		PTY LTD
Issue	Description	Date	Drawn	Approved		
1	1cm at full size 10cm					



hitect


ACOR Consultants (CC) Pty Ltd roject Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia T +61 2 4324 3499 DEVELOPMENT (No. 26) ROSE CRESCENT (No. 69-73) BOURKE STREE NORTH PARRAMATTA <del>2</del>@@


GERS INFRASTRU





SIDENTIAL	Drawing Title OSD CHECKLIST SHEET 2 OF 2								
	Drawn	Date	Scale A1	Q.A. Check	Date				
Τ&	RH	NOV 21	BAK 0	7.02.22					
EET	Designed	Project No.		Dwg. No.	Issue				
	BK	CC210	393	C6	D				





#### FROM HAZARD AREAS, INCLUDING LANDS CLOSER THAN 5 METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS ESPECIALLY WATERWAYS AND PAVED AREAS.

REMOVE TRAPPED SEDIMENT WHENEVER THE DESIGN CAPACITY OF THAT STRUCTURE HAS BEEN EXCEEDED

ENSURE THAT DRAINS OPERATE PROPERLY AND

REMOVE SPILLED SAND OR OTHER MATERIALS

- ENSURE REHABILITATED LANDS HAVE D) EFFECTIVELY REDUCED THE EROSION HAZARD AND TO INITIATE UPGRADING OR REPAIR AS NECESSARY
- CONSTRUCT ADDITIONAL EROSION AND/OR E) SEDIMENT CONTROL WORKS AS MIGHT BECOME NECESSARY TO ENSURE THE DESIRED PROTECTION IS GIVEN TO DOWNSLOPE LANDS AND WATERWAYS, MAKE ONGOING CHANGES TO THE PLAN WHERE IT PROVES INADEQUATE IN PRACTICE OR IS SUBJECTED TO CHANGES IN CONDITIONS ON THE WORK-SITE OR ELSEWHERE IN THE CATCHMENT
- F) MAINTAIN EROSION AND SEDIMENT CONTROL STRUCTURES IN A FULLY FUNCTIONING CONDITION UNTIL ALL FARTHWORK ACTIVITIES ARE
- COMPLETED AND THE SITE IS REHABILITATED THE SITE SUPERINTENDENT WILL KEEP A LOGBOOK MAKING ENTRIES AT LEAST WEEKLY, IMMEDIATELY BEFORE FORECAST RAIN AND AFTER RAINFALL. ENTRIES WILL INCLUDE:
- THE VOLUME AND INTENSITY OF ANY RAINFALL A) EVENTS.
- THE CONDITION OF ANY SOIL AND WATER B) MANAGEMENT WORKS
- THE CONDITION OF VEGETATION AND ANY NEED TO C) IRRIGATE
- THE NEED FOR DUST PREVENTION STRATEGIES. D) ANY REMEDIAL WORKS TO BE UNDERTAKEN F)
- THE LOGBOOK WILL BE KEPT ON-SITE AND MADE

AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. IT WILL BE GIVEN TO THE PROJECT MANAGER AT THE CONCLUSION OF THE WORKS.

### SEDIMENT CONTROL INSTRUCTIONS

- SEDIMENT FENCES WILL BE INSTALLED AS SHOWN ON THE WASTE CONTROL INSTRUCTIONS 9 PLAN AND ELSEWHERE AT THE DISCRETION OF THE SITE SUPERINTENDENT TO CONTAIN SOIL AS NEAR AS POSSIBLE TO THEIR SOURCE
- SEDIMENT FENCES WILL NOT HAVE CATCHMENT AREAS 10. EXCEEDING 900 SQUARE METRES AND HAVE A STORAGE DEPTH OF AT LEAST 0.6 METRES SEDIMENT REMOVED FROM ANY TRAPPING DEVICES WILL
- BE RELOCATED WHERE FURTHER POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS CANNOT OCCUR. 12
- STOCKPILES ARE NOT TO BE LOCATED WITHIN 5 METRES OF HAZARD AREAS INCLUDING AREAS OF HIGH VELOCITY FLOWS SUCH AS WATERWAYS, PAVED AREAS AND DRIVEWAYS WATER WILL BE PREVENTED FROM DIRECTLY ENTERING
- 13 THE PERMANENT DRAINAGE SYSTEM UNLESS THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR WATER HAS BEEN TREATED BY AN APPROVED DEVICE TEMPORARY SEDIMENT TRAPS WILL REMAIN IN PLACE 14
- UNTIL AFTER THE LANDS THEY ARE PROTECTING ARE COMPLETELY REHABILITATED. ACCESS TO SITES SHOULD BE STABILISED TO REDUCE 15
- THE LIKELIHOOD OF VEHICLES TRACKING SOIL MATERIALS ONTO PUBLIC ROADS AND ENSURE ALL-WEATHER ENTRY/EXIT

### SOIL EROSION CONTROL INSTRUCTIONS

- 16. EARTH BATTERS WILL BE CONSTRUCTED WITH AS LOW A GRADIENT AS PRACTICABLE BUT NO STEEPER, UNLESS OTHERWISE NOTED, THAN:
  - 2(H):1(V) WHERE SLOPE LENGTH LESS THAN 12 METRES
  - 2.5(H):1(V) WHERE SLOPE LENGTH BETWEEN 12 AND 16 METRES.
  - 3(H):1(V) WHERE SLOPE LENGTH BETWEEN 16 AND 20 METRES.
  - 4(H):1(V) WHERE SLOPE LENGTH GREATER THAN 20 METRES
- ALL WATERWAYS, DRAINS, SPILLWAYS AND THEIR 17 OUTLETS WILL BE CONSTRUCTED TO BE STABLE IN AT LEAST THE 1:20 YEAR ARI, TIME OF CONCENTRATION STORM EVENT.
- 18. WATERWAYS AND OTHER AREAS SUBJECT TO CONCENTRATED FLOWS AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUNDCOVER C-FACTOR OF 0.05 (70% GROUND COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION. FLOW VELOCITIES ARE TO BE LIMITED TO THOSE SHOWN IN TABLE 5-1 OF "MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION", DEPT OF HOUSING 1998 (BLUE BOOK). FOOT AND VEHICULAR TRAFFIC WILL BE PROHIBITED IN THESE AREAS.
- STOCKPILES AFTER CONSTRUCTION ARE TO HAVE A 19 MAXIMUM GROUND-COVER C-FACTOR OF 0.1 (60% GROUND-COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION.
- 20. ALL LANDS, INCLUDING WATERWAYS AND STOCKPILES, DURING CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.15 (50% GROUND COVER) WITHIN 20 WORKING DAYS FROM INACTIVITY EVEN THOUGH WORKS MAY CONTINUE LATER.
- 21 FOR AREAS OF SHEET FLOW USE THE FOLLOWING GROUND COVER PLANT SPECIES FOR TEMPORARY COVER: JAPANESE MILLET 20 KG/HA AND OATS 20 KG/HA
- 22. PERMANENT REHABILITATION OF LANDS AFTER CONSTRUCTION WILL ACHIEVE A GROUND-COVER C-FACTOR OF LESS THAN 0.1 AND LESS THAN 0.05 WITHIN 60 DAYS NEWLY PLANTED LANDS WILL BE WATERED. REGULARI Y UNTIL AN EFFECTIVE COVER IS ESTABLISHED AND PLANTS ARE GROWING VIGOROUSLY, FOLLOW-UP SEED AND FERTILISER WILL BE APPLIED AS NECESSARY REVEGETATION SHOULD BE AIMED AT RE-ESTABLISHING 23
- NATURAL SPECIES, NATURAL SURFACE SOILS SHOULD BE REPLACED AND NON-PERSISTANT ANNUAL COVER CROPS SHOULD BE USED

- ACCEPTABLE BINS WILL BE PROVIDED FOR ANY 24 CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHING, LIGHTWEIGHT WASTE MATERIALS AND LITTER. CLEARANCE SERVICES WILL BE PROVIDED AT LEAST WEEKLY, DISPOSAL OF WASTE WILL BE IN A MANNER APPROVED BY THE SITE SUPERINTENDENT.
- 25. ALL POSSIBLE POLLUTANT MATERIALS ARE TO BE STORED WELL CLEAR OF ANY POORLY DRAINED AREAS, FLOOD PRONE AREAS, STREAMBANKS, CHANNELS AND STORMWATER DRAINAGE AREAS. STORE SUCH MATERIALS IN A DESIGNATED AREA UNDER COVER WHERE POSSIBLE AND WITHIN CONTAINMENT BUNDS.
- ALL SITE STAFF AND SUB-CONTACTORS ARE TO BE 26 INFORMED OF THEIR OBLIGATION TO USE WASTE CONTROL FACILITIES PROVIDED
- 27. ANY DE-WATERING ACTIVITIES ARE TO BE CLOSELY MONITORED TO ENSURE THAT WATER IS NOT POLLUTED BY SEDIMENT, TOXIC MATERIALS OR PETROLEUM PRODUCTS
- 28. PROVIDE DESIGNATED VEHICULAR WASHDOWN AND MAINTENANCE AREAS WHICH ARE TO HAVE CONTAINMENT BUNDS

COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modifier UPDATED TO SUIT COUNCILS COMMENTS 08.03.23 RH BK **BARRY RUSH &** UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN & COUNCILS COMMENTS 08.12.22 RH BK & ASSOCIATES UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN 27.04.22 RH BK OP ISSUED FOR DEVELOPMENT APPROVAL 07.02.22 RH BK PTY LTD Date Drawn Appro ONSULTANTS ENGINEERS MANAGERS INFRASTRUCTURE PLAN

SITE MAINTENANCE INSTRUCTIONS

STORM EVENT TO:

A)

B)

C)

EROSION AND SEDIMENT CONTROL NOTES

THE SITE SUPERINTENDENT WILL INSPECT THE SITE AT

LEAST WEEKLY AND AT THE CONCLUSION OF EVERY

TO EFFECT ANY NECESSARY REPAIRS.

- THIS SOIL AND WATER MANAGEMENT PLAN IS TO BE READ 7. IN CONJUNCTION WITH OTHER ENGINEERING PLANS RELATING TO THIS DEVELOPMENT
- CONTRACTORS WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE GUIDELINES OF "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION", DEPT OF HOUSING, 1998 (BLUE BOOK)
- ALL SUBCONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN REDUCING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE AREAS.

#### LAND DISTURBANCE INSTRUCTIONS

GENERAL INSTRUCTIONS

- DISTURBANCE TO BE NO FURTHER THAN 5 (PREFERABLY 2) METRES FROM THE EDGE OF ANY ESSENTIAL ENGINEERING ACTIVITY AS SHOWN ON APPROVED PLANS. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE ZONES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- ACCESS AREAS ARE TO BE LIMITED TO A MAXIMUM WIDTH OF 10 METRES THE SITE MANAGER WILL DETERMINE AND MARK THE LOCATION OF THESE ZONES ON-SITE. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE BOUNDARIES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS
- ENTRY TO LANDS NOT REQUIRED FOR CONSTRUCTION OR 6 ACCESS IS PROHIBITED EXCEPT FOR ESSENTIAL THINNING OF PLANT GROWTH
- WORKS ARE TO PROCEED IN THE FOLLOWING SEQUENCE: INSTALL ALL BARRIER AND SEDIMENT FENCING A)
- WHERE SHOWN ON THE PLAN CONSTRUCT THE STABILISED SITE ACCESS B)
- CONSTRUCT DIVERSION DRAINS AS REQUIRED C)
- INSTALL MESH AND GRAVEL INLETS FOR ANY D) ADJACENT KERB INLETS
- INSTALL GEOTEXTILE INLET FILTERS AROUND ANY E) ON-SITE DROP INLET PITS.
- CLEAR SITE AND STRIP AND STOCKPILE TOPSOIL IN F) LOCATIONS SHOWN ON THE PLAN
- UNDERTAKE ALL ESSENTIAL CONSTRUCTION G) WORKS ENSURING THAT ROOF AND/OR PAVED AREA STORMWATER SYSTEMS ARE CONNECTED TO PERMANENT DRAINAGE AS SOON AS PRACTICABLE
- GRADE LOT AREAS TO FINAL GRADES AND APPLY H) PERMANENT STABILISATION (LANDSCAPING) WITHIN 20 DAYS OF COMPLETION OF CONSTRUCTION WORKS
- REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER THE PERMANENT LANDSCAPING HAS BEEN COMPLETED.
- ENSURE THAT SLOPE LENGTHS DO NOT EXCEED 80 METRES WHERE PRACTICABLE. SLOPE LENGTHS ARE DETERMINED BY SILTATION FENCING AND CATCH DRAIN SPACING
- ON COMPLETION OF MAJOR WORKS LEAVE DISTURBED LANDS WITH A SCARIFIED SURFACE TO ENCOURAGE WATER INFILTRATION AND ASSIST WITH KEYING TOPSOIL LATER

### **1 INTRODUCTION**

A CATCHMENT BASED WATER QUALITY MODEL WAS DEVELOPED TO ASSESS THE STORMWATER RUNOFF QUALITY IN ACCORDANCE WITH THE WATER SENSITIVE URBAN DESIGN (WSUD) REQUIREMENTS OF PARRAMATTA DEVELOPMENT CONTROL PLAN PART 3.3.6 AND APPENDIX 7. IN THIS REGARD WE REFER TO THE PRESCRIBED TARGETS TABLED FOLLOWING: TABLE 1 - STORMWATER POLLUTANT REDUCTION TARGETS

STORMWATER POLLUTANT	REDUCTION TARGETS
GROSS POLLUTANT	90%
TOTAL SUSPENDED SOLIDS (TSS)	85%
TOTAL PHOSPHORUS (TP)	60%
TOTAL NITROGEN (TN)	45%

### 2 STUDY METHODOLOGY

THE OBJECTIVES OF THIS REPORT ARE TO:

- ASSESS THE RUNOFF QUALITY FOR THE UNTREATED POST DEVELOPED SCENARIO AND IDENTIFY STORMWATER QUALITY CONTROLS LIKELY TO IMPACT ON RUNOFF QUALITY.
- ASSESS THE STORMWATER QUALITY FOR THE POST • DEVELOPED SCENARIO INCLUDING THE MEASURES PROPOSED TO MEET THE POLLUTANT REMOVAL TARGETS .

THE REPORT IS BASED ON THE APPLICATION OF MUSIC SOFTWARE (MODEL FOR URBAN STORMWATER IMPROVEMENT CONCEPTUALISATION). IN THIS REGARD THE MODEL IS DEFINED

AS FOLLOWS:

- A STORMWATER QUALITY MODEL TO CONVERT RAINFALL AND EVAPOTRANSPIRATION INTO RUNOFF.
- ESTIMATION OF STORMWATER FLOW AND POLLUTION GENERATION BY SIMULATING THE PERFORMANCE OF STORMWATER TREATMENT DEVICES INDIVIDUALLY AND AS PART OF A TREATMENT TRAIN.

THE MODEL DEFINES WATER QUALITY PROFILES FOR BOTH TREATED AND UNTREATED POST DEVELOPED SCENARIOS. THE TREATED POST DEVELOPED MODEL INCLUDES PARAMETERS WHICH REPRESENT THE WATER QUALITY MEASURES.

COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modifie

	Client					
D	UPDATED TO SUIT COUNCILS COMMENTS	08.03.23	RH	BK	North	BARRY RUSH 8
С	UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN & COUNCILS COMMENTS	08.12.22	RH	BK		
В	NIL ISSUE	-	-	-		& ASSOCIATES
A	NIL ISSUE	-	-	-		PTY LTD
Issue	Description	Date	Drawn	Approved		
1 0	10cm 10cm	_				

STORMWATER QUALITY REPORT

### **3 STORMWATER QUALITY MODELLING**

### 3.1 GENERAL

THE FOLLOWING PARAMETERS WERE ASSESSED FOR THE HYDROLOGICAL MODELLING ASSOCIATED WITH THE CATCHMENT.

- RAINFALL/RUNOFF AND EVAPOTRANSPIRATION.
- SUB CATCHMENT DIVERSIONS. •
- LAND USE (PERVIOUS AND IMPERVIOUS)

#### 3.2 RAINFALL/RUNOFF AND EVAPOTRANSPIRATION

THE MUSIC MODEL WAS FORCED WITH 6 MINUTE RAINFALL DATA FROM THE PARRAMATTA NORTH (MASONS DRIVE) GAUGE (ID 066124) FOR THE PERIOD 25 DECEMBER 1984 TO 30 DECEMBER 2007.

DAILY AVERAGE PET VALUES WERE NOT AVAILABLE FOR STATION ID 066124 AND WERE SOURCED FROM THE BUREAU OF METEOROLOGY FOR THE NEIGHBOURING PROSPECT RESERVOIR GAUGE (ID 067019). THE DETAILS ARE SUMMARISED IN TABLE 3.1 AND 3.2

TABLE 3.1 - DETAILS OF DAILY RAINFALL DATA						
STATION	NAME	PERIOD	TIMESTEP			
066124	PARRAMATTA NORTH (MASONS DRIVE)	25/12/1984-30/12/2007	6 min			

TABLE 3.2 - SUMMARY OF POTENTIAL EVAPOTRANSPIRATION (PET)								
JAN	FEB	MAR	APR	MAY	JUN			
170.5	131.6	120.9	87	62	48			
JUL	AUG	SEP	ОСТ	NOV	DEC			
51	77.5	108	136.4	155	173.6			

#### **3.3 CATCHMENT DEFINITION**

**IDENTIFIED IN TABLE 3.3.** 

TABLE 3.3 - POST

SUB CATCHMENT ID

ROOF TO RWT DRIVEWAY AND PARKING TO OSD DRIVEWAY BYPASSING OSD AREA TO OSD AREA BYPASSING OSD

WE NOTE THAT THE AREA WITHIN THE DRAINAGE EASEMENT ALONG THE SITE'S EASTERN BOUNDARY HAS BEEN EXCLUDED FROM THE WATER QUALITY ASSESSMENT.

### **4 MUSIC MODEL**

MEAN CONCENTRATIONS (EMCs).

### 4.1 WATER QUALITY PARAMETERS

	TABLE 4.1 - ADOPTED MUSIC RAINFALL/RUNOFF PARAMETERS						
	PARAMETER	VALUE					
	IMPERVIOUS AREA PROPERT	TIES					
	RAINFALL THRESHOLD (mm/DAY)	1.5 (0.3 ROOFS)					
	PERVIOUS AREA PROPERTI	IES					
	SOIL STORAGE CAPACITY (mm)	94					
	SOIL INITIAL STORAGE (% OF CAPACITY)	25					
	FIELD CAPACITY (mm)	70					
	INFILTRATION CAPACITY COEFFICIENT - a	135					
	INFILTRATION CAPACITY EXPONENT - b	4					
	GROUNDWATER PROPERTI	IES					
	INITIAL DEPTH (mm)	10					
	DAILY RECHARGE RATE (%)	10					
	DAILY BASEFLOW RATE (%)	10					
	DAILY DEEP SEEPAGE RATE (%)	0					
.td	Project	Drawing Title					



ACOR Consultants (CC) Ptv L Platinum Building, Suite 2.01, 4 Ilya Avenu

- 📀

 $\bigcirc$ 

PROPOSED RE T +61 2 4324 3499 DEVELOPMEN (No. 26) ROSE CRESCEN (No. 69-73) BOURKE STRI NORTH PARRAMATTA

9 August 2023



THE POST DEVELOPED CATCHMENT CHARACTERISTICS ARE

DEVELOPMENT SUB CATCHMENT DETAILS							
SUB CATCHMENT AREA (ha)	% IMPERVIOUS AREA	% PERVIOUS AREA					
0.074	100	0					
0.035	100	0					
0.005	100	0					
0.059	70	30					
0.035	70	30					

THE MUSIC MODEL IS BASED ON A 6 min RAINFALL-RUNOFF MODEL IN CONJUNCTION WITH REPRESENTATIVE BASEFLOW AND STORMFLOW EVENT

THE ADOPTED VALUES OF VARIOUS MUSIC RAINFALL AND RUNOFF PARAMETERS IN ACCORDANCE WITH NSW MUSIC MODELLING GUIDELINES 2015 FOR MEDIUM CLAY ARE SUMMARISED IN TABLE 4.1.

SIDENTIAL	Drawing Title STORMWATER QUALITY REPORT SHEET 1 OF 2							
1	Drawn	Date	Scale A1	Q.A. Check	Date			
& TI	RH	NOV 21	BAK 07	7.02.22				
REET	Designed	Project No.		Dwg. No.	Issue			
	ВК	CC210393		C9	D			

#### 4.1 WATER QUALITY PARAMETERS CONT.

STORMWATER QUALITY IS CHARACTERISED USING EVENT MEAN CONCENTRATION (EMCs) UNDER STORM AND BASE FLOW CONDITIONS. THE VALUE OF WATER QUALITY PARAMETERS ADOPTED IN THIS STUDY IS SUMMARISED IN TABLE 4.2

TABLE 4.2 - ADOPTED MUSIC WATER QUALITY PARAMETERS								
LAND-USE CATEGORY		Log₀TSS	g₀ TSS (mg/L) Log₀ TP (r		(mg/L) Log <sub>10</sub> TN		l (mg/L)	
		STORM FLOW	BASE FLOW	STORM FLOW	BASE FLOW	STORM FLOW	BASE FLOW	
	MEAN	2.15	1.20	-0.60	-0.85	0.30	0.11	
RESIDENTIAL	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12	
GENERAL	MEAN	2.20	1.10	-0.45	-0.82	0.42	0.32	
URBAN	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12	
	MEAN	1.30	1.10	-0.89	-0.82	0.30	0.32	
ROOFS	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12	

#### 4.2 STORMWATER TREATMENT MEASURES

#### THE PROPOSED STORMWATER TREATMENT MEASURES INCLUDED

IN THE POST DEVELOPED MODEL ARE AS FOLLOWS:

- 30,000 LITRE RAINWATER TANK (REUSE FOR IRRIGATION)
- 6 x SPELFILTERS (FULL HEIGHT)
- 3 x STORMSACKS

THE SCHEMATIC LAYOUT FOR THE POST DEVELOPED MUSIC

MODEL IS DEPICTED IN FOLLOWING FIGURE 1




FIGURE 1 - MUSIC MODEL SCHEMATIC

#### **5 RESULTS & CONCLUSION**

BASED ON THE FOREGOING AND THE RESULTS DEPICTED IN TABLE 5.1, THE PROPOSED STORMWATER QUALITY TREATMENT MEASURES MEET THE REQUIRED TARGETS OF THE CITY OF PARRAMATTA. REFER TO CC210393\_20221025.SQZ AS PREPARED BY ACOR CONSULTANTS (CC) PTY LTD FOR FURTHER INFORMATION.

TABLE 5.1 - TREATMENT TRAIN EFFECTIVENESS

	Sources	Residual Load	% Reduction
łow (ML/yr)	1.47	1.08	26.6
otal Suspended Solids (kg/yr)	227	32.3	85.8
otal Phosphorus (kg/yr)	0.458	0.148	67.8
otal Nitrogen (kg/yr)	3.42	1.31	61.7
iros <mark>s Pollutants (kg/yr)</mark>	39.7	0.000266	100

NGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified duced or copied wholly or in part without written permission from ACOR Consultants (CC) Pty Ltd. ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants (CC) Pty Ltd.


						Client
D	UPDATED TO SUIT COUNCILS COMMENTS	08.03.23	RH	BK	North	BARRY RUSH &
С	UPDATED TO SUIT THE LATEST ARCHITECTURAL PLAN & COUNCILS COMMENTS	08.12.22	RH	BK		
В	NIL ISSUE	-	-	-		& ASSOCIATES
A	NIL ISSUE	-	-	-		PTY LTD
Issue	Description	Date	Drawn	Approved		
1 0	1cm at full size 10cm	_				


OR CONSULTANTS ENGINEERS MANAGERS INFRASTRUCTURE PLA


hitect

9 August 2023


SIDENTIAL	STORMWATER QUALITY REPOR SHEET 2 OF 2							
	Drawn	Date	Scale A1	Q.A. Check	Date			
& TI	RH	NOV 21	AS NOTED	BAK 07	7.02.22			
REET	Designed	Project No.		Dwg. No.	Issue			
	вк	CC210	393	C10	D			







LEGEND:		No.	DATE	NOTATION/AMEN	IDMENT		
AWN - AWNING CL - CENTERLINE FL - FLOOR LEVEL RR - ROOF RIDGE DS - DOOR STEP LEVEL STP - STEP TF - TOP OF FENCE TK - TOP OF KERB	TW - TOP OF WINDOW BW - BOTTOM OF WINDOW TG - TOP OF GUTTER TOW - TOP OF WALL EB - EDGE OF BITUMEN EC - EDGE OF CONCRETE EG - EDGE OF GARDEN Ø.4/S10/H16 - DIAMETER/SPREAD/HEIGHT	1	05/05/2021	INITIAL ISSUE	CONTOUR INT DATUM: ORIGIN OF DATUM:	ERVAL SSI	
			FILE	FILE SIZE (MB)	CHECKED BY		
					GS		



## Long Section 1

			GRASS	CONCRETE DRIVEWAY			BITUMEN DRIVEWA	.Υ 					GRASS					
Datum : 54.00 Grade Lin	6	9.375%	-0.287%	0.631%	3.495%	1.276% 1.276%	1.717% 19.674%	-0	.582%	2.00	)9%		0.530%	1.423%		1.428%	0.208%	
Elevation	54.36	54.35	54.51	54.49	54.51	54.68	54.76 54.70	54.75 54.82	54,79			55.05	55.10		55.27		55.42	55.43
Chainage	0.000	2.701	4.333	10.788	14.781	19.601	26.006 26.559	29.475 29.868	35.451			48.179	58.681		70.149		80.748	87.815
Long Sectio	Vertic	al So	Scale 1 : 200	0														
Datum : 51.00 🧮														CONCRE	TE PATH			


Grade Line	0.232%	0.372%	0.954%	1.491%
FIEVOLION	51.36	51.39	51.45	51.54
Chainage	0.000	14.044	28.088	38.011
	Horizontal Scale 1 : 200 Vertical Scale 1 : 200			

No	DATE	NOTATION/AMENDMENT	No.	DATE	NOTATION/AME	ENDMENT	CONTOUR INTERVAL: DATUM: A.H.D. ORIGIN OF DATUM:		DATE OF SURVEY: 23/04/2021 SURVEY CONSULTANT:	NSV
							SSM76404 100 YEAR FLOOD RL:	LAND TITLE INFORMATION	SOLUTIONS ARTARMON   CAMDEN   MANLY VALE	Division of the
				FILE	FILE SIZE (MB)	CHECKED BY	RECOMMENDED MINIMUM FLOOR RL:	PLAN NOS : D.P. 215342		
							SOURCE OF FLOOD INFO:	OTHER:		1
								AREA:		1

Long	Section	2

<u>Section 2</u>					US SHELTER ): 2151130
Datum : 55.00	GRASS	CONCRETE	РАТН	Ц	
Grade Line	6.836%	-0.755%	6.295% -2.736% <		
Elevation	55.81	56.58	56.55	57.19 57.18	
Chainage	97.419	108.683	112.954	123.177 123.671	
Horizontal Scale 1 : Vertical Scale 1 : 20		I	1	<u>   </u>	

	CONCRETE PATH								
1.459%	1.590%	1.239%	1.502%	5.689% 7	7.591%	6.139%	6.738%	7.297%	
51.75	51.90	52.12	52.29	52.50 52.74		53.09	53.87	54.64	55.43
52.107	62.530	76.293	80.89 80.89 80 80	103.644		112.578	125.173	136.632	147.501



Land & Housing Corporation		A	
	STREET ADDRESS	TYPE	
the Department of Family & Community Services DRAWING TITLE LONGITUDINAL	26 ROSE CRESCENT		
	JOB	SHT.	3
SECTIONS	210719	OF	4

## <u>Long Section 4</u>

## <u>Crossing 1</u>

# BUS SHELTER ID: 2151131

			CONCRETE PATH		
Datum : 51.00					-
Grade Line	-0.224%	-0.126%	0.292%	-0.965%	
Elevation	51.50	51.48	51.47	51.51	51.40
Chainage	0.000	6.896	11.126	23.084	34.979
Horizontal Scale 1	: 200				

Vertical Scale 1 : 200

<u>Long Section 5</u>

								CONCRETE PATH				
Datum : 47.00 Grade Line	-4.378%	<b>7</b> – 2.591%	-2.4825	% -2.145	5% –2.733%	-1.794%	-1.827%	-1.786%	-1.332	-2.02	26%	-1.490%
Elevation	51.13	50.95	50.61	50.29	50.02	49.78	49.54	49.29	49.06	48.79	48.41	48.18
Chainage	52.421	56.357	69.457	82.352	94.960	104.037	117.444	130.833	143.790	163.691	182.562	198.390
Horizontal Scale Vertical Scale 1 :											C'	ONTINUED BELOW


## <u>Long Section 5</u>

CONCRETE PATH							
 -1.242%	-1.778%	-1.584%	-2.977%				
 48.18	48.03	47.84	47.66	47.40			
198.390	209.807	220.961	232.014	240.937			


CONTINUED

No. DATE	NOTATION/AMENDMENT	No.	DATE	NOTATION/AME	NOTATION/AMENDMENT		
						DATUM: A.H.D. ORIGIN OF DATUM: SSM76404 100 YEAR FLOOD RL:	
			FILE	FILE SIZE (MB)	CHECKED BY	RECOMMENDED MINIMUM FLOOR RL: SOURCE OF FLOOD INFO:	

## DETERMINED by the NSW Land and Housing Corporation on:



<u>Long Section 6</u>



 SEE INDIVIDUAL SCALES	DATE OF SURVEY: 23/04/2021 SURVEY CONSULTANT:	Land & Housing	NORTH PARRAMATTA		
LAND TITLE INFORMATION	TSS TOTAL SURVEYING SOLUTIONS	Division of the Department of Family & Community Services	STREET ADDRESS	TYPE	
LOTS: 2,3,4	ARTARMON   CAMDEN   MANLY VALE	DRAWING TITLE	26 ROSE CRESCENT		
PLAN NOS : D.P. 215342		LONGITUDINAL			
OTHER:		SECTIONS	JOB	SHT. 4	
AREA:			210719	OF 4	

crossing 3	PRAM CROSSING	IRWN	NIOL NMOYO	PRAM CROSSING	
Datum : 46.00					
Grade Line	-8.948%	2.081%	-4.587%	6.208%	
Elevation	47.40	47.06	47.22	46.89	47.03
Chainage	240.937	244.662	252.047	259.056	261.251

	CONCRE	TE PATH					BUS SI ID: 21	HELTER 51133
	-4.747%	-2.951%	-2.493%	%	-4.666%	-6.016%		
	46.53	46.36	46.23		46.00	45.46	45.40	
	284.086	287.633	292.076		301.232		313.778	
	Land & Housing Corporation				NORTH PAR	RAM	1ATT	A
the Department of Family & Community Services				STREET A	DDRESS			TYPE