
# PROPOSED DEVELOPMENT (No.2 - 8) GLENN AVENUE, NORTHMEAD

## STORMWATER MANAGEMENT PLANS



### DIAL BEFORE YOU DIG



IMPORTANT: THE CONTRACTOR IS TO MAINTAIN A CURRENT SET OF "DIAL BEFORE YOU DIG" DRAWINGS ON SITE AT ALL TIMES.

### **GENERAL NOTES**

- THESE PLANS SHALL BE READ IN CONJUNCTION WITH OTHER RELEVANT CONSULTANTS' PLANS, SPECIFICATIONS, CONDITIONS OF DEVELOPMENT CONSENT AND CONSTRUCTION CERTIFICATE REQUIREMENTS. WHERE DISCREPANCIES ARE FOUND ACOR CONSULTANTS (CC) MUST BE CONTACTED IMMEDIATELY FOR VERIFICATION
- WHERE THESE PLANS ARE NOTED FOR DEVELOPMENT APPLICATION PURPOSES ONLY, THEY SHALL NOT BE USED FOR OBTAINING A CONSTRUCTION CERTIFICATE NOR USED FOR CONSTRUCTION PURPOSES
- SUBSOIL DRAINAGE SHALL BE DESIGNED AND DETAILED BY THE STRUCTURAL ENGINEER. SUBSOIL DRAINAGE SHALL NOT BE CONNECTED INTO THE STORMWATER SYSTEM IDENTIFIED ON THESE PLANS UNLESS APPROVED BY ACOR CONSULTANTS (CC)

### STORMWATER CONSTRUCTION NOTES

- ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH AS/NZS 3500 (CURRENT EDITION) AND THE REQUIREMENTS OF THE LOCAL COUNCIL'S POLICIES AND CODES
- THE MINIMUM SIZES OF THE STORMWATER DRAINS SHALL NOT BE LESS THAN DN90 FOR CLASS 1 BUILDINGS AND DN100 FOR OTHER CLASSES OF BUILDING OR AS REQUIRED BY THE REGULATORY AUTHORITY
- 3. THE MINIMUM GRADIENT OF STORMWATER DRAINS SHALL BE 1%, UNLESS NOTED OTHERWISE
- COUNCIL'S TREE PRESERVATION ORDER IS TO BE STRICTLY ADHERED TO. NO TREES SHALL BE REMOVED UNTIL PERMIT IS OBTAINED
- 5. PUBLIC UTILITY SERVICES ARE TO BE ADJUSTED AS NECESSARY AT THE CLIENT'S EXPENSE
- . ALL PITS TO BE BENCHED AND STREAMLINED. PROVIDE STEP IRONS FOR ALL PITS OVER 1.2m DEEP
- 7. MAKE SMOOTH JUNCTION WITH ALL EXISTING WORK
- VEHICULAR ACCESS AND ALL SERVICES TO BE MAINTAINED AT ALL TIMES TO ADJOINING PROPERTIES AFFECTED BY CONSTRUCTION
- 9. SERVICES SHOWN ON THESE PLANS HAVE BEEN LOCATED FROM INFORMATION SUPPLIED BY THE RELEVANT AUTHORITIES AND FIELD INVESTIGATIONS AND ARE NOT GUARANTEED COMPLETE NOR CORRECT. IT IS THE CLIENT & CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL PRIOR TO CONSTRUCTION
- ANY VARIATION TO THE WORKS AS SHOWN ON THE APPROVED DRAWINGS ARE TO BE CONFIRMED BY ACOR CONSULTANTS (CC) PRIOR TO THEIR COMMENCEMENT

### RAINWATER RE-USE SYSTEM NOTES

- RAINWATER SUPPLY PLUMBING TO BE CONNECTED TO OUTLETS
   WHERE REQUIRED BY BASIX CERTIFICATE (BY OTHERS)
- TOWN WATER CONNECTION TO RAINWATER TANK TO BE TO THE SATISFACTION OF THE REGULATORY AUTHORITY. THIS MAY REQUIRE PROVISION OF:
  - 2.1. PERMANENT AIR GAR
- 2.2. BACKFLOW PREVENTION DEVICE
- 3. NO DIRECT CONNECTION BETWEEN TOWN WATER SUPPLY AND THE RAIN WATER SUPPLY
- I. AN APPROVED STOP VALVE AND/OR PRESSURE LIMITING VALVE AT THE RAINWATER TANK
- PROVIDE APPROPRIATE FLOAT VALVES AND/OR SOLENOID VALVES TO CONTROL TOWN WATER SUPPLY INLET TO TANK IN ORDER TO ACHIEVE THE TOP-UP INDICATED ON THE TYPICAL DETAIL
- ALL PLUMBING WORKS ARE TO BE CARRIED OUT BY LICENSED PLUMBERS IN ACCORDANCE WITH AS/NZS3500.1 NATIONAL PLUMBING AND DRAINAGE CODE
- 7. PRESSURE PUMP ELECTRICAL CONNECTION TO BE CARRIED OUT BY
- 8. ONLY ROOF RUN-OFF IS TO BE DIRECTED TO THE RAINWATER TANK SURFACE WATER INLETS ARE NOT TO BE CONNECTED
- 9. PIPE MATERIALS FOR RAINWATER SUPPLY PLUMBING ARE TO BE APPROVED MATERIALS TO AS/NZS3500 PART 1 SECTION 2 AND TO BE CLEARLY AND PERMANENTLY IDENTIFIED AS 'RAINWATER'. THIS MAY BE ACHIEVED FOR BELOW GROUND PIPES USING IDENTIFICATION TAPE (MADE IN ACCORDANCE WITH AS2648) OR FOR ABOVE GROUND PIPES BY USING ADHESIVE PIPE MARKERS (MADE IN ACCORDANCE WITH AS1345)
- EVERY RAINWATER SUPPLY OUTLET POINT AND THE RAINWATER TANK ARE TO BE LABELED 'RAINWATER' ON A METALLIC SIGN IN ACCORDANCE WITH AS1319
- 11. ALL INLETS AND OUTLETS TO THE RAINWATER TANK ARE TO HAVE SUITABLE MEASURES PROVIDED TO PREVENT MOSQUITO AND VERMIN ENTRY

### PARRAMATTA COUNCIL REQUIREMENTS

- ON-SITE DETENTION
   REFER TO SHEET C9 FOR THE UPPER PARRAMATTA RIVER
   CATCHMENT TRUST ON-SITE DETENTION DRAINAGE CALCULATIONS
- RAINWATER REUSE
   PROVIDE RAINWATER REUSE TANK AS REQUIRED BY BASIX.
  BASIX REQUIREMENT = 10m<sup>3</sup>.
- SITE DISCHARGE TO PROPOSED KERB INLET PIT IN GLENN AVENUE. REFER TO SHEET C4.
- DESIGN HAS BEEN PREPARED IN ACCORDANCE WITH PARRAMATTA COUNCIL DESIGN & DEVELOPMENT GUIDELINES, UPPER PARRAMATTA RIVER CATCHMENT TRUST, AR&R AND AS/ANZS 3500

SHEET INDEX					
COVER SHEET & NOTES	SHEET C1				
ON SITE DETENTION CATCHMENT PLAN	SHEET C2				
STORMWATER MANAGEMENT PLAN - PART 1	SHEET C3				
STORMWATER MANAGEMENT PLAN - PART 2	SHEET C4				
STORMWATER MANAGEMENT DETAILS SHEET No.1	SHEET C5				
STORMWATER MANAGEMENT DETAILS SHEET No.2	SHEET C6				
EROSION & SEDIMENT CONTROL PLAN	SHEET C7				
EROSION & SEDIMENT CONTROL NOTES & DETAILS	SHEET C8				
OSD CALCULATION SHEET & MAINTENANCE SCHEDULE	SHEET C9				
ON-SITE DETENTION CHECKLIST SHEET 1 OF 2	SHEET C10				
ON-SITE DETENTION CHECKLIST SHEET 2 OF 2	SHEET C11				
PIPE LONG SECTION PIT P1 - PIT P4	SHEET C12				
STORMWATER QUALITY REPORT SHEET 1 OF 2	SHEET C13				
STORMWATER QUALITY REPORT SHEET 2 OF 2	SHEET C14				

DEVELOPMENT APPLICATION ISSUE NOT FOR CONSTRUCTION

DRAWINGS MUST BE PRINTED IN COLOUR

© COPPRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified,

D	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK
С	RE-ISSUED FOR DEVELOPMENT APPROVAL	21.04.22	RH	BK
В	ISSUED FOR DEVELOPMENT APPROVAL	21.10.21	RH	BK
Α	ISSUED FOR REVIEW & COMMENT	02.09.21	RH	BK
Issue	Description	Date	Drawn	Approved

North


BARRY RUSH & ASSOCIATES











COVER	SHEET	& NOTE	S
Drawn	Date	Scale A1	Q.A. Check
RH	MAY 21	AS NOTED	BAK













PROVIDE CONFINED SPACE SIGNAGE AT ENTRY POINTS INTO TANK.

©COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified,

		Client				
	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK	North	BARRY RUSH &
	RE-ISSUED FOR DEVELOPMENT APPROVAL	21.04.22	RH	BK		
	ISSUED FOR DEVELOPMENT APPROVAL	21.10.21	RH	BK		ASSOCIATES
	NIL ISSUE	-	-			PTY LTD
sue	Description	Date	Drawn	Approved		
٥	ISSIJED*FOR*DEVELOPMENT APPROVAL 10cm	21.10.21	RH	BK		



ACOR Consultants (CC) Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia T +61 2 4324 3499

NA NSW 2250, Australia
T +61 2 4324 3499

DEVELOPMENT


LOTS 73, 74, 75 & 76


No. 2 - 8

GLENN AVENUE, NORTHMEAD

	Project
ie ia	PROPOSED RESIDENTIAL DEVELOPMENT
פ	LOTS 73 74 75 & 76

STORMWATER MANAGEMEN DETAILS SHEET No.1						
Drawn RH	OCT 21	Scale A1 AS NOTED	Q.A. Check BAK	2		
Designed BK	Project No.	Dwg. No.				







PROVIDE CONFINED SPACE SIGNAGE AT ENTRY POINTS INTO TANK.

COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants (CC) Pty Ltd, ACOR Consultants is a trademark licensed to ACOR Consultants (CC) Pty Ltd by ACOR Consultants (CC) Pty Ltd. ACOR CONSULTANTS (CC) P

						Client
	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK	North	BARRY RUSH 8
	RE-ISSUED FOR DEVELOPMENT APPROVAL	21.04.22	RH	BK		
	ISSUED FOR DEVELOPMENT APPROVAL	21.10.21	RH	BK		ASSOCIATES
	NIL ISSUE	-	-	-		PTY LTD
е	Description	Date	Drawn	Approved		
0	1cm at full size					1


CNSULTANTS ENGINEERS MANAGERS INFRASTRUCTURE PLA

ACOR Consultants (CC) Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia

GLENN AVENUE, NORTHMEAD

PROPOSED RESIDENTIAL T +61 2 4324 3499 DEVELOPMENT LOTS 73, 74, 75 & 76

	MWATER SHEET		EMENT	
Drawn RH	OCT 21	Scale A1 AS NOTED	Q.A. Check BAK	2
Designed BK	Project No.	Dwg. No.		



### **EROSION AND SEDIMENT CONTROL NOTES**

### GENERAL INSTRUCTIONS

- THIS SOIL AND WATER MANAGEMENT PLAN IS TO BE READ 7. IN CONJUNCTION WITH OTHER ENGINEERING PLANS RELATING TO THIS DEVELOPMENT
- CONTRACTORS WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE GUIDELINES OF "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION", DEPT OF HOUSING, 1998 (BLUE BOOK)
- ALL SUBCONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN REDUCING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE AREAS.

### LAND DISTURBANCE INSTRUCTIONS

- DISTURBANCE TO BE NO FURTHER THAN 5 (PREFERABLY 2) METRES FROM THE EDGE OF ANY ESSENTIAL ENGINEERING ACTIVITY AS SHOWN ON APPROVED PLANS. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE ZONES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- ACCESS AREAS ARE TO BE LIMITED TO A MAXIMUM WIDTH OF 10 METRES THE SITE MANAGER WILL DETERMINE AND MARK THE LOCATION OF THESE ZONES ON-SITE, ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE BOUNDARIES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS
- ENTRY TO LANDS NOT REQUIRED FOR CONSTRUCTION OR ACCESS IS PROHIBITED EXCEPT FOR ESSENTIAL THINNING OF PLANT GROWTH
- WORKS ARE TO PROCEED IN THE FOLLOWING SEQUENCE: INSTALL ALL BARRIER AND SEDIMENT FENCING A) WHERE SHOWN ON THE PLAN
- CONSTRUCT THE STABILISED SITE ACCESS
- CONSTRUCT DIVERSION DRAINS AS REQUIRED INSTALL MESH AND GRAVEL INLETS FOR ANY D)
- ADJACENT KERR INLETS INSTALL GEOTEXTILE INLET FILTERS AROUND ANY
- ON-SITE DROP INLET PITS.
- CLEAR SITE AND STRIP AND STOCKPILE TOPSOIL IN LOCATIONS SHOWN ON THE PLAN
- UNDERTAKE ALL ESSENTIAL CONSTRUCTION WORKS ENSURING THAT ROOF AND/OR PAVED AREA STORMWATER SYSTEMS ARE CONNECTED TO PERMANENT DRAINAGE AS SOON AS PRACTICABLE
- GRADE LOT AREAS TO FINAL GRADES AND APPLY PERMANENT STABILISATION (LANDSCAPING) WITHIN 20 DAYS OF COMPLETION OF CONSTRUCTION WORKS
- REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER THE PERMANENT LANDSCAPING HAS BEEN COMPLETED.
- ENSURE THAT SLOPE LENGTHS DO NOT EXCEED 80 METRES WHERE PRACTICABLE. SLOPE LENGTHS ARE DETERMINED BY SILTATION FENCING AND CATCH DRAIN
- ON COMPLETION OF MAJOR WORKS LEAVE DISTURBED LANDS WITH A SCARIFIED SURFACE TO ENCOURAGE WATER INFILTRATION AND ASSIST WITH KEYING TOPSOIL

### SITE MAINTENANCE INSTRUCTIONS

- THE SITE SUPERINTENDENT WILL INSPECT THE SITE AT LEAST WEEKLY AND AT THE CONCLUSION OF EVERY STORM EVENT TO:
  - ENSURE THAT DRAINS OPERATE PROPERLY AND TO EFFECT ANY NECESSARY REPAIRS.
  - REMOVE SPILLED SAND OR OTHER MATERIALS FROM HAZARD AREAS, INCLUDING LANDS CLOSER THAN 5 METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS ESPECIALLY WATERWAYS AND PAVED AREAS.
  - REMOVE TRAPPED SEDIMENT WHENEVER THE DESIGN CAPACITY OF THAT STRUCTURE HAS BEEN EXCEEDED
  - ENSURE REHABILITATED LANDS HAVE EFFECTIVELY REDUCED THE EROSION HAZARD AND TO INITIATE UPGRADING OR REPAIR AS
  - CONSTRUCT ADDITIONAL EROSION AND/OR SEDIMENT CONTROL WORKS AS MIGHT BECOME NECESSARY TO ENSURE THE DESIRED PROTECTION IS GIVEN TO DOWNSLOPE LANDS AND WATERWAYS, MAKE ONGOING CHANGES TO THE PLAN WHERE IT PROVES INADEQUATE IN PRACTICE OR IS SUBJECTED TO CHANGES IN CONDITIONS ON THE WORK-SITE OR ELSEWHERE IN THE CATCHMENT
  - MAINTAIN EROSION AND SEDIMENT CONTROL STRUCTURES IN A FULLY FUNCTIONING CONDITION UNTIL ALL EARTHWORK ACTIVITIES ARE COMPLETED AND THE SITE IS REHABILITATED
- THE SITE SUPERINTENDENT WILL KEEP A LOGBOOK MAKING ENTRIES AT LEAST WEEKLY, IMMEDIATELY BEFORE FORECAST RAIN AND AFTER RAINFALL. ENTRIES WILL INCLUDE:
- THE VOLUME AND INTENSITY OF ANY RAINFALL A) EVENTS.
- THE CONDITION OF ANY SOIL AND WATER MANAGEMENT WORKS
- THE CONDITION OF VEGETATION AND ANY NEFD TO IRRIGATE
- THE NEED FOR DUST PREVENTION STRATEGIES. ANY REMEDIAL WORKS TO BE UNDERTAKEN.
- THE LOGBOOK WILL BE KEPT ON-SITE AND MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. IT WILL BE GIVEN TO THE PROJECT MANAGER AT THE CONCLUSION OF THE WORKS.


### SEDIMENT CONTROL INSTRUCTIONS

- SEDIMENT FENCES WILL BE INSTALLED AS SHOWN ON THE WASTE CONTROL INSTRUCTIONS PLAN AND ELSEWHERE AT THE DISCRETION OF THE SITE SUPERINTENDENT TO CONTAIN SOIL AS NEAR AS POSSIBLE TO THEIR SOURCE
- SEDIMENT FENCES WILL NOT HAVE CATCHMENT AREAS EXCEEDING 900 SQUARE METRES AND HAVE A STORAGE DEPTH OF AT LEAST 0.6 METRES
- SEDIMENT REMOVED FROM ANY TRAPPING DEVICES WILL BE RELOCATED WHERE FURTHER POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS CANNOT OCCUR 12. STOCKPILES ARE NOT TO BE LOCATED WITHIN 5 METRES
- OF HAZARD AREAS INCLUDING AREAS OF HIGH VELOCITY FLOWS SUCH AS WATERWAYS, PAVED AREAS AND **DRIVEWAYS**
- WATER WILL BE PREVENTED FROM DIRECTLY ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR WATER HAS BEEN TREATED BY AN APPROVED DEVICE
- 14. TEMPORARY SEDIMENT TRAPS WILL REMAIN IN PLACE UNTIL AFTER THE LANDS THEY ARE PROTECTING ARE COMPLETELY REHABILITATED.
- ACCESS TO SITES SHOULD BE STABILISED TO REDUCE THE LIKELIHOOD OF VEHICLES TRACKING SOIL MATERIALS ONTO PUBLIC ROADS AND ENSURE ALL-WEATHER ENTRY/EXIT

### SOIL EROSION CONTROL INSTRUCTIONS

- 16. EARTH BATTERS WILL BE CONSTRUCTED WITH AS LOW A GRADIENT AS PRACTICABLE BUT NO STEEPER, UNLESS OTHERWISE NOTED, THAN:
  - 2(H):1(V) WHERE SLOPE LENGTH LESS THAN 12 METRES
  - 2.5(H):1(V) WHERE SLOPE LENGTH BETWEEN 12 AND 16 METRES. 3(H):1(V) WHERE SLOPE LENGTH BETWEEN 16
  - AND 20 METRES.
  - 4(H):1(V) WHERE SLOPE LENGTH GREATER THAN 20 METRES
- ALL WATERWAYS, DRAINS, SPILLWAYS AND THEIR OUTLETS WILL BE CONSTRUCTED TO BE STABLE IN AT LEAST THE 1:20 YEAR ARI, TIME OF CONCENTRATION STORM EVENT.
- 18. WATERWAYS AND OTHER AREAS SUBJECT TO CONCENTRATED FLOWS AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUNDCOVER C-FACTOR OF 0.05 (70%) GROUND COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION. FLOW VELOCITIES ARE TO BE LIMITED TO THOSE SHOWN IN TABLE 5-1 OF "MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION", DEPT OF HOUSING 1998 (BLUE BOOK). FOOT AND VEHICULAR TRAFFIC WILL BE PROHIBITED IN THESE AREAS.
- STOCKPILES AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.1 (60% GROUND-COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION.
- ALL LANDS, INCLUDING WATERWAYS AND STOCKPILES, DURING CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.15 (50% GROUND COVER) WITHIN 20 WORKING DAYS FROM INACTIVITY EVEN THOUGH WORKS MAY CONTINUE LATER.
- 21 FOR AREAS OF SHEET FLOW USE THE FOLLOWING GROUND COVER PLANT SPECIES FOR TEMPORARY COVER: JAPANESE MILLET 20 KG/HA AND OATS 20 KG/HA.
- 22. PERMANENT REHABILITATION OF LANDS AFTER CONSTRUCTION WILL ACHIEVE A GROUND-COVER C-FACTOR OF LESS THAN 0.1 AND LESS THAN 0.05 WITHIN 60 DAYS NEWLY PLANTED LANDS WILL BE WATERED. REGULARLY UNTIL AN EFFECTIVE COVER IS ESTABLISHED AND PLANTS ARE GROWING VIGOROUSLY FOLLOW-UP SEED AND FERTILISER WILL BE APPLIED, AS NECESSARY REVEGETATION SHOULD BE AIMED AT RE-ESTABLISHING
- NATURAL SPECIES, NATURAL SURFACE SOILS SHOULD BE REPLACED AND NON-PERSISTANT ANNUAL COVER CROPS SHOULD BE USED.


- ACCEPTABLE BINS WILL BE PROVIDED FOR ANY CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHING, LIGHTWEIGHT WASTE MATERIALS AND LITTER. CLEARANCE SERVICES WILL BE PROVIDED AT LEAST WEEKLY, DISPOSAL OF WASTE WILL BE IN A MANNER APPROVED BY THE SITE SUPERINTENDENT.
- 25. ALL POSSIBLE POLLUTANT MATERIALS ARE TO BE STORED WELL CLEAR OF ANY POORLY DRAINED AREAS, FLOOD PRONE AREAS, STREAMBANKS, CHANNELS AND STORMWATER DRAINAGE AREAS. STORE SUCH MATERIALS IN A DESIGNATED AREA UNDER COVER WHERE POSSIBLE AND WITHIN CONTAINMENT BUNDS.
- ALL SITE STAFF AND SUB-CONTACTORS ARE TO BE INFORMED OF THEIR OBLIGATION TO USE WASTE CONTROL FACILITIES PROVIDED
- ANY DE-WATERING ACTIVITIES ARE TO BE CLOSELY MONITORED TO ENSURE THAT WATER IS NOT POLLUTED BY SEDIMENT, TOXIC MATERIALS OR PETROLEUM PRODUCTS
- 28. PROVIDE DESIGNATED VEHICULAR WASHDOWN AND MAINTENANCE AREAS WHICH ARE TO HAVE CONTAINMENT BUNDS



- CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE
- DRIVE 1.5 METRE LONG STAP PICKETS INTO GROUND, 3 METRES APART.

  DIG A 150 MM DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE
- ENTIRENCH OVER BASE OF FABRIC.
  FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE. MANUFACTURER
- JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150 MM OVERLAP.

#### SEDIMENT FENCE SD 6-8



CONSTRUCTION NOTES: STRIP TOPSOIL AND LEVEL SITE.

COMPACT SUBGRADE

THIRD EDITION, AUGUST 1998

PRODUCED BY THE DEPARTMENT

- COVER AREA WITH NEEDLE-PUNCHED GEOTEXTILE
- CONSTRUCT 200MM THICK PAD OVER GEOTEXTILE USING ROADBASE OR 30MM AGREGATE. MINIMUM LENGT

GEOTEXTILE FABRIC DESIGNED TO PREVENT INTERMIXING OF SUBGRADE

AND BASE MATERIALS AND TO MAINTAIN GOOD PROPERTIES OF THE SUB-BASE LAYERS

GEOTEXTILE MAY BE A WOVEN OR NEEDLE

MIN WIDTH 3m

MIN LENGTH 1


EXISTING ROADWAY

CONSTRUCT ZOWINI THICK PAD UVER GEOLET HE CONSTRUCTION OF TO BUILDING ALIGNMENT, MINIMUM WIDTH 3 METRES.

CONSTRUCT HUMP IMMEDIATELY WITHIN BUUNDARY TO DIVERT WATER TO A SEDIMENT FENCE OR OTHER SEDIMENT TRAP.

STABILISED SITE ACCESS SD 6-14

STABILISE STOCKPILE



- FABRICATE A SEDIMENT BARRIER FROM GEOTEXTILE OR STRAW BALES.
- SUPPORT GEOTEXTILE WITH MESH TIED TO POSTS AT 1 METRE CENTRES.
- DO NOT COVER INLET WITH GEOTEXTILE
- CONSTRUCTION DETAILS ARE SIMILAR TO TYPICAL SEDIMENT FENCING DETAIL

GEOTEXTILE INLET FILTER SD 6-12

SOURCE: MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION THIRD EDITION AUGUST 1998 PRODUCED BY THE DEPARTMENT CONSTRUCTION NOTES: 1. LOCATE STOCKPILE AT LEAST 5 METRES FROM EXISTING VEGETATION, CONCENTRATED WATER FLOWS ROADS AND HAZARD AREAS I CONSTRUCT ON THE CONTOUR AS A LOW, FLAT, ELONGATED MOUND.

WHERE THERE IS SUFFICIENT AREA TOPSOIL STOCKPILES SHALL BE LESS THAN 2 METERS IN HEIGHT.

- CONSTRUCT EARTH BANK (STANDARD DRAWING 5-2) ON THE UPSLOPE SIDE TO DIVERT RUN OFF AROUND THE STOCKPILE AND A SEDIMENT FENCE (STANDARD DRAWING 6-7) 1 TO 2 METRES DOWNSLOPE OF STOCKPILE.

STOCKPILES

SD 4-1

COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modifie

D	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK	No
С	RE-ISSUED FOR DEVELOPMENT APPROVAL	21.04.22	RH	BK	
В	ISSUED FOR DEVELOPMENT APPROVAL	21.10.21	RH	BK	
Α	NIL ISSUE	-	-	-	
Issue	Description	Date	Drawn	Approved	ı
1 0	1cm at full size 10cm				i

**BARRY RUSH & ASSOCIATES** 



ACOR Consultants (CC) Ptv Ltd Platinum Building, Suite 2.01, 4 Ilya Avenu



GLENN AVENUE, NORTHMEAD

**EROSION & SEDIMENT CONTROL NOTES & DETAILS** AS NOTED OCT 21 20.04.22 CC210151

( ONSUITANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLAN

	This page last apt	auteu sum	. 2007	D.1-1	011-3110 3101	mwater beter	ition nanabo		
Form B1 <sup>1</sup> No.	DRAINAGE	DESIG	IN SUM	MAR'	/ SUB/DA	A			
Project:	CC210151	ı	ocation:		2-8 GLENN	AVENUE NOR	THMEAD		_
Designed By:	ВК		Company:	ACOF	CONSULTANTS	(CC) Pty. Ltd	Phone:	(02) 43	24 3499
SITE AREA	0.2813		na *See So	ection	3.4.3 for dual o	ccupancy			[A]
•	chment drainin	-		114/5		=	0	ha	[AA]
Basic storage			470 x [A]		2813	=	132.21	m³	[B]
Basic Discharg	ge =0.08	x [A]	0.2813	<u> </u>		=	0.0225	m³/s	[C]
(Must be as m	rained to storag nuch as possible without written	and no			% of	=	0.239	ha	[D]
[D]/[A] + [	0.239	]/[	0.2813	] x 10	00	=	85	%	[E]
Storage per h	a. Of contributi	ng area	= [B]/[D]			=	553.18		[F]
-	<i>/PSD adjustmer</i> D in litres/secon		. – .	sing [F	, and	*	64.59 * OSD 1 = 75% x OSD 2 = 25% x	64.59 = 4	
Determine PS	D = [G] x [D]	6	4.59	x	0.239	=	15.44 **	I/s	[H]
Maximum hea	ad to orifice cer	nter		**	OSD 1 = 75% x 15.44 OSD 2 = 25% x 15.44		1.6	m	[K]
Weir flow to	storage	Q <sup>Weir</sup> =0	CL(H <sup>Weir</sup> )	1.5	∴ <sub>H</sub> Weir	=	0.19	m	[1]
Select orifice	diameter: d=	(0.464×	(Q/√h) <sup>0.!</sup>	5 =(0.4	$64 \times [H] / \sqrt{[K]})^0$	.5 =	0.075 ***	m	[J]
Maximum dis	charge			***	OSD 1 ORIFICE = 9		15.44	l/s	[L]
Head for high	early discharge	2				=	1.5	m	[M]

(min 75% of [L])

 $\{[L] \times \sqrt{[M]/[K]}\}$ 

Average discharge/ha = [P]/[D] = 15.19 / 0.239

Determine final SSR =  $[R] \times [D] = 559.69 \times 0.239$ 

Enter volume/PSD adjustment chart (Fig 5.1) using [Q]

Approximate mean discharge = ([L] + [N])/2

And read off final storage volume per hectare

\*\*\*\* TOTAL STORAGE REQUIRED = 134m³
TOTAL STORAGE PROVIDED = 147m³
OSD TANK 1 = 107m³
OSD TANK 2 = 40m³

m³

= 14.95 l/s

= 15.19 l/s

= 63.56 l/s/ha [Q]

 $= 559.69 \text{ m}^3/\text{ha} [R]$ 

[N]

[P]

[S]

[T]

[U]

[V]

### **Upper Parramatta River Catchment Trust**

[S] x %

OCOPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified,

D	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK	North
С	RE-ISSUED FOR DEVELOPMENT APPROVAL	21.04.22	RH	BK	
В	ISSUED FOR DEVELOPMENT APPROVAL	21.10.21	RH	BK	
Α	NIL ISSUE	-	-	-	
Issue	Description	Date	Drawn	Approved	
0	1cm at full size 10cm		ĺ	I	

High early discharge

Primary storage proportion =

Secondary storage proportion =

Tertiary storage proportion =

Check [T] + [U] + [V] = [S]

BARRY RUSH &
ASSOCIATES
PTY LTD

### Ac OR

#### ACOR Consultants (CC) Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia

Annually

Inspect storages for subsidence

near pits.

### 

# Drawing Title OSD CALCULATION SHEET & MAINTENANCE SCHEDULE Drawn Date Scale A1 Q.A. Check RH OCT 21 AS NOTED BAK

CC210151

20.04.22

arrange for reconstruction to replace the volume lost.

Council to be notified of the proposal.

subsidence likely to indicate leakages.

Check along drainage lines and at pits for

# PROPOSED RESIDENTIAL DEVELOPMENT

Maintenance Contractor

MAINTENANCE	FREQUENCY	RESPONSIBILITY	PROCEDURE			
ACTION						
Drainage Control Pit (DCP)						
Inspect and remove any blockage of orifice	Six monthly	Owner	Remove grate and screen to inspect orifice. See plan for location of DCP			
Check attachment of orifice plate to wall of pit (gaps less than 5mm)	Annually	Maintenance Contractor	Remove grate and screen. Ensure plate mounted securely, tighten fixings if required. Seal gaps as required.			
Check orifice diameter correct and retains sharp edge	Five yearly	Maintenance Contractor	Compare diameter to design (see Work-As- Executed) and ensure edge is not pitted or damaged			
Inspect screen and clean	Six monthly	Owner	Remove grate and screen if required to clean it.			
Check attachment of screen to wall of pit	Annually	Maintenance Contractor	Remove grate and screen. Ensure screen fixings secure. Repair as required			
Check screen for corrosion	Annually	Maintenance Contractor	Remove grate and examine screen for rust or corrosion, especially at corners or welds.			
Inspect flap valve and remove any blockage	Six monthly	Owner	Remove grate. Ensure flap valve moves freely and remove any blockages or debris.			
Check attachment of flap valve to wall of pit	Annually	Maintenance Contractor	Remove grate. Ensure fixings of valve are secure			
Check flap valve seals against wall of pit	Annually	Maintenance Contractor	Remove grate. Fill pit with water and check that flap seals against side of pit with minimal leakage.			
Inspect overflow weir and remove any blockage	Six monthly	Maintenance Contractor	Remove grate and open cover to ventilate underground storage if present. Ensure weir clear of blockages.			
Inspect DCP walls (internal and external, if appropriate) for cracks or spalling	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.			
Inspect DCP sump and remove any sediment / sludge	Six monthly	Owner	Remove grate and screen. Remove sediment / sludge build-up and check orifice and flap valve clear.			
Inspect grate for damage or blockage	Six monthly	Owner	Check both sides of grate for corrosion (especially corners and welds) damage or blockage.			
Inspect return pipe from storage and remove any blockage	Six monthly	Maintenance Contractor	Remove grate and screen. Ventilate underground storage if present. Check orifice and remove any blockages in outlet pipe. Flush outlet pipe to confirm it drains freely. Check for sludge / debris on upstream side of return line.			
Storage						
Inspect pit and remove any sediment / sludge in pit	Six monthly	Maintenance Contractor	Remove grate and screen. Remove sediment / sludge build-up.			
Inspect internal tank walls (and external, if appropriate) for cracks or spalling	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.			
Inspect and remove any debris / litter / mulch etc. blocking grates	Six monthly	After storm event	Remove blockages from grate and check if pit blocked.			
Inspect tank storage are and remove debris / mulch / litter etc. likely to block screens / grates.	Six monthly	Maintenance Contractor	Remove debris and floatable material likely to be carried to grates.			
Compare storage volume to volume approved (Rectify if loss >	Annually	Maintenance Contractor	Compare actual storage available with Work-as- Executed plans. If volume loss is greater than 5%,			

OSD STORMWATER MAINTENANCE SCHEDULE

<sup>&</sup>lt;sup>1</sup> Revised for third edition to include flow from upstream and revised by pass flows

	E DETENTION CHE	
	a	
This page last updated December 1999 B.9-1 On-site Stormwater Detention Handbo	oŏk	
B9. OSD DETAILED DESIGN SUBMISSION		
This form is to be completed by the stormwater designer and submitted to Council together with the design plan/s and any necessary attachments.		
PROJECT ADDRESS:		
PROJECT APPLICANT:		P
OSD DESIGNER DETAILS:		
Company Name: ACOR CONSULTANTS (CC) PTY LTD	×29	
Address: SUITE 2.01, 4 ILYA AVENUE, ERINA NSW 2250	*	
Telephone No.: (02) 43243499 Fax No:	(7)	
Accreditation organisation:		- 34%
Accreditation Reference:		
Name and signature of designer: BRUCE KENNY (Print Name)		
(Print Name) Date: 21.10.21		
(Signature)  Items submitted: **		
SUCCESSION IN CAR OF	(Yes)/ No	
OSD Detailed Design Checklist	Yes/ No	
<ul> <li>Attachment A: Flood Affectation Information</li> </ul>	Yes / No	
<ul> <li>Attachment B: External Catchment Assessment</li> <li>Attachment C: On-line System Calculations</li> </ul>	Yes / No Yes / No	
Attachment D: Overflow and Surcharge Pathway Calculations	Yes / No	
<ul> <li>Attachment E: Site Drainage Calculations</li> </ul>	Yes / No	
Attachment F: Outlet Hydraulic Assessment	Yes / No	
<ul> <li>Attachment G: Site Storage Details</li> <li>Attachment H: Drainage Design Summary Sheet</li> </ul>	Yes / No (Yes) No	
Attachment in Prainage Pesign Summary Sheet	(1-05) INO	
COUNCIL REVIEW DETAILS:	to second modify	
Council Review Officer's Name:	in the second se	10 42
Review officer's comments:	200 27g	
3	\$	
CONTROL OF A SECURITY	*	
	al.	
Signature of Review Officer:Date:	LEO 0	
The control of the control of the control of the second the second the second the second the control of the second the control of the second th		
** The above items are to be submitted in a single bound form — a 'loose leaf' format is unacceptable.		

Upper Parramatta River Catchment Trust

This page last updated December 1999

B.9-2

On-site Stormwater Detention Handbook

### OSD DETAILED DESIGN CHECKLIST

ITEM	DESIG	SNER	COUNCIL REVIEW		
	YES	NO	YES	NO	
A Stormwater Concept Plan (SCP) has been approved previously (refer Section 4.1)	7	<b>/</b>			
2. The site (whole or partly) is defined as floodprone in a 100 year event			0-0-3 044		
If YES, see Plan No in Attachment A		1-200	PURE TE		
2(a) Has any floodplain storage been lost?	N/A	-6-3		E P. Andrews	
If YES, see Plan No in Attachment A				<del>ore in t</del>	
2(b) Has the floodprone area been excluded from the OSD calculations?	N/A	23 10200-003	Cal 28/4-91 (479)	Gr Table	
2(c) Is the OSD system performance adversely affected by the 100 year flood level?	N/A			-	
3. Is there an external catchment draining into the site?		/	WITH SOME WATER	APPENDED TO P	
If YES, see Plan No and calculations of 100 year ARI flow in Attachment B	0.00	/ D/ VIRBE MCI		P10/2 4/4/	
4. The location and extent of any floodway/flowpath has been determined, (refer Sections 4.1.3 & 4.2.2)	N/A				
If YES, see Plan Noand accompanying 100 year event hydraulic calculations in Attachment B. Buildings are not inundated (and have the required freeboard) nor are flows concentrated on an adjoining property (refer Sections 4.1.3, 4.2.7 & 4.2.9)					
5. The detailed design submission is consistent with the approved SCP		LEIDING CARACTER			
6. Are there any conditions on the development approval that may affect the drainage design (for example, trees to be retained)?					
The detailed design submission addresses the drainage-related conditions of the development approval					
<ol> <li>A site layout plan with accompanying ground levels/contours which extend into adjoining properties is submitted</li> </ol>	Edward Control			100 m 100 m	
If YES, see Plan NoC3-C4	September 1981	CONTRACTOR A	where to see	2 H 27	
9. Have other constraints, e.g. easements, services, been defined?	HADCIES N		semo.		
If YES, see Plan No.	Security instance	defended -char	and the second	-0-21	
10. How many OSD storage systems are there?TWQ	and the same	L BOTTON		No service	
11. Are the storage system/s off-line (refer Section 4.2.6)?		W/22 review 0.0000 11.		TRACT - T	
If NO, see alternative calculations included in Attachment C	APPLICATION COMM.	SI - CARLES			
12. State the type of discharge control device (i.e. orifice) or? Where the device is not an orifice, has specific Trust approval been obtained?					
<ol> <li>The area of the site to be drained by each OSD storage has been determined, (refer Section 4.2.2)</li> </ol>	/	-0-6348 48900 3		Co Unitro	
If YES, see Plan No C2 - CATCHMENT PLAN		The second secon			
If YES, the uncommanded site percentage is	3		į.		
25%, refer Section 4.1.4 unless specific approval has been granted).		Security Parallel Security Sec	er angewood	Lawrence Co.	
<ol> <li>The plan/s identify the maximum water levels, and the levels and locations of each storage's discharge point (refer Section 4.2.2)</li> </ol>		No. 915-1256 - 124	W442 TO CO. TO SAME	**************************************	
If YES, see Plan No C3 & C4 & DETAIL SHEET C5 & C6	r En Verticana	One substitute of	A. A. A.		
15. The location of overflow structures and surcharge pathways have been determined, (refer Sections 4.2.2 & 4.2.9)	<b>/</b>				
If YES, see Plan No C3 & C4 and calculations in Attachment D		×-500 5-		tere co	
Buildings are not inundated nor are flows concentrated on an adjoining property (refer Sections 4.2.7 & 4.2.9)	<b>/</b>				
The drainage plans have been checked for consistency against the Architectural and landscaping plans	<b>/</b>		100000		
17. A maintenance schedule has been prepared (ref Section 4.2.10)				100 and 100 and 10 hours	

Upper Parramatta River Catchment Trust

						Client
D	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK	North	BARRY RUSH &
С	RE-ISSUED FOR DEVELOPMENT APPROVAL	21.04.22	RH	BK		
В	ISSUED FOR DEVELOPMENT APPROVAL	21.10.21	RH	BK		ASSOCIATES
A	NIL ISSUE	-	-	-		PTY LTD
ssue	Description	Date	Drawn	Approved		
.0	1cm at full size 10cm					i



ACOR Consultants (CC) Pty Ltd
Platinum Building, Suite 2.01, 4 llya Avenue
ERINA NSW 2250, Australia
T +61 2 4324 3499
PROPOSED RESIDENTIAL
DEVELOPMENT LOTS 73, 74, 75 & 76 No. 2 - 8 GLENN AVENUE, NORTHMEAD

ON SITE DETENTION CHECKLIST SHEET 1 OF 2 Date 20.04.22 Scale A1 Q.A. Che
AS NOTED BAK OCT 21 Project No. CC210151

C10

### ON-SITE DETENTION CHECKLIST - SHEET 2 OF 2

This page last updated December 1999

On-site Stormwater Detention Handbook

Where there is more than one OSD system, Questions 18 to 26 are to be answered separately for each OSD storage system.

OSD Storage system identifier.....

ITEM	DESIGNER			INCIL /IEW
表 5、0.2.8.4 GRUP 25 0 4 17 GRUP 1 1995 (2005) 2 18 CESPETE (2005)	YES	NO	YES	
18. The design explicitly shows how all the drained area grades to the storage, including roof gutter overflows (refer Section 6.2)	phone with the Managemental according to a final behavior to the			
If YES, see Plan No			Year and the	
If NO, see calculations in Attachment E showing how all drainage	Paris State		- 95,9945 28	-
system components (including all roof gutters, downpipes, collecting pits and pipe systems, etc) have 100 year ARI capacities with 50% blockage factor				
<ol> <li>The invert level of storage is not less than ground level (or top of kerb) at point of connection to external stormwater system</li> </ol>		de de		
If YES, see Plan No.				hand the same of t
If NO, see explanatory notes in Attachment F	5w 1 Dieg D	V		
<ol> <li>The discharge control pit design is consistent with the principles shown in Figures 4.3, 7.10 and/or 7.11</li> </ol>				
20(a) The DCP has an open grating type lid (for ease of inspection)		LOWER LAND		
20(b) The DCP minimum dimensions are consistent with Section 4.2.3	Carl College C		25 280 19 o	
20(c) The floor of the DCP has a localised sump adjacent to the orifice with level at least 150 mm below the return pipe, (refer Section 4.2.8)	1			
20(d) The return pipe from the storage is at least 150 mm in diameter (refer Section 4.2.8).				
20(e) The return pipe flap valve is consistent with Figure 4.3	B	3	2310000 511 1.00	A CONTRACTOR
20(f) If an orifice control is specified, is it consistent with the requirements set out in Section 4.2.3?		700000 222		
If YES, see: Plan No		*		
20(g) The overflow weir is fitted with a basket (refer Section 6.3). There is a surface grate above the basket to facilitate inspection and maintenance				
20(h) The high early discharge (HED) characteristics are consistent with the requirements set out in Section 4.2.3	200			
If YES, see: Plan No			- AL - 100	
Accompanying weir calculations in Attachment E	The same of the sa	tunere escreta di la		
Plan No	Section in the section of the sectio			100 to
20(i) The screen design is consistent with Section 4.2.5			36.00	
If YES, see: Plan No for screen type, area and orientation				
Plan No for fabrication note re aperture orientation		1		
Plan No for fixing and handle details			200 644 F07-8.768	
Plan Noshowing how all inflows to the DCP are on the upstream side of the screen protecting the orifice		,		
20(j) The outlet pipe from the DCP has a capacity at least twice the PSD (refer Section 4.2.4)				
If YES, see calculations in Attachment E				1,100,000

Upper Parramatta River Catchment Trust

This page last updated December 1999

B.9-4

On-site Stormwater Detention Handbook

ITEM.	DESIG	NER	COUNCIL REVIEW		
	YES	NO.	YES	NO	
21. If an above ground/landscaped storage is specified, answer Q21(a) to Q21(g), otherwise move to Q22.				ogot i sant	
21(a) The first 10%-20% of storage is provided in an area able to tolerate frequent inundation(refer Section 4.2.7)					
21(b) Where the depth of ponding exceeds 600 mm, consideration has been given to whether there are steep drops, and/or a need for steps or 'walk-in' 'walk-out' batters, etc. when deciding if fencing and/or warning signs are required (Refer Sections 4.2.7 & 6.2)					
21(c) The landscaping treatment within the storage area is such that it does not limit storage volumes or provide a significant source of debris loading	L-40-1880-1-9-				
21(d) The minimum surface slope is consistent with Section 4.2.7				OTHER DESIGNATION OF	
21(e) Subsoil drainage is provided in areas subject to frequent ponding and around the outlet (refer Section 4.2.7)	ent a secul				
21(f) If the design includes a retaining wall, has it been structurally checked?			**************************************		
21(g) Does the system have the correct storage?		THOMESON AN	Te for to pole	11 · 2-4	
If YES, see stage-storage calculations in Attachment G					
22. If a driveway/car-park storage is specified, answer Q22(a) to Q22(c), otherwise move to Q23			-		
22(a) The maximum depth is less than or equal to 200mm (refer Section 4.2.7)		Ko Mari	n samen	VIOLENCE - THE .	
22(b) The minimum transverse slope is 0.7% (refer Section 4.2.7)	CORDON IN A			S E RIGGELIAN	
22(c) The system has the correct storage	ESPANSE - LIGHTS	Version of	Robbs _ A -ex-	. = 4,5	
If YES, see stage-storage calculations in Attachment G	AND				
23. If a structural/underground storage is specified, answer Q 23(a) to Q 23(f), otherwise move to Q24				- F - EL - L - L - L - L - L - L - L - L -	
23(a) The dimensions of openings are consistent with Section 4.2.8	<b>V.</b>		BY CAN THIS DATE		
23(b) The storage floor has a minimum slope of 0.7% (refer Section 4.2.8)	<b></b>			N Delicination	
23(c) There are sufficient access points for flushing purposes (refer Section 4.2.8)	my out anapass	La la Posso	A SAMPLE S		
23(d) There are sufficient grated openings for ventilation purposes (refer Section 4.2.8)			V-802		
23(e) All access points have light weight covers	<b>V</b>	COLUMN TO THE STATE OF	. Who we will be a second		
23(f) The system has the correct storage		nai yene yanaya - ee		No.	
If YES, see stage-storage calculations in Attachment G					
24. The distribution of storage minimises inconvenience (refer Section 5.1.4)		aredi e			
25. The Drainage Design Summary sheet has been completed (refer Appendix B1)	<b>/</b>				
If YES, see completed sheet in Attachment H			74		
<ol><li>The Drainage Design Summary sheet details are consistent with the design plans</li></ol>	<b>/</b>	AB 200000			

Upper Parramatta River Catchment Trust

D	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK	No
С	RE-ISSUED FOR DEVELOPMENT APPROVAL	21.04.22	RH	BK	l
В	ISSUED FOR DEVELOPMENT APPROVAL	21.10.21	RH	BK	l
Α	NIL ISSUE		-	-	l
Issue	Description	Date	Drawn	Approved	l
1 0	1cm at full size	_			1

BARRY RUSH & ASSOCIATES




ACOR Consultants (CC) Pty Ltd Project

Platinum Building, Suite 2.01, 4 Ilya Avenue
ERINA NSW 2250, Australia
T +61 2 4324 3499
PROPOSED RESIDENTIAL
DEVELOPMENT

ON SITE DETENTION CHECKLIST SHEET 2 OF 2

LOTS 73, 74, 75 & 76
No. 2 - 8
GLENN AVENUE, NORTHMEAD

Date 20.04.22 AS NOTED OCT 21 CC210151 C11



# PIPE LONG SECTION PIT P1 - P4 & EXISTING KIP HORIZONTAL SCALE - 1:200/A1, 1:400/A3 VERTICAL SCALE - 1:40/A1, 1:80/A3

						C
D	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK	North	ء ا
С	NIL ISSUE	-	-	-		5
В	NIL ISSUE	-	-	-		
Α	NIL ISSUE	-	-	-		F
Issue	Description	Date	Drawn	Approved		ı
1 0	1cm at full, size , 10cm	1	_		]	1

BARRY RUSH & ASSOCIATES PTY LTD





ACOR Consultants (CC) Pty Ltd
Platinum Building, Suite 2.01, 4 llya Avenue
ERINA NSW 2250, Australia
T +61 2 4324 3499
PROPOSED RESIDENTIAL
DEVELOPMENT No. 2 - 8 GLENN AVENUE, NORTHMEAD

Drawing ritte
PIPE LONG SECTION

Issue
20.04.22
Date

## STORMWATER QUALITY REPORT

### 1 INTRODUCTION

A CATCHMENT BASED WATER QUALITY MODEL WAS DEVELOPED TO ASSESS THE STORMWATER RUNOFF QUALITY IN ACCORDANCE WITH THE WATER SENSITIVE URBAN DESIGN (WSUD) REQUIREMENTS OF PARRAMATTA DEVELOPMENT CONTROL PLAN PART 3.3.6 AND APPENDIX 7. IN THIS REGARD WE REFER TO THE PRESCRIBED TARGETS TABLED FOLLOWING:

TABLE 1 - STORMWATER POLLUTANT REDUCTION TARGETS

STORMWATER POLLUTANT	REDUCTION TARGETS
GROSS POLLUTANT	90%
TOTAL SUSPENDED SOLIDS (TSS)	85%
TOTAL PHOSPHORUS (TP)	60%
TOTAL NITROGEN (TN)	45%

### 2 STUDY METHODOLOGY

THE OBJECTIVES OF THIS REPORT ARE TO:

- ASSESS THE RUNOFF QUALITY FOR THE UNTREATED POST DEVELOPED SCENARIO AND IDENTIFY STORMWATER QUALITY CONTROLS LIKELY TO IMPACT ON RUNOFF QUALITY.
- ASSESS THE STORMWATER QUALITY FOR THE POST DEVELOPED SCENARIO INCLUDING THE MEASURES PROPOSED TO MEET THE POLLUTANT REMOVAL TARGETS.

THE REPORT IS BASED ON THE APPLICATION OF MUSIC SOFTWARE (MODEL FOR URBAN STORMWATER IMPROVEMENT CONCEPTUALISATION). IN THIS REGARD THE MODEL IS DEFINED AS FOLLOWS:

- A STORMWATER QUALITY MODEL TO CONVERT RAINFALL AND EVAPOTRANSPIRATION INTO RUNOFF.
- ESTIMATION OF STORMWATER FLOW AND POLLUTION GENERATION BY SIMULATING THE PERFORMANCE OF STORMWATER TREATMENT DEVICES INDIVIDUALLY AND AS PART OF A TREATMENT TRAIN.

THE MODEL DEFINES WATER QUALITY PROFILES FOR BOTH TREATED AND UNTREATED POST DEVELOPED SCENARIOS. THE TREATED POST DEVELOPED MODEL INCLUDES PARAMETERS WHICH REPRESENT THE WATER QUALITY MEASURES.

### 3 STORMWATER QUALITY MODELLING

### 3.1 GENERAL

THE FOLLOWING PARAMETERS WERE ASSESSED FOR THE HYDROLOGICAL MODELLING ASSOCIATED WITH THE CATCHMENT.

- RAINFALL/RUNOFF AND EVAPOTRANSPIRATION.
- SUB CATCHMENT DIVERSIONS.
- LAND USE (PERVIOUS AND IMPERVIOUS)

### 3.2 RAINFALL/RUNOFF AND EVAPOTRANSPIRATION

THE MUSIC MODEL WAS FORCED WITH 6 MINUTE RAINFALL DATA FROM THE PARRAMATTA NORTH (MASONS DRIVE) GAUGE (ID 066124) FOR THE PERIOD 25 DECEMBER 1984 TO 30 DECEMBER 2007.

DAILY AVERAGE PET VALUES WERE NOT AVAILABLE FOR STATION ID 066124 AND WERE SOURCED FROM THE BUREAU OF METEOROLOGY FOR THE NEIGHBOURING PROSPECT RESERVOIR GAUGE (ID 067019). THE DETAILS ARE SUMMARISED IN TABLE 3.1 AND 3.2

TABLE 3.1 - DETAILS OF DAILY RAINFALL DATA						
STATION	STATION NAME PERIOD TIMESTER					
066124	PARRAMATTA NORTH (MASONS DRIVE)	25/12/1984-30/12/2007	6 min			

TABLE 3.2 - SUMMARY OF POTENTIAL EVAPOTRANSPIRATION (PET)								
JAN	FEB	MAR	APR	MAY	JUN			
170.5	131.6	120.9	87	62	48			
JUL	AUG	SEP	OCT	NOV	DEC			
51	77.5	108	136.4	155	173.6			

### 3.3 CATCHMENT DEFINITION

THE POST DEVELOPED CATCHMENT CHARACTERISTICS ARE IDENTIFIED IN TABLE 3.3.

TABLE 3.3 - POST DEVELOPMENT SUB CATCHMENT DETAILS							
SUB CATCHMENT ID	SUB CATCHMENT AREA (ha)	% IMPERVIOUS AREA	% PERVIOUS AREA				
ROOF TO RWT	0.055	100	0				
ROOF TO OSD 1	0.039	100	0				
AREA TO OSD 1	0.084	70	30				
OSD CATCHMENT 2	0.061	100	0				
OSD BYPASS	0.042	60	40				

### 4 MUSIC MODEL

THE MUSIC MODEL IS BASED ON A 6 min RAINFALL-RUNOFF MODEL IN CONJUNCTION WITH REPRESENTATIVE BASEFLOW AND STORMFLOW EVENT MEAN CONCENTRATIONS (EMCs).

### 4.1 WATER QUALITY PARAMETERS

THE ADOPTED VALUES OF VARIOUS MUSIC RAINFALL AND RUNOFF PARAMETERS IN ACCORDANCE WITH NSW MUSIC MODELLING GUIDELINES 2015 FOR MEDIUM CLAY ARE SUMMARISED IN TABLE 4.1.

TABLE 4.1 - ADOPTED MUSIC RAINFALL/RUNOFF PARAMETERS					
PARAMETER	VALUE				
IMPERVIOUS AREA PROPERTIES					
RAINFALL THRESHOLD (mm/DAY) 1.5 (0.3 F					
PERVIOUS AREA PROPERTIES					
SOIL STORAGE CAPACITY (mm)	94				
SOIL INITIAL STORAGE (% OF CAPACITY)	25				
FIELD CAPACITY (mm)	70				
INFILTRATION CAPACITY COEFFICIENT - a	135				
INFILTRATION CAPACITY EXPONENT - b	4				
GROUNDWATER PROPERTIES					
INITIAL DEPTH (mm)	10				
DAILY RECHARGE RATE (%)	10				
DAILY BASEFLOW RATE (%)	10				
DAILY DEEP SEEPAGE RATE (%)	0				

D	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK	North
С	NIL ISSUE	-	-	-	
В	NIL ISSUE	-	-	-	
Α	NIL ISSUE	-	-	-	
Issue	Description	Date	Drawn	Approved	

**BARRY RUSH & ASSOCIATES** 







GLENN AVENUE, NORTHMEAD

C13

### 4.1 WATER QUALITY PARAMETERS CONT.

STORMWATER QUALITY IS CHARACTERISED USING EVENT MEAN CONCENTRATION (EMCs) UNDER STORM AND BASE FLOW CONDITIONS. THE VALUE OF WATER QUALITY PARAMETERS ADOPTED IN THIS STUDY IS SUMMARISED IN TABLE 4.2

TABLE 4.2 - ADOPTED MUSIC WATER QUALITY PARAMETERS								
LAND-USE CATEGORY		Log <sub>10</sub> TSS (mg/L)		Log <sub>10</sub> TP (mg/L)		Log₁₀TN (mg/L)		
		STORM FLOW	BASE FLOW	STORM FLOW	BASE FLOW	STORM FLOW	BASE FLOW	
RESIDENTIAL	MEAN	2.15	1.20	-0.60	-0.85	0.30	0.11	
	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12	
GENERAL	MEAN	2.20	1.10	-0.45	-0.82	0.42	0.32	
URBAN	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12	
ROOFS	MEAN	1.30	1.10	-0.89	-0.82	0.30	0.32	
	STD DEV	0.32	0.17	0.25	0.19	0.19	0.12	

### 4.2 STORMWATER TREATMENT MEASURES

THE PROPOSED STORMWATER TREATMENT MEASURES INCLUDED

IN THE POST DEVELOPED MODEL ARE AS FOLLOWS:

- 12,000 LITRE RAINWATER TANK (REUSE FOR IRRIGATION)
- 4 x SPELFILTERS (FULL HEIGHT) IN EACH OSD TANK
- 2 x STORMSACKS

THE SCHEMATIC LAYOUT FOR THE POST DEVELOPED MUSIC

MODEL IS DEPICTED IN FOLLOWING FIGURE 1





FIGURE 1 - MUSIC MODEL SCHEMATIC

### 5 RESULTS & CONCLUSION

BASED ON THE FOREGOING AND THE RESULTS DEPICTED IN TABLE 5.1, THE PROPOSED STORMWATER QUALITY TREATMENT MEASURES MEET THE REQUIRED TARGETS OF THE CITY OF PARRAMATTA.

REFER TO CC210151\_20221008.SQZ AS PREPARED BY ACOR CONSULTANTS (CC) PTY LTD FOR FURTHER INFORMATION.

TABLE 5.1 - TREATMENT TRAIN EFFECTIVENESS



© COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 AT The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified,

D	REISSUED TO SUIT COUNCIL COMMENTS	09.10.22	RH	BK	North
С	NIL ISSUE	-	-	-	
В	NIL ISSUE	-	-	-	
Α	NIL ISSUE	-	-	-	
Issue	Description	Date	Drawn	Approved	
1 0	1cm at full size 10cm				

BARRY RUSH & ASSOCIATES PTY LTD



ACOR Consultants (CC) Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia



GLENN AVENUE, NORTHMEAD

C14

CC210151