

HEALTH INFRASTRUCTURE

Kingscliff Ambulance Station

Bundjalung Country

Decision Statement for Review of Environmental Factors –
Prepared by GeoLINK

20/03/2023

Version Number: 1



Health
Infrastructure

DETERMINED – APPROVAL

REF Approval No: 07/2023

Date: 29/03/2023

Signed by:

A handwritten signature in black ink, appearing to be 'J. Smith'.



Kingscliff Ambulance Station

Project Details

Project Name	Kingscliff Ambulance Station
Project Location	771 Cudgen Road, Cudgen
REF Prepared by	GeoLINK – dated 22 December 2022
Activity Description	Construction of a new ambulance station


Decision Statement

Based on the REF document, the Recommendation report and any other information and any advice from other relevant determining authorities:

- the proposed activity is not likely to have a significant impact on the environment and therefore an EIS is not required.
- the proposed activity will not be carried out in a declared area of outstanding biodiversity value and is not likely to significantly affect threatened species, populations or ecological communities, or their habitats or impact biodiversity values, meaning a SIS and/or BDAR is not required.
- the proposed activity may proceed subject to the mitigation measures in Schedule 1 below that are required to eliminate, minimise or manage environmental impacts.

Determination

Acting as a delegate of the Health Administration Corporation, and, in accordance with Section 5.5 of the *Environmental Planning and Assessment Act 1979*, having taken into account to the fullest extent possible all matters likely to affect the environment as a result of the proposed activity, and having regard to the Assessment Report, the Statement of Compliance and the Review of Environmental Factors prepared by GeoLINK dated 22 December 2022, I hereby determine the Review of Environmental Factors by granting approval subject to the Mitigation Measures in Schedule 1 below.



29 Mar 2023

Leisa Rathborne

Date

A/Chief Executive Health Infrastructure

Schedule 1

Mitigation measures

The following Mitigation Measures have been imposed to ensure that any development activity is carried out in accordance with the plans/documentation and any amendment approved under Part 5 of the *Environmental Planning and Assessment Act 1979*.

General measures

1. Obligation to prevent impacts to the environment

In addition to meeting the mitigation measures in this determination, all reasonable and feasible measures should be implemented to prevent impacts to the environment that may result from the activity, which relates to the construction of a new ambulance facility under 12m in height.

2. Development in Accordance with Plans and Documentation

The proposal must be carried out generally in accordance with the Review of Environmental Factors dated 22 December 2022 and prepared by GeoLINK on behalf of NSW Health Infrastructure (including accompanying appendices A - U) and generally in accordance with the following plans/documentation as modified below and by any of the under-mentioned measures:

Drawing Title	Drawing Ref	Revision	Date	Prepared by
ARCHITECTURAL				
Cover Page	R25-AR-0000	M	20/2/23	djrd
Site Analysis	R25-AR-0001	I	20/2/23	djrd
Tree Removal Plan	R25-AR-0101	L	20/2/23	djrd
Proposed Site Plan – Opt 1*	R25-AR-0102	N	20/2/23	djrd
Proposed Site Plan – Opt 2*	R25-AR-0103	E	23/8/22	djrd
Shadow Diagrams	R25-AR-105	F	20/2/23	djrd
Lower Ground Floor General Arrangement Plan	R25-AR-1101	O	20/2/23	djrd
Ground Floor General Arrangement Plan	R25-AR-1102	N	20/2/23	djrd
Roof Plan	R25-AR-1103	M	20/2/23	djrd
Elevations	R25-AR-2001	L	20/2/23	djrd
Elevations	R25-AR-2002	L	20/2/23	djrd
Sections	R25-AR-2501	K	20/2/23	djrd
Sections	R25-AR-2502	K	20/2/23	djrd
Render	R25-AR-9001	I	20/2/23	djrd
LANDSCAPE				
Landscape Coversheet	R25-LA-000	I	30/5/22	Site Image
Landscape Plan	R25-LA-101	H	30/5/22	Site Image
Landscape Plan	R25-LA-102	B	25/5/22	Site Image
Landscape Details	R25-LA-501	C	19/5/22	Site Image

CIVIL

Sediment and Erosion Control Plan – Lower Ground Floor Sheet 1	C1004	4	5/7/22	Meinhardt Bonacci
Sediment and Erosion Control Plan – Lower Ground Floor Sheet 2	C1005	3	5/7/22	Meinhardt Bonacci
Sediment and Erosion Control Plan – Ground Floor Sheet 3	C1006	3	5/7/22	Meinhardt Bonacci
Bulk Earthworks Detail Plan – Lower Ground Floor Sheet 1	C1008	4	5/7/22	Meinhardt Bonacci
Bulk Earthworks Detail Plan – Lower Ground Floor Sheet 2	C1009	4	5/7/22	Meinhardt Bonacci
Bulk Earthworks Detail Plan – Ground Floor Sheet 3	C1010	4	5/7/22	Meinhardt Bonacci
Siteworks and Stormwater Drainage Plan Sheet 1	C1030	5	5/7/22	Meinhardt Bonacci
Siteworks and Stormwater Drainage Plan Sheet 2	C1031	4	5/7/22	Meinhardt Bonacci
Siteworks and Stormwater Drainage Plan Sheet 3	C1032	4	5/7/22	Meinhardt Bonacci

* The appropriate Site Plan option is dependent on the required provision of water to the site. The appropriate water main option will be selected once a 200mm water main extension is installed on the future 250 mm water main on Cudgen Road and that main is pressure tested. This will occur during construction.

3. Crown Certificate

A Certificate under Section 6.28 of the *Environmental Planning and Assessment Act 1979* is to be obtained prior to any work commencing.

4. Building Code of Australia

All building work is to be undertaken in accordance with the Building Code of Australia and referenced Australian Standards, including the requirements of AS 1428.1 General Requirements for Access.

5. Approvals

These conditions do not remove any obligation to obtain all other licences, permits, approvals and land owner consents from all relevant authorities and land owners as required under any other legislation for the Project. The terms and conditions of such licences, permits, approvals and permissions must be complied with at all times. A copy of all approvals is to be kept on site.

6. Long Service Levy

The Crown Certificate must not to be issued unless the Crown Certifier is satisfied the required levy payable under Section 34 of the *Building and Construction Industry Long Service Payments Act 1986* has been paid. The levy must be paid by the person liable, as specified in Section 38 of the *Building and Construction Industry Long Service Payments Act 1986*. For further information contact the Long Service Payments Corporation on their Helpline 131441.

7. Tree Management and Landscape

- 7.1 Trees not proposed to be removed are to be protected in accordance with AS 4970 -2009 Protection of Trees on Development Sites.
- 7.2 No building materials, builder sheds and the like are permitted to be stored under the canopy of existing trees.

- 7.3 All trees to be removed are required to be replaced on at least a one-to-one basis of suitable species with a minimum pot size of 45L. The location for the replanting will be within the landscaping of the ambulance station and in the wider Tweed Valley Hospital site. The project landscape plans include the planting of 14 trees and the remaining trees are to be located in consultation with the Tweed Valley Hospital project team.
- 7.4 Development of the ambulance station must be consistent with the Biodiversity Management Plan approved for the Tweed Valley Hospital development (SSD-9575 and SSD-10353).

8. Prior Notice of Category 2 Remediation Work

Where relevant, all required regulatory notifications and permits are to be obtained including Notification of Category 2 Remediation Works to Council for the remedial work at least 30 days before the commencement of the work. Notice must be given in accordance with clause 4.13 of the *State Environmental Planning Policy (Hazards and Resilience) 2021*.

9. Structural adequacy

All new buildings and structures, and any alterations or additions to existing buildings and structures, that are part of the activity, must be constructed in accordance with the relevant requirements of the Building Code of Australia.

10. External walls and cladding

The external walls of buildings, including additions to existing buildings, that are part of the activity, must comply with the relevant requirements of the Building Code of Australia.

11. Sustainability

- 11.1 The activity is to achieve compliance with Section 2.5.6 of the Health Infrastructure Engineering Services Guidelines dated 6 August 2021, including Design Guidance Note No. 058.

12. Bushfire

The northern, eastern and western facades of the building shall be of BAL-19 construction. The southern façade shall be of BAL-12.5 construction, in order to meet the aims and objectives of *Planning for Bushfire Protection 2019*.

13. Compliance with Mitigation Measures

The Proponent engaged by HI, must ensure that all relevant personnel, including contractors (and their subcontractors), are aware of these Mitigation Measures, and the requirement to undertake the activity within these Measures.

14. Non-compliance notification

- 14.1 The HI-Planning Team and the HI-Regional Director must be notified where a non-compliance with a mitigation measure is identified.
- 14.2 The notification should identify relevant activity, set out the mitigation measure that is non-compliant with, the way in which it does not comply, any known reasons for the non-compliance and what actions have been, or will be undertaken, to address the non-compliance.

Prior to commencement of works

Note: The following Measures are to be complied with prior to the commencement of works on the subject site, and at other stages where stated.

15. Consultation Approach

- 15.1 Prior to the commencement of work, a consultation approach shall be prepared that:
- a. Identifies the relevant people that may be consulted during the construction phases of the activity. At the minimum this should include the relevant Council, community (including adjoining affected landowners, businesses and any other directly impacted by the activity) and those on an existing hospital site;
 - b. Determines the suitable methods of consultation with relevant stakeholders, including the receipt of feedback; and
 - c. Provides the approach access to project information.

16. Community Notification

- 16.1 Prior to commencement of work, the proponent must notify in writing Council and the occupier of any land within 40 metres of the boundary of the site works. The notification should outline the project, the expected timing for commencement and completion of construction works.
- 16.2 Where practicable, work programs for noisy work should be coordinated with the hospital, at least two (2) weeks prior to commencement to minimise impacts on their operations.
- 16.3 Complaints received prior to and during the undertaking of works shall be recorded and attended to promptly. On receiving a complaint, works shall be reviewed to determine whether issues relating to the complaint can be avoided or minimised. Feedback shall be provided to the complainant explaining what remedial actions (if any) were taken.
- 16.4 The proponent shall develop a complaints management system and record details of all complaints received and the means of resolution of those complaints. The Complaints Register shall be made available on request.
- 16.5 A site notice board must be located at the entrance or other appropriate location on the site in a prominent position and must including the following:
- a. 24-hour contact person for the site;
 - b. Telephone, facsimile numbers and email addresses;
 - c. Site activities and time frames.
 - d. Details of where accessible project information can be sourced.
- 16.6 The site notice must be placed at eye level and be erected no less than 2 days prior to the commencement of works.

17. Hazardous Materials

- 17.1 An Asbestos Management Plan is to be prepared to provide a procedure to control the risk of exposure from asbestos and lead impacted topsoil during the work.
- 17.2 An unexpected finds procedure is to be included in an overarching Construction Management Plan (CMP) for the work, in the event that other contamination is encountered which have not been identified during this assessment.
- 17.3 Waste must be transported by an appropriately licensed transporter, and disposed to a facility that is licensed to receive that class of waste. It is recommended that this report is sent to the proposed receiving facility to confirm their acceptance of the material prior to off-site disposal. If the description of the soil differ from that

described within, then further assessment for waste classification purposes may be required prior to off-site disposal.

- 17.4 SafeWork NSW is to be notified in accordance with the relevant policy prior to work involving asbestos material being undertaken.
- 17.5 Air monitoring devices shall be put in place, around the site, during demolition. A qualified environmental hygienist shall be on site to supervise the work to ensure the safety of workers and the public are not compromised in anyway. Daily monitoring and results will be taken and analysed to ensure safe air quality levels ensue.
- 17.6 A Lead Removal Control Plan will be developed and implemented by the contractor. Lead based paint is defined as paint containing more than 1% lead by weight, and is classified as hazardous waste according to EPA NSW 'Waste Classification Guidelines. Part 1: Classifying Waste'.

18. Dilapidation Report

Prior to construction, a dilapidation report is to be prepared for hospital, Council, or other assets within the zone of influence of the work.

19. Construction Management

A detailed Construction Environmental Management Plan (CEMP) is to be prepared prior to the commencement of works and implemented during the undertaking of works. The CEMP must be prepared having regard to the *Environmental Management Plan Guideline: Guideline for Infrastructure Projects (2020)* prepared by the Department of Planning and Environment, and is to include (where relevant), but not be limited to, the following:

- (a) Details of:
 - i. hours of work;
 - ii. 24-hour contact details of site manager;
 - iii. management of dust and odour;
 - iv. stormwater control and discharge;
 - v. measures to ensure that sediment and other materials are not tracked onto the roadway by vehicles leaving the site;
 - vi. any other specific environmental construction mitigation measures detailed in this REF;
 - vii. any requirements outlined in any relevant approvals, permits or licences.
 - viii. community consultation and complaints handling.
- (b) Construction traffic and pedestrian management plan;
- (c) Construction noise and vibration management;
- (d) Construction waste management, including contaminated waste;
- (e) Construction soil and water management;
- (f) Flood management;
- (g) Tree protection;
- (h) Air quality and dust management measures;
- (i) Demolition work plans;
- (j) Unexpected finds protocol for Aboriginal and non-Aboriginal heritage and associated communications procedure;
- (k) Unexpected finds protocol for historical heritage;
- (l) Unexpected finds protocol for contamination; and
- (m) Emergency Management Plan.
- (n) Training of responsibilities under *National Parks and Wildlife Act 1975*, *Heritage Act 1977* and any other relevant legislation.

20. Demolition/Construction Waste Management Plan

- 20.1 A Demolition/Construction Waste Management Plan shall be prepared by an appropriately qualified contractor prior to the commencement of works. The Waste Management Plan should be prepared in accordance with DECCW's "Waste Classification Guidelines (2008)" and the Protection of the Environment Operations Act 1997.

- 20.2 The Demolition/Construction Waste Management Plan is to include the following requirements and details:
- d. The type and volume of all waste materials (e.g. excavation material, green waste, bricks, concrete, timbers, plasterboard and metals) is to be estimated prior to the commencement of works, with the destination for each waste identified. Waste should be re-used or recycled as much as practicable. Where not practicable, the location of a suitable waste disposal facility is to be identified.
 - e. Cleaning out of batched concrete mixing plant is not permitted within any construction compound.
 - f. Non-recyclable waste and containers are to be regularly collected and disposed of at a licensed disposal site. Frequency of collection should be identified.
 - g. No burning or burying of waste is permitted on the site.
 - h. Any bulk garbage bins delivered by authorised waste contractors are to be placed and kept within the property boundary.
- 20.3 The following mitigation measures will be implemented in order to prevent adverse impacts in relation to waste generated by the proposed works:
- a. No materials will be used in a manner that will pose a risk to public safety and waste generated from the proposed works will be recycled where possible.
 - b. Unnecessary resource consumption will be avoided.
 - c. Non-recyclable wastes will be collected and disposed of or recycled in accordance with Office of Environment and Heritage (OEH) guidelines.

21. External walls and cladding

- 21.1 Prior to commencement of work, independent advice is required to confirm that the products and systems proposed for use or used in the construction of any external walls, including finishes and claddings such as synthetic or aluminium composite panels, comply with the requirements of the Building Code of Australia.
- 21.2 The independent advice is to be prepared and signed by a suitable qualified expert, such as a façade engineer or other building professional and a copy of the advice is to be provided to the Crown Certifier.

22. External lighting

- 22.1 Prior to commencement of work, independent advice is required to confirm that the proposed external lighting design would be in accordance Australian Standards AS/NZS 1158.3.1:2020 Lighting for roads and public spaces – Part 3.1: Pedestrian area (Category P) lighting – Performance and design requirements and AS/NZS 4282:2019 Control of the Obtrusive Effects of Outdoor Lighting.
- 22.2 The independence advice is to be prepared and signed by a suitably qualified expert, such as a practising lighting engineer, and a copy of the advice is to be provided to the Crown Certifier.

23. Monitoring and Reporting

- 23.1 Prior to the commencement of works, a program for the monitoring and reporting of compliance with these mitigation measures shall be prepared. The timing and scope of these are to be defined in the program, however, must be undertaken at least every 6 months following the commencement of works.

24. Noise Management Measures

- 24.1 During preparation of the construction program, consult with the hospital to determine what areas (if any) of the hospital is particularly noise sensitive, and at what time (ward rooms, operating theatres, etc.).
- 24.2 Identify feasible acoustic controls or management techniques (use of screens, scheduling of noisy works, notification of adjoining land users, respite periods) when excessive levels may occur.

- 24.3 For activities where acoustic controls and management techniques still cannot guarantee compliant noise levels, implement a notification process whereby nearby development is made aware of the time and duration of noise intensive construction processes.

25. Erosion and Sediment Control

- 25.1 Erosion and sediment controls will be implemented in accordance with the Landcom/ Department of Housing Managing Urban Stormwater, Soils and Construction Guidelines (the Blue Book) and ensure any water diversion or control outlets associated with the works do not result in scouring.
- 25.2 Works will only commence once all erosion and sediment controls have been established. The controls will be maintained in place until the works are complete and all exposed erodible materials are stable.
- 25.3 Erosion and sedimentation controls will be checked and maintained (including clearing of sediment from behind barriers) on a regular basis (including after any precipitation events) and records kept and provided on request.

26. Services and Utilities

Prior to the commencement of works, any services and utilities that may be impacted by the works are to be appropriately relocated.

27. Construction Traffic Management

A Construction Traffic Management shall be prepared in consultation with Council prior to commencement of works.

During construction/undertaking of work

Note: The following Conditions are to be complied with during the approved construction/the undertaking of works.

28. Site notice

The Site Notice(s) required by mitigation measure 16.5 must be prominently displayed during the construction of the activity.

29. Construction Site Management

- 29.1 Construction site fencing is to be installed around the construction site. Vehicle and workforce access points and roads to the construction compounds are to be clearly designated and controlled for authorised access only. Vegetation clearance is to be minimised.
- 29.2 The worksite should be left tidy and rubbish free each day prior to leaving the site and at the completion of works.
- 29.3 The use and storage of hazardous materials and dangerous goods, including petroleum, distillate and other chemicals, shall be in accordance with the relevant legislation including, but not limited to:
- Protection of the Environment Operations Act 1997
 - Work Health and Safety Regulation 2017
 - AS 1940 The storage and handling of flammable and combustible liquids
 - Safe Work NSW Code of Practice – Managing Risks of Hazardous Chemicals in the Workplace.
- 29.4 All materials on-site or being delivered to the site must be wholly contained within the site. The requirements of the Protection of the Environment Operations Act 1997 are to be complied with when placing/stockpiling loose material or when disposing of waste products or during any other activities likely to pollute drains or watercourses.

- 29.5 The public way must not be obstructed by any materials, vehicles, refuse, skips or the like, under any circumstances.
- 29.6 All equipment and machinery should be secured against vandalism outside of working hours.
- 29.7 No batching plant is permitted on the site.
- 29.8 A copy of the approved and certified plans, specifications and documentation shall be kept on site at all times and shall be available for perusal by any officer of Council.
- 29.9 Any contractor(s) must meet all workplace safety legislation and requirements.
- 29.10 No vehicle maintenance is permitted in the demolition and construction areas except in emergencies.
- 29.11 Any loose material stockpiles are to be stored within the temporary construction compound(s) and are to be protected from possible erosion.

30. Erosion and Sediment Control

- 30.1 Disturbance of sediment during the construction phase of the development and the design management and implementation of pollution controls must be consistent with "Managing Urban Stormwater: Soils and Construction" (NSW Landcom, 2004), (Blue Book), and "approved Methods for the Modelling and Assessment of air pollutants in NSW (EPA)".to ensure containment of sediment to the immediate work site.
- 30.2 All sediment control measures must be regularly inspected and cleaned out and/or repaired as necessary, and all collected silt disposed of appropriately. Stockpiles should also have adequate sediment control measures in place.
- 30.3 Erosion and control measures are not to be removed until disturbed areas have stabilised.

31. Air Quality and Dust Management

- 31.1 Spraying of paint and other materials with the potential to become air borne particulates is only to be undertaken on days with still or light wind conditions.
- 31.2 No burning of materials is permitted.
- 31.3 Dust generated during construction activities is to be controlled to avoid impact on surrounding properties
- 31.4 All necessary maintenance for construction vehicles and equipment is to be undertaken during the construction period.
- 31.5 Excessive use of vehicles and powered construction equipment is to be avoided.
- 31.6 Exposed areas are to be progressively revegetated as soon as practical.
- 31.7 Vehicle wash down areas are to be established to ensure all mud and soil from construction vehicles is not carried onto public roads.
- 31.8 All vehicles involved in any excavation and/or demolition and departing the site with demolition materials, spoil or loose matter must have their loads fully covered before entering the public roadway.
- 31.9 Vehicles, machinery and equipment will be maintained in accordance with manufacturer's specifications in order to meet the requirements of the Protection of the Environment Operations Act 1997 and associated regulations.

32. Construction

- 32.1 No blasting shall be permitted during construction.
- 32.2 The use of any rock excavation machinery or any mechanical pile drivers or the like is restricted to the hours of 7.00am to 5.00pm (maximum) on Monday to Friday only, to minimise the noise levels during construction and loss of amenity to the surrounding area.

33. Services

- 33.1 All services and utilities in the area of construction must be appropriately disconnected and reconnected as required. The contractor is required (if necessary) to consult with the various service authorities regarding their requirements for the disconnection of services.
- 33.2 Where services are found not to be adequate to support the development they shall be appropriately augmented.

34. Traffic Management

Existing traffic access and arrangements should be maintained during construction as much as practicable.

35. Contamination (Unexpected Finds)

- 35.1 Should any new soil contamination information or contaminants be identified during the undertaking of works which have the potential to alter previous conclusions about site contamination, then the Managing Contractor and HI must be immediately notified and works must cease in the location of the contamination.
- 35.2 Works must not recommence until a suitably qualified contaminated land specialist (i.e. a Certified Environmental Practitioner) has investigated and assessed the category of the contamination in accordance with SEPP (Resilience & Hazards) 2021 and if required prepared a Remediation Action Plan (RAP) which details the necessary remedial work or management required to render the site suitable for the proposed development.
- 35.3 Following completion of the remediation, a Site Remediation & Validation Report (SRVR) which documents the completeness of the remedial work is to be submitted to HI and the EPA, if required.
- 35.4 Any contaminated materials or hazardous substances that need to be removed from site are to be classified first and then stored, transported and disposed of in accordance with EPA requirements at an EPA licensed waste facility.
- 35.5 Asbestos removal and management in NSW is regulated under the Work Health and Safety Act 2011 and Work Health and Safety Regulation 2017. The handling of asbestos work must be carried out in accordance with Safework Australia Code of Practice "How to Manage and Control Asbestos in the Workplace" February 2016, including being undertaken by contractors who hold a current Safework Asbestos or Demolition Licence and any other current Safework Licence required
- 35.6 If soils are to be disposed offsite during construction, they are required to be disposed in accordance with the waste classification, subject to additional sampling and analysis.
- 35.7 Construction works should not result in the contamination of the site.
- 35.8 A spill containment kit will be available at all times. All personnel will be made aware of the location of the kit and trained in its effective deployment.
- 35.9 The contractor shall develop a procedure for the management of acid sulfate material (ASM) including identification, testing and treatment of ASM encountered during the works and opportunities for reuse of treated ASM within the site.

- 35.10 Materials will be sourced from licensed quarries and operators. All materials will be certified uncontaminated and environmentally safe.

36. Noise and Vibration Management

- 36.1 All works will be in accordance with AS2436-1981: Guide to Noise Control on Construction, Maintenance and Demolition Sites.
- 36.2 Building contractors are to implement the requirements of the Office of Environment “Interim Construction Noise Guideline (July 2009)” as far as practicable.
- 36.3 Construction is to be carried out in accordance with the Building Code of Australia deemed-to-satisfy provisions with respect to noise transmission.
- 36.4 All reasonable, practicable steps are to be undertaken to reduce noise and vibration from the site.
- 36.5 Plant and equipment is to be maintained, checked and calibrated in accordance with the appropriate design requirements and to ensure that maximum sound power levels are not exceeded.
- 36.6 Plant and equipment (where possible) is to be strategically positioned on site to reduce the emission of noise from the site to the surrounding area, users of the site and on-site personnel.
- 36.7 Unnecessary noise is to be avoided when carrying out manual operations and operating plant.
- 36.8 Any equipment not used for extended periods is to be switched off.

37. Non Aboriginal Heritage

- 37.1 All personnel working on site will receive training in their responsibilities under the Heritage Act 1977.
- 37.2 If any item of European heritage is discovered during works, work shall cease immediately and the project heritage consultant, the relevant Council and/or Office of Environment and Heritage notified.
- 37.3 Work shall not recommence until the significance of the find is established.

38. Aboriginal Heritage

- 38.1 If suspected Aboriginal material has been uncovered as a result of development activities within the Project Area:
- work in the surrounding area is to stop immediately
 - a temporary fence is to be erected around the site, with a buffer zone of at least 10 metres around the known edge of the site
 - an appropriately qualified archaeological consultant is to be engaged to identify the material, and
 - if the material is found to be of Aboriginal origin, the Aboriginal community is to be consulted in a manner as outlined in the OEH guidelines: Aboriginal Cultural Heritage Consultation Requirements for Proponents (2010).
- 38.2 Should Human Remains will be located at any stage during earthworks within the Project Area, all works must halt in the immediate area to prevent any further impacts to the remains. The Site should be cordoned off and the remains themselves should be left untouched. The nearest police station, the relevant Local Aboriginal Land Council and the OEH Regional Office are all to be notified as soon as possible.
- 38.3 If Aboriginal cultural materials are uncovered as a result of development activities within the Project Area, they are to be registered as Sites in the Aboriginal Heritage Information Management System (AHIMS) managed by the OEH. Any management outcomes for the site will be included in the information provided to the AHIMS.

- 38.4 All effort must be taken to avoid any impacts on Aboriginal Cultural Heritage values at all stages during the development works. If impacts are unavoidable, mitigation measures should be negotiated between the Proponent, OEH and the Aboriginal community.

39. Restriction on Hours during Construction

- 39.1 The undertaking of any construction activity on the subject site is to be limited to the following hours:
- Monday to Friday inclusive: 7.00am to 6.00pm
 - Saturdays: 8.00am to 1.00pm
 - Sundays and Public Holidays: No work permitted.
- 39.2 Entry and departure of vehicles from the site will be restricted to the imposed work hours.
- 39.3 Activities may be undertaken outside of hours in condition 39.1 and 39.2 if required
- By the police or a public authority for the delivery of vehicles, plant or materials; or
 - in an emergency to avoid the loss of life, damage to property or to prevent environmental harm.
 - Where the works are inaudible at the nearest external sensitive receiver, a disruption notice has been issued by the relevant LHD or Hospital and a letter of support has been provided from the relevant LHD or Hospital for the Out of Hours Works.
- 39.4 Consideration will be given to extending these hours to allow for specific work tasks on a case by case basis, subject to approval from Health Infrastructure being sought prior to this occurring and the assessment of any impact of this extension.

40. Access and pedestrian movements

- 40.1 Safe pedestrian access and movement to the hospital and surrounding buildings shall remain unimpeded at all times.
- 40.2 Appropriate signage and directional information shall be provided.

Prior to commencement of operation

Note: The following Conditions are to be complied with prior to commencement of operation of the facility.

41. Works as Executed

Prior to use of the facility, "Works as Executed" drawings are to be submitted to HI.

42. Post-construction survey

- 42.1 Prior to the use of the facility, a post-construction survey report is to be prepared.
43. The post-construction survey should identify whether construction work has caused any damage to surrounding development (including Stone Wall no. 5) and, be provided to the Crown Certifier in the form of Post-Construction Survey Report.
- 43.1 Where the post-construction survey report identifies any damage or non-compliance as a result of construction activity, the Proponent must repair any damage caused by carrying out the works or resolve the non-compliance.

During Operation

Note: The following Conditions are to be complied with during operation of the facility.

44. Operational Noise

- 44.1 Noise generated from mechanical plant should be controlled to ensure external noise emissions are not intrusive and do not impact on the amenity of the sensitive receivers.
- 44.2 Noise from ambulance sirens will be limited where possible in accordance with NSW Ambulance Emergency Driving and Use of Warning Policy Directive 2016-033
- 44.3 Use of noisy power tools, including the pressure washer is required to be restricted to 7am and 8pm Monday to Friday, and between 8am and 8pm on Saturday, Sundays and Public Holidays.

45. Bushfire Management

Asset protection zones:

- 45.1 The ambulance station footprint will be managed as an *Inner Protection Area* (IPA) in accordance with *Planning for Bushfire Protection 2019* (PBP).
- 45.2 A 29 m *Asset Protection Zone* (APZ) will be managed to the north between proposed ambulance station footprint and the swamp forest bushfire hazard.

Services:

- 45.3 Water supply will be provided for the development in accordance with Section 5.3.3 of PBP.
- 45.4 Electrical and gas services will be provided for the development in accordance with Section 5.3.3 of PBP.

Advisory Notes

AN1 Project Compliance – Town Planning Approvals – Guide to Post Approval Management (Feb 2023)

Health Infrastructure (HI) is responsible for ensuring that the conditions of consent are complied with during the course of the delivery of the project. To ensure that HI is complying with its legal obligations, compliance with the requirements of HI's *Town Planning Approvals – Guide to Post Approval Management (Feb 2023)* is required.