



Suite 2, Level 1 33 Herbert Street ST LEONARDS NSW 2065

ST LEONARDS NSW 1590

T 02 9438 5098 F 02 9438 5398

www.acor.com.au

ENGINEERS

MANAGERS

INFRASTRUCTURE PLANNERS

DEVELOPMENT CONSULTANTS

# CIVIL AND STRUCTURAL ENGINEERING

# **Tender Issue**

HI22291 SWMHIP - Concord Hospital

Prepared for: Health Infrastructure NSW Document no: ACR-CIVSTR-RPT-005 Issue no: Rev B



**Confidential & Commercial in Confidence** 





#### Disclaimer

This Report has been prepared in accordance with the scope of services described in the agreement between ACOR Consultants Pty Ltd] and the Client. The Report relies upon data, surveys, measurements and results based on instructions from, and in consultation with, the Client. Except as otherwise stated, ACOR Consultants Pty Ltd has not attempted to verify the accuracy or completeness of any information provided by the Client. If the information is subsequently determined to be false, inaccurate or incomplete then it is possible that changes may be required to the Report. Changes in circumstances or facts, the passage of time, manifestation of latent conditions or impacts of future events may also impact on the accuracy, completeness or currency of the information or material set out in this Report. This Report has been prepared solely for use by the Client, ACOR Consultants Pty Ltd] accepts no responsibility for its use by any third parties without the specific authorisation of ACOR Consultants Pty Ltd. ACOR Consultants Pty Ltd reserves the right to alter, amend, discontinue, vary or otherwise change any information, material or service at any time without subsequent notification. All access to, or use of, the information or material is at the user's risk and ACOR Consultants Pty Ltd accepts no responsibility for the results of any actions taken on the basis of information or material provided, nor for its accuracy, completeness or currency. For the reasons outlined above, however, no other warranty or guarantee, whether expressed or implied, is made as to the data, observations and findings expressed in this Report, to the extent permitted by law.

#### Revisions

Revision	Description	ion Date Prep		Approved by	Signature
F	Tender Issue	09.10.2023	Z. Pitt	T. Bosman	

#### COPYRIGHT

This document, including the concepts and information contained within it, are the property of ACOR Consultants Pty Ltd or any of its related or associated entities. Use or copying of this document in whole or in part without the written permission of ACOR Consultants Pty Ltd constitutes an infringement of copyright. No part of this document may be copied, reproduced, adapted, transmitted or stored in a retrieval system in any form or by any means without written permission or unless otherwise permitted under the Copyright Act 1968. Removal or modification of any copyright or other proprietary protection from this document will be a breach of copyright.

© ACOR Consultants Pty Limited

All intellectual property and copyright reserved.



# **Table of Contents**

1	Executi	ve Summary4
	1.1	Civil Engineering4
	1.2	Structural Engineering4
2	Introduc	ction5
	2.1	Project Scope5
3	Existing	Site Conditions6
	3.1	Existing Site Overview6
	3.2	Geotechnical Investigation & Site Geology7
	3.3	Site Survey, Grading and Topography10
	3.4	Existing Stormwater Drainage10
	3.5	Existing Easements and Constraints12
	3.6	Soil Contamination13
	3.7	Acid Sulphate Soils13
	3.8	Existing Site Access13
	3.9	In ground Infrastructure13
	3.10	Functionality of the Existing Facilities13
	3.11	Top Risks14
4	Develop	oment Design and Requirements14
	4.1	Development Overview14
	4.2	Civil Engineering15
	4.3	Stormwater Drainage Design15
	4.4	Structural Engineering19

# Appendices

Appendix A - Survey	25
Appendix B - Civil 100% Design Development	26
Appendix C - Structural 100% Design Development	27
Appendix D - El Australia – Report Ref No E25996.G03	28



# **1 Executive Summary**

ACOR Consultants Pty Ltd, in the capacity of the project Civil and Structural Engineering Consultants for tender issue, has reviewed and analysed the environmental and functional requirements as well as performance standards to be met by the civil and structural design elements for the new Concord Hospital Forensic Mental Health Unit.

Concord Hospital is located on Hospital Road, Concord, within the Canada Bay LGA. The site is bounded by Nullawarra Avenue to the west and Yaralla Bay to the south and east. The new Forensic Unit will be located within the Concord Centre for Mental Health, in between building 28 and building 109 & 110. The site is approximately 0.4 ha, of which the main building occupies approximately half of the area and is located to the east of the site. A new driveway and road are to be built to the north and east portion of the site.

There is an existing building and car park in the middle of the site. These are to be demolished in order to build the new mental health unit and road.

# 1.1 Civil Engineering

The main entrance to the site is located through the existing internal road to the north of the site with a driveway access provided at the west of the site, which will be shared by logistics, ambulances, and the general public. The driveway grades down to the south and crosses an existing footpath. The surrounding existing hospital roads are also required to remain operational during the construction of the new buildings.

The Concord Hospital site has not been identified to be within a Flood Planning Area as assessed by the Canada Bay LGA and as such is considered not to be flood effected.

The new forensic health building is intended to be drained via a conventional roof drainage system connecting to a new inground pit and pipe network which is to discharge into the existing Council drainage system. The onsite in-ground drainage will be sized for the 20-year ARI storm event with overland flow paths designed to convey flows up to 100-year ARI storm event.

Under the Canada Bay DCP Engineering Specifications, the site has an exemption from providing on-site detention. The new development will discharge to the existing stormwater system which discharges directly to Parramatta River which is tide affected.

Stormwater discharging from the site at each of the discharge point will include Water Sensitive Urban Drainage (WSUD) measures, with a treatment train consisting of a gross pollutant trap (GPT) plus a proprietary tertiary treatment filter device. The treatment train at each discharge point will be designed to meet the stormwater quality targets outlined in the DCP. More stringent requirements may need to be considered to address the ESD goals for the project.

# 1.2 Structural Engineering

Column and core foundations will be piled to the underlying weathered rock (shale), with pile caps provided as required. To minimise excavation into contaminated fill, the ground floor slab will be designed as a suspended slab on ground supported by CFA piers to shale.

For tender issue we have adopted a PT slab as an economic form of construction as part of the whole of life analysis. A structural grid which does not exceed approximately 8m has been adopted to allow an efficient flat slab system to be utilised. In situ concrete or precast stair and lift cores have also been adopted.

The roof structure is to be of lightweight construction. The roof support is designed to correspond with the typical Type A grid arrangement to enable flexibility. An alternative cost-effective solution is to utilise light gauge steel trusses supported on steel stud load bearing walls should flexibility not be necessary.



# 2 Introduction

# 2.1 Project Scope

Concord Repatriation General Hospital (hereafter referred to as Concord Hospital) is a major hospital in Sydney, located within the Canada Bay Local Government Area (LGA).

In the 2018-19 NSW budget the NSW Government announced a \$700m funding commitment to develop a Statewide Mental Health Infrastructure Program. The project announcement includes a new 42 bed Forensic Unit at Concord Hospital.

ACOR Consultants have been engaged by Health Infrastructure NSW as the Structural and Civil engineering consultants. This report has been prepared to outline the existing site conditions and the Civil and Structural engineering requirements applicable for the schematic design of the project.

The report will focus solely on the new Forensic Unit at Concord Hospital. Opportunities and constraints for this project have been reviewed and outlined with respect to the civil and structural engineering scope. Key design requirements and risks have also been highlighted for consideration.



# 3 Existing Site Conditions

### 3.1 Existing Site Overview

Concord Hospital is located on Hospital Road, Concord, within the Canada Bay LGA. The site is bounded by Nullawarra Avenue to the west and Yaralla Bay to the south and east. The new Forensic Unit will be located within the Concord Centre for Mental Health, in between building 28 and building 109 & 110. An existing site plan is provided in Figure 2.1 below, with the new development area highlighted in red.

The site is currently occupied by a 1 storey fibro and brick building (building 29) and an on-ground car park. The site slopes down to the south where it meets Yaralla Bay.



Figure 2.1 - Existing site plan (Source: Google Maps).



# 3.2 Geotechnical Investigation & Site Geology

A site-specific investigation was carried out by EI Australia Pty Ltd in August 2023 – report ref no E25996.G03. A copy of this report is provided in Appendix D. A plan view highlighting the location of boreholes is shown below in figure 2.2.



Figure 2.2: Coffey Bore Hole Locations

Results from all the borehole tests indicate that weathered sandstone is at depth varying between 1.5-2.5m. This rock is overlaid by fill and clay. Two of the borehole results are shown in figures 2.3 and 2,4 respectively. All remaining results of the borehole tests are shown in the Geotech report in appendix D.





# **BOREHOLE LOG**

# BH ID: BH1M

Loca	tion	1H Hospital Road, Co	oncore	d Wes	st, NSV	/	S	itarted	2	4 May	2023	
Clier	nt	Lipman Pty Ltd					c	omplete	d 2	4 May	2023	
Job	No.	E25996.G03					L	ogged B	y Ji	С	Date	24 May 2023
Shee	ets	1 of 2					R	Review B	y N	4L	Date	08 August 2023
Drill	ing Co	ontractor Geosense	e Drill	ing Er	nginee	rs	Surface RL - N	orthing	6	25446	60.6730 (MG/	\ 2020 Zone 56)
Plan	t	Comacch	io Ge	o 205	5		Inclination 90° E	asting	3	23863	.8164 (MGA	2020 Zone 56)
METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (m AHD)	MATERIAL DESCRIPTION		MOISTURE	CONSISTENCY / REL. DENSITY	MA & C	TERIAL ORIGIN IBSERVATIONS
	ľ.			0.00	10.00	-	ASPHALT: 100mm thick		-	-	ASPHALT	
		BH1M_0.50-0.95		0.10			FILL: Sity SAND: tine to medium grained, dark brown with angular to sub-rounded gravels, appears well compacted.	h sub-	D	8	FILL	
	10:00 AM	8,15,30 N=45	Q	0.60			Silty CLAY: low to medium plasticity, pale grey-orange	20. 20.	M < PL	н	RESIDUAL S	DIL
AD/T	5/2023 7:-	BH1M_1.50-1.65 SPT 1.50-1.65										
	A 7/2	18/150 mm HB N=R		2=			SANDSTONE: the to medium grained, pale gray-orange, extremely weathered.	6		~	WEATHERED	ROCK
		6		3.00			Log continued on next page.					

Figure 2.3: Borehole BH1M





# **BOREHOLE LOG**

# BH ID: BH4

Loca	tion	1H Hospital Road, Cor	cord \	Nes	t, NSV	V		Started	2	3 May	2023	
Clie	nt	Lipman Pty Ltd						Complete	ed 2	3 May	2023	
Job	No.	E25996.G03						Logged B	y Jo	0	Date	23 May 2023
She	ets	1 of 2						<b>Review B</b>	y N	1L	Date	08 August 2023
Drill	ing Co	ontractor Geosense	Drillin	g En	nginee	rs	Surface RL -	Northing	6	25441	6.9818 (MG	A 2020 Zone 56)
Plan	nt	Comacchie	Geo	205			Inclination 90°	Easting	3	23885	.7601 (MGA	2020 Zone 56)
METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (m AHD)	MATERIAL DESCRIPTION		MOISTURE	CONSISTENCY / REL. DENSITY	MA & (	TERIAL ORIGIN DBSERVATIONS
		BH4_0.50-0.95 SPT 0.50-0.95 8,6,12 N=18	c	0.00			FILL: Sitty SAND: fine to medium grained, dark brown angular to sub-rounded gravels, appears well compact Sitty CLAY: low to medium plasticity, pale grey-orange	trace sub- ed.	D		FILL RESIDUAL S	OIL
AD/T	GWNE	BH4_1.50-1.85 SPT 1.50-1.85 14,16,3/50 mm HB N=R		1					M < PL	VSt		
				85-			SANDSTONE: fine to medium grained, pale grey-oran extremely weathered.	ge		22	WEATHERED	) ROCK
	$\vdash$		2	.70			Log continued on next page.					

Figure 2.4: Borehole BH4M



# 3.3 Site Survey, Grading and Topography

A detailed topographical site survey and inground services survey has been undertaken by LTS. This has been used to inform the schematic design. Refer to Appendix A for site survey.

Name:	Concord Hospital
Contact Details:	LTS Tenancy 2, Level 6/205 Pacific Hwy, St Leonards NSW 2065
Job Reference:	33907 020DT
Date of Survey:	15/08/2022

The Campus is located on a peninsular in the Parramatta River with Yallah Bay to the Southeast. The campus is highly developed with buildings ranging in ages and construction form. The location for the Forensic Unit is in the centre of the campus within the mental health precinct. The site slopes to the southeast and is near the foreshore nature reserve. The site location is greater than 40m from the Mean High Water line.

# 3.4 Existing Stormwater Drainage

The site's current inground stormwater system connects to the Campus network. There are two main drainage lines to the North and South of the site. These pipes discharge into Yaralla Bay via headwalls as shown in figures 2.6 and 2.7.



Figure 2.6: Headwall into Yaralla Bay





Figure 2.7: Discharge Pipe into Yaralla Bay

A layout of the existing stormwater system is shown below in figure 2.8. This is based off site observations and should be confirmed with existing stormwater drawings.



Figure 2.8 – Existing Stormwater System



# 3.5 Existing Easements and Constraints

The LTS survey drawing indicates that the site is burdened by a number of easements. In particular there is an easement for access placed over the existing roads within the site. The easements for access have been highlighted in figure 2.9, and the easements for electrical inground infrastructure have been highlighted in figure 2.10 below.



Figure 2.9: Easements for Access, LTS Survey



Figure 2.10: Easements for Electrical Inground Infrastructure, LTS Survey



# 3.6 Soil Contamination

Soil samples from site were collected and tested in the lab as part of the Geotech investigation by EI Australia. The results from these tests indicate that no contaminants of concern were reported at concentrations above the adopted health-based criteria. Asbestos was also not detected in any of the fill samples collected from each of the investigated locations.

# 3.7 Acid Sulphate Soils

The 1:25,000 Prospect/Parramatta River Acid Sulfate Soil (ASS) Risk Map indicates that there is no know occurrence of acid sulfate soil where the site is to be located, as per figure 2.11 below.



Figure 2.11: Acid Sulfate Map

# 3.8 Existing Site Access

Access to the site is through Gate 3 and Helipad Road, with some possible secondary access via the internal hospital roads. The intersection and internal road performance will need to be confirmed with the traffic consultant particularly how construction vehicles are to be manoeuvred and materials delivered and stored.

# 3.9 In ground Infrastructure

The site is surrounded and traversed by infrastructure which services the Campus, as outlined in the LTS survey. These items will need to be protected or relocated. In particular, the site is crossed by Ausgrid HV and LV cables linking substations 2 and 3. There is also campus water and medical gas which are within the site.

# 3.10 Functionality of the Existing Facilities

Building 28 is to be retained and the design will need to preserve access to the existing loading dock during construction and in the final design.



### 3.11 Top Risks

- 1. <u>Inground services crossing site:</u> Major services cross the site (HV/LV in particular). There is a risk to the program and approvals if a strategy to divert or protect is not developed.
- 2. <u>Construction vibrations cause damage to existing buildings</u>: From our experience in the location area, we are aware that the excavation into rock can cause damage to the existing buildings. If this is not considered in the design, there is a risk of unexpected costs and delays during construction. Vibration monitoring and mitigation is recommending during construction to limit vibration to building 28. To be confirmed by geotechnical engineer.
- 3. <u>New services clash with existing</u>: If the existing services are not identified and co-ordinated with new services and new diversion such as HV lines and gravity services, major delays could arise.
- 4. <u>Existing foundations and inground structure</u>: There have been significant structures occupying the site in the past (including a current building that is to be demolished). There is a risk that the substructures remain buried causing cost over runs.
- 5. <u>Unexpected contamination encountered</u>: Unexpected contamination can cause cost over runs and delays. No contaminates were found in the samples tests by EI Australia, however there is a possibility that contaminates may be buried on other locations on site.

# 4 Development Design and Requirements

### 4.1 Development Overview

The development is intended to sit on the western side of the existing access road. This will help to enable the continued operation of the surrounding buildings during the construction of the new Forensic Unit building. At the completion of the works, new vehicle access and pedestrian access will be available surrounding the Forensic Unit building. The new Forensic Unit development site plan is shown below in Figure 3.1 below.



Figure 3.1 – Site Plan Prepared by NBRS Architecture



# 4.2 Civil Engineering

#### 4.2.1 Design standards

The following list indicates the relevant infrastructure design guides and standards to be considered through the Civil Engineering design:

- Austroads: Guide to Road Design
- Austroads: Guide to Pavement Technology
- Austroads: Guide to Traffic Engineering Practice Parts 1 14
- Austroads: Guide to the Geometric Design of Urban Roads
- AS1428.1 Design for Access & Mobility
- AS2890.1 Parking Facilities: Off-street car parking
- AS2890.2 Parking Facilities: Off-street commercial parking
- AS2890.5 Parking Facilities: On-street parking
- AS2890.6 Parking Facilities: Off-street for people with disabilities
- AS3798 Guidelines on Earthworks for Commercial and Residential Developments
- Canada Bay Council Development Control
- Health Infrastructure Guidance Notes

### 4.2.2 Site Access, Roads and Grading

The main entrance to the site is intended through the existing internal road to the north of the site with a driveway access provided at the west of the site, which will be shared by logistics, ambulances, and the general public. The driveway grades down to the south and crosses an existing footpath. The surrounding existing hospital roads are also required to remain operational during the construction of the new buildings.

Consideration has been given to the existing external road levels, where vehicular and pedestrian access points are intended, to allow for the extent of ramping required for access between existing road levels and new building floor levels. Similarly, the FFL has been raised to 8.00 to accommodate the surrounding natural ground levels.

All access roads are being designed in accordance with Australian Standards for parking and road designs as stated in section 4.2.1. Access roads within the site will typically grade between 1% and 10% longitudinal fall and will be designed to prevent scraping on the underside of vehicles including ambulances and trucks.

Cross fall for road lanes are generally between 2-3% to prevent ponding water and allow it to drain away to the kerbs for collection by the inground stormwater drainage.

The extent of new driveway and paving is shown in appendix B. Currently the driveway design has been narrowed at the entry to accommodate the substation clearance zone. This has been reviewed and approved by the traffic consultant.

Due regard needs to be given to accessibility requirements to ensure that equitable access is provided into and around the site to comply with AS1428.1 requirements.

# 4.3 Stormwater Drainage Design

The following list indicates the relevant infrastructure design guides and standards considered through the Stormwater design. The stormwater design, including new stormwater pipes and stormwater kerb inlet pits are shown in appendix B.



- Australian Rainfall and Runoff (2019) with AR&R (2016) rainfall datasets sourced from BoM
- AS3500.3:2018 Plumbing and Drainage Part 3: Stormwater Drainage
- Bureau of Meteorology IFD data sourced from http://www.bom.gov.au
- Austroads: Guide to Road Design, Part 5 Drainage Design 2008
- Managing Urban Stormwater: Soils and Construction, "The Blue Book" 4th edition 2004
- Canada Bay Development Control Plan

#### 4.3.1 Stormwater Quantity

Stormwater drainage design is to be in accordance with Canada Bay Council design criteria. Stormwater drainage network is generally to be designed for the 5% AEP (20-year ARI) storm event.

Under the Canada Bay DCP Engineering Specifications, the site has an exemption from providing on-site detention. *"Exemptions - OSD will be applied to the developments types as listed in the table under the Section Controls. Exemption from OSD would only apply in the following situations: ... The runoff from the development is directly discharged into one of the bays or waterways and does not pass through any public drainage system"* The new development will discharge to the existing stormwater system which discharges directly to Parramatta River which is tide affected. A pollutant trap system, as outlined in section 3.3.2 will be implemented during construction.

To avoid adversely affecting the existing campus system, it is intended that the post development flows be maintained at or below the current predevelopment conditions. Ideally this will be provided through the provision of landscaped areas however if the areas of permeable surfaces are reduced then a provision of a small detention tank will be considered.

Typically, in-ground pit and pipe systems will be designed to capture and convey all runoff for up to and including a 20-year ARI storm event. Overland flow paths will be designed to convey flows from all storms above a 20-year ARI event up to and including the 100-year ARI storm event. The IFD data extracted from the Bureau of Meteorology's IFD tool for the Concord Hospital Site is presented in the Table below and will be used for future design development.

Storm Duration	5-year ARI (mm/hr)	20-year ARI (mm/hr)	100-year ARI (mm/hr)
5 min	132	172	220
1 hour	37.8	49.2	62.7
12 hour	8.45	11.5	15.5

# 4.3.2 Stormwater Quality

Stormwater discharging from the site at each of the discharge point will include Water Sensitive Urban Drainage (WSUD) measures, with a treatment train consisting of a gross pollutant trap (GPT) plus a proprietary tertiary treatment filter device. Other measures which can be considered include vegetated swales, buffer strips and bioretention systems, however these may be difficult to implement due to the constrained nature of the site.

The treatment train at each discharge point will be designed to meet the stormwater quality targets outlined in the DCP. More stringent requirements may need to be considered to address the ESD goals for the project. A stormwater quality strategy will be implemented both during construction and post construction.



# 4.3.3 Flooding

It is not expected that any flood controls will be placed on the development at the Concord Hospital site as the hospital is not identified as subject to regional flooding as shown in figure 3.2 below.



Figure 3.2 – Flooding Planning Area Map (source: NSW ePlanning Spatial Viewer)

Overland flow will occur in significant rainfall events as the existing system is unlikely to have the capacity to convey flows from major storm events.

The Canada Bay DCP specifies the following freeboard requirements:



Freeboard requirements :	above 1% AEP water surface lev	vel		
	Maximum Water Level in (A)			
Finished Floor Level (B)	Adopted Flood planning area	Overland flow path identified by Council as "Minor"	Overland flow paths other than ones identified by Council as "Minor	Mainstream flooding
Residential – Habitable rooms	As per the adopted Plan	300mm	500mm	500mm
Residential – Non- habitable rooms	As per the adopted Plan	300mm	300mm	500mm
Commercial or Industrial – All internal areas	As per the adopted Plan	300mm	500mm	500mm
Carport open on 3 or 4 sides (At Ground Level)	As per the adopted Plan	150mm*	150mm	300mm
Entrance to Basement	As per the adopted Plan	300mm*	Difference between the 100-yr ARI Level and the PMF Level	Difference between the 100-yr ARI Level and the PMF Level
Critical Infrastructure	As per the adopted Plan	300mm	Difference between the 100-yr ARI Level and the PMF Level	Difference between the 100-yr ARI Level and the PMF Level

For planning purposes we recommend that a minimum freeboard of 500mm be provided to any overland flow paths. For schematic design it should be assumed that the top of kerbs are the 1% AEP overland flow level.



# 4.4 Structural Engineering

#### 4.4.1 Design standards

The structural design shall be in accordance with the latest revision of all relevant structural Australian Standards, relevant structural sections of the BCA and other statutory requirements.

In particular, the structural design will be in accordance with the following relevant Australian Standards and Guidelines:

- AS/NZS 1170.0 (2002) Structural Design Actions Part 0 General Principles
- AS/NZS 1170.1 (2002) Structural Design Actions Part 1 Permanent, Imposed and Other Actions
- AS/NZS 1170.2 (2011) Structural Design Actions Part 2 Wind Loads
- AS 1170.4 (2007) Structural Design Actions Part 4 Earthquake Actions in Australia
- AS 2159 (2009) Piling Design and Installation
- AS 3600 (2018) Concrete Structures
- AS 3700 (2018) Masonry Code
- AS 4100(2020) Steel Structures

- AS 4678 (2002) Earth Retaining Structures
- Health Infrastructure Guidance Notes

#### 4.4.2 Structural Design Elements

#### 4.4.2.1 Foundations

The building is to be no more than three stories in height, and the structure will be founded on weathered sandstone as per advice from Geotech report prepared by El Australia. For tender issue, we propose to use 600mm and 450mm diameter piles. The foundation parameters outlined in the report are shown below in figure 3.2.

Rock Class	Serviceability End Bearing Pressure (kPa) <sup>3</sup>	Ultimate Shaft Adhesion - Compression (kPa) <sup>2</sup>		
Class V Sandstone	700	100		
Class IV Sandstone	2000	500		
Class III Sandstone	4000	1000		

#### Figure 3.3: Foundation Parameters from EI Australia Report

To minimise site excavation, the ground floor slab will be designed as a suspended slab on ground supported by bored piers to the underlying rock.

#### 4.4.2.2 Superstructure

The superstructure is type A construction as it is maximum 3 stories. For the tender issue we have adopted a PT slab as an economic form of construction as part of the whole of life analysis in section 4.4.3. A structural grid which does not exceed approximately 8m has been adopted to allow an efficient flat slab system to be utilised. In situ concrete or precast stair and lift cores have also been adopted.

The design aims to align columns through the building to avoid structural transfers. The tender issue drawings are shown in Appendix C which indicate the location of columns. There are a number of columns which do not align due to the architectural wall arrangement, and as such, transfer beams have been designed to support



these columns. It has been confirmed that the fire water storage tank will be located on the western wing of L2. This has resulted in an uplift in structure to account for the additional loads.

A concrete slab has been designed to support the roof plant equipment. All other roof structure is to be of lightweight construction. The roof support corresponds with the typical Type A grid arrangement to enable flexibility. An alternative cost-effective solution is to utilise light gauge steel trusses supported on steel stud load bearing walls should flexibility not be necessary.

### 4.4.3 Whole of Life Analysis

By adopting a PT slab the slab thicknesses were reduced. Below is a summary of total concrete savings.

#### Level 1

	РТ	R.C.
Reinforcement (tonnes)	30	55
PT (tones)	2.2	N/A
Concrete (tonnes)	915	1100

#### Level 2

	РТ	R.C.
Reinforcement (tonnes)	27	50
PT (tones)	2	N/A
Concrete (tonnes)	815	980

### 4.4.4 Structural loads and design parameters

The following design loads and parameters will be applicable for the future development and will be used during the design phase of the structural elements.

# 4.4.5 Floor Loads

#### Table 3.2 – Floor Loads

Floor Type	Uniform Imposed Load (kPa)	Imposed Point Load (kN)	Ceilings, Services Load, Partitions, Floor Finished (kPa)	
Corridors, circulation areas, foyers and stairs	4.0	4.5	1.3	
Balcony/terrace	4.0	1.8	2.5	
Garden/landscape	0.5	1.4	8.0	



General floor areas	3.0	2.7	1.8
Plant rooms	7.5	4.5	2.4
Roof (non-accessible)	0.25	1.4	0.5
Roof (accessible)	3.0	2.7	1.0
PV	0.0	1.4	0.15
Fire Storage Tank	0.0	1.4	25

# 4.4.6 Floor Vibration

The Footfall response will be checked in accordance with the Concrete Centre Design Guide, with a further check based on the recommendations made within and Murray, Allen and Ungar in the AISC, 2003.

The footfall frequencies and corresponding response factors defined within the NSW Health Design Guidance Note No.1 which the different floor areas will be checked for compliance with the Concrete Centre Design Guide are given in table 3 below.

#### Table 1.3 - Footfall Response Factor Design Parameters – Concrete Centre Method

Facility/Equipment/Use	Design Response Factor	Footfall Frequency (Hz)	
Generally	4	2.5	

# 4.4.7 Earthquake Load Parameters

#### Table 3.4 – Earthquake Load Parameters

Item	Value		
Importance Level	2		
Probability Factor, Kp	1.0		
Hazard Factor, Z	0.08		
Sub-Soil Class	Be		
Earthquake Design Category	11		
Structural Ductility Factor, µ	1		
Structural Performance Factor, Sp	0.77		

### 4.4.8 Wind Load Parameters

### Table 3.5 – Wind Load Parameters

Item	Value
Location	Region A2
Importance Level	2
Vu	45m/s
Vs	37m/s
Ms	1.0



Mt	1.0
Md	1.0 (West)
Terrain Category	Varies

# Table 3.6 – Wind Site Speeds (ULS)

Direction	Site Speed (m/s)
North	37.11
Northeast	36.01
East	41.92
Southeast	42.32
South	44.64
Southwest	36.51
West	39.98
North West	46.46





Figure 3.3 – Site Terrain Category Factor (Source: CheckWind)

# 4.4.9 Fire Rating

# Table 3.6 – Fire Ratings

Building Element	FRL
External Walls (Load Bearing)	120/60/30
External Columns	120/-/-
Load Bearing Fire Walls	120/120/120
Shafts (Non-load Bearing)	-/-/-
Other Load Bearing Walls, Beams, Trusses, Columns	120/-/-
Floors	120/120/120



The architect proposed to reduce the column thickness to 200mm, however to achieve ire rating, the thickness of these columns was increased to minimum 250mm.

#### 4.4.10 Waterproofing of concrete slabs

The schematic design allows for concrete slabs to act as roof structures at the eastern wings. The following principles may be adopted to limit the risk of roof leakage:

#### 1. Non trafficable roofs

Either

- Construct a metal deck roof over the concrete slab to provide weather tightness.
- Rainwater is collected in eaves gutters.

Or

Provide a waterproof membrane adequately protected from damage and designed as per the requirements of a trafficable roof below. SLHD to advise in the next stage of design.

#### 2. Courtyards and trafficable roofs

- Slabs are to be post tensioned to achieve a prestress after losses greater than 2.0 MPa.
- Slab curing is to be specified and monitored.
- Construction joints are to be avoided through these areas.
- Slabs are to fall to drainage points at grades no shallower than 1 in 80.
- Hobs are to be cast integrally with the slab.
- Warranted waterproof membranes are to be installed over the concrete slab.
- The site staff constructing the roof slabs are to be made aware of these prior to construction.



# Appendix A - Survey



BENCH MARK	
INSPECTION PIT	OIP
PIT WITH CONCRETE LID	
PIT WITH METAL LID	🗆 MI
COMMS PIT	<b>—</b> ((
ELECTRICITY PIT	🗖 EP
POWER POLE	e Pf
ELECTRIC LIGHT BOLLARD	🜓 LE
ELECTRIC LIGHT POLE	🜓 EL
SEWER MANHOLE	AS 🚫
SEWER INSPECTION POINT	O SI
GIPD DRAIN	
GIPD DRAIN	🥏 G[
GIPD INLET PIT	🔲 GI
DOWNPIPE	o DF



н	00/00/00	-
G	00/00/00	-
F	00/00/00	-
Е	00/00/00	-
Revision	Date	Description

 00	D	00/00/00	-	00		
 00	C	00/00/00	-	00		DATED:
 00	В	00/00/00	•	00		
00	Α	00/00/00		00	CONFIDENCE TOGETHER	
Reference	Revision	Date	Description	Reference	www.ltsl.com.au P 1300 587 000	Registered Surveyor NSW



site Area PLAN OF DETAIL AND LEVELS OVER PART LOT 20 IN 1:500 @A1 15/08/2022 N/A DP1139098 KNOWN AS CONCORD HOSPITAL, CONCORD IGA SHEET WEST CANADA BAY OF 11









E00/00/00RevisionDate

Description

SCALE 1: 100 @ A1

 00	D	00/00/00	-	00		Clie
00		00/00/00		00		
00	С	00/00/00	•	00		
00	В	00/00/00	•	00		PLA
00	Α	00/00/00	•	00		DP
Reference	Revision	Date	Description	Reference	www.ltsl.com.au P 1300 587 000 Registered Surveyor NSW	WE

	datum AHD	referer numbe	nce 33	3907 020DT
DETAIL AND LEVELS OVER PART LOT 20 IN	site Area N/A	scale 1:100	@A1	date of survey 15/08/2022
98 KNOWN AS CONCORD HOSPITAL, CONCORD	lga Canada bay		SHE	







vina title	7.110	nombo		
	site Area	scale		dat
N OF DETAIL AND LEVELS OVER PART LOT 20 IN	N/A	1.100	@A1	15
139098 KNOWN AS CONCORD HOSPITAL, CONCORD	IGA			ССТ
ST			211	



00	D	00/00/00	•	00		THIS IS THE PLAN REFERRED TO IN MY LETTER
00	С	00/00/00	-	00		DATED:
00	В	00/00/00	•	00		
00	Α	00/00/00	-	00	CONFIDENCE TOGETHER	
Reference	Revision	Date	Description	Reference	www.ftsl.com.au P 1300 587 000	Registered Surveyor NSW

1 STOREY BRICK BUILDING METAL ROOF 'MANNING BUILDING' 'BUILDING 109 & 110'



M.H.W.M

EALTH INFRASTRUCTURE	datum AHD	referen numbe	r <sup>ce</sup> 33	907 02	20DT
DETAIL AND LEVELS OVER PART LOT 20 IN	site Area N/A	scale 1:100	@A1	date of s 15/08/	urvey 2022
78 KNOWN AS CONCORD HOSPITAL, CONCORD	lga CANADA BAY		SHE OF 1	ET	9





# MANNING BUILDING & STREETSCAPE - BUILDING No. 109 & 110 WESTERN ELEVATION





Н	00/00/00 -		00	D	00/00/00	-	00		THIS IS THE PLAN REFERRED TO IN MY LETTER	Client - HEALTH INFRASTRUCTURE	datum AHD	referenc number	<sup>;e</sup> 33907	7 020D1
G	00/00/00 -		00	С	00/00/00	-	00		DATED:	Drawing fifle	site Area	scale	date	e of survey
F	00/00/00 -		00	В	00/00/00	-	00			PLAN OF DETAIL AND LEVELS OVER PART LOT 20 IN	N/A	1:100	@A1 15/	/08/2022
E	00/00/00 -		00	Α	00/00/00	-	00	CONFIDENCE TOGETHER		DP1139098 KNOWN AS CONCORD HOSPITAL, CONCORD	, LGA			
Revisio	on Date	Description	Reference	Revisio	n Date	Description	Reference	www.ltsl.com.au P 1300 587 000	Registered Surveyor NSW	WEST	CANADA BAY		OF 11	10

	PARAPET 17.65		P	ARAPET 17.56
OPE16.37 H15.78 D FL13.65	UNDERSIDE PARAPET 16.95 H16.37 W S14.85	H16.37 W S14.85		
STEPS OPE12.17 H11.54 D S <sup>N</sup> FL9.47	H12.16 W S10.65	H12.16 W S10.65	H11.82 D	UNDERSIDE BEAM 11.8

# ASBESTOS DISEASE RESEARCH INSTITUTE SOUTHERRN ELEVATION

# MANNING BUILDING & STREETSCAPE - BUILDING No. 109 & 110 WESTERN ELEVATION





# CONCORD MEDICAL EDUCATION CENTRE EASTERN ELEVATION



# **BUILDING No 28** SOUTHERN ELEVATION





∟ Revision	Date	- Description
E	00/00/00	
F	00/00/00	-
G	00/00/00	-
Н	00/00/00	-



# JARA WARD BUILDING No 112) EASTERN ELEVATION

# JARA WARD BUILDING No 111 + 112) NORTHERN ELEVATION

								datum	roforonoo	
00	D	00/00/00	-	00		TO IN MY LETTER		AHD	number 3390	J7 020DT
00	С	00/00/00	-	00		DATED:	Drawing title	site Area	scale do	ate of survey
00	В	00/00/00	•	00			PLAN OF DETAIL AND LEVELS OVER PART LOT 20 IN	N/A	1:100 @A1 1	5/08/2022
00	Α	00/00/00	-	00	CONFIDENCE TOGETHER		DP1139098 KNOWN AS CONCORD HOSPITAL, CONCORD	LGA	CUEET	
Reference	Revision	Date	Description	Reference	www.ltsl.com.au P 1300 587 000	Registered Surveyor NSW	WEST	CANADA BAY	OF 11	11

H10.00	H10.00	H10.00	H10.00		H10.00	¥.	
w	D	D	W		W	COLUN	
S8.20			S8.20	4-	S8.20		
				-+			Ь


# Appendix B - Civil 100% Design Development

# CONCORD FMH 109 HOSPITAL RD, CONCORD, NSW, 2139 CIVIL ENGINEERING SERVICES



	DRAWING INE
DWG No.	
221192_0001	COVER SHEET AND DRAW
221192_0111	ENABLING WORKS CONSTI
221192_0115	ENABLING WORKS DETAILS
221192_0116	ENABLING WORKS DETAILS
221192_0450	SEDIMENT AND EROSION (
221192_1000	SITE WORKS AND STORMV

LOCALITY PLAN NOT TO SCALE

)	COPYRIGHT of this design and plan is the	N
-	property of ACOR Consultants Pty Ltd, ACN	
	079 306 246 ABN 40 079 306 246, all rights	
	reserved. It must not be used, modified,	
	reproduced or copied wholly or in part without	
	written permission from ACOR Consultants Pty	
	Ltd.	



~	Description	n JE		Date 06.09.2023	Drawn MD	Арр
•				00.00.2020	MB	
.1 (	) 1m at	full size				1
1 ( Client	) 1m at	full size		 		ł
1 ( Client				RE	-	
Client	<u> </u>			RE	_	<u> </u>
1 Client	<u>1mat</u>			RE		ł
Client	<u>1mat</u> ■ ■ ▲LTH	INFRAS	TRUCTU	RE	_	<u>+</u>
Client HE	ALTH	INFRAS	TRUCTU	RE		<u> </u>
Client HE Architec	ALTH	INFRAS	TRUCTU	RE		<u>+</u>
I Client HE Architec	ALTH	INFRAS	TRUCTU	RE		
Client HE Architec NB	ALTH t RS n St,	INFRAS	TRUCTU	RE		+
Architec NBI 4 Gle Milson (02) 99	ALTH	INFRAS	TRUCTU	RE		<u>+</u>
Architec NBI 4 Gle Milsor (02) 99 Project	t RS n St, ns Point, 1 22 2344	INFRAS	STRUCTU	RE		
Architec NBI 4 Gle Milson (02) 99 Project CO	ALTH ALTH RS n St, ns Point, 1 22 2344	INFRAS	TRUCTU	RE		
Architec NBI 4 Gle Milson (02) 99 Project CO	ALTH ALTH RS n St, ns Point, I 222 2344 NCOI	INFRAS	TRUCTU	RE		
Architec NBI 4 Gle Milsor (02) 99 Project CO	ALTH ALTH T RS n St, ns Point, I 22 2344 NCOI	INFRAS	TRUCTU	RE		
Architec NBI 4 Gle Milson (02) 99 Project CO	ALTH	INFRAS		RE		
Architec Architec NBI 4 Gle Milsor (02) 99 Project CO 109 H Conc NSW	ALTH ALTH RS n St, ns Point, I 22 2344 NCOI lospital R ord, 2139	INFRAS		RE		
Architec Architec NBI 4 Gle Milson (02) 99 Project CO 109 H Conc NSW	ALTH ALTH TRS In St, Ins Point, I Ins Point, Ins Point, Ins Point, Ins Point, I Ins Point, I Ins Point, Ins P	INFRAS	ACOR Co Suite 2. Lev	RE nsultar	ts Pt	⊥ 
Architec Architec NBI 4 Gle Milson (02) 99 Project CO 109 F Conc NSW	ALTH ALTH RS n St, ns Point, I 22 2344 NCOI lospital R ord, 2139	INFRAS	STRUCTUR	RE nsultar vel 1, 33 H St Leonard	hts Pt Herbert	<b>y l</b> Str
Architec NBI 4 Gle Milsor (02) 99 Project CO 109 F Conc NSW	ALTH ALTH TRS In St, Ins Point, I Ins Point, Ins Point, I Ins Point, I Ins Point, Ins Point, I Ins Point, Ins Point, Ins Point, I Ins Point, Ins Point, Ins Point, I Ins Point	INFRAS	STRUCTUR	RE nsultar vel 1, 33 H St Leonard T +61	ts Pt Herbert ds NSV 1 2 943	↓ 
Architec NBI 4 Gle Milsor (02) 99 Project CO 109 F Conc NSW	ALTH	INFRAS	STRUCTUR	RE nsultar vel 1, 33 H St Leonard T +61	ts Pt Herbert ds NSV 1 2 943	↓ <b>y l</b> Str V 20 8 5 ()
Architec NBI 4 Gle Milsor (02) 99 Project COO 109 H Conc NSW	ALTH ALTH TRS In St, Ins Point, I ACOI ACOI ACOI ACOI ACOI ACOI ACOI ACO	INFRAS		RE nsultar vel 1, 33 F St Leonard T +67	nts Pt Herbert ds NSV 1 2 943	<b>y l</b> Str V 20 8 5
Architec NBI 4 Gle Milson (02) 99 Project COO 109 F Conc NSW	ALTH ALTH TRS In St, Ins Point, I MCOI Hospital R ord, 2139	INFRAS	ACOR Co Suite 2, Lev Suite 2, Lev	RE nsultar vel 1, 33 H St Leonard T +61	nts Pt Herbert ds NSV 1 2 943	<b>y I</b> Str 8 5
Architec Architec NBI 4 Gle Milson (02) 99 Project CON 109 F Conc NSW CON ENGINEE Drawing CON	ALTH ALTH T RS n St, ns Point, I 22 2344 NCOI dospital R ord, 2139 ACOR sultan ERS [MANAC Title VER SH	INFRAS	ACOR Co Suite 2, Lev Suite 2, Lev DRAWING	RE nsultar vel 1, 33 H St Leonard T +67	Tts Pt Herbert ds NSV 1 2 943	<b>y l</b> Str V 20 8 5
Architec NBI 4 Gle Milsor (02) 99 Project CO 109 F Conc NSW	ALTH ALTH TRS In St, Ins Point, I 22 2344 NCOI Hospital R ord, 2139 ACOI SULTAN ERS MANAG	INFRAS	ACOR Co Suite 2, Lev Suite 2, Lev DRAWING	RE nsultar vel 1, 33 H St Leonard T +67	Tts Pt Herbert ds NSV 1 2 943	<b>y L</b> Str V 20 8 51
Architec NBI 4 Gle Milsor (02) 99 Project CO 109 F Conc NSW	ALTH ALTH TRS In St, Ins Point, I ACOI Accord 2139 ACOI 2139 ACOI	INFRAS	ACOR Co Suite 2, Lev Suite 2, L	RE nsultar vel 1, 33 H St Leonard T +67	Tts Pt Herbert ds NSV 1 2 943	<b>y L</b> Str V 20 8 50 SULT
Client HE Architec NB Architec Architec NB Architec NB Architec NB Architec Architec NB Architec NB Architec Architec NB Architec Architec NB Architec Architec Architec NB Architec	ALTH ALTH TRS In St, Ins Point, I 22 2344 NCOI Hospital R ord, 2139 ACOI SULTAN ERS MANAG	INFRAS	ACOR Co Suite 2, Lev Suite 2, Lev DRAWING	RE Insultar vel 1, 33 H St Leonard T +67 INDEX Q.A. Check SC Dwg No.	Tts Pt Herbert ds NSV 1 2 943	y L Str V 20 8 50 SULT.

X
SCRIPTION
INDEX
CTION NOTES
SHEET 1
SHEET 2
NTROL PLAN
ER PLAN

# SITEWORKS NOTES

- 1. ORIGIN OF LEVELS :- AUSTRALIAN HEIGHT DATUM (A.H.D.)
- 2. CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK.
- 3. ALL WORK IS TO BE UNDERTAKEN IN ACCORDANCE WITH THE DETAILS SHOWN ON THE DRAWINGS, THE SPECIFICATIONS AND THE DIRECTIONS OF THE PRINCIPAL'S REPRESENTATIVE.
- EXISTING SERVICES HAVE BEEN PLOTTED FROM SUPPLIED DATA AND AS SUCH THEIR ACCURACY CANNOT BE GUARANTEED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH THE LOCATION AND LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY WORK. ANY DISCREPANCIES SHALL BE REPORTED TO THE PRINCIPAL'S REPRESENTATIVE. CLEARANCES SHALL BE OBTAINED FROM THE RELEVANT SERVICE AUTHORITY.
- WHERE NEW WORKS ABUT EXISTING THE CONTRACTOR SHALL ENSURE THAT A SMOOTH EVEN PROFILE. FREE FROM ABRUPT CHANGES IS OBTAINED.
- 6. THE CONTRACTOR SHALL ARRANGE ALL SURVEY SETOUT TO BE CARRIED OUT BY A REGISTERED SURVEYOR.
- 7. CARE IS TO BE TAKEN WHEN EXCAVATING NEAR EXISTING SERVICES. NO MECHANICAL EXCAVATIONS ARE TO BE UNDERTAKEN OVER COMMUNICATIONS OR ELECTRICAL SERVICES. HAND EXCAVATE IN THESE AREAS.
- 8. ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH AN APPROVED NON-NATURAL GRANULAR MATERIAL AND COMPACTED TO 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS.1289.5.1.1.
- 9. ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL.
- 10. ON COMPLETION OF PIPE INSTALLATION ALL DISTURBED AREAS MUST BE RESTORED TO ORIGINAL, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL AND GRASSED AREAS AND ROAD PAVEMENTS.
- 11. PROVIDE 10mm WIDE EXPANDING CORK JOINTS BETWEEN CONCRETE PAVEMENTS AND ALL BUILDINGS, WALLS, FOOTINGS, COLUMNS, KERBS, DISH DRAINS, GRATED DRAINS, BOLLARD FOOTINGS ETC
- 12. CONTRACTOR TO OBTAIN ALL AUTHORITY APPROVALS.
- 13. ALL BATTERS TO BE GRASSED LINED WITH MINIMUM 100 TOPSOIL AND APPROVED COUCH LAID AS TURF.
- 14. MAKE SMOOTH TRANSITION TO EXISTING SERVICES AND MAKE GOOD.
- 15. THE CONTRACTOR SHALL PROVIDE ALL TEMPORARY DIVERSION DRAINS AND MOUNDS TO ENSURE THAT AT ALL TIMES EXPOSED SURFACES ARE FREE DRAINING AND WHERE NECESSARY EXCAVATE SUMPS AND PROVIDE PUMPING EQUIPMENT TO DRAIN EXPOSED AREAS.
- 16. THESE PLANS SHALL BE READ IN CONJUNCTION WITH APPROVED ARCHITECTURAL. STRUCTURAL. HYDRAULIC AND ELECTRICAL DRAWINGS AND SPECIFICATIONS.
- 17. TRENCHES THROUGH EXISTING ROAD AND CONCRETE PAVEMENTS SHALL BE SAWCUT TO FULL DEPTH OF CONCRETE AND A MIN 50mm IN BITUMINOUS PAVING.
- 18. ALL BRANCH GAS AND WATER SERVICES UNDER DRIVEWAYS AND BRICK PAVING SHALL BE LOCATED IN Ø80 uPVC SEWER GRADE CONDUITS EXTENDING A MIN OF 500mm PAST PAVING.
- 19. ON COMPLETION OF WORKS ALL DISTURBED AREAS MUST BE RESTORED TO ORIGINAL INCLUDING, BUT NOT LIMITED TO, KERBS, FOOTPATHS, CONCRETE AREAS, GRASS AND LANDSCAPED AREAS.

# **EROSION AND SEDIMENT CONTROL NOTES**

GENERAL INSTRUCTIONS

- 1. THIS SOIL AND WATER MANAGEMENT PLAN IS TO BE READ IN CONJUNCTION WITH OTHER ENGINEERING PLANS RELATING TO THIS DEVELOPMENT.
- CONTRACTORS WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE GUIDELINES OF "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION". DEPT OF HOUSING, 2004 (BLUE BOOK).
- 3. ALL SUBCONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN REDUCING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE AREAS.

# LAND DISTURBANCE INSTRUCTIONS

- 1. DISTURBANCE TO BE NO FURTHER THAN 5 (PREFERABLY 2) METRES FROM THE EDGE OF ANY ESSENTIAL ENGINEERING ACTIVITY AS SHOWN ON APPROVED PLANS, ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE ZONES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- 2. ACCESS AREAS ARE TO BE LIMITED TO A MAXIMUM WIDTH OF 10 METRES THE SITE MANAGER WILL DETERMINE AND MARK THE LOCATION OF THESE ZONES ON-SITE. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE BOUNDARIES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- 3. ENTRY TO LANDS NOT REQUIRED FOR CONSTRUCTION OR ACCESS IS PROHIBITED EXCEPT FOR ESSENTIAL THINNING OF PLANT GROWTH.
- 4. WORKS ARE TO PROCEED IN THE FOLLOWING SEQUENCE:
  - a. INSTALL ALL BARRIER AND SEDIMENT FENCING WHERE SHOWN ON THE PLAN.
  - b. CONSTRUCT THE STABILISED SITE ACCESS.
  - c. CONSTRUCT DIVERSION DRAINS AS REQUIRED.
  - INSTALL MESH AND GRAVEL INLETS FOR ANY d. ADJACENT KERB INLETS.
  - e. INSTALL GEOTEXTILE INLET FILTERS AROUND ANY ON-SITE DROP INLET PITS.
  - f. CLEAR SITE AND STRIP AND STOCKPILE TOPSOIL IN LOCATIONS SHOWN ON THE PLAN.
  - UNDERTAKE ALL ESSENTIAL CONSTRUCTION WORKS ENSURING THAT ROOF AND/OR PAVED AREA STORMWATER SYSTEMS ARE CONNECTED TO PERMANENT DRAINAGE AS SOON AS PRACTICABLE.
  - GRADE LOT AREAS TO FINAL GRADES AND APPLY PERMANENT STABILISATION (LANDSCAPING) WITHIN 20 DAYS OF COMPLETION OF CONSTRUCTION WORKS.
  - REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER THE PERMANENT LANDSCAPING HAS BEEN COMPLETED.
- 5. ENSURE THAT SLOPE LENGTHS DO NOT EXCEED 80 METRES WHERE PRACTICABLE. SLOPE LENGTHS ARE DETERMINED BY SILTATION FENCING AND CATCH DRAIN SPACING.
- 6. ON COMPLETION OF MAJOR WORKS LEAVE DISTURBED LANDS WITH A SCARIFIED SURFACE TO ENCOURAGE WATER INFILTRATION AND ASSIST WITH KEYING TOPSOIL LATER.

	ERC	SIO	N AND SEDIMENT CONTROL NOTES
	<u>SITE</u>	INSPE	ECTION AND MAINTENANCE INSTRUCTIONS
	1.	THE S THE S OF E	SITE PRINCIPAL'S REPRESENTATIVE WILL INSPECT SITE AT LEAST WEEKLY AND AT THE CONCLUSION VERY STORM EVENT TO:
R		a.	ENSURE THAT DRAINS OPERATE PROPERLY AND TO
)		b.	REMOVE SPILLED SAND OR OTHER MATERIALS FROM HAZARD AREAS, INCLUDING LANDS CLOSER THAN 5 METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS
		C.	REMOVE TRAPPED SEDIMENT WHENEVER THE DESIGN CAPACITY OF THAT STRUCTURE HAS BEEN
		d.	EXCEEDED. ENSURE REHABILITATED LANDS HAVE EFFECTIVELY REDUCED THE EROSION HAZARD AND TO INITIATE UPGRADING OR REPAIR AS NECESSARY.
		e.	CONSTRUCT ADDITIONAL EROSION AND/OR SEDIMENT CONTROL WORKS AS MIGHT BECOME NECESSARY TO ENSURE THE DESIRED PROTECTION IS GIVEN TO DOWNSLOPE LANDS AND WATERWAYS. MAKE ONGOING CHANGES TO THE PLAN WHERE IT PROVES INADEQUATE IN PRACTICE OR IS SUBJECTED TO CHANGES IN CONDITIONS ON THE WORK-SITE OR ELSEWHERE IN THE CATCHMENT.
5		f.	MAINTAIN EROSION AND SEDIMENT CONTROL STRUCTURES IN A FULLY FUNCTIONING CONDITION UNTIL ALL EARTHWORK ACTIVITIES ARE COMPLETED AND THE SITE IS REHABILITATED.
	2.	the f Loge Imme Raini	PRINCIPAL'S REPRESENTATIVE WILL KEEP A BOOK MAKING ENTRIES AT LEAST WEEKLY, DIATELY BEFORE FORECAST RAIN AND AFTER FALL. ENTRIES WILL INCLUDE:
		a. b. c. d. e.	THE VOLUME AND INTENSITY OF ANY RAINFALL EVENTS. THE CONDITION OF ANY SOIL AND WATER MANAGEMENT WORKS. THE CONDITION OF VEGETATION AND ANY NEED TO IRRIGATE. THE NEED FOR DUST PREVENTION STRATEGIES. ANY REMEDIAL WORKS TO BE UNDERTAKEN. THE
			LOGBOOK WILL BE KEPT ON-SITE AND MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. IT WILL BE GIVEN TO THE PROJECT MANAGER AT THE CONCLUSION OF THE WORKS.
		<u>SED</u>	IMENT CONTROL INSTRUCTIONS
)		1.	SEDIMENT FENCES WILL BE INSTALLED AS SHOWN ON THE PLAN AND ELSEWHERE AT THE DISCRETION OF THE PRINCIPAL'S REPRESENTATIVE TO CONTAIN SOIL AS NEAR AS POSSIBLE TO THEIR SOURCE.
1		2.	SEDIMENT FENCES WILL NOT HAVE CATCHMENT AREAS EXCEEDING 900 SQUARE METRES AND HAVE A STORAGE DEPTH OF AT LEAST 0.6 METRES.
		3.	SEDIMENT REMOVED FROM ANY TRAPPING DEVICES WILL BE RELOCATED WHERE FURTHER POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS CANNOT OCCUR.
		4.	STOCKPILES ARE NOT TO BE LOCATED WITHIN 5 METRES OF HAZARD AREAS INCLUDING AREAS OF HIGH VELOCITY FLOWS SUCH AS WATERWAYS, PAVED AREAS AND DRIVEWAYS.
-		5.	WATER WILL BE PREVENTED FROM DIRECTLY ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR WATER HAS BEEN TREATED BY AN APPROVED DEVICE.
		6.	TEMPORARY SEDIMENT TRAPS WILL REMAIN IN PLACE UNTIL AFTER THE LANDS THEY ARE PROTECTING ARE COMPLETELY REHABILITATED.
		7.	ACCESS TO SITES SHOULD BE STABILISED TO REDUCE THE LIKELIHOOD OF VEHICLES TRACKING SOIL MATERIALS ONTO PUBLIC ROADS AND ENSURE ALL-WEATHER ENTRY/EXIT.

# **EROSION AND SEDIMENT CONTROL NOT**

# SOIL EROSION CONTROL INSTRUCTIONS

- EARTH BATTERS WILL BE CONSTRUCTED WITH AS I GRADIENT AS PRACTICABLE BUT NO STEEPER. UNL OTHERWISE NOTED. THAN:
- a. 2(H):1(V) WHERE SLOPE LENGTH LESS THAN 1 METRES
- b. 2.5(H):1(V) WHERE SLOPE LENGTH BETWEEN 16 METRES.
- c. 3(H):1(V) WHERE SLOPE LENGTH BETWEEN 16 20 METRES.
- d. 4(H):1(V) WHERE SLOPE LENGTH GREATER TH METRES.
- 2. ALL WATERWAYS, DRAINS, SPILLWAYS AND THEIR OUTLETS WILL BE CONSTRUCTED TO BE STABLE IN LEAST THE 1:20 YEAR ARI. TIME OF CONCENTRATION STORM EVENT.
- 3. WATERWAYS AND OTHER AREAS SUBJECT TO CONCENTRATED FLOWS AFTER CONSTRUCTION AF HAVE A MAXIMUM GROUNDCOVER C-FACTOR OF 0. (70% GROUND COVER) WITHIN 10 WORKING DAYS F COMPLETION OF FORMATION. FLOW VELOCITIES AI BE LIMITED TO THOSE SHOWN IN TABLE 5-1 OF "MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION", DEPT OF HOUSING 2004 (BLUE BC FOOT AND VEHICULAR TRAFFIC WILL BE PROHIBITE THESE AREAS.
- 4. STOCKPILES AFTER CONSTRUCTION ARE TO HAVE MAXIMUM GROUND-COVER C-FACTOR OF 0.1 (60% GROUND-COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION.
- 5. ALL LANDS, INCLUDING WATERWAYS AND STOCKPI DURING CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.15 (50% GROUND COVER) WITHIN 20 WORKING DAYS FROM INACTIVIT EVEN THOUGH WORKS MAY CONTINUE LATER.
- 6. FOR AREAS OF SHEET FLOW USE THE FOLLOWING GROUND COVER PLANT SPECIES FOR TEMPORARY COVER: JAPANESE MILLET 20 KG/HA AND OATS 20
- 7. PERMANENT REHABILITATION OF LANDS AFTER CONSTRUCTION WILL ACHIEVE A GROUND-COVER C-FACTOR OF LESS THAN 0.1 AND LESS THAN 0.05 \ 60 DAYS. NEWLY PLANTED LANDS WILL BE WATERE **REGULARLY UNTIL AN EFFECTIVE COVER IS** ESTABLISHED AND PLANTS ARE GROWING VIGORO FOLLOW-UP SEED AND FERTILISER WILL BE APPLIE NECESSARY.
- 8. RE-VEGETATION SHOULD BE AIMED AT RE-ESTABLI NATURAL SPECIES. NATURAL SURFACE SOILS SHO BE REPLACED AND NON-PERSISTANT ANNUAL COV CROPS SHOULD BE USED.

# WASTE CONTROL INSTRUCTIONS

- 1. ACCEPTABLE BINS WILL BE PROVIDED FOR ANY CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHING, LIGHTWEIGHT WASTE MATERIALS AND L CLEARANCE SERVICES WILL BE PROVIDED AT LEAS WEEKLY. DISPOSAL OF WASTE WILL BE IN A MANNE APPROVED BT THE PRINCIPAL'S REPRESENTATIVE.
- 2. ALL POSSIBLE POLLUTANT MATERIALS ARE TO BE STORED WELL CLEAR OF ANY POORLY DRAINED AF FLOOD PRONE AREAS, STREAMBANKS, CHANNELS STORMWATER DRAINAGE AREAS. STORE SUCH MATERIALS IN A DESIGNATED AREA UNDER COVER WHERE POSSIBLE AND WITHIN CONTAINMENT BUN
- ALL SITE STAFF AND SUB-CONTACTORS ARE TO BE INFORMED OF THEIR OBLIGATION TO USE WASTE CONTROL FACILITIES PROVIDED.
- ANY DE-WATERING ACTIVITIES ARE TO BE CLOSELY MONITORED TO ENSURE THAT WATER IS NOT POLL BY SEDIMENT, TOXIC MATERIALS OR PETROLEUM PRODUCTS.
- 5. PROVIDE DESIGNATED VEHICULAR WASHDOWN AND MAINTENANCE AREAS WHICH ARE TO HAVE CONTAINMENT BUNDS.

	_							
ËS	C COI pro 079	PYRIGHT perty of <i>I</i> 9 306 246	of this design and p ACOR Consultants P ABN 40 079 306 24	plan is the Pty Ltd, ACN I6. all rights	North			
	rese rep	erved. It r roduced	nust not be used, n or copied wholly or bission from ACOB (	nodified, in part without				
	Ltd.							
LOW A LESS								
	This drav approved	wing has be d by: Appro	en assigned an electron	ic code that signifies th	ne drawing has be	en checked	and	
2	lssue. 0	Descript ISSUED	ion FOR INFORMATION		Date 10.02.2023	Drawn JE	Approved SN	
12 AND	1 2 3	ISSUED 50% ISS 100% IS	FOR INFORMATION UE SUE		17.05.2023 16.06.2023 06.09.2023	AL PC MD	SN SN SN	
AND								
AN 20								
		·						
I AT DN								
RETO 05								
ROM								
DOK).								
D IN								
А								
LES,								
ſΥ								
KG/HA.								
WITHIN								
D								
USLY. D. AS								
SHING	-1 0 Client	) 1m	at full size				250m	
ULD /ER	HEA	4LTH	I INFRAS	TRUCTU	RE			
	Architect	1						
ITTER	NB	RS						
ST	4 Clor	o \$t						
:R	Milsor	n Ot, ns Point, 22 2344	NSW 2061					
	Project							
REAS,		NCO	RDFMH					
AND	 109 H	losnital I	24					
IDS.	Conco	ord, 2139	·•• 1					
				ACOR Co	onsultar	nts Pt	y Ltd	T.rt
		A		Suite 2, Le	evel 1, 33 l St Leonar	Herbert	Street / 2065	VHTH-ACO-S
,			K		l +6′	1 2 943	5 5098	anslation Hub.
r .UTED	CONS	SULTAN	NTS					152 Health II.
	ENGINEE Drawing	ERS  MAN	AGERS  INFRASTRU	CTURE PLANNERS		ENT CONS	ULTANTS	sk Docs://SU
П	ENA	ABLIN	g works	CONSTRU	ICTION	NOTE	S	Autode
	Drawn MD		Date 06/09/2023	Scale A	1 Q.A. Check	06/	Date 09/2023	12-08 AM
	Designed	d	Project No.	)	Dwg No.	00/		1/2022 11:4.
	- SIN		ZZ   $ $ YZ	<b>-</b>			J 3	5

3





		50% ISSUE 100% ISSUE	16.06.2023 06.09.2023	MD	
GRASS TO RCHITECTS DETAILS					
INGLE SIZED DR EQUIVALENT RANULAR BACKFILL					
E WRAPPED IN GEOTEXTILE AT MIN. 0.5% FALL					
RUNOFF	Lient		RE		250m
THREE LAYERS OF SANDBAGS WITH ENDS OVERLAPPED.	Architect	RS			
KERB SAG PIT	4 Glen Milsons (02) 992 Project	St, s Point, NSW 2061 2 2344 NCORD FMH			
NON-WOVEN GEOTEXTILE FILTER FABRIC WIRE TIED TO GRATE IN ALL 4 CORNERS & CENTRE	109 Ho Conco NSW 2 CONS ENGINEER Drawing T	ACOR Co Suite 2, Lev Suite 2, L	IDEVELOPM	nts Pty Herbert ds NSW 1 2 9438	y Ltd Street / 2065 8 5098
AREAS WHERE TRAFFIC	Drawn MD Designed SN	Date Scale A1 06/09/2023 AS SHOWN Project No. 221192	Q.A. Check SC Dwg No. 0115	06/	Date 09/2023 Issue 3

C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN

Ltd.

approved by: Approver

ISSUED FOR INFORMATION

ISSUED FOR INFORMATION

Issue. Description

810

079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without

written permission from ACOR Consultants Pty

This drawing has been assigned an electronic code that signifies the drawing has been checked and

Date Drawn Approved

 10.02.2023
 JE
 SN

 17.05.2023
 AL
 SN







;)	COPYRIGHT of this design and plan is the
	property of ACOR Consultants Pty Ltd, ACN
	079 306 246 ABN 40 079 306 246, all rights
	reserved. It must not be used, modified,
	reproduced or copied wholly or in part without
	written permission from ACOR Consultants Pty
	Ltd.



~		IATION	10 02 2023	Drawn	Ар
1 2	ISSUED FOR INFORM	IATION	17.05.2023	AL PC	
3	100% ISSUE		06.09.2023	MD	
S	OIL AND WAT	<u>ER MANAGE</u>	MENT LEGEN	<u>ID</u>	
	77	GEOTEXT	ILE PIT FILTER /		
		SEDIMEN I INSTALLE	D ON EXISTING P	IT	
		OVERLAN	D FLOW		
			FENCE /		
		SITE ACC	SS GATE		
		TEMPORA	RY SHAKER RAM	Р	
		FOR ENTR	Y/EXIT		
<u>S</u>	URVEY LEGEN	<u>ID</u>			
	× 24.50	EX SURFAC	E LEVEL		
	5.00	EX SURFAC	E CONTOUR		
		EX TREE TO	) BE RETAINED.		
		ARBORIST I DETAILS.	REPORT FOR		
		EX TREE TO	BE REMOVED		
	°	ARBORIST F	ANDSCAPE AND REPORT FOR		
		EXISTING S	TORMWATER		
		DRAINAGE I	_INE		
		EXISTING S	EWER LINE		
		EXISTING W	ATER MAIN		
		EXISTING S	TORMWATER PIT		
-1	0 1m at full size	_			
Client	0 1m at full size	RASTRU			1
Client	ALTH INF	RASTRU			<u> </u>
Client	0 1m at full size	RASTRU	CTURE		<u>+</u>
Client	0 1m at full size	RASTRU	CTURE		<u> </u>
Client HE Archite	0 1m at full size	RASTRU	CTURE		<u>+</u>
Client HE Archite	0 1m at full size	RASTRU	CTURE		<u>+</u>
Client HE Archite NB	ALTH INFF	RASTRU	CTURE		
Archite NB 4 Gle Milsc (02) 9	ALTH INFF	RASTRU(	CTURE		
Archite Archite NB 4 Gle Milsc (02) 9 Project	ALTH INFF	RASTRU(	CTURE		
Archite Archite NB 4 Gle Milsc (02) 9 Project	ALTH INFF	RASTRU(	CTURE		
Archite Archite NB 4 Gle Milsc (02) 9 Project CC	ALTH INFF	ASTRU(	CTURE		
Archite Archite NB 4 Gle Milsc (02) 9 Project CC 109 109 NSW	ALTH INFF	ASTRU(	CTURE		
Archite Archite NB 4 Gle Milso (02) 9 Project CC 109 Conc NSW	ALTH INFF	ASTRU( 061 MH ACO Suite	CTURE	Ints Pt	<b>y I</b> Stu
Archite Archite NB 4 Gle Milsc (02) 9 Project CC 109 Conc NSW	ALTH INFF ALTH INFF	ASTRU( 061 MH ACO Suite	CTURE CTURE R Consulta e 2, Level 1, 33 St Leona T +(	Ints Pt Herbert ards NSV 61 2 943	± ± ± ± ± ± ± ± ± ± ± ± ± ± ±
Archite Archite NB 4 Gle Milso (02) 9 Project CC	ALTH INFF ALTH INFF ALTH INFF RS en St, ons Point, NSW 20 922 2344 NCORD F Hospital Rd, cord, / 2139	ASTRU( 061 MH ACO Suite	CTURE	Ints Pt Herbert ards NSV 61 2 943	<b>:y I</b> : Str : 8 5
Archite HE Archite NB 4 Gle Milso (02) 9 Project CC 109 109 NSW	ALTH INFF ALTH INFF ALTH INFF RS en St, ons Point, NSW 20 922 2344 NCORD F Hospital Rd, cord, 2139	ASTRU( MH ACO Suite	CTURE	Ints Pt ards NSV 61 2 943	<b>:y I</b> : Str V 2 :8 5 :8 5
Archite NB Archite NB A Gle Milso (02) 9 Project CC 109 CON NSW	ALTH INFR ALTH INFR ALTH INFR ALTH INFR RS en St, ons Point, NSW 20 922 2344 DNCORD F Hospital Rd, cord, / 2139 ACCORD F Hospital Rd, cord, / 2139 ACCORD F Hospital Rd, cord, / 2139		CTURE	Ints Pt Herbert ards NSV 61 2 943	
Archite NB Archite NB A Gle Milso (02) 9 Project CC 109 CON NSW	ALTHINFF ALTHINFF	RASTRUC 061 MH ACO Suite RASTRUCTURE PL D EROSION	CTURE	Ints Pt Herberd ards NSV 61 2 943	SULT
Archite Archite NB 4 Gle Milso (02) 9 Project CC 109 CON 109 CON NSW CON NSW CON Drawin SEI Drawin MD	ALTH INFF ALTH INFF ALTH INFF ALTH INFF S S S S S S S S S S S S S S S S S S	AASTRUC AASTRUC 161 MH ACO Suite ACO Suite 023 Scale 1:250	CTURE	Ints Pt ards NSV 61 2 943 MENT CONS L PLAI	xy I SULT SULT N D D



### LEGEND:



EX8.36	
● <sup>IK 6.70</sup>	
● <sup>TK6.55</sup>	
• TW8.65	
● <sup>TH8.70</sup>	
КО	





PAVEMENT TYPE 1 FULL DEPTH
PAVEMENT TYPE 2 MILL AND RE-SHEET
LANDSCAPE AREA COURTYARD
PAVING / LANDSCAPE TO LANDSCAPE ARCHITECT DETAILS
PAVEMENT TYPE 3 HEAVY DUTY CONCRETE
DESIGN SURFACE LEVEL
EXISTING SURFACE LEVEL
INVERT OF KERB LEVEL
TOP OF KERB LEVEL
TOP OF RETAINING WALL
TOP OF HOB
CONSTRUCT NEW KERB ONLY
CONSTRUCT NEW KERB & GUTTER
INSTALL NEW STORMWATER PIT
INSTALL NEW STORMWATER KERB INLET PIT
INSTALL NEW STORMWATER PIPE
INSTALL SUBSOIL DRAINAGE
CONSTRUCT NEW DISH DRAIN
CONSTRUCT NEW HOB
CONSTRUCT NEW RETAINING WALL
INSPECTION OPENING

C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.



This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: Approver

lssue.	Description	Date	Drawn	Approved
0	ISSUED FOR INFORMATION	10.02.2023	JE	SN
1	ISSUED FOR INFORMATION	17.05.2023	AL	SN
2	50% ISSUE	16.06.2023	PC	SN
3	50% ISSUE	17.06.2023	PC	SN
4	50% ISSUE	11.08.2023	MD	SN
5	100% ISSUE	06.09.2023	MD	SN

# HEALTH INFRASTRUCTURE

### Architect NBRS

4 Glen St, Milsons Point, NSW 2061 (02) 9922 2344

1m at full size

# CONCORD FMH

109 Hospital Rd, Concord, NSW 2139

CONSULTANTS

ACOR Consultants Pty Ltd Suite 2, Level 1, 33 Herbert Street St Leonards NSW 2065 T +61 2 9438 5098



ENGINEERS |MANAGERS |INFRASTRUCTURE PLANNERS |DEVELOPMENT CONSULTANTS

Drawing Title SITE WORKS AND STORMWATER PLAN

Drawn	Date	Scale	A1	Q.A. Check		Date
MD	06/09/2023	1:250		SC	06/0	)9/2023
Designed	Project No.			Dwg No.		Issue
SN	B-ACO	-CEC		1000		5



# Appendix C - Structural 100% Design Development

# CONCORD REPATRIATION GENERAL HOSPITAL 109 HOSPITAL ROAD, NSW 2139 STRUCTURAL SERVICES



DRAWING LIST				
DRAWING №	DRAWING TITLE			
S-00.00	COVER SHEET			
S-00.01	NOTES - SHEET 1			
S-00.02	NOTES - SHEET 2			
S-00.03	NOTES - SHEET 3			
S-02.00	CORE WALL PART PLANS AND ELEVATIONS - SHEET 1			
S-02.01	CORE WALL PART PLANS AND ELEVATIONS - SHEET 2			
S-02.10	TYPICAL CONCRETE WALL DETAILS - SHEET 1			
S-02.11	TYPICAL CONCRETE WALL DETAILS - SHEET 1			
S-03.00	TYPICAL STAIR DETAILS - SHEET 1			
S-05.00	TYPICAL FOOTING DETAILS - SHEET 1			
S-05.01	TYPICAL FOOTING DETAILS - SHEET 2			
S-06.00	FOOTING OVERALL PLAN			
S-06.01	FOOTING GA PLAN - PART 1			
S-06.02	FOOTING GA PLAN - PART 2			
S-07.00	GROUND FLOOR OVERALL PLAN			
S-07.01	GROUND FLOOR GA PLAN - PART 1			
S-07.02	GROUND FLOOR GA PLAN - PART 2			
S-07.10	LEVEL 1 OVERALL PLAN			
S-07.11	LEVEL 1 GA PLAN - PART 1			
S-07.12	LEVEL 1 GA PLAN - PART 2			
S-07.20	LEVEL 2 OVERALL PLAN			
S-07.21	LEVEL 2 GA PLAN - PART 1			
S-07.22	LEVEL 2 GA PLAN - PART 2			
S-07.30	ROOF OVERALL PLAN			
S-07.31	ROOF GA PLAN - PART 1			
S-07.32	ROOF GA PLAN - PART 2			
S-13.01	TYPICAL SUSPENDED SLAB DETAILS - SHEET 1			
S-14.00	TYPICAL STEEL DETAILS - SHEET 1			
S-14.01	TYPICAL STEEL DETAILS - SHEET 2			







ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPME CONSULTANTS

COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

ssu	е		
No.	Date	Description	Chko
1	13.02.2023	SCHEMATIC DESIGN	ZP
2	15.06.2023	50% DESIGN DEVELOPMENT	ΤВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ТВ





nbrs.com.au

ABN 16 002 247 565

# Health Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at

109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title COVER SHEET

Date 25/09/2023 6:21:29 AM Scale @ A1

Drawing Reference 22071-S-00.00

### GENERAL NOTES

- G1. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL AND OTHER CONSULTANTS DRAWINGS, SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE STRUCTURAL ENGINEER BEFORE PROCEEDING WITH THE WORK.
- DO NOT COMMENCE CONSTRUCTION USING THESE STRUCTURAL DRAWINGS G2. UNTIL A CONSTRUCTION CERTIFICATE IS ISSUED BY THE PRINCIPLE AUTHORITY.
- ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE G3. RELEVANT CURRENT STANDARDS AUSTRALIA CODES AND WITH THE BUILDING CODE OF AUSTRALIA.
- ALL DIMENSIONS RELEVANT TO SETTING OUT AND OFF-SITE WORK SHALL BE G4. VERIFIED BY THE CONTRACTOR BEFORE CONSTRUCTION AND FABRICATION IS COMMENCED
- DIMENSIONS SHALL NOT BE OBTAINED BY SCALING THE STRUCTURAL G5. DRAWINGS.
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS STATED OTHERWISE. ALL LEVELS ARE EXPRESSED IN METRES. THE RL'S SHOWN ON THESE DRAWINGS ARE FOR THE SOLE PURPOSE OF ASSISTING THE STRUCTURAL DOCUMENTATION. THEY MUST NOT BE USED FOR CONSTRUCTION. REFER TO THE ARCHITECT'S DRAWINGS FOR ALL CONSTRUCTION RL'S.
- DURING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR G7. MAINTAINING THE STRUCTURE IN A STABLE CONDITION AND ENSURING NO PART SHALL BE OVER STRESSED UNDER CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL PROVIDE TEMPORARY BRACING, SHORING AND PROPPING IN ORDER TO KEEP THE BUILDING WORKS AND EXCAVATIONS STABLE AT ALL TIMES.
- THE BUILDER IS RESPONSIBLE FOR THE ADEQUACY OF ALL TEMPORARY WORKS INCLUDING SHORING, PROPPING AND BRACING. WHERE NECESSARY THE CONTRACTOR IS TO ENGAGE A STRUCTURAL ENGINEER TO DESIGN AND CERTIFY THE TEMPORARY WORKS
- THE METHOD OF CONSTRUCTION AND THE MAINTENANCE OF SAFETY DURING G9. CONSTRUCTION ARE THE RESPONSIBILITY OF THE BUILDER. IF ANY STRUCTURAL ELEMENT PRESENTS DIFFICULTY IN RESPECT OF CONSTRUCTABILITY OR SAFETY, THE MATTER SHALL BE REFERRED TO THE STRUCTURAL ENGINEER FOR RESOLUTION BEFORE PROCEEDING WITH THE WORK.
- G10. IF THERE IS A DISCREPANCY IN MEMBER SIZES FOR ANY COMPONENT, ASSUME FOR PRICING PURPOSE ONLY THAT THE LARGER OR MORE EXPENSIVE SIZE IS CORRECT. REFER TO STRUCTURAL ENGINEER FOR DECISION BEFORE DETAILING OR CONSTRUCTION.
- THE APPROVAL OF A SUBSTITUTION SHALL BE SOUGHT FROM THE ENGINEER G11. BUT IS NOT AN AUTHORISATION FOR A VARIATION. ANY VARIATIONS INVOLVED MUST BE TAKEN UP WITH THE ARCHITECT OR PROJECT MANAGER BEFORE THE WORK COMMENCES.
- ANY DISCREPANCIES OR OMISSIONS SHALL BE REFERRED TO THE ENGINEER G12. FOR A DECISION BEFORE PROCEEDING WITH THE WORK
- THE WRITTEN CONSENT OF ADJOINING PROPERTY OWNERS SHALL BE G13. OBTAINED BEFORE INSTALLATION OF UNDERPINNING, ANCHORING WORKS, DRAINAGE LINES OR ANY OTHER WORKS BEYOND THE PROPERTY BOUNDARY.
- UNLESS AGREED OR SPECIFIED OTHERWISE, THE BUILDER IS REQUIRED TO G14. NOTIFY AND ALLOW TIME FOR THE STRUCTURAL ENGINEER TO INSPECT THE WORKS AT THE FOLLOWING POINTS, COMPLETED EXCAVATION, FORMWORK, REINFORCEMENT, MEMBRANES AND EMBEDMENT'S PRIOR TO PLACEMENT OF CONCRETE, COMPLETED ERECTED STRUCTURAL ELEMENTS PRIOR TO COVERING
- THE BUILDER SHALL GIVE 48 HOURS NOTICE FOR ALL ENGINEERING G15. INSPECTIONS.
- SITE INSPECTIONS DO NOT RELIEVE THE BUILDER OF RESPONSIBILITY FOR THE COMPLETENESS AND CORRECTNESS OF THEIR WORK.
- WHERE STRUCTURAL ELEMENTS ARE DESIGNED AND CERTIFIED BY OTHER G17. PARTIES, THE CONTRACTOR SHALL OBTAIN WRITTEN CERTIFICATION PRIOR TO PROCEEDING WITH ANY CONSTRUCTION WORK WHICH WOULD PREVENT INSPECTION OR REMEDIAL WORKS TO BE UNDERTAKEN. ALL CERTIFICATIONS ARE TO BE ISSUED TO THE STRUCTURAL ENGINEER FOR REVIEW PRIOR TO WORK PROCEEDING.
- G18. THE WORD 'ENGINEER' USED IN THESE NOTES REFERS TO AN EMPLOYEE OR NOMINATED REPRESENTATIVE OF ACOR CONSULTANTS PTY.LTD.

# FOUNDATIONS

- BEARING MATERIAL AT BASES OF PIERS TO BE CONFIRMED BY AN F1. EXPERIENCED GEOTECHNICAL ENGINEER OR ENGINEERING GEOLOGIST.
- EXCAVATION NEAR FOOTINGS SHALL NOT EXTEND BELOW FOUNDATION LEVEL F2. WITHOUT THE ENGINEERS APPROVAL.
- ALL FOOTINGS SHALL BE LOCATED CENTRALLY UNDER WALLS AND COLUMNS F3. UNLESS NOTED OTHERWISE
- F4. DO NOT BACKFILL RETAINING WALLS (OTHER THAN CANTILEVER WALLS) UNTIL FLOOR CONSTRUCTION AT TOP AND BOTTOM IS COMPLETED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ANY F5. EXCAVATION IN A STABLE CONDITION WITHOUT ADVERSELY AFFECTING SURROUNDING PROPERTY INCLUDING SERVICES. THIS INCLUDES OBTAINING ALL NECESSARY APPROVALS FOR SHORING AND ANCHOR SYSTEMS.
- F6. ANY OVER EXCAVATION SHALL BE BACKFILLED WITH CONCRETE GRADE N15.
- F7. FOUNDATIONS ADJACENT TO SERVICES ETC. SHALL BE EXTENDED DOWN SUCH THAT THE INFLUENCE LINE OF THE FOUNDATION IS BELOW THE ADJACENT SERVICE.
- ALL PILES TO BE FOUNDED INTO SANDSTONE CLASS IV TO LIMIT F8. DIFFERENTIAL SETTLEMENT AS NOTED IN THE GEOTECHNICAL REPORT ALL BORED HOLES TO BE INSPECTED BY A GEOTECHNICAL ENGINEER TO CONFIRM.

GEOTECH REPORT No: E25966.G03 PREPARED BY: ElAustralia

### CONCRETE NOTES

- C1. ALL WORKMANSHIP AND MATERIALS SHALL COMPLY WITH AS 3600 CURRENT EDITIONS WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- ALL CONCRETE SUPPLY SHALL COMPLY WITH AS1379. CONCRETE PROPERTIES C2. AND COVER TO REINFORCING.

ELEMENT		0	OVE	R (m	m)	f'c (MPa)	MAX 56 DAY	
						(28 DAYS)	SHRINKAGE	C22.
BORED PILES			7	0		40	800	
SLAB ON GROUND	EXTERNAL	Т	40	В	50	32	800	
	INTERNAL	Т	20	В	50	32	000	<u>TYPI</u>
STRIP FOOTINGS			5	0		40	800	C23.
PAD FOOTINGS			5	0		40	800	C24.
SUSPENDED SLABS	EXTERNAL	Т	40	В	40	40	650	
	INTERNAL	Т	20	В	20	40	000	C25.
BEAMS	EXTERNAL	Т		В				
	INTERNAL	Т		В				C26.
COLUMNS	EXTERNAL		4	0		32	800	
	INTERNAL		4	0		32	800	C27.
CONCRETE WALLS	EXTERNAL		4	0		40	800	
	INTERNAL		2	0		40	000	
PRECAST WALLS	EXTERNAL		N	/A		N/A	NI/A	
	INTERNAL		N	/A		N/A	N/A	
MAXIMUM AGGREGAT	E SIZE =			20				1
SLUMP DURING PLACE	EMENT =			80				
EXPOSURE CLASSIFIC	ATION =		A1 I	NTE	RNAL	-		
	=		B1 E	EXTE	ERNA	L		

C3. CEMENT TO BE TYPE SL TO AS 3972 UNLESS NOTED OTHERWISE THIS IS A MODIFIED TYPE 'GP' CEMENT. SEE ACSE CONCRETE SPECIFICATION.

- NO 'BRECCIA' TYPE AGGREGATE IS TO BE USED. C4.
- NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS APPROVED IN WRITING C5. BY THE ENGINEER.
- C6. PROJECT ASSESSMENT OF CONCRETE SHALL BE CARRIED OUT IN ACCORDANCE WITH AS1379.
- PROJECT CONTROL TESTING SHALL BE CARRIED OUT IN ACCORDANCE WITH AS1379 BY A NATA REGISTERED TESTING LABORATORY. SAMPLES SHALL BE TAKEN FOR TESTING OF SLUMP, COMPRESSIVE STRENGTH AND ANY OTHER TEST SPECIFIED.
- SLUMP SHALL BE SAMPLED FOR EACH TRUCK AT THE TIME OF POURING.

THE MINIMUM FREQUENCY OF SAMPLING FOR COMPRESSIVE TESTING OF EACH TYPE AND GRADE SHALL BE IN ACCORDANCE WITH THE FOLLOWING TABLE:

NUMBER OF BATCHES PER DAY	NUMBER OF SAMPLES 1 SAMPLE = 3 CYLINDERS
	(4 CYLINDERS FOR POST TENSIONED CONCRETE)
1	1 SAMPLE
1 TO 5	2 SAMPLES
6 TO 10	3 SAMPLES
11 TO 20	4 SAMPLES
FOR EACH ADDITIONAL 10	1 ADDITIONAL SAMPLE

SAMPLES SHALL BE TESTED FOR COMPRESSIVE STRENGTH AS FOLLOWS: ONE CYLINDER AT 3 DAYS (POST TENSIONED CONCRETE ONLY) ONE CYLINDER AT 7 DAYS **TWO CYLINDERS AT 28 DAYS** 

- BEAM DEPTHS ARE WRITTEN FIRST AND INCLUDE SLAB THICKNESS. C8.
- SIZES OF CONCRETE ELEMENTS DO NOT INCLUDE THICKNESS OF APPLIED C9. FINISHES.
- NO HOLES, CHASES OR EMBEDMENT OF PIPES OTHER THAN THOSE SHOWN ON C10. THE STRUCTURAL DRAWINGS SHALL BE MADE IN CONCRETE MEMBERS WITHOUT PRIOR APPROVAL OF THE ENGINEER.
- CONSTRUCTION JOINTS SHALL BE PROPERLY FORMED AND USE ONLY WHERE C34. C11. SHOWN OR SPECIFICALLY APPROVED BY THE ENGINEER.
- C12. ALL CONCRETE COLUMNS ARE TO BE POURED A MINIMUM OF 4 HOURS PRIOR TO SLAB OR BEAM OVER.
- REINFORCEMENT IS TO BE MAINTAINED.
- CONDUITS, PIPES AND THE LIKE SHALL NOT BE PLACED WITHIN THE CONCRETE C14. COVER
- C15. ALL CONCRETE (INCLUDING FOOTINGS AND SLABS ON GROUND) SHALL BE MECHANICALLY VIBRATED TO ACHIEVE FULL COMPACTION.
- C16. SAWN CUT JOINTS ARE TO BE CUT AFTER THE CONCRETE HAS SUFFICIENTLY HARDENED THAT WILL NOT BE DAMAGED BY THE SAWING BUT BEFORE SHRINKAGE CRACKING CAN OCCUR.

CURING OF ALL CONCRETE SHALL BE IN ACCORDANCE WITH AS3600 AND SHALL C17. COMMENCE WITHIN 2 HOURS OF FINISHING OPERATIONS. CURING SHALL BE BY CONTINUAL SATURATION WITH POTABLE WATER FOR 3 DAYS FOLLOWED BY PREVENTION OF MOISTURE LOSS FOR THE NEXT 4 DAYS USING POLYTHENE SHEETING OR WET HESSIAN PROTECTED FROM WIND OR TRAFFIC AND THEN ALLOWING GRADUAL DRYING OUT. CURING COMPOUNDS MAY BE USED PROVIDED THAT THEY COMPLY WITH AS3799 AND DO NOT AFFECT FLOOR FINISHES. THE COMPATIBILITY OF CURING COMPOUNDS WITH PROPOSED APPLIED FINISHES SHALL BE VERIFIED PRIOR TO APPLICATION. CURING COMPOUNDS ARE TO BE APPLIED UNIFORMLY IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATION. PVA BASED CURING COMPOUNDS ARE NOT ACCEPTABLE.

- ALIPHATIC ALCOHOL:-C18. WHEN SHADE TEMPERATURE EXCEEDS 35° C SPRAY THE EXPOSED SURFACE OF CONCRETE SLAB DURING THE PLACING AND FINISHING OPERATION WITH A FINE FILM OF APPROVED ALIPHATIC ALCOHOL. REPEAT THE SPRAY IF THE SPRAYED SURFACE HAS BEEN RE-WORKED.
- C19. ENSURE ADEQUATE SUPPLY OF ALIPHATIC ALCOHOL ON SITE BEFORE COMMENCING CONCRETE WORK.

### CONCRETE CONT'

C20.	SLIP JOIN TWO LAYE INTERNAL BETWEEN REQUIRED
C21.	NON LOAD
C22.	MASONRY UNTIL ALL HAS BEEN

C24 HOLE.

USE DETAILS BELOW.

IMMEDIATELY



C28. ENGINEER. C29. C30. C31. LEG.

IMMEDIATELY.

C32.





CASES, THE STRUCTURAL ENGINEER MUST BE CONSULTED.

C35.



TS ARE TO BE USED ON ALL LOAD BEARING MASONRY WALLS. USE ERS OF GALVANIZED FLAT STEEL WITH GRAPHITE GREASE BETWEEN IN CP2. . SKIN & TWO LAYERS OF STAINLESS STEEL WITH GRAPHIC GREASE I IN EXTERNAL SKINS. PROVIDE MORTAR LEVELLING STRIP AS

- D BEARING MASONRY SHALL BE SEPARATED FROM THE SOFFIT OF ID BEAMS BY 20mm.
- WALLS MUST NOT BE CONSTRUCTED ON SUSPENDED CONCRETE . TEMPORARY SUPPORTS ARE REMOVED AND ALL MASONRY TO BE LAID I STACKED ADJACENT TO PROPOSED POSITION.
- TYPICAL OPENINGS IN SLABS
- C23. LOCATION OF ALL OPENINGS TO BE TO THE APPROVAL OF ACOR.
  - FOR OPENINGS LESS THAN 300 x 300mm BARS TO BE RE-ARRANGED AROUND
  - FOR PENETRATIONS GREATER THAN 300 x 300mm BUT LESS THAN 1000 x 1000mm
  - FOR PENETRATIONS GREATER THAN 1000 x 1000mm REFER TO ENGINEER'S PLANS. WHERE OPENINGS ARE NOT DETAILED, CONTACT ENGINEER
  - TOP BARS: FOR EVERY TWO BARS THAT ARE TERMINATED BY OPENINGS, ADD ONE BAR EACH SIDE USING SAME GRADE AND SIZE OF REINFORCEMENT. WHERE NO TOP BARS ARE SHOWN, ADD 1-N16 TOP EACH SIDE OF OPENING.
    - TERMINATED BY PENETRATION, ADD ONE BAR EACH SIDE USING SAME GRADE AND SIZE OF REINFORCEMENT.

### PIPE PENETRATION THROUGH BEAM

- LOCATION OF ALL OPENINGS TO BE TO THE APPROVAL OF THE STRUCTURAL
- MINIMUM DISTANCE FROM BEAM SOFFIT TO PIPE SOFFIT TO BE 150mm.
- FOR PIPES UP TO Ø90, ADD ONE ROW OF TIES EACH SIDE OF PIPE. FOR PIPES Ø91 TO Ø150, ADD TWO ROWS OF TIES EACH SIDE OF PIPE AND 1-N16 HORIZONTAL BAR 1200 LONG TOP AND BOTTOM OF PIPE AT EVERY VERTICAL TIE
- FOR HOLES GREATER THAN Ø150 REFER TO ENGINEER'S DETAILS. WHERE PENETRATIONS ARE NOT DETAILED, CONTACT STRUCTURAL ENGINEER
- C33. LOCATION OF HOLES TO BE TO THE APPROVAL OF THE STRUCTURAL ENGINEER. CP5.

### PIERING REQUIREMENT

WHERE A SERVICE TRENCH IS PARALLEL TO A SIDE OF THE SLAB. WHETHER THE SLAB BE IN AN EXCAVATED OR FILLED AREA. THEN PIERING TO SUPPORT THE SLAB BESIDE THE SERVICE TRENCH IS ONLY REQUIRED IF THE SERVICE LINE IS BELOW A LINE OF INFLUENCE DRAWN FROM THE BOTTOM OF THE EDGE BEAM. REFER TO DIAGRAM BELOW.



THESE NOTES ARE INTENDED AS A GUIDE. THERE IS ALWAYS A POSSIBILITY OF SITE CONDITIONS REQUIRING VARIATION TO THESE PROCEDURES. IN SUCH

< 150 kPa SOILS

- CONCRETE PAVEMENT NOTES
- CP1. ALL WORK TO BE BROOM FINISHED.
  - JOINTS AS DETAILED.
- CP3. A) IN CASE OF DOUBT ASK.
  - B) BOND BREAKER TO BE TWO (2) UNIFORM COATS OF BITUMEN EMULSION ALL OVER THE EXPOSED SURFACE AND ON ENDS.
  - C) DOWELS AND TIE BARS TO MEET STRENGTH REQUIREMENTS OF STRUCTURAL GRADE STEEL IN ACCORDANCE WITH AS 1302. DOWELS AND TIE BARS SHALL
  - STRAIGH
  - TO LENGTH SPECIFIED
  - CLEAN AND FREE FROM MILL SCALE, RUST AND OIL SAWN TO LENGTH NOT CROPPED
- CP4. JOINT TO BE SAWN AS SOON AS CONCRETE HAS HARDENED SUFFICIENTLY THAT IT WILL NOT BE DAMAGED BY SAWING. IF AN UNPLANNED CRACK OCCURS THE CONTRACTOR SHALL REPLACE THE WHOLE SLABS EITHER SIDE OF THE CRACK, UNLESS DIRECTED OTHERWISE.
- CP5. DIMENSIONS OF SEALANT RESERVOIR DEPENDENT ON THE SEALANT TYPE ADOPTED. ENGINEER'S APPROVAL TO BE OBTAINED FOR SEALANT, RESERVOIR DIMENSIONS AND DETAIL PROPOSED BY THE CONTRACTOR. REFER TO DETAILS 'A AND 'B' FOR TYPICAL ARRANGEMENT AND SEALANT.
- CP6. REFER TO COMPACTING NOTES FOR PREPARATION OF SUB-BASE AND SUB-GRADE.

### CONCRETE PILE NOTES

- CP1. PILES SHALL COMPLY WITH AS2159 PILING DESIGN AND INSTALLATION AND ALL OTHER RELEVANT STANDARDS AND CODES OF PRACTICE.
- CP2. REFER TO LATEST GEOTECHNICAL REPORT FOR DETAIL OF SOIL CONDITIONS.
- THE PILES HAVE BEEN DESIGNED FOR BOTH THE LOADS AS SHOWN ON THE CP3. DRAWINGS, AND ANY LOADS DUE TO INSTALLATION. THE DESIGN LOADS PROVIDED HAVE BEEN DETERMINED IN ACCORDANCE WITH AS1170. PILES ARE TO BE DESIGNED FOR ALL RELEVANT LOAD COMBINATIONS IDENTIFIED IN AS1170 AND AS2159-2009. THE PILES SHALL BE DESIGN TO LIMIT DIFFERENTIAL SETTLEMENT. THE ABSOLUTE DIFFERENTIAL PILE SETTLEMENT AT ANY TIME BETWEEN ANY TWO ADJACENT PILES IS NOT TO EXCEED PILE SPACING (mm) / 1000. E.G. WHERE TWO PILE ARE LOCATED 8.4m APART THE MAXIMUM ABSOLUTE DIFFERENTIAL SETTLEMENT AT ANY TIME IS 8.4mm. THE MEASURE OF PILE SETTLEMENT IS TO INCLUDE ELASTIC SHORTENING OF THE PILE.
- PILE DESIGN CALCULATIONS ARE TO BE PROVIDED THAT INDICATE THE DESIGN CP4. LOADS AND ALL ASSUMED PARAMETERS. THE PILE DESIGN CALCULATIONS ARE TO BE CERTIFIED BY AN NPER STRUCTURAL OR GEOTECHNICAL ENGINEER COMPETENT IN PILE DESIGN. THESE CALCULATIONS ARE TO BE SUBMITTED TO THE STRUCTURAL AND GEOTECHNICAL ENGINEER FOR REVIEW. THIS REVIEW SHALL NOT RELIEVE THE PILING CONTRACTOR FROM ANY OBLIGATIONS AND THE PILING CONTRACTOR SHALL REMAIN COMPLETELY LIABLE FOR THE PILE WORKS. THE CONTRACTOR IS TO ALLOW FOR ANY COST AND TIME IMPLICATIONS FOR THIS REVIEW.
  - PILES SHALL BE CUT OFF AT THE LEVELS REQUIRED TO ACHIEVE CONSTRUCTION OF THE PILE CAPS AS INDICATED ON THE DRAWINGS. ALLOW REINFORCEMENT TO PROTRUDE INTO PILE CAPS.
- SETS, PLAN LOCATION, BEARING CAPACITY REACHED AND ANY PROBLEMS CP6. ENCOUNTERED.
- AT THE COMPLETION OF PILE WORKS, THE PILING CONTRACTOR IS TO ISSUE CERTIFICATION BY A REGISTERED NPER STRUCTURAL ENGINEER THAT THE INSTALLED PILES ARE SATISFACTORY TO CARRY THE DESIGN LOADS AS SHOWN ON THE DRAWINGS FOR THE SPECIFIED DESIGN LIFE OF 50 YEARS.
- ALL FOUND MATERIAL SHALL BE INSPECTED, APPROVED AND CERTIFIED AT THE CP8. PILING CONTRACTORS EXPENSE BY A SUITABLY QUALIFIED GEOTECHNICAL ENGINEER PRIOR TO PLACEMENT OF CONCRETE AND REINFORCEMENT CAGES. THE PILE CONTRACTOR SHALL CONDUCT ALL NECESSARY TESTING AS REQUIRED BY AS2159-2009 TO DEMONSTRATE THAT THE PILES ARE ABLE TO RESIST ALL LOADS NOMINATED ON THE STRUCTURAL DRAWINGS.
- CP9. PILES ARE TO BE FOUNDED AT A DEPTH WHERE SUITABLE TO SATISFY STRUCTURAL DESIGN INTENT. ALL PILES TO BEAR ON SIMILAR FOUNDATION STRATA. SOCKET LENGTHS ON PILE DRAWINGS INDICATE MINIMUM EMBEDMENT INTO REQUIRED ROCK STRATA AS PER GEOTECHNICAL REPORT.
- CP10. PLACING OF CONCRETE IN PILES SHALL BE IN ACCORDANCE WITH THE SPECIFICATION AND ANY REQUIREMENTS OF AS2159-2009.
- CP11. CONCRETE STRENGTH AND COVER TO REINFORCING IS TO BE IN ACCORDANCE WITH AS2159-2009 AND AS3600. THE PILE DESIGNER IS TO DETERMINE ALL DURABILITY REQUIREMENTS AND DESIGN ALL PILES TO SATISFY THE REQUIREMENTS OF AS2159-2009 AND AS3600 AND THE DESIGN LIFE NOMINATED.
- CP12. THE TOLERANCE ON THE INSTALLATION OF PILES SHALL BE IN ACCORDANCE WITH AS2159-2009. THE PILE & ITS CONNECTION TO THE FOOTING MUST BE DESIGNED FOR THESE CONSTRUCTION TOLERANCES & ANY ECCENTRICITIES AS A RESULT. THE STRUCTURAL ENGINEER IS TO BE NOTIFIED OF ANY PILES WHICH DO NOT SATISFY THE ABOVE CRITERIA, FOR ANY POSSIBLE FOOTING RECTIFICATION DESIGN. THE CONTRACTOR SHALL PAY FOR ANY COSTS FOR THIS REASSESSMENT, REDESIGN & CONSTRUCTION.
- CP13. THE BUILDING OWNER SHOULD BE ADVISED THAT IN CARRYING OUT SHORING WORKS, IT IS VIRTUALLY IMPOSSIBLE TO ENTIRELY PREVENT ANY MOVEMENT OF THE EXCAVATION, AND THAT EXCAVATION MOVEMENT MAY LEAD TO DAMAGE TO ADJOINING PROPERTIES. IT IS RECOMMENDED THAT CONSULTING ENGINEERS, WITH THE APPROPRIATE ADVICE FROM THE GEOTECHNICAL CONSULTANT, ADVISE OWNERS OF THE POSSIBLE RISK ASSOCIATED WITH THE WORKS AND THE POTENTIAL FOR DAMAGE TO ADJOINING PROPERTIES, WHICH AY SUBSEQUENTLY NEED REPAIRS (eg. THE DAMAGE MAY BE IN THE FORM OF CRACKS THAT WOULD NEED TO BE REPAIRED AT THE DEVELOPERS EXPENSE) THIS COURSE OF ACTION IS NOT INTENDED TO BE OR APPEAR TO BE ALARMIST, BUT SIMPLY A PROPER DISCHARGE OF THE ENGINEERS RESPONSIBILITIES. THE BUILDING OWNER SHOULD BE ADVISED TO ALLOW A SUM OF MONEY AS A CONTINGENCY FOR ANY REPAIRS TO ADJOINING BUILDINGS.
- CP14. CENTRE-LINE OF ALL PILES TO COINCIDE WITH CENTRE-LINE OF COLUMN U.N.O. WHERE PILES CAN NOT BE LOCATED ON THE CENTRE-LINE OF COLUMNS DUE TO AN EXISTING IN-GROUND SERVICE ETC, THE CONTRACTOR MUST NOTIFY THE ENGINEER PRIOR TO COMMENCING PILING.

### REINFORCEMENT

R3.

R6

- ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600, R1. AS4671 AND OTHER RELEVANT AUSTRALIAN CODES.
- R2. REINFORCEMENT TYPE AND GRADE

SYMBOL	TYPE	MPa	DUCTILITY CLASS
N	HOT ROLLED DEFORMED BARS	500	NORMAL
R	HOT ROLLED PLAIN BARS	250	NORMAL
W	COLD DRAWN PLAIN ROUND WIRE	500	LOW
SL	SQUARE WELDED MESH	500	LOW
RL	RECTANGULAR WELDED MESH	500	LOW
L TM	RECTANGULAR WELDED MESH	500	LOW

- AMENDMENTS. REINFORCEMENT NOTATION GIVES THE FOLLOWING INFORMATION: NO. OF BARS, TYPE, SIZE (MM), SPACING (MM), LAYER. FOR EXAMPLE 17N16 -250 T
- PRODUCT CODE, LAYER. FOR EXAMPLE SL82 T
- R4. REINFORCEMENT IS REPRESENTED DIAGRAMMATICALLY AND NOT NECESSARILY SHOWN IN TRUE PROJECTION.
- COVER TO REINFORCEMENT CLEAR COVER TO TO ALL REINFORCEMENT FOR R5. DURABILITY SHALL BE AS INDICATED IN THE CONCRETE NOTES. COVER SHALL NOT BE LESS THAN THE SIZE OF THE AGGREGATE OR THE MAIN BAR. PIPES OR CONDUITS SHALL NOT BE PLACED WITHIN THE COVER TO REINFORCEMENT. ADDITIONAL COVER MAY BE REQUIRED TO ACHIEVE FIRE RATING - REFER TO DESIGN DRAWINGS.

SUPPORT REINFORCEMENT ON MILD STEEL PLASTIC TIPPED CHAIRS, PLASTIC CHAIRS OR CONCRETE CHAIRS AT NOT GREATER THAN 1 METRE CENTRES BOTH WAYS. IN EXPOSED CONDITIONS B2 OR C (TO AS3600)

- USE ONLY PLASTIC OR CONCRETE CHAIRS. WELDING OF REINFORCEMENT SHALL NOT BE PERMITTED WITHOUT THE APPROVAL OF THE ENGINEER.
- PROVIDE DISTRIBUTION REINFORCEMENT OR TIE BARS IF NOT SHOWN. WHERE R7. NECESSARY PROVIDE N12-400 CENTRES (SPLICE 450) SITE BENDING OF N BARS SHALL BE DONE COLD WITH POWER OR MECHANICAL BENDING TOOLS AND A MANDREL OR FORMER WITH A BAR DIAMETER OF 5 TIMES THE BAR SIZE. NOTE: IF N BARS ARE HEATED ABOVE 450°C (LESS THAN
- RED HEAT) THEY LOSE STRENGTH. REINFORCEMENT LAPS
- LAP REINFORCEMENT ONLY AT LOCATIONS SHOWN ON THE STRUCTURAL DRAWINGS OR AS OTHERWISE APPROVED IN WRITING BY THE STRUCTURAL ENGINEER.

SLAB REINFORCEMENT - LAP LENGTH (mm)					
BAR	SAR CONCRETE GRADE				
DIA.	25 MPa	32 MPa	40 MPa		
N12	600	500	450		
N16	850	750	650		
N20 1100 1000 900					

- 6								
	BEAM REINFORCEMENT - LAP LENGTH (mm)							
	bar Dia.	< 300mr BE	n CONCRE <sup>®</sup> LOW THE B	TE CAST SAR	> 300mn BE	CONCRET	TE CAST BAR	
		CON	ICRETE GR	ADE	CON	ICRETE GR	ADE	
		25 MPa	32 MPa	40 MPa	25 MPa	32 MPa	40 MPa	
	N12	600	500	450	750	650	600	
l	N16	850	750	650	1100	950	850	
	N20	1100	1000	900	1450	1300	1150	
	N24	1400	1250	1100	1800	1600	1400	
	N28	1700	1500	1350	2200	1950	1700	
	N32	2000	1800	1600	2600	2300	2050	
	N36	2400	2100	1850	3050	2700	2400	
Г								
	BAR	COLUMN AND WALL REINFORCEMENT						
	DIA.	LAP LENGTH (mm)						
	N12	500						
	N16	650						
	N20	800						
	N24	950						
	N28			11	50			
I	N32	1300						

**|**⊲∽-|⊲∽-|

N36

R10. LAPS IN MESH (FABRIC) SHALL COMPLY WITH AS3600. THE TWO OUTERMOST TRANSVERSE WIRES OF ONE SHEET SHALL OVERLAP THE TWO OUTERMOST TRANSVERSE WIRES OF THE SHEET BEING LAPPED BY 25MM. A MAXIMUM OF 3 SHEETS OF MESH SHALL BE LAPPED AT ANY POINT.



- R11. SLAB REINFORCEMENT SHALL EXTEND 70mm ONTO SUPPORTING WALLS, WITH 50% OF BOTTOM BARS COGGED TO ACHIEVE ANCHORAGE AT SIMPLY SUPPORTED ENDS. MESH IN SLABS SHALL EXTEND 70mm ONTO SUPPORTING WALLS WITH A CROSS WIRE.
- R12. ALL BEAM TIES ARE TO HAVE BAR ANCHORAGES LOCATED ON THE TOP FACE OF THE BEAM UNO.
- R13. 12 BAR DIAMETERS.

ALL REINFORCEMENT TO CONFORM TO AS4671, CURRENT EDITIONS WITH

FABRIC OR MESH NOTATION GIVES THE FOLLOWING INFORMATION: "RL" OR "SL",



50 MAX.

N12 x 1200 LONG AT WIRE CENTRES

ALTERNATIVE FABRIC SPLICE DETAIL

REINFORCEMENT BAR JOGGLES SHALL BE 1 BAR DIAMETER OVER A LENGTH OF





ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS (C) COPYRIGHT of this design and plan is the property of ACOR Consultants

Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

sue	•		
Э.	Date	Description	Cł
	13.02.2023	SCHEMATIC DESIGN	ZF
	15.06.2023	50% DESIGN DEVELOPMENT	ΤE
	15.09.2023	80% DESIGN DEVELOPMENT	TE
	22.09.2023	100% DESIGN DEVELOPMENT DRAFT	TE





NSM

nbrs.com.au

ABN 16 002 247 565

# Health Infrastructure GOVERNMENT

### Project CONCORD REPATRIATION GENERAL HOSPITAL

109 HOSPITAL ROAD, NSW 2139

**NSW GOVERNMENT HEALTH & INFRUSTRUCTURE** 

Drawing Title NOTES - SHEET 1

25/09/2023 6:21:30 AM Date Scale @ A1

Drawing Reference 22071-S-00.01

### TEMPORARY UNSUPPORTED EXCAVATIONS

TEMPORARY UNSUPPORTED EXCAVATION ARE CONTRACTOR DESIGN AND BUILD TO ACHIEVE THE EXCAVATION LEVELS. RECOMMENDATIONS FOR UNSUPPORTED EXCAVATIONS ARE PROVIDED IN THE GEOTECHNICAL REPORTS ??????? PREPARED BY: ????????? FOR PRELIMINARY DESIGN PURPOSES ONLY. SPECIFIC REQUIREMENTS SHOULD BE

ADVISED BY AN EXPERIENCED GEOTECHNICAL ENGINEER FOR EVERY EXCAVATION AND ASSESSED AS THE WORKS PROCEED. ACTUAL LEVEL OF LOW STRENGTH SANDSTONE TO FILL BE ASSESSED BY AN RESIDUAL EXPERIENCED GEOTECH. SOIL ENGINEER DURING EXCAVATION AT SUBCONTRACTORS COST. SAFE WORKING ZONE, 600mm LOW MINIMUM STRENGTH \_ FUTURE CONSTRUCTION SANDSTONE OR BETTER LEVEL OF **EXCAVATION** 

<`/ / `/ / `/ / `/ / `/ /

VARIES, REFER PLAN

### UNSUPPORTED TEMPORARY EXCAVATION

- TUE1 AN EXPERIENCED GEOTECHNICAL ENGINEER SHOULD CARRY OUT CONTINUOUS INSPECTIONS AS THE EXCAVATION PROCEEDS.
- TUE2. ALL RECOMMENDATION ON BATTERS OR ADDITIONAL STABILISATION OF VERTICAL CUTS BY THE GEOTECHNICAL ENGINEER ARE TO BE CARRIED OUT IMMEDIATELY. THE GEOTECHNICAL ENGINEER SHOULD REVIEW AND CERTIFY THAT STABILISATION WORKS HAVE BEEN CONSTRUCTED CORRECTLY.
- TUE3. TEMPORARY EXCAVATION MAY BE OPEN FOR AN EXTENDED PERIOD OF TIME AND MUST PROVIDE A SAFE WORKING ENVIRONMENT FOR ALL PERSONNEL REQUIRED TO WORK INSIDE THE EXCAVATION. EXCAVATION SHOULD BE DRY.
- TUE4. THE EXCAVATION SHOULD BE CONSTANTLY MONITORED FOR ANY SIGN OF DISTRESS OR LOCALISED COLLAPSE. ANY SUCH SIGNS MUST BE REPORTED IMMEDIATELY AND WORKERS INSTRUCTED TO LEAVE THE EXCAVATION.
- TUE5. A SERIES OF LADDERS OR STAIRS SHOULD BE PROVIDED TO ENABLE ACCESS AND EXIT. THESE SHOULD BE PROVIDED AT SUITABLY CLOSE CENTRES.
- TUE6. A SAFETY AND RISK ASSESSMENT SHOULD BE UNDERTAKEN BY THE CONTRACTOR AND MEASURES PROPOSED TO ELIMINATE OR CONTROL THE HAZARDS.

### STRUCTURAL INSPECTIONS DURING CONSTRUCTION

SIN1 UNLESS AGREED OR SPECIFIED OTHERWISE, THE BUILDER IS REQUIRED TO HOLD CONSTRUCTION AND NOTIFY THE STRUCTURAL ENGINEER FOR INSPECTION AT THE FOLLOWING POINTS:

COMPLETED EXCAVATION, FORMWORK, REINFORCEMENT, MEMBRANES AND EMBEDMENTS PRIOR TO PLACING CONCRETE.

COMPLETED ERECTED STRUCTURAL. TIMBER FRAMING PRIOR TO COVERING (UNLESS COVERED BY AS1684 NATIONAL TIMBER FRAMING CODE).

COMPLETED ERECTED STRUCTURAL STEELWORK PRIOR TO COVERING.

- SIN2. 48 HOURS NOTICE IS REQUIRED FOR INSPECTION. ALL WORK TO BE INSPECTED MUST BE COMPLETED PRIOR TO THE TIME OF INSPECTION.
- SITE INSPECTIONS DO NOT RELIEVE THE BUILDER OF RESPONSIBILITY FOR THE SIN3 COMPLETENESS AND CORRECTNESS OF HIS WORK.
- INSPECTIONS WILL BE PERIODIC AND REPRESENTATIVE AND WILL NOT SIN4 NECESSARILY BE MADE OF ALL WORKS. ELECTION TO INSPECT OR OTHERWISE WILL BE AT THE ENGINEER'S DISCRETION. THE BUILDER IS TO ALLOW TIME AND PROVIDE SITE ACCESS FOR THE INSPECTION TO TAKE PLACE AND IS TO HAVE A RESPONSIBLE SITE FOREMAN AVAILABLE TO RECEIVE ANY COMMENT OR DIRECTION FROM THE ENGINEER.
- SIN5. WHERE STRUCTURAL ELEMENTS ARE DESIGNED AND CERTIFIED BY OTHER PARTIES. THE BUILDER SHALL OBTAIN WRITTEN CERTIFICATION. PRIOR TO PROCEEDING WITH ANY CONSTRUCTION WHICH MAY PREVENT INSPECTION OR REMEDIAL WORKS BEING UNDERTAKEN TO THESE ITEMS.

### SUBGRADE PREPARATION - CLAY

- S1 STRIP ALL VEGETATION, TOPSOIL OR OTHER DELETERIOUS MATERIAL TO SPOIL OR STOCKPILE IF SUITABLE FOR REUSE AS LANDSCAPE. THIS SITE SHOULD THEN BE INSPECTED BY A GEOTECHNICAL ENGINEER OR EXPERIENCED TECHNICIAN AT THE CONTRACTORS EXPENSE TO ENSURE THAT THE STRIPPING IS SATISFACTORY.
- S2. COMPACT THE STRIPPED SURFACE OVER THE PROPOSED FILL AREAS TO AT LEAST 98% STANDARD MAXIMUM DRY DENSITY (SMDD) AT A MOISTURE CONTENT WITHIN 2% OF OPTIMUM MOISTURE CONTENT (OMC)
- S3 THE EXPOSED SURFACE OF THE SITE SHOULD THEN BE PROOF ROLLED AND INSPECTED TO DETECT ANY SOFT AREAS. IF THE PROOF ROLLING IS SATISFACTORY, THEN IN-SITU DENSITY TESTS SHOULD BE CARRIED OUT.
- S4 FILLING SHOULD COMPRISE EXCAVATED CLAY SOILS FROM THE SITE OR IMPORTED FILL AND SHOULD BE PLACED IN LAYERS NOT EXCEEDING 200mm COMPACTED THICKNESS TO AT LEAST 98% SMDD WITH A MOISTURE CONTENT WITHIN 2% OF OMC.
- S5. DENSITY TESTING AT THIS SITE (AREA GREATER THAN 1500m ) SHOULD BE CARRIED OUT IN ACCORDANCE WITH AT LEAST THE MINIMUM FREQUENCY RECOMMENDED IN AS3798 "GUIDELINES ON EARTHWORKS FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENTS", TABLE 8.1 (P.28), IE;

A) ONE TEST PER LAYER OR 200MM THICKNESS PER MATERIAL TYPE PER 2500m<sup>2</sup>; OR

B) ONE TEST PER 500m<sup>3</sup> DISTRIBUTE REASONABLY EVENLY THROUGHOUT DEPTH AND AREA: OR

C) THREE TESTS PER VISIT, WHICHEVER REQUIRES THE MOST TESTS.

THE LEVEL OF ENGAGEMENT FOR A GEOTECHNICAL TESTING AUTHORITY SHOULD BE LEVEL 1 AS THE FILLING OF THE SITE WILL BE CRITICAL TO THE PERFORMANCE OF THE RAFT SLAB FOOTING SYSTEM. THE TESTING OF THE SUBGRADE SHALL BE CARRIED OUT BY AN APPROVED NATA REGISTERED LABORATORY.

### CONSTRUCTION LOADING ON SLABS

- CL1. U.N.O. ON PLANS, SLABS ON GRADE AND SUSPENDED SLABS HAVE BEEN DESIGNED TO SUIT THE END USE AS SHOWN ON THE LOADING NOTES AND HAVE NOT BEEN DESIGNED TO CARRY EXCESS LOADS (EITHER DISTRIBUTED OR POINT LOADS) FROM BUILDERS EQUIPMENT, MATERIALS OR TEMPORARY WORKS
- CL2. IF THE BUILDER WISHES TO STORE MATERIALS OR RUN EQUIPMENT / VEHICLES ON SLABS WHICH ARE IN EXCESS OF THE END USERS REQUIREMENTS THE BUILDER MAY, AT HIS OWN EXPENSE, EITHER: HAVE THE SLAB DESIGN REVISED TO SUIT HIS REQUIREMENTS. BRIDGE OVER THE SLAB DELAY INSTALLATION OF THE SLAB UNTIL LATER IN THE CONSTRUCTION PROGRAMME WITH APPROPRIATE JOINTING BACK PROP THE SLAB DESIGN AND DOCUMENTATION COSTS AND DELAY COSTS ASSOCIATED WITH SUCH WORK WILL BE BORNE BY THE BUILDER.

### SUBGRADE PREPARATION

REMOVE ALL TOP SOIL, VEGETABLE MATTER AND RUBBLE. IDENTIFY AND SP1. REMOVE ANY SOFT AREAS AND PLACE AND COMPACT APPROVED NON-ORGANIC FILL IN ACCORDANCE WITH AS2870.

### TEMPORARY WORKS

- ACOR'S DOCUMENTATION DEPICTS THE "PERMANENT" STRUCTURE. DESIGN AND INSTALLATION OF ALL TEMPORARY WORKS AND PROCEDURES WILL BE THE SOLE RESPONSIBILITY OF THE BUILDER.
- TW2. THE BUILDER MUST ENGAGE NPER QUALIFIED ENGINEER FOR THE DESIGN OF ALL TEMPORARY WORKS NECESSARY TO SAFELY ERECT THIS STRUCTURE, AS A MINIMUM THE FOLLOWING TEMPORARY WORKS REQUIRE ATTENTION FORMWORK / TEMPORARY PROPPING / NEEDLE BEAMS / SCAFFOLDING /HOARDING.
- TW3. BUILDER MUST CONTACT ACOR IF THEY CONSIDER ANY PART OF THE STRUCTURE IS UNSAFE TO ERECT.
- TW4. THE BUILDER WILL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE CAUSED TO ADJOINING BUILDINGS AND ROADWAYS DURING THE INSTALLATION OF THE TEMPORARY WORKS AND THE PERMANENT WORKS.
- TW5. ANY TEMPORARY WORK DETAILS AND PROCEDURES GIVEN IN THESE DRAWINGS ARE FOR THE GUIDANCE OF THE BUILDER ONLY.

### REINFORCED CONCRETE BLOCKWORK

- RB1. ALL WORKMANSHIP SHALL COMPLY WITH AS 3700, AND THE SPECIFICATIONS.
- RB2. ALL BLOCKS SHALL CONFORM TO AS 2733.
- RB3. THE DESIGN STRENGTH OF CONCRETE MASONRY SHALL BE AS FOLLOWS :

ELEMENT	BLOCK STRENGTH GRADE	MORTAR MIX CEMENT:LIME:SAND				
WALLS	15	M3 MORTAR (NORMAL) 1 : 1 : 6 M4 MORTAR (EXPOSURE GRADE) 1 : 0.5 : 4.5				
LAY BOTTOM COURSE OF BLOCKS ON FULL MORTAR BED. ALL PERPENDS SHALI BE FULLY FILLED WITH MORTAR, EXCEPT WHERE REQUIRED FOR WEEPHOLES.						
CLEAN OUT BL	OCKS SHALL BE PROV	IDED AT THE BASE OF ALL REINFORCEI BE CLEANED OF MORTAR PROTRUSION				

- BEFORE GROUTING. RB6. ALL REINFORCED CORES SHALL BE FILLED WITH GROUT. THE GROUT FILLING SHALL BE THOROUGHLY COMPACTED BY MECHANICAL VIBRATOR OR RODDING. UNREINFORCED CORES NEED NOT BE FILLED UNLESS OTHERWISE NOTED.
- RB7. GROUT COVER TO REINFORCEMENT IN BLOCK RETAINING WALLS SHALL BE MAINTAINED BY THE USE OF PLASTIC "BLOCKAID" REINFORCEMENT LOCATION BRACKETS (OR APPROVED EQUIVALENT) AT THE INTERSECTION OF ALL HORIZONTAL AND VERTICAL REINFORCEMENT.
- RB8. GROUT SHALL BE IN ACCORDANCE WITH AS 3600 AND COMPLY WITH THE FOLLOWING :-

CHARACTERISTIC STRENGTH fc = 20 MPa AT 28 DAYS. MAXIMUM AGGREGATE SIZE = 10 mm. SLUMP = 230 mm.

RB9. MAXIMUM CONTINUOUS POUR HEIGHT SHALL BE 3600 mm, STOP POUR 50 mm BELOW TOP OF BLOCK TO PROVIDE KEY FOR THE FOLLOWING POUR.

RB10. BUILDER IS TO PROVIDE TEMPORARY PROPPING TO WALLS WHERE REQUIRED FOR STABILITY DURING CONSTRUCTION.

### VERTICAL JOINTS

RB11. PROVIDE VERTICAL CONTROL JOINTS IN ALL WALLS AT A MAXIMUM OF 8000 mm CENTRES OR AT SLAB JOINTS UNLESS INDICATED OTHERWISE ON THE STRUCTURAL DRAWINGS

### HORIZONTAL JOINTS

- RB12. PROVIDE HORIZONTAL JOINT REINFORCEMENT EVERY THIRD COURSE FOR SOLID OR CORE FILLED BLOCKS
- RB13. REFER TO TYPICAL "REINFORCED BLOCK WALL JUNCTION DETAILS" FOR REINFORCEMENT REQUIREMENTS AT CORNERS AND INTERSECTIONS.
- RB14. REFER TO THE ARCHITECTS SPECIFICATIONS FOR ALL WATERPROOFING DETAILS OF WALLS AS REQUIRED.
- RB15. REFER TO "RETAINING WALL NOTE" FOR ADDITIONAL INFORMATION ON BACKFILLING AND DRAINAGE SYSTEMS BEHIND RETAINING WALLS.
- RB16. REFER TO TYPICAL DETAILS FOR BOND BEAM LINTELS.
- RB17. MASONRY WALLS MUST NOT BE CONSTRUCTED ON SUSPENDED CONCRETE UNTIL ALL TEMPORARY SUPPORTS ARE REMOVED AND ALL MASONRY TO BE LAID HAS BEEN STACKED ADJACENT TO PROPOSED POSITION.

TP1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600. SCOPE OF WORKS PT1. THE SCOPE OF WORKS SHALL CONSIST OF THE DESIGN, INSTALLATION AND TP2. REINFORCEMENT IN TILT-UP PANELS TO BE AS PER TILT-UP SUB-CONTRACTORS CERTIFICATION OF THE POST-TENSIONED PRESTRESSING AND NON-TENSIONED DETAILS. REINFORCEMENT, FOR ALL SUSPENDED FLOOR SLABS SHOWN PT2. THE POST TENSIONED PRESTRESSING AND NON-TENSIONED REINFORCEMENT TP3. TILT-UP PANELS TO BE MAINTAINED IN A STABLE CONDITION BY THE SHALL EXTEND FOR THE FULL PLAN AREA, INCLUDING ALL STRUCTURAL HOBS, CONTRACTOR UNTIL ALL PERMANENT BRACING IS IN PLACE. FOLDS, SET-DOWNS FORMING PART OF THE FLOOR SLAB. TP4. CONNECTION DETAILS FOR TILT-UP PANELS THAT ARE NOT DETAILED ON THE PT3. IT IS THE SUB-CONTRACTORS RESPONSIBILITY TO ENSURE THAT THE POST ENGINEERS DRAWINGS TO BE AS PER TILT-UP SUB-CONTRACTORS DETAILS. TP5. TILT-UP PANELS TO BE DESIGNED TO WITHSTAND ALL FORCES THAT MAY BE INSTALLED AND CERTIFIED IN ACCORDANCE WITH THESE NOTES AND THE APPLIED TO THEM FROM, BUT NOT LIMITED TO THE MAIN STRUCTURAL STEEL ELEMENTS, CONCRETE SLABS AND FORCES DUE TO THE RETENTION OF SOIL. ANCHORAGE ZONES ANTI BURSTING REINFORCEMENT, THE REINFORCEMENT OF ANY SLAB AREAS NOT INCLUDED IN THE PRESTRESSED AREAS. TP6. ANY FORCES APPLIED TO THE STRUCTURAL STEELWORK AND/OR CONCRETE ELEMENTS FROM TILT-UP PANELS TO BE BROUGHT TO THE ATTENTION OF THE DESIGN - DESIGN LOADS ENGINEER AND APPROVAL TO APPLY SUCH FORCE OBTAINED PRIOR TO PT4. ALL LOADS ARE TO BE IN ACCORDANCE WITH THE LOADS NOMINATED ON THE POURING TILT-UP PANELS. STRUCTURAL DRAWINGS, DESIGN BRIEF AND AS1170. TP7. REFER TO ARCHITECTS DRAWINGS FOR ALL PANEL DIMENSIONS, SHAPES, PT5. WHERE COLUMN LOADS ARE NOT NOMINATED ON THE STRUCTURAL DRAWINGS GROOVES, BLOCKOUTS AND FINISHES ETC. IT IS THE SUB-CONTRACTORS RESPONSIBILITY TO CALCULATE LOADS. WHERE TP8. JOINTS BETWEEN PANELS TO BE SEALED USING APPROVED FILLER. BACKING LOADS ARE CALCULATED BY THE SUB-CONTRACTOR LOADS ARE TO BE ISSUED ROD AND SEALANT, BY THE TILT-UP PANEL SUB-CONTRACTOR. TO ACOR FOR REVIEW PRIOR TO COMMENCEMENT OF DESIGN. SERVICEABILITY TP9. ALL LIFTING AND PROPPING ANCHORS THAT ARE EXPOSED AT THE FINAL STAGE ARE TO BE APPROVED BY THE ARCHITECT. TP10. PANEL CONTRACTOR TO ALLOW FOR ANY ADDITIONAL CONCRETE (PAD FOOTINGS OR SLAB THICKENINGS) THAT MAY BE REQUIRED TO FACILITATE TEMPORARY PANEL PROPPING AND LIFTING/PLACING REQUIREMENTS. PRECAST PANELS PP1. ALL PANELS ARE DETAILED WITH INSIDE OR BRACING FACE UP U.N.O. PP2. ANY VARIATIONS TO DIMENSIONS, SPECIFIED PRODUCTS, RIGGING ETC, SHALL BE APPROVED BY THE ENGINEER. PP3. CONCRETE SHALL BE AS NOTED IN CONCRETE NOTES C2. PT6. COLUMN STIFFNESS: MINIMUM CONCRETE STRENGTHS REQUIRED PRIOR TO LIFTING ARE :-MODULUS OF RUPTURE 3.45MPa ANY CONTRIBUTION OF THE COLUMNS IN THE FLOOR SLAB / BEAM DESIGN а COMPRESSIVE STRENGTH 20MPa SHALL BE LIMITED TO A MAXIMUM OF 20% OF THE GROSS COLUMN STIFFNESS. b. PT7. MINIMUM PRESTRESS: PP4. CRANAGE: ALL SLABS SHALL HAVE AN AVERAGE RESIDUAL PRESTRESS IN EACH THE SIZE AND TYPE OF CRANE SHALL BE DETERMINED BY OTHERS ALLOWING DIRECTION AFTER ALL LOSSES OF: FOR ALL CONDITIONS, IN PARTICULAR: P/A > 1.5MPA FOR ALL INTERNAL AREAS FULLY ENCLOSED WEIGHT OF PANELS AND REACH REQUIRED FOR ERECTION WHILST P/A > 1.8MPA FOR ALL EXTERNAL AREAS MAINTAINING LOAD LINE OVER THE CENTRE OF THE LIFT. PT8. PROVIDE MINIMUM SL82 MESH (TOP) TO ALL EXTERNAL AREAS. AVOIDANCE OF SLIDING OR JERKING. SITE CONDITION AND OBSTRUCTIONS PT9 ALL TENDONS AND REINFORCEMENT SHALL HAVE CONCRETE COVER IN ACCORDANCE WITH AS3600 FOR THE FOLLOWING EXPOSURE CLASSIFICATIONS: PP5. LIFTING DESIGN ASSUMPTION: INTERNAL - A1 NO BOND BETWEEN PANEL AND CASTING SURFACE EXTERNAL - B1 NO SHRINKAGE CRACKS PT10. ALL TENDONS AND REINFORCEMENT SHALL HAVE CONCRETE COVER IN NO IMPACT LOADS DURING ERECTION ACCORDANCE WITH AS3600 TO PROVIDE A 180 MINUTE FIRE RESISTANCE PERIOD. PP6. NO LIFTING OR BRACING EQUIPMENT SHALL BE USED IF DAMAGED. PT11. UNDER ALL PRECAST & MASONRY WALLS ENSURE CONCRETE ZONE NO WELDING OR APPLICATIONS OF HEAT SHALL BE PERMITTED TO ANY PP7. IMMEDIATELY BELOW THE WALLS DOES NOT HAVE POST TENSIONING DUCTS SPECIFIED INSERTS OR EQUIPMENT. PARALLEL TO THE WALL PT12. THE CONCRETE STRENGTH SHALL BE THE SAME AS THAT SHOWN ON THE PP8. ALL FLOOR BRACE INSERTS SHALL BE NOT LESS THAN 600mm FROM JOINTS. STRUCTURAL DRAWINGS. PP9. REFER TO ARCHITECTS DRAWINGS FOR SILL BEVEL, REBATE AND SPITTER PT13. THE SUB-CONTRACTOR IS TO ALLOW TO COORDINATE DESIGN WITH ALL OTHER DETAILS. CONSULTANTS AND SUB-CONTRACTORS DRAWINGS. PP10. PRECAST PANELS SHALL COMPLY WITH AS 3850. PT14. THE SUB-CONTRACTOR MUST SUBMIT ONE COPY OF THE TENDON AND REINFORCEMENT PLANS FOR APPROVAL 14 DAYS PRIOR TO COMMENCEMENT OF SURFACE QUALITY: ANY INSTALLATION WORK. PLANS MUST SHOW ALL TENDONS - LOCATION, SIZE DIMENSIONAL TOLERANCES OF PANELS SHALL COMPLY WITH TABLE AND DRAPE, AND ALL NON-TENSIONED REINFORCEMENT. INSTALLATION WORK 3.7.1 OF AS 3850. HENCE CASTING BEDS (FLOOR SLABS, PAVEMENTS MAY NOT COMMENCE UNTIL THE APPROVED LAYOUT PLANS, INCORPORATING AND TEMPORARY CASTING BEDS) MUST BE POURED TO TOLERANCES ANY REQUIREMENTS, ARE RETURNED TO THE SUB-CONTRACTOR. ALLOW 7 DAYS WHICH WILL REFLECT THE REQUIRED SURFACE FINISHES OF THE FOR THE REVIEW AND APPROVAL OF DRAWINGS. THE REVIEW AND APPROVAL PANELS. OF THE DRAWINGS DOES NOT RELIEVE THE SUBCONTRACTOR OF THEIR ALL PRECAST PANELS, FLOOR SLABS AND CASTING BEDS SHALL HAVE RESPONSIBILITY. A STEEL TROWELLED FINISH WHICH DOES NOT EXHIBIT TROWEL MARKS, NOR, IN THE CASE OF FLOORS AND CASTING BEDS, REFLECT PT15. ALL DESIGNS ARE TO BE PREPARED AND CERTIFIED BY A PROFESSIONAL TROWEL MARKS IN THE PANELS POURED ON THEM. STRUCTURAL ENGINEER WITH NPER REGISTRATION. CERTIFICATION IS TO BE PROVIDED PRIOR TO COMMENCEMENT OF INSTALLATION THAT THE FLOOR IN ADDITION WITH COMPLYING WITH THE DEFLECTION LIMITS OF AS C. 3600 SECTION 24.9. SURFACE IMPERFECTIONS ON FORMED AND STRUCTURE IS STRUCTURALLY ADEQUATE TO RESIST THE DESIGN LOADS IN TROWELLED SURFACES SHALL NOT EXCEED THOSE SPECIFIED FOR ACCORDANCE WITH ALL RELEVANT AUSTRALIAN STANDARDS. THE CERTIFYING ENGINEER SHALL MAINTAIN PROFESSIONAL INDEMNITY INSURANCE OF AT LEAST THE RELEVANT CLASSIFICATION OF FORMWORK REQUIRED BY ARCHITECT IN AS 3610. \$5.0 MILLION AND PROVIDE A COPY OF THEIR INSURANCE CURRENCY. <u>CONSTRUCTION</u> PP12. ALL PRECAST PANELS SHALL BE GROUTED TO PROVIDE A CONTINUOUS PT16. ALL WORKMANSHIP AND MATERIALS MUST COMPLY WITH AS3600. BEARING UNDER THE FULL WIDTH OF THE PANELS. WHERE PANELS SUPPORT SUSPENDED SLABS GROUTING SHALL BE ADEQUATELY CURED PRIOR TO PT17. PRESTRESSING STRANDS SHALL BE STRESS RELIVED SUPER GRADE AND REMOVAL OF FORMWORK. LOCATION OF SHIMS ARE ONLY ALLOWED AT COMPLY WITH AS4672 POSITIONS SHOWN ON THE DRAWINGS. PT18. ALL TENDONS SHALL BE PLACED IN A GALVANIZED DUCT. PP13. PANEL LIFTING SHALL BE CARRIED OUT USING THE FOLLOWING METHOD PT19. ALL TENDONS AND REINFORCEMENT MUST BE SECURELY POSITIONED AND STATEMENT: FIXED PRIOR TO PLACEMENT OF CONCRETE.

### **TILT-UP PANELS**

C.

- WITH THE CRANE LOAD DIRECTLY OVER THE CENTRE OF THE LIFT, THE CRANE SHALL BE SET TO THE INITIAL LIFT LOAD. STEEL WEDGES SHALL THEN BE PLACED AGAINST THE PANEL AND FLOOR AT AND/OR NEAR THE TOP OF THE PANEL AND STRUCK UNTIL
- SUCTION BETWEEN THE PANEL AND THE FLOOR SLAB HAS BEEN RELIEVED. LIFTING MANY THEN PROCEED.
- PP14. ALL REINFORCEMENT SHOWN ON THE STRUCTURAL DRAWINGS IS FOR IN-
  - SERVICE LOADING ONLY. THE PRECAST PANEL CONTRACTOR IS RESPONSIBLE FOR THE DESIGN OF ANY ADDITIONAL REINFORCEMENT WHICH MAY BE REQUIRED TO ENSURE LIFTING STRESSES ARE WITHIN THE RELEVANT CODES AND ALL BRACING AND SUPPORTING STRUCTURES (DEADMAN OR FLOOR SLAB) ARE STRUCTURALLY ADEQUATE TO SUPPORT ALL RELEVANT WIND LOADINGS. THE SUB CONTRACTOR SHALL PROVIDE AN ENGINEERS CERTIFICATE (WITH THEIR REGISTERED NUMBER) FOR ALL THESE ITEMS TO THE BUILDER AND FORWARD A
  - COPY TO ACOR CONSULTANTS PTY LTD CERTIFYING THAT THEY COMPLY WITH AS 3850, AS 3608 AND AS/NZS 1170.2. ACOR CONSULTANTS PTY LTD ARE UNABLE TO REVIEW OR SIGN OFF PANEL

SHOP DRAWINGS UNTIL WE RECEIVE THIS DESIGN CERTIFICATION.

POST TENSIONED CONCRETE - DESIGN AND CONSTRUCT

- TENSIONED PRESTRESSING AND NON-TENSIONED REINFORCEMENT IS DESIGNED, REQUIREMENTS OF AS3600. THE NON-TENSIONED REINFORCEMENT INCLUDES ALL

AREA	DEFLECTION CRITERIA		
	INCREMENTAL DEFLECTION	LONG TERM DEFLECTION	
OFFICE	LESS THAN SPAN/500 UNDER ALL MASONRY WALL	LESS THAN SPAN/300 OR 25mm	
PODIUM	LESS THAN SPAN/1000 UNDER COLUMN TRANSFERS	LESS THAN SPAN/300 OR 25mm	
	LESS THAN SPAN/1000 UNDER COLUMN TRANSFERS		

- PT20. STRESSING RECORDS OF THE PRESSURE GAUGE AND EXTENSIONS SHALL BE ACCURATELY MADE
- PT21. ALL TENDONS MUST BE GROUTED IN THEIR DUCTS AFTER APPROVAL OF THE STRESSING RECORDS.
- PT22. ALL ANCHORAGE RECESSES AND PANS MUST BE FILLED WITH 30MPA GROUT, FINISHED TO A SMOOTH AND LEVEL SURFACE.
- PT23. UPON COMPLETION PROVIDE AN AS BUILT DRAWING OF ALL DUCT LOCATIONS FOR CO-ORDINATION BY OTHER SUB-CONTRACTORS.
- PT24. A PROFESSIONAL ENGINEER WITH NPER REGISTRATION SHALL INSPECT ALL WORKS AND CERTIFY THAT THE PRESTRESSING AND REINFORCEMENT AS INSTALLED IN THE SLAB COMPLIES WITH THE APPROVED CONSTRUCTION DRAWINGS, IN PARTICULAR, THAT ALL TENDONS AND REINFORCEMENT WERE ACCURATELY POSITIONED WITH THE CORRECT COVER AND THAT ALL TENDONS HAVE BEEN CORRECTLY STRESSED AND GROUTED. THE CERTIFYING ENGINEER SHALL MAINTAIN PROFESSIONAL INDEMNITY INSURANCE OF AT LEAST \$5.0 MILLION AND PROVIDE A COPY OF THEIR INSURANCE CURRENCY.





ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

ssu	е		
No.	Date	Description	Cł
1	13.02.2023	SCHEMATIC DESIGN	ZF
2	15.06.2023	50% DESIGN DEVELOPMENT	TE
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤE
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	TE





nbrs.com.au

ABN 16 002 247 565

# Health Infrastructure GOVERNMENT

Project CONCORD REPATRIATION GENERAL HOSPITAL

NSV

109 HOSPITAL ROAD, NSW 2139

**NSW GOVERNMENT HEALTH & INFRUSTRUCTURE** 

Drawing Title NOTES - SHEET 2

25/09/2023 6:21:30 AM Date @ A1 Scale

Drawing Reference 22071-S-00.02

### FORMWORK

- FW1. THE DESIGN, CERTIFICATION, CONSTRUCTION, INSPECTION AND PERFORMANCE OF THE FORMWORK AND FALSE WORK SHALL BE CERTIFIED BY AN NPER STRUCTURAL ENGINEER AND IS THE RESPONSIBILITY OF THE BUILDER, EXCEPT TO THE EXTENT THAT FORMWORK DESIGN IS SHOWN ON THE STRUCTURAL DRAWINGS.
- FW2. FORMWORK DESIGN, CONSTRUCTION, TOLERANCES AND STRIPPING TIMES SHALL COMPLY WITH AS3610 AND AS3600 UNLESS OTHERWISE APPROVED BY THE STRUCTURAL ENGINEER.
- CONCRETE FORMED SURFACE FINISHES SHALL COMPLY WITH AS3610 AS FW3. SPECIFIED BY THE PROJECT ARCHITECT.
- DIMENSIONAL TOLERANCES SHALL COMPLY WITH AS3610 FOR APPROPRIATE FW4. FINISH CLASS.
- FORMWORK SHALL BE DESIGNED TO ACCOMMODATE MOVEMENTS AND LOAD FW5. REDISTRIBUTION DUE TO POST-TENSIONING.
- FORMWORK SHALL NOT BE DESIGNED TO RELY ON RESTRAINT OR SUPPORT FW6. FROM THE PERMANENT STRUCTURE WITHOUT PRIOR APPROVAL FROM THE ENGINEER.
- FW7. WHERE METAL FORMWORK IS SHOWN IE BONDEK, CONDEK, KINGFLOOR ETC IS SHOWN, THE CONTRACTOR SHALL INSTALL AND PROP THE WORKS IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATION UNLESS NOTED OTHERWISE ON THE STRUCTURAL DRAWINGS
- DESIGN INFORMATION CONCERNING THE FOUNDATIONS FOR FORMWORK SHALL FW8 BE DETERMINED FROM THE CONDITIONS EXISTING ON SITE AT THE TIME OF CONSTRUCTION. REFER TO THE GEOTECHNICAL REPORT FOR THE SITE.
- DURING CONSTRUCTION PROVIDE PROPPING WHERE LOADS FROM STACKED FW9. MATERIALS, FORMWORK AND OTHER SUPPORTED SLABS INDUCE LOADS IN THE SLAB OR BEAM WHICH EXCEED THE DESIGN LOAD FOR STRENGTH OR SERVICEABILITY AT THAT AGE. ONCE THE NOMINATED 28 DAY STRENGTH HAS BEEN ATTAINED, THESE LOADS SHALL NOT EXCEED THE DESIGN SUPERIMPOSED LOADS SET-OUT IN THE STRUCTURAL DESIGN LOADS.
- FW10. IN MULTI-STOREY CONSTRUCTION PROPPING MAY NEED TO EXTEND A NUMBER OF FLOORS LEVELS BELOW THE FLOOR BEING CAST. PROP REMOVAL IS TO BE PROGRAMMED TO AVOID DISTRESS TO PREVIOUSLY CAST FLOORS, RE-SHORING OR BACK-PROPPING IS SUBJECT TO THE STRUCTURAL ENGINEER.
- FW11. DO NOT PLACE PERMANENT LOADS ON THE CONCRETE STRUCTURE UNTIL AFTER FORMWORK AND PROPPING IS REMOVED.
- FW12. REFER TO ARCHITECTS DRAWINGS FOR TEST PANEL DETAILS. REINFORCEMENT FOR TEST PANELS SHALL BE SIMILAR TO THAT IN THE PERMANENT STRUCTURE BEING REPRESENTED
- FW13. BEFORE PLACING REINFORCEMENT IN FORMWORK, APPLY A RELEASE AGENT TO THE FACE OF THE FORMWORK COMPATIBLE WITH THE REQUIRED SURFACE FINISH
- FW14. CHAMFER RE-ENTRANT ANGLES AND FILLETS AT CORNERS BY 25MM UNO.
- FW15. BEFORE PLACING CONCRETE, REMOVE ALL WATER, DUST AND DEBRIS FROM THE FORMWORK.
- FW16. FILL ALL HOLES LEFT BY FORM TIE BOLTS WITH MORTAR MATCHING THE SURFACE COLOUR OF THE FINISHED SURFACE.
- FW17. CONCRETE FORMED SURFACES TO HAVE THE FOLLOWING FINISHES IN ACCORDANCE WITH AS 3610.

FW18.	ELEMENT	SURFACE FINISH	CRITICAL FACE
	FOOTING BEAMS	CLASS 3	EXPOSED FACE
	SLABS AND BEAMS	REFER TO ARCHITECTS SI	PECIFICATIONS

### STRUCTURAL STEELWORK

ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH STEEL S1. STRUCTURE - AS 4100 AND WELDING - AS 1554 EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENT.

S2. STEEL COMPONENTS SHALL CONFORM TO THE FOLLOWING TABLE U.N.O. COMPONENT AUS. STAND. GRADE PLATE 3678 250 HOT ROLLED SECTIONS 300 3679 C350 CHS > 80 mm DIA. 1163 CHS < 80 mm DIA. 1163 C250 RHS & SHS 1163 C350 **PURLINS & GIRTS** 1397 450 WELDED BEAMS & COLUMNS 3679 300 250 FLAT BARS & RODS. 3679

S3. BOLT DESIGNATION

ALL BOLTS TO BE 8.8/S UNLESS NOTED OTHERWISE

- COMMERCIAL BOLTS OF GRADE 4.6 TO AS 1111 SNUG TIGHTENED. 4.6/S 8.8/S HIGH STRENGTH STRUCTURAL BOLTS OF GRADE 8.8 TO AS 1252 SNUG
- TIGHTENED. 8.8/TB HIGH STRENGTH BOLTS OF GRADE 8.8 TO AS 1252 FULLY TENSIONED
- TO AS 4100 AS A BEARING JOINT. HIGH STRENGTH STRUCTURAL BOLTS OF GRADE 8.8 TO AS 1252 FULLY 8.8/TF TENSIONED TO AS 4100 AS A FRICTION JOINT WITH CONTACT SURFACES LEFT UNCOATED.
- ALL BOLTS SHALL BE M20 GRADE 8.8/S U.N.O. S4. ALL STUDS SHALL BE M20 GRADE 4.6/S U.N.O.
- NO STEEL TO STEEL CONNECTION TO HAVE LESS THAN 2 BOLTS.
- ALL PLATES TO BE 10 mm THICK U.N.O. S5.
- S6. UNLESS NOTED OTHERWISE, ALL FILLET WELDS SHALL BE 6mm CONTINUOUS FOR PLATES LESS THAN OR EQUAL TO 12 PL 8mm CONTINUOUS FOR 16 PL

10mm CONTINUOUS FOR 20 PL AND ABOVE.					
ELEMENT	WELD CATEGORY				
ALL	SP				

ALL BUTT WELDS TO BE COMPLETE PENETRATION BUTT WELDS. ELECTRODES TO BE E48XX U.N.O. WELD CATEGORY AS TABULATED ABOVE.

- **S**7 THE CONTRACTOR SHALL MAKE THE NECESSARY ALLOWANCES FOR COORDINATING ALL ARCHITECTURAL & STRUCTURAL ELEMENTS IN THE PREPARATION OF STRUCTURAL STEELWORK SHOP DRAWINGS & SUBSEQUENT FABRICATION & ERECTION. CONNECTION DETAILS SHOWN ON STRUCTURAL DRAWINGS ARE TYPICAL ONLY. WHERE A DETAIL IS NOT SHOWN THE FABRICATOR / SHOP DETAILER SHALL PREPARE DETAILS IN ACCORDANCE WITH AS4100 & THE AISC PUBLICATIONS 'DESIGN OF STRUCTURAL CONNECTIONS' & 'STANDARDISED STRUCTURAL CONNECTIONS'. THESE DETAILS SHALL TAKE DUE ACCOUNT OF ARCHITECTURAL & SERVICE REQUIREMENTS & SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL. THE ENGINEER WILL SUPPLY LOADS AS REQUIRED. ALL COSTS & TIME IMPLICATIONS ASSOCIATED WITH THESE WORKS ARE TO BE ALLOWED FOR BY THE CONTRACTOR.
- STRUCTURAL STEELWORK SHALL HAVE THE FOLLOWING TREATMENT: S8.

ELEMENT	SURFACE PREPARATION	PROTECTIVE COATING
INTERIOR MEMBERS	BLAST CLEAN TO CLASS 2 (AS 1627)	ZINC PHOSPHATE PRIMER FILM THICKNESS 0.075mm
EXPOSED TO WEATHER INCLUDING ALL STIFFENERS	PICKLE (AS 1627 PART 5)	HOT DIP GALVANISED REFER TO SPECIFICATIONS.

- S9. ALL STRUCTURAL STEELWORK WHICH IS EXPOSED. STEELWORK IN CONTACT WITH EXTERNAL CAVITY BRICKWORK & ALL LINTELS SHALL BE HOT DIP GALVANISED OR STAINLESS STEEL - REFER TO DRAWINGS. GALVANISING OF STRUCTURAL SECTIONS SHALL BE IN ACCORDANCE WITH AS 4680 AND THE GALVANISING OF THREADED FASTENERS SHALL BE IN ACCORDANCE WITH AS 1214
- S10. AFTER FABRICATION ALL EXPOSED STEELWORK AND STEELWORK BUILT IN EXTERNAL WALLS INCLUDING FITMENTS, NUTS, BOLTS, WASHERS AND HOLDING DOWN BOLTS TO BE HOT DIP GALVANISED.
- ANY FURTHER WELDED JOINTS ARE TO BE PAINTED WITH 2 COATS OF S11. APPROVED GALVANISED PAINT.
- THE ENDS OF ALL TUBULAR MEMBERS ARE TO BE SEALED WITH NOMINAL S12. THICKNESS PLATES AND CONTINUOUS FILLET WELD UNLESS OTHERWISE SHOWN ON THE DRAWINGS.
- S13. THE SUB-CONTRACTOR SHALL PROVIDE ALL CLEATS AND DRILL ALL HOLES NECESSARY FOR ALL ATTACHMENTS WHETHER OR NOT DETAILED ON THE DRAWINGS.
- PROVIDE HOOK BOLTS AT EVERY THIRD PURLIN TO CONTROL BRACE SAG. S14.
- ALL STEELWORK IS TO BE TEMPORARILY BUT SECURELY BRACED UNTIL ALL S15. FINAL BRACING, CLADDING & STABILISING BRICK OR BLOCKWORK HAVE BEEN COMPLETED.
- S16. GRAVITY &/OR GAUGE LINES TO INTERSECT U.N.O.
- S17 CONCRETE ENCASED STEELWORK TO BE WRAPPED WITH F41 MESH & TO HAVE 50mm MIN. COVER OF CONCRETE GRADE 25 TO AS3600
- ALL BASEPLATES ARE TO BE FULLY GROUTED WITH CONBEXTRA GP S18. CEMENTITIOUS NON-SHRINK GROUT, OR SIMILAR, WITH A MINIMUM COMPRESSIVE STRENGTH OF 50 MPa
- SHOP DRAWINGS SHALL BE PREPARED BY THE FABRICATOR FOR ALL S19. STRUCTURAL STEELWORK. SUBMIT COPIES OF ALL WORKSHOP DRAWINGS TO ACOR CONSULTANTS FOR STRUCTURAL APPROVAL AT LEAST 14 DAYS PRIOR TO FABRICATION. DO NOT FABRICATE STEELWORK UNTIL WORKSHOP DRAWINGS ARE APPROVED.

PURLINS AND GIRTS S20. PROPERTIES S21. S22 S23. S24.









S29. S30.

\$31

NOGGINGS ETC. ROOF SAFETY ACCESS SYSTEMS A ROOF SAFETY ACCESS SYSTEM WHICH COMPLIES WITH THE RELEVANT OH&S RS1. REGULATIONS FOR FALL ARREST AND THE RELEVANT AUSTRALIAN STANDARDS IS TO BE INSTALLED AND CERTIFIED BY AN APPROPRIATELY EXPERIENCED SPECIALIST SUPPLIER.

# **GROUTING OF BASE PLATES**

GB1. GB3.

RS2.

### STRUCTURAL STEELWORK CONT'

- ALL PURLINS AND GIRTS TO BE COLD FORMED LIGHT-GAUGE STEEL SECTIONS CONFORMING TO ANZ4600 FOR DESIGN AND TO AS1397 FOR MATERIAL
- THE OVERALL DIMENSIONS OF PURLINS AND GIRTS SHALL NOT BE LESS THAN THE NOMINAL SIZE GIVEN, BOTH FLANGES SHALL BE LIPPED
- SETOUT OF PURLINS & GIRTS TO BE OBTAINED FROM ARCHITECT'S DRAWINGS OR ROOFING CONTRACTOR
- PROVIDE TRIMMER PURLINS BETWEEN MAIN PURLINS TO SUIT ROOF PROFILE(HIPS, VALLEYS, RIDGE LINES ETC.) AND CONNECT WITH PROPRIETARY CLEATS AS RECOMMENDED BY MANUFACTURER
- WHERE NECESSARY TO HANG CEILING, SERVICE PIPES, DUCTWORK ETC. FROM PURLINS, THE BUILDER SHALL ONLY USE THE FOLLOWING APPROVED METHODS.

INSTALLATION.

### FIRE PROTECTION

FIRE PROTECTION REQUIREMENTS TO STEELWORK ARE TO BE AS PER FIRE ENGINEERS DETAILS OR ARCHITECTURAL SPECIFICATIONS.

### LIGHT WEIGHT STEEL FRAMING

- UNLESS SPECIFICALLY DETAILED ON THE STRUCTURAL DRAWINGS, ALL STEEL STUD WALL FRAMING AND FIXINGS SHALL BE AS MANUFACTURED BY 'RONDO BUILDING SERVICES PTY. LTD.' OR EQUIVALENT, ALL TO BE IN ACCORDANCE WITH THEIR DESIGN MANUAL AND INSTALLATION MANUALS FOR STEEL STUD WALL SYSTEMS.
- THE DESIGN SHALL COMPLY WITH AS4600, TO SUIT THE LOADS SPECIFIED IN THE GENERAL NOTES AND THE SPECIFICATION. AN NPER STRUCTURAL ENGINEER SHALL CERTIFY THE DESIGN. PROVIDE ALL TRIMMERS, HEADS,

- THE DESIGN BY THE SPECIALIST IS TO INCLUDE SYSTEM SELECTION, LAYOUT, INSTALLATION, FLASHING, STRENGTHENING WORKS AND CERTIFICATION.
- ALL GROUT SHALL BE CURED BY THE APPLICATION OF 'MBT AUSTRALIA' 'FLOORSEAL' APPLIED TO THE GROUT STRICTLY IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN PROCEDURE.
- GB2. THE THICKNESS OF THE GROUT BED SHALL BE 50mm.
  - GROUT ALL STEEL BASES BY DRY PACKING USING GROUT WHICH IS NON-SHRINK AND HAS A MINIMUM COMPRESSIVE STRENGTH AT 7 DAYS OF 40 Mpa

### DRILLED IN CHEMICAL AND MECHANICAL ANCHORS

- DA1. DRILLED ANCHORS SHALL BE USED WHERE SHOWN ON THE DRAWINGS, OR WHERE PERMITTED IN WRITING BY THE ENGINEER. SUBMIT DETAILS OF PROPOSED ANCHORS, BEFORE USE, IN WRITING, TO THE ENGINEER FOR REVIEW. INSTALL ANCHORS IN ACCORDANCE WITH MANUFACTURER'S WRITTEN DIRECTIONS. TEST ANCHORS AS SPECIFIED BELOW.
- DA2. SPACING AND EDGE DISTANCES SHALL BE AS SHOWN, OR IN ACCORDANCE WITH THE MANUFACTURERS DIRECTIONS, AND SHALL BE APPROPRIATE FOR THE LOAD ON THE ANCHOR. UNLESS SHOWN OTHERWISE OR ALLOWED BY THE MANUFACTURER, THE FOLLOWING MINIMUMS SHALL BE USED FOR M20 CHEMICAL ANCHORS IN CONCRETE: SPACING=150mm, EDGE DISTANCE=150mm.
- DA3. FOR ATTACHMENT TO HOLLOW MASONRY OR CONCRETE PANELS, USE HILTI HIT HY20 OR EQUIVALENT.
- HOLES IN STEELWORK SHALL BE: DA4. 2mm OVERSIZE WHEN THE STEEL IS TO BE USED AS A DRILLING TEMPLATE, OR 6mm MAXIMUM OVERSIZE WHERE THE BOLTS ARE INSTALLED BEFOREHAND.

### DRILLED-IN ANCHOR TESTING DA5.

ANCHOR TESTING LOAD TO BE 150% OF SAFE WORKING LOAD OR 100% OF ULTIMATE LOAD, TO MANUFACTURER'S PRODUCT SPECIFICATION. TESTS TO BE CARRIED OUT BY N.A.T.A. REGISTERED LABORATORY AT THE CONTRACTOR'S EXPENSE.

### CHEMICAL ANCHORS

NUMBER OF CHEMICAL ANCHORS TO BE TESTED IS AS FOLLOWS: INSTALLATION FROM ABOVE AND SIDE = 20% OF TOTAL NUMBER IS TO BE TESTED.

INSTALLATION FROM BELOW = 100% OF TOTAL NUMBER IS TO BE TESTED

### MECHANICAL ANCHORS

TEST 10% OF MECHANICAL ANCHORS

### FAILURE

IF ONE ANCHOR IN A GROUP FAILS UNDER TESTING THEN ALL ANCHORS SHALL BE TESTED. AS SPECIFIED ABOVE. AT THE CONTRACTOR'S EXPENSE. ALL ANCHORS THAT FAIL ARE TO BE REPLACED AND RETESTED. FORWARD CERTIFICATES OF ALL TEST RESULTS TO ACOR CONSULTANTS.

### STRUCTURAL DESIGN LOADS

- THE STRUCTURAL COMPONENTS DETAILED ON THESE DRAWINGS HAVE BEEN L1. DESIGNED IN ACCORDANCE WITH THE RELEVANT STANDARDS AUSTRALIA CODE AND THE BUILDING CODE OF AUSTRALIA FOR THE FOLLOWING LOADINGS. REFER TO ARCHITECTURAL DRAWINGS FOR PROPOSED FLOOR USAGE.
- SUPERIMPOSED LOADS IN ACCORDANCE WITH AS1170.1 L2.

FLOOR USAGE	SUPERIMPOSED DEAD LOAD (kPa)	LIVE LOAD (kPa)
GENERAL FLOOR AREA	1.8	2.0
OFFICE AREA	1.8	3.0
STAIRS LANDINGS	4.0	0.0
ROOF	1.0	0.25
PLANT AREA	2.4	7.5

WIND LOADS IN ACCORDANCE WITH AS1170.2 L3.

REGION		A2	
STRUCTURAL IMPORTANCE LEVEL		2	
REGIONAL WIND SPEED	Vr (ULTIMATE)	46	m/s
	Vr (SERVICEABILITY)	37	m/s
TERRAIN CATEGORY		VARIES	6
TERRAIN / HEIGHT MULTIP	LIER	1	
SHIELDING MULTIPLIER		1	
TOPOGRAPHIC MULTIPLIE	R	1	
HILL-SHAPE MULTIPLIER		1	

EARTHQUAKE DESIGN PARAMETERS TO AS1170.4 L4.

STRUCTURAL IMPORTANCE LEVEL		2
PROBABILITY FACTOR	kp	1.0
HAZARD FACTOR	Z	0.08
SITE SUB SOIL CLASS		Be (TBC)
EARTHQUAKE DESIGN CATEGORY		

### RETAINING WALL - REINFORCED CONCRETE BLOCKWORK

RW2.	RETAINING WALL FOOTINGS HAV BEARING PRESSURE AS NOTED SHALL BE UNIFORM AND BE APP PRIOR TO THE PLACEMENT OF A
RW3.	REFER TO "REINFORCED CONCR SPECIFICATIONS.
RW4.	TEMPORARY BATTERS TO BE AS
RW5.	PROVIDE CLEAN-OUT BLOCKS AT CORES SHALL BE CLEANED OF M
RW6.	HORIZONTAL REINFORCEMENT I
RW7.	REFER TO TYPICAL DETAILS FOR DETAILS, AND VERTICAL CONTRO
RW8.	COVER TO REINFORCEMENT IN E BY THE USE OF PLASTIC "BLOCK APPROVED EQUIVALENT) AT THE VERTICAL REINFORCEMENT.
RW9.	ALL CORES ARE TO BE FULLY GF WITH AS 3600 AND COMPLY WITH CHARACTERISTIC STRENGTH fc MAXIMUM AGGREGATE SIZE = 10 SLUMP = 230 mm.
RW10.	PROVIDE WATERPROOFING MEM SPECIFICATIONS. DESIGN, EXTER PROVIDED BY WATERPROOFING
RW11.	RETAINING WALLS ARE DESIGNE FUNCTIONING DRAINAGE SYSTE PRESSURE . PROVIDE CONTINUC THE RETAINING WALL. THE DRAIL

RW1

ED BASED ON THE ASSUMPTION THAT A M IS EFFECTIVE IN REMOVING HYDRAULIC OUS AG DRAINS BEHIND THE ENTIRE EXTENT OF INAGE SYSTEM IS TO BE DESIGNED FOR LONG TERM PERFORMANCE EQUAL TO THAT OF THE DESIGN LIFE OF THE WALL. THE DESIGN AND DOCUMENTATION OF THIS SYSTEM IS BY OTHERS AND IS TO INCLUDE DETAILS OF EFFLUX POINTS FOR THE DRAINAGE AND ACCESS / MAINTENANCE POINTS. RW12. BACKFILL BEHIND THE WALL IS TO BE CLASSIFIED AS FREE DRAINING GRANULAR MATERIAL. FREE DRAINING GRANULAR MATERIAL SHALL BE A NON-COHESIVE

WELL GRADED GRANULAR MATERIAL COMPRISING SOUND STONE PARTICLES WHICH DO NOT BREAK DOWN UNDER COMPACTION, WETTING OR EXPOSURE TO AIR. THE MATERIAL PROPERTIES SHALL COMPLY WITH THOSE SPECIFIED IN TABLE BELOW.

FREE DRAINING GRANULAR MATERIAL PROPERTIES				
PROPERTY LIMIT VALUE				
STONE SIZE MAXIMUM 20 mm				
% PASSING 0.15 mm SIEVE MAXIMUM 5 %				
PLASTICITY INDEX MAXIMUM 8				

RW13. PROVIDE GEOTEXTILE SEPARATION LAYER BETWEEN FREE DRAINING GRANULAR MATERIAL AND RETAINED FILL MATERIAL.

- GIVEN BY THE ENGINEER.

RW15. PROVIDE VERTICAL CONTROL JOINTS IN ALL WALLS AT A MAXIMUM OF 8000 mm CENTRES UNLESS INDICATED OTHERWISE ON THE STRUCTURAL DRAWINGS. WHERE EVER POSSIBLE, SURFACE WATER SHALL BE DIRECTED AWAY FROM THE RW16 TOP OF THE WALL AND NOT BE ALLOWED TO POND BEHIND THE TOP OF THE WALL OR ENTER THE SUBSURFACE DRAINAGE SYSTEM.

### ABBREVIATIONS

ALT

C/S

ΒJ

CEN

CTS

DJ

FF

F'c=

EW

FF

NF

FFL

GD

GL

LV

LVL

MC

NSOE

NSOP

S/S

STAG

SSL

TYP

U/S

UNO

(U+O)

GALV

BTM

ALL WORKMANSHIP SHALL COMPLY WITH AS 4679 AND AS 3700.

VE BEEN DESIGNED FOR AN ALLOWABLE ON DRAWINGS. THIS FOUNDATION MATERIAL PROVED BY THE GEOTECHNICAL ENGINEER ANY FOOTING REINFORCEMENT. RETE BLOCKWORK" NOTES FOR ADDITIONAL

S PER GEOTECHNICAL ENGINEERS REPORTS

T THE BASE OF EACH POUR LIFT. REINFORCED MORTAR PROTRUSIONS BEFORE GROUTING IN WALLS IS TO BE SPLICED 600 AS REQUIRED.

R FOOTING STEPS, INTERSECTION / CORNER OL JOINT DETAILS.

BLOCK RETAINING WALLS SHALL BE MAINTAINED (AID" REINFORCEMENT LOCATION BRACKETS (OR E INTERSECTION OF ALL HORIZONTAL AND

ROUTED. GROUT SHALL BE IN ACCORDANCE H THE FOLLOWING : = 20 MPa AT 28 DAYS.

MBRANES AS REQUIRED BY ARCHITECTURAL INT AND CERTIFICATION OF MEMBRANE IS TO BE SPECIALIST.

RW14. COMPACTION OF BACKFILL BEHIND WALLS - COMPACTION SHALL BE BY MECHANICAL PLATE VIBRATOR TO A MINIMUM OF 100% STANDARD COMPACTION. - BACKFILLING IS NOT TO TAKE PLACE UNTIL APPROVAL HAS BEEN

ALTERNATIVE BARS **BRICKWORK COURSE** BOTTOM BOTTOM BLOCK JOINT CENTRAL CENTRES DOWEL JOINT EACH FACE CONCRETE STRENGTH EACH WAY FAR FACE NEAR FACE FINISH FLOOR LEVEL GALVANISED GRATED DRAIN GROUND LINE LENGTH VARIES LAMINATED VENEER LUMBER MASS CONCRETE NOT SHOWN ON ELEVATION NOT SHOWN ON PLAN REDUCED LEVEL REINFORCED CONCRETE REINFORCEMENT LAID FIRST REINFORCEMENT LAID SECOND REINFORCEMENT LAID THIRD REINFORCEMENT LAID FOURTH STAINLESS STEEL STAGGERED BARS STRUCTURAL SLAB LEVEL TYPICAL TOP

UNDERSIDE UNLESS NOTED OTHERWISE UNDER AND OVER



ACOR Consultants Pty Ltd Suite 2, Level 1, 33 Herbert Street St Leonards NSW 2065 T +61 2 9438 5098

ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

lssu	е	
No.	Date	Desc
1	13.02.2023	SCH
2	15.06.2023	50%
3	15.09.2023	80%
4	22.09.2023	100%

Description	Chk
SCHEMATIC DESIGN	ΖP
50% DESIGN DEVELOPMENT	ΤВ
80% DESIGN DEVELOPMENT	ΤВ
100% DESIGN DEVELOPMENT DRAFT	ΤВ
199115	





NSV

nbrs.com.au

ABN 16 002 247 565

# Health Infrastructure GOVERNMENT

Project CONCORD REPATRIATION GENERAL HOSPITAL

109 HOSPITAL ROAD, NSW 2139

**NSW GOVERNMENT HEALTH & INFRUSTRUCTURE** 

Drawing Title NOTES - SHEET 3

Date 25/09/2023 6:21:31 AM Scale @ A1

Drawing Reference 22071-S-00.03



WALL SCHEDULE						
		WALL REIN	FORCEMENT			
MARK	SIZE & TYPE	HORIZONTAL	VERTICAL	COMMENTS		
CONCRETE WALL						
CW150	150 CONCRETE WALL	N12-200 EF	N16-200 EF	FRL + 180 min		
CW200	200 CONCRETE WALL	N12-200 EF	N16-200 EF	FRL + 180 min		
CW300	300 CONCRETE WALL	N12-200 EF	N16-200 EF	FRL + 180 min		



ACOR Consultants Pty Ltd Suite 2, Level 1, 33 Herbert Street St Leonards NSW 2065 T +61 2 9438 5098 And the state of t

ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

 $(\widehat{\mathbf{C}})$  COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

ssue			
No.	Date	Description	Chko
1	15.06.2023	50% DESIGN DEVELOPMENT	ΤВ
2	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ
3	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ТВ





nbrs.com.au

ABN 16 002 247 565

# Health Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at

NSW

109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title CORE WALL PART PLANS AND **ELEVATIONS - SHEET 1** 

Date 25/09/2023 6:21:32 AM Scale 1:100@A1



Drawing Reference 22071-S-02.00 0 10 20 30 40 50 60 70









	WALL SCHEDULE							
		WALL REINF	ORCEMENT					
MARK	SIZE & TYPE	HORIZONTAL	VERTICAL	COMMENTS				
CONCRETE WA	LL							
CW150	150 CONCRETE WALL	N12-200 EF	N16-200 EF	FRL + 180 min				
CW200	200 CONCRETE WALL	N12-200 EF	N16-200 EF	FRL + 180 min				
CW300	300 CONCRETE WALL	N12-200 EF	N16-200 EF	FRL + 180 min				





ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

whendar wheten permission nonn teon eonsaltants r ty Eta.						
lssue	;					
No.	Date	Description	Chk			
1	15.06.2023	50% DESIGN DEVELOPMENT	ΤВ			
2	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ			
3	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ТВ			





nbrs.com.au

ABN 16 002 247 565

# Health Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at

**NSW** GOVERNMENT

109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title CORE WALL PART PLANS AND **ELEVATIONS - SHEET 2** 

Date 25/09/2023 6:21:33 AM Scale 1 : 100 @ A1



Drawing Reference 22071-S-02.01

0 10 20 30 40 50 60 70



TYPICAL STAIR FLIGHT DETAILS SCALE 1:20



# TYPICAL STAIR WALL AND BASE DETAIL SCALE 1:20

C.J DENOTES CONSTRUCTION JOINT. SCABBLE CONCRETE TO 1/3 OF THE AGGREGATE DEPTH AND REMOVE MATERIAL PRIOR TO 2ND POUR. TYP.

D WALL STRUCTURAL DIMENSIONS	3
DIMENSION (mm)	

E AND WALL REINFORCEMENT	
REINFORCEMENT	
N20-200	
N20-200	







CONSULTANTS

ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT (C) COPYRIGHT of this design and plan is the property of ACOR Consultants

Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

ssue	•		
No.	Date	Description	Chl
1	13.02.2023	SCHEMATIC DESIGN	ΖP
2	15.06.2023	50% DESIGN DEVELOPMENT	ΤВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ΤВ

ssu	е	
No.	Date	Description
1	13.02.2023	SCHEMATIC DESIGN
2	15.06.2023	50% DESIGN DEVELOPN
3	15.09.2023	80% DESIGN DEVELOPN
4	22.09.2023	100% DESIGN DEVELOP

- COG PILE REINFORCEMENT INTO PILE





nbrs.com.au

ABN 16 002 247 565

# Health **NSW** GOVERNMENT Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for

NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title TYPICAL STAIR DETAILS - SHEET 1

Date 25/09/2023 6:21:34 AM Scale 1 : 20 @ A1

Drawing Reference 22071-S-03.00

Revision

0 10 20 30 40 50 60 70 80 90 100



FOOTING BEAM STEP SCALE 1:20

FOOTING BEAM STEP SCALE 1:20

# FOOTING STEP FOR ABRUPT SLOPES

SCALE 1:20 STEP FOOTING TO SUIT COURSING





ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

ssue			
No.	Date	Description	С
1	13.02.2023	SCHEMATIC DESIGN	Zł
2	15.06.2023	50% DESIGN DEVELOPMENT	ΤE
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤE
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	T





nbrs.com.au

ABN 16 002 247 565



Project CONCORD REPATRIATION GENERAL HOSPITAL

at

109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title **TYPICAL FOOTING DETAILS - SHEET 1** 

Date 25/09/2023 6:21:34 AM Scale 1 : 20 @ A1

Drawing Reference

Revision 4 80 90 100

22071-S-05.00 0 10 20 30 40 50 60 70



### **DIAGRAMMATIC PILE CAP DETAIL - SECTION VIEW** SCALE 1:20

REFER TO PILE CAP SCHEDULE FOR PILE CAP / PILE DIMENSIONS AND REINFORCEMENT

REFER TO GENERAL NOTES FOR MIN BEARING CAPACITY UNDER FOOTINGS REFER TO GENERAL NOTES FOR CONCRETE STRENGTH GRADE 3.

SCALE 1:20 3

ALL TOP OF PILES ARE TO BE DETERMINED BY BUILDER



# **DIAGRAMMATIC PILE / COLUMN DETAIL - SECTION VIEW**

REFER TO PILE CAP SCHEDULE FOR PILE CAP / PILE DIMENSIONS AND REINFORCEMENT REFER TO GENERAL NOTES FOR MIN BEARING CAPACITY UNDER FOOTINGS REFER TO GENERAL NOTES FOR CONCRETE STRENGTH GRADE





ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

ssue			
No.	Date	Description	Chkd
1	13.02.2023	SCHEMATIC DESIGN	ZP
2	15.06.2023	50% DESIGN DEVELOPMENT	ΤВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ТВ





nbrs.com.au

ABN 16 002 247 565



Project CONCORD REPATRIATION GENERAL HOSPITAL

at

109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title TYPICAL FOOTING DETAILS - SHEET 2

Date 25/09/2023 6:21:35 AM Scale 1 : 20 @ A1

22071-S-05.01 0 10 20 30 40 50 60 70 80 90 100

Revision 4

Drawing Reference



FOOTING OVERALL PLAN SCALE: 1:200







ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

Issue	;		
No.	Date	Description	Chkd
1	13.02.2023	SCHEMATIC DESIGN	ZP
2	15.06.2023	50% DESIGN DEVELOPMENT	ТВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ТВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ТВ



**KEY PLAN** 





nbrs.com.au

ABN 16 002 247 565



Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title FOOTING OVERALL PLAN

Date 25/09/2023 6:25:36 AM Scale 1:200@A1



Drawing Reference 22071-S-06.00 0 10 20 30 40 50 60 70 80 90 100



- REFER TO DRAWINGS S-00.01-S-00.03 FOR ALL STRUCTURAL GENERAL NOTES..
  REFER TO DRAWINGS S-02.00-2-02.01 FOR CONCRETE WALL ELEVATIONS & WALL
- SCHEDULE. • REFER TO S-05.00-S-05.01 FOR FOOTING SCHEDULE & TYPICAL DETAILS
- ALL FALLS, SETDOWNS & WATERPROOFING ARE TO ARCHITECTS DETAILS U.N.O.

	PILE SCHEDULE								
MARK	PILE DIAMETER	WORKING LOAD (kN)	DEAD LOAD (kN)	LIVE LOAD (kN)	ULTIMATE LATERAL LOAD (kN)	ULTIMATE COMPRESSION LOAD (kN)	ULTIMATE TENSION LOAD (kN)	REINFORCEMENT	SOCKET LENGTH (mm)
P1	600								4500
P3	450								4500
									4500

Date 25/09/2023 6:25:38 AM Scale 1 : 100 @ A1

Revision

Drawing Reference 22071-S-06.01 0 10 20 30 40 50 60 70 80 90 100



# FOOTING GA PLAN - PART 2

SCALE: 1:100

# FOOTING NOTES:

- REFER TO DRAWINGS S-00.01-S-00.03 FOR ALL STRUCTURAL GENERAL NOTES..
- REFER TO DRAWINGS S-02.00-2-02.01 FOR CONCRETE WALL ELEVATIONS & WALL SCHEDULE.
- REFER TO S-05.00-S-05.01 FOR FOOTING SCHEDULE & TYPICAL DETAILS
  ALL FALLS, SETDOWNS & WATERPROOFING ARE TO ARCHITECTS DETAILS U.N.O.

# PILE SCHEDULE

					ULTIMATE				
	PILE	WORKING LOAD			LATERAL LOAD	ULTIMATE COMPRESSION LOAD	ULTIMATE TENSION LOAD		SOCKET
MARK	DIAMETER	(kN)	DEAD LOAD (kN)	LIVE LOAD (kN)	(kN)	(kN)	(kN)	REINFORCEMENT	(n
P1	600								45
P3	450								45
									45





nbrs.com.au

ABN 16 002 247 565

# GOVERNMENT Health Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title FOOTING GA PLAN - PART 2

Date 25/09/2023 6:25:39 AM Scale 1 : 100 @ A1



Drawing Reference 22071-S-06.02

 ZZUTI-S-U0.UZ
 +

 0
 10
 20
 30
 40
 50
 60
 70
 80
 90
 100



GROUND FLOOR OVERALL PLAN SCALE: 1:200







ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

lssu	е		
No.	Date	Description	Chk
1	13.02.2023	SCHEMATIC DESIGN	ΖP
2	15.06.2023	50% DESIGN DEVELOPMENT	ΤВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ΤВ



**KEY PLAN** 





nbrs.com.au

ABN 16 002 247 565

# Health **NSW** GOVERNMENT Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for

NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title GROUND FLOOR OVERALL PLAN

Date 25/09/2023 6:25:44 AM Scale 1:200@A1



Drawing Reference 22071-S-07.00 0 10 20 30 40 50 60 70 80 90 100



111111

- - DENOTES SLAB STEP. REFER TO PLAN FOR
  - VARIATION.

### HATCH DENOTES 50mm WET AREA SETDOWN

- ALL FALLS, SETDOWNS & WATERPROOFING ARE TO ARCHITECTS DETAILS U.N.O.
- UNLESS NOTED OTHERWISE ALL WET AREA SETDOWNS ARE TO BE A MINIMUM 40mm NON STRUCTURAL KERBS AND HOBS ARE NOT SHOWN. REFER TO ARCHITECTURAL DRAWINGS FOR EXTENT AND LOCATIONS.

MARK	SIZE	VERTICAL REINFORCEMENT	TIES
CONCRETE COLU	JMN		
CC1	300 x 500mm	12N20	N12-200
CC2	200 X 800mm	14N16	N12-200
CC3	250 x 800mm	14N16	N12-200
CC4	Ø600	12N20	N12-200

Drawing Reference 22071-S-07.01 0 10 20 30 40 50 60 70

90 100 80



CONCRETE COLUMN SCHEDULE					
MARK	SIZE	VERTICAL REINFORCEMENT	TIES	CONCRETE STRENGTH (MPa)	COMMENTS
CONCRETE COLL	JMN				
CC1	300 x 500mm	12N20	N12-200	fc = 40mPa	FRP = 120 MIN.
CC2	200 X 800mm	14N16	N12-200	fc = 40mPa	FRP = 120 MIN (ON SIDE EXPOSED TO FIRE)
CC3	250 x 800mm	14N16	N12-200	fc = 40mPa	FRP = 120 MIN
CC4	Ø600	12N20	N12-200	fc = 40mPa	FRP = 120 MIN.

Infrastructure Project CONCORD REPATRIATION GENERAL

HOSPITAL at

109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title GROUND FLOOR GA PLAN - PART 2

Date 25/09/2023 6:25:49 AM Scale 1 : 100 @ A1



Drawing Reference 22071-S-07.02 0 | 10 | 20 | 30 | 40 | 50 | 60 | 70 | 80 | 90 100 |



LEVEL 1 OVERALL PLAN SCALE: 1:200







ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

 $(\widehat{C})$  COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

Issue	)		
No.	Date	Description	Chkd
1	13.02.2023	SCHEMATIC DESIGN	ZP
2	15.06.2023	50% DESIGN DEVELOPMENT	ТВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ТВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ТВ



**KEY PLAN** 





nbrs.com.au

ABN 16 002 247 565



Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title LEVEL 1 OVERALL PLAN

Date 25/09/2023 6:25:52 AM Scale 1:200@A1



1

Drawing Reference 22071-S-07.10 0 10 20 30 40 50 60 70 80 90 100



# **LEGEND**



DENOTES SLAB STEP. REFER TO PLAN FOR VARIATION.

HATCH DENOTES 50mm WET AREA SETDOWN

• REFER TO DRAWINGS S-02.00 - S-02.01 FOR CONCRETE WALL ELEVATIONS & WALL SCHEDULE.

 REFER TO ARCHITECTURAL DRAWINGS FOR ALL CONCRETE SETOUT INFORMATION. • ALL FALLS, SETDOWNS & WATERPROOFING ARE TO ARCHITECTS DETAILS U.N.O. UNLESS NOTED OTHERWISE ALL WET AREA SETDOWNS ARE TO BE A MINIMUM 40mm • NON STRUCTURAL KERBS AND HOBS ARE NOT SHOWN. REFER TO ARCHITECTURAL DRAWINGS FOR EXTENT AND LOCATIONS.



MARK SB1 P1 SB2

21	STEEL COLUMN SCHEDULE				
	SIZE	COMMENTS			
	89 x 89 x 5 SHS				
	FRAMING SCHEDULE				
	SIZE	COMMENTS			
	SIZE 200UB25.4	COMMENTS			
	SIZE 200UB25.4 Z15024	COMMENTS			

Date 25/09/2023 6:25:54 AM Scale 1 : 100 @ A1



22071-S-07.11 0 10 20 30 40 50 60 70 80 90 100

Drawing Reference



CONCRETE COLUMN SCHEDULE						
MARK	SIZE	VERTICAL REINFORCEMENT	TIES	CONCRETE STRENGTH (MPa)	COMMENTS	
CONCRETE COLU	IMN					
CC1	300 x 500mm	12N20	N12-200	fc = 40mPa	FRP = 120 MIN.	
CC2	200 X 800mm	14N16	N12-200	fc = 40mPa	FRP = 120 MIN (ON SIDE EXPOSED TO FIRE)	
CC3	250 x 800mm	14N16	N12-200	fc = 40mPa	FRP = 120 MIN	
CC4	Ø600	12N20	N12-200	fc = 40mPa	FRP = 120 MIN.	

STEEL COLUMN SC					
MARK	SIZE				
SC1	89 x 89 x 5 SHS				
	FRAMING S	CHED			

MARK	SIZE	
SB1	200UB25.4	
P1	Z15024	
SB2	89 x 89 x 5 SHS	

# HEDULE COMMENTS

DULE COMMENTS



Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title LEVEL 1 GA PLAN - PART 2

Date 25/09/2023 6:25:56 AM Scale 1 : 100 @ A1



Drawing Reference 22071-S-07.12 0 10 20 30 40 50 60 70 80 90 100



SCALE: 1:200

![](_page_62_Picture_2.jpeg)

![](_page_62_Picture_3.jpeg)

![](_page_62_Picture_4.jpeg)

ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

 $(\widehat{C})$  COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

Issue	<del>)</del>		
No.	Date	Description	Chkd
1	13.02.2023	SCHEMATIC DESIGN	ZP
2	15.06.2023	50% DESIGN DEVELOPMENT	ТВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ТВ

![](_page_62_Picture_8.jpeg)

**KEY PLAN** 

![](_page_62_Picture_10.jpeg)

![](_page_62_Picture_11.jpeg)

nbrs.com.au

ABN 16 002 247 565

![](_page_62_Picture_14.jpeg)

Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title LEVEL 2 OVERALL PLAN

Date 25/09/2023 6:27:09 AM Scale 1:200@A1

Drawing Reference

22071-S-07.20

![](_page_62_Picture_20.jpeg)

![](_page_63_Figure_0.jpeg)

DENOTES SLAB STEP. REFER TO PLAN FOR

HATCH DENOTES 50mm WET AREA

![](_page_63_Picture_4.jpeg)

VARIATION.

SETDOWN

- SCHEDULE.

 REFER TO ARCHITECTURAL DRAWINGS FOR ALL CONCRETE SETOUT INFORMATION. • ALL FALLS, SETDOWNS & WATERPROOFING ARE TO ARCHITECTS DETAILS U.N.O. UNLESS NOTED OTHERWISE ALL WET AREA SETDOWNS ARE TO BE A MINIMUM 40mm NON STRUCTURAL KERBS AND HOBS ARE NOT SHOWN. REFER TO ARCHITECTURAL DRAWINGS FOR EXTENT AND LOCATIONS.

![](_page_63_Figure_10.jpeg)

![](_page_63_Figure_11.jpeg)

FRAMING SCHEDULE COMMENTS SIZE 200UB25.4 Z15024 89 x 89 x 5 SHS

Drawing Reference 22071-S-07.21 0 10 20 30 40 50 60 70

Scale 1 : 100 @ A1

![](_page_64_Figure_0.jpeg)

CONCRETE COLUMN SCHEDULE					
MARK	SIZE	VERTICAL REINFORCEMENT	TIES	CONCRETE STRENGTH (MPa)	COMMENTS
CONCRETE COLU	JMN				
CC1	300 x 500mm	12N20	N12-200	fc = 40mPa	FRP = 120 MIN.
CC2	200 X 800mm	14N16	N12-200	fc = 40mPa	FRP = 120 MIN (ON SIDE EXPOSED TO FIRE)
CC3	250 x 800mm	14N16	N12-200	fc = 40mPa	FRP = 120 MIN
CC4	Ø600	12N20	N12-200	fc = 40mPa	FRP = 120 MIN.

STEEL COLUMN SC					
MARK	SIZE				
SC1	89 x 89 x 5 SHS				
	FRAMING S	CHE			
MARK	FRAMING S	CHE			
MARK SB1	FRAMING S SIZE 200UB25.4	CHE			
MARK SB1 P1	FRAMING S SIZE 200UB25.4 Z15024	CHE			

![](_page_64_Figure_12.jpeg)

DULE COMMENTS CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title LEVEL 2 GA PLAN - PART 2

Date 25/09/2023 6:27:14 AM Scale 1 : 100 @ A1

![](_page_64_Picture_19.jpeg)

Drawing Reference 22071-S-07.22

![](_page_65_Figure_0.jpeg)

![](_page_65_Picture_5.jpeg)

![](_page_65_Picture_6.jpeg)

ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

C COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

Issue	•		
No.	Date	Description	Chkd
1	13.02.2023	SCHEMATIC DESIGN	ZP
2	15.06.2023	50% DESIGN DEVELOPMENT	ТВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ТВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ТВ

![](_page_65_Picture_10.jpeg)

**KEY PLAN** 

![](_page_65_Picture_12.jpeg)

![](_page_65_Picture_13.jpeg)

nbrs.com.au

ABN 16 002 247 565

![](_page_65_Picture_16.jpeg)

Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title ROOF OVERALL PLAN

Date 25/09/2023 6:28:46 AM Scale 1:200@A1

![](_page_65_Picture_22.jpeg)

Drawing Reference 22071-S-07.30 0 10 20 30 40 50 60 70 80 90 100

![](_page_66_Figure_0.jpeg)

# ROOF GA PLAN - PART 1

SCALE: 1:100

# NOTE: LIGHT GAUGE STEEL ROOF TRUSS SYSTEM AND ASSOCIATED STRUCTURE. LIGHT GAUGE STEEL ROOF TRUSS SYSTEM BY D & C CONCTRACTOR. TYPICAL.

PROPRIETRY LIGHT GUAGE STEEL TRUSSES ARE TO BE DESIGNED, INSPECTED AFTER ERRECTION AND CERTIFIED BY A STRUCTURAL ENGINEER ENGAGED BY THE FABRICATOR OR BUILDER. CERTIFICATION SHALL INCLUDE ROOF BRACING

AND TIE DOWN TO SUPPORTS. THE DESIGN SHALL COMPLY WITH ASNZS 4600.

THE FABRICATOR SHALL PROVIDE LAYOUT DRAWINGS TO ACOR FOR CONFIRMATION OF ALL DESIGN ASSUMPTIONS FOR

THE SUPPORTING STURCTURE (INCLUDING REACTIONS TO BE SUSTAINED BY MAIN STRUCTURE). THE DESIGN OF THE TRUSSES TO BE COORDINATED WITH ALL SERVICE DISCIPLINES TO INCLUDE BUT NOT LIMITED TO

THE FOLLOWING: POSITION AND WEIGHT OF EQUIPTMENT AND DUCTING. TYPICAL.

TRUSS DESIGN SHALL ALSO ACCOUNT FOR ALL PV PANELS AS SPECIFIED ON MECHANICAL ENGINEERS DOCUMENTATION

![](_page_66_Picture_10.jpeg)

(13)

ACOR Consultants Pty Ltd Suite 2, Level 1, 33 Herbert Street St Leonards NSW 2065 T +61 2 9438 5098 And the source of the source o 

ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

Issue	e		
No.	Date	Description	Chl
1	13.02.2023	SCHEMATIC DESIGN	ΖP
2	15.06.2023	50% DESIGN DEVELOPMENT	ΤВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ΤВ

![](_page_66_Picture_15.jpeg)

**KEY PLAN** 

![](_page_66_Picture_17.jpeg)

![](_page_66_Picture_18.jpeg)

nbrs.com.au

ABN 16 002 247 565

# NSW GOVERNMENT Health Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title ROOF GA PLAN - PART 1

Date 25/09/2023 6:28:48 AM Scale 1 : 100 @ A1

![](_page_66_Picture_27.jpeg)

Drawing Reference 22071-S-07.31 0 10 20 30 40 50 60 70 80 90 100

![](_page_67_Figure_0.jpeg)

# ROOF GA PLAN - PART 2

SCALE: 1:100

### NOTE: LIGHT GAUGE STEEL ROOF TRUSS SYSTEM AND ASSOCIATED STRUCTURE. LIGHT GAUGE STEEL ROOF TRUSS SYSTEM BY D & C CONCTRACTOR. TYPICAL.

PROPRIETRY LIGHT GUAGE STEEL TRUSSES ARE TO BE DESIGNED, INSPECTED AFTER ERRECTION AND CERTIFIED BY A STRUCTURAL ENGINEER ENGAGED BY THE FABRICATOR OR BUILDER. CERTIFICATION SHALL INCLUDE ROOF BRACING

AND TIE DOWN TO SUPPORTS. THE DESIGN SHALL COMPLY WITH ASNZS 4600.

THE FABRICATOR SHALL PROVIDE LAYOUT DRAWINGS TO ACOR FOR CONFIRMATION OF ALL DESIGN ASSUMPTIONS FOR THE SUPPORTING STURCTURE (INCLUDING REACTIONS TO BE SUSTAINED BY MAIN STRUCTURE).

THE DESIGN OF THE TRUSSES TO BE COORDINATED WITH ALL SERVICE DISCIPLINES TO INCLUDE BUT NOT LIMITED TO

THE FOLLOWING: POSITION AND WEIGHT OF EQUIPTMENT AND DUCTING. TYPICAL. TRUSS DESIGN SHALL ALSO ACCOUNT FOR ALL PV PANELS AS SPECIFIED ON MECHANICAL ENGINEERS DOCUMENTATION

$\overline{5}$	6	7) (8)	9	(10)	(11)	(12)
	FOR	CONTINUATION	REFER TO DR	AWING S-07.31		
P1 SB2	P1 دون د	SB1	SB1	P1 AT 1200 MAX CTS		
	 پې	SB1	SB1			
	- - - - - - - - - - - - - - - - - - -	FALL SB1	FALL SB1	جي		
	çc	SB1	SB1	, cs		

![](_page_67_Picture_10.jpeg)

(13)

ACOR Consultants Pty Ltd Suite 2, Level 1, 33 Herbert Street St Leonards NSW 2065 T +61 2 9438 5098 the state of the s 

ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

		······································	
Issu	е		
No.	Date	Description	Chł
1	13.02.2023	SCHEMATIC DESIGN	ΖP
2	15.06.2023	50% DESIGN DEVELOPMENT	ΤВ
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ΤВ

![](_page_67_Picture_15.jpeg)

**KEY PLAN** 

![](_page_67_Picture_17.jpeg)

![](_page_67_Picture_18.jpeg)

nbrs.com.au

ABN 16 002 247 565

# Health **NSW** GOVERNMENT Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at

109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title ROOF GA PLAN - PART 2

Date 25/09/2023 6:28:48 AM Scale 1 : 100 @ A1

![](_page_67_Picture_28.jpeg)

Drawing Reference 22071-S-07.32 0 10 20 30 40 50 60 70 80 90 100

![](_page_67_Picture_30.jpeg)

![](_page_68_Figure_0.jpeg)

![](_page_68_Figure_1.jpeg)

TYPICAL WET AREA DETAIL

- REINFORCEMENT AND PT BY OTHERS

# **TYPICAL BALCONY DETAIL**

(HOB NOT SHOWN ON PLAN, REFER TO ARCHITECTS)

![](_page_68_Figure_5.jpeg)

TYPICAL HOB 'H1' DETAILS

![](_page_68_Figure_7.jpeg)

![](_page_68_Figure_8.jpeg)

SCALE 1:20

![](_page_68_Figure_10.jpeg)

**TYPICAL UPSTAND DETAIL** SCALE 1:20

![](_page_68_Picture_12.jpeg)

![](_page_68_Picture_13.jpeg)

ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

ssue	sue				
No.	Date	Description	Chkd		
1	13.02.2023	SCHEMATIC DESIGN	ZP		
2	15.06.2023	50% DESIGN DEVELOPMENT	ΤВ		
3	15.09.2023	80% DESIGN DEVELOPMENT	ΤВ		
4	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	ТВ		

![](_page_68_Picture_17.jpeg)

![](_page_68_Picture_18.jpeg)

nbrs.com.au

ABN 16 002 247 565

# Health Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at

NSW

109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title TYPICAL SUSPENDED SLAB DETAILS -SHEET 1

Date 25/09/2023 6:28:49 AM Scale 1 : 20 @ A1

![](_page_68_Picture_28.jpeg)

Drawing Reference 22071-S-13.01

![](_page_69_Figure_0.jpeg)

![](_page_69_Figure_1.jpeg)

![](_page_69_Figure_2.jpeg)

# **TYPICAL PURLIN CLEAT CONNECTION**

```
SCALE
1:10
```

# PURLIN CLEAT SCHEDULE

"H"	MIN CLEAT SIZE (SPLICED PURLIN)	MIN CLEAT SIZE (CONT PURLIN)
UPTO 50	130 x 8 PLATE	75 x 8 PLATE
UPTO 100	130 x 10 PLATE	75 x 10 PLATE
UPTO 150	130 x 12 PLATE	75 x 12 PLATE
150 + (500 MAX)	150 x 90 x 8 UA	75 x 75 x 6 EA

![](_page_69_Figure_7.jpeg)

![](_page_69_Figure_9.jpeg)

![](_page_69_Figure_10.jpeg)

# TYPICAL COLUMN CAP PLATE DETAIL SCALE 1:10

![](_page_69_Figure_12.jpeg)

BEAM TO BEAM DETAIL

BEAM TO BEAM DETAIL

BEAM TO BEAM COLUMN

BEAM TO BEAM COLUMN

# MINIMUM WEB CLEAT CONNECTION DETAILS

U.N.O. SCALE 1:10

BEAM SIZE	CONNECTION ULTIMATE SHEAR CAP.	WEB CLEAT	BOLTS
180UB OR 180 PFC	50 kN	10 PLATE	2M20 8.8/S
200UB/UC OR 200 PFC / 230 PFC	60 kN	10 PLATE	2M20 8.8/S
250UB/UC OR 250 PFC	85 kN	10 PLATE	2M20 8.8/S
310UB/UC OR 300 PFC	140 kN	10 PLATE	3M20 8.8/S
360UB OR 380 PFC	175 kN	10 PLATE	3M20 8.8/S
410UB	260 kN	10 PLATE	4M20 8.8/S
460UB	260 kN	10 PLATE	4M20 8.8/S
530UB	360 kN	10 PLATE	5M20 8.8/S
610UB	440 kN	12 PLATE	6M20 8.8/S

![](_page_69_Picture_20.jpeg)

![](_page_69_Picture_21.jpeg)

ENGINEERS | MANAGERS | INFRUSTUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

(C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

ssu	е		
No.	Date	Description	CI
1	13.02.2023	SCHEMATIC DESIGN	ZF
2	15.06.2023	50% DESIGN DEVELOPMENT	TE
3	22.09.2023	100% DESIGN DEVELOPMENT DRAFT ISSUE	TE

20 THICK BASE PLATE 4M20 H.D. BOLTS x 500 LONG 20 NOMINAL GROUT

![](_page_69_Figure_27.jpeg)

![](_page_69_Figure_28.jpeg)

![](_page_69_Picture_30.jpeg)

![](_page_69_Picture_31.jpeg)

**NSW** GOVERNMENT

nbrs.com.au

ABN 16 002 247 565

# Health Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title **TYPICAL STEEL DETAILS - SHEET 1** 

Date 25/09/2023 6:28:49 AM Scale 1:10@A1

Drawing Reference 22071-S-14.00 0 10 20 30 40 50 60 70

![](_page_70_Figure_0.jpeg)

![](_page_70_Figure_1.jpeg)

![](_page_70_Figure_3.jpeg)

![](_page_70_Figure_8.jpeg)

![](_page_70_Figure_9.jpeg)

![](_page_70_Figure_10.jpeg)

(DENOTED BR ON PLAN) BRACING TO BE HUNG FROM PURLINS AS INDICATED IN SCHEDULE

D - STEEL DETAILS 1 TO 10 SHEET 1 - SHEET 2 SCALE: 1:10

![](_page_70_Figure_13.jpeg)

250 UB	16	4
310 UB	16	4
360 UB	16	4
410 UB	16	6
460/530 UB	16	6

TYPICAL CONNECTION AT CONCRETE STRUCTURE SCALE 1:10

# Health **NSW** GOVERNMENT Infrastructure

Project CONCORD REPATRIATION GENERAL HOSPITAL

at 109 HOSPITAL ROAD, NSW 2139

for NSW GOVERNMENT HEALTH & INFRUSTRUCTURE

Drawing Title **TYPICAL STEEL DETAILS - SHEET 2** 

Date 25/09/2023 6:28:50 AM Scale As indicated @ A1

![](_page_70_Picture_28.jpeg)

Drawing Reference 22071-S-14.01 0 10 20 30 40 50 60 70 80 90 100

![](_page_71_Picture_0.jpeg)

# Appendix D - El Australia – Report Ref No E25996.G03


# LIPMAN PTY LTD



# **Geotechnical Investigation**

1H Hospital Road, Concord West NSW

E25996.G03 10 August 2023

## **Document Control**

Report Title: Geotechnical Investigation, 1H Hospital Road, Concord West NSW

Report No: E25996.G03

Copies	Recipient
1 Soft Copy (PDF – Secured, issued by email)	Craig Butler Lipman Pty Ltd Level 6, 66 Berry Street, NORTH SYDNEY NSW 2060
2 Original (Saved to Digital Archives) (\\Pah\ei-au\$\07 - Projects\E25996_MOITS_Concord_Soil Testing\05_Deliverables\Work in Progress\G03\E25996.G03 - Geotechnical Investigation.docx)	El Australia Suite 6.01, 55 Miller Street, PYRMONT NSW 2009

Author		Technical Reviewer	Technical Reviewer		
771,36		mits			
Jack (Haojie) Chen		Mike Leung			
Geotechnical Engineer		Principal Geotechnical Engineer			
Revision	Details	Date	Amended By		
	Original	10 August 2023			

#### © 2023 El Australia (El) ABN: 42 909 129 957

This report is protected by copyright law and may only be reproduced, in electronic or hard copy format, if it is copied and distributed in full and with prior written permission by El.



## Table of Contents

#### Page Number

1.	INT	RODUC <sup>-</sup>	TION	1	
	1.1	1			
	1.2	1			
	1.3	1			
	1.4	2			
	1.5	Constra	aints	3	
2.	SIT	E DESCI	RIPTION	4	
	2.1	Site De	escription and Identification	4	
	2.2	Local L	and Use	5	
	2.3	Region	al Setting	5	
3.	INV	ESTIGA	TION RESULTS	7	
	3.1	Stratigr	raphy	7	
	3.2	Ground	dwater Observations	8	
	3.3 Test Results				
4.	REC	COMME	NDATIONS	11	
	4.1 Geotechnical Considerations				
	4.2	Site Pre	eparation	11	
	4.3	Founda	ations	11	
		4.3.1	Pile Footings	12	
		4.3.2	Piled Stiffened Raft Slab	12	
	4.4	Subgra	de Preparation and Engineered Fill	13	
		4.4.1	Subgrade Preparation for slabs and pavements	13	
		4.4.2	Engineered Fill Specifications	14	
	4.5	Pavem	ent Subgrade	14	
5.	FUF	RTHER O	GEOTECHNICAL INPUTS	16	
6.	STA	TEMEN	IT OF LIMITATIONS	17	
RE	FERE	ENCES		18	
AB	BRE	VIATION	IS	18	

## Schedule of Tables

Table 1-1	Augering and Rock Coring Depths
Table 2-1	Summary of Site Information



2

Table 2-2	Summary of Local Land Use	5
Table 2-3	Topographic and Geological Information	5
Table 3-1	Summary of Subsurface Conditions	7
Table 3-2	Depth to Overburden Units and Rock Classes	8
Table 3-3	Groundwater Levels	8
Table 3-4	Summary of Soil Laboratory Test Results	9
Table 3-5	Summary of CBR Test Results	10
Table 4-1	Summary of foundation parameters for bored piles	12

## Appendices

#### FIGURES

- Figure 1 Site Locality Plan
- Figure 2 Borehole Location Plan

#### APPENDIX A – BOREHOLE LOGS AND EXPLANATORY NOTES

#### **APPENDIX B – LABORATORY CERTIFICATES**

#### **APPENDIX C – VIBRATION LIMITS**

**APPENDIX D – IMPORTANT INFORMATION** 



## 1. Introduction

#### 1.1 Background

At the request of Mr Jacob Nielson on behalf of Lipman Pty Ltd (the Client), El Australia (El) has carried out a Geotechnical Investigation (GI) for the proposed development at 1H Hospital Road, Concord West NSW (the Site).

This GI report has been prepared to provide advice and recommendations to assist in the preparation of designs for the proposed development. The investigation has been carried out in accordance with the agreed scope of works outlined in EI's proposal referenced P21305.1, dated 24 March 2023, and with the Client's signed authorisation to proceed, dated 2 June 2023.

#### 1.2 Proposed Development

The following documents, supplied by the Client, were used to assist with the preparation of this GI report:

- Approximate Borehole Location Plan prepared by ACOR Consultants Pty Ltd;
- Ground Floor Overall Plan, drawing ref.: 221192-S-07.00 Revision 1, prepared by NBRS & Partners Pty Ltd;
- Site Layout Plan, drawing ref.: 22071-A-0200 Revision 4, prepared by NBRS & Partners Pty Ltd;
- Investigation brief provided by the client.

Based on the provided documents, EI understand the following to be the proposed development:

- The development area hereafter referred to as the 'Site' is irregular in shape, currently
  occupied by an existing building in part, with the remaining areas comprising car park,
  driveways and lawns;
- The existing building will be demolished to make wat for a new building; and
- The development is proposed to comprise a three-storey building with no basement.

#### 1.3 Objectives

The objective of the GI was to assess site surface and subsurface conditions at seven (7) borehole locations, and to provide geotechnical advice and recommendations addressing the following:

- Building foundation options, including;
  - Appropriate foundation materials for the proposed structural footings;
  - Geotechnical parameters;
  - Foundation types, serviceability bearing pressures and settlements;
  - Earthquake loading factor in accordance with AS1170.4:2007.
- Earthworks and subgrade preparation recommendations;
- The requirement for additional geotechnical works.



#### 1.4 Scope of Works

The scope of works for the GI included:

- Preparation of a Work Health and Safety Plan;
- Review of relevant geological maps for the project area;
- Site walkover inspection by a Geotechnical Engineer to assess topographical features and site conditions;
- Scanning of proposed borehole locations for buried conductive services using a licensed service locator with reference to Dial Before You Dig (DBYD) plans;
- Auger drilling of seven boreholes (BH1M, BH2, BH3M, BH4, BH5, BH6M and BH7) by a track-mounted drill rig using solid flight augers equipped with a 'Tungsten-Carbide' (T-C) bit. The boreholes were auger drilled to depths as shown in **Table 1-1** below:

Rorobolo ID	Augering	Rock Coring	
Borenole iD	Termination Depth (m)	Termination Depth (m)	
BH1M	3.00	7.60	
BH2	3.00	7.24	
ВНЗМ	2.52	6.0	
BH4	2.70	6.0	
BH5	3.45	6.0	
BH6M	2.30	7.2	
BH7	3.0	6.0	

Table 1-1 Auger Drilling and Rock Coring Depths

- Standard Penetration Testing (SPT) was carried out (as per AS 1289.6.3.1-2004), where possible, during auger drilling of the boreholes to assess soil strength/relative densities.
- Measurements of groundwater seepage/levels, where possible, in the augered sections of the boreholes during and shortly after completion of auger drilling;
- The strength of the bedrock in the augered sections of the boreholes was assessed by observation of the auger penetration resistance using a T-C drill bit and examination of the recovered rock cuttings. It should be noted that rock strengths assessed from augered boreholes are approximate and strength variances can be expected.
- Continuation of all boreholes using NMLC diamond rock coring techniques to termination depths shown above in Table 1-1. The rock core photographs are presented in Appendix A;
- Borehole BH1M, BH3M and BH6M were converted into groundwater monitoring wells with screen depths of between 3m to 6m in all three wells to allow for future groundwater monitoring.



- Borehole BH2, BH4, BH5, and BH7 were backfilled with drilling spoils and capped with concrete upon completion;
- Soil and rock core samples were sent to STS Geotechnics Pty Ltd (STS) and SGS Australia (SGS), which are National Australian Testing Authority (NATA) accredited laboratories, for testing and storage.
- Preparation of this GI report.

El's Geotechnical Engineer was present full-time onsite to set out the borehole locations, direct the testing and sampling, log the subsurface conditions and record groundwater levels.

#### 1.5 Constraints

The GI was limited by the intent of the investigation and the presence of existing site structures. The discussions and advice presented in this report are intended to assist in the preparation of initial designs for the proposed development. Further geotechnical inspections should be carried out during construction to confirm the geotechnical and groundwater models, and the design parameters provided in this report.

The presence of underground services and the need to maintain vehicle thoroughfare within the investigation area precluded positioning of boreholes at locations stipulated in the Client's investigation brief. El have relocated boreholes (where required) to as close as possible to the intended locations.



## 2. Site Description

#### 2.1 Site Description and Identification

The site identification details and associated information are presented in **Table 2-1** below while the site locality is shown on **Figure 1**. An aerial photograph of the site is presented in **Plate 1** below.

Information	Detail
Street Address	1H Hospital Road, Concord West NSW
Lot and Deposited Plan (DP) Identification	Lot 2 in DP 1280788
Brief Site Description	The site was occupied by an existing single-storey building in the southern portion of the site. The remaining areas are open space comprising lawns and asphalt surfaced car park and access roadways.
Site Area	The site area is approximately 2,706m <sup>2</sup>



Plate 1: Aerial photograph of the site (source: SIXMaps, accessed 30/5/23)



#### 2.2 Local Land Use

The site is situated within an area of commercial (hospital) use. Current uses on surrounding land at the time of our presence on site are described in **Table 2-2** below. For the sake of this report, the site boundary adjacent to Hospital Road shall be adopted as the northern site boundary.

Table 2-2 Summary of Local Land Use

Direction Relative to Site	Land Use Description
North Hospital Road, a two lane, asphalt-paved road.	
East Manning Concord Hospital unit 110, a double storey brick rendered facility.	
South Jara Ward unit 112, a single storey brick building with grassy areas.	
West	Concord medical education centre unit 26, a single brick rendered building.

#### 2.3 Regional Setting

The site topography and geological information for the locality is summarised in Table 2-3 below.

Attribute	Description
Topography	The site is located at the central portion of the Concord Hospital within gently (0° to 5°), south- west dipping topography.
Regional Geology	Information on regional sub-surface conditions, referenced from the Department of Mineral Resources Geological Map Sydney 1:100,000 Geological Series Sheet 9130 (DMR 1983) indicates the site to be underlain by Quaternary Aged Holocene deposits (Qha) associated with stream alluvial and estuarine sediments, which consists of silty to peaty quartz sand, silt, and clay, Ferruginous and humic cementation in places, and common shell layers. It is expected that the soils are underlain by Hawkesbury Sandstone.
	Previous geotechnical site investigations by Coffey Services Australia were carried out as part of the Phase 2 redevelopment of the hospital precinct in 2016 to 2017. The Phase 2 redevelopment footprint investigated by Coffey was located west and south-west of the subject site. The borehole encountered Ashfield Shale (Rwa) and Hawkesbury Sandstone (Rh) beneath the overburden soils. Depending on location, a residual soil profile was encountered beneath the Quaternary alluvium. Shale bedrock was encountered at depths ranging from 1.2m to 2m below ground surface levels underlain by Sandstone at depths of about 8m to 10m.





Plate 2: Excerpt of geological map showing location of site.



#### 3.1 Stratigraphy

For the development of a site-specific geotechnical model, the stratigraphy observed in the GI has been grouped into four geotechnical units. A summary of the subsurface conditions across the site, interpreted from the assessment results, is presented in **Table 3-1** below. More detailed descriptions of subsurface conditions at each borehole location are available on the borehole logs presented in **Appendix A**. The details of the methods of soil and rock classifications, explanatory notes and abbreviations adopted on the borehole logs are also presented in **Appendix A**.

Unit	Material <sup>2</sup>	Depth to Top of Unit (m BEGL) <sup>1</sup>	Observed Thickness (m)	Comments
1	Topsoil/Fill	Surface to 0.15	0.3 to 1.6	Asphalt pavements of 100mm to 150mm thickness, underlain by well compacted Fill material comprising fine to medium grained silty sand with traces of sub- angular to sub-rounded gravels, and appeared well compacted based on our observations during drilling and SPT N value of 11 in BH6M.
2	Residual Soil / Extremely Weathered Sandstone (Class V)	0.3 to 1.6	1.0 to 3.6	Low to medium plasticity, stiff to hard clay, overlying extremely weathered sandstone (assess Class V Sandstone). SPT N values range from 14 to practical refusal (hammer bounding) in the overburden soils profile. The hammer bounced occurred in extremely weathered sandstone. From depths between 3.0m to 4.15m and 3.0 to 3.2m, core loss of 1150mm and 200mm was observed in BH1M and BH7 respectively. Core loss is inferred to be extremely weathered sandstone.
3a	Class IV Sandstone	2.52 to 4.3	0.3 to 3.11	Distinctly weathered, very low to medium strength sandstone. A layer of very low to medium strength shale was observed in BH2 from depths between 3m to 5.5m. Core losses observed in BH2, BH4M, and BH6M are inferred to be bands of decomposed or highly fractured material.
3b	Class III Sandstone	3.85 to 6.11	_3	Slightly weathered medium to high strength sandstone.

Table 3-1 Summary of Subsurface Conditions

Note 1 Approximate depth and level at the time of our assessment. Depths and levels may vary across the site.

Note 2 For more detailed descriptions of the subsurface conditions, reference should be made to the borehole logs attached to **Appendix A.** 

Note 3 Observed up to termination depth in all boreholes.



Unit	Depth to top of material unit (m BEGL)									
<b>C</b>	BH1M	BH2	BH3M	BH4	BH5	BH6M	BH7			
1 – Topsoil/Fill	0.10	0.10	0.00	0.00	0.15	0.00	0.10			
2 – Residual Soil/ Extremely Weathered Sandstone (Class V)	0.60	0.60	0.30	0.70	0.60	1.60	0.80			
3a – Class IV Sandstone	4.15	3.00	2.52	4.30	3.55	-	4.20			
3b – Class III Sandstone	6.00	6.11	4.35	5.15	3.85	4.20	4.10			

#### Table 3-2 Depth to Overburden Units and Rock Classes

#### 3.2 Groundwater Observations

Following completion of auger drilling, groundwater monitoring wells were installed in BH1M, BH3M, and BH6M and bailed dry. The groundwater levels were then measured within the monitoring wells as per **Table 3-3** below:

Borehole ID	Groundwater Seepage Level During Auger Drilling	Monitoring	Well Details	Groundwater Level After Well Development	Measurement Date
	m BEGL	Screened Zone (mBEGL)	Screen Length (m)	m BEGL	
BH1M	Not encountered	3 - 6	3.0	2.27	25-July-2023
BH3M	Not encountered	3 - 6	3.0	2.44	25-July-2023
BH6M	Not encountered	3 - 6	3.0	2.58	25-July-2023

 Table 3-3
 Groundwater Levels

No groundwater or significant seepage was observed during or after auger drilling of the boreholes. We note that the groundwater levels may not have become evident or stabilised in the augered boreholes within the limited observation period. Water circulation as is required for rock coring within the boreholes prevented further observations of groundwater levels within the cored section of the boreholes. No long term groundwater monitoring was carried out.



#### 3.3 Test Results

Ten grab size soil samples and one bulk size sample were selected for laboratory testing to assess the following:

- Atterberg Limits;
- Soil Moisture Content;
- Particle Size Distribution;
- Soil aggressivity (pH, chloride and sulfate content and electrical conductivity); and
- California Bearing Ratio (CBR).

A summary of the soil test results is provided in **Table 3-4** and **Table 3-5** below. Laboratory test certificates are presented in **Appendix B**.

Test/ ID	/ Sample	BH1M 1.5-1.65	BH7 1.5-1.8	BH5 3.0-3.45	BH4 1.5-1.85	BH5 1.5-1.68	BH3M 1.5-1.95	BH2 1.5-1.72	BH6M 1.5-1.95
Unit		2	2	2	2	2	2	2	2
Mate Desc	rial ription <sup>1</sup>			Residual Sc	il/ Extremel	y Weathered	d Sandstone	9	
	Chloride Cl (ppm)	290	70	520	-	-	-	-	-
sivity	Sulfate SO <sub>4</sub> (ppm)	160	91 170		-	-	-		
ggre	рН	5.1	5.5	4.3	-	-	-	-	-
A .	Electrical Conductiv ity (µS/cm)	240	110	480	-	-	-	-	-
	Moisture Content (%)	10.8	12.1	-	13.0	11.8	17.0	17.0	22.6
nits	Liquid Limit (%)	37	36	-	39	40	-	-	-
rberg Li	Plastic Limit (%)	20	21	-	21	21	-	-	-
Atte	Plasticity Index (%)	17	15	-	18	19	-	-	-
Size	Gravel (%)	-	-	-	-	-	6.0	13.5	7.1
icle S tributi	Sand (%)	-	-	-	-	-	6.1	23.7	9.7
Dist	Clay & Silt (%)	-	-	-	-	-	87.9	62.8	83.2

Table 3-4 Summary of Soil Laboratory Test Results



Note 1 More detailed descriptions of the subsurface conditions at each borehole location are available on the borehole logs presented in **Appendix A**.

The Atterberg Limits result on the selected clay samples indicated clays to be of medium plasticity and therefore expected to exhibit moderate shrink-swell potential.

The assessment indicated low permeability soil was present both above and below the groundwater table. In accordance with Tables 6.4.2(C) and 6.5.2(C) of AS 2159:2009 'Piling – Design and Installation', the results of the pH, chloride and sulfate content and electrical conductivity of the soil provided the following exposure classifications:

- 'Moderate' for buried concrete structural elements; and
- 'Non-Aggressive' for buried steel structural elements.

BH6_CBR
1.5-1.6
1
FILL: Sandy Clay, low to medium plasticity
8.0
1.784
16.4
14.8
1.6% Dry

#### Table 3-5Summary of CBR Test Results

Note 1 More detailed descriptions of the subsurface conditions at each borehole location are available on the borehole logs presented in **Appendix A**.

Bulk samples of the Unit 1 silty clay fill material from BH6 was tested for standard compaction and four day soaked CBR with 9kg surcharge, yielding a CBR value of 8%.

Twenty-eight selected rock core samples were tested by STS Geotechnics Pty Ltd to estimate the Point Load Strength Index ( $Is_{50}$ ) values to assist with rock strength assessment. The results of the testing are summarised on the laboratory test report and replicated in the borehole logs.



## 4. Recommendations

#### 4.1 Geotechnical Considerations

Based on the results of the assessment, we consider the following to be the main geotechnical considerations for the proposed development:

- Foundation design for building loads;
- Earthworks and subgrade preparation;
- Design subgrade CBR value to inform pavement thickness design.

#### 4.2 Site Preparation

At the time of preparing this report, the design subgrade levels for the building and subgrade levels for pavements are not known. It is assumed that the proposed building and pavements will be constructed at grade with minimal cut/fill operations.

Based on subsurface conditions encountered in all boreholes, the materials expected to be encountered within the depth of excavation / stripping for site preparation may include topsoil and fill comprising silty sand and clayey sand. Fill materials comprising sandy clay was encountered to a depth of 1.6m BEGL at the location of BH6M, although it may not be encountered during site preparation works considering that BH6M is located outside the proposed building footprint. Excavation of topsoil and fill may be readily achieved using excavators fitted with excavation buckets and if needed fitted with tiger teeth.

Following removal of all vegetation and trees (including their root balls), demolition of the existing structures, slabs and pavements, all grass, topsoil, root affected soils and any deleterious fill (if present) or contaminated soil should be stripped. Based on the results of the investigation, topsoil/root affected soil should be stripped to a nominal depth. We note that it is difficult to accurately assess the depth of topsoil and root affected soils. If considered to be an important contractual issue, we recommend that a number of shallow test pits be excavated across the site to more accurately confirm the topsoil/root affected soil stripping depth or alternatively a geotechnical inspection could be carried out after initial stripping to confirm the depth. Stripped topsoil and root affected soils should be stockpiled separately as they are considered unsuitable for reuse as engineered fill.

#### 4.3 Foundations

At the time of preparing this report, the design building loads are not known.

The most competent foundation stratum at the site is the underlying sandstone bedrock, and in view of the relatively shallow bedrock depths and shallow groundwater levels, we recommend that the proposed building be supported on pile footings founded into the underlying sandstone bedrock. However, the option of piled stiffened raft slab footings is also provided.

We note that only one groundwater measurement visit was carried out post site investigation in the three installed groundwater monitoring wells on 25 July 2023. We recommend that additional groundwater studies may be required, including pump out testing and groundwater level measurement to understand the groundwater regime to inform recommendations on groundwater control during pile hole drilling.



#### 4.3.1 Pile Footings

The proposed building may be supported on deep foundations, such as piles, founded into sandstone bedrock.

The recommended bearing pressures and shaft adhesion for foundation bored piles are presented in **Table 4-1**.

 Table 4-1
 Summary of foundation parameters for bored piles

Rock Class	Serviceability End Bearing Pressure (kPa) <sup>3</sup>	Ultimate Shaft Adhesion - Compression (kPa) <sup>2</sup>
Class V Sandstone	700	100
Class IV Sandstone	2000	500
Class III Sandstone	4000	1000

Notes:

1 More detailed descriptions of subsurface conditions are available on the borehole logs presented in Appendix A.

2 Side adhesion values given assume there is intimate contact between the pile and foundation material and should achieve a clean socket roughness category R2 or better. Design engineer to check both 'piston pull-out' and 'cone liftout' mechanics in accordance with AS4678-2002 Earth Retaining Structures.

3 To adopt these parameters we have assumed that:

- Footings have a nominal socket of at least 0.3m, into the relevant founding material;
  - For piles, there is intimate contact between the pile and foundation material (a clean socket roughness category of R2 or better);
  - Potential soil and groundwater aggressivity will be considered in the design of piles and footings;
- Piles should be drilled in the presence of a Geotechnical Engineer prior to pile construction to verify that ground conditions meet design assumptions. Where groundwater ingress is encountered during pile excavation, concrete is to be placed as soon as possible upon completion of pile excavation. Pile excavations should be pumped dry of water prior to pouring concrete, or alternatively a tremmie system could be used;
- The bases of all pile, pad and strip footing excavations are cleaned of loose and softened material and water is pumped out prior to placement of concrete;
- The concrete is poured on the same day as drilling, inspection and cleaning.
- The allowable bearing pressures given above are based on serviceability criteria of settlements at the footing base/pile toe of less than or equal to 1% of the minimum footing dimension (or pile diameter).

The shaft adhesion for uplift in sandstone bedrock may adopt 50% of that in compression for the socket length in excess of 0.5m into the material.

It must be noted that all footings should be founded on similar materials and rock class to minimise the impact of differential settlement.

At least the initial drilling of piles should be completed in the presence of a geotechnical engineer to verify that ground conditions meet design assumptions.

Where groundwater ingress is encountered during pile excavation, concrete is to be placed as soon as possible upon completion of pile excavation. Pile excavations should be pumped dry of water and sludge and cleaned using a cleaning bucket prior to pouring concrete. The use of a tremmie pipe to place concrete from the base of the open pile hole is recommended. Concrete must be poured on the same day as drilling, inspection and drilling.

The aggressivity of natural soils and groundwater (if encountered) should be taken into consideration in the design.

#### 4.3.2 Piled Stiffened Raft Slab

Raft slabs are well suited to uniform slab conditions and building loads. Further detailed evaluation of expected performance including the evaluation of allowable bearing pressures and settlements would be required once design loads, founding level, and column layout are better known.

In the case of a piled stiffened raft slab, the piles are designed to their ultimate capacity and act as settlement reducers to the stiffened raft slab.



The subgrade preparation below any raft slabs will be important in the final performance of the raft. Detailed analysis of a piled raft would be required to estimate the settlements and the contact pressures below the raft. Further discussion regarding sub-grade preparation is provided in **Section 4.4** below. It is also recommended that a 150mm thick layer of good quality granular material such as recycled concrete or crushed rock be placed and compacted over the prepared surface, particularly at heavily loaded areas. This layer helps confine the sandy soils from disturbances and improve the compacted and density of the surface soils.

#### 4.4 Subgrade Preparation and Engineered Fill

#### 4.4.1 Subgrade Preparation for slabs and pavements

Earthworks recommendations provided in this report should be complemented by reference to AS3798-2007.

- Considering that the depth of existing fill materials are relatively shallow (within 0.6m of the existing ground surface) across the proposed building footprint, and the history and compaction control of that existing fill is not known, it is therefore recommended that the fill should be fully excavated down to surface of the residual soils, and stockpiled separately for further suitability assessment for potential re-use as engineered fill. Such excavation may need to be carried out with the excavation sides battered at an angle of no steeper than 1 Vertical to 3 Horizontal. The new fill must be 'keyed-in' the sides of these batters.
- The exposed subgrade at the base of the excavation should be proof rolled with a smooth drum roller (say 12 tonne) used in static or non-vibratory mode of operation. Caution is required when proof rolling near existing infrastructures and utilities (where present). The purpose of the proof rolling is to detect any soft or heaving areas, and to allow for some further improvement in strength or compaction.
- The final pass should be undertaken in the presence of an experienced geotechnician or geotechnical engineer, to detect any unstable or soft subgrade areas, and to allow for some further improvement in strength/compaction.
- If dry conditions prevail at the time of construction then any exposed alluvial clay subgrade may become desiccated or have shrinkage cracks prior to pouring any concrete slabs. If this occurs, the subgrade must be watered and rolled until the cracks disappear.
- Unstable subgrade detected during proof rolling should be locally excavated down to a sound base and replaced with engineered fill or further advice should be sought. Any fill placed to raise site levels should also be engineered fill, as per the specifications below.
- Where a raft slab is adopted, the geotechnical engineer would also need to carry out a series of Dynamic Cone Penetrometer (DCP) tests to assess the consistency of the subgrade materials. We expect that a capping layer of well graded crushed rock or recycled concrete (maximum particle size limited to 40mm) will be required to achieve adequate compaction. This granular layer will be required below the entire raft slab and would be of about 150mm thick.
- The performance of raft (including piled raft) slabs are also dependent on the whole of the design and construction team being familiar with the sensitivity of the situation. It is essential that any services which have to be placed in the subgrade are carefully positioned and an appropriate construction schedule/sequence is provided to the geotechnical engineer for approval at the planning stage.
- Disturbance of the subgrade must be minimised and kept outside the zone of influence of column or wall loads. A documented Inspection and Test Plan (ITP) should be prepared prior to construction with appropriate "hold" points in the Quality System.



#### 4.4.2 Engineered Fill Specifications

Any fill used to backfill unstable subgrade areas, raise surface levels or backfill service trenches should be engineered fill. Materials preferred for use as engineered fill are well-graded granular materials, such as ripped or crushed sandstone, free of deleterious substances and having a maximum particle size not exceeding 75 mm. such fill should be compacted in layers not greater than 200 mm loose thickness, to a minimum density of 98% of SMDD for cohesive soils, or minimum density index of 75% for cohesionless soils.

Density tests should be regularly carried out on the fill to confirm the above specifications are achieved. The frequency of density testing should be at least one test per layer per material type per  $1000 \text{ m}^2$  or 1 test per  $200\text{m}^3$  distributed reasonably evenly throughout full depth and area or 1 test per lot per layer, whichever requires the most tests, commensurate to Type 2 earthworks per Table 8.1 of AS3798-2007. We recommend that at least Level 2 control of fill compaction, as defined in AS3798-2007, be adhered to on this Site. Preferably, the geotechnical testing authority (GTA) should be engaged directly on behalf of the client and not by the earthworks subcontractor.

We recommend that the engineered fill layers extend a horizontal distance of at least 1m beyond the design geometry. The roller must extend over the edge of each placed layer in order to seal the batter surface. On completion of filling, the excess under-compacted edge fill should be trimmed back to the design geometry.

The 'tying in' of engineered fill to temporary cut batter slopes can be achieved by locally benching the cut slopes in no greater than 0.4m high steps. This can be carried out progressively as the height of engineered fill increases.

For backfilling confined excavations such as service trenches, a similar compaction to engineered fill should be adhered to, but if light compaction equipment is used then the layer thickness should be limited to 100mm loose thickness.

During construction of the fill, platform runoff should be enhanced by providing suitable falls to reduce ponding of water on the surface of the fill. Ponding of water may lead to softening of the fill and subsequent delays in the earthworks program. A poorly drained subgrade may become un-trafficable when wet. We recommend that if soil softening occurs, the subgrade be over-excavated to below the affected soil, and then replaced with engineered fill as specified above.

#### 4.5 Pavement Subgrade

The design of new pavements will depend on subgrade preparation, subgrade drainage, the nature and composition of fill excavated or imported to the site, as well as vehicle loadings and use. Various alternative types of construction could be used for the pavements. Concrete construction would undoubtedly be the best in areas where heavy vehicles manoeuvre such as trucks turning and manoeuvring. Flexible pavements may have a lower initial cost, but maintenance will be higher. These factors should be considered when making the final choice.

Based on the laboratory test results, the samples collected of the existing sandy clay from BH6M returned a CBR value 8%. Additional CBR testing of subgrade materials will be required where the subgrade materials and conditions differ to that tested across proposed pavement areas.

Further soaked CBR tests may be carried out on representative samples of the subgrade to obtain a large population of values to enable a proper statistical analysis to be performed and possibly an increase in the design CBR value. However, it should be borne in mind that even with more test values being obtained there will still be isolated pavement areas where the risk of potential failure and higher maintenance will occur due to the subgrade having a lower CBR value than the statistical characteristic value opted for design purposes.



We recommend that in situ density tests be completed on the proof rolled and prepared subgrade to confirm that at least 98% Standard Maximum Dry Density (SMDD) has been achieved. If the existing fill is removed and replaced with imported fill, the CBR of the imported material may be taken into account. These design values should be confirmed by inspection and Dynamic Cone Penetration (DCP) testing of the subgrade following proof rolling.

All upper (base) course should be crushed rock to RMS QA specification 3051 (2013) unbound base and compacted to at least 100% of SMDD. All lower (sub-base) course should be crushed rock to RMS QA specification 3051 (2013) unbound base or ripped/crushed sandstone with CBR greater than 40%, maximum particle size of 60mm, well graded and Plastic Index less than 10. All lower course material should be compacted to an average of no less than 100% of SMDD, but with a minimum acceptance value of 98% of SMDD.

Concrete pavements should have a sub-base layer of at least 100mm thickness of crushed rock to RMS QA specification 3051 (2013) unbound base material (or equivalent good quality and durable fine crushed rock) which is compacted to at least 100% SMDD. Concrete pavements should be designed with an effective shear transmission of all joints by way of either doweled or keyed joints.

Careful attention to subsurface and surface drainage is required in view of the effect of moisture on the clay soils. Pavement levels will need to be graded to promote rapid removal of surface water so ponding does not occur on the surface of pavements. The drainage trenches should be excavated with a uniform longitudinal fall to appropriate discharge points so as to reduce the risk of water ponding. The capacity of the stormwater collection system from the pavement should be checked and upgraded if necessary. In order to protect the pavement edge, subsoil drains should be provided along the perimeter of all proposed new external pavement areas, particularly in those areas of cut, with invert levels of at least 200mm below subgrade level.

The long-term successful performance of the pavements is dependent on the satisfactory completion of the earthworks. In order to achieve this, the quality assurance programme should not be limited to routine compaction density testing only. Other important factors associated with the earthworks includes subgrade preparation, selection of fill materials, control of moisture content and drainage, etc.



## 5. Further Geotechnical Inputs

Below is a summary of the recommended additional work that may need to be carried out:

- Additional CBR tests to inform pavement thickness design, if required;
- Classification of all excavated material transported off site; and
- Geotechnical inspections of all new footings/piles by an experienced geotechnical professional before concrete or steel are placed to verify their bearing capacity and the insitu nature of the founding strata.

We recommend that a meeting be held after initial structural design has been completed to confirm that our recommendations have been correctly interpreted. We also recommend a meeting at the commencement of construction to discuss the primary geotechnical issues and inspection requirements.



## 6. Statement of Limitations

This report has been prepared for the exclusive use of Craig Butler and Lipman Pty Ltd who is the only intended beneficiary of El's work. The scope of the assessment carried out for the purpose of this report is limited to those agreed with Craig Butler and Lipman Pty Ltd

No other party should rely on the document without the prior written consent of EI, and EI undertakes no duty, or accepts any responsibility or liability, to any third party who purports to rely upon this document without EI's approval.

El has used a degree of care and skill ordinarily exercised in similar investigations by reputable members of the geotechnical industry in Australia as at the date of this document. No other warranty, expressed or implied, is made or intended. Each section of this report must be read in conjunction with the whole of this report, including its appendices and attachments.

The conclusions presented in this report are based on a limited investigation of conditions, with specific sampling and test locations chosen to be as representative as possible under the given circumstances.

El's professional opinions are reasonable and based on its professional judgment, experience, training and results from analytical data. El may also have relied upon information provided by the Client and other third parties to prepare this document, some of which may not have been verified by El.

El's professional opinions contained in this document are subject to modification if additional information is obtained through further investigation, observations, or validation testing and analysis during construction. In some cases, further testing and analysis may be required, which may result in a further report with different conclusions.

We draw your attention to the document "Important Information", which is included in **Appendix D** of this report. The statements presented in this document are intended to advise you of what your realistic expectations of this report should be. The document is not intended to reduce the level of responsibility accepted by EI, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in so doing.

Should you have any queries regarding this report, please do not hesitate to contact El.



## References

AS1289.6.3.1:2004, Methods of Testing Soils for Engineering Purposes, Standards Australia.

AS1726:2017, Geotechnical Site Investigations, Standards Australia.

AS2159:2009, Piling - Design and Installation, Standards Australia.

AS3600:2009, Concrete Structures, Standards Australia

AS3798-2007, Guidelines on Earthworks for Commercial and Residential Developments

Safe Work Australia Excavation Work Code of Practice, dated January 2020 – WorkCover NSW

NSW Department of Finance and Service, Spatial Information Viewer, maps.six.nsw.gov.au.

NSW Department of Mineral Resources (1983) Sydney 1:100,000 Geological Series Sheet 9130 (Edition 1). Geological Survey of New South Wales, Department of Mineral Resources.

## Abbreviations

AHD	Australian Height Datum
AS	Australian Standard
BEL	Bulk Excavation Level
BEGL	Below Existing Ground Level
BH	Borehole
DBYD	Dial Before You Dig
DP	Deposited Plan
EI	El Australia
GI	Geotechnical Investigation
NATA	National Association of Testing Authorities, Australia
RL	Reduced Level
SPT	Standard Penetration Test
T-C	Tungsten-Carbide
UCS	Unconfined Compressive Strength



## Figures

- Figure 1 Site Locality Plan
- Figure 2 Borehole Location Plan





- Site boundary \_ \_ \_
- ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   ●
   Borehole locations
- Monitoring Well locations

eiaustralia Suite 6.01, 55 Miller Street, PYRMONT 2009 Ph (02) 9516 0722 Fax (02) 9518 5088

Drawn:	J.O.	
Approved:	M.L.	
Date:	8-8-2023	

Lipman Pty Ltd Geotechnical Investigation 1H Hospital Road, Concord, NSW Borehole Location Plan

2

Project: E25996.G03

Appendix A – Borehole Logs And Explanatory Notes



### BH ID: BH1M

Loca Clien Job N Shee	tion1H Hospital Road, Concord West, NSWStartntLipman Pty LtdCompNo.E25996.G03Loggeets1 of 2Revie						arted impleted gged By iview Bv	24 24 JC	4 May 4 May ) 1L	2023 2023 Date Date	24 May 2023 08 August 2023	
Drilli	ng Co	ontractor Geosense	Drill	ing Er	nginee	rs	Surface RL - Nor	orthing	6	25446	0.6730 (MGA	2020 Zone 56)
Plan	t	Comacchie	o Ge	- o 205	_		Inclination 90° Eas	sting	32	23863	.8164 (MGA	2020 Zone 56)
METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION			CONSISTENCY / REL. DENSITY	MAT & O	TERIAL ORIGIN BSERVATIONS
		BH1M_0.50-0.95		0.00_ 0.10_ -			ASPHALT: 100mm thick FILL: Silty SAND: fine to medium grained, dark brown with si angular to sub-rounded gravels, appears well compacted.	sub-	- D	-	ASPHALT FILL	,
AD/T	2023 7:10:00 AM	SPT 0.50-0.95 8,15,30 N=45 BH1M_1.50-1.65		0.60			Silty CLAY: low to medium plasticity, pale grey-orange	м	< PL	Н	RESIDUAL SC	DIL
	7/25/	18/150 mm HB N=R		1.65- - 2 - - - - - - - - - - - - - -			SANDSTONE: fine to medium grained, pale grey-orange, extremely weathered.		-	-	WEATHERED	ROCK
				3.00 <sup>-</sup>			Log continued on next page.					

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



### BH ID: BH1M

Locat Clien Job N Shee	tion t lo. ts	1H H Lipm E259 2 of 2	ospita an Pt 96.G( <u>2</u>	Started     24 May 2023       Pty Ltd     Completed     24 May 2023       G03     Logged By     JO     Date     24 May 2023       Review By     ML     Date     08 Augu										20: ust	23 202	23		
Drilli	ng Co	ontrac	tor	Geo	sense	Drilli	ng Engineers Surface RL -				N	lor	thi	ng 6254460.6730 (MGA 2020 Zo	ne !	56)	)	
Plant				Com	nacchi	o Geo	205 Inclination 90°		1		E	as	ting	g 323863.8164 (MGA 2020 Zon	20 Zone 56)			
METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	WEATHERING	VL 0.4	STF STF	REN Is(50 Dian	iGTI D) xial metr	D H al ₽ H	DISCONTINUITIES & ADDITIONAL DATA	F 02	SPA		3000 3000
							Log continued nom previous page.											
				2														
	0% Water	0	0	3			NO CORE: 1150mm thick	-										
LC		100	57	4.15			SANDSTONE: fine to medium grained, pale grey-orange, thinly to medium bedded	DW										
MN	0% Water			- 6-				sw		-				5.91: JT 45° PR SM CN				
	96	100	92					FR			•	,		7.43: JT 1° PR SM CN				
				9			Terminated at 7.60m. Target Depth Reached.											

This log should be read in conjunction with El Australia's accompanying explanatory notes.



### BH ID: BH1M

Loca Clien Job N Shee	tion 1H Hospita t Lipman Pty No. E25996.GC ets 1 of 1	il Roac / Ltd )3	l, Conco	ord V	Vest, NSW		Started Completed Logged By Review By	24 May 202 24 May 202 JO ML	3 3 Date Date	24 May 2023 08 August 2023
Drilli	ng Contractor	Geos	ense Di	filling	Engineers Surface RL -		Northing	6254460.67	'30 (MGA	2020 Zone 56)
Plan	t	Coma	acchio (	Geo 2	205 Inclination 90°		Easting	323863.816	54 (MGA 2	2020 Zone 56)
WATER	SAMPLES & FIELD TESTS	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	MOISTURE	BACKFILL DETAILS			STANDPIPE DETAILS
	BH1M_0.50-0.95	0.00			ASPHALT: 100mm thick FILL: Silty SAND: fine to medium grained, dark brown with sub-angular to sub-rounded gravels, appears well compacted.	- D	Grout 0.00m - 0.10m			Well Stickup =0.0m
23 7:10:00 AM	SPT 0.50-0.95 8,15,30 N=45	0.60			Silty CLAY: low to medium plasticity, pale grey- orange	M < PL	Sand . 0.10m - 2.50m			
7/25/20	BH1 <u>M</u> _1.50-1.65 SPT 1.50-1.65 18/150 mm HB N=R	1.65 2-			SANDSTONE: fine to medium grained, pale grey- orange, extremely weathered.	-				0.0m - 3.0m PVC casing (50mm Ø)
		3.80		-	NO CORE: 1150mm thick		Bentonite 2.50m - 3.00m			
0% Water		4-								
		4.15			SANDSTONE: fine to medium grained, pale grey- orange, thinly to medium bedded		Sand			3.0m - 6.0m PVC screen (50mm Ø)
90% Water		6-					3.00m - 7.60m			
		8-			Terminated at 7.60m. Target Depth Reached.	-		7994 1979 1999 1997 1999 1999 1997 1999 1999		
		9-								

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



### **CORE PHOTOGRAPH OF BOREHOLE: BH1M**

Project	Proposed Redevelopment			Depth Range	3.0m to 7.6	0m BEGL	
Location	1H Hospital Road, Concord West, NSW			Contractor	Geosense	Drilling E	ngineers Pty Ltd
Position	See Figure 2	Surface RL	≈-	Drill Rig	Comacchie	o GEO 20	5
Job No.	E25669.G03	Inclination	<b>-</b> 90°	Logged	JO	Date	24 / 05 / 2023
Client	Lipman Pty Ltd	Box	1 of 1	Checked	KX	Date	16 / 06 / 2023





### BH ID: BH2

Locat Clien Job N Shee	tion t No. ts	1H Hospital Road, Cor Lipman Pty Ltd E25996.G03 1 of 2	ncord	d Wes	it, NSW	/	Sta Cor Log Rev	arted mpletec gged By view Bv	24 I 24 JC	4 May 4 May C 1L	2023 2023 Date 24 May 2023 Date 08 August 2023
Drilli	illing Contractor Geosense Drilling Enginee				nginee	rs	Surface RL - Noi	rthing	6	25449	1.6526 (MGA 2020 Zone 56)
Plant	t	Comacchie	o Ge	o 205			Inclination 90° Eas	sting	3	23813	.7977 (MGA 2020 Zone 56)
МЕТНОD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION		MOISTURE	CONSISTENCY / REL. DENSITY	MATERIAL ORIGIN & OBSERVATIONS
				0.00		-	ASPHALT: 100mm thick FILL: Silty SAND: fine to medium grained, dark brown with s	sub-	-	-	ASPHALT FILL
		BH2_0.50-0.95 SPT 0.50-0.95		0.60			angular to sub-rounded gravels, appears well compacted. Silty CLAY: low to medium plasticity, brown		D	-	RESIDUAL SOIL
<u>у</u> т	NE	4,0,0 N= 14		- 1- - - -				M	< PL	St	
AC	GM	SPT 1.50-1.72 7,8/75 mm HB N=R		1.72 2			SANDSTONE: fine to medium grained, pale grey-orange, extremely weathered.				WEATHERED ROCK
									-	-	
				3.00	-	_	Log continued on next page.				
				-		_					
				-	-	_					
				4-		_					
				-	-	_					
						_					
				-	-	_					
				5-	-	_					
				-	-	_					
				-		_					
				-	-	_					
				6-		_					
						_					
				-	-	_					
				-	-	_					
				7-	-	_					
				-	-	_					
				-		_					
				-	-	_					
				8-		_					
				-		_					
						_					
						_					
				9-		-					
				-		_					
					-	_					

This log should be read in conjunction with El Australia's accompanying explanatory notes.



### BH ID: BH2

Loca	tion	1H H	ospita	al Roa	id, Coi	ncord	West, NSW				St	arte	ed 24 May 2023	
Clien	t	Lipman Pty Ltd Completed 24 May 2023											pleted 24 May 2023	
Job N	No.	E259	96.G(	)3							Lo	gge	<b>ed By</b> JO <b>Date</b> 24 May 2023	
Shee	ts	2 of 2	2						Review By ML Date 08 Augu					
Drilli	ng Co	ontrad	tor	Geo	sense	Drilli	ng Engineers Surface RL -	Northing 6254491.6526 (MGA 2020 Zone 56)						
Plant	t			Com	nacchi	o Geo	205 Inclination 90°				Ea	ng 323813.7977 (MGA 2020 Zone 56)		
	c			-				U		ESTI		ED	FRACTURE	
QQ	eturi					AHD		RIN		ls ▼	s(50)	al	SPACING	
ШЩ	sh R	TCR	gD	PTF	RAP LO(	(m)	MATERIAL DESCRIPTION	ATHE	7	7 - D	Diam	etral	& ADDITIONAL DATA	
≥	ΡĽ	·	-	BE	G	님		WE/	/L 0.1	. 0·3	 	ΞΞ		
				0-		-	Log continued from previous page.							
				-		-								
				-		_								
				-		_								
				-		-								
				-		E								
				-		L								
				-		-								
				-		-								
				2—		-								
				-		-								
						E								
				-		E								
				-		_								
				3-		-	SHALE: dark grey-brown, very thinly bedded						3.10-3.15: CS	
				-		-			v					
				-										
		œ	<u>-</u>	_				DW						
		~	<i>с</i> о	4-										
				-						Y				
				4.24 –	$\times$	-	NO CORE: 360mm thick	-						
		<u> </u>		4.60	5.50	SHALE: dark grev-brown thinly bedded			_					
	<u> </u>													
ILC	Wate			5-			sw							
N	, %06	2	5	-						Ĭ				
	0,	9	-	5 50		-	SANDSTONE: fine to medium grained, hale gray						5.50-5.59: CS	
				5.58		ş- -	NO CORE: 530mm thick				1			
				6-				-						
				6.11			SANDSTONE: fine to medium grained, pale grey, medium							
				-		_	bedded					1		
		0	6	-	_	-								
		þ	6	_		-		FK						
				7—		-								
							Terminated at 7 24m Target Depth Reached							
				-			Terminated at 7.24m. Target Deptil Acadica.							
				-		_								
				-		_								
				8		-								
				-		E								
				_										
						L								
				9-		F								
				-		F								
				-		F								
				-		F								
				-		E								
L		I		10-		⊥ This	L s log should be read in conjunction with EI Australia'	s acco	<u>с</u> ст	par	nyir	ng ex		



### **CORE PHOTOGRAPH OF BOREHOLE: BH2**

Project	Proposed Redevelopment	Depth Range	3.0m to 7.24m BEGL						
Location	1H Hospital Road, Concord West, NSW	Contractor	gineers Pty Ltd						
Position	See Figure 2	≈-	Drill Rig	5					
Job No.	E25669.G03	Inclination	<b>-</b> 90°	Logged	JO	Date	24 / 05 / 2023		
Client	Lipman Pty Ltd	Box	1-2 of 2	Checked	KX	Date	16 / 06 / 2023		





### BH ID: BH3M

Location		1H Hospital Road, Cor	ncord	d Wes	st, NSW	'	Star	arted	2	3 May	2023		
Client		Lipman Pty Ltd					Con	mpleted	<b>d</b> 2	3 May	2023		
Job I	lo.	E25996.G03					Log	gged By	JC	)	Date	23 May 2023	
Shee	ts	1 of 2	<b>D</b>				Rev	view By	N N	1L	Date	08 August 2023	
Driili	ng Co	ontractor Geosense	Drill	ing Ei	ngineer	S	Surface RL - Nor	ortning	6.	25439	1.6565 (IVIGA	(2020 Zone 56)	
Plan	t Irr	Comacchio	o Ge	o 205	5		Inclination 90° East	sting	3	23860	.6592 (MGA :	2020 Zone 56)	
METHOD	GROUND WATEF	SAMPLES & FIELD TESTS	SAMPLE RECOVERN	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION		MOISTURE CONDITION	CONSISTENCY REL. DENSITY	MAT & O	TERIAL ORIGIN BSERVATIONS	
				0.00		_	FILL: Clayey SAND: fine to medium grained, dark brown, app well compacted.	opears	D	-	FILL		
AD/T	MA OC	BH9M_0.50-0.95 SPT 0.50-0.95 4,6,8 N=14		0.30			Silty CLAY: low to medium plasticity, orange-brown			St	RESIDUAL SC	DIL	
	7/25/2023 7:15:00	BH9M_1.50-1.95 SPT 1.50-1.95 6,7,12 N=19	9M_1.50-1.95 r 1.50-1.95 ,12 N=19				From 1.80m, pale grey-orange	30m, pale grey-orange VSt					
				2.52		-	Log continued on next page.						
				3- 									

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



### BH ID: BH3M

Loca Clien Job N Shee	tion It No. ets	1H H Lipm E259 2 of 2	ospit an Pt 96.G( 2	al Roa y Ltd 03	ıd, Coı	ncord	West, NSW	Star Con Log Rev					d leted d By w By	23 May 2023 23 May 2023 JO <b>Date</b> ML <b>Date</b>	23 May 08 Augu	202 Jist 2	23	3	
Drilli	ng Co	ontrad	tor	Geo	sense	Drillir	ng Engineers Surface RL -				No	orth	ing	6254391.6565 (MG	A 2020 Zo	ne !	56)		
Plan	t		-	Com	nacchi	o Geo	205 Inclination 90°				Ea	stin	g	323860.6592 (MGA	2020 Zon	e 50	5)		
METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	WEATHERING	VL <sub>0.1</sub>	ESTI STR Is ▼-D	IMAT ENG s(50) - Axia Diame	ED GTH al etral ♀ H∧		DISCONTINUITIES & ADDITIONAL DATA					
		100	26	- 0         			Log continued from previous page. SANDSTONE: fine to medium grained with iron staining and pale grey clay seams, very thinly bedded									3			
NMLC	%06	100	20				SANDSTONE: fine to medium grained, pale grey-brown mottled orange, very thinly bedded, with shale laminations From 4.50m, pale grey-brown, thinly bedded	FR		•	•	2							
							Terminated at 6.00m. Target Depth Reached.							story notes					



### BH ID: BH3M

Loca Clien Job N Shee	tion 1H Hospita t Lipman Pty No. E25996.GO ts 1 of 1	Il Roac / Ltd  3	l, Conco	ord V	Started Completed Logged By Review By	23 May 2023 23 May 2023 JO ML	Date Date	23 May 2023 08 August 2023			
Drilli	ng Contractor	Geos	ense Di	rilling	Engineers Surface RL -	Northing	6254391.65	65 (MGA	2020 Zone 56)		
Plan	t	Coma	acchio (	Geo 2	205 Inclination 90°		Easting	323860.659	2 (MGA 2	2020 Zone 56)	
WATER	SAMPLES & FIELD TESTS	DEPTH (m)	GRAPHIC LOG	RL (m AHD)	MATERIAL DESCRIPTION	MOISTURE CONDITION	BACKFILL DETAILS			STANDPIPE DETAILS	
		0.00	-	F	FILL: Clayey SAND: fine to medium grained, dark brown, appears well compacted.	D	Grout 0.00m - 0.10m			Well Stickup =0.0m	
:15:00 AM	BH9M_0.50-0.95 SPT 0.50-0.95 4,6,8 N=14	0.30			Silty CLAY: low to medium plasticity, orange-brown	M <	Sand 0.10m - 2.50m				
7/25/2023 7	BH9M_1.50-1.95 SPT 1.50-1.95 6,7,12 N=19	1.80			From 1.80m, pale grey-orange	PL				0.0m - 3.0m PVC casing (50mm Ø)	
%06		3-			SANDSTONE: fine to medium grained with iron staining and pale grey clay seams, very thinly bedded SANDSTONE: fine to medium grained, pale grey- brown mottled orange, very thinly bedded, with shale laminations		Bentonite 2.50m - 3.00m				
		4.50			From 4.50m, pale grey-brown, thinly bedded		Sand 3.00m - 6.00m			3.0m - 6.0m PVC screen (50mm Ø)	
		7			Terminated at 6.00m. Target Depth Reached.	alia's :	accompanying explanat	ory notes.			


# CORE PHOTOGRAPH OF BOREHOLE: BH3M

Location     1H Hospital Road, Concord West, NSW     Contractor     Geosense Drilling Engineers Pty Ltd       Job No.     E25669.G03     Inclination     -90°     Logged     JO     Date     23/05/2023       Client     Lipman Pty Ltd     Box     1 of 1     Checked     KX     Date     16/06/2023	Location     1H Hospital Road, Concord West, NSW     Surface RL     ≈ -     Contractor     Geosense Drilling Engineers Pty Ltd       Job No.     E25669.G03     inclination     -90°     Logged     JO     Date     23 / 05 / 2023       Client     Lipman Pty Ltd     Box     1 of 1     Checked     KX     Date     16 / 06 / 2023	Project	Proposed Redevelopment			Depth Range	2.52m to 6	.0m BEG	L
Position Job No.     See Figure 2 E25669.G03     Surface RL Lipman Pty Ltd     ≈- Inclination Box     Drill Rig Logged     Comacchio GEO 205       Client     Lipman Pty Ltd     Box     1 of 1     Checked     KX     Date     23 / 05 / 2023       E25699.G03     Eigend     Iof 1     Checked     KX     Date     16 / 06 / 2023	Position Job No.     See Figure 2 E25669.G03     Surface RL ≈- Inclination -90°     Drill Rig Logged     Comacchio GEO 205       Client     Lipman Pty Ltd     Box     1 of 1     Checked     KX     Date     23 / 05 / 2023	Location	1H Hospital Road, Concord West, NSW			Contractor	Geosense	Drilling E	Engineers Pty Ltd
Job No.         E25669.G03         Inclination         -90°         Logged         JO         Date         23/05/2023           Client         Lipman Pty Ltd         Box         1 of 1         Checked         KX         Date         16/06/2023           E25996-CONCORD         BH3M           ZSTART         CORING         2.52         2.52	Job No. E25669.G03 Client Lipman Pty Ltd Box 1 of 1 Checked KX Date 23/05/2023 E259996-CONCORD BH3M 2 START CORTING @ 2.52 3 4	Position	See Figure 2	Surface RL	≈-	Drill Rig	Comacchi	o GEO 2	05
Client Lipman Pty Ltd Box 1 of 1 Checked KX Date 16/06/2023 E25996-CONCORD BH3M 2 START CORTING @ 2.52m 3	Client     Lipman Pty Ltd     Box     1 of 1     Checked     KX     Date     16/06/2023	Job No.	E25669.G03	Inclination	<b>-</b> 90°	Logged	JO	Date	23 / 05 / 2023
E25996-CONCORD BH3M 2 START CORING @ 2.52 M 3	E25996-CONCORD BH3M 2 START CORING @ 2.52m 3 4	Client	Lipman Pty Ltd	Box	1 of 1	Checked	KX	Date	16 / 06 / 2023
A CARLENDER CONTRACTOR AND A CARLENDER AND A CAR		E 2 3 4 5	E25996 - CONCORD START CORING @ 2.52	BH3M					
5 LEAD AND AND AND AND AND AND AND AND AND A									



## BH ID: BH4

Loca Clier	tion It	1H Hospital Road, Cor Lipman Pty Ltd	cord	d Wes	t, NSV	/	Star Con	arted mpleted	2	3 May 3 May	2023 2023	
Job I	No.	E25996.G03					Log	gged By	JC	)	Date	23 May 2023
Shee	ts ng Ca	1 of 2	Drill	ing Er	nginoo	rc	Rev Surface Pl	view By	N	1L 25441	Date	08 August 2023
Plan	ng cu t	Comacchi	o Ge	o 205	Iginee	15	Inclination 90° East	sting	3	23885	.7601 (MGA	2020 Zone 56)
METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION		MOISTURE	CONSISTENCY / REL. DENSITY	MA & (	TERIAL ORIGIN DESERVATIONS
		BH4_0.50-0.95 SPT 0.50-0.95 8,6,12 N=18		0.00			FILL: Silty SAND: fine to medium grained, dark brown trace s angular to sub-rounded gravels, appears well compacted. Silty CLAY: low to medium plasticity, pale grey-orange	sub-	D	-	FILL RESIDUAL S	OIL
AD/T	GWNE	BH4_1.50-1.85 SPT 1.50-1.85 14,16,3/50 mm HB N=R		1				М	I < PL	VSt	WEATHEREI	POCK
				2			extremely weathered.		-	-	WEATHERE	, KOCK
				3								
				9								

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



## BH ID: BH4

Loca	tion	1H H	ospita	al Roa	d, Coi	ncord	West, NSW				S	tart	ec	d 23 May 2023
Clien	t	Lipm	an Pt	y Ltd							С	om	plo	eted 23 May 2023
Job I	No.	E259	96.G(	)3							L	ogg	ed	J By         JO         Date         23 May 2023           D         Date         Date         Date         Date
Shee	ts	2 of .	2	6		D					R	evie	ew 	<b>V By</b> ML <b>Date</b> 08 August 2023
Driili	ng Co	ontrac	tor	Geo	sense	Drillir	ng Engineers Surface RL -				N	ort	nı	ng 6254416.9818 (MGA 2020 Zone 56)
Plan	t I	1		Com	acchi	o Geo T	0 205 Inclination 90°	,	Т	EST	E	asti	ing	g 323885.7601 (MGA 2020 Zone 56)
METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (m AHD)	MATERIAL DESCRIPTION	WEATHERING	L 0.1	STF I ▼ - I	REN Is(50 - Ax Diam	GTH (ial netral	ц	DISCONTINUITIES & ADDITIONAL DATA
				0-		Ļ	Log continued from previous page.	-	>		≥ı		ш	
							SANDSTONE: fine to medium grained, pale grey with	iron						
				3-			staining and clay seams, very thinly to thinly bedded	DW		•				
Q	/ater	96	28	3.40 _ - - 4_ -	$\left \right\rangle$		NO CORE: 900mm thick	-						
NMN	M %06			4.30   5			SANDSTONE: fine to medium grained, pale grey with staining and clay seams, thinly to medium bedded	sw			•			4.34-4.41: XWS
		100	78					FR			T			
							Terminated at 6.00m. Target depth reached.	tralia's acc	orr	пра	nyi	nge	ex	planatory notes.



# CORE PHOTOGRAPH OF BOREHOLE: BH4

Project	Proposed Redevelopment			Depth Range	2.70m to	6.0m BEGL	-
Location	1H Hospital Road, Concord West, NSW			Contractor	Geosens	e Drilling E	ngineers Pty Ltd
Position	See Figure 2	Surface RL	≈-	Drill Rig	Comacch	nio GEO 20	)5
Job No.	E25669.G03	Inclination	<b>-</b> 90°	Logged	JO	Date	23 / 05 / 2023
Client	Lipman Pty Ltd	Box	1 of 1	Checked	KX	Date	16 / 06 / 2023
1							
		0114					
ter st	=25996 - CONCORD	BH4			1.4.5	1	
2	START CORTNIC 270	m		17			
4	UTART CONTING 2.10						a state of the sta
31			CORE	LOS	S 9	00r	nm
4 -	$\longrightarrow$			LUIT -		P	
50		11		1 18 61			
1000		16 17 18	no in 20 in 20 In 20 in 2 In 20 in 2	26 217 28 29 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7	30 31 5 5 7 5 50	32 33 3	a <u>as maa</u> t 38 3 Teeleony 12 5 4 5 6 1 4 5



## BH ID: BH5

Loca	tion	1H Hospital Road, Cor	ncord	d Wes	st, NSW	/	Starte	ed	2	3 May	2023
Clier	nt	Lipman Pty Ltd					Comp	lete	<b>d</b> 2	3 May	2023
JOD I	NO. tc	1 of 2					Logge Bovie	a By		) //	Date 23 May 2023
Drilli	ing Co	ntractor Geosense	Drill	ing Fr	ngineer	rs	Surface RL - North	ing	6	25441	5.7362 (MGA 2020 Zone 56)
Plan	t	Comacchi	o Ge	o 205			Inclination 90° Eastin	Ig	3	23823	.2479 (MGA 2020 Zone 56)
ИЕТНОD	UND WATER LEVELS	SAMPLES & FIELD TESTS	PLE RECOVERY	EPTH (m)	SRAPHIC LOG	L (m AHD)	MATERIAL DESCRIPTION		IOISTURE DNDITION	ISISTENCY /	MATERIAL ORIGIN & OBSERVATIONS
-	GRO		SAMI		0	R			Σö	CON	
				0.00		_	ASPHALT: 150mm thick	ılar	-	-	ASPHALT
		BH4_0.50-0.60 BH4_0.50-0.95		0.60		-	to sub-rounded gravels, appears well compacted.	ie	D	-	
		SPT 0.50-0.95 4,10,16 N=26				- - -	fine to medium grained	13		VSt	
		BH4_1.50-1.68		1.40		-	Silty CLAY: low to medium plasticity, pale grey-orange				
AD/T		10,3/35 mm HB N=R		2-		_ _ _ _			/1 < PL		
				-		-				н	
	Ш					-					
	GW	SPT 3.00-3.45 20,16,19 N=35									
				3.45-	-	_	Log continued on next page.				
				4							
				9-							

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



## BH ID: BH5

Loca	tion	1H H	ospit	al Roa	d, Coi	ncord	West, NSW			:	Starte	ed	23 N	May 2023					
Clien	nt	Lipm	an Pt	y Ltd							Comp	leted	23 N	May 2023					
Jop I	No.	E259	96.G	03						I	Logge	d By	JO		Date	23 May	202	3	
Shee	ets	2 of :	2								Revie	w By	ML		Date	08 Augi	ıst 2	023	}
Drilli	ng Co	ontra	tor	Geo	sense	Drillir	ng Engineers Surface RL -			I	North	ing	625	4415.736	2 (MGA	2020 Zo	ne 5	6)	
Plan	t			Com	acchi	o Geo	205 Inclination 90°				Eastir	g	323	823.2479	(MGA 2	020 Zon	e 56	)	
гнор	Return	K %	2D %	TH (m)	APHIC 0G	n AHD)	MATERIAL DESCRIPTION	HERING		ESTIN STREI Is(5 V - Dia	ATED NGTH 50) Axial		ŗ		UITIES		FF	RACT	URE ING
ME	Flush	Ĭ	Ж	OEF	GR	BL (		WEAT	VI 0.1	Ξ Ξ	EH M H H H	5		ADDITION			30	300	3000
							Log continued from previous page.												
NMLC	90% GWNE	100	92	4			SANDSTONE: fine to medium grained, pale grey-orange, thinly to medium bedded	DW SW- FR			• •								
							Terminated at 6.00m. Target Depth Reached.				ingo			atas					



# CORE PHOTOGRAPH OF BOREHOLE: BH5

Project	Proposed Redevelopment			Depth Range	3.45m to 6	0.0m BEGI	-
Location	1H Hospital Road, Concord West, NSW			Contractor	Geosense	e Drilling E	Ingineers Pty Ltd
Position	See Figure 2	Surface RL	≈-	Drill Rig	Comacchi	io GEO 20	05
Job No.	E25669.G03	Inclination	<b>-</b> 90°	Logged	JO	Date	23 / 05 / 2023
Client	Lipman Pty Ltd	Box	1 of 1	Checked	KX	Date	16 / 06 / 2023
	E25996 - CONCORD	BH5			•		
3	START CORE 3.45m				<u>J</u>		
4				·	Alexandra	the second	
5	TO MANY MERCE				1.ju		
	CORE TERMINATE G	) 6.0 <sup>-</sup>	19 - 20 - 21 - 22 - 23 - 14 - 23 - 2 19 - 20 - 21 - 22 - 23 - 14 - 23 - 23 - 2	6 27 28 29 29 3 5 5 10 1 5 5 4 5	3.0 3.1 3.2	33 34	



## BH ID: BH6M

Location 1H Hospital Road, Concord West, NSW Started 22 May 2023 Lipman Pty Ltd 22 May 2023 Client Completed Job No. E25996.G03 Date 22 May 2023 Logged By JO Sheets 1 of 2 **Review By** ML Date 08 August 2023 Drilling Contractor Geosense Drilling Engineers Surface RL Northing 6254392.3215 (MGA 2020 Zone 56) Plant Comacchio Geo 205 Inclination 90° Easting 323853.4352 (MGA 2020 Zone 56) GROUND WATER LEVELS CONSISTENCY / REL. DENSITY SAMPLE RECOVER' MOISTURE GRAPHIC LOG RL (m AHD) DEPTH (m) METHOD SAMPLES & FIELD TESTS MATERIAL ORIGIN & OBSERVATIONS MATERIAL DESCRIPTION 0.00 FILL: Sandy CLAY: low to medium plasticity, brown-orange, with sub-angular to sub-rounded gravels, appears well compacted. FILL BH12M\_0.50-0.95 SPT 0.50-0.95 4,5,6 N=11 D -1-AD/T 7/25/2023 7:20:00 AM BH12M\_1.50-1.95 SPT 1.50-1.95 3,5,7 N=12 RESIDUAL SOIL Silty CLAY: low to medium plasticity, pale grey-orange 1.60 M < PL St 2 2.30 Log continued on next page. 3. 4 5-6 7 8-9-

This log should be read in conjunction with El Australia's accompanying explanatory notes.



## BH ID: BH6M

Locat Clien Job N Shee	tion t lo. ts	1H H Lipm E259 2 of 2	ospita an Pt 96.G( 2	al Roa y Ltd )3	ıd, Cor	ncord	West, NSW				9 () 	Star Con Logg Rev	teo npl geo iev	22 May 2023           sted         22 May 2023           By         JO         Date           My         ML         Date	22 May 08 Augu	20 ust :	23	23	
Drilli	ng Co	ontrac	tor	Geo	sense	Drilli	ng Engineers Surface RL -				ſ	Nor	thi	ng 6254392.3215 (M	GA 2020 Zo	ne	56)		
Plant	t			Com	nacchio	o Geo	205 Inclination 90°		-		6	East	ing	323853.4352 (MG	4 2020 Zon	e 5	5)		
METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (m AHD)	MATERIAL DESCRIPTION	WEATHERING	VI	ES ST ▽-	TIM REN Is(5 7 - A Dia	ATEL NGTH i0) Axial metra HX	EH = + C	DISCONTINUITIE: & ADDITIONAL DA	3 TA	F 30			3000
				0			Log continued from previous page.												
				-		-	SANDSTONE: fine to medium grained, pale grey, thinly to medium bedded	DW						2.43-2.73: CZ					1
IMLC	%0	46	25	2.73 3   4 4.20 			NO CORE: 1470mm thick SANDSTONE: fine to medium grained, pale grey-orange, medium bedded	-	-		1	V						-	
		100	100					FR			•	•							
						- - -	Terminated at 7.20m. Target depth reached.		t										+
				8 															

This log should be read in conjunction with El Australia's accompanying explanatory notes.



## BH ID: BH6M

Location 1H Hospital Road, Concord West, NSW Started 22 May 2023 Client Lipman Pty Ltd Completed 22 May 2023 Job No. E25996.G03 Logged By Date JO 22 May 2023 Sheets 1 of 1 **Review By** ML Date 08 August 2023 Drilling Contractor Geosense Drilling Engineers Surface RL Northing 6254392.3215 (MGA 2020 Zone 56) \_ Plant Comacchio Geo 205 90° 323853.4352 (MGA 2020 Zone 56) Inclination Easting MOISTURE GRAPHIC LOG (m AHD) Ē WATER SAMPLES & FIELD TESTS DEPTH ( MATERIAL DESCRIPTION STANDPIPE DETAILS BACKFILL DETAILS 님 0.00 FILL: Sandy CLAY: low to medium plasticity, brown-orange, with sub-angular to sub-rounded gravels, appears well compacted. Grout 0.00m - 0.10m Well Stickup =0.0m BH12M\_0.50-0.95 SPT 0.50-0.95 4,5,6 N=11 D 1-7/25/2023 7:20:00 AM Sand 0.10m - 2.50m BH12M\_1.50-1.95 SPT 1.50-1.95 3,5,7 N=12 0.0m - 3.0m PVC casing (50mm Ø) Silty CLAY: low to medium plasticity, pale grey-1.60 orange M < PL 2-SANDSTONE: fine to medium grained, pale grey, thinly to medium bedded 2.30 2.73 NO CORE: 1470mm thick Bentonite 2.50m - 3.00m 3 4 4 20 SANDSTONE: fine to medium grained, pale greyorange, medium bedded 3.0m - 6.0m PVC screen (50mm Ø) %0 5 Sand 3.00m - 7.20m 6 7 Terminated at 7.20m. Target depth reached. 8 9 10 This log should be read in conjunction with El Australia's accompanying explanatory notes.



# CORE PHOTOGRAPH OF BOREHOLE: BH6M

Project Location	Proposed Redevelopment 1H Hospital Road, Concor	d West, NSW				Depth Range Contractor	2.3m to 7 Geosens	7.2m BEGL se Drilling E	Engineers Pty Lto	d
Position	See Figure 2			Surface RL	≈-	Drill Rig	Comacc	hio GEO 2	05	
Job No.	E25669.G03			Inclination	<b>-</b> 90°	Logged	JO	Date	22 / 05 / 2023	
Client	Lipman Pty Ltd			Box	1 of 1	Checked	KX	Date	16 / 06 / 2023	
2E	25996 BH6M	START CORE		<b>DEC</b>		CC	PRE L	oss I	470mm	
4	4.20m ->									
5										
6						7:11				
7		CORE	TERMINAT		7.20m	27 28 29 3	0 at 3'2	3.3 34		3.8 35



## BH ID: BH7

Loca	tion	1H Hospital Road, Cor	ncor	d Wes	st, NSV	V	Started	2	4 May	2023
Clien	it No	Lipman Pty Ltd					Comple	ted 2	24 May	2023
Shee	vo. ts	1 of 2					Loggeu Review	By J By N	Л	Date 24 May 2023
Drilli	ng Co	ntractor Geosense	Drill	ing Ei	nginee	rs	Surface RL - Northin	<b>g</b> 6	525444	5.9364 (MGA 2020 Zone 56)
Plan	t	Comacchi	o Ge	o 205	5		Inclination 90° Easting	3	23879	.7716 (MGA 2020 Zone 56)
METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY / REL. DENSITY	MATERIAL ORIGIN & OBSERVATIONS
μQ	MNE	BH7_0.50-0.95 SPT 0.50-0.95 5,5,13 N=18 BH7_1.50-1.80		0.00			ASPHALT: 100mm thick FILL: Silty SAND: fine to medium grained, dark brown with sub- angular to sub-rounded gravels, appears well compacted. Silty CLAY: low to medium plasticity, brown-orange trace sub- angular to sub-rounded gravels	- D M < Pl		ASPHALT FILL RESIDUAL SOIL
1	Ö	SPT 1.50-1.80 8,21/150 mm HB N=R		1.60			SANDSTONE: fine to medium grained, pale grey, extremely weathered.	-	-	WEATHERED ROCK
				3.00 			Log continued on next page.			

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



## BH ID: BH7

Locat Clien Job N Shee	tion t lo. ts	1H H Lipm E259 2 of 2	ospita an Pt 96.G( <u>2</u>	al Roa y Ltd 03	ıd, Cor	ncord	West, NSW				Sta Co Lo Re	arte ompl gge eviev	d 2 leted 2 d By J w By I	24 May 2 24 May 2 10 ML	2023 2023 	Date Date	24 May 08 Augi	202 ust 2	23	3		
Drilli	ng Co	ontrac	tor	Geo	sense	Drilli	ng Engineers Surface RL -				No	orth	ing (	5254445	5.936	4 (MG/	4 2020 Zo	ne 5	56)			
Plant	:	-		Con	nacchi	o Gec	205 Inclination 90°	-	_		Ea	stin	g 3	323879.	7716	(MGA	2020 Zon	e 56	5)			
METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	WEATHERING	VL0:1 2 5	ESTII STRE Is ▼ - D	MAT ENG (50) - Axia	ED TH al etral P H		DISCO & ADDI	ONTIN TIONA	UITIES AL DATA	λ.	F : 08			3000 <sup>m</sup>	-
				0		E	Log continued from previous page.													7	Ţ	
NMLC	90% Water	ő	60	3.20 			NO CORE: 200mm thick SANDSTONE: fine to medium grained, pale grey-brown, thinly to medium bedded	- SW	_		•		3.20-3.2	5: XWS								
				8 			Terminated at 6.00m. Target Depth Reached.															

This log should be read in conjunction with El Australia's accompanying explanatory notes.



# CORE PHOTOGRAPH OF BOREHOLE: BH7

Project	Proposed Redevelopment			Depth Range	3.0m to 6.0n	n BEGL	
Location	1H Hospital Road, Concord West, NSW			Contractor	Geosense [	Drilling E	Engineers Pty Ltd
Position	See Figure 2	Surface RL	≈-	Drill Rig	Comacchio	GEO 2	05
Job No.	E25669.G03	Inclination	<b>-</b> 90°	Logged	JO	Date	24 / 05 / 2023
Client	Lipman Pty Ltd	Box	1 of 1	Checked	KX	Date	16 / 06 / 2023
1 - All	OFAQ CONCORD	DUT CT	ADT COD	TNIC Q 2	Am		
1	E23446 - CUNCURL	BH/ JI	ANICOM	ING (a) J.	UM		
and the second s	Non-shares and the state of the		and the second second		SPATER SALES	SARDINESS	
Co. F	CARE LOCE 200	Sale Land	Leaner V	Constant Constant of Constant	in second beach and the	Alar Sector	THE ACT
1.50	LOKE LOSS ZOOMM	A Street					
							and the second
NUMBER OF STREET, ST	CALLER PROVIDE THE CALLER AND	Sector and the sector of the s		Wand Med and a second of the second	The lose highly have a	17007020	Terret S.
A	The second s		A CONTRACT OF A	SEL MARKED CARE AND A LARGE	A MARTIN MARTIN	ar kne	CONTRACTOR DE LA CONTRACT
44				a hand the second		1 al	
4							
4							
4							
4							
4							
4	CORE TERMINATE	@ 6.0m					
4	CORE TERMINATE	@ 6.0m	20 21 22 23 14		o a1 a2	3.3 34	35 pa 2/ 36
4	CORE TERMINATE	@ 6.0m	20 21 22 23 17	25 25 27 78 29 3		32 24	



### EXPLANATION OF NOTES, ABBREVIATIONS & TERMS USED ON BOREHOLE AND TEST PIT LOGS

### DRILLING/EXCAVATION METHOD

нд	Hand Auger		Hollow Auger	NO	Diamond Core - 47 mm
рт	Diatube Coring	RT	Rotary Tricone bit		Diamond Core - 52 mm
	Non-destructive digging	RAR	Rotary Air Blast	HO	Diamond Core - 63 mm
	Auger Drilling	RC	Reverse Circulation	нміс	Diamond Core - 63 mm
*\/	V_Bit	DT	Push Tube	EV	Tracked Hydraulic Excavator
∨ ∗т					Executed by Lond Methods
		WB	Washbore	HAND	Excavated by Hand Methods
PENE	TRATION RESISTANCE				
L	Low Resistance	Rapid penet	ration/ excavation possible w	ith little effort from e	equipment used.
м	Medium Resistance	Penetration/	excavation possible at an ac	ceptable rate with r	noderate effort from equipment used.
н	High Resistance	Penetration/ equipment u	excavation is possible but at sed.	a slow rate and rec	quires significant effort from
R	<b>Refusal/Practical Refusal</b>	No further p	ogress possible without risk	of damage or unacc	ceptable wear to equipment used.
These drilling	assessments are subjective and a tools and experience of the operation	re dependent o tor.	on many factors, including eq	uipment power and	weight, condition of excavation or
WATE	R				
	aggreen Standing Water L	evel		$\lhd$ Partial v	vater loss
	▷Water Seepage			Comple	te Water Loss
GWN	GROUNDWATE	ER NOT OBS	ERVED - Observation of gr	oundwater, whethe	r present or not, was not possible
	due to drilling wat	er, surface see	page or cave-in of the boreh	ole/ test pit.	<i>6</i>
GWN	E GROUNDWATE groundwater coul	ER NOT ENC	OUNTERED - Borehole/ te less permeable strata, Inflov	est pit was dry soon v mav have been ol	after excavation. However, oserved had the borehole/ test pit
	been left open for	a longer perio	d.		Fi
SAMP	LING AND TESTING				
SPT	Standard Pene	tration Test to	AS1289.6.3.1-2004		
4,7,11 N 30/80mr	l=18 4,7,11 = Blows Where practica	per 150mm. Frefusal occurs	N = Blows per 300mm pene the blows and penetration f	for that interval are	150mm seating drive reported. N is not reported
RW	Penetration occ	curred under th	e rod weight only, N<1		
HW	Penetration occ	curred under th	e hammer and rod weight on	ly, N<1	
⊓⊳ Sampli	na	bounding on			
DS	Disturbed Sam	ple			
ES	Sample for env Bulk disturbed	ironmental test Sample	ing		
GS	Gas Sample	Campio			
WS	Water Sample	e sample - nun	nher indicates nominal sampl	le diameter in millin	oetres
Testing		e sample - num	iber indicates norminal samp		
FP	Field Permeabi	lity test over se	ection noted		
FVS	Field Vane She	ar test express	sed as uncorrected shear stre	ength (sv= peak val	ue, sr= residual value)
PM	Pressuremeter	test over section	on noted		
PP	Pocket Penetro	meter test exp	ressed as instrument reading	j in kPa	
WPT	Water Pressure	e tests Penetrometer	toet		
CPT	Static Cone Pe	netration test			
CPTu	Static Cone Pe	netration test v	<i>i</i> ith pore pressure (u) measur	rement	
GEOL	OGICAL BOUNDARIES			2 2	2 Doundon
	= Observed Boundary (position known)		= Observed Boundar (position approxima	ry –	(interpreted or inferred)
ROCK	CORE RECOVERY				
	TCR=Total Core Reco	overy (%)		RQD = Rock Qua	ality Designation (%)
	$=\frac{Length of core recove}{Length of core recove}$	<u>red</u> × 100		$=\frac{\sum Axial \ lengths \ d}{\sum Axial \ lengths \ d}$	<i>of core</i> > 100 <i>mm</i> × 100
	Length of core run			Length of	f core run

eiaus	tralia				METHO	D OF SO BORE	IL DES HOLE	SCRIPTION	USED ON PIT LOGS	
Contamination   Rem	FILL		<u>346 346 346</u> <u>346 346</u> 346 346 346	ORGA	NIC SOILS			CLAY (CL. (	CI or CH)	
	COUBL	ES or	<u>Mr 446</u>		DH or Pt)				, or SM()	
	BOULD	ERS	<u>**,*,*</u> Combinati	tions of t	these basic s	mbols may	be used to	indicate mixed ma	aterials such as	
0000	GRAVE	L (GP or GW)	sandy clay	ly ly		ymbols may		indicate mixed me		
CLASSIF Soil is broa Soil descri	<b>ICATION A</b> adly classified ption and clas	ND INFERRED and described in I sification.	STRATIGRAF Borehole and Te	PHY 'est Pit L	ogs using the	e preferred m	nethod give	en in AS 1726:201	7, Section 6.1 –	
PARTICL	E SIZE CH	ARACTERISTIC	S		GROUP S	YMBOLS				
Fraction	Component	s Sub	Size	_	Major Di	visions	Symbol	Desc	ription	
	BOULDERS	6	>200			is. of	GW	mixtures, little	or no fines, no dry	
Oversize	COBBLES	Coarse	63 to 200	)	<b>colLS</b> coluding ter than	t <b>AVEL</b> lan 50% fraction 36mm	GP	Poorly graded gra mixtures, little o	avel and gravel-sand or no fines, no dry ength.	
	GRAVE	Medium	6 7 to 19		n grea	GR ore th barse >2.	GM	Silty gravel, grave	el-sand-silt mixtures, um dry strength.	
Coarse	ONAVEL	Fine	2 36 to 6 7	7	<b>RAIN</b> 6 of s on is 75mr	С С С С	GC	Clayey gravel,	gravel-sand-clay	
grained		Coarse	0.6 to 2.36	, J	<b>E GF</b> 1 65% ractic 0.0	o f	SW	Well graded sand	d and gravelly sand,	
3011	SAND	Medium	0.21 to 0.6	5	e thar size t	<b>D</b> 50% mm	SP	Poorly graded sar	and gravelly sand,	
		Fine	0.075 to 0.2	21	CC More over	SAN than than se fra se fra	SM	Silty sand, sand-s	silt mixtures, zero to	
Fine	SILT		0.002 to 0.0	75		More coar	SC	Clayey sand, sa medium to bi	indy-clay mixtures,	
grained soil	CLAY		< 0.002		0_	v	МІ	Inorganic silts of lo	w plasticity, very fine	
	PLAST	ICITY PROPER	TIES		LS cludir thar	tless		sands, zero to m	sands, zero to medium dry strength. Inorganic clays of low to medium	
60 50				ED SOI soil ex n is les	uid Lim 50%	CL, CI	plasticity, gravelly silty clays, medium Organic silts and	/ clays, sandy clays, to high dry strength. organic silty clays of		
3 40 M			100 A UN9 200	% of Solution			OL	low plasticity, l	ow to medium dry ength.	
CHOLOH CHOLOH		1,00731	an 36 fr		. %	MH	Inorganic silts of h	high plasticity, high to dry strength.		
		0 or 01		ersiz		iquid mit > n 50°	СН	Inorganic clays of high plasticity, high very high dry strength.		
PLAST	CL or OL	ИН	oroH	он <sub>б</sub>			ОН	Organic clays	of medium to high	
	CL ML	NL or OL 40 50 60	70 80 90	100	Higl Orga so	nly anic il	PT	T Peat muck and other highly organic soils.		
MOISTU		ON								
Symbol	Term	Description								
D	Dry	Non- cohesive and	d free-running.	0 - 11 - 1						
W	Wet	Solis feel cool, dai Soils feel cool, dai	rkened in colou	ir. Soil te ir. Soil te	ends to stick t	ogether. ogether. free	water forr	ns when handling.		
Moisture content a liquid lim	content of col as follows: Moi it ( $w \approx LL$ ), We	nesive soils shall b st, dry of plastic li et, wet of liquid lim	be described in mit (w < PL); Mo it (w > LL),	relation oist, nea	to plastic limit ar plastic limit	it (PL) or liqu (w≈PL); Mo	id limit (LL pist, wet of	) for soils with high plastic limit ( <i>w</i> < F	er moisture PL); Wet, near	
	CONS	SISTENCY					DENS	ТҮ		
Symbol	Term	Undrained Shear Strength (kPa)	SPT "N" #		Symbol	Term	n [	Density Index %	SPT "N" #	
VS	Very Soft	≤ 12	≤2		VL	Very Lo	ose	≤ 15	0 to 4	
S F	Soft Firm	>12 to ≤ 25 >25 to ≤ 50	>2 to $\leq 4$ >4 to 8		L MD	Loose Medium D	e Dense	>15 to $\leq 35$ >35 to $\leq 65$	4 to 10 10 to 30	
St	Stiff	>50 to ≤ 100	>8 to 15		D	Dens	e	>65 to ≤ 85	30 to 50	
VSt H	Very Stiff Hard	>100 to ≤ 200 >200	>15 to 30 >30		VD	Very De	nse	>85	Above 50	
Fr	Friable	-								
In the abse # SPT corr and equipr	ence of test re relations are n ment type.	sults, consistency ot stated in AS172	and density ma 26:2017, and ma	ay be as lay be si	sessed from ubject to corre	correlations ections for ov	with the ob verburden	pressure, moisture	or the material. content of the soil,	
MINOR	OMPONEN	TS					-	<i></i>		
Term	Assessme	ent Guide	feel or ove but	soil pro-	portion little		Pi	oportion by Mass	5%	
Add 'Trac	e' or no diffe	rent to general pro	perties of prima	ary com	ponent		Coarse grained soils: ≤ 5% Fine grained soil: ≤ 15%			
Add 'With	n' Presence or no diffe	easily detectable l rent to general pro	by feel or eye be	ut soil p ary com	roperties little ponent		Coars Fine	e grained soils: 5 - grained soil: 15 - 3	12% 30%	
Prefix so name	general pr	Presence easily detectable by feel or eye in conjunction with the general properties of primary component				Coarse grained soils: >12% Fine grained soil: >30%				



### **TERMS FOR ROCK MATERIAL STRENGTH** AND WEATHERING

#### **CLASSIFICATION AND INFERRED STRATIGRAPHY**

Rock is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS1726 -2017, Section 6.2 - Rock identification, description and classification.

ROCK MATERIAL STRENGTH CLASSIFICATION							
Symbol	Term	Point Load Index, Is <sub>(50)</sub> (MPa) <sup>#</sup>	Field Guide				
VL	Very Low	0.03 to 0.1	Material crumbles under firm blows with sharp end of pick; can be peeled with knife; too hard to cut a triaxial sample by hand. Pieces up to 30 mm can be broken by finger pressure.				
L	Low	0.1 to 0.3	Easily scored with a knife; indentations 1 mm to 3 mm show in the specimen with firm blows of pick point; has dull sound under hammer. A piece of core 150 mm long by 50 mm diameter may be broken by hand. Sharp edges of core may be friable and break during handling.				
М	Medium	0.3 to 1	Readily scored with a knife; a piece of core 150 mm long by 50 mm diameter can be broken by hand with difficulty.				
н	High	1 to 3	A piece of core 150 mm long by 50 mm diameter cannot be broken by hand but can be broken with pick with a single firm blow; rock rings under hammer.				
VH	Very High	3 to 10	Hand specimen breaks with pick after more than one blow; rock rings under hammer.				
EH	Extremely High	>10	Specimen requires many blows with geological pick to break through intact material; rock rings under hammer.				
<sup>#</sup> Rock St	rength Test Res	ults 🔻	Point Load Strength Index, Is(50), Axial test (MPa)				
		•	Point Load Strength Index, Is(50), Diametral test (MPa)				

Relationship between rock strength test result  $(Is_{(50)})$  and unconfined compressive strength (UCS) will vary with rock type and strength, and should be determined on a site-specific basis. However UCS is typically 20 x  $Is_{(50)}$ .

### ROCK MATERIAL WEATHERING CLASSIFICATION

Sym	bol	Term	Field Guide				
RS		Residual Soil	Soil developed on extremely weathered rock; the mass structure and substance fabric are no longer evident; there is a large change in volume but the soil has not been significantly transported.				
XW		Extremely Weathered	Rock is weathered to such an extent that it has soil properties - i.e. it either disintegrates or can be remoulded, in water.				
	HW		Rock strength usually changed by weathering. The rock may be highly discoloured, usually by iron staining. Porosity may be increased by leaching, or				
DW	MW	Distinctly Weathered	may be decreased due to deposition of weathering products in pores. In some environments it is convenient to subdivide into Highly Weathered and Moderately Weathered, with the degree of alteration typically less for MW.				
SW	1	Slightly Weathered	Rock slightly discoloured but shows little or no change of strength relative to fresh rock.				
FR		Fresh	Rock shows no sign of decomposition or staining.				



### ABBREVIATIONS AND DESCRIPTIONS FOR ROCK MATERIAL AND DEFECTS

#### CLASSIFICATION AND INFERRED STRATIGRAPHY

Rock is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS1726 – 2017, Section 6.2 – Rock identification, description and classification.

DETAILED ROCK DEFE	ECT SP	ACING									
Defect Spacing						Bedd	ling Tl	hickness (Stra	tification		
Spacing/width (mm)	Descriptor				Symbol	Term	Term			Spacing (mm)	
					-,		ly laminated				<6
<20	Ext	tremely Clo	se		EC	Lamir	nated				6 – 20
20-60	Ve	ry Close			VC	Very	thinly	bedded			20 – 60
60-200	Clo	se			С	Thinly	/ bedd	led			60 – 200
200-600	Me	dium			Μ	Mediu	um be	dded			200 - 600
600-2000	Wie	de			W	Thick	ly bed	ded			600 - 2,000
2000-6000	Ve	ry Wide			VW	Very	thickly	bedded			> 2,000
ABBREVIATIONS AND	DESC	RIPTIONS I	FOR DEFE	СТ ТҮРІ	ES						
Defect Type		Abbr.	Descripti	on							
Joint		JT	Surface o May be cl	f a fractu osed or t	ure or parting, forme filled by air, water o	ed withou r soil or r	t displ ock su	acement, acros Ibstance, which	s which th acts as c	ne rock has lit ement.	tle or no tensile strength.
Bedding Parting		BP	Surface o layering/ b resulting i	f fracture bedding. n planar	e or parting, across Bedding refers to the anisotropy in the re	which the he layerir ock mater	e rock ng or s rial.	has little or no to the stratification of a	tensile str 1 rock, ind	ength, paralle icating orienta	l or sub-parallel to ation during deposition,
Contact		СО	The surfa	ce betwe	een two types or ag	es of rocl	k.				
Sheared Surface		SSU	A near pla	anar, cui	rved or undulating s	urface w	hich is	usually smooth	n, polisheo	d or slickensic	led.
Sheared Seam/ Zone (Fault)		SS/SZ	Seam or a mm) para	zone with Ilel and ι	n roughly parallel al usually smooth or sl	most plai lickenside	ost planar boundaries of rock substance cut by closely spaced (often <50 ckensided joints or cleavage planes.				ely spaced (often <50
Crushed Seam/ Zone CS/CZ			Seam or zone composed of disoriented usually angular fragments of the host rock substance, with roughly parallel near-planar boundaries. The brecciated fragments may be of clay, silt, sand or gravel sizes or mixtures of these.								
Extremely Weathered Seam/ Zone	×	WS/XWZ	Seam of soil substance, often with gradational boundaries, formed by weathering of the rock material in places.								
Infilled Seam		IS	Seam of s migrating	soil subs into joint	tance, usually clay of the tance, usually clay of the tank tank to the tank tank tank tank tank tank tank tank	or clayey	, with v	very distinct rou	ighly para	llel boundarie	s, formed by soil
Vein		VN	Distinct sh	neet-like	body of minerals cr	ystallised	d withi	n rock through t	ypically o	pen-space fill	ing or crack-seal growth.
NOTE: Defects size of	<100m	m SS, CS a	Ind XWS. D	efects s	ize of >100mm SZ,	CZ and 2	XWZ.				
ABBREVIATIONS AND	DESC	RIPTIONS I	FOR DEFE	CT SHA	PE AND ROUGHN	ESS					
Shape	Abbr.	Descrip	tion		Roughness	Abbr.	Des	cription			
Planar	PR	Consist	ent orientat	ion	Polished	POL	Shin	y smooth surfa	ce		
Curved	CU	Gradua orientat	l change in ion		Slickensided	SL	Groo	oved or striated	surface, u	usually polishe	ed
Undulating	UN	Wavy s	urface		Smooth	SM	Smo	oth to touch. Fe	ew or no s	urface irregul	larities
Stepped	ST	One or steps	more well o	lefined	Rough	RO	Man Feel	y small surface s like fine to co	irregulari arse sand	ties (amplitud paper	e generally <1mm).
Irregular	IR	Many sl orientat	harp chang ion	es in	Very Rough	VR Many large surface irregularities, amplitude generally >1mm. Feels like very coarse sandpaper					
Orientation:	Ve Inc	rtical Borel lined Bore	<b>ioles –</b> The holes – The	dip (incl e inclinat	ination from horizon ion is measured as t	tal) of the the acute	defec angle	t. to the core axis			
ABBREVIATIONS AND	DESCF	RIPTIONS F	OR DEFEC		TING			DEFECT APE	RTURE		
Coating	Abbr	. Descript	ion					Aperture	Abbr.	Description	
Clean	CN	No visible	coating or	infilling				Closed	CL	Closed.	
Stain	SN	No visible often limo	coating bu	t surface e-brown)	es are discoloured b	y staining	g,	Open	OP	Without any i	infill material.
Veneer	VNR	A visible o measure (	coating of so (< 1 mm); m	oil or mir nay be p	neral substance, us atchy	ually too	thin to	Infilled	-	Soil or rock i. quartz, etc.	e. clay, silt, talc, pyrite,

Appendix B – Laboratory Certificates



### **ANALYTICAL REPORT**





CLIENT DETAILS		LABORATORY DE	TAILS
Contact	Jacky Ong	Manager	Huong Crawford
Client	EI AUSTRALIA	Laboratory	SGS Alexandria Environmental
Address	SUITE 6.01 55 MILLER STREET PYRMONT NSW 2009	Address	Unit 16, 33 Maddox St Alexandria NSW 2015
Telephone Facsimile	61 2 95160722 (Not specified)	Telephone Facsimile	+61 2 8594 0400 +61 2 8594 0499
Email	jacky.ong@eiaustralia.com.au	Email	au.environmental.sydney@sgs.com
Project Order Number Samples	E25996.G03 1H Hospital Road, Concord NSW E25996.G03 3	SGS Reference Date Received Date Reported	<b>SE248316 R0</b> 30/5/2023 6/6/2023

COMMENTS

Accredited for compliance with ISO/IEC 17025 - Testing. NATA accredited laboratory 2562(4354).

SIGNATORIES -

Shone

Shane MCDERMOTT Inorganic/Metals Chemist

SGS Australia Pty Ltd ABN 44 000 964 278 Australiat +61 2 8594 0400Australiaf +61 2 8594 0499

www.sgs.com.au



### Soluble Anions (1:5) in Soil/Solids by Ion Chromatography [AN245] Tested: 6/6/2023

			BH1M_1.5-1.65	BH7_1.5-1.8	BH5_3-3.45
			SOIL	SOIL	SOIL
				24/5/2023	
PARAMETER	UOM	LOR	SE248316.001	SE248316.002	SE248316.003
Chloride	mg/kg	0.25	290	70	520
Sulfate	mg/kg	5	160	91	170



### pH in soil (1:5) [AN101] Tested: 5/6/2023

			BH1M_1.5-1.65	BH7_1.5-1.8	BH5_3-3.45
			SOIL	SOIL	SOIL
				24/5/2023	
PARAMETER	UOM	LOR	SE248316.001	SE248316.002	SE248316.003
рН	pH Units	0.1	5.1	5.5	4.3



### Conductivity and TDS by Calculation - Soil [AN106] Tested: 5/6/2023

			BH1M_1.5-1.65	BH7_1.5-1.8	BH5_3-3.45
			SOIL	SOIL	SOIL
				24/5/2023	
PARAMETER	UOM	LOR	SE248316.001	SE248316.002	SE248316.003
Conductivity of Extract (1:5 dry sample basis)	µS/cm	1	240	110	480



### Moisture Content [AN002] Tested: 2/6/2023

			BH1M_1.5-1.65	BH7_1.5-1.8	BH5_3-3.45
			SOIL	SOIL	SOIL
				24/5/2023	
PARAMETER	UOM	LOR	SE248316.001	SE248316.002	SE248316.003
% Moisture	%w/w	1	9.9	11.4	12.6



METHOD	
AN002	The test is carried out by drying (at either 40°C or 105°C) a known mass of sample in a weighed evaporating basin. After fully dry the sample is re-weighed. Samples such as sludge and sediment having high percentages of moisture will take some time in a drying oven for complete removal of water.
AN101	pH in Soil Sludge Sediment and Water: pH is measured electrometrically using a combination electrode and is calibrated against 3 buffers purchased commercially. For soils, sediments and sludges, an extract with water (or 0.01M CaCl2) is made at a ratio of 1:5 and the pH determined and reported on the extract. Reference APHA 4500-H+.
AN106	Conductivity and TDS by Calculation: Conductivity is measured by meter with temperature compensation and is calibrated against a standard solution of potassium chloride. Conductivity is generally reported as $\mu$ mhos/cm or $\mu$ S/cm @ 25°C. For soils, an extract of as received sample with water is made at a ratio of 1:5 and the EC determined and reported on the extract, or calculated back to the as-received sample. Salinity can be estimated from conductivity using a conversion factor, which for natural waters, is in the range 0.55 to 0.75. Reference APHA 2510 B.
AN245	Anions by Ion Chromatography: A water sample is injected into an eluent stream that passes through the ion chromatographic system where the anions of interest ie Br, Cl, NO2, NO3 and SO4 are separated on their relative affinities for the active sites on the column packing material. Changes to the conductivity and the UV-visible absorbance of the eluent enable identification and quantitation of the anions based on their retention time and peak height or area. APHA 4110 B

		LEC.
_	FUU	

*	NATA accreditation does not cover	-	Not analysed.	UOM	Unit of Measure.
	the performance of this service.	NVL	Not validated.	LOR	Limit of Reporting.
**	Indicative data, theoretical holding	IS	Insufficient sample for analysis.	¢↓	Raised/lowered Limit of
	time exceeded.	LNR	Sample listed, but not received.		Reporting.
***	Indicates that both * and ** apply.				

Unless it is reported that sampling has been performed by SGS, the samples have been analysed as received. Solid samples expressed on a dry weight basis.

Where "Total" analyte groups are reported (for example, Total PAHs, Total OC Pesticides) the total will be calculated as the sum of the individual analytes, with those analytes that are reported as <LOR being assumed to be zero. The summed (Total) limit of reporting is calculated by summing the individual analyte LORs and dividing by two. For example, where 16 individual analytes are being summed and each has an LOR of 0.1 mg/kg, the "Totals" LOR will be 1.6 / 2 (0.8 mg/kg). Where only 2 analytes are being summed, the "Total" LOR will be the sum of those two LORs.

Some totals may not appear to add up because the total is rounded after adding up the raw values.

If reported, measurement uncertainty follow the ± sign after the analytical result and is expressed as the expanded uncertainty calculated using a coverage factor of 2, providing a level of confidence of approximately 95%, unless stated otherwise in the comments section of this report.

Results reported for samples tested under test methods with codes starting with ARS-SOP, radionuclide or gross radioactivity concentrations are expressed in becquerel (Bq) per unit of mass or volume or per wipe as stated on the report. Becquerel is the SI unit for activity and equals one nuclear transformation per second.

Note that in terms of units of radioactivity:

- a. 1 Bq is equivalent to 27 pCi
- b. 37 MBq is equivalent to 1 mCi

For results reported for samples tested under test methods with codes starting with ARS-SOP, less than (<) values indicate the detection limit for each radionuclide or parameter for the measurement system used. The respective detection limits have been calculated in accordance with ISO 11929.

The QC and MU criteria are subject to internal review according to the SGS QAQC plan and may be provided on request or alternatively can be found here: <u>www.sgs.com.au/en-gb/environment-health-and-safety</u>.

This document is issued by the Company under its General Conditions of Service accessible at <u>www.sqs.com/en/Terms-and-Conditions.aspx</u>. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.

Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client only. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law.

This report must not be reproduced, except in full.



14/1 Cowpasture Place, Wetherill Park NSW 2164 Phone: (02)9756 2166 | Email: enquiries@stsgeo.com.au



Accredited for Compliance with ISO/IEC 17025 - Testing No. 2750

## Atterberg Limits and Linear Shrinkage Report

Project: E25996.G03 - 1H Hospital Road, Concord	Project No.:	31380
Client: El Australia Pty Ltd	Report No.:	23/1820
Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009	Report Date:	22/06/2023
Test Method: AS1289.3.1.2, 3.2.1, 2.1.1	Page:	1 of 1

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	7694D-L/2	7694D-L/4	7694D-L/5	7694D-L/7	
Sample Location	BH 01M	BH 04	BH 07	BH 05	
Material Description	Silty Sandy Clay, brown trace of gravel	Silty Clay, grey orange brown trace of gravel	Silty Clay, light grey trace of gravel	Silty Clay, light grey brown trace of gravel	
Depth (m)	1.50 - 1.65	1.50 - 1.85	1.50 - 1.80	1.50 - 1.68	
Sample Date	29/05/2023	29/05/2023	29/05/2023	29/05/2023	
Sample History	Oven Dried	Oven Dried	Oven Dried	Oven Dried	
Method of Preparation	Dry Sieved	Dry Sieved	Dry Sieved	Dry Sieved	
Liquid Limit (%)	37	39	36	40	
Plastic Limit (%)	20	21	21	21	
Plasticity Index	17	18	15	19	
Linear Shrinkage (%)	N/A	N/A	N/A	N/A	
Mould Size (mm)	N/A	N/A	N/A	N/A	
Crumbing	N/A	N/A	N/A	N/A	 
Curling	N/A	N/A	N/A	N/A	
Remarks <sup>.</sup>					

Technician: BV

Approved Signatory.....

Orlando Mendoza - Laboratory Manager



14/1 Cowpasture Place, Wetherill Park NSW 2164 Phone: (02)9756 2166 | Email: enquiries@stsgeo.com.au



Compliance with ISO/IEC 17025 - Testing No. 2750

## Moisture Content of Soil and Aggregate Samples

Project: E25996.G03 - 1H Hospital Road, Concord	Project No.:	31380
Client: El Australia Pty Ltd	Report No.:	23/1819
Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009	Report Date:	22/06/2023
Test Method: AS1289.2.1.1	Page:	1 of 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	7694D-L/2	7694D-L/3	7694D-L/4	7694D-L/5	7694D-L/6	7694D-L/7
Sample Location	BH 01M	BH 02	BH 04	BH 07	BH 03M	BH 05
Material Description	Silty Sandy Clay, brown trace of gravel	Silty Clay, grey orange brown with sand and gravel	Silty Clay, grey orange brown trace of gravel	Silty Clay, light grey trace of gravel	Silty Clay, pale grey orange brown trace of sand and gravel	Silty Clay, light grey brown trace of gravel
Depth (mm)	1.50 - 1.65	1.50 - 1.725	1.50 - 1.685	1.50 - 1.80	1.5 - 1.95	1.50 - 1.68
Sample Date	29/05/2023	29/05/2023	29/05/2023	29/05/2023	29/05/2023	29/05/2023
Moisture Content (%)	10.8	17.0	13.0	12.1	17.0	11.8

Remarks:

Approved Signatory.....

Technician: ΒV Orlando Mendoza - Laboratory Manager



14/1 Cowpasture Place, Wetherill Park NSW 2164 Phone: (02)9756 2166 | Email: enquiries@stsgeo.com.au



Accredited for Compliance with ISO/IEC 17025 - Testing No. 2750

## Moisture Content of Soil and Aggregate Samples

Project: E25996.G03 - 1H Hospital Road, Concord	Project No.:	31380
Client: El Australia Pty Ltd	Report No.:	23/1819
Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009	Report Date:	22/06/2023
Test Method: AS1289.2.1.1	Page:	2 of 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	7694D-L/8			
Sample Location	BH 06M			
Material Description	Silty Clay, pale grey orange brown trace of sand and gravel			
Depth (mm)	1.50 - 1.95			
Sample Date	29/05/2023			
Moisture Content (%)	22.6			

Remarks:

Approved Signatory.....

Technician: BV

Orlando Mendoza - Laboratory Manager

GEOTECHN CONSULTING GEOTE	ICS PTY LTD ICHNICAL ENGINEERS	Ph	STS C 14/1 Cowpasture none: (02)9756 2166	ieotechnics Pty Lt Place, Wetherill Parl   Email: enquiries@sm	<b>d</b> < NSW 2164 nectesting.com.au	NAT	Accredited for Compliance with ISO/IEC 17025 - Testing No. 2750
Project: E259 <b>Client: El Aus</b> Address: Suit Test Method No. of Days S Sampling Pro	96.G03 - 1H H tralia Pty Ltd e 6.01, 55 Mil : AS1289.6.1.1 oaked: 4 cedure: Samp	Califo Iospital Road, Concor ler Street, Pyrmont N I, 5.1.1, 2.1.1	ornia Bearing <sup>rd</sup> ISW 2009 It (Not covered und	Ratio Determ	ination Report Targ	Project No.: Report No.: Report Date: Page: Compactive Effort: get Compaction (%): Surcharge (Kg):	31380 23/1822 22/06/2023 1 of 1 Standard 100 9
STS / Sai	mple No.	7694D-L/1					
Sample	Location	BH 6					
Material D	escription	Silty Clay, orange red brown wih sand and gravel					
Depth of S	ample (m)	1.50 - 1.60					
Sampl	e Date	29/05/2023					
Oversize or +19m	n Wet Basis m (%)	3.0					
Field Moist	ure Content	14.8					
Optimum	Moisture	16.4					
Maximum	Dry Density	1.784					
Dry (t	Before	1.785					
Densit :/m³)	After	1.765					
Com	Before	100					
elative ipactio (%)	After	99					
n Ma Con	Before	16.6					
oisture tent (%	After	20.5					
Moisture R	atio Before	101.5					
aft	Top 30mm	20.1					
oisture ontent er test (%)	Entire Depth	19.5					
Swell after	Soaking (%)	1.1					
CBR Va	lue (%)	8.0					
Penetrat	ion (mm)	2.5					
Remarks:	+19mm mate	erial excluded from t	est	1	1	()N	da .
					Approved Signatory	S.	3
Technician: E	V					Orlando Mendoza - I	_aboratory Manager









14/1 Cowpasture Place, Wetherill Park NSW 2164 Phone: (02)9756 2166 | Email: enquiries@stsgeo.com.au

### Point Load Strength Index Report



Accredited for Compliance with ISO/IEC 17025 - Testing No. 2750

Project No.: 31380/7694D-L

Report No.: 23/1844

Report Date: 23/06/2023 Page: 1 OF 2

Project: E25996.G03, 1H Hospital Road, CONCORD, NSW

Client: EI AUSTRALIA

Address: Suite 6.01, 55 Miller Street, PYRMONT

Test Method: AS 4133.4.1

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

Borehole / Sample No.	Depth (m)	Date Sampled	Date Tested	Test Type	Is (MPa)	Is <sub>(50)</sub> (MPa)	Rock Type	Failure Type	Moisture
BH1M	4.18	29/05/2023	22-23/06/2023	А	0.2	0.2	SH	3	М
BH1M	5.34	29/05/2023	22-23/06/2023	А	1.4	1.3	SS	3	М
BH1M	6.07	29/05/2023	22-23/06/2023	А	1.7	1.7	SS	3	М
BH1M	7.03	29/05/2023	22-23/06/2023	А	1.6	1.6	SS	3	М
BH2	3.33	29/05/2023	22-23/06/2023	А	0.06	0.059	SH	3	М
BH2	4.11	29/05/2023	22-23/06/2023	А	0.3	0.31	SS	3	М
BH2	5.13	29/05/2023	22-23/06/2023	А	1.1	1.1	SS	3	М
BH2	6.26	29/05/2023	22-23/06/2023	А	2.9	2.8	SS		
BH4	2.91	29/05/2023	22-23/06/2023	А	0.3	0.3	SS	3	м
BH4	3.32	29/05/2023	22-23/06/2023	Α	0.14	0.14	SS	3	M
BH4	4 48	29/05/2023	22-23/06/2023	۵	0.49	0.51	55	3	w
вни	5.42	20/05/2023	22_23/06/2023	Δ	1.2	1.2	55	3	M
	5.42	25/05/2025	22 23/00/2023	~	1.2	1.5			101
BH7	3.40	29/05/2023	22-23/06/2023	Δ	2.6	2.7	22	3	м
BH7	1 15	20/05/2023	22 23/00/2023	Λ	1.1	1.1	55	3	M
BH7	4.15	29/05/2023	22-23/00/2023	^	2.2	2.2	55	3	M
	4.31 E OE	29/03/2023	22-23/00/2023	A	1.5	1.5	55	2	IVI
DEL	5.05	29/03/2023	22-23/00/2023	A	1.5	1.5	33	5	
DUDM	2.02	20/05/2022	22 22/06/2022	٥	0.25	0.25	55	2	NA
DUDM	2.65	29/05/2025	22-23/00/2023	A	0.25	0.25	55	2	IVI
BH3IVI	3.40	29/05/2023	22-23/06/2023	A	1.5	1.0	SH	3	IVI
BH3M	4.03	29/05/2023	22-23/06/2023	A	0.12	0.12	SH	3	M
BH3M	4.50	29/05/2023	22-23/06/2023	A	2.7	2.7	SS	3	M
BH5	3.66	29/05/2023	22-23/06/2023	A	1.2	1.3	SS	3	M
BH5	4.05	29/05/2023	22-23/06/2023	A	0.98	1	SS	3	M
BH5	4.79	29/05/2023	22-23/06/2023	A	0.84	0.83	SS	3	М
BH5	5.36	29/05/2023	22-23/06/2023	А	1.4	1.4	SS	3	М
Failure Type				Test Type		Moisure Conditio	n	Rock Type	
1 = Fracture through the second	ugh bedding or w	eak plane		A = Axial		W = Wet		SS = Sandstone	
2 = Fracture along	g beduing					N = NOISC		ST = Shale	
4 = Fracture influ	enced by natural	defect or drilling		C = Cube		D - Dry		YS = Claystone	
5 = Partial fracture or chip (invalid result)									
Remarks:								0	
								Jusep	helosquy S.
							Approved Signat	ory	10

Fernando Velasquez Senior Geotechnician

Technician: FV



14/1 Cowpasture Place, Wetherill Park NSW 2164 Phone: (02)9756 2166 | Email: enquiries@stsgeo.com.au

### Point Load Strength Index Report



Accredited for Compliance with ISO/IEC 17025 - Testing No. 2750

Project No.: 31380/7694D-L

Report No.: 23/1844

Report Date: 23/06/2023

Page: 2 OF 2

Project: E25996.G03,	1H Hospital Road,	CONCORD,	NSW

Client: EI AUSTRALIA

Address: Suite 6.01, 55 Miller Street, PYRMONT

Test Method: AS 4133.4.1

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

Borehole / Sample No.	Depth (m)	Date Sampled	Date Tested	Test Type	Is (MPa)	Is <sub>(50)</sub> (MPa)	Rock Type	Failure Type	Moisture
BH6M	4.24	29/06/2023	22-23/06/2	А	1.6	1.6	SS	3	М
BH6M	5.12	29/06/2023	22-23/06/2	А	2.2	2.1	SS	3	М
BH6M	5.90	29/06/2023	22-23/06/2	А	1.3	1.3	SS	3	М
BH6M	6.63	29/06/2023	22-23/06/2	А	0.85	0.85	SS	3	М
	-				-	-			
		ļļ							
		ļl		ļ!					
				ļ!					
				!					
		++							
			]						
				ļ!					
		ļl		!					
							<u> </u>		
		++							
		++							
		<u> </u>	[						
		ļ		ļ!					
		ļ!		<u> </u> !					
		ļ!							
				<u> </u>			<u> </u>		
Failure Type				Test Type		Moisure Conditio	n	Rock Type	
1 = Fracture throu	ugh bedding or w	eak plane		A = Axial		W = Wet		SS = Sandstone	
2 = Fracture along	3 bedding			D = Diametrial		M = Moist		ST = Siltstone	
3 = Fracture throu	ugh rock mass	. Contra datilia a		I = Irregular		D = Dry		SH = Shale	
4 = Fracture innue 5 = Partial fractur	enced by natural	defect or arming		C = Cube				YS = Claystone	
Remarks:		i court,					the second Circuit	fusefu	loigueg .
							Approved Signate	ory	
Technician: FV							Fernand	do Velasquez Seni	or Geotechnician

# Appendix C – Vibration Limits

German Standard DIN 4150 – Part 3: 1999 provides guideline levels of vibration velocity for evaluating the effects of vibration in structures. The limits presented in this standard are generally considered to be conservative.

The DIN 4150 values (maximum levels measured in any direction at the foundation, OR, maximum levels measured in (x) or (y) directions, in the plane of the uppermost floor), are summarised in **Table A** below.

It should be noted that peak vibration velocities higher than the minimum figures in **Table A** for low frequencies may be quite 'safe', depending on the frequency content of the vibration and the actual conditions of the structures.

It should also be noted that these levels are 'safe limits', up to which no damage due to vibration effects has been observed for the particular class of building. 'Damage' is defined by DIN 4150 to include even minor non-structural cracking in cement render, the enlargement of cracks already present, and the separation of partitions or intermediate walls from load bearing walls. Should damage be observed at vibration levels lower than the 'safe limits', then it may be attributed to other causes. DIN 4150 also states that when vibration levels higher than the 'safe limits' are present, it does not necessarily follow that damage will occur. Values given are only a broad guide.

		Peak Vibration Velocity (mm/s)						
Group	Type of Structure	At Foundatio	Plane of Floor of Uppermost Storey					
		Less than 10 Hz	10 Hz to 50 Hz	50 Hz to 100 Hz	All Frequencies			
1	Buildings used for commercial purposes, industrial buildings and buildings of similar design	20	20 to 40	40 to 50	40			
2	Dwellings and buildings of similar design and/or use	5	5 to 15	15 to 20	15			
3	Structures that because of their particular sensitivity to vibration, do not correspond to those listed in Group 1 and 2 and have intrinsic value (e.g. buildings that are under a preservation order)	3	3 to 8	8 to 10	8			

### Table A DIN 4150 – Structural Damage – Safe Limits for Building Vibration

**Note:** For frequencies above 100 Hz, the higher values in the 50 Hz to 100 Hz column should be used.



Appendix D – Important Information
# **Important Information**



# SCOPE OF SERVICES

The geotechnical report ("the report") has been prepared in accordance with the scope of services as set out in the contract, or as otherwise agreed, between the Client And El Australia ("El"). The scope of work may have been limited by a range of factors such as time, budget, access and/or site disturbance constraints.

# **RELIANCE ON DATA**

El has relied on data provided by the Client and other individuals and organizations, to prepare the report. Such data may include surveys, analyses, designs, maps and plans. El has not verified the accuracy or completeness of the data except as stated in the report. To the extent that the statements, opinions, facts, information, conclusions and/or recommendations ("conclusions") are based in whole or part on the data, El will not be liable in relation to incorrect conclusions should any data, information or condition be incorrect or have been concealed, withheld, misrepresented or otherwise not fully disclosed to El.

#### **GEOTECHNICAL ENGINEERING**

Geotechnical engineering is based extensively on judgment and opinion. It is far less exact than other engineering disciplines. Geotechnical engineering reports are prepared for a specific client, for a specific project and to meet specific needs, and may not be adequate for other clients or other purposes (e.g. a report prepared for a consulting civil engineer may not be adequate for a construction contractor). The report should not be used for other than its intended purpose without seeking additional geotechnical advice. Also, unless further geotechnical advice is obtained, the report cannot be used where the nature and/or details of the proposed development are changed.

## LIMITATIONS OF SITE INVESTIGATION

The investigation programme undertaken is a professional estimate of the scope of investigation required to provide a general profile of subsurface conditions. The data derived from the site investigation programme and subsequent laboratory testing are extrapolated across the site to form an inferred geological model, and an engineering opinion is rendered about overall subsurface conditions and their likely behaviour with regard to the proposed development. Despite investigation, the actual conditions at the site might differ from those inferred to exist, since no subsurface exploration program, no matter how comprehensive, can reveal all subsurface details and anomalies. The engineering logs are the subjective interpretation of subsurface conditions at a particular location and time, made by trained personnel. The actual interface between materials may be more gradual or abrupt than a report indicates.

#### SUBSURFACE CONDITIONS ARE TIME DEPENDENT

Subsurface conditions can be modified by changing natural forces or man-made influences. The report is based on conditions that existed at the time of subsurface exploration. Construction operations adjacent to the site, and natural events such as floods, or ground water fluctuations, may also affect subsurface conditions, and thus the continuing adequacy of a geotechnical report. El should be kept appraised of any such events, and should be consulted to determine if any additional tests are necessary.

## VERIFICATION OF SITE CONDITIONS

Where ground conditions encountered at the site differ significantly from those anticipated in the report, either due to natural variability of subsurface conditions or construction activities, it is a condition of the report that EI be notified of any variations and be provided with an opportunity to review the recommendations of this report. Recognition of change of soil and rock conditions requires experience and it is recommended that a suitably experienced geotechnical engineer be engaged to visit the site with sufficient frequency to detect if conditions have changed significantly.

# **REPRODUCTION OF REPORTS**

This report is the subject of copyright and shall not be reproduced either totally or in part without the express permission of this Company. Where information from the accompanying report is to be included in contract documents or engineering specification for the project, the entire report should be included in order to minimize the likelihood of misinterpretation from logs.

# **REPORT FOR BENEFIT OF CLIENT**

The report has been prepared for the benefit of the Client and no other party. El assumes no responsibility and will not be liable to any other person or organisation for or in relation to any matter dealt with or conclusions expressed in the report, or for any loss or damage suffered by any other person or organisation arising from matters dealt with or conclusions expressed in the report (including without limitation matters arising from any negligent act or omission of El or for any loss or damage suffered by any other party relying upon the matters dealt with or conclusions expressed in the report). Other parties should not rely upon the report or the accuracy or completeness of any conclusions and should make their own inquiries and obtain independent advice in relation to such matters.

## **OTHER LIMITATIONS**

El will not be liable to update or revise the report to take into account any events or emergent circumstances or fact occurring or becoming apparent after the date of the report.