




HAVE 27.7% OF OSD STORAGE BELOW 1% AEP FLOOD LINE (DROWNED ORIFICE). THIS IS BELOW THE 30% AS OUTLINED IN GEORGES RIVER COUNCIL STORMWATER MANAGEMENT POLICY 2021 SECTION 4.13

NOTES:

- ALL BALCONIES TO BE PICKED UP VIA RAINWATER OUTLETS WITH AN ADEQUATE OVERFLOW SYSTEM
- ALL BALCONIES TO HAVE THRESHOLD DRAINS
- ALL RAINWATER OUTLETS TO CONNECT INTO THE MAIN STORMWATER LINE PROPOSED AT GROUND LEVEL

BERNADOTTE STREET

1 DA-007



DRAWING REVIEWED BY:
Scott McMillan
Civil Manager
B.E. Civil (Hons)
MIEAust CPEng NER
2465653



this document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN DJA
DATE 13/06/2024
SIZE A1
SCALE 1:100
PROJECT MGR GC

CIVIL SKETCH
LEVEL 1 STORMWATER
PLAN

**Proposed Seniors
Housing Development**
10-14 Munmurra Road and 5
Bernadotte St Riverwood NSW 2210
**Custance Associates Australia Pty
Ltd**

N0221293
CSK02G

NOTES:

- ALL GUTTERING TO BE EAVES GUTTER UNLESS SPECIFIED OTHERWISE
- DOWNPIPES AND EAVES GUTTERS TO BE SIZED DURING CC STAGE
- DOWNPIPE LOCATIONS ARE INDICATIVE AND SUBJECT TO CHANGE



DRAWING REVIEWED BY:

Scott McMillan
Civil Manager
B.E. Civil (Hons)
MIEAust CPEng NER
2465653



This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN DJA
DATE 13/06/2024
SIZE A1
SCALE 1:100
PROJECT MGR GC

CIVIL SKETCH

ROOF STORMWATER
PLAN

**Proposed Seniors
Housing Development**
10-14 Munmurra Road and 5
Bernadotte St Riverwood NSW 2210
**Custance Associates Australia Pty
Ltd**


**N0221293
CSK03 G**





Legend

Description	Quantity	Unit
OSD 1 BYPASS	141.33	sq m
OSD 1 DRIVEWAY	322.06	sq m
OSD 1 PERVIOUS	466.31	sq m
OSD 1 REMAINING IMPERVIOUS	117.63	sq m
OSD 2 BYPASS	120.69	sq m
OSD 2 DRIVEWAY	100.61	sq m
OSD 2 PERVIOUS	277.79	sq m
OSD 2 REMAINING IMPERVIOUS	84.83	sq m
REMAINING ROOF	111.42	sq m
ROOF TO RWT	751.74	sq m



MUSIC MODEL

Treatment Train Effectiveness - 80/40/40

	Sources	Residual Load	% Reduction
Flow (ML/yr)	2.47	2.34	5.2
Total Suspended Solids (kg/yr)	339	59.1	82.6
Total Phosphorus (kg/yr)	0.763	0.345	54.8
Total Nitrogen (kg/yr)	5.8	3.47	40.2
Gross Pollutants (kg/yr)	54.4	1.44	97.4

MUSIC RESULTS

NJN
Responsive Engineering

DRAWING REVIEWED BY:
Scott McMillan
Civil Manager
B.E. Civil (Hons)
MIEAust CPEng NER
2465653



This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN DJA
DATE 13/06/2024
SIZE A1
SCALE 1:200
PROJECT MGR GC

CIVIL SKETCH
WSUD PLAN

**Proposed Seniors
Housing Development**
10-14 Munmurra Road and 5
Bernadotte St Riverwood NSW 2210
**Custance Associates Australia Pty
Ltd**


**N0221293
CSK04G**

10-14 Munmurra Road & 5 Bernadotte Street, Riverwood NSW 2210

Job No. N0221293

ENVIRONMENTAL SITE MANAGEMENT


1. EROSION & SEDIMENT CONTROLS TO BE INSTALLED IN ACCORDANCE WITH COUNCIL'S SPECIFICATION & THE NSW DEPARTMENT OF HOUSING 'BLUE BOOK'. SOILS AND CONSTRUCTION - MANAGING URBAN STORMWATER, 2004. REFER TO THE BLUE BOOK FOR STANDARD DRAWINGS.
2. SEDIMENT EROSION CONTROLS MUST BE IN PLACE PRIOR TO THE COMMENCEMENT OF ANY EARTHWORKS OR DEMOLITION ACTIVITY. THE LOCATION OF SUCH DEVICES IS INDICATIVE ONLY AND FINAL POSITION SHOULD BE DETERMINED ON SITE.
3. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL MEASURES ARE TAKEN TO PREVENT THE SOURCE OF EROSION OR PREVENT SEDIMENT EROSION AND POLLUTION OF THE DOWNSTREAM SYSTEM. SUPERVISING ENGINEER SHOULD BE CONTACTED IF IN DOUBT. ALL SEDIMENT CONTROL STRUCTURES TO BE INSPECTED AFTER EACH RAINFALL EVENT FOR STRUCTURAL DAMAGE AND ALL TRAPPED SEDIMENT TO BE REMOVED TO A NOMINATED OFF-SITE LOCATION.
4. RETAIN ALL EXISTING GRASS COVER WHEREVER POSSIBLE. TOPSOIL FROM ALL AREAS THAT WILL BE DISTURBED TO BE STRIPPED AND STOCKPILED AT THE NOMINATED SITE. A SEDIMENT FENCE TO BE PLACED DOWNHILL OF STOCKPILE.
5. ALL AREAS TO BE EXCAVATED TO BE PROTECTED PROGRESSIVELY DURING THE WORKS AND STABILISED AS EARLY AS POSSIBLE. THE SUPERVISING ENGINEER MAY DIRECT THE CONTRACTOR TO HAVE AREAS OF DISTURBANCE COMPLETED AND STABILISED DURING THE COURSE OF THE WORKS.
6. ALL EXPOSED AREAS ARE TO BE SEEDED & FERTILISED WITHIN 14 DAYS OF EXPOSURE.
7. ALL EXISTING TREES TO BE RETAINED UNLESS SHOWN OTHERWISE ON APPROVED DRAWINGS. TREES RETAINED ARE TO BE PROTECTED WITH A HIGH VISIBILITY FENCE, PLUS FLAGGING TO INDIVIDUAL TREES NECESSARY.
8. INSTALL TEMPORARY SEDIMENT BARRIERS TO ALL INLET PITS PRIOR TO COLLECT SILT LAID WATER. UNTIL SURROUNDING AREAS ARE PAVED OR REGRASS, GRAVEL OR GEOTEXTILE INLET FILTERS TO SD6-11 & SD6-12.
9. ALL SILT FENCES & BARRIERS ARE TO BE MAINTAINED IN GOOD ORDER & REGULARLY DESIGNED DURING THE CONSTRUCTION PERIOD. SILT FENCES TO SD6-8 OR SD6-9.
10. ALL EXPOSED AREAS TO BE PROTECTED WITH A HIGH VISIBILITY FENCE TO BE COVERED WITH GEOTEXTILE SILT FENCE MATERIAL. PLASTIC SHEETING OR MEMBRANE MUST NOT BE USED. SAFETY BARRICADING SHOULD BE USED TO ISOLATE STOCKPILES OF SOLID MATERIALS SUCH AS SIFT, REINFORCING, FORMWORK AND STOCKPILING.
11. ALL EXISTING MATERIALS ARE TO BE STOCKPILED OR LOADED INTO SKIP-BINS LOCATED ON SITE AS SHOWN ON PLAN.
12. NO MORE THAN 150m OF TRENCHING TO BE OPEN AT ANY ONE TIME. IMMEDIATELY AFTER TRENCH BACKFILLING, PROVIDE SANDBAGS OR SAUSAGE FILTERS AGAINST EACH TRENCH AT 10M SPACINGS. FILTERS TO REMAIN IN PLACE UNTIL REVEGETATION HAS OCCURRED.
13. ALL VEHICLES LEAVING THE SITE MUST PASS OVER THE STABILISED SITE ACCESS BALLAST AREA (SIMILAR TO SD6-14) TO SHAKE OFF SITE CLAY AND SOIL. IF NECESSARY WHEELS AND AXLES ARE TO BE HOSED DOWN. BALLAST IS TO BE MAINTAINED & REPLACED AS NECESSARY DURING CONSTRUCTION.
14. THE HEAD CONTRACTOR IS TO INFORM ALL SITE STAFF AND SUB-CONTRACTORS OF THEIR OBLIGATIONS UNDER THE EROSION AND SEDIMENT CONTROL PLAN.
15. ANY SEDIMENT DEPOSITED ON THE PUBLIC WAY, INCLUDING FOOTPATH RESERVE AND ROAD SURF, IS TO BE REMOVED IMMEDIATELY.
16. PROVIDE BARRIERS AROUND ALL CONSTRUCTION WORKS WITHIN THE FOOTPATH AREA TO PROVIDE SAFE ACCESS FOR PEDESTRIANS.
17. CONCRETE PUMPS AND CRANES ARE TO OPERATE FROM WITHIN THE BALLAST AREA TO PREVENT VIBRATION AND AVOID TO OPERATE FROM THE PUBLIC ROADWAY UNLESS SPECIFIC COUNCIL PERMISSION IS OBTAINED.
18. DELIVERY VEHICLES MUST NOT STAND WITHIN THE PUBLIC ROADWAY FOR MORE THAN 20 MINUTES AT A TIME.
19. TRUCKS TO BE USED TO EXCAVATED / DEMOLISHED MATERIAL SHOULD TRAVEL ON STABILISED CONSTRUCTION PATHS. MATERIAL TO BE TAKEN TO THE TRUCK TO REDUCE TRUCK MOVEMENT ON SITE. TRUCKS TO BE LIMITED TO SINGLE UNIT HEAVY RIGID VEHICLES. (NO SEMITRAILERS)
20. ANY CONSTRUCTION WORK ADJACENT TO ADJOINING PROPERTIES OR THE PUBLIC ROADWAY IS NOT TO BE COMMENCED UNTIL THE STRUCTURAL ENGINEER IS CONSULTED AND SPECIFIC INSTRUCTIONS RECEIVED FROM THE ENGINEER.
21. TOILET FACILITIES MUST BE EITHER A FLUSHING TYPE OR APPROVED PORTABLE CHEMICAL CLOSET. CHEMICAL CLOSETS ARE TO BE MAINTAINED & SERVICED ON A REGULAR BASIS SO AS TO PREVENT AN OUBOUR.
22. DURING TRENCH EXCAVATION ALL SPILL SHALL BE MOUNDED ON THE UPHILL SIDE OF THE TRENCHES AND PLACEMENT IS TO COMPLY WITH THE SUPERINTENDENTS REQUIREMENT.
23. DIVERSION BANKS SHOULD BE CONSTRUCTED BY MOUNDING STRIPPED TOPSOIL (MIN 150mm) WHERE DIRECTED. MATERIAL TO BE RESPAED ON FOOTWAYS AFTER FINAL TRIMMING.
24. UNDISTURBED BUFFER ZONE AREAS ARE CLOSED TO ALL TRAFFIC MOVEMENTS UNLESS OTHERWISE NOTED BY THE SUPERINTENDENT AND ACCESS TO THE SEWER OR C.D.L. ARE TO BE SHOWN ON THE PLAN.
25. TRAFFIC MANAGEMENT MEASURES ARE REQUIRED TO BE IMPLEMENTED AND MAINTAINED DURING CONSTRUCTION. IN ACCORDANCE WITH R.T.A. TRAFFIC CONTROL AT WORK SITES - CURRENT EDITION AND AS 1742 MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
26. PEDESTRIAN CONTROL MEASURES ARE REQUIRED TO BE IMPLEMENTED AND MAINTAINED DURING CONSTRUCTION. IN ACCORDANCE WITH AS 1742 MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.



SEDIMENT FENCE

GENERAL CONSTRUCTION NOTES


- ### GENERAL CONSTRUCTION NOTES
1. CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE.
 2. DRIVE 1.5m LONG STAR PICKETS IN GROUND 3m APART.
 3. DIG A 200mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE FABRIC TO BE ENTRENCHED.
 4. BACKFILL TRENCH OVER BASE OF FABRIC
 5. FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
 6. JOIN SECTIONS OF FABRIC AT A SUPPORT WITH A 150m OVERLAP.



SILT FENCE DETAIL


SEDIMENT SILT FENCE DETAIL

SCALE 1 : 20




GEOTEXTILE FILTER FABRIC DROP INLET SEDIMENT TRAP DETAIL

SCALE 1 : 20



SANDBAG SEDIMENT TRAP DETAIL

SCALE 1 : 20





GENERAL CONSTRUCTION NOTES:

- GENERAL CONSTRUCTION NOTES:**
1. CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE.
 2. FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
 3. JOIN SECTIONS OF FABRIC AT A SUPPORT WITH A 150mm OVERLAP.
 4. REFER TO DETAIL SD 6-9 "BLUE BOOK"

SEDIMENT FENCE - ALTERNATIVE

SCALE 1 : 20






STOCKPILES

N.T.S

GENERAL CONSTRUCTION NOTES:

1. LOCATE STOCKPILE AT LEAST 5m FROM VEGETATION, CONCENTRATED WATER FLOWS, ROADS AND HAZARD AREAS.
2. CONSTRUCT ON THE CONTOUR AS A LOW FLAT ELONGATED MOUND.
3. WHERE THERE IS A SUFFICIENT AREA TOPSOIL STOCKPILES SHALL BE LESS THAN 2m IN HEIGHT. (TO ALLOW AIR VENTILATION FOR FUTURE REUSE)
4. REHABILITATE IN ACCORDANCE WITH THE SWMP/ESCP.
5. CONSTRUCT EARTH BANK ON THE UPSLOPE SIDE TO DIVERT RUN OFF AROUND THE STOCKPILE AND A SEDIMENT FENCE 1m TO 2m DOWNSLOPE OF STOCKPILE.

STOCKPILES

ENVIRONMENTAL SITE MANAGEMENT LEGEND	
SYMBOL	DESCRIPTION
	PROPOSED BUILDING LINE
	PROPOSED BUILDING ROOF OUTLINE
	PROPRIETARY SILT FENCE
	PROVIDE TEMPORARY CHAIN WIRE FENCING (HOARDING) ALONG THE SITE BOUNDARY
	TEMPORARY STABILISED CONSTRUCTION ENTRY/EXIT, (SHAKER PAD)
	TEMPORARY FILTER TUBE WITH SAFETY BARRICADE TO KERB INLET PITS.
	TEMPORARY MASS CONCRETE FOOTPATH CROSSING.
	DIRECTION OF FLOW
	DIVERSION BANK
	SURFACE INLET DRAINAGE PIT WITH SURROUNDING FILTER FABRIC INLET SEDIMENT TRAP OR FILTER TUBES (SANDBAGS)
	TEMPORARY GEOTEXTILE WRAPPED HAY BALES/SAND BAGS
	SANDBAG SEDIMENT INLET TRAP
	SANDBAG KERB SEDIMENT TRAP



This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN	DJA
DATE	13/06/2024
SIZE	A1
SCALE	AS SHOWN
PROJECT MGR	GC

CIVIL SKETCH

ESM SITE PLAN

Proposed Senior Development

10-14 Munmurra Road and 5
Bernadotte St Riverwood NSW 2210

**Custance Associates Australia Pty
Ltd**

N0221293
ESM1 B



This document is issued by
Jones Nicholson Pty Ltd (ABN 51 003 316 032)

DESIGN	DJA
DATE	13/06/2024
SIZE	A1
SCALE	1:200
PROJECT MGR	GC

CIVIL SKETCH ESM SITE PLAN

**Proposed Senior
Development**
10-14 Munmurra Road and 5
Bernadotte St Riverwood NSW 2210
**Custance Associates Australia Pty
Ltd**

**N0221293
ESM2 B**