
# PROPOSED DEVELOPMENT No.'s 41 & 43 OWEN AVENUE, WYONG

## STORMWATER MANAGEMENT PLANS



## DIAL BEFORE YOU DIG



IMPORTANT: THE CONTRACTOR IS TO MAINTAIN A CURRENT SET OF "DIAL BEFORE YOU DIG" DRAWINGS ON SITE AT ALL TIMES.

## **GENERAL NOTES**

- . THESE PLANS SHALL BE READ IN CONJUNCTION WITH OTHER RELEVANT CONSULTANTS' PLANS, SPECIFICATIONS, CONDITIONS OF DEVELOPMENT CONSENT AND CONSTRUCTION CERTIFICATE REQUIREMENTS. WHERE DISCREPANCIES ARE FOUND ACOR CONSULTANTS (CC) MUST BE CONTACTED IMMEDIATELY FOR VERIFICATION
- WHERE THESE PLANS ARE NOTED FOR DEVELOPMENT APPLICATION PURPOSES ONLY, THEY SHALL NOT BE USED FOR OBTAINING A CONSTRUCTION CERTIFICATE NOR USED FOR CONSTRUCTION PURPOSES
- SUBSOIL DRAINAGE SHALL BE DESIGNED AND DETAILED BY THE STRUCTURAL ENGINEER. SUBSOIL DRAINAGE SHALL NOT BE CONNECTED INTO THE STORMWATER SYSTEM IDENTIFIED ON THESE PLANS UNLESS APPROVED BY ACOR CONSULTANTS (CC)

## STORMWATER CONSTRUCTION NOTES

- ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH AS/NZS 3500 (CURRENT EDITION) AND THE REQUIREMENTS OF THE LOCAL COUNCIL'S POLICIES AND CODES
- 2. THE MINIMUM SIZES OF THE STORMWATER DRAINS SHALL NOT BE LESS THAN DN90 FOR CLASS 1 BUILDINGS AND DN100 FOR OTHER CLASSES OF BUILDING OR AS REQUIRED BY THE REGULATORY AUTHORITY
- THE MINIMUM GRADIENT OF STORMWATER DRAINS SHALL BE 1%, UNLESS NOTED OTHERWISE
- COUNCIL'S TREE PRESERVATION ORDER IS TO BE STRICTLY
  ADHERED TO. NO TREES SHALL BE REMOVED UNTIL PERMIT IS
  OBTAINED
- 5. PUBLIC UTILITY SERVICES ARE TO BE ADJUSTED AS NECESSARY AT THE CLIENT'S EXPENSE
- . ALL PITS TO BE BENCHED AND STREAMLINED. PROVIDE STEP IRONS FOR ALL PITS OVER 1.2m DEEP
- 7. MAKE SMOOTH JUNCTION WITH ALL EXISTING WORK
- VEHICULAR ACCESS AND ALL SERVICES TO BE MAINTAINED AT ALL TIMES TO ADJOINING PROPERTIES AFFECTED BY CONSTRUCTION
- 9. SERVICES SHOWN ON THESE PLANS HAVE BEEN LOCATED FROM INFORMATION SUPPLIED BY THE RELEVANT AUTHORITIES AND FIELD INVESTIGATIONS AND ARE NOT GUARANTEED COMPLETE NOR CORRECT. IT IS THE CLIENT & CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL PRIOR TO CONSTRUCTION
- 0. ANY VARIATION TO THE WORKS AS SHOWN ON THE APPROVED DRAWINGS ARE TO BE CONFIRMED BY ACOR CONSULTANTS (CC) PRIOR TO THEIR COMMENCEMENT

### **RAINWATER RE-USE SYSTEM NOTES**

- RAINWATER SUPPLY PLUMBING TO BE CONNECTED TO OUTLETS
   WHERE REQUIRED BY BASIX CERTIFICATE (BY OTHERS)
- TOWN WATER CONNECTION TO RAINWATER TANK TO BE TO THE SATISFACTION OF THE REGULATORY AUTHORITY. THIS MAY REQUIRE PROVISION OF:
- 2.1. PERMANENT AIR GAR
- 2.2. BACKFLOW PREVENTION DEVICE
- . NO DIRECT CONNECTION BETWEEN TOWN WATER SUPPLY AND THE RAIN WATER SUPPLY
- . AN APPROVED STOP VALVE AND/OR PRESSURE LIMITING VALVE AT THE RAINWATER TANK
- PROVIDE APPROPRIATE FLOAT VALVES AND/OR SOLENOID VALVES TO CONTROL TOWN WATER SUPPLY INLET TO TANK IN ORDER TO ACHIEVE THE TOP-UP INDICATED ON THE TYPICAL DETAIL
- ALL PLUMBING WORKS ARE TO BE CARRIED OUT BY LICENSED PLUMBERS IN ACCORDANCE WITH AS/NZS3500.1 NATIONAL PLUMBING AND DRAINAGE CODE
- 7. PRESSURE PUMP ELECTRICAL CONNECTION TO BE CARRIED OUT BY
- 8. ONLY ROOF RUN-OFF IS TO BE DIRECTED TO THE RAINWATER TANK SURFACE WATER INLETS ARE NOT TO BE CONNECTED
- PIPE MATERIALS FOR RAINWATER SUPPLY PLUMBING ARE TO BE APPROVED MATERIALS TO AS/NZS3500 PART 1 SECTION 2 AND TO BE CLEARLY AND PERMANENTLY IDENTIFIED AS 'RAINWATER'. THIS MAY BE ACHIEVED FOR BELOW GROUND PIPES USING IDENTIFICATION TAPE (MADE IN ACCORDANCE WITH AS2648) OR FOR ABOVE GROUND PIPES BY USING ADHESIVE PIPE MARKERS (MADE IN ACCORDANCE WITH AS1345)
- EVERY RAINWATER SUPPLY OUTLET POINT AND THE RAINWATER TANK ARE TO BE LABELED 'RAINWATER' ON A METALLIC SIGN IN ACCORDANCE WITH AS1319
- 11. ALL INLETS AND OUTLETS TO THE RAINWATER TANK ARE TO HAVE SUITABLE MEASURES PROVIDED TO PREVENT MOSQUITO AND VERMIN ENTRY

| SHEET INDEX                                |          |
|--|----------|
| COVER SHEET & NOTES                        | SHEET C1 |
| STORMWATER MANAGEMENT PLAN                 | SHEET C2 |
| STORMWATER MANAGEMENT DETAILS SHEET No.1   | SHEET C3 |
| STORMWATER MANAGEMENT DETAILS SHEET No. 2  | SHEET C4 |
| ON SITE DETENTION REPORT                   | SHEET C5 |
| EROSION & SEDIMENT CONTROL PLAN            | SHEET C6 |
| EROSION & SEDIMENT CONTROL NOTES & DETAILS | SHEET C7 |
|  |          |

## CENTRAL COAST COUNCIL REQUIREMENTS

 SITE AREA (m²)
 1161.5

 POST DEVELOPED IMPERVIOUS AREA (m²)
 757.2 (65.2%)

#### ON SITE DETENTION

DRAINS SOFTWARE ADOPTED FOR MODELLING, REFER TO DRAINS FILE CC210464.dm. REFER TO SHEET C5 FOR ON SITE DETENTION REPORT.

VOLUME PROVIDED = 10m<sup>3</sup>
ORIFICE DIAMETER = 200mm

## ON SITE RETENTION

RAINWATER REUSE TANK PROVIDED IN ACCORDANCE WITH THE BASIX.
REFER TO SHEET C2 FOR LOCATION AND SHEET C4 FOR DETAIL.

DESIGN PREPARED IN ACCORDANCE WITH COUNCIL'S "CENTRAL COAST DEVELOPMENT CONTROL PLAN 2022", CIVIL WORKS DESIGN GUIDELINE, AR&R AND AS/NZS 3500.



DEVELOPMENT APPLICATION ISSUE NOT FOR CONSTRUCTION

DRAWINGS MUST BE PRINTED IN COLOUR

COPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATT The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified,

| repro | duced or copied wholly of in part without written permission from ACOR Consultants (CC) Pty Ltd. ACOR Consul | tants is a tr | ademark | icensed to A | ACOR Consultants | (CC) |
|-------|--|---------------|---------|--------------|------------------|------|
|       |  |               |         |              |                  |      |
| D     | UPDATED TO SUIT LATEST ARCHITECTURAL PLANS   | 02.03.23      | ED      | BK           | North            | 7    |
| С     | PIT P1 AMENDED   | 30.11.22      | ED      | BK           |                  | 11.  |
| В     | UPDATED TO SUIT NEW ARCHITECTURAL PLANS  | 30.11.22      | RH      | BK           |                  |      |
| Α     | ISSUED FOR DEVELOPMENT APPROVAL  | 11.10.22      | RH      | BK           | 7                |      |
| Issue | Description  | Date          | Drawn   | Approved     |                  |      |

BA & A PTY


BARRY RUSH & ASSOCIATES PTY LTD





ACOR Consultants (CC) Pty Ltd Platinum Building, Suite 2.01, 4 Ilya Avenue ERINA NSW 2250, Australia



| CL    | SEPT 2022 | AS NOTED | -          |
|-------|-----------|----------|------------|
| Drawn | Date      |          | Q.A. Check |
| COVER | SHEET     |          |            |
|       |           |          |            |







OCPYRIGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modified,

|       |  |          |       |          |       | Client                          | Architect |
|-------|--|----------|-------|----------|-------|---------------------------------|-----------|
| D     | UPDATED TO SUIT LATEST ARCHITECTURAL PLANS | 02.03.23 | ED    | BK       | North | BARRY RUSH & ASSOCIATES PTY LTD |           |
| С     | PIT P1 AMENDED                             | 30.11.22 | ED    | BK       |       |                                 |           |
| В     | UPDATED TO SUIT NEW ARCHITECTURAL PLANS    | 30.11.22 | RH    | BK       |       | & ASSOCIATES                    |           |
| Α     | NIL ISSUE                                  | -        | -     | -        |       | PTY LTD                         |           |
| Issue | Description                                | Date     | Drawn | Approved |       |                                 |           |
| 1 0   | 1cm at full size                           |          |       |          |       |                                 |           |

Platinum Buildii

## ACOR Consultants (CC) Pty Ltd Platinum Building, Suite 2.01, 4 llya Avenue ERINA NSW 2250, Australia T +61 2 4324 3499

roject
12.01, 4 llya Avenue
ISW 2250, Australia
T +61 2 4324 3499
PROPOSED RESIDENTIAL
DEVELOPMENT

STORMWATER MANAGEMENT
DETAILS SHEET No.1

Drawn Date A1 Q.A. Check
RH SEPT 2022 AS NOTED -

CC210464

C4

No.'s 41 & 43 OWEN AVENUE WYONG

## ON-SITE STORMWATER DETENTION REPORT

## 1.1. METHODOLOGY

1.1.1. THE DRAINS PROGRAM WAS ADOPTED AS AN APPROPRIATE MODEL FOR THIS PROJECT. PRE-DEVELOPED AND POST-DEVELOPED HYDROLOGICAL AND HYDRAULIC MODELS WERE DEVELOPED FOR THE 1, 2, 5, 10, 20, 50 AND 100 YEAR ARI DESIGN STORM EVENTS, ASSESSING STACKED RAINFALL PATTERNS RANGING FROM 5 MINUTES TO 2 HOURS. THE ADOPTED PRE & POST DEVELOPED FLOWS ARE THOSE ASSIGNED TO THEIR RESPECTIVE PEAKS.

## 1.2. PRE-DEVELOPED DRAINS MODEL

- 1.2.1. THE PRE-DEVELOPED DRAINS MODEL COMPRISED A SINGLE SUB-CATCHMENT DISCHARGING TO A DUMMY NODE. THE PARAMETERS INPUT TO THE DRAINS MODEL FOR THE SUB-CATCHMENT ARE IDENTIFIED IN THE DRAINS SUB-CATCHMENT DATA INPUT FILE. REFER TO DRAINS FILE "GOSFORD CC210464.drn" THE CATCHMENT AREA ADOPTED IS 0.1161ha. THE PRE & POST DEVELOPED IMPERVIOUS AREAS ADOPTED IN THE MODEL ARE 0% AND 65% RESPECTIVELY.
- 1.2.2. THE PRE-DEVELOPED PEAK FLOWRATES CALCULATED BY THE DRAINS PROGRAM ARE SUMMARISED BELOW:

| SITE AREA (m²) | 1161 (34% PERVIOUS)                    |
|----------------|--|
| ARI (YEARS)    | PEAK FLOWRATE<br>(PRE-DEVELOPED) (L/s) |
| 5              | 33                                     |
| 20             | 45                                     |
| 100            | 57                                     |

## 1.3. POST-DEVELOPED MODEL

- 1.3.1. THE POST DEVELOPED DRAINS MODEL COMPRISES OF TWO SUB CATCHMENTS FORMED BY THE POST DEVELOPED ROOF AREA WHICH DRAINS TO RAINWATER TANKS WITH OVERFLOWS TO DETENTION TANK, AND RESIDUAL SURFACE AREAS THAT DRAIN DIRECTLY TO DETENTION TANK. REFER TO DRAINS MODEL "CC210464.drn" FOR DETAIL.
- 1.3.2. THE PARAMETERS INPUT INTO THE DRAINS MODEL FOR THE POST-DEVELOPED DETENTION TANK IS IDENTIFIED IN THE DRAINS SUB-CATCHMENT DATA, REFER TO DRAINS MODEL "CC210464.drn" FOR DETAILS.
- 1.3.3 THE OSD STORAGE/OUTFLOW PARAMETERS ADOPTED IN THE DRAINS MODEL ARE IDENTIFIED IN DRAINS MODEL "CC210464.drn"
- 1.3.4 THE PEAK STORAGE VOLUME CALCULATED BY THE DRAINS MODEL OCCURS DURING THE 100 YEAR ARI 25 MINUTE DESIGN STORM EVENT. THE VOLUMETRIC GRAPH FOR THIS STORM EVENT IS IDENTIFIED IN DRAINS MODEL "CC210464.drn".

## 1.3. POST-DEVELOPED MODEL (CONTINUED)

- THE INFLOW AND OUTFLOW HYDROGRAPH FOR THIS STORM EVENT IS IDENTIFIED IN DRAINS MODEL "CC210464.drn"
- THE PEAK FLOWRATES AND WATER SURFACE LEVELS DEVELOPED 1.3.6. BY THE DRAINS MODEL FOR THE 100 YEAR ARI DESIGN STORM EVENT. REFER TO DRAINS MODEL "CC210464.drn" FOR DETAIL.
- 1.3.7 THE POST-DEVELOPED PEAK FLOWRATES ARE TABLED BELOW:

| ARI (YEARS) | PEAK FLOWRATE<br>(POST-DEVELOPED) (L/s) |
|-------------|---|
| 5           | 32                                      |
| 20          | 42                                      |
| 100         | 50                                      |

## 1.4. CONCLUSION

1.4.6. BASED ON THE FOREGOING THE PROPOSED OSD TANK WILL ATTENUATE POST-DEVELOPED PEAK FLOWRATES TO EQUIVALENT FLOWRATES OR LESS THAN THE COMPARABLE PRE-DEVELOPED FLOWRATES. THE PEAK FLOWRATES FOR THE PRE & POST-DEVELOPED STORM EVENTS FOR THE ENTIRE CATCHMENT DISCHARGE TO THE EXISTING STORMWATER SYSTEM ARE TABLED BELOW:

|             | PEAK FLOW |      |           |  |  |
|-------------|-----------|------|-----------|--|--|
| ARI (YEARS) | OVERAL    |      |           |  |  |
|             | PRE       | POST | REMARKS   |  |  |
| 5           | 33        | 32   | REDUCTION |  |  |
| 20          | 45        | 42   | REDUCTION |  |  |
| 100         | 57        | 50   | REDUCTION |  |  |

| D     | UPDATED TO SUIT LATEST ARCHITECTURAL PLANS | 02.03.23 | ED    | BK       | North |
|-------|--|----------|-------|----------|-------|
| С     | PIT P1 AMENDED                             | 30.11.22 | ED    | BK       |       |
| В     | UPDATED TO SUIT NEW ARCHITECTURAL PLANS    | 30.11.22 | RH    | BK       |       |
| Α     | ISSUED FOR DEVELOPMENT APPROVAL            | 11.10.22 | RH    | BK       |       |
| Issue | Description                                | Date     | Drawn | Approved |       |
| 1 0   | 1cm at full size                           | _        |       |          |       |


**BARRY RUSH** & ASSOCIATES





CC210464

OWEN AVENUE



#### **EROSION AND SEDIMENT CONTROL NOTES**

#### GENERAL INSTRUCTIONS

- THIS SOIL AND WATER MANAGEMENT PLAN IS TO BE READ 7. IN CONJUNCTION WITH OTHER ENGINEERING PLANS RELATING TO THIS DEVELOPMENT
- CONTRACTORS WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE GUIDELINES OF "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION", DEPT OF HOUSING, 1998 (BLUE BOOK)
- ALL SUBCONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN REDUCING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE AREAS.

#### LAND DISTURBANCE INSTRUCTIONS

- DISTURBANCE TO BE NO FURTHER THAN 5 (PREFERABLY 2) METRES FROM THE EDGE OF ANY ESSENTIAL ENGINEERING ACTIVITY AS SHOWN ON APPROVED PLANS. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE ZONES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- ACCESS AREAS ARE TO BE LIMITED TO A MAXIMUM WIDTH OF 10 METRES THE SITE MANAGER WILL DETERMINE AND MARK THE LOCATION OF THESE ZONES ON-SITE. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE BOUNDARIES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS
- ENTRY TO LANDS NOT REQUIRED FOR CONSTRUCTION OR ACCESS IS PROHIBITED EXCEPT FOR ESSENTIAL THINNING OF PLANT GROWTH
- WORKS ARE TO PROCEED IN THE FOLLOWING SEQUENCE: A) INSTALL ALL BARRIER AND SEDIMENT FENCING WHERE SHOWN ON THE PLAN
- CONSTRUCT THE STABILISED SITE ACCESS
- CONSTRUCT DIVERSION DRAINS AS REQUIRED INSTALL MESH AND GRAVEL INLETS FOR ANY D)
- ADJACENT KERR INLETS
- INSTALL GEOTEXTILE INLET FILTERS AROUND ANY ON-SITE DROP INLET PITS.
- CLEAR SITE AND STRIP AND STOCKPILE TOPSOIL IN LOCATIONS SHOWN ON THE PLAN
- UNDERTAKE ALL ESSENTIAL CONSTRUCTION WORKS ENSURING THAT ROOF AND/OR PAVED AREA STORMWATER SYSTEMS ARE CONNECTED TO PERMANENT DRAINAGE AS SOON AS PRACTICABLE
- GRADE LOT AREAS TO FINAL GRADES AND APPLY PERMANENT STABILISATION (LANDSCAPING) WITHIN 20 DAYS OF COMPLETION OF CONSTRUCTION WORKS
- REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER THE PERMANENT LANDSCAPING HAS BEEN COMPLETED.
- ENSURE THAT SLOPE LENGTHS DO NOT EXCEED 80 METRES WHERE PRACTICABLE. SLOPE LENGTHS ARE DETERMINED BY SILTATION FENCING AND CATCH DRAIN
- ON COMPLETION OF MAJOR WORKS LEAVE DISTURBED LANDS WITH A SCARIFIED SURFACE TO ENCOURAGE WATER INFILTRATION AND ASSIST WITH KEYING TOPSOIL

#### SITE MAINTENANCE INSTRUCTIONS

- THE SITE SUPERINTENDENT WILL INSPECT THE SITE AT LEAST WEEKLY AND AT THE CONCLUSION OF EVERY STORM EVENT TO:
  - ENSURE THAT DRAINS OPERATE PROPERLY AND TO EFFECT ANY NECESSARY REPAIRS.
  - REMOVE SPILLED SAND OR OTHER MATERIALS FROM HAZARD AREAS, INCLUDING LANDS CLOSER THAN 5 METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS ESPECIALLY WATERWAYS AND PAVED AREAS.
  - REMOVE TRAPPED SEDIMENT WHENEVER THE DESIGN CAPACITY OF THAT STRUCTURE HAS BEEN EXCEEDED
  - ENSURE REHABILITATED LANDS HAVE EFFECTIVELY REDUCED THE EROSION HAZARD AND TO INITIATE UPGRADING OR REPAIR AS
  - CONSTRUCT ADDITIONAL EROSION AND/OR SEDIMENT CONTROL WORKS AS MIGHT BECOME NECESSARY TO ENSURE THE DESIRED PROTECTION IS GIVEN TO DOWNSLOPE LANDS AND WATERWAYS, MAKE ONGOING CHANGES TO THE PLAN WHERE IT PROVES INADEQUATE IN PRACTICE OR IS SUBJECTED TO CHANGES IN CONDITIONS ON THE WORK-SITE OR ELSEWHERE IN THE CATCHMENT
  - MAINTAIN EROSION AND SEDIMENT CONTROL STRUCTURES IN A FULLY FUNCTIONING CONDITION UNTIL ALL EARTHWORK ACTIVITIES ARE COMPLETED AND THE SITE IS REHABILITATED
- THE SITE SUPERINTENDENT WILL KEEP A LOGBOOK MAKING ENTRIES AT LEAST WEEKLY, IMMEDIATELY BEFORE FORECAST RAIN AND AFTER RAINFALL. ENTRIES WILL INCLUDE:
- THE VOLUME AND INTENSITY OF ANY RAINFALL A) EVENTS.
- THE CONDITION OF ANY SOIL AND WATER MANAGEMENT WORKS
- THE CONDITION OF VEGETATION AND ANY NEFD TO IRRIGATE
- THE NEED FOR DUST PREVENTION STRATEGIES.
- ANY REMEDIAL WORKS TO BE UNDERTAKEN. THE LOGBOOK WILL BE KEPT ON-SITE AND MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. IT WILL BE GIVEN TO THE PROJECT MANAGER AT THE CONCLUSION OF THE WORKS.

## SEDIMENT CONTROL INSTRUCTIONS


- SEDIMENT FENCES WILL BE INSTALLED AS SHOWN ON THE WASTE CONTROL INSTRUCTIONS PLAN AND ELSEWHERE AT THE DISCRETION OF THE SITE SUPERINTENDENT TO CONTAIN SOIL AS NEAR AS POSSIBLE TO THEIR SOURCE
- SEDIMENT FENCES WILL NOT HAVE CATCHMENT AREAS EXCEEDING 900 SQUARE METRES AND HAVE A STORAGE DEPTH OF AT LEAST 0.6 METRES
- SEDIMENT REMOVED FROM ANY TRAPPING DEVICES WILL BE RELOCATED WHERE FURTHER POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS CANNOT OCCUR
- 12. STOCKPILES ARE NOT TO BE LOCATED WITHIN 5 METRES OF HAZARD AREAS INCLUDING AREAS OF HIGH VELOCITY FLOWS SUCH AS WATERWAYS, PAVED AREAS AND **DRIVEWAYS**
- WATER WILL BE PREVENTED FROM DIRECTLY ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR WATER HAS BEEN TREATED BY AN APPROVED DEVICE
- 14. TEMPORARY SEDIMENT TRAPS WILL REMAIN IN PLACE UNTIL AFTER THE LANDS THEY ARE PROTECTING ARE COMPLETELY REHABILITATED.
- ACCESS TO SITES SHOULD BE STABILISED TO REDUCE THE LIKELIHOOD OF VEHICLES TRACKING SOIL MATERIALS ONTO PUBLIC ROADS AND ENSURE ALL-WEATHER ENTRY/EXIT

### SOIL EROSION CONTROL INSTRUCTIONS

- 16. EARTH BATTERS WILL BE CONSTRUCTED WITH AS LOW A GRADIENT AS PRACTICABLE BUT NO STEEPER, UNLESS OTHERWISE NOTED, THAN:
  - 2(H):1(V) WHERE SLOPE LENGTH LESS THAN 12 METRES
  - 2.5(H):1(V) WHERE SLOPE LENGTH BETWEEN 12 AND 16 METRES.
  - 3(H):1(V) WHERE SLOPE LENGTH BETWEEN 16 AND 20 METRES.
  - 4(H):1(V) WHERE SLOPE LENGTH GREATER THAN 20 METRES
- ALL WATERWAYS, DRAINS, SPILLWAYS AND THEIR OUTLETS WILL BE CONSTRUCTED TO BE STABLE IN AT LEAST THE 1:20 YEAR ARI, TIME OF CONCENTRATION STORM EVENT.
- 18. WATERWAYS AND OTHER AREAS SUBJECT TO CONCENTRATED FLOWS AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUNDCOVER C-FACTOR OF 0.05 (70%) GROUND COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION. FLOW VELOCITIES ARE TO BE LIMITED TO THOSE SHOWN IN TABLE 5-1 OF "MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION", DEPT OF HOUSING 1998 (BLUE BOOK). FOOT AND VEHICULAR TRAFFIC WILL BE PROHIBITED IN THESE AREAS.
- STOCKPILES AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.1 (60% GROUND-COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION.
- ALL LANDS, INCLUDING WATERWAYS AND STOCKPILES, DURING CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.15 (50% GROUND COVER) WITHIN 20 WORKING DAYS FROM INACTIVITY EVEN THOUGH WORKS MAY CONTINUE LATER.
- 21 FOR AREAS OF SHEET FLOW USE THE FOLLOWING GROUND COVER PLANT SPECIES FOR TEMPORARY COVER: JAPANESE MILLET 20 KG/HA AND OATS 20 KG/HA.
- 22. PERMANENT REHABILITATION OF LANDS AFTER CONSTRUCTION WILL ACHIEVE A GROUND-COVER C-FACTOR OF LESS THAN 0.1 AND LESS THAN 0.05 WITHIN 60 DAYS NEWLY PLANTED LANDS WILL BE WATERED. REGULARLY UNTIL AN EFFECTIVE COVER IS ESTABLISHED AND PLANTS ARE GROWING VIGOROUSLY FOLLOW-UP SEED AND FERTILISER WILL BE APPLIED, AS NECESSARY REVEGETATION SHOULD BE AIMED AT RE-ESTABLISHING NATURAL SPECIES, NATURAL SURFACE SOILS SHOULD BE

REPLACED AND NON-PERSISTANT ANNUAL COVER CROPS


- SHOULD BE USED
- ACCEPTABLE BINS WILL BE PROVIDED FOR ANY CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHING, LIGHTWEIGHT WASTE MATERIALS AND LITTER. CLEARANCE SERVICES WILL BE PROVIDED AT LEAST WEEKLY, DISPOSAL OF WASTE WILL BE IN A MANNER APPROVED BY THE SITE SUPERINTENDENT.
- 25. ALL POSSIBLE POLLUTANT MATERIALS ARE TO BE STORED WELL CLEAR OF ANY POORLY DRAINED AREAS, FLOOD PRONE AREAS, STREAMBANKS, CHANNELS AND STORMWATER DRAINAGE AREAS. STORE SUCH MATERIALS IN A DESIGNATED AREA UNDER COVER WHERE POSSIBLE AND WITHIN CONTAINMENT BUNDS.
- ALL SITE STAFF AND SUB-CONTACTORS ARE TO BE INFORMED OF THEIR OBLIGATION TO USE WASTE CONTROL FACILITIES PROVIDED
- ANY DE-WATERING ACTIVITIES ARE TO BE CLOSELY MONITORED TO ENSURE THAT WATER IS NOT POLLUTED BY SEDIMENT, TOXIC MATERIALS OR PETROLEUM **PRODUCTS**
- 28. PROVIDE DESIGNATED VEHICULAR WASHDOWN AND MAINTENANCE AREAS WHICH ARE TO HAVE CONTAINMENT BUNDS



- CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE
- CONSTRUCT SECURIOR TERROLE AS OLUSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE. DRIVE 1.5 METRE LONG STAR PICKETS INTO GROUND, 3 METRES APART. DIG A 150 MM DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO SECURIOR FOR THE STAR OF THE STAR
- TO BE ENTRENCHED.

  BACKFILL TRENCH OVER BASE OF FABRIC.
  FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
- JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150 MM OVERLAP.

#### SEDIMENT FENCE SD 6-8




- STRIP TOPSOIL AND LEVEL SITE.
- COMPACT SUBGRADE
- COVER AREA WITH NEEDLE-PUNCHED GEOTEXTILE
- CONSTRUCT 200MM THICK PAD OVER GEOTEXTILE USING ROADBASE OR 30MM AGREGATE.
- CONSTRUCT ZOUMN THICK PRO USE OF SETTED SOUND ROADS ON SOUMN ACCESSES.

  KININIUM LENGTH 15M OR TO BUILDING ALIGNMENT, MINIMUM WIDTH 3 METRES.

  CONSTRUCT HUMP IMMEDIATELY WITHIN BUUNDARY TO DIVERT WATER TO A SEDIMENT FENCE OR OTHER SEDIMENT TRAP.

STABILISED SITE ACCESS SD 6-14



- FABRICATE A SEDIMENT BARRIER FROM GEOTEXTILE OR STRAW BALES. SUPPORT GEOTEXTILE WITH MESH TIED TO POSTS AT 1 METRE CENTRES
- DO NOT COVER INLET WITH GEOTEXTILE
- CONSTRUCTION DETAILS ARE SIMILAR TO TYPICAL SEDIMENT FENCING DETAIL

GEOTEXTILE INLET FILTER SD 6-12

SOURCE: MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION THIRD EDITION AUGUST 1998 PRODUCED BY THE DEPARTMENT STABILISE STOCKPILE CONSTRUCTION NOTES: 1. LOCATE STOCKPILE AT LEAST 5 METRES FROM EXISTING VEGETATION. CONCENTRATED WATER FLOWS ROADS AND HAZARD AREAS I CONSTRUCT ON THE CONTOUR AS A LOW, FLAT, ELONGATED MOUND.

WHERE THERE IS SUFFICIENT AREA TOPSOIL STOCKPILES SHALL BE LESS THAN 2 METERS IN HEIGHT.

- CONSTRUCT EARTH BANK (STANDARD DRAWING 5-2) ON THE UPSLOPE SIDE TO DIVERT RUN OFF AROUND THE STOCKPILE AND A SEDIMENT FENCE (STANDARD DRAWING 6-7) 1 TO 2 METRES DOWNSLOPE OF STOCKPILE.

STOCKPILES

SD 4-1

IGHT of this design and plan is the property of ACOR Consultants (CC) Pty Ltd, ACN 127 012 104 ATF The ACOR (CC) Unit Trust ABN 81 392 991 647, all rights reserved. It must not be used, modifier

| D     | UPDATED TO SUIT LATEST ARCHITECTURAL PLANS | 02.03.23      | ED    | BK       | ٨ |
|-------|--|---------------|-------|----------|---|
| С     | PIT P1 AMENDED                             | 30.11.22      | ED    | BK       | ı |
| В     | UPDATED TO SUIT NEW ARCHITECTURAL PLANS    | 30.11.22      | RH    | BK       | ı |
| Α     | A ISSUED FOR DEVELOPMENT APPROVAL          |               |       | BK       | ı |
| Issue | Description                                | Date          | Drawn | Approved | ı |
| 1 0   | 1cm at full size 10cm                      | $\overline{}$ |       |          | i |

BARRY RUSH & ASSOCIATES







**EROSION & SEDIMENT CONTROL NOTES & DETAILS** AS NOTED SEPT 2022 CC210464 C7