

• 798.79	PROPOSED FINISHED SURFACE LEVELS
•	DENOTES MATCH LEVELS
DP	DENOTES PROPOSED DOWNPIPE
FL	FLOOR LEVEL
TOB	TOP OF BATTER
	100 THICK CONCRETE PATH OVER 50 MIN. COMPACTED BEDDING MATERIAL, N25 CONCRETE, 1 LAYER SL72 MESH, 30 TOP COVER. PROVIDE TOOLED JOINTS AT 1.5m CTS.
	DENOTES AFFECTED AREA TO BE REGRASSED AND/OR TURFED
• B	1300 HIGH COREFILLED 139.5x5.0 CHS H.D. GALV. BOLLARD, PAINTED SAFETY YELLOW. CAST 500 INTO 4500x600 DEEP MASS CONCRETE FOOTING.
	PROPOSED STORMWATER DRAINAGE
s	EXISTING SEWER MAIN
w	EXISTING WATER MAIN
E	EXISTING UNDERGROUND ELECTRICAL
ОН⊖	EXISTING OVERHEAD ELECTRICAL LINES AND POWER POLES
—— т ——	EXISTING TELECOMMUNICATION LINES
g	EXISTING GAS MAIN
-0-	DENOTES EXISTING TREE TO REMAIN.
<b>*</b>	DENOTES EXISTING TREE TO BE REMOVED.
798.00	MAJOR EXISTING SURFACE CONTOURS (1.0m INTERVALS)
	MINOR EXISTING SURFACE CONTOURS (0.2m INTERVALS)