


13086-01C - SOIL REF CONSERVATION WORKS

EUROBODALLA HOSPITAL

PRINCES HIGHWAY, MORUYA, NSW



DRAWING NO.	DESCRIPTION
ERH-TTW-00-DR-CI-0501	DRAWING REGISTER AND LOCALITY PLAN
ERH-TTW-00-DR-CI-0502	CONSTRUCTION NOTES
ERH-TTW-00-DR-CI-0530	SITE WORKS PLAN
ERH-TTW-00-DR-CI-0540	DETAILS AND SECTIONS SHEET 1
ERH-TTW-00-DR-CI-0541	DETAILS AND SECTIONS SHEET 2

REF SUBMISSION
NOT TO BE USED FOR CONSTRUCTION

A ISSUER FOR REVIEW	JH	WW	18.08.23	Client	Multiplex	Engineer	TTW Structural Civil Traffic Façade	Project	EUROBODALLA HOSPITAL	Sheet Subject	SOIL REF DRAWING REGISTER AND LOCALITY PLAN	Scale : A1 NTS	Drawn WW	Authorised AH
Rev Description	Eng	Draft	Date	Rev Description	Eng	Draft	Date	Rev Description	Eng	Draft	Date	Job No	Drawing No	Revision
												221896	ERH-TTW-00-DR-CI-0501	A

GENERAL NOTES

- G1 THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ARCHITECTURAL AND OTHER CONSULTANTS DRAWINGS AND SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS OR SKETCHES AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE SUPERINTENDENT BEFORE PROCEEDING WITH WORK.
- G2 MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE CURRENT SAA CODES, BUILDING REGULATIONS AND THE REQUIREMENTS OF ANY OTHER RELEVANT STATUTORY AUTHORITIES.
- G3 THESE DRAWINGS MUST NOT BE SCALED. ALL DIMENSIONS ARE IN METERS. ALL SET OUT DIMENSIONS AND LEVELS, INCLUDING THOSE SHOWN ON THESE DRAWINGS SHALL BE IN ACCORDANCE WITH THE ARCHITECT'S DRAWINGS AND VERIFIED ON SITE.
- G4 ALL SETOUT AND DIMENSIONS OF THE STRUCTURE INCLUDING KERBS AND RETAINING WALLS MUST BE TAKEN FROM THE ARCHITECT'S DRAWINGS. SETOUT OF THE STORMWATER PITS BY OTHERS, CONTRACTOR TO CONFIRM SETOUT OF SERVICE TRENCHING INCLUDING SUBSOIL ON SITE.
- G5 THE CONTRACTOR SHALL COMPLY WITH ALL REGULATIONS OF AUTHORITIES HAVING JURISDICTION OVER THE WORKS. REFER TO GEOTECHNICAL REPORT BY JK GEOTECHNICS PTY LTD DATED 21ST MAY 2021, REF: 33942LTrp12
- G6 ALL DIMENSIONS AND REDUCED LEVELS MUST BE VERIFIED ON SITE BEFORE THE COMMENCEMENT OF ANY WORK.
- G7 THE APPROVAL OF A SUBSTITUTION SHALL BE SOUGHT FROM THE SUPERINTENDENT BUT IS NOT AN AUTHORISATION OF A COST VARIATION. THE SUPERINTENDENT MUST APPROVE ANY COST VARIATION INVOLVED BEFORE ANY WORK STARTS.
- G8 ALL LEVELS SHOWN ARE TO THE AUSTRALIAN HEIGHT DATUM.
- G9 SERVICE INFORMATION SHOWN IS APPROXIMATE ONLY. PRIOR TO COMMENCEMENT OF ANY WORKS, THE CONTRACTOR SHALL LOCATE ALL UNDERGROUND SERVICES AND COMPLY WITH ALL REQUIREMENTS OF THOSE AUTHORITIES.
- G10 EXISTING SURFACE CONTOURS, WHERE SHOWN, ARE INTERPOLATED AND MAY NOT BE ACCURATE.
- G11 UNLESS NOTED OTHERWISE, ALL VEGETATION SHALL BE STRIPPED TO A MINIMUM DEPTH OF 150mm UNDER ALL PROPOSED PAVEMENT AND BUILDING AREAS.
- G12 MAKE SMOOTH CONNECTION WITH ALL EXISTING WORKS.

SITEWORKS NOTES

- S1 PRIOR TO THE PLACEMENT OF ANY PAVEMENTS, BUILDINGS OR DRAINS THE EXPOSED SUBGRADE SHALL BE COMPACTION TO A MINIMUM OF 98% STANDARD COMPACTION IN ACCORDANCE WITH TEST 'E11 OF AS 1289 FOR THE TOP 300mm. ANY SOFT SPOTS SHALL BE REMOVED AND REPLACED WITH GRANULAR FILL TO THE ENGINEERS APPROVAL AND COMPACTION IN ACCORDANCE WITH THE COMPACTION REQUIREMENTS SET OUT BELOW ON HIGHLY REACTIVE CLAY AREAS SITE EXCAVATED MATERIAL MAY BE USED WITH THE PRIOR AUTHORISATION OF THE ENGINEER
 - LANDSCAPED AREAS 98% STD.
 - FILL UNDER ANY FOOTINGS AND FLOOR SLABS FOR ANY STRUCTURE TO SUBGRADE LEVEL, - FINE CRUSHED ROCK 98% STD.
 - SELECTED FILL WITHOUT CONSPICUOUS CLAY CONTENT 98% STD.
 - BUILDING BASECOURSE 98% MOD.
 - FILL UNDER ROAD PAVEMENTS, - TO WITHIN 500mm OF FINISHED SUBGRADE LEVEL 98% STD.
 - UP TO FINISHED SUBGRADE LEVEL 98% STD.
 - ROAD PAVEMENT MATERIALS, - SUB BASE 98% MOD.
 - BASE COURSE 98% MOD.
- S2 ALL FILL AND PAVEMENT MATERIALS SHALL BE COMPACTION IN ACCORDANCE WITH GEOTECHNICAL REPORT BY JK GEOTECHNICS PTY LTD DATED 21ST MAY 2021, REF: 33942LTrp12. MOISTURE CONTENT TO BE MAINTAINED AT +/- 2% OM. MINIMUM COMPACTION REQUIREMENTS ARE DETAILED BELOW FOR (ALL REQUIREMENTS ARE TO BE VERIFIED BY A SUITABLY QUALIFIED GEOTECHNICAL ENGINEER)
 - LANDSCAPED AREAS 98% STD.
 - FILL UNDER ANY FOOTINGS AND FLOOR SLABS FOR ANY STRUCTURE TO SUBGRADE LEVEL, - FINE CRUSHED ROCK 98% STD.
 - SELECTED FILL WITHOUT CONSPICUOUS CLAY CONTENT 98% STD.
 - BUILDING BASECOURSE 98% MOD.
 - FILL UNDER ROAD PAVEMENTS, - TO WITHIN 500mm OF FINISHED SUBGRADE LEVEL 98% STD.
 - UP TO FINISHED SUBGRADE LEVEL 98% STD.
 - ROAD PAVEMENT MATERIALS, - SUB BASE 98% MOD.
 - BASE COURSE 98% MOD.
- S3 THE MAXIMUM COMPACTION IS TO BE NO GREAT THAN 4% ON TOP OF THE ABOVE MENTION VALUES.
- S4 GRADE EVENLY BETWEEN FINISHED SURFACE SPOT LEVELS. FINISHED SURFACE CONTOURS ARE SHOWN FOR CLARITY. WHERE FINISHED SURFACE LEVELS ARE NOT SHOWN, THE SURFACE SHALL BE GRADED SMOOTHLY SO THAT IT WILL DRAIN AND MATCH ADJACENT SURFACES OR STRUCTURES.
- S5 ALL DIMENSIONS GIVEN ARE TO FACE OF KERB, CENTER OF PIPE OR EXTERIOR FACE OF BUILDING UNLESS NOTED OTHERWISE.
- S6 ANY STRUCTURES, PAVEMENTS OR SURFACES DAMAGED, DIRTYED OR MADE UNSERVICEABLE DUE TO CONSTRUCTION WORK SHALL BE RESTATED TO THE SATISFACTION OF THE ENGINEER.
- S7 ANY FILL REQUIRED SHALL BE APPROVED BY THE ENGINEER / GEOTECHNICAL CONSULTANT.
- S8 CONTRACTOR IS TO ENSURE THAT ALL EXCAVATIONS ARE MAINTAINED IN A DRY CONDITION WITH NO WATER ALLOWED TO REMAIN IN THE EXCAVATIONS.
- S9 ALL FINISHES AND COLOURS TO BE IN ACCORDANCE WITH ARCHITECTURAL SPECIFICATIONS.
- S10 REFER TO STRUCTURAL DRAWINGS FOR CONCRETE, REINFORCEMENT AND RETAINING WALL DETAILS.
- S11 GENERALLY FOR TRENCHING WORKS THE CONTRACTOR MUST
 - A) COMPLY WITH THE GENERAL PROVISIONS OF PART 3.1 "MANAGING RISKS TO HEALTH AND SAFETY" OF NSW WORK AND HEALTH AND SAFETY REGULATION 2011
 - B) COMPLY PART 6 & DIVISION 3 "EXCAVATION WORK" OF NSW WORK HEALTH AND SAFETY REGULATION NSW 2011

BOUNDARY AND EASEMENT NOTE

The property boundary and easement locations shown on Taylor Thomson Whiting drawing's have been based from information received from : LTS

Taylor Thomson Whiting makes no guarantees that the boundary or easement information shown is correct. Taylor Thomson Whiting will accept no liabilities for boundary inaccuracies. The contractor/builder is advised to check/confirm all boundaries in relation to all proposed work prior to the commencement of construction. Boundary inaccuracies found are to be reported to the superintendent prior to construction starting.

CONCRETE FINISHING NOTES

1. All exposed concrete pavements are to be broomed finished.
2. All edges of the concrete pavement including keyed and dowelled joints are to be finished with an edging tool.
3. Concrete pavements with grades greater than 10 % shall be heavily broomed finished.
4. Carbondum to be added to all stair treads and ramped crossings U.N.O.

STORMWATER DRAINAGE NOTES

- 1 Stormwater Design Criteria :
- (A) Average exceedance probability -
 - 1% AEP for roof drainage to first external pit
 - 5% AEP for paved and landscaped areas
 - (B) Rainfall intensities
 - Time of concentration: 5 minutes
 - 1% AEP = 252 mm/hr
 - 5% AEP = 183 mm/hr
 - (C) Rainfall losses
 - Impervious areas: IL = 1.5 mm , CL = 0 mm/hr
 - Pervious areas: IL = 21mm , CL = 6.4 mm/hr
2. Pipes 300 dia and larger to be reinforced concrete Class " 2 " approved spigot and socket with rubber ring joints U.N.O.
3. Pipes up to 300 dia may be sewer grade uPVC with solvent welded joints, subject to approval by the engineer
4. Equivalent strength VCP or FRP pipes may be used subject to approval.
5. Precast pits may be used external to the building subject to approval by Engineer
6. Enlargers, connections and junctions to be manufactured fittings where pipes are less than 300 dia.
7. Where subsoil drains pass under floor slabs and vehicular pavements, unsolted UPVC sewer grade pipe is to be used.
8. Grates and covers shall conform with AS 3996-2006, and AS 1428.1 for access requirements.
9. Pits shall be installed in accordance with AS 3725. All bedding to be 100mm U.N.O.
10. Care is to be taken with invert levels of stormwater lines. Grades shown are not to be reduced without approval.
11. All stormwater pipes to be 150 dia at 1.0% min fall U.N.O.
12. Subsoil drains to be sloped flexible uPVC U.N.O.
13. Adopt invert levels for pipe installation (grades shown are only nominal).

EROSION AND SEDIMENT CONTROL NOTES

1. All work shall be generally carried out in accordance with
 (A) Local authority requirements,
 (B) EPA - Pollution control manual for urban stormwater,
 (C) LANDCOM NSW - Managing Urban Stormwater: Soils and Construction ("Blue Book").

2. Erosion and sediment control drawings and notes are provided for the whole of the works. Should the Contractor stage these works then the design may be required to be modified. Variation to these details may require approval by the relevant authorities.
3. Maintain all erosion and sediment control devices to the satisfaction of the superintendent and the local authority.
4. When stormwater pits are constructed prevent site runoff entering the pits unless silt fences are erected around pits.
5. Minimise the area of site being disturbed at any one time.
6. Protect all stockpiles of materials from scour and erosion. Do not stockpile loose material in roadways, near drainage pits or in watercourses.
7. All soil and water control measures are to be put back in place at the end of each working day, and modified to best suit site conditions.
8. Control water from upstream of the site such that it does not enter the disturbed site.
9. All construction vehicles shall enter and exit the site via the temporary construction entry/exit.
10. All vehicles leaving the site shall be cleaned and inspected before leaving.
11. Maintain all stormwater pipes and pits clear of debris and sediment. Inspect stormwater system and clean out after each storm event.
12. Clean out all erosion and sediment control devices after each storm event.

SEQUENCE OF WORKS

1. Prior to commencement of excavation the following soil management devices must be installed.
 - 1.1. Construct silt fences below the site and across all potential runoff sites.
 - 1.2. Construct temporary construction entry/exit and divert runoff to suitable control systems.
 - 1.3. Construct measures to divert upstream flows into existing stormwater system.
 - 1.4. Construct sedimentation traps/basin including outlet control and overflow.
 - 1.5. Construct turf lined swales.
 - 1.6. Provide sandbag sediment traps upstream of existing pits.
2. Construct geotextile filter pit surround around all proposed pits as they are constructed.
3. On completion of pavement provide sand bag kerb inlet sediment traps around pits.
4. Provide and maintain a strip of turf on both sides of all roads after the construction of kerbs.

SAFETY IN DESIGN

Contractor to refer to Appendix B of the Civil Specification for the Civil Risk and Solutions Register.

EXISTING SERVICES

Contractor to be aware existing services are located within the site. Location of all services to be verified by the Contractor prior to commencing works. Contractor to confirm with relevant authority regarding measures to be taken to ensure services are protected or procedures are in place to demolish and/or relocate.

EXISTING STRUCTURES

Contractor to be aware existing structures may exist within the site. To prevent damage to existing structures(s) and/or personnel, site works to be carried out as far as practicably possible from existing structures. Advice needs to be sought from Arborist and/or Landscape Architect on measures required to protect trees.

EXISTING TREES

Contractor to be aware existing trees exist within the site which need to be protected. To prevent damage to trees and/or personnel, site works to be carried out as far as practicably possible from existing trees. Advice needs to be sought from Arborist and/or Landscape Architect on measures required to protect trees.

GROUNDWATER

Contractor to be aware ground water levels are close to existing surface level. Temporary de-watering may be required during construction works.

EXCAVATIONS

Deep excavations due to stormwater drainage works is required. Contractor to ensure safe working procedures are in place for works. All excavations to be fenced off and batters adequately supported to approval of Geotechnical Engineer.

GROUND CONDITIONS

Contractor to be aware of the site geotechnical conditions. Refer to geotechnical report by (JKGeotechnics) for details.

HAZARDOUS MATERIALS

Existing asbestos products & contaminated material may be present on site. Contractor to ensure all hazardous materials are identified prior to commencing works. Safe working practices as per relevant authority to be adopted and appropriate PPE to be used when handling all hazardous materials. Refer to geotechnical/environmental report by (JKGeotechnics) for details.

CONFINED SPACES

Contractor to be aware of potential hazards due to working in confined spaces such as stormwater pits, trenches and/or tanks. Contractor to provide safe working methods and use appropriate PPE when entering confined spaces.

MANUAL HANDLING

Contractor to be aware manual handling may be required during construction. Contractor to take appropriate measures to ensure manual handling procedures and assessments are in place prior to commencing works.

WATER POLLUTION

Contractor to ensure appropriate measures are taken to prevent pollutants from construction works contaminating the surrounding environment.

SITE ACCESS/EGRESS

Contractor to be aware site works occur in close proximity to footpaths and roadways. Contractor to erect appropriate barriers and signage to protect site personnel and public.

VEHICLE MOVEMENT

Contractor to supply and comply with traffic management plan and provide adequate site traffic control including a certified traffic marshal to supervise vehicle movements where necessary.

CIVIL SAFETY IN DESIGN

Taylor Thomson Whiting (NSW) Pty Ltd operates under Safe Work Australia's Code of Conduct for the Safe Design of Structures.

These drawings shall be read in conjunction with the Taylor Thomson Whiting Transfer of Information Letter and Civil Risk and Solutions Register.

Under the Code of Conduct it is the Client's responsibility to provide a copy of the Civil Risk and Solutions Register to the Principal Contractor.

It is the Principal Contractor's responsibility to review the hazards and risks identified during the design process to ensure a safe workplace is maintained for the construction, maintenance and eventual demolition of the civil infrastructure.

SURVEY AND SERVICES INFORMATION SURVEY

Origin of levels : PM 67885 R.L. 6.96

Datum of levels : A.H.D. AUSTRALIAN HEIGHT DATUM

Coordinate system : MGA

Survey prepared by : LTS

Setout Points : CONTACT THE SURVEYOR

Taylor Thomson Whiting does not guarantee that the survey information shown on these drawings is accurate and will accept no liability for any inaccuracies in the survey information provided to us from any cause whatsoever.

UNDERGROUND SERVICES - WARNING

The locations of underground services shown on Taylor Thomson Whiting's drawings have been plotted from diagrams provided by service authorities. This information has been prepared solely for the authorities own use and may not necessarily be updated or accurate. The position of services as recorded by the authority at the time of installation may not reflect changes in the physical environment subsequent to installation.

Taylor Thomson Whiting does not guarantee that the services information shown on these drawings shows more than the presence or absence of services, and will accept no liability for inaccuracies in the services information shown from any cause whatsoever.

The Contractor must confirm the exact location and extent of services prior to construction and notify any conflict with the drawings immediately to the Engineer/Superintendent.

The contractor is to get approval from the relevant state survey department, to remove/adjust any survey mark. This includes but is not limited to: State Survey Marks (SSM), Permanent Marks (PM), cadastral reference marks or any other survey mark which is to be removed or adjusted in any way.

Taylor Thomson Whiting plans do not indicate the presence of any survey mark. The contractor is to undertake their own search.

SIGNS AND LINE MARKING NOTES

1. Pavement marking and sign posting to be in accordance with R.M.S. "Interim Guide to Signs and Markings".

2. Contractor is to provide guide posts, spaced in accordance with AS1742.2. They are to be located near all head walls and pipe outlets.

3. Raised pavement markers to be in accordance with AS1742.2

4. Where existing pavement marking conflicts with proposed, it is to be removed.

5. Lane widths do not include width of gutter.

6. Line marking plan does not define boundaries.

7. Erect temporary sign 'changed traffic conditions ahead' 120m ahead of new work in both directions.

8. Establish the location of existing utility services and locate new signs clear of these installations.

9. The sloped face of the SF median kerbs which adjoin through lanes, are to be painted white in lieu of an E3 edge line. The reflective pavement markers normally associated with an E3 edge line are to be located on the pavement adjacent to the SF kerb.

10. Bicycle pavement markings and sign posting to be in accordance with Austroads Standards.


11. The design of major directional sign posting to be prepared and assessed by the R.M.S.

SITEWORKS NOTES

1. All basecourse material to comply with RMS specification No 3051 and compacted to minimum 98% modified standard dry density in accordance with AS 1289 5.2.1.

2. All trench backfill material shall be compacted to the same density as the adjacent material.

3. All service trenches under vehicular pavements shall be backfilled with an approved select material and compacted to a minimum 98% standard maximum dry density in accordance with AS 1289 5.1.1



SCALE 1:1000 0 10 20 30 40 50 m

THIS DRAWING HAS BEEN PREPARED USING COLOUR

REF SUBMISSION NOT TO BE USED FOR CONSTRUCTION

Scale : A1 Drawn Authorised
1:1000 JH AH
Job No Drawing No Revision
221896 ERH-TTW-00-DR-CI-0530 E
Plot File Created: Aug 17, 2023 - 11:53am

Sheet Subject
SOIL REF SITE WORKS PLAN


Project

EUROBODALLA HOSPITAL

Engineer
TTW Structural Civil Traffic Façade
612 9439 7288 | Level 6, 73 Miller Street, North Sydney, NSW 2060

Client
Multiplex

Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date
E	RE-ISSUED FOR REVIEW	JH	JH	15.08.23										
D	RE-ISSUED FOR REVIEW	JH	JH	15.08.23										
C	RE-ISSUED FOR REVIEW	JH	JH	15.08.23										
B	RE-ISSUED FOR REVIEW	JH	JH	04.08.23										
A	ISSUED FOR REVIEW	JH	JH	21.07.23										



REF SUBMISSION NOT TO BE USED FOR CONSTRUCTION


Scale : A1 Drawn Authorised
1:1000 JH AH

Job No Drawing No Revision

221896 ERH-TTW-00-DR-CI-0530 H

Plot File Created: Sep 07, 2023 - 9:47am

SCALE 1:500



F	RE-ISSUED FOR REVIEW	JH	WW	05.09.23
E	RE-ISSUED FOR REVIEW	JH	JH	15.08.23
D	RE-ISSUED FOR REVIEW	JH	JH	15.08.23
C	RE-ISSUED FOR REVIEW	JH	JH	15.08.23
B	RE-ISSUED FOR REVIEW	JH	JH	04.08.23
A	ISSUED FOR REVIEW	JH	JH	21.07.23
Rev Description	Eng	Draft	Date	Rev Description
	Eng	Draft	Date	Rev Description
	Eng	Draft	Date	Rev Description
	Eng	Draft	Date	Rev Description



Client
Multiplex

Engineer

TTW
Structural Civil Traffic Façade
612 9439 7288 | Level 6, 73 Miller Street, North Sydney, NSW 2060

Project
EUROBODALLA HOSPITAL




Sheet Subject
SOIL REF SITE WORKS PLAN




NOM SIZE OUTLET PIPE	A	B	C	D	E	F
375 TO 525	600	1200	d + 150	d + 900	300	2000
600 TO 825	900	1600	d + 225	d + 1200	600	4000
900 TO 1200 * BOX CULVERTS	1250	2500	d + 300	d + 2500	900	6000

ENERGY DISSIPATER DETAIL
SCALE 1:20

HEADWALL DIMENSIONS													
CULVERT SIZE (P x Q)	A	B	C	D	E	F	G	H	J	K	N	W	L
1200 x 450	260	700	450	600	150	130	50	160	100	300	200	2300	1760



TYPICAL HEADWALL DETAIL
SCALE 1:20



SCALE 1:1000 0 10 20 30 40 50 m
AT ORIGINAL SIZE

THIS DRAWING HAS BEEN PREPARED USING COLOUR

SCOUR PROTECTION
SCALE 1:20

REF SUBMISSION
NOT TO BE USED FOR CONSTRUCTION

Client	Engineer	Project	Sheet Subject	Scale : A1 Drawn Authorised	
Multiplex	TTW Structural Civil Traffic Façade	EUROBODALLA HOSPITAL	SOIL REF SITE WORKS TYPICAL DETAILS SHEET 2	AS SHOWN JH AH	
A ISSUED FOR REVIEW JH JH 18.08.23	Rev Description Eng Draft Date	Rev Description Eng Draft Date	Job No 221896 ERH-TTW-00-DR-CI-0541 A	Drawing No Revision	
Rev Description Eng Draft Date	Rev Description Eng Draft Date	Rev Description Eng Draft Date	Plot File Created: Aug 17, 2023 - 11:52am		


Site area	Site				
	A	B	C	D	E
Total catchment area (ha)	1.12	1.79	0.28	0.78	1.48
Disturbed catchment area (ha)	0.84	1.343	0.21	0.585	1.11

Soil analysis					
% sand (fraction 0.02 to 2.00 mm)	60	60	60	60	60
% silt (fraction 0.002 to 0.02 mm)	5	5	5	5	5
% clay (fraction finer than 0.002 mm)	35	35	35	35	35
Dispersion percentage	50.0	50.0	50.0	50.0	50.0
% of whole soil dispersible	18.75	18.75	18.75	18.75	18.75
Soil Texture Group	D	D	D	D	D


Rainfall data					
Design rainfall depth (days)	5	5	5	5	5
Design rainfall depth (percentile)	85	85	85	85	85
x-day, y-percentile rainfall event	37.4	37.4	37.4	37.4	37.4

RUSLE Factors					
Rainfall erosivity (R-factor)	2500	2500	2500	2500	2500
Soil erodibility (K-factor)	0.02	0.02	0.02	0.02	0.02
Slope length (m)	70	70	70	70	70
Slope gradient (%)	9	6	9	3	5
Length/gradient (LS-factor)	2.22	1.36	2.22	0.61	1.1
Erosion control practice (P-factor)	1.3	1.3	1.3	1.3	1.3
Ground cover (C-factor)	1	1	1	1	1

Calculations					
Soil loss (t/ha/yr)	144	88	144	40	72
Soil Loss Class	1	1	1	1	1
Soil loss (m³/ha/yr)	111	68	111	31	55
Sediment basin storage volume, m³	16	16	4	3	10



TYPICAL ROAD SECTION 1
N.T.S.



TYPICAL ROAD SECTION 2
N.T.S.

NOTE
ENSURE THAT ALL UTILITY ASSETS ARE MAINTAINED AND PROTECTED AT ALL TIMES IN THE VICINITY OF THE TEMPORARY CONSTRUCTION EXIT

GEOTEXTILE FABRIC DESIGNED TO PREVENT INTERMINGLING OF SUBGRADE AND BASE MATERIALS AND TO MAINTAIN GOOD PROPERTIES OF THE SUB-BASE LAYERS. THE GEOTEXTILE MAY BE WOVEN OR NEEDLE PUNCHED PRODUCT WITH A MINIMUM CBR BURST STRENGTH (AS3706.4-90) OF 2500N.

CONSTRUCTION NOTES

- STRIP TOPSOIL AND LEVEL SITE.
- COMPACT SUBGRADE.
- COVER AREA WITH NEEDLE-PUNCHED GEOTEXTILE.
- CONSTRUCT 200mm THICK PAD OVER GEOTEXTILE USING 30mm SINGLE SIZE AGGREGATE.
- CONSTRUCT HUMP IMMEDIATELY WITHIN BOUNDARY TO DIVERT WATER TO A SEDIMENT FENCE OR OTHER SEDIMENT TRAP WHERE THE SEDIMENT IS COLLECTED AND REMOVED.


Maintenance Notes

THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH PREVENTS TRACKING OR FLOWING OF SEDIMENT OFF THE CONSTRUCTION SITE. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL GRAVEL AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED DROPPED, WASHED OR TRACKED OFF THE CONSTRUCTION SITE MUST BE REMOVED IMMEDIATELY.

TEMPORARY STABILISED CONSTRUCTION EXIT
N.T.S.


Peak flow calculations, 1						
Site	A (ha)	tc (mins)	Rainfall Intensity, I, mm hr⁻¹			
			1 yr,tc	5 yr,tc	10 yr,tc	20 yr,tc
A	1.12	8	58.6	98	117	138
B	1.79	10	58.6	98	117	138
C	0.28	5	58.6	98	117	138
D	0.78	7	58.6	98	117	138
E	1.48	9	58.6	98	117	138

Peak flow calculations, 2						
ARI (yrs)	Frequency factor (F_y)	Peak flows				
		A (m³/s)	B (m³/s)	C (m³/s)	D (m³/s)	Comment
1 yr,tc	0.8	0.131	0.210	0.033	0.091	0.174
5 yr,tc	0.95	0.261	0.417	0.065	0.182	0.345
10 yr,tc	1	0.328	0.524	0.082	0.228	0.433
20 yr,tc	1.05	0.406	0.649	0.102	0.283	0.537
50 yr,tc	1.15	0.541	0.865	0.135	0.377	0.715
100 yr,tc	1.2	0.646	1.032	0.161	0.450	0.853



SECTION STRAW BALE BUND
N.T.S.

STRAW BALE AND GEOTEXTILE SEDIMENT FILTER
N.T.S.



SECTION DETAIL




PLAN


CONSTRUCTION NOTES

- CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE.
- DRIVE 1.5M LONG STAR PICKETS INTO GROUND, 2.5 METRES APART (MAX). ENSURE STAR PICKETS ARE FITTED WITH SAFETY CAPS.
- DIG A 150MM DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
- BACKFILL TRENCH OVER BASE OF FABRIC.
- FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
- JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150MM OVERLAP.


SEDIMENT CONTROL FENCE
N.T.S.




ROCK CHECK DAM



(FOR CATCHMENT GREATER THAN 2ha)
DIVERSION SWALE WITH BANK AND CHANNEL
N.T.S.



PLAN VIEW



Construction Notes

1. REMOVE ANY VEGETATION AND TOPSOIL FROM UNDER THE DAM WALL AND FROM WITHIN THE STORAGE AREA.

2. CONSTRUCT A CUT-OFF TRENCH 200MM DEEP AND 200MM WIDE ALONG THE CENTRELINE OF THE EMBANKMENT EXTENDING TO A POINT ON THE GULY WALL LEVEL WITH THE RISER CREST.

3. MANTAIN THE TRENCH FREE OF WATER AND RECOMPACT THE MATERIALS WITH EQUIPMENT AS SPECIFIED IN THE SWMP TO 95 PER CENT STANDARD PROCTOR DENSITY.

4. SELECT FILL FOLLOWING THE SWMP THAT IS FREE OF ROOTS, WOOD, ROCK, LARGE STONE OR FOREIGN MATERIAL.

5. PROVIDE A 100MM THICK EARTH EMBANKMENT BY RIPPLING TO AT LEAST 100 MM TO HELP BOND COMPACTED FILL TO THE EXISTING SUBSTRATE.

6. SPREAD THE FILL IN 100 MM TO 150 MM LAYERS AND COMPACT IT AT OPTIMUM MOISTURE CONTENT.

7. CONSTRUCT THE EMERGENCY SPILLWAY.

8. REHABILITATE THE STRUCTURE FOLLOWING THE SWMP.

SEDIMENT BASIN
(APPLIES TO TYPE D' AND TYPE F SOILS ONLY)