

All dimensions to be verified on site and any discrepancies referred to architect for determination. figured dimensions to take precedence over scaled dimensions.

This design including its associated drawings, images, etc. is the intellectual property of stanton dahl & associates pty limited and must not be referenced copied or used without written permission of stanton dahl & associates pty limited.





Landscape Design Institute Stanton Dahl Architects

botanique design berry nsw 2535 p. 0404 887 620 adv. dip. interior design

cert III landscape construction





LAHC

Seniors living Development (x8 Units)

15-17 Combles Pde & 2-4 Hamel Matraville, NSW


Drawn; MM Checked; AT Plot date; 9/10/2023

Scale;1:100 as noted @ AI

LAHC Project No; Project No; **BGXPR**

Drawing No; Revision#;

Landscape Plan



Legend Legend (landscape plan)
note: drawing may not contain all items listed below

existing trees to be retained existing trees to be removed

proposed trees - install rootguard near services as

ensure that the mass planting areas have been excavated to 300mm below finished levels. rip to a further depth of 150mm. supply and install 300mm soil mix. soil mix to comprise of one part approved compost to three parts top soil. topsoil shall be either imported topsoil or the topsoil of the topsoil stockpiled site topsoil (if suitable ie. no clay). install 75mm of selected mulch. mulch to be non toxic shredded pine flakes (25 x 4 x 2mm)

fencing -for all fencing materials and types refer to the architects plans.

turf excavate/ grade areas to be turfed to 120mm below the required finished levels. do not excavate with 1500mm of any existing tree to be retained. ensure that all of the surface water runoff is to be directed towards the inlet pits, kerbs etc. ad away from buildings. ensure that no pooling or ponding will occur. rip subgrade to 150mm deep. install 100mm depth of imported topsoil. just prior to spreading turf, spread 'shirleys no. 17 lawn fertiliser' over the topsoil at the recommended rate. lay Sir Walter Buffalo turf rolls closely butted. fill any small gaps with topsoil. water thoroughly.

ex.contours & ex.RL00.00 → existing levels RL00.00 → proposed levels

– – brick garden edging

access panel balustrade (type) broom finished concrete brick on edge coloured concrete (type)

ceramic floor tile (type)

clothes line

column

cft(1)

downpipe drp doorpost existing fb(1) facebrick work (type) ft(1) fence (type) garbage bin grated drain hr(1) handrail (type) hose tap hot water unit hydrant

kerb ramp letter box off form concrete permeable paving power pole rw(1) retaining wall (type) rainwater outlet rainwater tank steel float concrete storm water pit trowel finished concrete tactile ground surface indicator Refer to L02 for Plant Schedule



botanique design botan que design







LAHC

Seniors living Development (x8 Units)

15-17 Combles Pde & 2-4 Hamel Matraville, NSW

Drawn; MM Checked; AT Plot date; 13/9/2023

L02

Scale;1:20, 1:10 as noted @ AI

LAHC Project No; Project No; 2701.21 **BGXPR**

Drawing No; Revision#;

Landscape Details




Garden Bed Preparation Detail


imported topsoil/

compost mix to 300mm

— 150mm deep cultivated



Brick Edge Section




Brick Edge Plan



common name


mature height pot size stake



plant schedule

code botanical name

Turf Preparation Detail



Note: it is the responsibility of the contractor to confirm the location of all underground services prior to commencement of any excavation or staking works. Strong central leading trunk to be evident at time of planting

> All trees supplied must meet the criteria of AS2303-2018: tree stock for landscape use & be healthy specimens free of pests and diseases. Trees to be well watered of a maximum of 24 hours prior to

Set 3 of 50x50x2400mm hardwood stakes vertically and clear of root ball and canopy at 900mm spacing, offset a min. 200mm from underground services to ensure no damage is caused to services. Stakes must be positioned so as to prevent damage to structural branches and prevent rubbing on branches.


50mm wide hessian ties of good quality wrapped around the trunk and nailed or stapled to the stake. Tree tie is to be positioned as high as possible, looped around the trunk and not the branches, and be loose, however still be tight enough to prevent excessive movement

Position tree in hole with the top of the rootball at the same height as the surrounding ground and backfill with 50/50 blend of site soil and imported organic topsoil. Imported organic topsoil must be as per AS:4419 2003: soils for landscape & gardens.
At the time of planting, if the roots are matted, slice the bottom 50mm off and apply the spade to the bottom in each quadrant.

Apply and spread mulch (as per AS4454-2012) to a depth of 150mm and 1200mm diameter from tree. No mulch is to be touching the tree.

Apply 500gms of gypsum to the planting site at a radius of a minimum 1200mm diameter from centre of hole. Apply 500gms of gypsum to inside of hole. Lightly compact soil at the base to prevent settling.

Excavate a planting hole with sloping sides 3 times the width of the rootball. Break up sides and base. If digging in soil of low permeability, the hole should be wider and deeper. In this instance backfill will be required at base of hole. Augers are not to be used for excavation of the planting hole. Planting hole is to be watered prior to planting. No tree is to be planted into naturally waterlogged soil. If soil is waterlogged, planting must be rescheduled to allow sufficient time for the soil to dry out.



Garden Bed Planting Detail

