

Modified ACTIVITY DETERMINATION – Determined by the New South Wales Land and Housing Corporation

Project No. BGYVZ

Conflict of Interest¹

In this matter:

- 1. I have declared any possible conflict of interests (real, potential or perceived) to the Head of Housing Portfolio, Homes NSW.
- 2. I do not consider I have any personal interests that would affect my professional judgement.
- 3. I will inform the Head of Housing Portfolio, Homes NSW as soon as I become aware of a possible conflict of interest.

Signed...

Dated.²¹ March 2025

Lisa Marigliano Executive Director, Portfolio Development Housing Portfolio Homes NSW

Having regard to the Determination Recommendation Report, the Statement of Compliance and the Review of Additional Environmental Factors for this project addressing matters under Part 5 of the *Environmental Planning and Assessment Act 1979*, I as a delegate of the New South Wales Land and Housing Corporation, determine that the activity proceed as described below and subject to the Identified Requirements set out in **Schedule 1**.

| SITE IDENTIFICATION | | | | | |
|--|--|--|--|--|--|
| STREET ADDRESS | | | | | |
| Unit/Street No | Street or property name | | | | |
| 2-10 & 20 | Birch Street & Debrincat Avenue | | | | |
| Suburb, town or locality North St Marys NSW | Postcode 2760 | | | | |
| Local Government Area(s) | Real property description (Lot and DP) | | | | |
| Penrith | Lots 346-350 in Deposited Plan 31990 and Lot 305 in Deposited Plan 30223 | | | | |

Conflict of interest includes actual and potential. A conflict of interest includes pecuniary i.e. financial interests to you or a related party or non-pecuniary i.e. benefits to relatives, friends, business associates and personal causes, etc. This includes "close relative of a person" as defined in section 49(6) of the Property and Stock Agents Act 2002.

ACTIVITY DESCRIPTION

Provide a description of the activity

Demolition of existing dwellings and structures, removal of trees, boundary adjustment with 20 Debrincat Avenue, and the construction of 22 independent living seniors housing units comprising 10 x 1 bedroom and 12 x 2 bedroom units, with associated landscaping and fencing, surface parking for 10 cars, creation of a stormwater easement across 20 Debrincat Avenue and consolidation into a single lot.

Mosah Signed....

Dated.21 March 2025

Lisa Marigliano Executive Director, Portfolio Development Housing Portfolio Homes NSW

SCHEDULE 1

IDENTIFIED REQUIREMENTS

PART A – Standard Identified Requirements

THE DEVELOPMENT

The following Identified Requirements are to ensure that the residential activity is carried out in accordance with the plans / documents and any amendments arising from the Review of Environmental Factors under Part 5 of the Environmental Planning & Assessment Act 1979, Section 171 of the Environmental Planning and Assessment Regulation 2021 and the requirements of State Environmental Planning Policy (Housing) 2021.

1. The development shall be carried out substantially in accordance with the following plans / documents as modified below and by any of the undermentioned identified requirements:

| Title / Name: | Drawing No / | Revision | Date | Prepared by: |
|----------------------|--------------|----------|---------------|----------------|
| | Document Ref | / Issue: | [dd.mm.yyyy]: | |
| Architectural | | | | |
| Cover Page | 1 of 22 | D | 4.12.2024 | DTA Architects |
| Block Analysis Plan | 2 of 22 | С | 26.10.2023 | DTA Architects |
| Site Analysis Plan | 3 of 22 | С | 26.10.2023 | DTA Architects |
| Demolition Plan | 4 of 22 | С | 26.10.2023 | DTA Architects |
| Subdivision Plan | 5 of 22 | С | 26.10.2023 | DTA Architects |
| Development Data | 6 of 22 | D | 27.11.2024 | DTA Architects |
| Site Plan | 7 of 22 | D | 27.11.2024 | DTA Architects |
| Ground Floor Plan | 8 of 22 | D | 27.11.2024 | DTA Architects |
| First Floor Plan | 9 of 22 | С | 26.10.2023 | DTA Architects |
| Roof Plan | 10 of 22 | С | 26.10.2023 | DTA Architects |
| Elevations | 11 of 22 | D | 27.11.2024 | DTA Architects |
| Elevation & Internal | 12 of 22 | D | 27.11.2024 | DTA Architects |
| Elevations | | | | |
| Internal Elevations | 13 of 22 | D | 27.11.2024 | DTA Architects |
| Sections | 14 of 22 | D | 27.11.2024 | DTA Architects |
| Sections | 15 of 22 | D | 27.11.2024 | DTA Architects |

| Title / Name: | Drawing No / Document Ref | Revision / Issue: | Date [dd.mm.yyyy]: | Prepared by: |
|---------------------------------------|------------------------------|----------------------|-----------------------|--------------------------|
| Shadow Diagrams – 21st June 9am | 16 of 22 | С | 26.10.2023 | DTA Architects |
| Shadow Diagrams – 21st June 12pm | 17 of 22 | С | 26.10.2023 | DTA Architects |
| Shadow Diagrams – 21st June 3pm | 18 of 22 | С | 26.10.2023 | DTA Architects |
| Solar Access – View From Sun | 19 of 22 | С | 26.10.2023 | DTA Architects |
| Solar Access – View From Sun | 20 of 22 | С | 26.10.2023 | DTA Architects |
| Solar Access – View From Sun | 21 of 22 | С | 26.10.2023 | DTA Architects |
| Perspectives | 22 of 22 | D | 27.11.2024 | DTA Architects |
| Civil/ Stormwater | | | | |
| Specification Sheet | 1 of 8 | F | 27.11.2024 | MSL Consulting Engineers |
| Site Drainage Plan | 2 of 8 | F | 27.11.2024 | MSL Consulting Engineers |
| Drainage Plan – Sheet 1 | 3 of 8 | F | 27.11.2024 | MSL Consulting Engineers |
| Drainage Plan – Sheet 2 | 4 of 8 | F | 27.11.2024 | MSL Consulting Engineers |
| OSD Section and Stormwater Details | 5 of 8 | F | 27.11.2024 | MSL Consulting Engineers |
| Stormwater Details | 6 of 8 | F | 27.11.2024 | MSL Consulting Engineers |
| Sediment Control Plan | 7 of 8 | F | 27.11.2024 | MSL Consulting Engineers |
| OSD Catchment Plan | 8 of 8 | F | 27.11.2024 | MSL Consulting Engineers |
| Landscape | | | | |
| Landscape Plan | 1 of 1 | E | 27.11.2024 | DTA Architects |
| Survey | | • | • | |
| Detail & Survey Level | 1 of 10 | A | 31.03.2023 | Norton Survey Partners |
| Detail & Survey Level | 2 of 10 | - | - | Norton Survey Partners |
| Detail & Survey Level | 3 of 10 | - | - | Norton Survey Partners |
| Detail & Survey Level | 4 of 10 | - | - | Norton Survey Partners |
| Detail & Survey Level | 5 of 10 | - | - | Norton Survey Partners |
| Detail & Survey Level | 6 of 10 | - | - | Norton Survey Partners |
| Detail & Survey Level | 7 of 10 | - | - | Norton Survey Partners |
| Detail & Survey Level | 8 of 10 | - | - | Norton Survey Partners |
| Detail & Survey Level | 9 of 10 | - | - | Norton Survey Partners |
| Detail & Survey Level | 10 of 10 | - | - | Norton Survey Partners |
| Footpath Survey and | Upgrades | | | • |
| Footpath Layout Plan | 1 of 4 | В | 29.11.2023 | MSL Consulting Engineers |
| Footpath Standard Details | 2 of 4 | В | 29.11.2023 | MSL Consulting Engineers |
| Footpath Long section – 1 | 3 of 4 | В | 29.11.2023 | MSL Consulting Engineers |

| Title / Name: | Drawing No / Document Ref | Revision / Issue: | Date [dd.mm.yyyy]: | Prepared by: |
|--|---|----------------------|-----------------------|---------------------------------|
| Footpath Long section – 2 | 4 of 4 | В | 29.11.2023 | MSL Consulting Engineers |
| BASIX | • | • | | |
| BASIX Certificate | BASIX Certificate No 1376255M_06 | - | 28.10.2024 | Greenview Consulting Pty Ltd |
| Nationwide house energy rating scheme – class 2 summary | NatHERS Certificate No 0008706870 | - | 25.10.2024 | Greenview Consulting Pty Ltd |
| Reports | | | | |
| Access Report | 22088-DA | R1.2 | 23.05.2023 | Access-i |
| Arborist's Impact Assessment and Tree Management Plan | 7800.1 | - | 30.11.2023 | Redgum Horticultural |
| Statutory Compliance Report | J4409 | FINAL | 22.05.2023 | DPC |
| Geotechnical Investigation | 22/1495 | - | May 2022 | STS Geotechnics Pty Ltd |
| Waste Management Plan | - | - | - | Land and Housing Corporation |
| Traffic Impact Assessment – Seniors Housing | - | 3 | 18.05.2023 | ParkTransit Pty Ltd |
| Cut and Fill Plan | 1 of 1 | В | 19.06.2023 | MSL Consulting Engineers |

(Modified Identified Requirement)

- **2.** All building work is to be undertaken in accordance with the National Construction Code and referenced Australian Standards.
- **3.** All commitments listed in the BASIX certificate and stamped plans shall be implemented.
- **4.** All construction documentation and building work is to be certified in accordance with Section 6.28 of the Environmental Planning and Assessment Act 1979.
- **5.** The land the subject of this determination shall be consolidated into a single lot. The plan of consolidation shall be lodged at the NSW Land Registry Services and shall be registered prior to the occupation of the development. A copy of the registered plan shall be provided to the Land & Housing Corporation.

It is noted that the boundary adjustment between Lot 350 DP31990 and Lot 305 DP30223 (affecting the rear portion of 20 Debrincat Avenue, North St Marys) is to be registered prior to the commencement of building works for the seniors housing development, as detailed in Identified Requirement 79 below.

OPERATIONAL MATTERS

The following Identified Requirements relate to the use of the site and are to ensure that the activity and its operation do not interfere with the amenity of the surrounding area.

Stormwater Run-off

- 6. Stormwater shall be collected within the site and conveyed in a pipeline to the appropriate gutter or drain under the control of Penrith City Council substantially in accordance with the approved concept stormwater drainage plans.
- 7. Alterations to the natural surface contours or surface absorption characteristics of the site shall not impede, increase, or divert natural surface water runoff so as to cause a nuisance to adjoining property owners.
- 8. All driveways shall be graded in such a manner as to provide continuous surface drainage flow paths to the appropriate points of discharge.
- **9.** To prevent water from entering buildings, surface waters shall be collected and diverted clear of the buildings by a sub-surface / surface drainage system.

Vehicular Access and Parking

- 10. Concrete vehicular crossings and laybacks shall be provided at the entrances / exits to the property. The crossings and laybacks shall be constructed in accordance with Penrith City Council's standard requirements for residential crossings. Council shall be provided with plans for the crossings and laybacks together with the payment of any council inspection fees.
- 11. Particular care shall be taken in the location of vehicular crossings and/or laybacks to avoid poles, pits etc. The cost of any necessary adjustments to utility mains and services associated with the construction of the layback / driveway shall be borne by the Land & Housing Corporation. Obsolete gutter laybacks shall be constructed as kerb in accordance with Penrith City Council's standards.

Note:

It is recommended that discussion be held with the relevant authorities before construction works commence.

12. Car parking spaces and driveways shall be constructed of concrete or other approved hard surfaced materials. The spaces must be clear of obstructions and columns, permanently line marked and provided with adequate manoeuvring facilities. The design of these spaces must comply with AS 2890.1.

Site Works

- **13.** All soil erosion and sediment control measures required to be put in place prior to the commencement of demolition / construction works shall be maintained during the entire period of the works until all the disturbed areas are restored by turfing, paving or revegetation. Soil erosion and sediment control measures shall be designed in accordance with the guidelines set-out in the Blue Book *Managing Urban Stormwater: Soils and Construction* (4th edition, Landcom, 2004).
- 14. An appropriately qualified person shall design retaining walls or other methods necessary to prevent the movement of excavated or filled ground, including associated stormwater drainage measures.

Building Siting

15. All buildings shall be sited well clear of any easements affecting the site. The builder shall ascertain if any easements do exist and, if they do, obtain full details of such prior to construction commencing.

Smoke Detection System(s)

- **16.** Smoke detection systems shall be installed throughout the building(s) in accordance with requirements of Clause E2.2a of the Building Code of Australia. Detectors and alarms shall comply with AS 3786 and AS 1670 and must:
 - i. be connected to a permanent 240V power supply; and
 - ii. be provided with a battery backup to activate the alarm unit in the event of failure of the permanent power supply.

Site Soil Contamination

17. If the site is identified as being potentially affected by soil contamination, it shall be inspected by a suitably qualified person to identify any contaminated or hazardous material present. A proposal for remediation shall be prepared, which may include preparation of a Remedial Action Plan, and remediation shall be carried out in accordance with the proposal. A Validation Report, prepared in accordance with Environment Protection Authority requirements, shall be obtained from a qualified expert on completion of the remediation work to verify that the site is suitable for the intended residential use. A copy of the Validation Report shall be provided to the Land & Housing Corporation on completion of the remediation works.

Landscaping

- **18.** Landscaping shall be carried out substantially in accordance with the approved Landscape Plan and maintained for a period of 12 months by the building contractor. Penrith City Council shall be consulted in relation to the planting of any street trees.
- **19.** All scheduled plant stock shall be pre-ordered, prior to commencement of construction or 3 months prior to the commencement of landscape construction works, whichever occurs sooner, for the supply to the site on time for installation. The builder shall provide written confirmation of the order to the Land & Housing Corporation.

Tree Removal

20. Removal of trees within the boundaries of the site is to be carried out in accordance with the trees shown for removal on the approved Landscape Plan and Arboricultural Impact Assessment and Tree Management Plan and no other trees shall be removed without further approval(s).

Fencing

21. All front fencing and gates shall be constructed wholly within the boundaries of the site. Any gates associated with the fencing shall swing inwards towards the site.

Provision of Letterbox Facilities

22. Suitable letterbox facilities are to be provided in accordance with Australia Post specifications.

Public Liability Insurance

23. A valid public liability insurance policy of at least \$10M shall be maintained throughout the demolition / construction works by the contractor.

PRIOR TO ANY WORK COMMENCING ON THE SITE

The following Identified Requirements are to be complied with prior to any work commencing on the site, including demolition.

Disconnection of Services

- **24.** All services that are required to be disconnected shall be appropriately disconnected and made safe prior to commencement of the demolition / construction works. The various service authorities shall be consulted regarding their requirements for the disconnection of services.
- **25.** All existing services within the boundary to remain live shall be identified, pegged and made safe.

Demolition

- 26. The builder shall notify the occupants of premises on either side, opposite and at the rear of the site a minimum of 5 working days prior to demolition. Such notification shall be clearly written on an A4 size paper giving the date demolition will commence and be placed in the letterbox of every premise (including every unit in a multi-unit residential building or mixed use building). The demolition shall not commence prior to the date that is stated in the notice letter.
- 27. Prior to the demolition, a Work Plan shall be prepared by a competent person(s) in accordance with AS 2601 and shall be submitted to the Land & Housing Corporation. The Work Plan shall outline the identification of any hazardous materials (including surfaces coated with lead paint), method of demolition, the precautions to be employed to minimise any dust nuisance and the disposal methods for hazardous materials.
- 28. If buildings to be demolished are determined as, or suspected of, containing asbestos cement, a standard commercially manufactured sign containing the words 'DANGER ASBESTOS REMOVAL IN PROGRESS', and measuring not less than 400mm x 300mm, shall be erected in a prominent visible position on the site for the duration of the demolition works.

Note:

Any buildings constructed before 1987 is assumed to contain asbestos.

Utilities Service Provider Notification

29. The demolition / construction plans shall be submitted to the appropriate water utility's office (e.g. Sydney Water office) to determine whether or not the development will affect the utility's sewer and water mains, stormwater drains and any easements.

Note:

If the development complies with water utility's requirements, the plans will be stamped indicating that no further requirements are necessary.

Council Notification

30. Penrith City Council shall be advised in writing, of the date it is intended to commence work, including demolition. A minimum period of **5** working days notification shall be given.

Site Safety

- **31.** A sign shall be erected in a prominent position on any site on which demolition or building work is being carried out:
 - (a) showing the name, address and telephone number of the responsible Land & Housing Corporation officer for the work, and
 - (b) showing the name of the principal contractor (if any) and a telephone number on which that person may be contacted outside working hours, and
 - (c) stating that unauthorised entry to the work site is prohibited.

The sign shall be maintained while the work is being carried out but shall be removed when the work has been completed.

Note:

This requirement does not apply in relation to building work that is carried out inside an existing building that does not affect the external walls of the building.

32. A minimum 1.8m high security fence or Class A / Class B (overhead) hoarding must be erected between the work site and any public place prior to demolition / construction. Access to the site shall be restricted to authorised persons only and the site shall be secured against unauthorised entry when demolition / construction work is not in progress or the site is otherwise unoccupied.

Note:

Approval from the relevant roads authority will be required under Section 138 of the Roads Act 1993 where a Class A or B hoarding encroaches onto the footpath of / or a public thoroughfare within a classified road.

33. No building or demolition materials are to be stored on the footpath or roadway.

Site Facilities

- **34.** The following facilities shall be installed on the site:
 - (a) Toilet facilities shall be provided at the rate of 1 toilet for every 20 persons or part thereof employed at the site. Each toilet provided shall be a standard flushing toilet and shall be connected to a public sewer or if connection to a public sewer is not practicable, to an accredited sewerage management facility provided by Penrith City Council or if this is not practicable to some other council approved management facility.
 - (b) Adequate refuse disposal methods and builders storage facilities. Builders' wastes, materials or sheds shall not to be placed on any property other than that which this approval relates to.

35. Access to the site shall only be provided via an all-weather driveway on the property and is not to be provided from any other site.

Protection of Trees

36. Trees and other vegetation that are to be retained on site shall be protected prior to the commencement of works and for the duration of the construction period in accordance with the details provided in the Arboricultural Impact Assessment and Tree Management Plan.

Waste Management

37. A final Waste Management Plan shall be prepared and submitted to the Land & Housing Corporation by the building contractor prior to the commencement of demolition / construction. The plan shall detail the amount of waste material and the destination of all materials, recyclable and non-recyclable.

PRIOR TO ANY CONSTRUCTION WORK COMMENCING ON SITE

The following Identified Requirements are to be complied with prior to any construction works occurring on the site, excluding demolition.

Service Authority Clearances

38. A compliance certificate, or other evidence, shall be obtained from the relevant water utility provider (e.g. Sydney Water), confirming service availability prior to work commencing.

Note:

Payment of water and/or sewer service charges and/or a notice of requirements for works to be carried out during construction/prior to occupation may be applicable prior to issue of the compliance certificate.

- **39.** A written clearance from an electricity supply authority stating that electrical services are available to the site, or that arrangements have been entered into for the provision of services to the site, shall be obtained prior to work commencing.
- **40.** A certificate from an approved telecommunications carrier certifying that satisfactory arrangements have been made for the provision of underground telephone services, to the site and to each dwelling, shall be obtained prior to work commencing.
- **41.** Where the site is to be connected to reticulated gas, a certificate from an approved gas carrier to certify that satisfactory arrangements have been made to ensure the provision of underground gas services to each dwelling in the development shall be obtained prior to work commencing.

Stormwater Disposal

42. A detailed stormwater drainage plan(s), substantially in accordance with the approved concept stormwater drainage plan(s), shall be prepared and submitted to the Land & Housing Corporation. Any on-site detention system shall be designed in accordance with the relevant catchment authority's requirements (e.g. the Upper Parramatta River Catchment Trust On-site Detention Handbook) and/or Penrith City Council's drainage code.

43. A drainage easement is required, proof of lodgement of the plan of the drainage easement at the NSW Land Registry Services shall be submitted to the Land & Housing Corporation prior to commencement of works. Registration of the plan of easement shall be completed prior to occupation of the development and a copy of the registered plan shall be provided to the Land & Housing Corporation.

DURING DEMOLITION AND CONSTRUCTION WORKS

The following Identified Requirements are to be complied with whilst demolition and construction works are occurring on the site.

Landfill

- **44.** Where site filling is necessary, a minimum of 95% standard compacting shall be achieved and certified by a NATA registered Soils Lab.
- **45.** Land fill materials must satisfy the following requirements:
 - i. be Virgin Excavated Natural Matter (VENM);
 - ii. be free of slag, hazardous, contaminated, putrescible, toxic or radio-active matter; and
 - iii. be free of industrial waste and building debris.

Heritage

- **46.** Historic and indigenous archaeological sites and relics are protected under the *Heritage Act 1977* and *National Parks and Wildlife Act 1974,* respectively. Should any relics be uncovered during the course of the approved works, work must cease immediately in the affected area. Subsequently, in cases where historical or indigenous items have been uncovered, the Department of Planning and Environment must be contacted.
- **47.** All workers / contractors on the site shall be informed of their obligations, under the Heritage Act and *National Parks and Wildlife Act 1974,* that it is illegal to disturb, damage or destroy a relic without the prior approval of the Department of Planning and Environment.

Demolition

- **48.** Any existing structures identified for demolition shall be demolished prior to commencement of the construction of the activity.
- **49.** Demolition shall be carried out in accordance with the appropriate provisions of AS 2601.
- **50.** Where materials containing asbestos are to be removed, demolition shall be carried out by a licensed contractor(s) who have current SafeWork NSW accreditation in asbestos removal.
- **51.** Removal of asbestos-based thermal or acoustic insulation, such as sprayed asbestos and asbestos-based lagging, including friable asbestos boards, shall be carried out in accordance with the National Occupational Health and Safety Commission's Code of Practice for the Safe Removal of Asbestos, 2nd Edition [NOHSC:2002 (2005)].

- **52.** Hazardous or intractable wastes, including all asbestos laden waste, arising from the demolition process shall be removed and disposed of in accordance with the requirements of SafeWork NSW and the Department of Planning and Environment.
- **53.** Documentary evidence, in the form of tip receipts from an approved Waste Management Facility, shall be obtained by the demolition contractor and submitted to the Land & Housing Corporation demonstrating the appropriate disposal of the asbestos waste.
- **54.** Demolition procedures shall maximise the reuse and recycling of demolished materials in order to reduce the environmental impacts of waste disposal.
- **55.** During demolition, the public footpath and the public road shall not be obstructed by any vehicles. The public road and footpath shall be swept (not hosed) clean of any material, including clay, soil and sand.
- **56.** All vehicles leaving the site with demolition materials shall have their loads covered and vehicles shall not track soil and other material onto the public roads and footpaths. The footpath shall be suitably protected against damage when plant and vehicles access the site. All loading of vehicles with demolished materials shall occur on site.

Survey Reports

57. Survey reports shall be submitted by the building contractor to the Land & Housing Corporation prior to the placement of the footings / slab and on completion of the dwellings to verify the correct position of the structures in relation to the allotment boundaries.

Hours of Demolition / Construction / Civil Work

58. Demolition / construction / Demolition / construction / civil work shall only occur on the site between the hours of 7.00am to 5.00pm Monday to Saturday with no work permitted on Sundays or public holidays.

Excavation and Backfilling

59. All excavations and backfilling associated with the demolition or erection of building(s) shall be executed safely and in accordance with appropriate professional standards. All such work shall be guarded and protected to prevent it from being dangerous to life or property.

Pollution Control

- **60.** Any noise generated during the construction of the development shall not exceed the limits specified in the July 2009 Interim Construction Noise Guidelines, published by the former Department of Environment and Climate Change.
- 61. No fires shall be lit or waste materials burnt on the site.
- 62. No washing of concrete forms or trucks shall occur on the site.
- **63.** Any contamination / spills on the site during construction works shall be actively managed and reported immediately to appropriate regulatory authorities to minimise any potential damage to the environment.

- **64.** Dust generation during demolition / construction shall be controlled using regular control measures such as on site watering or damp cloth fences.
- **65.** All vehicles transporting loose materials and travelling on public roads shall be secured (ie closed tail gate and covered) to minimise dust generation.
- **66.** Non-recyclable waste and containers shall be regularly collected and disposed of at a licensed landfill or other disposal site in accordance with details set out in the final Waste Management Plan.

Impact of Construction Works

- **67.** The Land & Housing Corporation shall bear the cost of any necessary adjustments to utility mains and services.
- **68.** Care shall be taken to prevent any damage to adjoining properties. The building contractor shall be liable to pay compensation to any adjoining owner if, due to demolition/construction works, damage is caused to such adjoining property.

Termite Protection

69. To protect buildings from subterranean termite, termite barriers installed in accordance with AS 3660.1, shall be placed on the underside and in penetrations of the concrete slab floor.

In addition, a durable notice must be permanently fixed inside the meter box indicating:

- (a) the method of protection,
- (b) the date of installation of the system,
- (c) where a chemical barrier is used, its life expectancy as listed on the National Registration Authority label and
- (d) the need to maintain and inspect the system on a regular basis.

PRIOR TO OCCUPATION OF THE DEVELOPMENT

The following Identified Requirements are to be complied with prior to the occupation of the development.

General

70. The use or occupation of the development shall not commence until all the Identified Requirements of this determination have been complied with.

Council Infrastructure Damage

71. The cost of repairing any damage caused to Penrith City Council's assets in the vicinity of the site as a result of demolition / construction works shall be met in full by the building contractor.

Stormwater Drainage

- 72. Prior to occupation, a Work As Executed Plan shall be prepared by the building contractor clearly showing all aspects of the constructed stormwater drainage system, including any on-site detention system. The plan shall demonstrate general compliance with the approved concept stormwater drainage plan(s) and shall include:
 - sufficient levels and dimensions to verify the constructed storage volumes; and
 - location and surface levels of all pits; and
 - invert levels of the internal drainage lines, orifice plates fitted and levels within the outlet control pits; and
 - finished floor levels of all structures; and
 - verification that any required trash screens have been installed; and
 - locations and levels of any overland flow paths; and
 - verification that any drainage lines are located wholly within easements, where applicable.

The Work-As-Executed Plan information shall be shown on the final civil works drawings.

A positive covenant and restriction-as-to-user shall be placed over the onsite detention system in accordance with Penrith City Council's on-site detention policy to ensure that the system will be adequately maintained. The positive covenant and restriction-as-to-user shall be registered at NSW Land Registry Services prior to occupation. A copy of the registered restriction-as-to-user shall be provided to the Land & Housing Corporation and Penrith City Council.

PART B – Additional Identified Requirements

Specific Requirements for Seniors Housing

73. The independent living units shall comply with the accessibility and useability standards referenced in section 85 and set out in Schedule 4 of *State Environmental Planning Policy (Housing) 2021.*

Note:

This requirement does not apply to the provisions set out under sections 2, 7-13 and 15-20 of Schedule 4 for an independent living unit, or part of such a unit, that is located above the ground floor.

- **74.** Only the following kinds of people shall be accommodated in the approved development:
 - (a) seniors or people who have a disability; or
 - (b) people who live within the same household with seniors or people who have a disability; or
 - (c) staff employed to assist in the administration and provision of services to the seniors housing development.

Note:

It should be noted that 'seniors', as defined in the Housing SEPP, are any of the following:

- (a) people aged 60 or more years,
- (b) people who are resident at a facility at which residential care (within the meaning of the Aged Care Act 1997 of the Commonwealth) is provided, and

(c) people who have been assessed as being eligible to occupy housing for aged persons provided by a social housing provider.

A restriction as to user shall be registered against the title of the property, prior to occupation, in accordance with Section 88E of the Conveyancing Act 1919 limiting the use of any accommodation to the kinds of people referred to above and that the dwellings cannot be subdivided.

- **75.** Pathway lighting shall be designed to provide a minimum of 20 lux at ground level and be located to avoid glare for pedestrians and adjacent dwellings.
- **76.** Access to, and within, the site shall be provided in accordance with AS 1428.1 so that a person using a wheelchair can use common areas and common facilities associated with the activity.
- 77. A 1.2m wide concrete footpath across the site frontage, connecting to the existing footpath system in Debrincat Avenue shall be constructed in accordance with the Penrith City Council specifications to provide an accessible pathway from the site to the bus stops ID 276024 (Debrincat Ave after Birch St) and ID276017 (North St Mary's neighbourhood centre, Debrincat Ave). The footpath upgrades must be designed and constructed to satisfy the access and gradient requirements under clause 93(4) in the *State Environmental Planning Policy (Housing) 2021*.

Note:

The responsible officer at the Penrith City Council shall be contacted regarding council's specifications and any necessary approvals. Should the footpath upgrade works conflict with existing service utility pits, and adjustments are required to these pits, the builder is to contact the relevant authorities for concurrence on the proposed works to the utility pits.

78. Entry doors to units shall be provided with door viewers to enable residents to view approaches to their units without the need to open the door.

Site Specific Requirements

79. The plan of subdivision to facilitate the boundary adjustment between Lot 350 DP31990 and Lot 305 DP30223 shall be lodged at the NSW Land Registry Services and shall be registered prior to commencement of construction. A copy of the registered plan shall be provided to the Land & Housing Corporation.

Requirements Resulting from Council Comments

- **80.** The existing sewer line must be inspected prior to the construction of the stormwater infrastructure and associated easement to ensure the stormwater pipeline does not impact on the integrity of the sewer main.
- 81. The detailed construction documentation for stormwater management must be amended to incorporate an additional junction pit at the new property boundary within 20 Debrincat Avenue, as well as at the end of the drainage easement prior to the connection to the Council drainage system on Debrincat Avenue.
- 82. The existing bus shelters at bus stop ID 276024 and ID 276017) at Debrincat Avenue must be upgraded, where required, to comply with the relevant accessibility standard prior to occupation.
- **83.** LAHC is to consult with Penrith City Council regarding the utilisation of Council's Waste Collection Service and enter into necessary agreements.

Modification Requirements

84. Air Conditioning

Design and Installation

Any air conditioning unit installed on the premises must be designed, specified and installed to ensure that they comply with the requirements of the Protection of the Environment Operations (Noise Control) Regulations 2017 and must not emit a noise that exceeds 5dB(A) above the ambient background noise level measured at any property boundary. Acoustic treatment may be required to ensure this is achieved.

Certification, from an appropriately qualified acoustic consultant, shall be provided at construction documentation stage that the air conditioning units can comply with this requirement.

Further certification, from an appropriately qualified acoustic consultant, shall be provided prior to occupation that the installed air conditioning units comply with this requirement.

<u>On-Going</u>

The use of any air-conditioning unit must comply with the requirements of the Protection of the Environment Operations (Noise Control) Regulations 2017 and must not:

- (a) emit a noise that is audible within a habitable room in any adjoining residence (regardless of whether any door or window to that room is open);
 (i) before 8.00 am and after 10.00 pm on any Saturday, Sunday or Public Holiday; or
 (ii) before 7.00 am or after 10.00 pm on any other day;
- (b) emit a noise that exceeds 5dB(A) above the ambient background noise level measured at any property boundary.

(Additional Identified Requirement)

ADVISORY NOTES

- i. Approval of this development activity does not imply or infer compliance with Section 23 of the *Disability Discrimination Act 1992*. Refer to AS 1428.1 and the Building Code of Australia for detailed guidance.
- ii. Information regarding the location of underground services may be obtained from Dial Before You Dig at <u>www.1100.com.au</u> or by dialing 1100.



DECISION STATEMENT NSW Land and Housing Corporation

Project No. BGYVZ

| SITE IDENTIFICATION | | | | | | |
|--------------------------|---|--------------------------|--|--|--|--|
| STREET ADDRESS | | | | | | |
| Unit/Street No | Street or property name | | | | | |
| 2-10 & 20 | Birch Street & Debrincat Avenue | | | | | |
| Suburb, town or locality | | Postcode | | | | |
| North St Marys NSW | | 2760 | | | | |
| Local Government Area(s) | Real property description (Lo | ot and DP) | | | | |
| Penrith | Lots 346-350 in Deposited P Deposited Plan 30223 | lan 31990 and Lot 305 in | | | | |
| ACTIVITY DESCRIPTION | | | | | | |

Provide a description of the activity

Demolition of existing dwellings and structures, removal of trees, boundary adjustment with 20 Debrincat Avenue, and the construction of 22 independent living seniors housing units comprising 10 x 1 bedroom and 12 x 2 bedroom units, with associated landscaping and fencing, surface parking for 10 cars, creation of a stormwater easement across 20 Debrincat Avenue and consolidation into a single lot.

NSW Land & Housing Corporation has proposed to modify the above activity under the provisions of *State Environmental Planning Policy (Housing) 2021* (Housing SEPP) which has previously been determined under Part 5 of the *Environmental Planning & Assessment Act 1979* (EP&A Act). This Decision Statement relates to the Review of Additional Environmental Factors for the above modified activity prepared under Part 5 of the EP&A Act and the *Environmental Planning and Assessment Regulation 2021*.

Based on the Review of Environmental Factors document and supporting documentation, a decision to proceed with the modified activity has been made. This decision included consideration of the following:

Significant Impact on the Environment

- The modified activity is not likely to have a significant impact on the environment and therefore an EIS is not required.
- The activity was not proposed to be carried out in a declared area of outstanding biodiversity value and is therefore not likely to significantly affect threatened species, populations or ecological communities, or their habitats or impact biodiversity values, meaning a SIS and/or BDAR is not required. The proposed modified activity does not alter this situation.

Reasons for the Decision

- Following an assessment of the modified activity and associated environmental impacts within the Review of Additional Environmental Factors document it was decided that the modified development will have economic and social benefits and any minor short-term impacts on the environment or surrounding properties can be appropriately mitigated.
- The modified development will assist in the provision of much-needed social and affordable housing and assist in addressing the existing and growing demand for housing in the local government area.

Mitigation Measures

- Mitigation measures were required to minimise or manage environmental impacts and are detailed throughout the original REF. All mitigation measures are detailed as Identified Requirements within the Activity Determination. Changes to the Identified Requirements because of this Review of Additional Environmental Factors will include the following:
 - Amend Identified Requirement No.1 to reference all the updated version of plans and specialist reports which reflect the proposed modifications; and
 - Add one Identified Requirement No. 84 relating to the air conditioning units.

Signed.....

Date 21 March 2025

Lisa Marigliano Executive Director, Portfolio Development Housing Portfolio Homes NSW

DA ISSUE ONLY SENIORS LIVING DEVELOPMENT Lots 346-350 in DP 31990 & Lot 305 in DP 30223 2-10 Birch Street & 20 Debrincat Ave, North St Marys NSW 2760

DRAWING SCHEDULE:

| ARCHITECTURAL | Туре | Shee | et No. | Rev |
|----------------------------------|------|------|----------|-----|
| COVER PAGE | | А | 01 of 22 | D |
| BLOCK ANALYSIS PLAN | | А | 02 of 22 | C |
| SITE ANALYSIS PLAN | | А | 03 of 22 | С |
| DEMOLITION PLAN | | А | 04 of 22 | С |
| SUBDIVISION PLAN | | А | 05 of 22 | С |
| DEVELOPMENT DATA | | А | 06 of 22 | D |
| SITE PLAN | | А | 07 of 22 | |
| GROUND FLOOR PLAN | | А | 08 of 22 | |
| FIRST FLOOR PLAN | | А | 09 of 22 | C |
| ROOF PLAN | | А | 10 of 22 | С |
| ELEVATIONS | | А | 11 of 22 | D |
| ELEVATIONS & INTERNAL ELEVATIONS | | А | 12 of 22 | |
| INTERNAL ELEVATIONS | | А | 13 of 22 | |
| SECTIONS | | А | 14 of 22 | |
| SECTIONS | | А | 15 of 22 | |
| SHADOW DIAGRAMS - 21st JUNE 9AM | | А | 16 of 22 | C |
| SHADOW DIAGRAMS - 21st JUNE 12PM | | А | 17 of 22 | С |
| SHADOW DIAGRAMS - 21st JUNE 3PM | | А | 18 of 22 | С |
| SOLAR ACCESS - VIEW FROM SUN | | А | 19 of 22 | С |
| SOLAR ACCESS - VIEW FROM SUN | | А | 20 of 22 | С |
| SOLAR ACCESS - VIEW FROM SUN | | А | 21 of 22 | С |
| PERSPECTIVES | | A | 22 of 22 | D |

SITE / GROUND FLOOR PLAN FIRST FLOOR PLAN

HYDRAULIC

LEGENDS & NOTES

ROOF PLAN

CIVIL

CUT AND FILL CUT AND FILL PLAN

STORMWATER CONCEPT PLAN SPECIFICATION SHEET SITE DRAINAGE PLAN **DRAINAGE PLAN - SHEET 1** DRAINAGE PLAN - SHEET 2 OSD SECTION AND STORMWATER DETAILS STORMWATER DETAILS SEDIMENT CONTROL PLAN

FOOTPATH UPGRADE PLAN

FOOTPATH LAYOUT PLAN FOOTPATH STANDARD DETAILS FOOTPATH LONGSECTION - 1 FOOTPATH LONGSECTION - 2

| SURVEY |
|-----------------------|
| DETAIL & LEVEL SURVEY |

| Туре | She | et No. | Rev |
|------|-----|----------|-----|
| | S | 1 of 10 | А |
| | S | 2 of 10 | - |
| | S | 3 of 10 | - |
| | S | 4 of 10 | - |
| | S | 5 of 10 | - |
| | S | 6 of 10 | - |
| | S | 7 of 10 | - |
| | S | 8 of 10 | - |
| | S | 9 of 10 | - |
| | S | 10 of 10 | - |

LANDSCAPE

LANDSCAPE PLAN



LOCKED BAG 5022 PARRAMATTA NSW 2124 PHONE No. 1800 738 718 www.dpie.nsw.gov.au

Homes NSW APPROVED PLANS Date: 21 March 2025






LOCATION PLAN:

| Туре | Shee | t No. | Rev |
|------|------|---------|-----------|
| | н | 1 of 4 | В |
| | Н | 2 of 4 | В |
| | Н | 3 of 4 | В |
| | Н | 4 of 4 | В |
| | | | |
| Туре | She | eet No. | Rev |
| | С | 1 of 1 | В |
| | | | \bigcap |
| | С | 1 of 7 | F |
| | С | 2 of 7 | F |
| | С | 3 of 7 | F |
| | С | 4 of 7 | F |
| | С | 5 of 7 | F) |
| | С | 6 of 7 | > F) |
| | С | 7 of 7 | F |
| | | | |
| | С | 1 of 4 | А |
| | С | 2 of 4 | А |
| | С | 3 of 4 | А |
| | С | 4 of 4 | А |
| | | | |
| Туре | Shee | t No. | Rev |
| | L | 1 of 1 | E |









DTA Architects PH (02) 9601 1011

ARCHITECT

PROJECT MANAGER

HOMES NSW PH 1800 738 718

DATE: 4/12/2024 DESIGN: DA PROJECT No: BGYVZ

NOMINATED ARCHITECTS: **Daniel Donai** NSW ARB No.9068 Membe

- 0_5_10_20 40MM SCALE FOR PRINTING PURPOSE ONLY
- DO NOT SCALE FROM DRAWINGS. USE WRITTEN DIMENSIONS ONLY.
 BUILDER TO CHECK & VERIFY ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT OF WORK.
 IT IS THE OWNERS RESPONSIBILITY TO ENSURE THAT THE ENGINEER HAS INVESTIGATED SUBSOIL CONDITIONS & DESIGNED ALL STRUCTURAL ELEMENTS TO SUIT

- THE DESIGN & DETAILS SOLE CONTAINED ON THIS & DESIGNED ALL STRUCTURAL ELEMENTS TO SUIT. THE DESIGN & DETAILS CONTAINED ON THIS DRAWING IS SUPPLIED IN CONFIDENCE & IS NOT TO BE USED FOR ANY OTHER PURPOSE, EXCEPT THAT AUTHORISED BY DTAARCHITECTS



ST MARY'S NORTH PUBLIC SCHOOL & CHILDRENS CENTRE



EXISTING SINGLE STOREY DUPLEX



20 DEBRINCAT AVE. SINGLE STOREY RESIDENCE



TYPICAL 2 STOREY RESIDENCE



2-10 BIRCH ST. PROPOSED DEVELOPMENT OWNED BY LAND AND HOUSING CORPORATION




Locked Bag 5022 Parramatta NSW 2124 Phone No. 1800 738 718 www.dpie.nsw.gov.au

NSW GOVERNMENT



109, 31 lasso road gregory hills i ta.net.au | e:adminilidta.net.au | t:+61

4 BIRCH STREET






EXISTING 2 STOREY DUPLEX



6 BIRCH STREET

| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 |
|---------------|---|
| | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 |
| IONS ON SITE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 |

HYDRAULIC ABEL & BROWN Pty Ltd PH (02) 9709 5705 ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712





8 BIRCH STREET

at

SENIORS HOUSING DEVELOPME

Lots 346-350 in DP 31990 & Lot 30 2-10 Birch Street & 20 Debrincat A Marys NSW 2760

LEGEND: BLOCK PLAN



PROPOSED DEVELOPMENT OWNED BY DEPARTMENT OF HOUSING

BOUNDARY LINE TO LOTS OWNED BY OTHERS

<u>NOTE:</u> MOSTLY TYPICAL RECTANGULAR LOTS WITH VARIED LOT SIZES IN THE VICINITY OF THE NEW DEVELOPMENT. LOTS BECOME IRREGULAR TOWARDS BLOCK ENDS.



TYPICAL 2 STOREY RESIDENCE




TYPICAL 2 STOREY RESIDENCE




10 BIRCH STREET


| ENT | BLOCK ANALYSIS PLAN | | | STATUS: DA ISSUE DATE: SCALE: PROJ: JOB: 4/12/2024 As shown @ A1 BGYVZ 2022.011 | | | |
|-----------------|---|-------------------------------|-------------|---|----------|------------|--|
| 305 in DP 30223 | | | STAGE: C | DRAWN: SD | CHECKED: | CERTIFIER: | |
| Ave, North St | FILE: CAD File: S:\Data3\2022\2022.011.LAHC.SL. 2-10 Birch St North St Marys\3.Design\3.2 DA \2022.011.LAHC.2-10 Birch Street North St. DA04 - MOD.pln | PLOTTED: 4/12/2024 3:52 PM | туре: | SHEET: 2 0 | f 22 | REV: | |



| | ARCHITECT | HYDRAULIC | | | PROJECT: |
|-------------------------|--|--|------------|-------|--|
| | DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | ABEL & BROWN Pty Ltd PH (02) 9709 5705 | | | SENIORS HOUSING DEVELOPME |
| | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | | Homes | at Lots 346-350 in DP 31990 & Lot 30 |
| SIONS ON SITE. ENCE. | - | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | GOVERNMENT | NSW | 2-10 Birch Street & 20 Debrincat A Marys NSW 2760 |



| | ARCHITECT | HYDRAULIC | | | PROJECT: |
|------------------------------|---|--|------------|-------|--|
| | DTAARCHITECTS Pty Ltd PH (02) 9601 1011 | ABEL & BROWN Pty Ltd PH (02) 9709 5705 | | | SENIORS HOUSING DEVELO |
| | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | | Homes | at Lots 346-350 in DP 31990 & Lo |
| IENSIONS ON SITE. EDENCE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | GOVERNMENT | NSW | 2-10 Birch Street & 20 Debrine Marys NSW 2760 |



LEGEND - DEMOLITION - - - EXTENT OF SITE BOUNDARY EXISTING STRUCTURES TO BE DEMOLISHED. 1 REPAIR & REINSTATE ADJOINING SURFACES. DEMOLISHED A2EXISTING TREES TO REMAIN. REFER ALSO TO LANDSCAPE DRAWING. $\int \nabla$ EXISTING TREES TO BE REMOVED. REFER ALSO TO LANDSCAPE DRAWING. 十 🔊 EXISTING LEVELS

PERFORM ALL THE DEMOLITION AS SHOWN ON THE DRAWING AND/OR AS NECESSARY REQUIRED CARRYING OUT THE WORKS UNDER THE CONTRACT.


NB: CARE MUST BE TAKEN WHILE CARRING OUT THE WORKS. PROTECT EXISTING PROPERTY FROM DAMAGE BY APPROPRIATE MEANS INCLUDING SHORING, STRUTTING, PROTECTIVE SCREENS, SHEETING AND THE LIKE.

REPAIR & REINSTATE ANY SUCH DAMAGE TO MATCH EXISTING. EXISTING SERVICES: DEAL AS APPROPRIATE WITH EXISTING SERVICES INCLUDED IN OR ENCOUNTERED DURING THE COURSE OF THE DEMOLITIONS.

BEFORE DEMOLISHING AND REMOVING PARTS OF BUILDING HAVING ELECTRICAL WIRING, GAS, SEWER AND WATER PIPES, CONDUIT OR SIMILAR ITEMS EMBEDDED IN THEM, NOTIFY THE PROJECT MANAGER/ SUPERINTENDENT, AUTHORITIES HAVING JURISDICTION, AND MAKE SURE THAT THESE ITEMS ARE OUT OF SERVICE SO THAT THEY CAN BE REMOVED WITHOUT DANGER.



| DEMOL | ITION PLAN | | | | | |
|----------------|---|-------------------------------|-------------|---------------|----------|----------|
| | 1:200 | | | | | |
| ENT | | STATUS: DA | | I PROJ: | IJOB: | |
| | | | 4/12/2024 | As shown @ A1 | BGYVZ | 2022.011 |
| 05 in DP 30223 | | | STAGE: C | DRAWN: SD | CHECKED: | |
| Ave, North St | FILE: CAD File: S:\Data3\2022\2022.011.LAHC.SL. 2-10 Birch St North St Marys\3.Design\3.2 DA \2022.011.LAHC.2-10 Birch Street North St. DA04 - MOD.pln | PLOTTED: 4/12/2024 3:52 PM | ТУРЕ: | SHEET: 4 O | f 22 | REV: |



| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | HYDRAULIC ABEL & BROWN Pty Ltd PH (02) 9709 5705 | | SENIORS HOUSING DEVELOPM |
|-----------------------|---|--|-------|--|
| | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | Homes | at Lots 346-350 in DP 31990 & Lot 3 |
| IONS ON SITE. NCE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | NSW | 2-10 Birch Street & 20 Debrincat Marys NSW 2760 |
| | | | | |



| | | DEVELOP | MENT DATA | | | | | |
|-------------------------|------------------------|----------|-------------------------|-----------------------|-----------------------|--|--|--|
| Site Area | | | 3613.72m ² | | | | | |
| Number of existing lots | | 5 | | | | | | |
| Number of dwellings | | 22 units | - 12 x 2bed + 10 x 1 | bed (55:45 ratio) | - | | | |
| Dwellings | Number | Туре | No. of Bedrooms | Area (m2) | POS (m2) | | | |
| | 1 | Ground | 1 (SEPP Sch. 4) | 60.97 | 60.10 | | | |
| | 2 | Ground | 2 (SEPP Sch. 4) | 77.85 | 102.98 | | | |
| | 3 | First | 1 | 61.71 | 8.11 | | | |
| | 4 | First | 2 | 78.35 | 10.24 | | | |
| | 5 | Ground | 1 (SEPP Sch. 4) | 60.02 | 44.58 | | | |
| | 6 | Ground | 1 (SEPP Sch. 4) | 60.57 | 42.11 | | | |
| | 7 | First | 1 | 60.71 | 8.86 | | | |
| | 8 | First | 1 | 61.26 | 8.86 | | | |
| | 9 | Ground | 2 (SEPP Sch. 4) | 79.41 | 154.82 | | | |
| | 10 | Ground | 1 (SEPP Sch. 4) | 60.97 | 55.24 | | | |
| | 11 | First | 2 | 80.64 | 10.48 | | | |
| | 12 | First | 1 | 62.55 | 10.52 | | | |
| | 13 | Ground | 1 (SEPP Sch. 4) | 60.25 | 63.50 | | | |
| | 14 | Ground | 2 (SEPP Sch. 4) | 78.61 | 88.11 | | | |
| | 15 | Ground | 2 (SEPP Sch. 4) | 78.62 | 194.48 | | | |
| | 16 | First | 1 | 61.45 | 8.44 | | | |
| | 17 | First | 2 | 78.78 | 10.10 | | | |
| | 18 | First | 2 | 79.37 | 10.10 | | | |
| | 19 | Ground | 2 (SEPP Sch. 4) | 79.41 | 102.30 | | | |
| | 20 | Ground | 2 (SEPP Sch. 4) | 79.41 | 148.56 | | | |
| | 21 | First | 2 | 80.64 | 10.48 | | | |
| | 22 | First | 2 | 80.64 | 10.48 | | | |
| | Con | | Require | | Provided | | | |
| | HOUSING SEPP | | | | 1902.35m ² | | | |
| roposed FSR | (excl. external walls) | | 0.5 | :1 | 0.52:1 | | | |
| | , , | | | | 0.52.1 | | | |
| | Penrith LEP | | | 1785.43m ² | | | | |
| | (excl. externa | | not pres | 0.49:1 | | | | |
| | vertical circu | lation) | | 011012 | | | | |
| Building Height | Penrith LEP | | max. 8 | 8.2m | | | | |
| building neight | HOUSING SEP | р | max. 9 | 8.2m | | | | |
| | | | a. average of | 8.06m | | | | |
| | | Front | neighbour | (6.55m to | | | | |
| | | | b. 5.5m (whiche | balcony) | | | | |
| Setbacks | Penrith DCP | | 2m | Salcony) | | | | |
| JEIDALKS | | Side | | 3.1m | | | | |
| | | | (max. 50% of a | | | | | |
| | | Rear | Single Stor | 6m | | | | |
| | | neur | Second Sto | 0111 | | | | |
| Connorling | LAHC | | 10 | | | | | |
| Car parking | LARC | | (0.4/1bed , | 0.5/2bed) | 10 | | | |
| | HOUSING SER | pp | 5 (1/5 acc | | | | | |
| Landscaping | HOUSING SEF | | 35m ² / unit | | 1463.1 m2 | | | |
| Deep Soil | HOUSING SEF | | 15% of site | | 746.23m2 | | | |
| Deep Soli | | Γ, | | | | | | |
| | | | preferably 65% de | | 413.8m2 | | | |
| | | | 352 | m- | to rear | | | |
| | | | | | | | | |
| Solar Orientation | HOUSING SER | р | | | Living - 86% | | | |
| | | • | 70% of dwellings to | o receive 2 hours | POS - 86% | | | |
| | | | of sunlight betwee | | | | | |
| | | | mid w | | 72% (16/22 | | | |
| | | | mia w | | Dwellings | | | |
| | | | | | Overall) | | | |
| | | | 1 | | (3) (a) (1) | | | |

| \bigvee | \checkmark | $\overline{\mathbf{A}}$ | \sim | \sim | | \sim | | | |
|--------------------------------|---|---|-------------------------------------|--------------------|---|-----------------------------|--|-----------------------------|--|
| | | NCC 2022 NathERS TH | nermal Performance Specification | - North St Marve | | | | | |
| | | | External Walls | r - North St Marys | | | | | |
| | Wall Type | Insulation | Colour | | Comm | nents | | | |
| | Cavity brick | Min R0.7 required (R4.0 Firemax specified) | Med - SA 0.475 - 0.70 | | As per el | evations | K | | |
| | | | SA - Solar Absorptance | • | | | | | |
| | | | Internal Walls | | | | | | |
| | Wall Type | Insulation | | | omments | | K | | |
| | Single skin brick | None | | | units (Ground floor) | | \ | | |
| | Plasterboard stud Cavity brick | None | | | y in units (Level 1) between units/lobbies | | | | |
| | cavity brick | None | Floors | Silarea walis | between units/1000ies | | | | |
| | Floor Type | Insulation | 110013 | c | omments | | | | |
| | Concrete slab on ground | None | | Gr | ound floor | | | | |
| | Concrete | None | | Level 1 | 1 (Units below) | | | | |
| | | | Ceilings | | | | | | |
| | Ceiling Type | Insulation | | | omments | |) | | |
| | Plasterboard | None | | | Init above | | | | |
| | Plasterboard | R2.5 | | | of/air above | | | | |
| | Insulation loss due to downlights h | as not been modelled in this asse | | been included in e | very kitchen, bathroom, l | laundry and ensuite. |) | | |
| | 0 | transfertiere | Roof | 1 | | *- | —— K | | |
| | Roof Type Metal | Insulation R1.3 foil-faced blanket | Colour Med - SA 0.475 - 0.70 | | Comm Throughout (Ve | | —————————————————————————————————————— | | |
| | Wetar | N1.5 Ion faced blanker | SA - Solar Absorptance | | Throughout (ve | | | | |
| | | | Glazing | | | | | | |
| | Opening type | U-Value | SHGC | | Glazing & F | rame Type | | | |
| Sliding + Fixed | (Throughout except below) | 4.8 | 0.59 | e.g. Singl | e glazed High performir | ng Low-e clear Aluminium fr | ame | | |
| - | l (Units: 10 & 15) | 4.5 | 0.61 | e.g. Singl | e glazed High performir | ng Low-e clear Aluminium fr | ame | | |
| Awning (Throu Awning (Units | ughout except below) | 4.8 | 0.51 | | | ng Low-e clear Aluminium fr | | | |
| U and | SHGC values are based on the AFRC De | | ns to be installed must have an equ | | | ng Low-e clear Aluminium fr | | | |
| | Skylight Type | Fram | Skylights e Type | 1 | Comm | nents | | | |
| | Fixed | | d Aluminium | + | Single gla | | | | |
| | | | Ceiling fan | 1 | | | | | |
| | Size | Loc | ation | | Comn | nents | | | |
| | 1200mm in diameter | Liv | ving | | Throu | ghout | | | |
| | 900mm in diameter | Bed | rooms | | Throu | ghout | | | |
| | Certificate Prepared by Greenview Consulting Pty Ltd ABN: 32600067338 Email: dean@greenview.net.au Phone: 0404 649 762 | | | | | | | | |
| | | | | | | | | | |
| | TITLE: DEVELOPM | έντ σάτα | | | | ISSUE | | | |
| | | | | | date: 4/12/2024 | SCALE: As shown @ A1 | BGYVZ | ^{JOB:} 2022.011 | |
| | | | | | STAGE: | DRAWN: | CHECKED: | CERTIFIER: | |
| DP 30223 | | | | | С | SD | DD | DD | |
| | FILE: CAD File: S:\Data3\20 |)22\2022.011.LAHC.SL. | PLOTTED: A / A O | | TYPE: | SHEET: | 1 | REV: | |
| North St | | t Marys\3.Design\3.2 DA | | /2024 | _ | | | | |
| | \2022.011.LAHC.2-10 | Birch Street North St. | 3:52 | DM | A | 6 n' | f 22 | | |
| | DA04 - MOD.pln | | 3.52 | . 17 111 | | | | | |

0_5_10_20 40MM SCALE FOR PRINTING

GOVERNMENT

- STRUCTURAL ELEMENTS TO SUIT.
- EXCEPT THAT AUTHORISED BY DTAARCHITECTS






| | | | ARCHITECT | HIDRAULIC | | | TROOLOT. |
|-----|------------|---|----------------------------|---------------------------------|------------|-------|-----------------|
| | | | DTA ARCHITECTS Pty Ltd | ABEL & BROWN Pty Ltd | | | |
| | | | PH (02) 9601 1011 | PH (02) 9709 5705 | | | SENIORS HOU |
| | | | PROJECT MANAGER | ELECTRICAL / BASIX CONSULTANT | | | |
| D | 27/11/2024 | MODIFICATION - Substation + HWUs Included, Paths adjusted | LAND & HOUSING CORPORATION | GREENVIEW CONSULTING Pty Ltd | | | at |
| С | 26/10/2023 | UPDATED DA ISSUE | PH (02) 9354 1880 | 5 | | Homes | |
| В | 23/06/2023 | DAISSUE | PH (02) 9354 1060 | PH (02) 8544 1683 | | | Lots 346-350 in |
| А | 16/05/2023 | DAISSUE | STRUCTURAL / CIVIL | LANDSCAPE CONSULTANT | | NSW | |
| REV | DATE | NOTATION/AMENDMENT | | RAY FUGGLE & ASSOCIATES Pty Ltd | | | 2-10 Birch Stre |
| | DO NOT SCA | ALE DRAWINGS. CHECK ALL DIMENSIONS ON SITE. | | | GOVERNMENT | | Marys NSW 27 |
| | FIC | GURED DIMENSIONS TAKE PRECEDENCE. | PH (02) 4226 5247 | PH 0412 294 712 | | | wialys NSW 27 |
| | | | | | | | |

in DP 31990 & Lot 305

eet & 20 Debrincat Av Marys NSW 2760




| SITE LEGEN | D |
|---|----------------------------------|
| | 1 BED |
| | 2 BED |
| | PRIVATE OPEN SPACE (POS) |
| | LANDSCAPE AREA |
| | DRIVEWAY, FOOT PATH & PAVED AREA |
| | DEEP SOIL ZONE |
| | CERAMIC TILE (NS-CT) |
| | BRICK RETAINING WALL |
| | EX.TREES TO BE RETAINED |
| The t | EX. TREES TO BE REMOVED |
| SWP | STORMWATER PIT |
| —E | OVERHEAD POWERLINE |
| —S | UNDERGROUND SEWER |
| | AMENDMENTS |

Nom. 270mm thick cavity brick wall, finish as specified


Non-slip ceramic floor tiles. Refer to finishes schedule

| | LEGEND |
|--------------|--|
| | |
| AB ABH | ARMCO BARRIER ARMCO BARRIER WITH HANDRAIL |
| ANG | CONTINUOUS 100 x 100 x 6 GALVANISED STEEL |
| | PROTECTIVE ANGLE TO WALL LINE, REFER TO DETAILS |
| ANG-1 | CONTINUOUS 100 x 100 x 6 GALVANISED STEEL PROTECTIVE ANGLE FIXED TO FLOOR EXACT |
| | POSITION TO BE DETERMINED ON SITE |
| | EL PROTECTIVE BOLLARDS REFER TO DETAILS |
| B-1 | VANITY BASIN WALL HUNG BASIN - DISABLE COMPLIANT |
| B-2 B-3 | WALL HUNG BASIN - DISABLE COMPLIANT |
| BC | BATTERY CHARGE |
| BF | BACK FLASHING |
| BFC C | BROOM FINISHED CONCRETE CARPET AS SPECIFIED |
| CAP | CEILING ACCESS PANEL |
| CH | CLOTHES HOOK |
| CR CS | CEMENT RENDERED FINISH CLEANERS SHELF |
| CT | CERAMIC TILES |
| C/W | |
| DB DP | ELECTRICAL DISTRIBUTION BOARD DOWNPIPE - COLORBOND. |
| DPS | DOWNPIPE & SPREADER - COLORBOND. |
| DT | DOOR THRESHOLD REFER TO DETAIL |
| DW EAC | DISHWASHER AS SPEC. EXPOSED AGGREGATE CONCRETE |
| EDB | ELECT. DISTRIBUTION BOARD, |
| | REFER TO ELECT. DOCUMENTS |
| EF EG | EXHAUST FAN EAVES GUTTER |
| EW | EYE WASH |
| F | FRIDGE AS SPEC. |
| FG FHR | FIXED GLASS FIRE HOSE REEL REFER TO HYDRAULUC |
| | ENGINEERS DETAILS |
| FIP | FIR INDICATOR PANEL (LOCATED MAIN ENTRY) |
| FM FW | RECESSED FLOOR MAT FLOOR WASTE |
| GD | GRATED DRAIN |
| GPO-S | SINGLE GENERAL PURPOSE OUTLET |
| GPO-D GPB | DOUBLE GENERAL PURPOSE OUTLET GOAL POST BOLLARDS |
| GR | GRAB RAIL |
| HD | HAND DRYER |
| HTH | HEATED THRESHOLD HOT WATER UNIT |
| HWU HYD | HYDRANT REFER TO HYDRAULUC |
| | ENGINEERS DETAILS |
| LC | LAMINATED BENCH TOP & CUPBOARDS |
| LK M1 | LOCKERS MIRROR |
| MSB | ELECTRICAL MAIN SWITCH BOARD |
| MW | MICROWAVE OVEN AS SPEC. |
| NS-CT OF | NON-SLIP CERAMIC TILE OVERFLOW |
| PB | PLASTERBOARD LINING |
| PTD | PAPER TOWEL DISPENSER |
| RH RM | RANGE HOOD RECESSED ENTRY MAT |
| SCR | SHOWER CURTAIN RAIL |
| SC | COLUMN TO STRUCTURAL |
| SD | ENGINEERS DETAILS SOAP DISPENSER |
| SH | WALL SHELF |
| SK | SEWER STACK REFER TO HYDRAULIC |
| SK-1 | ENGINEERS DETAILS STAINLESS STEEL SINK |
| SK-2 | CLEANER SINK |
| SMP | BOX GUTTER SUMP & OVERFLOW |
| STF TGSI | STEEL TROWEL FINISHED CONCRETE TACTILE INDICATOR |
| TH | THRESHOLD RAMP |
| TIM | |
| TP TPH | TOILET PARTITIONS TOILET PAPER HOLDER |
| TRS | TRANSLUCENT ROOF SHEETING |
| TS-1 | TAP SET - WASHROOMS |
| TS-2 TS-3 | TAP SET - DISABLE COMPLIANT TAP SET - KITCHEN |
| TS -4 | TAP SET - CLEANERS |
| US | MOP & BROOM SHELF |
| V VP | VINYL VENT PIPE |
| | REFER TO HYDRAULIC DOCUMENTS |
| VTY | VANITY UNIT |
| WB WC-1 | WORK BENCH TOILET PAN / SUITE |
| WC-1 WC-2 | TOILET PAN / SUIT DISABLE COMPLIANT |
| WC-3 | TOILET PAN / SUITE AMBULANT |
| WG WT | WHEEL GUIDE WASH TROUGH |
| WU-1 | WASH TROOGH WALL HUNG URINAL |
| WS | WHEEL STOP |
| XP | EPOXY FLOORING |


| | тты SI | | | | STATUS: DA | ISSUE | | |
|----------------|-----------|---|----------|-----------|------------|---------------|----------|------------|
| ENT | SITE FEAN | | | DATE: | SCALE: | PROJ: | JOB: | |
| | | | | | 4/12/2024 | As shown @ A1 | BGYVZ | 2022.011 |
| | | | | | STAGE: | DRAWN: | CHECKED: | CERTIFIER: |
| 05 in DP 30223 | | | | | С | SD | DD | DD |
| | FILE: | CAD File: S:\Data3\2022\2022.011.LAHC.SL. 2-10 Birch St North St Marys\3.Design\3.2 DA | PLOTTED: | 4/12/2024 | TYPE: | SHEET: | | REV: |
| | | 2022.011.LAHC.2-10 Birch Street North St. DA04 - MOD.pln | | 3:52 PM | A | 7 o | f 22 | D |



| | ARCHITECT | HYDRAULIC | | | PROJECT: |
|-----------------------------------|--|---|------------|--------------|---|
| | DTAARCHITECTS Pty Ltd PH (02) 9601 1011 | ABEL & BROWN Pty Ltd PH (02) 9709 5705 | | | SENIORS HOUSING |
| WUs Included, Paths adjusted | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | | Homes | at |
| | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd | LANDSCAPE CONSULTANT | _ | NSW | 2-10 Birch Street & 20 |
| DIMENSIONS ON SITE. RECEDENCE. | PH (02) 4226 5247 | PH 0412 294 712 | GOVERNMENT | | Marys NSW 2760 |
| DIMENSIONS ON SITE. | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd | | Homes NSW | at Lots 346-350 in I 2-10 Birch Stree |







| ARCHITECT | HYDRAULIC | | PROJECT: |
|------------------------|------------------------------|-------|------------------------------------|
| DTA ARCHITECTS Pty Ltd | ABEL & BROWN Pty Ltd | | |
| - | PH (02) 9709 5705 | | SENIORS HOUSING DEVELOPMENT |
| | | | |
| | | | at |
| | GREENVIEW CONSULTING Pty Ltd | Homes | |
| PH (02) 9354 1660 | PH (02) 8544 1683 | | Lots 346-350 in DP 31990 & Lot 305 |
| | | | |



GOVERNMENT

- PURPOSE ONLY . DO NOT SCALE FROM DRAWINGS. USE WRITTEN DIMENSIONS ONLY.
- BUILDER TO CHECK & VERIFY ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT OF WORK.

0008706870 25 Oct 2024

Address

2760

2-10 Birch street,

North St Marys, NSW,

7.5

Average star rating

HOUS ENERGY BATING SCHER


Assessor Dean Gorman


Accreditation No. DMN/13/1645


eet –

hstar.com.au

- IT IS THE OWNERS RESPONSIBILITY TO ENSURE THAT THE ENGINEER HAS INVESTIGATED SUBSOIL CONDITIONS & DESIGNED ALL
- STRUCTURAL ELEMENTS TO SUIT. THE DESIGN & DETAILS CONTAINED ON THIS DRAWING IS SUPPLIED IN CONFIDENCE & IS NOT TO BE USED FOR ANY OTHER PURPOSE, EXCEPT THAT AUTHORISED BY DTAARCHITECTS







| nes | | |
|-----|--|--|

Marys NSW 2760

| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 |
|-------------------|---|
| | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 |
| NS ON SITE. E. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 |
| | |

ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712









| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | HYDRAULIC ABEL & BROWN Pty Ltd PH (02) 9709 5705 | | | PROJECT: SENIORS HOUSING DEVELOPMENT | ELEVATION | | A ISSUE | | JOB: |
|------------------------|---|--|------------|-------|--|-------------------------------|--------------------------|-------------------------------|-------|------------------------------|
| cluded, Paths adjusted | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | | Homes | at Lots 346-350 in DP 31990 & Lot 305 in DP 30223 | | 4/12/2024 STAGE: C | As shown @ A1 DRAWN: SD | | 2022.011 CERTIFIER: DD |
| JSIONS ON SITE | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | GOVERNMENT | NSW | 2-10 Birch Street & 20 Debrincat Ave, North St Marys NSW 2760 | PLOTTED: 4/12/2024 3:53 PM | туре: | SHEET: 12 (| of 22 | REV: |



PH (02) 4226 5247

PH 0412 294 712

2-10 Birch Street & 20 Debrincat A Marys NSW 2760

GOVERNMENT

| SCHEDULE | | |
|---|----|--|
| OOF (SMR) Strength - Basalt Matt | 8 | ENTRY AWNING / BALCONY SLAB EDGE / BALCONY BALUSTRADE Concrete - Rockcote Finish |
| NPIPE / BARGE BOARD & FASCIA / POST & STRUCTURE t | 9 | BALCONY SOFFIT & FEATURE WALL / BALCONY PRIVACY SCREEN Decowood - Aluminium Colour - Kwila |
| G (MC1) - Colorbond Metal Wall Cladding 55 - Basalt Matt | 10 | WINDOW & DOOR FRAMES Aluminium Powdercoat - Basalt |
| STE ENCLOSURE 1 (FBK1) lour, Name - Volcanic | 11 | FRONT DOOR LEAF Paint Finish - Shale Grey |
| 2 (FBK2) lour, Name - Crushed Grey | 12 | GLASS BALCONY BALUSTRADE Balustrade - Obsure glass Frame - Aluminium Powdercoat , Shale Grey |
| 3 (FBK3) Iour, Name - Volcanic | 13 | FRONT METAL FENCE Vertical Bars - Steel Powdercoat, Woodland Grey SIDE, REAR & POS FENCE Colorbond, Woodland Grey |
| 4 (FBK4) lour, Name - Crushed Grey | | |


| | | | | | | STATUS: DA ISSUE | | | | | |
|----------------|--|---|--------------------|-------------------------|----------------|-----------------------------|----------|------------|--|--|--|
| ENT | | | DATE: 4/12/2024 | SCALE: As shown @ A1 | PROJ: BGYVZ | ^{ЈОВ:} 2022.011 | | | | | |
| 05 in DP 30223 | | | | | STAGE: C | DRAWN: SD | CHECKED: | CERTIFIER: | | | |
| | | CAD File: S:\Data3\2022\2022.011.LAHC.SL. 2-10 Birch St North St Marys\3.Design\3.2 DA \2022.011.LAHC.2-10 Birch Street North St. DA04 - MOD.pln | PLOTTED: | 4/12/2024 3:53 PM | | SHEET: 13 (| of 22 | REV: | | | |


0_5_10_20 40MM

SCALE FOR PRINTING

- PURPOSE ONLY . DO NOT SCALE FROM DRAWINGS. USE WRITTEN DIMENSIONS ONLY.
- BUILDER TO CHECK & VERIFY ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT OF WORK.
- IT IS THE OWNERS RESPONSIBILITY TO ENSURE THAT THE ENGINEER HAS INVESTIGATED SUBSOIL CONDITIONS & DESIGNED ALL
- STRUCTURAL ELEMENTS TO SUIT. THE DESIGN & DETAILS CONTAINED ON THIS DRAWING IS SUPPLIED IN CONFIDENCE & IS NOT TO BE USED FOR ANY OTHER PURPOSE, EXCEPT THAT AUTHORISED BY DTAARCHITECTS










LOCKED BAG 5022 PARRAMATTA NSW 2124 PHONE No. 1800 738 718 www.dpie.nsw.gov.au





| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | HYDRAULIC ABEL & BROWN Pty Ltd PH (02) 9709 5705 | | PROJECT: SENIORS HOUSING DEVELOPMENT | | | DATE: | | | ^{ЈОВ:} 2022.011 |
|-------------------------|---|--|-------|--|---|-------------------------------|--------------------------|----------------|------|-----------------------------|
| ncluded, Paths adjusted | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | Homes | at Lots 346-350 in DP 31990 & Lot 305 in DP 30223 | | | 4/12/2024 STAGE: C | DRAWN: C | | CERTIFIER: |
| ENSIONS ON SITE | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | NSW | 2-10 Birch Street & 20 Debrincat Ave, North St Marys NSW 2760 | FILE: CAD File: S:\Data3\2022\2022.011.LAHC.SL. 2-10 Birch St North St Marys\3.Design\3.2 DA \2022.011.LAHC.2-10 Birch Street North St. DA04 - MOD.pln | PLOTTED: 4/12/2024 3:54 PM | түре: | SHEET: 14 O | f 22 | REV: |


| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | HYDRAULIC ABEL & BROWN Pty Ltd PH (02) 9709 5705 | | | PROJECT: SENIORS HOUSING DEVELOPMENT | | | STATUS: DA | | PROJ: | JOB: |
|-------------------------------|---|--|------------|-------|--|---|--|-------------|----------------|-------------------------|------------------------------|
| s Included, Paths adjusted | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | | Homes | at Lots 346-350 in DP 31990 & Lot 305 in DP 30223 | | | STAGE: C | drawn: SD | BGYVZ CHECKED: DD | 2022.011 CERTIFIER: DD |
| MENSIONS ON SITE. CEDENCE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | GOVERNMENT | NSW | 2-10 Birch Street & 20 Debrincat Ave, North St Marys NSW 2760 | FILE: CAD File: S:\Data3\2022\2022.011.LAHC.SL. 2-10 Birch St North St Marys\3.Design\3.2 DA \2022.011.LAHC.2-10 Birch Street North St. DA04 - MOD.pln | ^{PLOTTED:} 4/12/2024 3:54 PM | | SHEET: 14 O | of 22 | REV: |





- PURPOSE ONLY
- DO NOT SCALE FROM DRAWINGS. USE WRITTEN DIMENSIONS ONLY.
 BUILDER TO CHECK & VERIFY ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT OF WORK.
 IT IS THE OWNERS RESPONSIBILITY TO ENSURE THAT THE ENGINEER HAS INVESTIGATED SUBSOIL CONDITIONS & DESIGNED ALL STDUCTURAL EL MENTET OF SUIT
- STRUCTURAL ELEMENTS TO SUIT. THE DESIGN & DETAILS CONTAINED ON THIS DRAWING IS SUPPLIED IN CONFIDENCE & IS NOT TO BE USED FOR ANY OTHER PURPOSE, EXCEPT THAT AUTHORISED BY DTAARCHITECTS











Member Australian Institute of Architects

 A
 100032023
 DATSSUE

 REV
 DATE
 NOTATION/AMENDMENT

 DO NOT SCALE DRAWINGS. CHECK ALL DIMENSI

 FIGURED DIMENSIONS TAKE PRECEDEN


| | ARCHITECT DTA ARCHITECTS Pty Ltd | HYDRAULIC ABEL & BROWN Pty Ltd | | | PROJECT: |
|-----------------|---|--|------------|-------|--|
| | PH (02) 9601 1011 | PH (02) 9709 5705 | | | SENIORS HOUSING DEVELOPM |
| | PROJECT MANAGER | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd | | | at |
| | PH (02) 9354 1880 | PH (02) 8544 1683 | NSW | Homes | Lots 346-350 in DP 31990 & Lot 3 |
| ISIONS ON SITE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | GOVERNMENT | NSW | 2-10 Birch Street & 20 Debrincat Marys NSW 2760 |
| ENCE. | FTT (02) 4220 3247 | PH 0412 294 712 | | | Marys 1000 2700 |







Red area indicates existing shadows cast by neighbouring properties










| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | HYDRAULIC ABEL & BROWN Pty Ltd PH (02) 9709 5705 | | | PROJECT: SENIORS HOUSING DEVELOPI |
|---------------------------|---|--|--------------------------|-------|---|
| | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | | Homes | at Lots 346-350 in DP 31990 & Lot |
| ISIONS ON SITE. DENCE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | NSW government | NSW | 2-10 Birch Street & 20 Debrinca Marys NSW 2760 |








NSW GOVERNMENT


www.dpie.nsw.gov.au





| | ARCHITECT DTA ARCHITECTS Pty Ltd | HYDRAULIC ABEL & BROWN Pty Ltd | | | PROJECT: SENIORS HOUSING DEVE |
|-----------------------------|--|---|------------|-------|--|
| | PH (02) 9601 1011 PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | PH (02) 9709 5705 ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | | Homes | at |
| ENSIONS ON SITE. EDENCE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | GOVERNMENT | NSW | Lots 346-350 in DP 31990 8 2-10 Birch Street & 20 Deb Marys NSW 2760 |







^{TTED:} 4/12/2024 3:54 PM

Α


18 of 22

С





| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | HYDRAULIC ABEL & BRC PH (02) 9709 57 |
|---------------|---|---|
| | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / GREENVIE PH (02) 8544 10 |
| IONS ON SITE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE (RAY FUGGL PH 0412 294 71 |






LOCKED BAG 5022 PARRAMATTA NSW 2124 PHONE No. 1800 738 718 www.dpie.nsw.gov.au





NOMINATED ARCHITECTS: Daniel Donai NSW ARB No.9068 Member Australian Institute of Architects

/ DATE NOTATION/AMENDME DO NOT SCALE DRAWINGS. CHEC FIGURED DIMENSIONS TA



| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | HYDRAULIC ABEL & BROWN Pty Ltd PH (02) 9709 5705 | |
|---|---|--|-------|
| | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | Homes |
| ENT CK ALL DIMENSIONS ON SITE. FAKE PRECEDENCE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | NSW |

PROJECT:

at

SENIORS HOUSING DEVELOPME

Lots 346-350 in DP 31990 & Lot 305 2-10 Birch Street & 20 Debrincat Av Marys NSW 2760

| | | | | | STATUS: DA | ISSUE | | |
|----------------|------------------------------|--|----------|-----------|------------|---------------|----------|------------|
| ENT | SOLAR ACCESS - VIEW FROM SUN | | | DATE: | SCALE: | PROJ: | JOB: | |
| | | | | | 4/12/2024 | As shown @ A1 | BGYVZ | 2022.011 |
| | | | | | STAGE: | DRAWN: | CHECKED: | CERTIFIER: |
| 05 in DP 30223 | | | | | С | SD | DD | DD |
| | FILE: | | PLOTTED: | 4/12/2024 | TYPE: | SHEET: | • | REV: |
| Ave, North St | | 2-10 Birch St North St Marys\3.Design\3.2 DA \2022.011.LAHC.2-10 Birch Street North St. | | | ^ | 20 4 | of 22 | C |
| | | DA04 - MOD.pln | | 3:55 PM | A | 20 0 | א ונ | |



| | | Unit 13 | Living | |
|-----------|---|---------|--------|--|
| | | | POS | |
| | | Unit 14 | Living | |
| | | | POS | |
| | | Unit 15 | Living | |
| | | | POS | |
| | | Unit 16 | Living | |
| | | | POS | |
| | | Unit 17 | Living | |
| | | | POS | |
| - 2.30 pm | I | Unit 18 | Living | |
| | | | POS | |
| | | Unit 19 | Living | |
| | | | POS | |
| | | Unit 20 | Living | |
| | | | POS | |
| | | Unit 21 | Living | |
| | | | POS | |
| | | Unit 22 | Living | |
| | | | POS | |
| | | Total | | |
| | 1 | | | |

| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | HYD ABE PH (0 |
|--------------|---|---------------------|
| | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELE GRE PH (0 |
| ONS ON SITE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LAN RAY PH 0 |

| HYDRAULIC ABEL & BROWN Pty Ltd PH (02) 9709 5705 | ABEL & BROWN Pty Ltd | |
|--|---------------------------------|--|
| ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 | GREENVIEW CONSULTING Pty Ltd | |
| LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712 | RAY FUGGLE & ASSOCIATES Pty Ltd | |



PROJECT:

SENIORS HOUSING DEVELOPME

at Lots 346-350 in DP 31990 & Lot 305 2-10 Birch Street & 20 Debrincat Av Marys NSW 2760

| Unit 1 | Living | | | 11-11.30am 11.30-12pm | ·_ ·_··· | · _ · • • • · • • · • | 1.30-2pm | 2-2.30pm | 2.30-3pm | Hours 5 | Complies |
|---------|--------|--|--|-----------------------|----------|-----------------------|--------------|----------|----------|------------|----------|
| Offic 1 | POS | | | | | | | | | 6 | Yes |
| Unit 2 | Living | | | | | | | | | 2.5 | |
| | POS | | | | | | | | | 3 | Yes |
| Unit 3 | Living | | | | | | | | | 3.5 | |
| | POS | | | | | | | | | 2.5 | Yes |
| Unit 4 | Living | | | | | | | | | 3.5 | |
| | POS | | | | | | | | | 2.5 | Yes |
| Unit 5 | Living | | | | | | | | | 1.5 | |
| - | POS | | | | | | | | | 3 | |
| Unit 6 | Living | | | | | | | | | 1.0 | |
| - | POS | | | | | | | | | 2 | |
| Unit 7 | Living | | | | | | | | | 6 | |
| - | POS | | | | | | | | | 2.5 | Yes |
| Unit 8 | Living | | | | | | | | | 6 | |
| - | POS | | | | | | | | | 1 | |
| Unit 9 | Living | | | | | | | | | 4 | Maria |
| - | POS | | | | | | | | | 6 | Yes |
| Unit 10 | Living | | | | | | | | | 4 | Nee |
| - | POS | | | | | | | | | 5.5 | Yes |
| Unit 11 | Living | | | | | | | | | 5 | Vaa |
| - | POS | | | | | | | | | 2.5 | Yes |
| Unit 12 | Living | | | | | | | | | 3.5 | |
| | POS | | | | | | | | | 1.5 | |
| Unit 13 | Living | | | | | | | | | 5 | Yes |
| | POS | | | | | | | | | 2 | 103 |
| Unit 14 | Living | | | | | | | | | 3 | Yes |
| | POS | | | | | | | | | 3.5 | 100 |
| Unit 15 | Living | | | | | | | | | 1.5 | _ |
| | POS | | | | | | | | | 3 | |
| Unit 16 | Living | | | | | | | | | 6 | Yes |
| | POS | | | | | | | | | 3 | |
| Unit 17 | Living | | | | | | | | | 4 | Yes |
| | POS | | | | | | | | | 3 | |
| Unit 18 | Living | | | | | | | | | 4 | Yes |
| | POS | | | | | | | | | 3 | |
| Unit 19 | Living | | | | | | | | | 4 | Yes |
| | POS | | | | | | | | | 5.5 | |
| Unit 20 | Living | | | | | | | | | 4.5 | Yes |
| | POS | | | | | | | | | 5 | |
| Unit 21 | Living | | | | | | | | | 5 | Yes |
| | POS | | | | | | | | | <u> </u> | |
| Unit 22 | Living | | | | | | | | | 4.5 | |
| Tatal | POS | | | | | | | | | | 700/ |
| Total | | | | | | | | | 16/22 dw | enngs | 72% |

| | SOLAR ACCESS - VIEW FROM SUN | | | | STATUS: DA ISSUE | | | | |
|------------------------|------------------------------|---|----------|----------------------|-----------------------------------|---|-------------------------|--------------------------------------|--|
| ENT 305 in DP 30223 | JOLAN ACC | | | | DATE: 4/12/2024 STAGE: C | SCALE: As shown @ A1 DRAWN: SD | BGYVZ CHECKED: DD | JOB: 2022.011 CERTIFIER: DD | |
| | | 22\2022.011.LAHC.SL. Marys\3.Design\3.2 DA Birch Street North St. | PLOTTED: | 4/12/2024 3:55 PM | туре: | SHEET: 21 C | of 22 | REV: | |

0 5 10 20 40MM SCALE FOR PRINTING

- PURPOSE ONLY

- DO NOT SCALE FROM DRAWINGS. USE WRITTEN DIMENSIONS ONLY.
 BUILDER TO CHECK & VERIFY ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT OF WORK.
 IT IS THE OWNERS RESPONSIBILITY TO ENSURE THAT THE ENGINEER HAS INVESTIGATED SUBSOIL CONDITIONS & DESIGNED ALL STRUCTURAL ELEMENTS TO SUIT.
 THE DESIGN & DETAILS CONTAINED ON THIS DRAWING IS SUPPLIED IN CONFIDENCE & IS NOT TO BE USED FOR ANY OTHER PURPOSE, EXCEPT THAT AUTHORISED BY DTAARCHITECTS











LOCKED BAG 5022 PARRAMATTA NSW 2124 PHONE No. 1800 738 718 www.dpie.nsw.gov.au





NOMINATED ARCHITECTS: Daniel Donai NSW ARB No.9068 Member Australian Institute of A.

 1/2024
 MODIFICATION - Substation + HWUs Include

 2023
 UPDATED DA ISSUE

 223
 DA ISSUE

 REV
 DATE
 NOTATION/AMENDMENT

 DO NOT SCALE DRAWINGS.
 CHECK ALL DIMENSION

 FIGURED DIMENSIONS TAKE PRECEDENC

STREET VIEW - UNITS 13-18

| 3 - | |
|-----|--|





| | ARCHITECT DTA ARCHITECTS Pty Ltd PH (02) 9601 1011 | HY AB PH |
|--------------------|---|-----------------|
| ed, Paths adjusted | PROJECT MANAGER LAND & HOUSING CORPORATION PH (02) 9354 1880 | ELE GF PH |
| ONS ON SITE. | STRUCTURAL / CIVIL MSL CONSULTING ENGINEERS Pty Ltd PH (02) 4226 5247 | LAN RA PH |

HYDRAULIC ABEL & BROWN Pty Ltd PH (02) 9709 5705 ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING Pty Ltd PH (02) 8544 1683 ANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATES Pty Ltd PH 0412 294 712






PROJECT: SENIORS HOUSING DEVELOPME

at Lots 346-350 in DP 31990 & Lot 30 2-10 Birch Street & 20 Debrincat A Marys NSW 2760



REAR VIEW - UNITS 1-8, 10 & 12

| FNT | | | | ISSUE | | |
|------------------------|---|--|-----------------------------------|---|----------------------------------|--------------------------------------|
| ENT 305 in DP 30223 | | | DATE: 4/12/2024 STAGE: C | SCALE: As shown @ A1 DRAWN: SD | PROJ: BGYVZ CHECKED: DD | JOB: 2022.011 CERTIFIER: DD |
| Ave, North St | FILE: CAD File: S:\Data3\2022\2022.011.LAHC.SL. 2-10 Birch St North St Marys\3.Design\3.2 DA \2022.011.LAHC.2-10 Birch Street North St. DA04 - MOD.pln | ^{PLOTTED:} 4/12/2024 3:55 PM | | SHEET: 22 C | of 22 | REV: |



GENERAL

- 1. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL OTHER CONSULTANTS' DRAWINGS AND SPECIFICATIONS, AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ALL DISCREPANCIES SHALL BE REFERRED TO THE PROJECT MANAGER FOR DECISION BEFORE PROCEEDING WITH THE WORK.
- 2. DIMENSIONS SHALL NOT BE OBTAINED BY SCALING THE DRAWINGS. 3. SETTING OUT DIMENSIONS SHOWN ON THE DRAWING SHALL BE VERIFIED BY THE CONTRACTOR. ALL BENCHMARKS ARE TO BE CONFIRMED FOR LEVEL PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- 4. DURING CONSTRUCTION, THE STRUCTURE SHALL BE MAINTAINED IN A STABLE CONDITION AND NO
- PART SHALL BE OVER-STRESSED. 5. TBM'S AND LEVELS ARE SHOWN TO AHD. CONTRACTOR TO PERFORM QUALITY CONTROL SURVEY
- AND MAINTAIN IT DURING THE EXTENT OF THE CONSTRUCTION PERIOD. 6. THE LOCATION OF ALL EXISTING SERVICES HAVE BEEN OBTAINED FROM THE AVAILABLE
- AUTHORITY RECORDS. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL PROVE ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF WORKS. 7. THE CONTRACTOR IS RESPONSIBLE FOR THE LOWERING AND REALIGNMENT OF MINOR
- DISTRIBUTION SERVICES IN CONSULTATION WITH THE RELEVANT CODE OF PRACTICE STIPULATED BY THE ASSET OWNER. ALL EXISTING STREET SIGNS TO BE REINSTATED AS REQUIRED. 8. ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE SPECIFICATIONS AND TO THE
- SATISFACTION OF THE SUPERINTENDENT, COUNCIL, AND THE SERVICE AUTHORITIES. THE SUPERINTENDENT SHALL CARRY OUT REGULAR SITE INSPECTIONS. THE CONTRACTOR SHALL NOTIFY COUNCIL 7 DAYS PRIOR TO COMMENCEMENT OF WORKS.
- 9. THE CONTRACTOR IS TO SUBMIT AN ENVIRONMENTAL MANAGEMENT PLAN IDENTIFYING THE RISKS ASSOCIATED WITH THE WORKS AND CONTROL MEASURES FOR APPROVAL, PRIOR TO COMMENCING WORKS ON SITE. THE EMP MUST COMPLY WITH ALL STATUES, BY-LAWS, STANDARDS, AND SECTION 6.3 OF URBAN STORMWATER - BEST PRACTICE ENVIRONMENTAL MANAGEMENT GUIDELINES. THE CONTRACTOR SHALL CONTROL SEDIMENTATION, EROSION , AND POLLUTION DURING CONSTRUCTION IN ACCORDANCE WITH THE 'GUIDELINES FOR ENVIRONMENTAL MANAGEMENT - DOING IT RIGHT ON SUBDIVISIONS'
- 10. ANY STRUCTURES, PAVEMENTS OR SURFACE DAMAGED, DIRTIED OR MADE UNSERVICEABLE DUE TO CONSTRUCTION WORK SHALL BE REINSTATED TO THE SATISFACTION OF THE SUPERINTENDENT. ALL MATERIAL ASSETS MODIFIED OR DAMAGED BY THE PROPOSED WORKS ARE TO BE REINSTATED TO THE SATISFACTION OF THE LOCAL CITY COUNCIL. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL DAMAGES BY SETTLEMENT SUBSIDENCE OR REMOVAL SUPPORT CONSEQUENT UPON OPERATION UNDER THE CONTRACT AND SHALL MAKE GOOD ALL DAMAGES AT THEIR OWN COST.
- 11. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH THE CURRENT LOCAL COUNCIL'S
- STANDARD DRAWINGS AND TO THE SATISFACTION OF THE COUNCIL SUPERVISING ENGINEER. 12. THE CONTRACTOR SHALL ARRANGE AND PAY ALL FEES TO CONNECT TO COUNCIL'S STORMWATER
- SYSTEM, IN COMPLIANCE WITH COUNCIL REQUIREMENTS. 13. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH AS 4300 AND WITH THE PLANS APPROVED BY THE LOCAL CITY COUNCIL.
- 14. ANY VARIATION TO THE DETAILS SHOWN ON THE DRAWINGS MUST BE AUTHORISED BY THE SUPERINTENDENT PRIOR TO FABRICATION AND/OR CONSTRUCTION.
- 15. ALL CONSTRUCTION WORKS SHALL BE RESTRICTED TO THE HOURS AS ADVISED BY THE SUPERINTENDENT
- 16. THE CONTRACTOR SHALL NOT ENTER OR WORK IN ADJOINING PROPERTIES WITHOUT WRITTEN PERMISSION FROM THE PROPERTY OWNERS OR RESPONSIBLE AUTHORITIES.
- 17. ALL NEW WORKS TO HAVE A SMOOTH JUNCTION WITH EXISTING WORK. 18. ALL PROPERTY ITEMS TO BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURES
- SPECIFICATIONS. ANY ALTERNATIVE PRODUCTS ARE TO BE APPROVED BY THE SUPERINTENDENT PRIOR TO INSTALLATION.
- 19. THE CONTRACTOR IS RESPONSIBLE TO CARRY OUT ALL WORKS WITH ADEQUATELY SKILLED, TRAINED, AND QUALIFIED TRADE WORKERS. 20. IT IS THE MAIN CONTRACTORS RESPONSIBILITY TO SUPPLY THE RELEVANT NOTES.
- SPECIFICATIONS, AND DRAWINGS TO ALL SUB-CONTRACTORS.
- 21. TRAFFIC CONTROL MEASURES ARE TO BE IMPLEMENTED AT ALL TIMES IN ACCORDANCE WITH AS 1742. A SITE SAFETY PLAN IS TO BE PREPARED BY THE CONTRACTOR IN ACCORDANCE WITH THE RELEVANT STANDARDS.
- 22. THE CONTRACTOR IS TO ENSURE THE SITE IS KEPT AT CONSISTENTLY CLEARED OF RUBBISH AND IS MAINTAINED IN A SAFE AND TIDY CONDITION TO THE SATISFACTION OF THE SUPERINTENDENT. 23. THE CONTRACTOR IS TO COMPLY WITH THE REQUIREMENTS OF THE LATEST OCCUPATIONAL
- HEALTH AND SAFETY ACT.
- 24. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY FENCING TO THE SATISFACTION OF THE SUPERINTENDENT DURING THE CONTRACT TO PREVENT UNAUTHORISED ENTRY INTO THE SITE. WITH CONTRACTOR SHALL ALSO REMOVE TEMPORARY FENCING ON COMPLETION OF THE WORK.
- 25. ALL NEW WORKS SHALL MAKE A SMOOTH JUNCTION WITH EXISTING CONDITIONS. 26. ROADS ADJOINING THE SITE MUST BE KEPT CLEAN AND FREE OF ALL EXCAVATED/TRANSPORTED SPOIL MATERIAL

CONCRETE

- 1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600–2018 AND AS 3610–1995 & AS 3610.1-2018 WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
- 2. ALL CONCRETE TO BE 32 MPa WITH A MAXIMUM SLUMP OF 80mm, AND MAXIMUM AGGREGATE SIZE OF 20mm UNO.
- 3. CONCRETE SHALL BE PLACED IN A MANNER THAT AVOIDS SEGREGATION. CONCRETE SHALL NOT BE PLACED IF THE AMBIENT AIR TEMPERATURE IS LESS THAN 5 °C OR GREATER THAN 35 °C. ADDITIONAL PRECAUTIONS MAY NEED TO BE TAKEN IN WINDY CONDITIONS AND/OR TEMP. ABOVE 30°C.
- 4. THE CONTRACTORS SHALL SUBMIT PROPOSED CURING METHODS FOR THE ENGINEERS WRITTEN APPROVAL PRIOR TO CONCRETE POUR. 5. REPAIRS TO CONCRETE SHALL NOT BE ATTEMPTED WITHOUT INSPECTION & PERMISSION OF THE
- ENGINEER
- 6. CONCRETE FORMED SURFACE TO HAVE FINISHED IN ACCORDACE WITH AS 3610-1995 & AS 3610.1-2018 OR AS SPECIFIED OTHERWISE.

EARTHWORKS

- 1. THE CONTRACTOR SHALL INSTALL EFFECTIVE ERROSION AND SEDIMENTATION CONTROL MEASURES TO THE SATISFACTION OF THE SUPERINTENDANT PRIOR TO COMMENCING EARTHWORKS. THESE MEASURES SHALL BE MAINTAINED FOR THE DURATION OF THE CONTRACT.
- 2. ADEQUATE DRAINAGE OF ALL WORKING AREAS SHALL BE MAINTAINED THROUGHOUT THE PERIOD OF CONSTRUCTION TO ENSURE RUN-OFF OF WATER WITHOUT PONDING, EXCEPT WHERE PONDING FORMS PART OF AN APPROVED EROSION AND AND SEDIMENTATION CONTROL SYSTEM. 3. THE CONTRACTOR SHALL OBTAIN THE WRITEN CONSENT OF THE SUPERINTENDANT OR THE USE OF
- ANY STOCKPILE WITE WHICH IS NOT SHOWN ON THE DRAWINGS. PROPOSAL IN THIS REGARD SHALL BE SUBMITTED AT LEAST THREE WORKING DAYS BEFORE STOCKPILING IS DUE TO COMMENCE AND SHALL SPECIFY THE MAXIMUM DIMENSIONS OF THE PROPOSAL.
- 4. COMPACTION OF ALL MATERIALS INCLUDING ROAD SURFACES SHALL BE AS SPECIFIED BY THE GEOTECHINCAL ENGINEER.

STORMWATER DRAINAGE

- 1. ALL STORMWATER WORKS ARE TO BE UNDERTAKEN GENERALLY IN ACCORDANCE WITH AS/NZS 3500.3-2021 STORMWATER DRAINAGE
- 2. PIPES OF 300mm DIA. AND UNDER SHALL BE UPVC TO AS/NZS 1254-2010. 3. PIPES OF 375mm DIA. AND LARGER SHALL BE FRC OR CONCRETE CLASS 2 TO AS/NZS 4058-2007, RUBBER RING JOINTED U.N.O.
- 4. PIPES UP TO 150mm DIA. SHALL BE LAID AT A MINIMUM GRADE OF 1.0%. PIPES 225mm DIA. AND OVER TO BE LAID AT A MINIMUM GRADE OF 0.5%. UNO. BEDDING MATERIAL TO AS/NZS 2032-2006 OR AS/NZS 3725-2007 AS APPROPRIATE.
- 5. MINIMUM COVER TO PIPES 300mm DIA. AND OVER GENERALLY SHALL BE 450mm IN CARPARK & ROADWAY AREAS U.N.O.
- 6. UNLESS NOTED OTHERWISE, ALL CONCRETE PIPE ARE TO BE CLASS 2 AND RUBBER RING JOINTED. RUBBER RINGS SHALL BE MANUFACTURED AND TESTED IN ACCORDANCE WITH AS 1646-2007. THE EXCAVATED TRENCH WIDTH FOR PIPE LAYING MUST BE AT LEAST 400mm WIDER THAN THE OUTER DIAMETER OF THE PIPE. PIPES ARE TO BE LAID CENTRALLY WITHIN THE EXCAVATED TRENCH.
- 7. ALL PIPEWORK SHALL BE BEDDED ON A CONTINUOUS UNDERLAY OF SAND, NOT LESS THAN 75mm THK. IN OTHER THAN ROCK AND 200mm THK. IN ROCK AFTER COMPACTION. THE SAND SHALL BE GRADED IN ACCORDANCE WITH AS/NZS 3500.3-2021 AND COMPACTED TO AT LEAST 90% OF THE MAXIMUM DRY DENSITY AND SHALL BE GRADED EVENLY WITH THE ADDITIONAL BEDDING.
- 8. THE BED AND HAUNCH MATERIAL SHALL BE COMPACTED FOR THE FULL WIDTH OF THE TRENCH BY A MINIMUM OF TWO PASSES OF A VIBRATING PLATE OR HAND TAMPING METHODS TO THE SATISFACTION OF THE SUPERINTENDENT 9. CHASES SHALL BE FORMED WHERE NECESSARY TO PREVENT SOCKETS, FLANGES OR THE LIKE FROM BEARING ON THE
- BOTTOM OF THE TRENCH. 10. THE CONTRACTOR MUST LEAVE ALL STORMWATER DRAINAGE WORKS UNCOVERED UNTIL ANY TESTING DEEMED
- NECESSARY BY THE SUPERINTENDENT HAS BEEN PERFORMED. 11. THE CONTRACTOR SHALL ENSURE THAT ANY EXISTING STRUCTURES LOCATED ADJACENT TO EXCAVATED TRENCHES ARE SUPPORTED OR PROTECTED TO PREVENT DAMAGE TO OR MOVEMENT TO THESE STRUCTURES. 12. PIPE LAYING SHALL BEGIN AT THE DOWNSTREAM END OF THE LINE WITH THE SOCKET ENDS OF THE PIPE FACING
- UPSTREAM. THE BARREL OF EACH PIPE SHALL BE IN CONTACT WITH THE BEDDING MATERIAL THROUGHOUT ITS FULL LENGTH.
- 13. FOR RUBBER RING JOINTS THE PIPE ENDS SHALL BE TIGHTLY JOINED WITH THEIR INNER SURFACES AT THE MANUFACTURES NOMINATED LAYING GAP.
- 14. LIFTING HOLES IN PIPES SHALL BE PLUGGED WITH MORTAR, PRECAST TAPERED PLUGS, OR TAPE SURROUNDINGS OR OTHER APPROVED MEANS PRIOR TO BACKFILL MATERIAL BEING PLACED. 15. CUTTING OPERATIONS FOR CONCRETE PIPES SHALL PROVIDE NEAT END SURFACES. THE CUT SURFACES SHALL BE
- GIVEN TWO COATS OF A APPROVED EPOXY PAINT. 16. COMPLETED CEMENT MORTAR JOINTS SHALL BE KEPT DAMP AND PROTECTED FROM THE DIRECT RAYS OF THE SUN
- UNTIL BACKFILLED.
- 17. DRAINAGE LINES SHALL BE CONSTRUCTED TO THE TOLERANCES IN ACCORDANCE WITH THE RELIANT AUSTRALIAN STANDARDS, SUPERINTENDENTS SPECIFICATIONS AND THE MANUFACTURES SPECIFICATIONS. 18. BACKFILL MATERIAL SHALL BE INSPECTED AND APPROVED BY THE SUPERINTENDENT PRIOR TO PLACING AND COMPACTION.
- 19. ALL BACKFILL FOR STORMWATER DRAINAGE WORKS IS TO BE COMPACTED IN LAYERS NOT EXCEEDING 30mm LOOSE THICKNESS AND COMPACTED WITHOUT DAMAGING OR DISPLACING THE PIPEWORK.
- 20. STEP IRONS AT SPACINGS OF 300m ARE TO BE PROVIDED IN DRAINAGE PITS MORE THAN 0.9m DEEP U.N.O. 21. PROVIDE 3.0m LENGTH OF Ø100 SUBSOIL DRAINAGE PIPE WRAPPED IN FABRIC SOCK AT UPSTREAM END OF EACH PIT. 22. UNLESS OTHERWISE SPECIFIED, ALL DRAINAGE GRATES TO BE CLASS "C" GALVANISED MILD STEEL TO AS 3996-2019. 23. upvc pipes shall be transported. Handled, and stored in accordance with the manufactures
- SPECIFICATIONS. 24. uPVC PIPE LAYING SHALL BEGIN AT THE DOWNSTREAM END OF THE LINE WITH THE SOCKET END OF THE PIPE FACING UPSTREAM. WHEN THE PIPES ARE LAID. THE BARREL OF EACH PIPE SHALL BE IN CONTACT WIT THE BEDDING
- MATERIAL THROUGHOUT ITS FULL LENGTH.
- 25. THE UPVC PIPE ENDS SHALL BE THOROUGHLY CLEANED BEFORE THE JOINT IS MADE. JOINTING SHALL BE IN ACCORDANCE WIT THE MANUFACTURES SPECIFICATIONS WITH JOINTING SOLVENT AND PRIMER.

RAINWATER TANK

- 1. PUMP FOR RAINWATER TANK TO BE CONNECTED TO TOILETS, LAUNDRY AND GARDEN TAP FOR IRRIGATION. 2. PUMP MUST HAVE MAINS WATER BACKUP WITH AN APPROVED BACKFLOW PREVENTION DEVICE. DEVICE TO BE ACCESSIBLE FOR TESTING
- 3. A FIRST FLUSH DEVICE OR FILTER BAG IS TO BE INSTALLED.
- 4. RAINWATER TANK MUST NOT BE CONNECTED TO THE MAIN DRINKING WATER SUPPLY. 5. RAINWATER TANK MUST CONTAIN A BYPASS OF THE PUMP IN THE EVENT OF A POWER FAILURE. 6. RAINWATER TANK MUST BE CONSTRUCTED IN ACCORDANCE WITH AUSTRALIAN STANDARD. AS/NZS 3500.1.-2021: NATIONAL PLUMBING AND DRAINAGE - WATER SUPPLY- ACCEPTABLE SOLUTIONS, WHICH PROVIDES GUIDANCE ON
- THE DESIGN OF STORMWATER AND RAINWATER REUSE SYSTEMS. RAINWATER TANK MUST BE PROVIDED WITH AN AIR GAP (SEE AS/NZS 3500.1-2021 AND AS 2845.2-2010) 8. RAINWATER TANK MUST BE KEPT WELL MAINTAINED AND CLEANED IN ACCORDANCE WITH THE MANUFACTURING
- REQUIREMENTS AND THE REQUIREMENTS OF SYDNEY WATER.

BUILDER TO CHECK & VERIFY ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT OF WORK IT IS THE OWNERS RESPONSIBILITY TO ENSURE THAT THE ENGINEER

DO NOT SCALE FROM DRAWINGS. USE WRITTEN DIMENSIONS ONLY

HAS INVESTIGATED SUBSOIL CONDITIONS & DESIGNED ALL STRUCTURAL ELEMENTS TO SUIT THE DESIGN & DETAILS CONTAINED ON THIS DRAWING IS SUPPLIED IN CONFIDENCE & IS NOT TO BE USED FOR ANY OTHER PURPOSE. EXCEPT THAT AUTHORISED BY MSL CONSULTING ENGINEERS



LEVEL 4, 12 DARCY STREET PARRAMATTA NSW 2150 PHONE No (02) 9354 1836 Homes NSW PPROVED PLANS Date: 21 March 2025 Project No.: BGYVZ

MSL Consulting Engineers Pty Limited ABN 72 903 080 591 ACN 142 291 165 Suite 102 - 62 Harbour St. Wollongong PO Box 567 Dapto NSW p: 02 4226 5247 e: info@mslengineers.com.au w: www.mslengineers.com.au

| | F | 27.11.2024 | ISSUED FOR D.A. |
|-----|-----|------------|---|
| | E | 29.11.2023 | ISSUED FOR D.A. |
| | D | 19.06.2023 | ISSUED FOR D.A. |
| | С | 10.05.2023 | ISSUED FOR D.A. |
| NSW | В | 17.04.2023 | ISSUED FOR D.A. |
| | REV | DATE | NOTATION/AMENDMENT |
| | | DO NOT S | SCALE DRAWINGS. CHECK ALL DIMENSIC FIGURED DIMENSIONS TAKE PRECEDENC |

- EROSION, SEDIMENT AND SITE MANAGEMENT SEQUENCE OF OPERATIONS PROVIDE SHAKE DOWN PAD AT ENTRY OF SITE EC01 ALL EROSION AND SILTATION CONTROL DEVICES ARE TO BE PLACED PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCT SEDIMENT FENCING (REFER DETAILS) CONSTRUCTION WORKS. THE LOCATION OF SUCH DEVICES (SHOWN ON THIS DRAWINGS) IS INDICATIVE ONLY CONSTRUCT DRAINAGE & CIVIL WORKS (MODIFY SEDIMENT CONTROL DRAINS TO SUIT AND FINAL POSITION SHOULD BE DETERMINED ON SITE. CONSTRUCTION. EC02 SURPLUS TOPSOIL SHALL BE STOCKPILED WHERE DIRECTED. DIVERSION BANKS ARE TO BE PLACED PITS & PIPES TO BE PROTECTED WITH FILTER BARRIERS REFER DETAILS UPSTREAM AND SHALL DISCHARGE TO SEDIMENT BARRIERS. ALL STOCKPILES ARE TO BE VEGETATED WITHIN AT COMPLETION OF ALL WORKS REVEGETATE BATTERS WITHIN 14 DAYS 14 DAYS OF FORMATION. SILT FENCES ARE TO BE PLACED ON THE DOWNSTREAM FACE. AFTER COMPLETION OF BUILDING WORKS, ALL CONTROL MEASURES CAN BE REMOVED. EC03 DURING TRENCH EXCAVATION ALL SPOIL SHALL BE MOUNDED ON THE UPHILL SIDE OF TRENCHES AND PLACEMENT IS TO COMPLY WITH THE SUPERINTENDENTS REQUIREMENTS. EC04 PROVIDE SEDIMENT TRAPS TO ALL INLET PITS. EC05 ALL TURF SODS AND SEEDED AREAS ARE TO BE WATERED AND FERTILISED AS DIRECTED. MAINTENANCE PROCEDURES DURING EC06 ALL EROSION AND SILTATION CONTROL DEVICES ARE TO BE CLEARED OF DEPOSITED SILT AND MAINTAINED TO THE SATISFACTION OF THE SUPERINTENDENT. CONSTRUCTION EC07 GENERALLY BARRIERS SHOULD BE PLACED APPROXIMATELY 5.0 METRES OUTSIDE POTENTIAL DISTURBED AREAS. EC09 A LOG BOOK OR OTHER SUITABLE RECORDS MUST BE KEPT BY THE SITE SUPERVISOR IN ACCORDANCE WITH THE EPA'S REQUIREMENTS. 1 ALL EROSION CONTROL MEASURES ARE TO BE MAINTAINED AT ALL TIMES SO THAT THOSE EC08 CONTRACTOR TO FOLLOW THE RECOMMENDED SEQUENCE OF OPERATIONS AS SPECIFIED BY THE DEPARTMENT OF CONSERVATION AND LAND MANAGEMENT IN THE BROCHURE "PREPARING SOIL AND MEASURES ARE FULLY FUNCTIONAL/OPERATIONAL DURING THE CURRENCY OR WORKS. ALL SUCH CONTROLS MUST ALSO BE FULLY FUNCTIONAL/OPERATIONAL. SHOULD WORK OPERATIONS CEASE WATER MANAGEMENT PLANS". TEMPORARILY, (e.g. WEEKENDS, ROSTERED DAYS OFF, etc.) EC10 BUILDER IS TO CONDUCT WORKS IN ACCORDANCE WITH COUNCILS CONDITION TO DUST SUPPRESSION AND RESPREAD MATERIAL GAINED DURING MAINTENANCE OPERATION OR SEDIMENT REMOVAL MEASURES ALTERNATIVELY PLACE ON STOCKPILES. EC11 BUILDER TO CONFIRM LOCATION OF STOCKPILES, FENCING, STABILISED ACCESS ETC. ON COMMENCEMENT OF NON-COMPLIANCE WITH AGREED PERFORMANCE CRITERIA WILL BE IDENTIFIED BY WORK. ENGINEER TO BE NOTIFIED. VISUAL INSPECTIONS IDENTIFYING EC12 WASTE MATERIALS ARE TO BE STOCKPILED OR LOADED INTO SKIP-BINS LOCATED AS SHOWN ON PLAN. BUILD-UP OF SEDIMENT OFF THE SITE EC13 STOCKPILES OF LOOSE MATERIALS SUCH AS SAND, SOIL, GRAVEL MUST BE COVERED WITH GEOTEXTILE EXCESSIVE SEDIMENT BUILD-UP ON THE SITE SILT FENCE MATERIAL. PLASTIC SHEETING OR MEMBRANE MUST NOT BE USED. SAFETY BARRICADING EXCESSIVE EROSION ON THE SITE SHOULD BE USED TO ISOLATE STOCKPILES OF SOLID MATERIALS SUCH AS STEEL REINFORCING, RELEASE OF CONSTRUCTION MATERIAL FROM THE SITE FORMWORK, SCAFFOLDING. POOR VEGETATION ESTABLISHMENT EC14 TRUCKS REMOVING EXCAVATED / DEMOLISHED MATERIAL SHOULD TRAVEL ON STABILISED POORLY MAINTAINED, DAMAGED OR FAILED ESC DEVICES. CONSTRUCTION PATHS. MATERIAL TO BE TAKEN TO THE TRUCK TO REDUCE TRUCK MOVEMENT ON SITE. DETERIORATED WATER QUALITY IDENTIFIED BY THE ENVIRONMENTAL CONSULTANT AS BEING TRUCKS TO BE LIMITED TO SINGLE UNIT HEAVY RIGID VEHICLES. (NO SEMITRAILERS) ATTRIBUTABLE TO THE CONSTRUCTION ACTIVITIES. EC15 ANY SEDIMENT DEPOSITED ON THE PUBLIC WAY, INCLUDING FOOTPATH RESERVE AND ROAD SURFACE, IS BUILD-UP OF SEDIMENT OFF THE SITE - THE MATERIAL MUST BE COLLECTED AND DISPOSED OF IN A TO BE REMOVED IMMEDIATELY. MANNER THAT WILL NOT CAUSE ONGOING ENVIRONMENTAL NUISANCE OR HARM: THEN ON-SITE ESC EC16 PROVIDE BARRIERS AROUND ALL CONSTRUCTION WORKS WITHIN THE FOOTPATH AREA TO PROVIDE SAFE MEASURES AMENDED, WHERE APPROPRIATE, TO REDUCE THE RISK OF FURTHER SEDIMENTATION. EXCESSIVE SEDIMENT BUILD-UP ON THE SITE - COLLECT AND DISPOSE OF MATERIAL. THEN AMEND ACCESS FOR PEDESTRIANS. UP-SLOPE DRAINAGE AND/OR EROSION CONTROL MEASURES AS APPROPRIATE TO REDUCE FURTHER EC17 CONCRETE PUMPS AND CRANES ARE TO OPERATE FROM WITHIN THE BALLAST ENTRY DRIVEWAY AREA AND ARE NOT TO OPERATE FROM THE PUBLIC ROADWAY UNLESS SPECIFIC COUNCIL PERMISSION IS OCCURRENCE. OBTAINED. SEDIMENT FENCE FAILURE – REPLACE AND MONITOR MORE FREQUENTLY. REGULAR FAILURES MAY MEAN EC18 DELIVERY VEHICLES MUST NOT STAND WITHIN THE PUBLIC ROADWAY FOR MORE THAN 20 MINUTES AT A THAT THE SEDIMENT FENCE LOCATION, ALIGNMENT OR INSTALLATION MAY NEED TO BE AMENDED. IF THE RELEASE OF EXCESSIVE SEDIMENT AND/OR OTHER MATERIALS OFF THE SITE OCCURS, OR WATER EC19 ANY EXCAVATION WORK ADJACENT TO ADJOINING PROPERTIES OR THE PUBLIC ROADWAY IS NOT TO BE QUALITY MONITORING INDICATES LEVELS ARE NOT WITHIN THE WQOS, CLEAN UP DEPOSITION, AND COMMENCED UNTIL THE STRUCTURAL ENGINEER IS CONSULTED AND SPECIFIC INSTRUCTIONS RECEIVED INSPECT ALL CONTROL MEASURES.
- FROM THE ENGINEER. EC20 TOILET FACILITIES MUST BE EITHER A FLUSHING TYPE OR APPROVED PORTABLE CHEMICAL CLOSET.
- CHEMICAL CLOSETS ARE TO BE MAINTAINED & SERVICED ON A REGULAR BASIS SO THAT OFFENSIVE ODOUR IS NOT EMITTED.
- EC21 ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH LOCAL CITY COUNCIL ENVIRONMENTAL SITE MANAGEMENT DEVELOPMENT CONTROL PLAN DOCUMENTS, CURRENT EDITION.
- EC23 IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL MEASURES ARE TAKEN DURING THE COURSE OF THE CONSTRUCTION TO PREVENT SEDIMENT EROSION AND POLLUTION OF THE DOWNSTREAM SYSTEM, SUPERVISING ENGINEER SHOULD BE CONTACTED IF IN DOUBT. ALL SEDIMENT CONTROL STRUCTURES TO BE INSPECTED AFTER EACH RAINFALL EVENT FOR STRUCTURAL DAMAGE AND TRAPPED SEDIMENT TO BE REMOVED TO A NOMINATED SOIL STOCKPILE SITE.
- EC22 PROVIDE BARRIERS AROUND ALL CONSTRUCTION WORKS WITHIN THE FOOT PATH AREA TO PROVIDE SAFE ACCESS FOR PEDESTRIANS.

ROCK WORKS

- 1. ROCK SIZES ARE SPECIFIED ACCORDING TO THEIR POSITION AND RESISTANCE TO HYDRAULIC FORCES THE ROCK HAS BEEN SHOWN SCHEMATICALLY IN THE DRAWINGS AND SHALL BE 100mm NOMINAL SIZE.
- ROCK SUPPLIED FOR THE WORKS MUST BE HARD, DURABLE, AND LOCALLY SOURCED
- 3. ROCK IN THE FORM OF BLOCKS WITH ANGULAR EDGES IS REQUIRED TO ENSURE CONSISTENT
- INTERLOCKING DURING PLACEMENT. 4. ROCK IS TO BE IN THE NATURAL FORM AND NOT CUT OF SHAPED.
- 5. ALL GAPS WITHIN ROCK TO BE FILLED WITH COARSE GRAVEL TO THE TOP AND THEN FILLED WITH A FILTER MEDIA. THIS GRADED ROCK IS TO BE OVERLAID ON A COARSE GRAVEL BEDDING WITH A MIN. 20mm THICKNESS. PROVIDE A GEOTEXTILE FABRIC BIDIM A64 OR APPROVED EQUIVALENT.


| PROJECT MANAGER | STRUCTURAL / STORMWATER / CIVIL CONSULTANT | BUSINESS PARTNER: | | PROJECT: |
|---|---|-------------------|-------|----------------------------------|
| HOMES NSW PH (02) 9354 1836 | MSL CONSULTING ENGINEERS PTY LTD PH (02) 4226 5247 | | | SENIORS HOUSING DEVELOPME |
| ARCHITECT | HYDRAULIC CONSULTANT | | | |
| DTA Architects Pty Ltd | ABEL & BROWN PTY LTD | | | at |
| PH (02) 9601 1011 | PH (02) 9709 5705 | NICIAL | Homes | Lots 346-350 in DP31990 & Lot 30 |
| ELECTRICAL / BASIX CONSULTANT | LANDSCAPE CONSULTANT | NSW | NSW | 2-10 BIRCH STREET & 20 DEBRIN |
| GREENVIEW CONSULTING PTY LTD PH (02) 8544 1683 | RAY FUGGLE & ASSOCIATED PTY LTD PH 0412 294 712 | GOVERNMENT | | NORTH ST MARYS NSW 2760 |

| | | | | PURP | OSE ONLY | |
|---------------|---------------------|------------------------|-------------------|--------------------|----------------|--------------------------|
| | SPECIFICATION SHEET | | STATUS: DA ISSUE | | | |
| IENT | | | date: 27/11/24 | SCALE: NTS @ A1 | PROJ: BGYVZ | ^{ЈОВ:} 22084 |
| 05 in DP30223 | | | STAGE: B | DRAWN: TP/WT | CHECKED: MP | |
| | FILE: | PLOTTED: 27/11/2024 | SW | SHEET: | of 8 | REV: |


40MM


0 5 10 20

SCALE FOR PRINTING



| SYMBOLS & NOTATION | | | | |
|--------------------|---|--|--|--|
| | Ø150 STORMWATER DRAINAGE LINE @ 1% MIN GRADE U.N.O. TO STORMFILTER CHAMBER | | | |
| | Ø150 STORMWATER DRAINAGE LINE @ 1% MIN GRADE, FROM ROOF CATCHMENT TO RW TANK | | | |
| | 600 OR 900 SQUARE GRATED PIT FITTED WITH OCEANGUARD BASKETS U.N.O. | | | |
| | 450 SQUARE GRATED PIT | | | |
| | 900 SQUARE SEALED LID PIT | | | |
| 150 TG | 150 WIDE TRENCH GRATE @ MIN. 1.0% BASE FALL | | | |
| 200 TG | 200 WIDE TRENCH GRATE @ MIN. 1.0% BASE FALL | | | |
| 300 TG | 300 WIDE TRENCH GRATE @ MIN. 1.0% BASE FALL | | | |
| DP1 o | DOWNPIPE FROM UPPER & LOWER ROOF (REFER TO HYDRAULIC DRAWINGS FOR SIZE) | | | |
| DP2 0 | DOWNPIPE FROM BALCONY & CONCRETE AWNING (REFER TO HYDRAULIC DRAWINGS FOR SIZE) | | | |
| P0 0 | PATIO OUTLET | | | |
| GD | DOOR ENTRY GRATE DRAIN | | | |






DO NOT SCALE FROM DRAWINGS. USE WRITTEN DIMENSIONS ONLY. BUILDER TO CHECK & VERIFY ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT OF WORK. IT IS THE OWNERS RESPONSIBILITY TO ENSURE THAT THE ENGINEER

HAS INVESTIGATED SUBSOIL CONDITIONS & DESIGNED ALL STRUCTURAL ELEMENTS TO SUIT. THE DESIGN & DETAILS CONTAINED ON THIS DRAWING IS SUPPLIED IN CONFIDENCE & IS NOT TO BE USED FOR ANY OTHER PURPOSE, EXCEPT THAT AUTHORISED BY MSL CONSULTING ENGINEERS




LEVEL 4, 12 DARCY STREET PARRAMATTA NSW 2150 PHONE No (02) 9354 1836 Homes NSW APPROVED PLANS PART 5 (DIV 5.1) MODIFIED ACTIVITY DETERMINATION Date: 21 March 2025 Project No.: BGYVZ Homes NSW

SL 38.97




| SYMBOLS & NOTATION | | | | |
|--------------------|---|--|--|--|
| | Ø150 STORMWATER DRAINAGE LINE @ 1% MIN GRADE U.N.O. TO STORMFILTER CHAMBER | | | |
| | Ø150 STORMWATER DRAINAGE LINE @ 1% MIN GRADE, FROM ROOF CATCHMENT TO RW TANK | | | |
| | 600 OR 900 SQUARE GRATED PIT FITTED WITH OCEANGUARD BASKETS U.N.O. | | | |
| | 450 SQUARE GRATED PIT | | | |
| | 900 SQUARE SEALED LID PIT | | | |
| 150 TG | 150 WIDE TRENCH GRATE @ MIN. 1.0% BASE FALL | | | |
| 200 TG | 200 WIDE TRENCH GRATE @ MIN. 1.0% BASE FALL | | | |
| 300 TG | 300 WIDE TRENCH GRATE @ MIN. 1.0% BASE FALL | | | |
| DP1 o | DOWNPIPE FROM UPPER & LOWER ROOF (REFER TO HYDRAULIC DRAWINGS FOR SIZE) | | | |
| DP2 o | DOWNPIPE FROM BALCONY & CONCRETE AWNING (REFER TO HYDRAULIC DRAWINGS FOR SIZE) | | | |
| P0 0 | PATIO OUTLET | | | |
| GD | DOOR ENTRY GRATE DRAIN | | | |





| | PROJECT MANAGER | STRUCTURAL / STORMWATER / CIVIL CONSULTANT | BUSINESS PARTNER: | | PROJECT: |
|-----------------|-------------------------------|--|-------------------|-------|---------------------------------|
| | HOMES NSW | MSL CONSULTING ENGINEERS PTY LTD | | | SENIORS HOUSING DEVELOP |
| | PH (02) 9354 1836 | PH (02) 4226 5247 | | | SENIORS HOUSING DEVELOPIN |
| | | | | | - 4 |
| | | ABEL & BROWN PTY LTD PH (02) 9709 5705 | | Homes | |
| | ELECTRICAL / BASIX CONSULTANT | | | | Lots 346-350 in DP31990 & Lot 3 |
| ISIONS ON SITE. | GREENVIEW CONSULTING PTY LTD | RAY FUGGLE & ASSOCIATED PTY LTD | GOVERNMENT | NSW | 2-10 BIRCH STREET & 20 DEBR |
| NCE. | PH (02) 8544 1683 | PH 0412 294 712 | | | NORTH ST MARYS NSW 2760 |



TYPICAL SURFACE INLET PIT -NATURAL SURFACE

NOT TO SCALE

1


NOTES : ALTERNATIVE PIT CONSTRUCTION MAY BE USED, SUBJECT TO THE ENGINEERS APPROVAL

| Depth to Invert | Pit Internal Dimensions | | |
|-----------------|----------------------------|--|--|
| ≼600 | 450x450 | | |
| >600 ≤900 | 600×600 | | |
| >900 ≤1200 | 600×900 | | |
| >1200 | 900×900 | | |
| >900 <1200 | 600x900 | | |

2. PROVIDE STEP IRONS UNDER LID AT 300 CTS. TO COUNCIL SPECIFICATIONS WHERE PIT DEPTH IS DEEPER THAN 900mm.

- 3. REINFORCEMENT NOTED IS ONLY REQUIRED FOR PITS EXCEEDING 900 DEEP, SUBJECT TO COUNCIL REQUIREMENTS. PITS GREATER THAN 2500 mm DEEP WILL REQUIRE STRUCTURAL ENGINEER'S DESIGN.
- 4. PROVIDE Ø90 x 3000 LONG SUBSOIL DRAINAGE STUB PIPE SURROUNDED WITH 100mm THICKNESS OF NOMINAL 20mm COARSE FILTER MATERIAL WRAPPED IN GEOTEXTILE FILTER FABRIC (BIDUM A24 OR APPROVED SIMILAR), TO BE PARALLEL TO UPSTREAM SIDE OF EACH INLET PIPE.
- 5. ALTERNATIVE PIT CONSTRUCTION MAY BE USED SUBJECT TO THE ENGINEERS APPROVAL.

6. CONCRETE STRENGTH f'c = 32 MPa



DO NOT SCALE FROM DRAWINGS. USE WRITTEN DIMENSIONS ONLY. BUILDER TO CHECK & VERIFY ALL DIMENSIONS & LEVELS PRIOR TO COMMENCEMENT OF WORK. IT IS THE OWNERS RESPONSIBILITY TO ENSURE THAT THE ENGINEER HAS INVESTIGATED SUBSOIL CONDITIONS & DESIGNED ALL


STRUCTURAL ELEMENTS TO SUIT. THE DESIGN & DETAILS CONTAINED ON THIS DRAWING IS SUPPLIED IN CONFIDENCE & IS NOT TO BE USED FOR ANY OTHER PURPOSE, EXCEPT THAT AUTHORISED BY MSL CONSULTING ENGINEERS




LEVEL 4, 12 DARCY STREET PARRAMATTA NSW 2150 PHONE No (02) 9354 1836 Homes NSW APPROVED PLANS PART 5 (DIV 5.1) MODIFIED A Date: 21 March 2025 Project No.: BGYVZ

Homes NSW







27/11/2024

6 of 8

F

| | PROJECT MANAGER HOMES NSW | STRUCTURAL / STORMWATER / CIVIL CONSULTANT MSL CONSULTING ENGINEERS PTY LTD | BUSINESS PARTNER: | | PROJECT: |
|----------------------|--|--|-------------------|-------|--|
| | PH (02) 9354 1836 | PH (02) 4226 5247 | | | SENIORS HOUSING DEVELOPN |
| | ARCHITECT DTA Architects Pty Ltd | HYDRAULIC CONSULTANT ABEL & BROWN PTY LTD | | Homoo | at |
| | PH (02) 9601 1011 | PH (02) 9709 5705 | NSW | Homes | Lots 346-350 in DP31990 & Lot 3 |
| ions on site. Ce. | ELECTRICAL / BASIX CONSULTANT GREENVIEW CONSULTING PTY LTD PH (02) 8544 1683 | LANDSCAPE CONSULTANT RAY FUGGLE & ASSOCIATED PTY LTD PH 0412 294 712 | GOVERNMENT | NSW | 2-10 BIRCH STREET & 20 DEBR NORTH ST MARYS NSW 2760 |

