



CIVIL STORMWATER MANAGEMENT REPORT

Richmond Agricultural Centre

2 College Street, Richmond NSW

Ref: SY240854-00-CV-RP01

Rev: 2

Date: 26 May 2025

PREPARED FOR

Richard Crookes Constructions Pty Ltd

Level 14, 558 Pacific Highway

St Leonards NSW 2065

Project:	Richmond Argricultural Centre
Document Title:	Civil Report
Client:	Richard Crookes Constructions Pty Ltd
Revision:	2
Status:	Issue for Information
Revision Date:	26 May 2025
Author:	Nicole Sutherland

Table of Contents

1.	Introduction.....	3
1.1	General.....	3
1.2	Site Description	3
1.3	Project Description	6
1.4	Referenced Documents	7
1.5	Referenced Standards and Guidelines	7
2.	Existing Authority Services and Connections	8
2.1	General.....	8
2.2	Applicable Planning Controls	8
2.3	Civil.....	8
3.	Site Conditions	9
3.1	General.....	9
3.2	Civil.....	9
4.	Proposed New Works	10
4.1	Proposed Civil Works.....	10
4.2	Stormwater Quantity Management	10
5.	Early and Enabling Works.....	12
5.1	Civil.....	12
6.	Mitigation Measures	14
7.	Appendix A – Civil REF Drawings.....	15

1. Introduction

1.1 General

This Civil Stormwater Management Report has been prepared by Northrop Engineers Pty Ltd on behalf of the Department of Education (DoE) (the Proponent) to assess the potential environmental impacts that could arise from the activities associated with the Richmond Agricultural Centre development at 2 College Street Richmond (Part Lot 2 DP1051798) (the site).

1.2 Site Description

The Site is located on 2 College Street, Richmond (Part Lot 2 DP 1051798). The site is located within the Hawkesbury City Council area and is zoned SP1 Special Activities (the SP1 zone) by the *Hawkesbury Local Environmental Plan 2012* (the LEP).

Figure 1 is a site plan showing the location of the proposed Richmond Agricultural Centre within its regional context. **Figure 2** is an aerial image of the site and its immediate surrounds




Figure 1: Location of the proposed Richmond Agricultural Centre (source: ePlanning Spatial Viewer).



Figure 2: Aerial image of the site showing the location of the proposed Richmond Agricultural Centre (source: Nearmap, dated 27 October 2024).

The boundary of the REF works is shown in **Figure 3** and comprises:

- Leased area: This is the area of land leased by the Department of Education from Western Sydney University (WSU) for the proposed Richmond Agricultural Centre. This area comprises 14.25 ha of land with frontage to College Drive of 480 meters. The future school site comprises existing agricultural land within the WSU campus bound by College Drive to the east, Londonderry Road to the west, WSU facilities to the south and vacant WSU agricultural land to the north.
- WSU Campus: This the area of land between the leased area and College Drive




Figure 3: Extent of proposed works at Richmond Agricultural Centre (source: NBRS Architecture).

1.3 Project Description

This Civil Stormwater Management Report has been prepared by Northrop on behalf of the Department of Education (DoE) (the Proponent) to assess the potential environmental impacts that could arise from the activities associated with the Richmond Agricultural Centre development at 2 College Street Richmond (Part Lot 2 DP1051798) (the site).

The report has been prepared to outline the proposed management of stormwater for the Richmond Agricultural Centre.

This report accompanies a Review of Environmental Factors (REF) that seeks approval for the construction and operation of the agricultural centre which will provide facilities for a specialist agricultural curriculum at the site. The activities associated with establishing the Richmond Agricultural Centre involves the following works:

- The removal of trees and fencing
- Construction of a general learning hub
- Construction of a science hub
- Construction of a multipurpose hall
- Construction of an administration building
- Construction of canteen and amenities building
- Construction of a new parking area (including accessible spaces) driveway and kiss and drop facilities
- The provision of outdoor agricultural learning areas comprising:
 - Agricultural plots
 - Aboriginal enterprise
 - Agricultural shed and greenhouse
 - Animal plots with associated stock yard, animal shelters, troughs and stock lane
 - Gravel access road with wash bay
- Landscaping including new trees, entry forecourt, village green and kitchen garden
- Ancillary services and infrastructure upgrades including new substation and HV Works, sewer pump station, water booster, dual carriage vehicle access and pedestrian paths
- Wayfinding and school identification signage

For a detailed project description, please refer to the Review of Environmental Factors (REF) prepared by EPM Projects.

1.4 Referenced Documents

The following external documents have been used in reference to this report.

Documents	Description
EFSG – Education Facilities Guidelines	SINSW
Architectural Drawings	Prepared by NBRS
NCC 2022	National Construction Code of Australia 2022
HCC DCP	Hawkesbury Development Control Plan Appendix E – Civil Works Specification

1.5 Referenced Standards and Guidelines

All works shall be in accordance with the following standards unless noted otherwise:

1.5.1 Civil

Reference	Standard Title
NCC 2022	National Construction Code of Australia 2022
AS2890.1-2004	Parking Facilities Part 1: Off Street Car Parking
AS2890.2-2018	Parking Facilities Part 2: Off Street Commercial Vehicle Facilities
AS2890.6-2009	Parking Facilities Part 6: Parking Facilities Off Street parking for People with Disabilities
AS3500.3-2018	Plumbing and Drainage Part 3: Stormwater Drainage

2. Existing Authority Services and Connections

2.1 General

The following section outlines the requirements of existing stormwater on the site.

2.2 Applicable Planning Controls

The site is located within the Western Sydney University precinct part of Hawkesbury City Council's LGA. The site is relatively flat falling from First Ave to College Street. The site is boundary by rural roads, Londonderry Road to the west and College Drive to the East.



Figure 2.1: Mecone Mosaic Map

2.3 Civil

2.3.1 Existing Stormwater Infrastructure – (External) Legal Point of Discharge

The site is relevantly flat and does not have any existing stormwater infrastructure for connection. There is an existing stormwater culvert crossing College Drive, however there is no in-ground stormwater infrastructure on College Drive or Londonderry Drive for the school stormwater connection.

The current site stormwater runoff is uncontrolled sheet flow through the paddocks.

3. Site Conditions

3.1 General

The following section outlines items of the existing site which have implications on the development.

3.2 Civil

3.2.1 Site Topography

The existing site topography generally falls towards the north east to College Drive. The site is flat and therefore the existing stormwater runoff has a high time of concentration.

3.2.2 Access to Site

The main access to the school, both vehicular and pedestrian is on College Drive. There is also vehicular access to the carparking area, waste and delivery areas. These have been rationalized by the project team in consultation with a Traffic and Transport Engineer in developing the proposed layout.

3.2.3 Existing Stormwater Infrastructure (Internal)

There is no in-ground stormwater drainage pit and pipe network on site for connection of this new development.

3.2.4 Flooding

The site is not flood affected in the 1:100 AEP Flood based on the Hawkesbury – Nepean Flood Study, however the site is partially affected in the 1:200 AEP Flood and above, including the PMF. As part of this REF, the proposal is to locate the school above the 1:200 AEP Flood extents. Below is a screenshot of the 1:200 AEP Flood extents.

Refer Northrop's separate reports relating to Flood Emergency Response Strategy, and Flood Impact and Risk Assessment Report for further details.




Figure 3.1 Flood Map 1:200 AEP Flood (Hawkesbury – Nepean River Flood Study)

4. Proposed New Works

4.1 Proposed Civil Works

The following section refer to works associated with the construction of the Richmond Agricultural Centre, Hawkesbury.

4.1.1 Pavements

For the purposes of schematic design, we will design the pavements with consideration to traffic loading specified in the Educational Facilities Guidelines and Standards (5×10^5 ESAs) and an assumed CBR 3%. Based on Geotechnical investigations, the existing subgrade CBR values range from 1.5% to 3% which is relatively low. As the internal driveway and carpark is provided on imported fill material, we have assumed the subgrade CBR of 3% would be achieved.

Should the existing subgrade achieve less than CBR 3, or compaction of the subgrade is not achievable, ground improvement may be required such as lime stabilisation or replacement with a select fill layer such as crushed sandstone.

4.1.2 Stormwater Management Strategy

A stormwater management plan for the development has been prepared by Northrop to satisfy the aims of the documents as stated above. The key elements of the stormwater management include:

- Stormwater Quantity Management
- Stormwater Quality Management

4.2 Stormwater Quantity Management

4.2.1 Major/Minor Design

The major/minor approach to stormwater drainage is the recognised drainage concept for catchments within the Hawkesbury City Council Local Government Area.

The minor drainage system is comprised of below ground pit and pipe network and is designed to control nuisance flooding and enable effective stormwater management for the site. Council requires the minor drainage system to be designed for the critical 5% AEP (~1 in 20-year ARI) event.

The major drainage system is inclusive of overland flow paths which are designed to control and convey flows in excess of the minor system capacity. Council requires the major drainage system to be designed for the critical 1% AEP (1 in 100-year ARI event).

As the site is relatively flat, we are proposing to capture the stormwater runoff through swales and high level culverts discharging the headwalls with scour protection downstream from the development.

4.2.2 On-Site Stormwater Detention (OSD)

Based, on outcomes from a Pre-Lodgement Advice Meeting with Council on 28th January 2025, we note that Council does not require OSD for this development based on the site being flood affected and also limitations with lack of Council's stormwater infrastructure for connection.

In addition, as the site is flat, we note that OSD is not achievable for this development. We note that rainwater tanks for non-potable uses are proposed to capture the new building roof runoff to limit the stormwater runoff discharge.

4.2.3 Stormwater Quality Management

4.2.3.1 Water Quality Objectives

Based, on outcomes from a Pre-Lodgement Advice Meeting with Council on 28th January 2025, we note that Council does not require MUSIC modelling in order to provide a treatment train for water quality measures for this development. This is due to the site being flat and therefore treatment is not feasible. We are proposing to manage the stormwater runoff through swales and discharging to headwalls on the site, which then sheet flows through the agricultural plots.

4.2.3.2 Rainwater Storage and Reuse

A rainwater tank/s has been included to capture all roof water. This water is used for irrigation and toilet flushing re-use where applicable. The overflow is connected to a piped system and discharges freely on site via a headwall and scour protection.

4.2.3.3 Swales

Swales run parallel to the proposed driveway, carpark and buildings to direct upstream overland flows around the development. These help to guide the runoff towards downstream of the development.

4.2.3.4 Stormwater Pit Inserts

For primary pollutant removal from the internal driveway and carpark, stormwater pits are proposed with Oceanguard inserts, supplied by Ocean Protect. These help alleviate Total Suspended Solids (TSS), Total Phosphorous (TP), Total Nitrogen (TN) and Gross Pollutants (GP)

5. Early and Enabling Works

5.1 Civil

5.1.1 Sediment and Soil Erosion Control

The objectives of the erosion and sediment control for the development site are to ensure:

- Adequate erosion and sediment control measures are applied prior to the commencement of construction and are maintained throughout construction; and
- Construction site runoff is appropriately treated in accordance with Hawkesbury City Council's requirements.

As part of the works, the erosion and sedimentation control will be constructed in accordance with Council requirements and "Managing Urban Stormwater Soil & Construction" 2004 (Blue Book) prepared by Landcom, prior to any earthworks commencing on site.

5.1.2 Sediment Basin

A temporary sediment basin has been designed to capture site runoff during construction and has been located towards the north eastern side of the site, in the lowest point. The construction of the basin will be undertaken in stages to enable maximum runoff capture assisted by diversion swales and direct runoff to the basin.

Calculations have been undertaken to determine the concept design basin size have been based on available geotechnical information regarding soil types and through the use of the Soils and Construction Volume 1 Manual. The volume of the sediment basin is 273m³, refer below for calculations.

To ensure the sediment basin is working effectively it will be maintained throughout the construction works. Maintenance includes ensuring adequate settlement times or flocculation and pumping of clean water to reach the minimum storage volume at the lower level of the settling zone. The settling zone will be identified by pegs to clearly show the level at which design storage capacity is available.

The pumped water from the sediment basin can be reused for dust control during construction.

Overflow weirs are to be provided to control overflows for rainfall events in excess of the design criteria.

SEDIMENT BASIN CALCULATIONS	
PARAMETER	ADOPTED VALUE
TOTAL DISTURBED AREA (ha)	1.63
SOIL TEXTURE GROUP	D
DESIGN RAINFALL DEPTH (DAYS)	5
DESIGN RAINFALL DEPTH (PERCENTILE)	80%
x-DAY, y-PERCENTILE RAINFALL EVENT (mm)	22.4
Cv	0.5
SETTLING ZONE VOLUME (m ³)	182.56
SEDIMENT STORAGE VOLUME (m ³)	91.28
TOTAL BASIN VOLUME REQUIRED (m ³)	273.84

5.1.3 Sediment and Erosion Control Measures

Prior to any earthworks commencing on site, sediment and erosion control measure shall be implemented generally in accordance with the Construction Certificate drawings and the "Blue Book". The measures shown on the drawings are intended to be a minimum treatment only as the contractor will be required to modify and stage the erosion and sedimentation control measures to suit the construction program, sequencing and techniques. These measures will include:

A temporary site security/safety fence is to be constructed around the site, the site office area and the proposed sediment basin.

Sediment fencing provided downstream of disturbed areas, including any topsoil stockpiles.

Dust control measures including covering stockpiles, installing fence hessian and watering exposed areas.

Placement of hay bales or mesh and gravel inlet filters around and along proposed catch drains and around stormwater inlets pits; and

The construction of a temporary sediment basin as noted on the drawings;

Stabilised site access at the construction vehicle entry/exits.

Any stockpiled material, including topsoil, shall be located as far away as possible from any associated natural watercourses or temporary overland flow paths. Sediment fences shall be installed to the downstream side of stockpiles and any embankment formation. All stockpiles and embankment formations shall be stabilised by hydroseeding or hydro mulching on formation.

5.1.4 Wet Weather Management

In circumstances of heavy rain sufficient to affect site access and ground conditions the Site Manager and Site HSE Committee representative should complete a site inspection before work commences. The inspection needs to focus on.

- The suitability of pedestrian access to the amenities and into the construction work areas
- The suitability of access for plant and equipment
- The suitability of ground conditions for plant and equipment to operate
- Nominate the construction zones suitable for work to commence
- Actions to remediate those areas not suitable for work to commence (de-water; prepare ground conditions and access ways etc.)

It is noted that the storage of equipment during wet weather will be placed in areas to not prohibit or disrupt operation of the sediment and soil erosion control measures.

5.1.5 Bulk Earthworks

The proposed works will generally consist of earthworks cut and fill operations to form design levels of the proposed buildings and internal road. Filling is required due to the flat topography of the site, and therefore we are proposing to excavate a portion of the site in order to help mitigate some of the loss of flood storage requirement for the development.

Earthworks shall be undertaken in accordance with geotechnical advice with specific regard to temporary earthworks including batters etc.

6. Mitigation Measures

Below is a table identifying civil engineering mitigation measures.

Project Stage	Mitigation Measure	Relevant Section of Report
Design and Construction	Erosion and sedimentation control will be constructed in accordance with Council requirements and "Managing Urban Stormwater Soil & Construction" 2004 (Blue Book) prepared by Landcom, prior to any earthworks commencing on site.	Section 5.1.1
Design and Construction	A temporary sediment basin has been designed to capture site runoff during construction and has been located towards the north eastern side of the site	Section 5.1.2
Design and Construction	Erosion and Sediment control measures such as sediment fence, temporary swales, construction access is proposed during construction.	Section 5.1.3
Design and Construction	Wet weather management during heavy rainfalls needs to be monitored	Section 5.1.4
Design and Construction and Operation	Earthworks - Cut is proposed on the site in order to mitigate some of the loss of site's flood storage. As such, it is not expected that the development will result in adverse flood impacts on surrounding properties nor additional inundation of the immediate downstream of the site.	Section 5.1.5
Design and Operation	Rainwater re-use tanks are proposed for irrigation and toilet flushing to reduce water demand and stormwater quantity from the development.	Section 4.2.3.2
Design and Operation	Stormwater Quality – Oceanguard inserts are proposed for pits for stormwater runoff from the driveway and carpark area.	Section 4.2.3.4

7. Appendix A – Civil REF Drawings

RICHMOND AGRICULTURAL CENTRE

COLLEGE DRIVE, RICHMOND, NSW 2753
CIVIL ENGINEERING PACKAGE



LOCALITY PLAN

SOURCE : NEARMAP.COM.AU (©2024)

CIVIL DRAWING SCHEDULE



DWG No.	DRAWING TITLE
RAC-NRE-ZZ-ZZ-DR-C-0000	COVER SHEET, DRAWING SCHEDULE AND LOCALITY PLAN
RAC-NRE-ZZ-ZZ-DR-C-0001	SPECIFICATION NOTES - SHEET 01
RAC-NRE-ZZ-ZZ-DR-C-0002	SPECIFICATION NOTES - SHEET 02
RAC-NRE-ZZ-ZZ-DR-C-1101	SEDIMENT AND SOIL EROSION CONTROL PLAN
RAC-NRE-ZZ-ZZ-DR-C-2001	CUT AND FILL PLAN
RAC-NRE-ZZ-ZZ-DR-C-3001	SITEWORKS AND STORMWATER MANAGEMENT PLAN - SHEET 01
RAC-NRE-ZZ-ZZ-DR-C-4001	STORMWATER LONGITUDINAL SECTIONS - SHEET 1
RAC-NRE-ZZ-ZZ-DR-C-4002	STORMWATER LONGITUDINAL SECTIONS - SHEET 2
RAC-NRE-ZZ-ZZ-DR-C-4201	STORMWATER CATCHMENT PLAN
RAC-NRE-ZZ-ZZ-DR-C-4301	STORMWATER PIT SCHEDULE
RAC-NRE-ZZ-ZZ-DR-C-6001	DETAILS - SHEET 01
RAC-NRE-ZZ-ZZ-DR-C-6002	DETAILS - SHEET 02
RAC-NRE-ZZ-ZZ-DR-C-6003	DETAILS - SHEET 03

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR
SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE
INCOMPLETE IF COPIED TO BLACK & WHITE



DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED.
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP
CONSULTING ENGINEERS PTY LTD.

REV	DESCRIPTION	ISS'D	VER'D	APP'D	DATE
01	ISSUED FOR DRAFT CONCEPT DESIGN	WD		NS	11.12.24
02	ISSUED FOR CONCEPT DESIGN	WD		NS	19.12.24
03	ISSUED FOR CONCEPT DESIGN	WD		NS	14.02.25
04	ISSUED FOR COORDINATION	WD		NS	24.03.25
05	ISSUED FOR REF	WD		NS	28.04.25



JOB NUMBER	DRAWING SHEET SIZE = A1	
SY240854		
DRAWING NO	REV	
RAC-NRE-ZZ-ZZ-DR-C- 0000	05	

NOT FOR CONSTRUCTION

HAWKESBURY CITY COUNCIL

ENGINEERING CERTIFICATION

1. TO CERTIFY THE CONSTRUCTED CIVIL WORKS, A QUALIFIED EXPERIENCED ENGINEER IS TO VISIT THE SITE TO OBSERVE CONSTRUCTION TECHNIQUES AND VARIOUS ELEMENTS THAT MAY BE CONCEALED WHEN THE WORKS ARE COMPLETE.
2. THIS SPECIFICATION ALLOWS FOR CERTIFICATION OF WORKS CONTROLLED BY A PRIVATE CERTIFIER FOR LAND DEVELOPMENT WORKS. THIS SPECIFICATION DOES NOT COVER CERTIFICATION REQUIREMENTS FOR AUTHORITIES SUCH AS COUNCIL, TNSW OR WATER NSW. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE AND PROVIDE ALL PROJECT SPECIFIC CONSTRUCTION COMPLIANCE (WORKS AS EXECUTED) INFORMATION TO THE SATISFACTION OF THE STAKEHOLDER / AUTHORITY. DISCREPANCIES BETWEEN THIS SPECIFICATION AND SPECIFICATIONS OF OTHER EXTERNAL STAKEHOLDERS / AUTHORITIES IS TO BE REPORTED TO THE SUPERINTENDENT FOR CLARIFICATION.
3. THE CONTRACTOR IS TO AGREE WITH THE ENGINEER AN APPROPRIATE SITE VISIT SCHEDULE AND FEE ARRANGEMENT PRIOR TO COMMENCEMENT OF THE WORKS. THE CONTRACTOR SHALL ENSURE THAT THE ENGINEER CAN SAFELY ACCESS ALL CIVIL ELEMENTS TO BE REVIEWED. SITE VISITS ARE CONDUCTED DURING NORMAL BUSINESS HOURS. WE REQUIRE TWO (2) WORKING DAY NOTICE FOR ANY SITE VISIT.
4. TO PROVIDE CERTIFICATION THE ENGINEER MUST VISIT THE SITE TO OBSERVE.
 - 4.1. PAVEMENTS (BY GEOTECHNICAL ENGINEER)
 - 4.1.1. POOR SUBGRADE CONDITIONS
 - 4.1.2. PROOF ROLLING OF SUB-GRADE
 - 4.1.3. PLACEMENT OF SUB-BASE COURSE, BASE COURSE AND WEARING COURSE.
 - 4.1.4. PLACEMENT OF STEEL REINFORCEMENT, DOWELS AND JOINT CRACKLES PRIOR TO POURING OF CONCRETE
 - 4.2. EARTHWORKS (BY GEOTECHNICAL ENGINEER)
 - 4.2.1. TOPSOIL STRIP
 - 4.2.2. EARTHWORKS BATTER
 - 4.2.3. FILLING
 - 4.3. STORMWATER DRAINAGE
 - 4.3.1. DRAINAGE TRENCHES PRIOR TO BACKFILLING
 - 4.3.2. LEGAL POINT OF CONNECTION PRIOR TO BACKFILLING
 - 4.3.3. ANY OTHER DRAINAGE STRUCTURE THAT MAY BE CONCEALED DURING THE COURSE OF THE WORKS
 - 4.4. CONCRETE STRUCTURES
 - 4.4.1. PLACEMENT OF ANY STEEL REINFORCEMENT PRIOR TO CONSTRUCTION.
5. THE CONTRACTOR SHALL PROVIDE SURVEYED LEVELS, PREPARED BY A QUALIFIED SURVEYOR FOR SUBGRADE, SUB-BASE COURSE, BASE COURSE AND WEARING COURSE.
6. THE CONTRACTOR SHALL PROVIDE WORKS AS EXECUTED (WAE) DOCUMENTATION PREPARED BY A QUALIFIED PRACTISING SURVEYOR. THE WAE DRAWINGS SHALL CLEARLY SHOW, STORMWATER GRATE/ COVER LEVELS, STORMWATER PIT INVERT LEVELS AND CORRESPONDING INVERT LEVELS OF ANY INCOMING OR OUTGOING PIPES, DIAMETER OF ALL PIPES, DIMENSIONS AND VOLUME OF ON-SITE DETENTION FACILITIES, INVERT LEVELS OF ORIFICE PLATES, OVERFLOW WEIRS, BASE OF TANK FINISHED LEVELS OF PAVEMENTS. THE WAE SHALL SHOW WHERE THE SIZE OR ALIGNMENT OF CIVIL ENGINEERING ELEMENTS WHEN THEY DEViate FROM THE DESIGN DOCUMENTATION.
7. THE WAE DRAWINGS SHALL BE STAMPED WITH THE FOLLOWING STATEMENT "THESE WAE DRAWINGS HAVE BEEN PREPARED BY [COMPANY NAME] AS A TRUE AND ACCURATE REPRESENTATION OF THE CONSTRUCTED WORKS". EACH DRAWING SHALL BE SIGNED AND DATED BY THE SURVEYOR WHO PREPARED THE DRAWINGS.

THESE WAE DRAWINGS HAVE BEEN PREPARED BY [COMPANY NAME] AND ARE A TRUE AND ACCURATE REPRESENTATION OF THE CONSTRUCTED WORKS.

SIGNED..... DATE.....

NAME.....

POSITION.....

8. WAE SHALL BE PROVIDED IN BOTH AUTOCAD AND PDF FORMAT. NORTHROP CONSULTING ENGINEERS WILL PROVIDE ENGINEERING PLANS TO THE CONTRACTOR IN AUTOCAD FORMAT TO AID PREPARATION OF WAE DOCUMENTATION.
9. IF THE WORKS ARE SUBJECT TO APPROVAL BY THE UPPER PARRAMATTA RIVER CATCHMENT TRUST (UPRCT) THE CONTRACTOR IS TO ADOBE BY THE UPRCT APPROVAL CHECKLIST.
10. CONTRACTOR IS TO UNDERTAKE A CCTV INSPECTION OF ALL STORMWATER DRAINAGE PIPELINES AND PROVIDE TO THE ENGINEER FOR APPROVAL.
11. THE CONTRACTOR SHALL PROVIDE ALL RELEVANT TEST CERTIFICATES PROGRESSIVELY THROUGHOUT THE DURATION OF THE WORKS. ALL TEST CERTIFICATES SHALL BE PREPARED BY A NATA REGISTERED LABORATORY. TEST CERTIFICATES ARE REQUIRED FOR PROOF ROLLING, SUBGRADE COMPACTION, COMPACTION OF PAVEMENT LAYERS, COMPACTION OF FILLING OPERATIONS, CONCRETE SLUMP TEST, AND CONCRETE STRENGTH TESTS. THE CONTRACT SHALL PROVIDE ALL RELEVANT VALIDATIONS BY A GEOTECHNICAL ENGINEER FOR ALL IMPORTED FILL
12. EACH TEST CERTIFICATE WILL NOMINATE THE DATE AND TIME OF THE TEST AND PROVIDE A LOCATION OF WHERE THE TEST SAMPLE WAS TAKEN FROM.
13. THE CONTRACTOR SHALL ARRANGE FOR THE ENGINEER TO CONDUCT A FINAL VISIT TO REVIEW OF THE CONSTRUCTED WORKS, THIS WILL REVIEW WILL NOT TAKE PLACE UNTIL THE WAE DOCUMENTATION AND RELEVANT TEST CERTIFICATES HAVE BEEN RECEIVED.
14. IF DEFECTIVE OR INCOMPLETE WORK IS FOUND DURING THE FINAL INSPECTION ANOTHER INSPECTION MAY BE REQUIRED AT THE CONTRACTORS EXPENSE TO VERIFY THE RECTIFICATION WORKS HAVE BEEN COMPLETED.

STORMWATER DRAINAGE

1. ALL PIPES TO BE BLACKMAX OR SIMILAR CLASS SN8
2. RCP USED TO CONNECT TO COUNCIL'S SYSTEM.
3. ALL STORMWATER PIPES EXTERNAL TO THE SITE ARE TO BE RCP IN ACCORDANCE WITH BLACKTOWN CITY COUNCIL'S SPECIFICATION.
4. ALL PIPE ARE TO BE LAID AT 10% MIN GRADE U.N.O.
5. PROVIDE Truflow SPS (250mm) FLOOR WASTES TO UNDERCOVER AREAS AS SHOWN WITH Ø150 uPVC OUTLET PIPE TO NEAREST GSP AT MIN. 1% GRADE
6. PROVIDE 100mm WIDE ACO GRATED DRAIN AT ALL DOORWAYS, 30mm BELOW FFL. CONNECT Ø100mm uPVC OUTLET PIPE TO NEAREST GSP AS SHOWN. MIN. 300 COVER AND MIN 1% GRADE
7. COVERS
 1. USE HOT DIPPED GALVANISED COVERS AND GRATES COMPLYING WITH RELEVANT COUNCIL AND AUSTRALIAN STANDARDS.
 2. ALL COVERS AND GRATES TO BE POSITIONED IN A FRAME AND MANUFACTURED AS A UNIT.
 3. ALL COVERS AND GRATES TO BE FITTING WITH POSITIVE COVER LIFTING KEYS
 4. OBTAIN SUPERINTENDENTS APPROVAL FOR THE USE OF CAST IRON SOLID COVERS AND GRATES. CAST IRON SOLID COVERS (IF APPROVED) TO CONSIST OF CROSS-WEBBED, CELLULAR CONSTRUCTION WITH THE RIBS UPPEMOST TO ALLOW INFILLING WITH CONCRETE. INSTALL POSITIVE COVER LIFTING KEYS AND PLASTIC PLUGS.
 5. UNLESS DETAILED OR SPECIFIED OTHERWISE, COVERS AND GRATES TO BE CLASS 'D' IN VEHICULAR PAVEMENTS AND CLASS 'B' ELSEWHERE.
 6. ALL GRATED TRENCH DRAINS SHOULD BE 'CLASS D' CAST IRON WITHIN VEHICULAR PAVEMENTS AND CLASS 'B' HEEL SAFE WITHIN PEDESTRIAN PAVEMENTS.
8. ALL PIPE BENDS, JUNCTIONS, ETC ARE TO BE PROVIDED USING PURPOSE MADE FITTINGS OR STORMWATER PITS.
9. ALL CONNECTIONS TO EXISTING DRAINAGE STRUCTURES SHALL BE MADE IN A TRADESMAN-LIKE MANNER AND CEMENT RENDERED TO ENSURE A SMOOTH FINISH.
10. ENSURE PIPEWORK DOES NOT PROTRUDE BEYOND THE INSIDE FACE OF THE PIT WALL. PIPEWORK IS TO FINISH FLYSH WITH INTERNAL WALL (UNLESS OTHERWISE NOTED OR DETAILED). CONNECTION TO BE RENDERED AND MADE NEAT ON THE INSIDE FACE OF THE PIT
11. THE CONTRACTOR SHALL SUPPLY AND INSTALL ALL FITTINGS AND SPECIALS INCLUDING VARIOUS PIPE ADAPTORS TO ENSURE PROPER CONNECTION BETWEEN DISSIMILAR PIPEWORK.
12. U.N.O. MATERIAL USED FOR BEDDING OF PIPES SHALL BE APPROVED NON-COHESIVE GRANULAR MATERIAL HAVING HIGH PERMEABILITY AND HIGH STABILITY WHEN SATURATED AND FREE OF ORGANIC AND CLAY MATERIAL.
13. BEDDING SHALL BE U.N.O TYPE H52 UNDER ROADS AND H2 UNDER GENERAL AREAS IN ACCORDANCE WITH CURRENT RELEVANT INDUSTRY STANDARDS AND GUIDELINES.
14. THE CONTRACTOR SHALL ENSURE AND PROTECT THE INTEGRITY OF ALL STORMWATER PIPES DURING CONSTRUCTION. ANY AND ALL DAMAGE TO THESE PIPES AS A RESULT OF THESE WORKS SHALL BE REPAIRED BY THE CONTRACTOR UNDER THE DIRECTION OF THE SUPERINTENDENT AND AT NO EXTRA COST TO THE CONTRACT.
15. NOTE THAT THE PIT COVER LEVEL NOMINATED IN GUTTERS ARE TO THE INVERT OF THE GUTTER WHICH ARE 40mm LOWER THAN THE PAVEMENT LEVEL AT LIP OF GUTTER. REFER KERB DETAILS FOR CONFIRMATION.
16. SUBSOIL DRAINAGE
 1. Ø100mm SUBSOIL DRAINAGE LINES WITH NON-WOVEN GEOTEXTILE FILTER SOCK SURROUND SHALL BE CONNECTED TO A STORMWATER DRAINAGE PIT (AT MIN 1% LONGITUDINAL GRADE) AND PROVIDED IN THE FOLLOWING LOCATIONS:
 1. THE HIGH SIDE OF PROPOSED TRAFFICKED PAVEMENT AREAS.
 2. ALL PLANTER AND TREE BEDS PROPOSED ADJACENT TO PAVEMENT AREAS.
 3. BEHIND RETAINING WALLS IN ACCORDANCE WITH RETAINING WALL DETAILS.
 4. UPSTREAM OF STORMWATER PITS
 5. BENEATH FLEXIBLE PAVEMENT ALONG A SAG PROFILE
 6. ALL OTHER AREAS SHOWN ON DRAWINGS.
 7. CONTRACTOR IS TO MAKE ALLOWANCE IN BOTH TENDER AND CONSTRUCTION COSTING TO ALLOW FOR SUBSURFACE DRAINAGE BEHIND ALL RETAINING WALLS / ABOVE LOCATIONS AND TO MAKE CONNECTION TO STORMWATER SYSTEM.
 2. WHERE SUBSOIL DRAINAGE PASSES BENEATH BUILDINGS / PAVED AREAS AND/OR PAVEMENTS. CONTRACTOR TO ENSURE Ø100mm CLASS 'SN8' uPVC DRAINAGE LINE IS USED AND THAT PROPRIETARY FITTINGS ARE USED TO RECONNECT SUBSOIL DRAINAGE LINE.
19. THE CONTRACTOR SHALL INSTALL INSPECTION OPENINGS / CLEAROUTS TO ALL SUBSOIL DRAINAGE LINES AND DOWNPIPE LINES AS SPECIFIED ON DRAWINGS AND IN ACCORDANCE WITH COUNCIL SPECIFICATIONS. HOWEVER AS A MINIMUM THEY ARE TO BE PLACED AT MAXIMUM 30m CENTRES AND AT ALL UPSTREAM ENDPOINTS.
20. PROVIDE 3.0m Length of Ø100 SUBSOIL DRAINAGE LINE WRAPPED IN NON-WOVEN GEOTEXTILE FILTER FABRIC TO THE UPSTREAM SIDE OF STORMWATER PITS, LAID IN STORMWATER PIPE TRENCHES AND CONNECTED TO DRAINAGE PIT.
21. IN AREAS WHERE DUMPED / HAND PLACED ROCK IS USED AS A MEANS OF SCOUR PROTECTION, CONTRACTOR IS TO EXCAVATE A MINIMUM OF 100mm FROM PROPOSED SURFACE, LEVEL AND COMPACT SUBGRADE AS SPECIFIED. ROCK TO THEN BE PLACED ON GEOTEXTILE FILTER FABRIC A34.
22. THE CONTRACTOR IS TO ENSURE THAT A MINIMUM 150mm CLEARANCE IS PROVIDED BETWEEN THE INTERNAL FACE OF PIPE AND ADJACENT INTERNAL PIT WALLS
23. WHERE TRENCHES ARE IN ROCK, THE PIPE SHALL BE BEDDED ON A MIN 50mm CONCRETE BED (OR 75mm THICK BED OF 12mm BLUE MATERIAL) UNDER THE BARREL OF THE PIPE. THE PIPE COLLAR AT NO POINT SHALL BEAR ON THE ROCK. (E.G. CLEAN 5-12mm AGGREGATE)

PAVEMENTS

ALL PAVEMENT MATERIALS SHALL COMPLY WITH CURRENT TNSW SPECIFICATIONS. PROVIDE MECHANICAL ANALYSIS FOR EACH BATCH OF PAVEMENT MATERIAL TO ENSURE CONFORMITY.

1. COMPACTION STANDARDS

BASE	98% MODIFIED MAXIMUM DRY DENSITY
SUBBASE	98% MODIFIED MAXIMUM DRY DENSITY
SUBGRADE	100% STANDARD MAXIMUM DRY DENSITY
2. THE CONTRACTOR SHALL CONFIRM THE DESIGN CBR WITH A MINIMUM OF 3 TESTS TAKEN AT SUBGRADE LEVEL. WHERE DISCREPANCY IS FOUND, CONTACT THE DESIGN ENGINEER.
3. ALLOW FOR COMPACTION TESTING BY A N.A.T.A. REGISTERED LABORATORY FOR BASE LAYER, SUBBASE LAYER AND SUBGRADE LAYER IN ACCORDANCE WITH THE LATEST VERSION OF AS3798 FOR PAVEMENTS (MINIMUM 2 TESTS PER LAYER). ALLOW FOR AT LEAST TWO SUCCESSFUL COMPACTION TESTS IN EACH LAYER.
4. MATCH NEW PAVEMENTS NEATLY AND FLUSH WITH EXISTING
5. AFTER BASE IS APPROVED, SWEEP CLEAN AND PRIME AT NOMINAL RATE OF 1.0L PER 1.0 sq.m.
6. PAVEMENT HOLD POINTS
 - 6.1. SUB-GRADE PROOF ROLL PRIOR TO SET-UP AND FORM FOR CONCRETE POUR
 - 6.2. INSPECTION OF FORMWORK / STEEL PRIOR TO CONCRETE POUR.

LANDSCAPING	
1.	REFER TO DRAWINGS BY OTHERS FOR DETAILS OF PROPOSED LANDSCAPING TREATMENT.
2.	IF NO LANDSCAPING PLANS EXIST OR PLANS DO NOT SPECIFY GENERAL SURFACE STABILISATION THEN ALL DISTURBED SURFACE TO BE TEMPORARILY STABILISED WITH HYDROMULCH UPON COMPLETION OF WORKS.

3D INFORMATION DISCLAIMER

PLEASE BE ADVISED 12D DESIGN FILE, IF SUPPLIED, IS DEEMED TO BE AN ACCURATE REFLECTION OF NORTHRUP'S DESIGN AT THE TIME OF FINAL DESIGN DEVELOPMENT AND MAY NOT FULLY REFLECT THE DESIGN SURFACE AS PRESENTED. HOWEVER THIS INFORMATION SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO INCORPORATION IN THE CONSTRUCTION WORKS.

YOU ARE FURTHER ADVISED THAT ISSUED HARDCOPY/PDF PLANS AND DOCUMENTS TAKE PRECEDENCE OVER THE SUPPLIED ELECTRONIC INFORMATION AND ANY DISCREPANCIES SHOULD IMMEDIATELY BE REPORTED TO NORTHRUP CONSULTING ENGINEERS FOR VERIFICATION PRIOR TO THEIR INCORPORATION IN THE WORKS.

NORTHRUP CONSULTING ENGINEERS TAKES NO RESPONSIBILITY FOR USE OF NON-VERIFIED 3D DESIGN INFORMATION USED IN THE WORKS.

THE USE OF THE 3D MODEL INFORMATION SHALL CONSTITUTE ACKNOWLEDGMENT AND ACCEPTANCE OF THE ABOVE STATEMENTS BY THE RECIPIENT.

CONCRETE

- CARRY OUT ALL CONCRETE WORK IN ACCORDANCE WITH AS3600 AND NATSPEC CONCRETE STANDARDS.
- CONCRETE PROPERTIES AND COVER TO REINFORCING:

ELEMENT	CONCRETE STRENGTH f'c (MPa)	MAX. 56 DAY DRYING SHRINKAGE	COVER (mm)	
SLABS ON GROUND	32	650microns	TOP 40	BTM 40
TANK LID	40	700microns	TOP 40	BTM 40

MAXIMUM AGGREGATE SIZE = 20mm U.N.O.
SLUMP DURING PLACING = 75mm
EXPOSURE CLASSIFICATION = B1
NO ADMIXTURES SHALL BE USED IN CONCRETE MIX UNLESS APPROVED BY STRUCTURAL ENGINEER IN WRITING.

- CONCRETE PROPERTIES FOR SLABS AND BEAMS SHALL BE VARIED FROM NORMAL CLASS AS FOLLOWS:
 - MINIMUM CEMENT CONTENT 250kg/cu.m.
 - PRIOR TO COMMENCEMENT CONCRETE SUPPLIER TO PROVIDE DRYING SHRINKAGE TESTRESULTS FROM PRODUCTION ASSESSMENT AS EVIDENCE THAT SPECIFIED DRYING SHRINKAGE LIMITS CAN BE ACHIEVED USING NORMAL MIX DESIGN.
- SUBMIT FOR APPROVAL THE FOLLOWING TO THE STRUCTURAL ENGINEER:
 - CURING PROCEDURE (PVA MEMBRANES NOT PERMITTED)
 - STRIPPING PROCEDURE
 - DETAILS AND LOCATION OF CAST IN SERVICES
 - CONDUITS, PENETRATIONS AND CONSTRUCTION JOINT LOCATIONS
- ALL CONCRETE MIXES SHALL BE DESIGNED BY A RECOGNISED TESTING LAB AND SUBMITTED FOR REVIEW BY THE STRUCTURAL ENGINEER.
- ALL COMPRESSIVE STRENGTH TEST RESULTS SHOULD BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR REVIEW.
- PROJECT CONTROL TESTING SHALL BE CARRIED OUT ON ALL CONCRETE IN ACCORDANCE WITH AS1379. TEST CYLINDERS ARE TO BE KEPT ON SITE.

CONCRETE (cont.)

8. FOR TENDER PURPOSES ASSUME MINIMUM STRIPPING TIMES AND EXTENT OF BACK PROPPING AS PER AS3610-1995 SECTION 5.0 AND AS PER GENERAL NOTES FOR FORMWORK AND PROPPING.

9. FORMWORK FINISH CLASSIFICATION TO AS3600:

ELEMENT	CLASS
INGROUND FOOTINGS	5
RETAINING WALLS	5 EARTH FACE
RETAINING WALLS	3 EXPOSED FACE
COLUMNS	2
BEAMS AND SLABS	2

10. SURFACE FINISHES:
- COLUMNS AND WALLS OFF FORM

11. COMPACT ALL CONCRETE INCLUDING FOOTINGS AND SLABS, USING MECHANICAL VIBRATORS.

12. PLACE CONCRETE CONTINUOUSLY BETWEEN CONSTRUCTION JOINTS. SHOWN ON PLAN, DO NOT BREAK OR INTERRUPT SUCCESSIVE POURS SUCH THAT COLD JOINTS OCCUR. ANY REVISIONS OR ADDITIONS TO CONSTRUCTION JOINTS SHOWN ON PLAN REQUIRE APPROVAL FROM THE STRUCTURAL ENGINEER.

13. CONCRETE PROFILES:
- BEAM DEPTHS ARE WRITTEN FIRST AND INCLUDE THE SLAB THICKNESS.
- SIZES OF CONCRETE ELEMENTS DO NOT INCLUDE THICKNESS OF APPLIED FINISHES.
- NO HOLES, CHASES OR EMBEDMENT OF PIPES OTHER THAN SHOWN IN THE STRUCTURAL DRAWINGS SHALL BE MADE IN CONCRETE MEMBERS WITHOUT THE PRIOR WRITTEN APPROVAL OF THE STRUCTURAL ENGINEER.
- PROVIDE DRIP GROOVES AT ALL EXPOSED EDGES, CHAMFERS, DRIP GROOVES, REGLETTS ETC TO BE TO ARCHITECTS DETAILS.

14. ALL PENETRATIONS TO HAVE 2-N16 TRIMMER BARS TOP AND BOTTOM TO EACH FACE U.N.O. EXTEND TRIMMERS 600 BEYOND PENETRATION.

15. SETDOWNS OR FALLS IN FLOOR SURFACES ARE NOT PERMITTED UNLESS SHOWN ON DRAWINGS. MAINTAIN MINIMUM SLAB THICKNESS SHOWN ON PLAN WHERE FALLS OCCUR.

16. REINFORCEMENT GRADE AND NOTATION:

SYMBOL	BAR SHAPE	STRENGTH GRADE (MPa)	DUCTILITY CLASS	TO COMPLY WITH AUST. STANDARD
N	DEFORMED RIB BAR	500	NORMAL	AS4671
R	PLAIN ROUND BAR	250	NORMAL	AS4671
RL	RECTANGULAR MESH OF DEFORMED RIB BAR	500	LOW	AS4671
SL	SQUARE MESH OF DEFORMED RIB BAR	500	LOW	AS4671
L-TM	TRENCH MESH	500	LOW	AS4671

ALL REINFORCING BARS SHALL BE GRADE D500N TO AS4671 AND ALL MESH SHALL BE GRADE 500L TO AS4671 U.N.O. CLASS L REINFORCEMENT SHALL NOT BE USED U.N.O.

REINFORCEMENT LABELS:

N12-300

↑

↑

↑

SPACING (mm)

BAR SIZE (mm)

TYPE OF REINFORCEMENT

3-N28

↑

↑

↑

BAR SIZE (mm)

TYPE OF REINFORCEMENT

NUMBER OF BARS

SL92

↑

↑

↑

CENTRES AT 200mm

BAR SIZE (mm)

DUCTILITY CLASS

SQUARE MESH

17. REINFORCEMENT IS REPRESENTED DIAGRAMMATICALLY, AND NOT NECESSARILY IN TRUE PROJECTION. BARS SHOWN ARE INDICATIVE ONLY AND LENGTHS MAY VARY. BEAM ELEVATIONS TAKE PRECEDENCE OVER SECTIONS. SLAB PLANS TAKE PRECEDENCE OVER SECTIONS. REFER TO SECTIONS FOR EXTRA BARS THAT MAY BE REQUIRED.

18. USE ONLY ALL PLASTIC OR CONCRETE CHAIRS AT EXTERNAL SURFACES.

19. SITE BENDING OF REINFORCEMENT BARS SHALL BE DONE WITHOUT HEATING USING A RE-BENDING TOOL. THE BARS SHALL BE RE-BENT AGAINST A FLAT SURFACE OR A PIN WITH A DIAMETER NOT LESS THAN THE MINIMUM PIN SIZE PRESCRIBED IN AS3600-2001.

20. SPLICES IN REINFORCEMENT SHALL BE MADE ONLY IN POSITIONS SHOWN ON THE STRUCTURAL DRAWINGS OR IN POSITIONS OTHERWISE APPROVED IN WRITING BY THE ENGINEER. LAPS SHALL BE IN ACCORDANCE WITH AS3600 SECTION 13 AND NOT LESS THAN THE DEVELOPMENT LENGTH FOR EACH BAR.

21. FOR LAPS IN MESH REFER TO SLAB ON GROUND NOTES.

22. WELDING OF REINFORCEMENT SHALL NOT BE PERMITTED UNLESS SHOWN ON THE STRUCTURAL DRAWINGS OR APPROVED BY THE STRUCTURAL ENGINEER.





23. AT EXTERNALLY EXPOSED SURFACES NO METALLIC ITEMS INCLUDING FORM BOLTS, FORM SPACERS, METALLIC BAR CHAIRS AND TIE WIRE ARE TO BE PLACED IN THE COVER ZONE.


24. ALL REINFORCEMENT, ANCHOR BOLTS AND OTHER CONCRETE INSERTS SHALL BE WELL SECURED IN POSITION AND INSPECTED BY THE STRUCTURAL ENGINEER PRIOR TO PLACING CONCRETE.

25. HOLD DOWN BOLTS SHALL BE HOT DIPPED GALVANISED.

26. U.N.O. ALL MASONRY ANCHORS INTO CONCRETE SHALL BE RAMSET TRUBOLTS (LONGEST EXTENSION) OR APPROVED EQUIVALENT. BOLTS SHALL BE GALVANISED WHERE THEY ARE ADJOINING NON FERROUS OR PREPAINTED MEMBERS. PROVIDE STAINLESS STEEL BOLTS FOR ALL EXTERNAL CONDITIONS, OR WHERE EXPOSED TO THE WEATHER.


[illegible]

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED. THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD.						
REV	DESCRIPTION	ISS'D	VER'D	APP'D	DATE	
01	ISSUED FOR DRAFT CONCEPT DESIGN	WD		NS	11.12.24	
02	ISSUED FOR CONCEPT DESIGN	WD		NS	19.12.24	
03	ISSUED FOR CONCEPT DESIGN	WD		NS	14.02.25	
04	ISSUED FOR COORDINATION	WD		NS	24.03.25	
ARCHITECT						
						
BUILDING						
						
CLIENT						
						
PROJECT						
RICHMOND AGRICULTURAL CENTRE, COLLEGE ROAD, RICHMOND, NSW, 2753						
						
Sydney Level 11 345 George Street, Sydney NSW 2000 Ph (02) 9241 4188 Fax (02) 9241 4324 Email sydney@northrop.com.au ABN 81 094 433 100						
<div style="display: flex; justify-content: space-between;"> <div style="width: 20%;"></div> <div style="width: 80%;"></div> </div>						
DRAWING TITLE						
CIVIL ENGINEERING PACKAGE SPECIFICATION NOTES - SHEET 02						
JOB NUMBER						
SY240854						
DRAWING NO						
RAC-NRE-ZZ-ZZ-DR-C- 0002						
DRAWING SHEET SIZE = A1						
REV						04



DRAWING NO	REV
RAC-NRE-ZZ-ZZ-DR-C- 1101	01

DRAWN: W. DODIC



CONSTRUCTION NOTES

CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, AND TO THE FENCE LINE AS SHOWN IN THE DRAWING TO LIGN THE CATCHMENT AREA. ANY SLOPE OF THE CATCHMENT AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW & CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND. THE FENCE SHOULD BE CONSTRUCTED TO A MINIMUM OF 1.5 METRE DEPTH ALONG THE UPSLOPE LINE OF THE FENCE. FROM THE BOTTOM OF THE FABRIC TO BE ENTERED.


DRIVE 15 METRE LONG STAKE PILES INTO GROUND AT 25 METRE INTERVALS (MAX) AT THE DOWNSLOPE EDGE OF THE FENCE. ENSURE ANY STAKE PILES ARE FITTED WITH SAFETY CAPS.

FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE POSTS. THE POSTS SHOULD BE DRIVEN INTO THE GROUND TO A MINIMUM OF 1.5 METRE DEPTH. THE GEOTEXTILE SHOULD BE SUFFICIENTLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.

JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 10mm overlap.

BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.

NOT FOR CONSTRUCTION



LEGEND

EXISTING BOUNDARY LINE
EASEMENT LINE

PROPOSED BATTERS

CUT FILL DEPTH

DEPTH OF CUT

DEPTH OF FILL

TREE TO BE RETAINED

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR
SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE
INCOMPLETE IF COPIED TO BLACK & WHITE

CUT AND FILL CALCULATIONS

1. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL / RELEVANT AUTHORITY SPECIFICATIONS AND DETAILS.
2. CAD FILES / DTM FILES TO BE SUPPLIED IN AUTOCAD FORMAT FOR SETOUT PURPOSES (UPON REQUEST).
3. NO ALLOWANCE HAS BEEN MADE FOR BULKING FACTORS. NOTE ALL VOLUMES DEPICTED ARE SOLID VOLUMES ONLY AND MAY NOT REFLECT DETAILED EARTHWORKS.
4. NO ALLOWANCE HAS BEEN MADE FOR DETAILED EARTHWORKS, ie SERVICE TRENCHING, DETAILED EXCAVATION, FOOTINGS, RETAINING WALLS AND THE LIKE. CONTRACTOR IS TO ALLOW FOR REMOVAL OF ALL EXCESS MATERIAL GENERATED BY THE WORKS.
5. THE CONTRACTOR SHALL USE FINAL SURFACE LEVELS AND TYPICAL PAVEMENT DETAILS FOR ACTUAL EARTHWORKS LEVELS.
6. APPROXIMATE CUT AND FILL VALUES AS FOLLOWS;
6.1. CUT 2806.5 m³
6.2. FILL 11245.9 m³
6.3. BALANCE 8439.4 m³
6.4. NOTE: NO SITE STRIPPING HAS BEEN ALLOWED FOR.

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED.
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP
CONSULTING ENGINEERS PTY LTD.

REV	DESCRIPTION	ISS'D	VER'D	APP'D	DATE
02	ISSUED FOR CONCEPT DESIGN	WD		NS	19.12.24
03	ISSUED FOR CONCEPT DESIGN	WD		NS	04.02.25
04	ISSUED FOR CONCEPT DESIGN	WD		NS	14.02.25
05	ISSUED FOR COORDINATION	WD		NS	24.03.25
06	ISSUED FOR REF	WD		NS	28.04.25

ARCHITECT

NBRS

BUILDER

**RICHARD CROOKES
CONSTRUCTIONS**

CLIENT



PROJECT

**RICHMOND AGRICULTURAL
CENTRE,
COLLEGE ROAD,
RICHMOND, NSW, 2753**



Sydney
Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

DRAWING TITLE

**CIVIL ENGINEERING PACKAGE
CUT AND FILL PLAN**

JOB NUMBER

SY240854

DRAWING SHEET SIZE = A1


DRAWING NO

RAC-NRE-ZZ-ZZ-DR-C- 2001

REV

06

NOT FOR CONSTRUCTION



LEGEND

- PROPOSED BOUNDARY LINE
- ADJACENT BOUNDARY LINE
- EASEMENT LINE
- PROPOSED BUILDING FOOTPRINT
- PROPOSED BUILDING ROOF OUTLINE
- EXISTING SEWER
- EXISTING STORMWATER
- DIRECTION OF GRADE
- DIRECTION OF GRADE
- CONTOURS
- EXISTING CONTOURS
- EXISTING DRAINAGE STRUCTURE
- CONCRETE HEADWALL
- ROCK HEADWALL
- DOWN PIPE
- NEW DRAINAGE STRUCTURE
- STORMWATER PIPE
- STRUCTURE No / LINE ID
- STORMWATER PIT TAG
- DRAINAGE SWALE
- SAWCUT AND PAVEMENT INFILL
- WHEEL STOP
- CONCRETE PAVEMENT TYPE 1
- MULCH SOIL
- POROUS PAVING
- UNIT PAVERS
- DECOMPOSED GRANITE
- CONCRETE PAVEMENT TYPE 3
- LANDSCAPE

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR
SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE
INCOMPLETE IF COPIED TO BLACK & WHITE

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED.
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP
CONSULTING ENGINEERS PTY LTD.

REV	DESCRIPTION	ISS'D	VER'D	APP'D	DATE
02	ISSUED FOR DRAFT CONCEPT DESIGN	WD		NS	11.12.24
03	ISSUED FOR CONCEPT DESIGN	WD		NS	19.12.24
04	ISSUED FOR CONCEPT DESIGN	WD		NS	14.02.25
05	ISSUED FOR COORDINATION	WD		NS	24.03.25
06	ISSUED FOR REF	WD		NS	28.04.25

ARCHITECT

NBRS

BUILDER

**RICHARD CROOKES
CONSTRUCTIONS**

CLIENT

NSW Education
GOVERNMENT School Infrastructure

PROJECT

**RICHMOND AGRICULTURAL
CENTRE,
COLLEGE ROAD,
RICHMOND, NSW, 2753**

NORTHROP

Sydney
Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

SCALE 1:800@A1

0 10 20 30 40m

DRAWING TITLE

**CIVIL ENGINEERING PACKAGE
SITEWORKS AND STORMWATER
MANAGEMENT PLAN - SHEET 01**

JOB NUMBER

SY240854

DRAWING SHEET SIZE = A1

DRAWING NO


RAC-NRE-ZZ-ZZ-DR-C- 3001

REV

06

NOT FOR CONSTRUCTION

DRAWN: W. DOOIC
DESIGNED: EBRADLEY
JOB MANAGER: N. SUTHERLAND
VERIFIER: .



LINE 01

LINE 02

NOT FOR CONSTRUCTION

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR
SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE
INCOMPLETE IF COPIED TO BLACK & WHITE

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED.
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP
CONSULTING ENGINEERS PTY LTD.

REV	DESCRIPTION	ISS'D	VER'D	APP'D	DATE
01	ISSUED FOR COORDINATION	WD		NS	28.04.25

ARCHITECT

NBRS

BUILDER

RICHARD CROOKES
CONSTRUCTIONS

CLIENT

NSW GOVERNMENT
Education
School Infrastructure

PROJECT

RICHMOND AGRICULTURAL
CENTRE,
COLLEGE ROAD,
RICHMOND, NSW, 2753

NORTHROP

Sydney

Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

SCALE 1:250@ A1
SCALE 1:50@ A1

DRAWING TITLE

CIVIL ENGINEERING PACKAGE
STORMWATER LONGITUDINAL
SECTIONS - SHEET 1

JOB NUMBER

SY240854

DRAWING SHEET SIZE = A1

DRAWING NO

RAC-NRE-ZZ-ZZ-DR-C- 4001

REV
01

STRUCTURE ID (LINE \ STRUCTURE)	STRUCTURE DESCRIPTION	GRATE AND FRAME SIZE	ACCESS COVER AND CLASS	DEPTH TO INVERT	EASTING	NORTHING	REMARKS
01 \ 01	SURFACE INLET PIT	900 x 900	GRATED FEELSAFE LOCKABLE, CLASS D	0.520	291239.199	6279039.312	
01 \ 02	SURFACE INLET PIT	1200 x 1200	GRATED FEELSAFE LOCKABLE, CLASS D	0.470	291259.126	6279038.597	FITTED WITH 'OCEAN GUARD'
01 \ 03	SURFACE INLET PIT	1200 x 1200	GRATED FEELSAFE LOCKABLE, CLASS D	0.410	291281.593	6279037.836	FITTED WITH 'OCEAN GUARD'
03 \ 01	SURFACE INLET PIT	900 x 900	GRATED FEELSAFE LOCKABLE, CLASS D	0.410	291385.697	6278937.076	FITTED WITH 'OCEAN GUARD'
04 \ 01	SURFACE INLET PIT	900 x 900	GRATED FEELSAFE LOCKABLE, CLASS D	0.330	291377.991	6279103.596	FITTED WITH 'OCEAN GUARD'
HW-01	HEADWALL OUTLET	-	-	-	291337.415	6279038.140	PROPOSED HEADWALL
HW-02	HEADWALL OUTLET	-	-	-	291208.284	6279200.700	PROPOSED HEADWALL
HW-03	HEADWALL OUTLET	-	-	-	291390.169	6278975.834	PROPOSED HEADWALL
HW-04	HEADWALL OUTLET	-	-	-	291414.884	6279136.420	PROPOSED HEADWALL
HW-05	HEADWALL OUTLET	-	-	-	291254.484	6279110.529	PROPOSED HEADWALL
RWT BLOCK E	-	-	-	-	291378.570	6279100.668	RAINWATER TANK TO HYDRAULICS DRAWINGS
RWT MAIN	-	-	-	-	291239.055	6279105.447	RAINWATER TANK TO HYDRAULICS DRAWINGS

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR
SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE
INCOMPLETE IF COPIED TO BLACK & WHITE


DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED.
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP
CONSULTING ENGINEERS PTY LTD.

REV	DESCRIPTION	ISS'D	VER'D	APP'D	DATE
01	ISSUED FOR COORDINATION	WD		NS	28.04.25

ARCHITECT



BUILDER



CLIENT





PROJECT

**RICHMOND AGRICULTURAL
CENTRE,
COLLEGE ROAD,
RICHMOND, NSW, 2753**



Sydney
Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100



SCALE 1:800@ A1


DRAWING TITLE

**CIVIL ENGINEERING PACKAGE
STORMWATER PIT SCHEDULE**

JOB NUMBER

SY240854

DRAWING SHEET SIZE = A1

DRAWING NO

RAC-NRE-ZZ-ZZ-DR-C- 4301




REV

01

NOT FOR CONSTRUCTION



	MEAN ROCK SIZE (d50) (mm)	DESIGN LENGTH (m)	THICKNESS (m)	WIDTH (m)	SIZE DISTRIBUTION (d50/d90)
HW 1	100	3.00	0.18	1.7	0.67
HW 2	100	1.50	0.18	1.1	0.67
HW 3	100	3.00	0.18	1.7	0.67
HW 4	100	1.00	0.18	1.1	0.67
HW 5	200	1.50	0.36	1.1	0.67
HW 6	100	3.00	0.18	1.5	0.67
DP 1	100	1.00	0.18	1.1	0.67
DP 2	100	1.00	0.18	1.1	0.67



NOT FOR CONSTRUCTION

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR
SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE
INCOMPLETE IF COPIED TO BLACK & WHITE

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED.
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHERN
CONSULTING ENGINEERS PTY LTD.

REV	DESCRIPTION	ISS'D	VER'D	APP'D	DATE
01	ISSUED FOR DRAFT CONCEPT DESIGN	WD		NS	11.12.24
02	ISSUED FOR CONCEPT DESIGN	WD		NS	19.12.24
03	ISSUED FOR CONCEPT DESIGN	WD		NS	14.02.25
04	ISSUED FOR COORDINATION	WD		NS	24.03.25
05	ISSUED FOR REF	WD		NS	28.04.25

ARCHITECT

NBRS

BUILDER

RICHARD CROOKES
CONSTRUCTIONS

CLIENT



PROJECT

**RICHMOND AGRICULTURAL
CENTRE,
COLLEGE ROAD,
RICHMOND, NSW, 2753**



Sydney
Level 11 345 George Street, Sydney NSW 2000
Ph (02) 9241 4188 Fax (02) 9241 4324
Email sydney@northrop.com.au ABN 81 094 433 100

SCALE VARIES


DRAWING TITLE
**CIVIL ENGINEERING PACKAGE
DETAILS - SHEET 01**

JOB NUMBER
SY240854

DRAWING SHEET SIZE = A1


DRAWING NO
RAC-NRE-ZZ-ZZ-DR-C- 6001

REV
05




FOOTPATH EXPANSION JOINT 'EJ'

- TO ALSO BE USED AS A 'STOPWORK JOINT'
- MAXIMUM CONTINUOUS POUR NOT TO EXCEED 36m
- JOINT TO BE INSTALLED TO MANUFACTURERS SPECIFICATIONS
- REFER SPECIFICATION NOTES FOR JOINT SPACINGS (6m UNO)




FOOTPATH SAWN / CONTRACTION JOINT 'SJ'

- JOINT TO BE SAWN AS SOON AS CONCRETE HAS HARDENED SUFFICIENTLY THAT IT WILL NOT BE DAMAGED BY SAWING (MAX 24HRS)
- REFER SPECIFICATION NOTES FOR JOINT SPACINGS (2m UNO)




ISOLATION JOINT 'IJ'

- PROVIDE JOINT BETWEEN ALL NEW CONCRETE AND EXISTING STRUCTURES
- JOINT TO BE USED AGAINST ALL WALLS, FOOTINGS, COLUMNS, BACK OF KERB, SERVICE PITS, DRAINAGE PITS AND ALL SLAB PENETRATIONS













TRAFFICKED EXPANSION JOINT 'EJ'

- TO ALSO BE USED AS A 'STOPWORK JOINT'
- JOINT TO BE INSTALLED TO MANUFACTURERS SPECIFICATIONS
- REFER SPECIFICATION NOTES FOR JOINT SPACINGS (18m UNO)



TRAFFICKED SAWN / CONTRACTION JOINT 'SJ'

- JOINT TO BE SAWN AS SOON AS CONCRETE HAS HARDENED SUFFICIENTLY THAT IT WILL NOT BE DAMAGED BY SAWING (MAX 24HRS)
- REFER SPECIFICATION NOTES FOR JOINT SPACINGS (6m UNO)



TYPICAL TRIMMER BAR DETAILS (TB)

- NOTE:
- PROVIDE 2/N12 TRIMMER BARS MINIMUM 1200mm LONG UNLESS NOTED OTHERWISE AT ALL PITS, COLUMNS, INSPECTION OPENINGS, DOWNPIPES ETC THAT CAUSE A PENETRATION THROUGH THE SLAB.
 - ALL TRIMMER BARS MUST MAINTAIN A MINIMUM 70mm COVER FROM PENETRATION & CONTROL JOINTS.
 - UNLESS NOTED OTHERWISE PROVIDE ISOLATION JOINT (IJ) AT ALL PAVEMENT INTERFACES WITH STRUCTURE / PITS.
 - APPLIES TO ALL DRAINAGE/SEWER PITS, SERVICE PITS, COLUMNS & SLAB PENETRATIONS.

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE INCOMPLETE IF COPIED TO BLACK & WHITE

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS VERIFICATION SIGNATURE HAS BEEN ADDED.
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP CONSULTING ENGINEERS PTY LTD.

REV	DESCRIPTION	ISS'D	VER'D	APP'D	DATE
01	ISSUED FOR COORDINATION	WD		NS	28.04.25



PROJECT
**RICHMOND AGRICULTURAL CENTRE,
COLLEGE ROAD,
RICHMOND, NSW, 2753**



SCALE VARIES

DRAWING TITLE
**CIVIL ENGINEERING PACKAGE
DETAILS - SHEET 02**


JOB NUMBER
SY240854

DRAWING SHEET SIZE = A1


DRAWING NO	REV
RAC-NRE-ZZ-ZZ-DR-C- 6002	01

NOT FOR CONSTRUCTION


JOB MANAGER: N. SUTHERLAND VERIFIER: .
DESIGNED: EBRADLEY
DRAWN: W. DODIC




PAVEMENT TYPE '1' FOOTPATH
MIN CBR 3% (CONTRACTOR TO CONFIRM ONSITE).
CONTRACTOR TO ALLOW FOR JOINTS - REFER JOINT DETAILS




PAVEMENT TYPE '2' CARPARK AND DRIVEWAY
MIN CBR 3% (CONTRACTOR TO CONFIRM ONSITE).
CONTRACTOR TO ALLOW FOR JOINTS - REFER JOINT DETAILS




PAVEMENT TYPE '3' GRAVEL SERVICE DRIVEWAY
MIN CBR 3% (CONTRACTOR TO CONFIRM ONSITE)



SECTION 1



ELEVATION




PLAN
KERB RAMP 'KR'

ALL DIMENSIONS TO BE VERIFIED ON SITE BEFORE COMMENCING WORK.
NORTHROP ACCEPTS NO RESPONSIBILITY FOR THE USABILITY, COMPLETENESS OR
SCALE OF DRAWINGS TRANSFERRED ELECTRONICALLY.
THIS DRAWING MAY HAVE BEEN PREPARED USING COLOUR, AND MAY BE
INCOMPLETE IF COPIED TO BLACK & WHITE

DRAWING NOT TO BE USED FOR CONSTRUCTION UNLESS
VERIFICATION SIGNATURE HAS BEEN ADDED.
THE COPYRIGHT OF THIS DRAWING REMAINS WITH NORTHROP
CONSULTING ENGINEERS PTY LTD.

REV	DESCRIPTION	ISS'D	VER'D	APP'D	DATE
01	ISSUED FOR COORDINATION	WD		NS	28.04.25



PROJECT
**RICHMOND AGRICULTURAL
CENTRE,
COLLEGE ROAD,
RICHMOND, NSW, 2753**



SCALE VARIES

DRAWING TITLE
**CIVIL ENGINEERING PACKAGE
DETAILS - SHEET 03**

JOB NUMBER
SY240854

DRAWING SHEET SIZE = A1

DRAWING NO
RAC-NRE-ZZ-ZZ-DR-C- 6003

REV
01

NOT FOR CONSTRUCTION

Contact Us

BRISBANE

07 3365 0400
brisbane@northrop.com.au
Level 25, 12 Creek Street
Brisbane QLD 4000

CANBERRA

02 6285 1822
canberra@northrop.com.au
Level 6, 224 Bunda Street
Canberra ACT 2608

CENTRAL COAST

02 4365 1668
centralcoast@northrop.com.au
Ground Level, Suite 4, 257-259 Central
Coast Highway
Erina NSW 2250

COFFS HARBOUR

02 5603 3053
coffsharbour@northrop.com.au
Suite 6, 27 Orlando Street
Coffs Harbour NSW 2450

MELBOURNE

03 9600 2645
melbourne@northrop.com.au
Level 3, 520 Collins Street
Melbourne VIC 3000

NEWCASTLE

02 4943 1777
newcastle@northrop.com.au
Level 1, 215 Pacific Highway
Charlestown NSW 2290

PARRAMATTA

02 9241 4188
sydney@northrop.com.au
Level 15, 6 Hassall Street
Parramatta NSW 2150

SYDNEY

02 9241 4188
sydney@northrop.com.au
Level 10, 400 George St
Sydney NSW 2000

WOLLONGONG

02 4226 3333
southcoast@northrop.com.au
Level 1, 57 Kembla Street
Wollongong NSW 2500