# Cammeray Public School Upgrade Schematic Design Report

For NSW Department of Education

# **Document Quality Control**

| Project:    | Cammeray Public School Upgrade |  |
|-------------|--------------------------------|--|
| Client:     | NSW Department of Education    |  |
| Project No: | 7068CY01                       |  |

This document has been prepared by:

Fulton Trotter Architects Pty Ltd trading as

Fulton Trotter Architects

# ABN: 57 677 264 550

NOTES:

# Quality Assurance

The information below is used as document quality control under Fulton Trotter Architects' Quality Management System. The accuracy of this document cannot be controlled once this document has been printed.

# **Revision History**

| Issue            | Date                       | Revision Details/Status | Prepared by: | Approved by: |
|------------------|----------------------------|-------------------------|--------------|--------------|
| А                | 2 <b>0</b> .1 <b>2</b> .24 | Draft for Review        | JW           | NK           |
| В                | 07.03.25                   | SD Issue                | JW           | NK           |
| С                | 07.03.25                   | SD Issue – Revised      | JW           | NK           |
| D                | 13.03.25                   | SD Issue – Revised      | JW           | NK           |
| CURRENT ISSUE: D |                            |                         |              |              |

**Document Quality Control** 

Fulton Trotter Architects acknowledge the **Cammeraygal** people as the traditional custodians of the land upon which the **Cammeray Public School** stands. We recognise their continuing connection to land, waters and culture and pay our respects to their Elders past, present and emerging.

# Contents

| 1 | EXECUTIVE SUMMARY        | 4  |
|---|--------------------------|----|
| 2 | SITE                     | 6  |
| 3 | DESIGN BRIEF             | 8  |
| 4 | DESIGN                   | 10 |
| 5 | CONSULTATION             | 15 |
| 6 | SERVICES AND ENGINEERING | 16 |
| 7 | NEXT STEPS               | 18 |

# Appendices

- 1 CONTACT LIST
- 2 SCHEDULE OF ACCOMMODATION
- **3 ARCHITECTURAL SCHEMATIC DESIGN**
- 4 LANDSCAPE SCHEMATIC DESIGN
- 5 EFSG DEPARTURE SCHEDULE
- 6 RFI TRACKER
- 7 SAFETY IN DESIGN REGISTER
- **8 DESIGN COMMENTS TRACKER**

# 1 Executive Summary

Fulton Trotter Architects have been engaged by NSW Department of Education (DOE) to design the upgrades to Cammeray Public School.

Following the completion of the Master Plan Validation phase, Fulton Trotter have been engaged to deliver concept and schematic design phases.

This document outlines the design that has been developed for this project as well as the process that has been undertaken to develop the project details during this phase. The new facilities will be constructed using a combination of conventional and modern construction methods. Due to site constraints, the design will not be fully compliant with DOE's standard 'Hub Layouts' and pattern book. However, the designs and details are to comply with the intentions of these standards wherever possible.



Image: Fulton Trotter Architects

| Proposed Project                      |  |  |  |
|---------------------------------------|--|--|--|
| School:                               | Cammeray Public School (K-6 co-educational)  |  |  |
| Projected students:                   | 667  |  |  |
| Proposed Number of<br>Teaching Spaces | 29 permanent teaching spaces total   |  |  |
| EFSG Core                             | 4 stream, Large Primary School (EFSG V2)   |  |  |
| Proposed Works:                       | <ul> <li>Construction of 4 new permanent<br/>teaching spaces in a two-storey building<br/>incorporating 2 general learning spaces<br/>and 2 practical activity areas</li> <li>New egress lift and stairs for access to all<br/>building levels</li> <li>External covered walkways connecting<br/>the new building to the existing school<br/>network</li> <li>Landscaping and external works<br/>including compensatory planting</li> <li>Upgrades to site infrastructure and<br/>services to support the new buildings</li> <li>Removal of 3 temporary (demountable)<br/>classrooms from the eastern side of the<br/>school</li> <li>50 bicycle parking spaces</li> </ul> |  |  |
| Open play space per student:          | 12.28sqm / student   |  |  |
| Amenities                             | Total toilet count 39  |  |  |

| Project Status   |                  |
|------------------|------------------|
| Current Phase    | Schematic Design |
| Phase completion | March 2025       |

| Design                       |  |
|------------------------------|--|
| Site Due Diligence           | Additional survey of Building E has been completed.  |
| Brief                        | Scope of Work for upgrade has been agreed.<br>Refer design brief outline in <b>Section 3</b> .   |
| Schedule of<br>Accommodation | Shortfalls have been identified beyond the agreed project scope of work. These are detailed in <b>Appendix 2</b> of this report  |
| Concept Design               | The design of a custom layout due to site<br>constraints, however the requirements of the DOE<br>standard layouts will be applied to the proposed<br>design wherever possible. |
| Town Planning<br>Pathway     | REF pathway  |



Image: Fulton Trotter Architects

| Consultation               |   |  |
|----------------------------|---|--|
| Stakeholders               | This project has been a collaborative effort with multiple key stakeholders A contact list is included in <b>Appendix 1</b> of this report  |  |
| Buildability               | The site can be accessed via Miller Street,<br>however, access for emergency and service<br>vehicles onto the site will need to be maintained<br>throughout the construction period.  |  |
| Safety in Design           | A safety in design schedule has been developed for the project.   |  |
| Connecting with<br>Country | A formal Connecting with Country process is not<br>being undertaken for this project. A local<br>consultation process will happen. Consultation<br>has been undertaken with a representative from<br>the AECG for the region. |  |
| Sustainability             | Green Star will not be required based on the value and size of the proposed works   |  |
| EFSG                       | The project has been designed to comply with the requirements of EFSG and all relevant legislation. Refer departures schedule in <b>Appendix 5.</b>   |  |

| Engineering & Services |  |
|------------------------|--|
| Fire & Hydraulic       | Hydrant system design to connect to Bellevue<br>Street to ensure sufficient pressure and flow.   |
| Electrical & ICT       | Upgrades to be confirmed.  |
| Civil / Structural     | Structural design has been developed based on a concrete structure with lightweight framing infill and roof structure.                                 |
| Traffic                | 50 bicycle parking spaces will be required as part of the project.   |
| Landscaping            | 2 existing mature trees are to be removed. Offset planting is proposed on Miller St and adjacent to Building C   |
| BCA                    | Building is considered an extension of the fire<br>compartment of existing Building E. Therefore,<br>the extended fire compartment area is acceptable. |

# 2 Site

# Site Details

Cammeray Public School is located within the Northern Sydney suburbs. The school has frontages to Miller Street, Palmer Street and Bellevue Street. Vehicular access is provided from Miller and Bellevue Streets. Pedestrian access is provided from both Palmer and Bellevue Streets.

The selected site for the new works is in the south-west corner of the campus – connected into the existing adjacent building (Building E). The new building will be visible from Miller Street



Aerial Image: SixMaps


| Site Details              |  |  |
|---------------------------|--|--|
| Address:                  | 68 Palmer Street, Cammeray   |  |
| Lots                      | Lot 66 DP1049613, Lots 4 & 5 of Section 35<br>DP758790, Lots 1&2 DP174370, Lot 1 DP123406,<br>Lots 3 & 4 DP571310, Lot 11 DP837836, Lot<br>1DP316130 and Lot 1 DP316706              |  |
| LGA                       | North Sydney Council   |  |
| Site Area                 | 1.36 hectares  |  |
| Adjacent Land Uses        | The site is bounded to the North East and South west by residential properties.  |  |
| Site Established          | 1915, as the 'Suspension Bridge' school  |  |
| Existing Site<br>Features | The existing buildings consist of a series of one or<br>two storey buildings. The buildings are finished with<br>predominantly brick and metal wall cladding feature<br>metal roofs. |  |

| Town planning Constraints     |  |  |
|-------------------------------|--|--|
| Land Zoning                   | SP2 Educational Establishment in accordance with<br>North Sydney Council LEP   |  |
| Easements / Site<br>Servicing | Electrical Services Easement is locate to the Palmer Street frontage.  |  |
| Floor Space Ratio             | No FSR applicable to the site  |  |
| Height                        | 8.5m   |  |
| Environmental<br>Constraints  | The building is located within a heritage listed<br>precinct. The Miller Street façade must be designed<br>to be in keeping with the character of the surrounding<br>area. |  |

# Site Analysis

Key site issues identified during a site visit undertaken by Fulton Trotter Architects are tabled below.

Issues identified in Due Diligence reports and the REF reports have also been noted as relevant.



|    | Site Issue                         | Comment / Status  |
|----|------------------------------------|---|
| 1  | Acoustic<br>Impact                 | Traffic noise from Miller Street may necessitate consultation with an acoustic expert   |
| 2  | Temporary<br>buildings             | Subject Demountables already removed from the site for the proposed building.   |
| 3  | Building<br>extension              | The proposed building is to be located right against the existing Building E structure. The interaction between the two structures will need to be reviewed further   |
| 4  | In ground<br>services              | There are some existing in-ground services nominated<br>around the proposed building location in the site survey.<br>Impact on these services will need to be reviewed during<br>future phases of the project |
| 5  | Site levels &<br>DDA<br>compliance | The first level of Building E and the new building is ~1.5<br>meters out of the ground. DDA-compliant pathways will<br>need to be considered in the design  |
| 6  | Cut and Fill                       | Any proposed cut and fill on the site must be reviewed to<br>ensure alignment with the brief and compliance with local<br>council DCP controls.   |
| 7  | Tree<br>Protection<br>Zones        | Trees along the boundary are close to the proposed<br>building. These TPZs should be considered as planning<br>progresses.  |
| 8  | Principle<br>entry                 | Access to the proposed site from Principal entry point<br>must be reviewed due to the significant site level<br>differences.  |
| 9  | Vehicle<br>access                  | Vehicle gate and access from Miller Street should be maintained and clearway for vehicle access should be considered in design  |
| 10 | Mould                              | Mechanical ventilation consideration to be given to the<br>west façade of Building E as part of the design scope.<br>Mould is apparent in the underfloor area   |


# 3 Design Brief

# **Master Plan Validation**

The Master Plan Validation (MPV) phase was undertaken to confirm the planning direction. This involved a review of the NBRS masterplan feasibility report, various due diligence reports, site conditions and liaison with advisory groups. The following scheme has been endorsed by the PCG.

Since the MPV was submitted, these following items have been developed further

- Review of the plant areas to the Miller Street frontage
- Development of the lift and stair locations
- Layout of the classroom spaces and Practical Activities Area
- Creation of a Withdrawal space within the Practical Activities Area



Site plan from MPV report

## © Fulton Trotter Architects Iris 7068CY01 – 05.05.01 – Cammeray PS – Schematic Design Report - Architectural

# The following is the endorsed scope of work:

| Design Brief           |  | Teaching Spaces |
|------------------------|--|-----------------|
| Block G<br>(Classroom) | Ground Floor: General Learning<br>Space x2, Practical Activity Area                | 2               |
|                        | Level 1: General Learning Space x2,<br>Practical Activity Area                     | 2               |
| External Works         | Covered walkways connecting the<br>new buildings to the existing school<br>network |                 |
|                        | New egress stair and lift  |                 |
|                        | Landscaping and external works   |                 |
|                        | Upgrades to site infrastructure and services to support the new buildings          |                 |
|                        | Removal of 3 existing demountable buildings  |                 |
|                        | 50 bicycle parking spaces  |                 |
|                        | Compensatory planting  |                 |
| Works external to site | N/A  |                 |
|                        | TOTAL Teaching Spaces  | 4               |

# The Pattern Book Approach

The new facilities will be constructed using a combination of conventional and modern construction methods. The designs will be a custom design but will align with the principals of the DOE Pattern Book wherever possible. By utilising these established layouts, the project avoids the complexities and uncertainties of developing entirely new designs, ensuring a more efficient and predictable build. This approach not only simplifies construction but also facilitates smoother project management and delivery.

# Schedule of Accommodation

A detailed schedule of accommodation for the proposed works and the overall site has been developed. It is included in **Appendix 2** of this report.

# **EFSG GAP Statement**

A desktop gap analysis prepared by NBRS highlights that most key internal and external facilities identified are not included in the upgrade works and, therefore, do not need to align with the EFSG. While the analysis addresses no shortfall in staff and student amenities and storage, it does not account for the further reduction in these facilities post-demolition, exacerbating the overall gap. These deficiencies must be considered in the design of the proposed classroom buildings

Amenities - Fulton Trotter Architects has conducted a gap analysis to determine the required number of student amenities for the current student population capacity of approximately 667 students. This analysis has demonstrated that there is no shortfall in the number of student amenities provided on the site. Therefore, there are no student amenities proposed as part of this project.

Staff toilets are also included to this analysis. However, as there are no staff facilities proposed as part of this project this is not considered part of the project.

# 4 Design

# **Concept Design Planning**

The new building (Block G) is created adjacent to the existing Block E building. The new building is created to set between the existing building and the setback from Miller Street. The building location requires the removal of 2 of the existing mature trees to the Miller Street frontage. The tree protection zones for the remaining trees can be maintained by the planning and will be protected during the construction period.


The planning of the building allows for 2 General Learning Spaces (GLS) across a 2-storey building. A Practical Activities Area and an adjoining Withdrawal Space is created between the two GLS.

The spaces are accessed from a verandah to the North that provides a connection to the existing Block E verandah. A new stair and a lift are created to the verandah area. This also provides access to the lower level of the building – to connect to the playground area.

Generous windows are provided to the South of the classrooms with views out into the trees.

# **Concept Design Finishes**

Materials and finishes follow the DOE Pattern Book Materials & Finishes principles to be contextual, durable, local & economical. The colour combination is based on project specific local context.



# Design Statement

The proposed building (Builidng G) presents as an extension to the existing building form of Block E. The building sits as a simple form, presenting a simple façade to the Miller Street frontage. Due to the location of the building in a heritage precinct, the façade will sit as a recessive element in the streetscape – sitting behind the existing trees.

The materiality of the building takes its cues from the existing buildings on the site. The façade to Miller Street will be predominantly brickwork in a colour to reflect the existing building materials. The remainder of the building is completed in CFC and anodised aluminium elements. These are finished with a neutral palette – punctuated with a number of feature colours. The feature colours feature red (referring to the colours of the heritage building) and blue (taking cues from Block E as well as the connections to the whale totem that is an important element of Country).






# **Schematic Design Planning**


Following endorsement of the Concept Design for the project the documentation was developed further through greater consultation with the school and coordination with the consultant team. Throughout this phase the design concepts were developed largely in line with the concept design package

Since the Concept Design was submitted, the following items have been developed further:

- The layout of the lift and stairs to the Northern Verandah was reviewed and reconfigured. This came as a result of concerns about the restrictions to circulation paths that the previous layout was creating. The revised layout allows for a more open verandah, allows for more natural light into the teaching spaces and allows for a simpler arrangement of the services spaces (the BCR and EDB rooms)
- The materiality and layout of the elevations has been detailed to refine the building facades.
- The height of the roof was reviewed and increased following coordination with the final detailed survey of the existing Building E roof.
- The layout of the joinery and fixtures inside the teaching spaces was reviewed with the school. The designs are based on what is provided in the Pattern Book, but these have been modified to suit the custom layout of this building.
- The elevation to the building has been reviewed with the DOE Heritage representatives in order to confirm that it is in keeping with the wider community. The changes in the layout of the lift and the stair aided in simplifying the façade. This was approved by the DOE Heritage representatives.
- The removal of 3 existing demountables and the provision of landscaping to 'make good' the area.
- The location of the bike parking and compensatory planting was reviewed with the school and accepted.



Proposed Ground Floor Plan



# **Consultant Coordination**

During the Schematic Design phase coordination was undertaken with the consultant team to develop the details of the project.

The key elements of consultant coordination undertaken during the Schematic Design Phase are outlined below:

- The location and layout of the mechanical plant to the subfloor has been reviewed and coordinated. Following the reconfiguration of the lift and stairs it was rationalised to largely open onto the Miller Street frontage – sitting behind the buffer planting on that streetscape.
- The location of the structural columns has been reviewed, coordinated and rationalilsed to minimise the number of columns required – particularly at the connection to Building E.
- The layout and location of the BCR and EDB rooms as been revised and coordinated following the reconfiguration of the stairs and lift.
- The roof and drainage outside of the lift shaft to provide weather protection for the lift shaft has been developed.
- The work needed on the Main Switchboard for the site has been reviewed and approved by the DOE heritage consultants

# Value Engineering

Fulton Trotter Architects participated in Value Engineering workshops with RP Infrastructure and DOE to review the cost plan for the project. A number of value engineering items in relation to the architectural design were explored as part of this process but have not been adopted.



Artist's Impression – View from South-East

# Landscape


The approach to the Landscape Architectural design draws inspiration from the traditional flora and fauna of the area. The planting selections will also take cues from the new garden spaces being created as part of a separate project. These species are selected because they are native to the area. This has been reviewed with representatives from the AECG as part of the consultation for this project.

Replacement planting is proposed to the Miller Street frontage to replace the trees that are being removed. The new planting in that area provides some screen planting to the building.

Offset planting is also provided adjacent to Building C as a replacement for the 2 mature trees that are removed as part of the project.

Landscaping is also provided to the Bellevue Street frontage – replacing the demountables with synthetic turf (under a separate planning pathway) and providing new bicycle parking. A small welcome garden is also proposed providing and acknowledgement of country and 'Welcome Garden' for the site.

Details of the landscape concept are attached to this report in Appendix 4.




Proposed Landscape Plan (prepared by Ground Ink)

| Design Strategy                |  |
|--------------------------------|--|
| Pattern Book Hubs              | n/a  |
| Teaching Spaces                | 3 demountable removed<br>4 new teaching spaces (Block G)<br>29 permanent teaching spaces total   |
| Amenities Strategy             | The existing amenities for the site has been reviewed<br>and it has been determined that there is no shortfall in<br>the student amenities. There are no new amenities<br>provided as part of these proposed works.                              |
| Play Space                     | 12sqm / student  |
| Building Services<br>Strategy  | New BCR and EDB cupboards are provided to the<br>verandah areas of the new building. Upgrades are<br>required to the existing MSB in Block A.<br>Mechanical plant is located in the sub-floor areas<br>around the perimeter of the new building. |
| Circulation Design<br>Strategy | External walkways to comply with Pattern Book and<br>EFSG Circulation Guidelines (DG08).<br>Walkways tie into the existing building.<br>Lift is integrated into walkway.<br>1 set of stairs – standard design.                                   |
| Connecting with<br>Country     | A formal Connecting with Country process is not<br>being undertaken for this project, however the design<br>team have met with the AECG representatives to<br>discuss initiatives that could be included in the<br>campus.                       |

# **Concept Diagrams**


- Play Space Calculation




| ZONE                            | AREA                 | STUDENTS/SQM                  |
|---------------------------------|----------------------|-------------------------------|
| PROPOSED OUTDOOR PLAYSPACE AREA | 8,191 m <sup>2</sup> | 12.28m <sup>2</sup> /STUDENT* |

\*STUDENT/SQM CALCULATION IS BASED ON A PROPOSED STUDENT POPULATION OF 667

- Accessibility and wayfinding (principal entry) DDA



- Amenities Strategy



|        | STUDENTS | STUDENTS | STAFF & STUDENTS | STAFF |    |   |
|--------|----------|----------|------------------|-------|----|---|
| WC     | 8        | 17       | 4                | 5     |    |   |
| URINAL | 20       |          |                  |       |    | E |
| TOTAL  | 28       | 17       | 4                | 5     | 54 |   |

URINALS - 17+ 1 DISABLED ACCESS WC - 2 UNISEX - 4 PARENT - 1 STAFF ACCESS TOILET - 1 STAFF HWO - 6 HALL -GIRLS - WC - 2 BOYS - WC - 1 URINALS - 3 ACCESS WC - 1

# 5 Consultation

# **Design Consultation**

Fulton Trotter Architects have undertaken a detailed consultation process with the school, the various stakeholders within the NSW Department of Education and the school community as part of planning each phase of this development.

# Buildability

Staging Issues: The site for the proposed building is currently vacant, so there are no early works required to establish the site. A construction zone will be created along the Miller Street frontage. This will need to be established in order to maintain the vehicular access into the school – for service and emergency vehicles.

During the construction period part or all of the existing Block E will need to be vacated to avoid impact of construction noise on the classrooms.

# Safety in Design

A safety in design schedule has been developed for the project. A copy of this report is included in **Appendix 8.** 


# **Connecting with Country**

A formal Connecting with Country process is not being undertaken for this project; however, the design team will contact the school or AECG representatives to discuss initiatives that could be included in the campus.

Following consultation with the AECG representative (Jules Woodhouse) it was determined that a small welcome garden should be created in a small, currently unused garden area at the pedestrian entry off Bellevue Street.

The area will feature native planting and sandstone blocks that will be engraved with a Welcome to Country / Acknowledgement of Country statement.

The area is intended to be a welcoming statement at the point of entry for many of the students.



Details of this proposed response is outlined in the Landscape Drawings attached to this report in Appendix 4.

# Sustainability

The project is not required to achieve a Green Star rating. The environmental performance of the development will be considered in the following ways –

- Siting and Orientation
- Natural Ventilation
- Façade design, utilising the Pattern Book shading devices as appropriate
- Energy Efficient Fixtures and Equipment
- External walls and roof material selection and insulation
- Potential for Rainwater Harvesting

# EFSG

The project has been designed to comply with the requirements of the EFSG and all relevant legislation. Departures that have been raised during Concept Design from these requirements have been recorded in the **EFSG Departures Schedule** included in **Appendix 5**. of this report.

Further discussions, directions and advice from the Design Advisory Team is recorded in the **RFI Tracker** – which is included in **Appendix 6** of this report.

# 6 Services and Engineering

The provision of services to the site and proposed building have been considered and integrated into the overall design outcome. A summary of the services management is outlined below –



| Rainwater &<br>Stormwater<br>Management<br>(Meinhardt) | Because the existing site of the building is bitumen paving<br>no additional OSD tank is required. New in-ground<br>stormwater pipes will be created to collect the roof water<br>drainage and will connect into the existing infrastructure.   |
|--|---|
| Structural<br>Engineering<br>(Meinhardt)               | The 2-storey building is proposed to be a concrete frame<br>structure with reinforced & / post-tensioned flat plate<br>suspended floors. The upper most storey (incl. roof) is to<br>be a proprietary D&C light-weight steel modular frame<br>structure (e.g. Austruss system).   |
| Electrical<br>Services<br>(NDY)                        | <ul> <li>The school is currently supplied by a 315kVa transformer which has capacity for the proposed works (with dispensation from the 15% spare capacity requirement o the AHFG)</li> <li>New submain cabling will be reticulated in existing conduits to new building from the Main Switch Room (MSR) in Block A</li> <li>Replacement of the Main Switch Board insitu in Block A, the heritage listed building.</li> <li>An electrical distribution board (EDB) and a building controom (BCR) will be provided on the verandah areas of the new Block G.</li> <li>New communications reticulation will be provided from the Main Communications Room (MCR) in Block A</li> </ul> |
| Mechanical<br>Services & Air<br>Conditioning<br>(NDY)  | Air conditioning is provided to the proposed new Block G<br>in line with EFSG Requirements. This is provided as a<br>centralised system. Plant areas are to be provided in the<br>sub-floor area at ground level, with ventilation through the<br>façade of the building. A unit is also proposed for the BC  |



| Service                         |   |  |  |  |  |  |  |  |
|---------------------------------|---|--|--|--|--|--|--|--|
| BCA & DDA<br>Assessment         | New Block G<br>Classification: BCA Class 9b (Educational Purposes<br>(classrooms))<br>Construction Type: B  |  |  |  |  |  |  |  |
|                                 | Rise in storeys: 2<br>Climate zone: 6   |  |  |  |  |  |  |  |
| Disability<br>Access:           | Block G has been sited to allow access from the existing<br>Block E. Therefore, no additional DDA accessibility<br>measures are required within the sie. A new lift is provided<br>to create access to all levels of the site.                  |  |  |  |  |  |  |  |
| Traffic                         | A Transport Working Group has been established between<br>DOE and North Sydney Council. This has been facilitated<br>by the project's Traffic Engineer's (Crossley TP). 50<br>additional bike parking spaces are to be provided on the<br>site. |  |  |  |  |  |  |  |
| Waste<br>Management             | Construction and Operational waste management plans have been prepared by EcCell.   |  |  |  |  |  |  |  |
| Loading Zones<br>and Deliveries | The current arrangements for loading zones and deliveries for the site will be maintained.  |  |  |  |  |  |  |  |

# 7 Next Steps

**Design Comments** – items to be resolved in next phase

- 1. **D&C Contractor:** The project will be tendered to D&C contractors based on the Schematic Design documentation.
- Design Development / Issued for Construction Documentation: Once a contractor is engaged they will complete the remainder of the project documentation (through the Design Development phase) to allow for the construction of the project. The remainder of the details and coordination will be completed during this phase.
- 3. **Planning Approval:** Planning approval will be sought for the project through a Review of Environmental Factors (REF).

Refer also to the Design Comments Tracker in Appendix 8



# Appendix 1 CONTACT LIST



| Company                   | Discipline                               | Title/description                                | First Name | Surname          | Work Phone   | Email                                   | Cammeray PS  |
|---------------------------|--|--|------------|------------------|--------------|---|--------------|
| ACOR                      | Hydraulic/Fire                           | Senior Hydraulic Designer                        | Rhys       | Edwards          | 0421 760 925 | redwards@acor.com.au                    |              |
| ADE Consulting Group      | Geotechnical & Contamination<br>Services | Environmental Consultant                         | Karrin     | Azzam            | 0490 072 877 | karin.azzam@adegroup                    |              |
| Arcadis                   | Cost Manager                             | Programme Director                               | David      | Ball             | 0431 639 495 | david.ball@arcadis.com                  |              |
| Arcadis                   | Cost Manager                             | Cluster Director                                 | Sumi       | Sumithiran       | 0415 390 312 | sumi.sumithiran@arcadis.com             |              |
| Arcadis                   | Cost Manager                             | Project Lead                                     | Vincent    | Caspe            | 0423 920 506 | vincent.caspe@arcadis.com               |              |
| Arcadis                   | Cost Manager                             | Project Lead - Senior Cost Manager               | Nicholas   | Koutsoukis       | 0433 634 822 | nicholas.koutsoukis@arcadis.com         |              |
| Arcadis                   | Cost Manager                             | Cost Planner                                     | Juliana    | Campbell         |              | juliana.campbell@arcadis.com            |              |
| City Plan Heritage        | Heritage Consultant                      | Director   | Kerime     | Danis            | 0414 421 035 | kerimed@cityplan.com.au                 |              |
| DoE                       | DoE                                      | Director, Educational Leadership                 | Sharon     | Sands            |              | Sharon.Sands@det.nsw.edu.au             |              |
| DoE                       | DoE                                      | Principal  | Victor     | Tan              | 9955 7200    | VICTOR.TAN@det.nsw.edu.au               |              |
| Fulton Trotter Architects | Architecture                             | Project Director                                 | John       | Ward             | 0411 877 753 | johnw@fultontrotter.com.au              |              |
| Fulton Trotter Architects | Architecture                             | Project Leader                                   | Niloofar   | Khodabandehloo   | 02 8383 5151 | niloofark@fultontrotter.com.au          |              |
| Gyde Consulting           | Town Planner                             | Associate Director                               | Debrah     | Barr             | 9071 1894    | debrahb@gyde.com.au                     |              |
| Gyde Consulting           | Town Planner                             | Assistant Planner                                | Lauren     | Daley            | 9071 1848    | laurend@gyde.com.au                     |              |
| Laurence & Co             | Arborist                                 | Director   | Matthew    | Laurence         | 0404 282 825 | matthew@laurenceco.com.au               |              |
| Wall Shuler & Associates  | BCA/DDA                                  | Senior BCA/DDA Consultant                        | Daniel     | Murrow           | 938/ 4441    | daniel@msaconsultants.com.au            |              |
| (MSA)                     | BONY BER                                 | Schiol Bory BBR Schistitant                      | Damer      | Warrow           | 0414 062 759 | daniciem saconsultants.com.au           |              |
| Meinhardt                 | Project Lead                             | Associate Director                               | John       | Bea              | 0414 350 360 | john.bea@meinhardtgroup.com             |              |
| Meinhardt                 | Structural Lead                          | Associate Structural Engineer                    | Vivien     | Chen             | 02 8247 8424 | vivien.chen@meinhardtgroup.com          | $\checkmark$ |
| Meinhardt                 | Civil                                    | Associate Civil Engineer                         | Yolandi    | Cooper           | 0432 323 113 | yolandi.cooper@meinhardtgroup.com       |              |
| Meinhardt                 | Civil                                    | Civil Lead                                       | Brad       | Lusty            |              | brad.lusty@meinhardtgroup.com           |              |
| Meinhardt                 | Civil                                    | Structural Engineer                              | Goran      | Milenkovic       | 02 8252 0422 | goran.milenkovic@meinhardtgroup.com     |              |
| NDY                       | Elec/Mech/Acoustic/ESD                   | Associate Director (Project Director)            | Jarrad     | Underwood        | 0434 671 435 | j.underwood@ndy.com                     |              |
| NDY                       | Elec/Mech/Acoustic/ESD                   | Senior Engineer (Project Leader)                 | Shri       | Sapre            | 0410 529 520 | s.sapre@ndy.com                         |              |
| NDY                       | Elec/Mech/Acoustic/ESD                   | Engineer (Project Support)                       | Caitlan    | Gilmore          | 0401 471 856 | c.gilmore@ndy.com                       |              |
| NDY                       | Mechanical                               | Senior Engineer (Mechanical Lead)                | Chia       | Halim            | 0401 322 715 | c.halim@ndy.com                         |              |
| NDY                       | Electrical                               | Senior Engineer (Electrical Lead)                | Kristina   | Fernandez-Garcia | 0449 094 451 | k.fernandez@ndy.com                     |              |
| NDY                       | Acoustics                                | Senior Engineer (Acoustic Lead)                  | Victoria   | Rastelli         | 0421 736 119 | v.rastelli@ndy.com                      |              |
| NDY                       | ESD                                      | Senior Engineer (ESD Lead)                       | Richard    | Burton           | 0431 544 918 | r.burton@ndy.com                        |              |
| NDY                       | Acoustics                                | Acoustic Engineer                                | Jim        | Wu               | 0482 598 946 | j.wu@ndy.com                            |              |
| RP Infrastructure         | Project Manager                          | Associate Director (Program Lead)                | Matt       | Spooner          | 0418 203 222 | matthew.spooner@rpinfrastructure.com.au |              |
| RP Infrastructure         | Project Manager                          | Senior Project Manager (North Metro Cluster      | Lynne      | Donohoe          | 0416 143 638 | Lynne.Donohoe@rpinfrastructure.com.au   |              |
| RP Infrastructure         | RP Infrastructure                        | Senior Project Coordinator                       | Ann        | Connolly         | 0401 313 437 | ann.connolly@rpinfrastructure.com.au    |              |
| SINSW                     | Infrastructure Planning                  | Senior Transport Planner, North Region Transport |            | Ng               | 0460 821 882 | jessica.ng11@det.nsw.edu.au             |              |
| SINSW                     | Internal SINSW Statutory Planner         | Statutory Planning Officer (Planning)            | Patrick    | Mills            | 0413 692 339 | patrick.mills11@det.nsw.edu.au          |              |
| SINSW                     | Internal SINSW Statutory Planner         | Statutory Planning                               | David      | Lewis            |              | david.lewis83@det.nsw.edu.au            |              |
| SINSW                     | Infrastructure Planning / Delivery       | Senior Group Leader                              | Meenu      | Bansal           | 0457 058 513 | meenu.bansal@det.nsw.edu.au             |              |
| SINSW                     | Infrastructure Delivery                  | Community Engagement Manager                     | Sara       | Gardner Gentles  |              | Sara.GardnerGentles1@det.nsw.edu.au     |              |
| SINSW                     | Technical Services                       | Project Manager - Transport                      | Kamoru     | Adetunmbi        | 0499 845 783 | Kamoru.Adetunmbi2@det.nsw.edu.au        |              |

Appendix 2 SCHEDULE OF ACCOMMODATION



# **Primary School**

# GAP ANALYSIS AND SCHEDULE OF ACCOMMODATION - DETAILS

| Project information        |                                |
|----------------------------|--------------------------------|
| School name                | Cammeray Public School (K-6)   |
| Current enrolments         | 687 (source: myschool website) |
| Target Proposed enrolments |                                |
| Current Stream size        | 2                              |
| Proposed Stream size       | 2 (Primary School Medium)      |

|              |                                |             | Stream                                    |      |     |        |              |      | Exis | ting   |              |       |           |           |       |
|--------------|--------------------------------|-------------|---|------|-----|--------|--------------|------|------|--------|--------------|-------|-----------|-----------|-------|
|              |                                |             |   |      | EF  | SG     |              |      | AMS  | Data   |              | New a | nd Refurb | ished Are | as To |
| EFSG Unit ID | Proposed<br>AMS Room<br>Number | Room Number | Space                                     | Size | No. | Total  | FTS<br>Count | Size | No.  | Total  | FTS<br>Count | Size  | No.       | Total     | FTS   |
| PS 100       |                                |             | GENERAL LEARNING SPACES                   |      |     |        |              |      |      |        |              |       |           |           |       |
| PS101        |                                |             | GENERAL LEARNING SPACES HUB               |      |     |        |              |      |      |        |              |       |           |           |       |
| PS101.01     |                                |             | General Learning Space (GLS)              | 67.5 | 24  | 1620   | 24           | 60   | 25   | 1495   | 25           |       |           |           |       |
|              |                                | GR101       | General Learning Space 1                  |      |     |        |              |      |      |        |              | 66.0  | 1         | 66        |       |
|              |                                | GR102       | General Learning Space 2                  |      |     |        |              |      |      |        |              | 66.0  | 1         | 66        |       |
|              |                                | GR201       | General Learning Space 3                  |      |     |        |              |      |      |        |              | 66.0  | 1         | 66        |       |
|              |                                | GR202       | General Learning Space 4                  |      |     |        |              |      |      |        |              | 66.0  | 1         | 66        |       |
| PS101.02     |                                |             | Storage                                   |      | 1   |        |              |      |      |        |              |       |           |           | ┢     |
|              |                                |             | included in GLS as cabinetary             |      |     |        |              |      |      |        |              |       |           |           |       |
|              |                                |             | Home base Store                           |      |     |        |              | 6    | 21   | 132    |              |       |           |           |       |
| PS101.03     |                                |             | Learning Commons (LC)                     | 135  | 6   | 810    |              |      |      |        |              |       |           |           | ┝     |
| 15101.05     |                                |             |   | 155  | 0   | 010    |              |      |      |        |              |       |           |           | ┢     |
| PS101.04     |                                |             | Practical Activities Area (PAA)           |      | 2   |        |              | 19   | 20   | 387    |              |       |           |           |       |
|              |                                |             | included within Learning Common           |      |     |        |              |      |      |        |              |       |           |           |       |
|              |                                | GR103       | Practical Activities Area (PAA) 1         |      |     |        |              |      |      |        |              | 55.0  | 1         | 55.0      |       |
|              |                                | GR203       | Practical Activities Area (PAA) 2         |      |     |        |              |      |      |        |              | 55.0  | 1         | 55.0      |       |
| PS101.05     |                                |             | Multi Purpose Space (MPS)                 |      | 6   |        |              |      |      |        |              |       |           |           | ┢     |
|              |                                |             | Withdrawl Type 1                          |      |     |        |              | 10   | 12   | 124    |              |       |           |           |       |
|              |                                |             | TOTAL sqm GLS                             |      |     | 2430.0 | 24           |      |      | 2138.0 | 25           |       |           | 374.0     |       |
|              |                                |             |   |      |     | 2430.0 | 24           |      |      | 2156.0 | 25           |       |           | 574.0     | -     |
| PS102        |                                | •           | GENERAL LEARNING SPACES HUB (SUPPORT HUB) |      |     |        |              |      |      |        |              |       |           |           |       |
|              |                                |             |   | Size | No. | Total  | FTS<br>Count | Size | No.  | Total  | FTS<br>Count | Size  | No.       | Total     | FTS   |
| PS102.01     |                                |             | General Learning Space (GLS)              | 67.5 |     | 202.5  |              |      |      |        |              |       |           |           |       |
| PS102.02     |                                |             | Storage                                   |      | 1   |        |              |      |      |        |              |       |           |           |       |
|              |                                |             | included in GLS as cabinetary             |      |     |        |              |      |      |        |              |       |           |           |       |
| DS102.02     |                                |             | Learning Commons (LC)                     | 125  | 4   | 125    |              |      |      |        |              |       |           |           | ╞     |
| PS102.03     |                                |             | Learning Commons (LC)                     | 135  |     | 135    |              |      |      |        |              |       |           |           |       |



| otal    |  |
|---------|--|
|         |  |
|         |  |
| S Count | Comments   |
|         |  |
|         |  |
|         | All demountables are excluded from cout.All home |
|         | bases <47sqm                                     |
| 1       |  |
| 1       |  |
|         |  |
| 1       |  |
| 1       |  |
|         |  |
|         |  |
|         |  |
|         |  |
|         |  |
|         |  |
|         |  |
|         |  |
|         |  |
| 0       |  |
| 0       |  |
|         |  |
|         |  |
|         |  |
|         |  |
| 4       |  |
|         |  |
|         |  |
|         |  |
| 6 Count |  |
|         |  |
|         |  |
|         |  |
|         |  |
|         |  |
|         |  |



|                      |                                |             | Stream                          |           |       |           |              |      | Exis     | sting |              |       |           |           |       |
|----------------------|--------------------------------|-------------|---------------------------------|-----------|-------|-----------|--------------|------|----------|-------|--------------|-------|-----------|-----------|-------|
|                      |                                |             |                                 |           | EF    | SG        |              |      | AMS      | Data  |              | New a | nd Refurb | ished Are | as To |
| EFSG Unit ID         | Proposed<br>AMS Room<br>Number | Room Number | Space                           | Size      | No.   | Total     | FTS<br>Count | Size | No.      | Total | FTS<br>Count | Size  | No.       | Total     | FTS   |
| PS102.04             |                                |             | Practical Activities Area (PAA) |           | 2     |           |              |      |          |       |              |       |           |           |       |
|                      |                                |             | included in Learning Commons    |           |       |           |              |      |          |       |              |       |           |           |       |
|                      |                                |             |                                 |           |       |           |              |      |          |       |              |       |           |           |       |
| PS102.05             |                                |             | Multi Purpose Space (MPS)       |           | 1     |           |              |      |          |       |              |       |           |           |       |
|                      |                                |             | included in Learning Commons    |           |       |           |              |      |          |       |              |       |           |           |       |
| PS102.06             |                                |             | Support Hub Meeting Room        | 20        | 1     | 20        |              |      |          |       |              |       |           |           |       |
| PS102.07             |                                |             | Staff WC                        | 5.5       | 1     | 5.5       |              |      |          |       |              |       |           |           |       |
| PS102.08             |                                |             | Access Toilet                   | 6.5       | 2     | 13        |              |      |          |       |              |       |           |           |       |
| PS102.09             |                                |             | Adult Change Facility + Shower  | 14        | 1     | 14        |              |      |          |       |              |       |           |           |       |
| PS102.10             |                                |             | Ambulant Toilets                | 3.5       | 2     | 7         |              |      |          |       |              |       |           |           |       |
| PS102.11             |                                |             | Laundry                         | 8         | 1     | 8         |              |      |          |       |              |       |           |           |       |
|                      |                                |             |                                 |           |       |           |              |      |          |       |              |       |           |           |       |
| PS102.12             |                                |             | Outdoor Learning Commons (OLC)  | 1         | 135   | 135       |              |      |          |       |              |       |           |           |       |
|                      |                                |             |                                 |           |       |           |              |      |          |       |              |       |           |           |       |
|                      |                                |             | TOTAL sqm SUPPORT GLS           |           |       | 540.0     | 0            |      |          | 0.0   | 0            |       |           | 0.0       |       |
|                      |                                |             |                                 |           |       |           |              |      |          |       |              |       |           |           |       |
| PS 200               |                                |             | CORE FACILITIES                 |           |       |           |              |      |          |       |              |       |           |           |       |
| PS201                |                                |             | ADMINISTRATION HUB              |           |       |           |              |      |          |       |              |       |           |           |       |
|                      |                                |             |                                 | Size      | No.   | Total     |              | Size | No.      | Total |              | Size  | No.       | Total     | FTS   |
| PS201.01             |                                |             | Entry Vestibule                 | 22        | 1     | 22        |              | 16   | 1        | 16    |              |       |           |           |       |
| PS201.02             |                                |             | Principal / Meeting Room        | 20        | 1     | 20        |              | 13   | 1        | 13    |              |       |           |           |       |
| PS201.03             |                                |             | Deputy Principal's Office       | 48        | 1     | 48        |              | 14   | 1        | 14    |              |       |           |           |       |
|                      |                                |             | Deputy Principal type 2         |           |       |           |              | 18   | 1        | . 18  |              |       |           |           |       |
| PS201.04             |                                |             | Interview Room / Office         | 33        | 1     | 33        |              | 14   | 1        | . 14  |              |       |           |           |       |
|                      |                                |             | Interview office - type 3       |           |       |           |              | 17   | 1        | . 17  |              |       |           |           |       |
| PS201.05             |                                |             | Clerical / Printing             | 61.5      | 1     | 61.5      |              | 24   | 2        | 48    |              |       |           |           |       |
| PS201.06             |                                |             | Security Store Room             | 11        | 1     | 11        |              | 11   | 2        | 22    |              |       |           |           |       |
| PS201.07             |                                |             | Sick Bay                        | 14        | 1     | 14        |              | 10   | 1        | 10    |              |       |           |           |       |
| PS201.08             |                                |             | Accessible Toilet / Shower      | 8         | 1     | 8         |              |      |          |       |              |       |           |           |       |
| PS201.09             |                                |             | Store / Community Clinic        |           | 0     | 0         |              |      |          |       |              |       |           |           |       |
| PS201.10             |                                |             | Circulation                     | 19.5      | 1     | 19.5      |              |      |          |       |              |       |           |           |       |
|                      |                                |             | TOTAL sqm ADMIN                 |           |       | 237.0     | 0            |      |          | 172.0 | 0            |       |           | 0.0       |       |
| PS202                |                                |             | STAFF HUB                       |           |       |           |              |      |          |       |              |       |           |           |       |
|                      |                                |             |                                 | Size      | No.   | Total     |              | Size | No.      | Total |              | Size  | No.       | Total     | FTS   |
| PS202.01             |                                | 1           | Staff Loungo                    |           | NU. 1 |           |              | 23   | NU.<br>3 | 74    |              | 3120  | NO.       | TOLAI     |       |
| PS202.01<br>PS202.02 |                                |             | Staff Lounge<br>Kitchen Area    | 125<br>10 | 1     | 125<br>10 |              | 23   | 5        | 74    |              |       |           | <u> </u>  |       |
| PS202.02<br>PS202.03 |                                |             | Staff Toilets                   | 33        | 1     | 33        |              | 0    | 0        | 0     |              |       |           |           | -     |
| . 5202.05            |                                |             |                                 | 55        | 1     |           |              | 0    | 0        | 0     |              |       |           |           |       |
|                      |                                |             | Access shower toilet            |           |       |           |              | 0    | 0        | Ŭ     |              |       |           |           |       |
|                      |                                |             | Staff room annex                |           |       |           |              | 24   | 1        | 24    |              |       |           |           |       |

| otal    |   |
|---------|---|
|         |   |
| S Count | Comments  |
|         |   |
|         |   |
|         |   |
|         |   |
|         |   |
|         |   |
|         |   |
|         |   |
|         |   |
|         |   |
| 0       |   |
| 0       |   |
|         |   |
|         |   |
| S Count |   |
|         |   |
|         | 1 x single 13sqm min office & 1x double 26sqm min office                                      |
|         | 1x 13sqm rooms min & 1x 17sqm room min.   |
|         |   |
|         |   |
|         |   |
|         |   |
|         | Not standard inclusion. Could be archive store,<br>community clinici, other. Confirm with DoE |
|         |   |
| 0       |   |
|         |   |
| S Count |   |
|         |   |
|         | 2F + 2M + 1 Acc (includes circulation)  |
|         | requires site validation  |
|         | requires site validation<br>requires site validation  |
|         |   |



|                      |                                |             | Stream  |           |     |           |              |      | Exis | ting     |              |       |                                 |          |           |  |
|----------------------|--------------------------------|-------------|---|-----------|-----|-----------|--------------|------|------|----------|--------------|-------|---------------------------------|----------|-----------|--|
|                      |                                |             |   |           | EF  | SG        |              |      |      | Data     |              | New a | New and Refurbished Areas Total |          | as Total  |  |
| EFSG Unit ID         | Proposed<br>AMS Room<br>Number | Room Number | Space   | Size      | No. | Total     | FTS<br>Count | Size | No.  | Total    | FTS<br>Count | Size  | No.                             | Total    |           | Comments   |
| PS202.04             |                                |             | External Circulation                          | 0         | 0   | 0         | count        | 5120 | NO.  | TOTAL    |              | SIZE  | NO.                             | TOLA     |           | Not a standard inclusion. Found in S size only.<br>Footprint could be utilised for other purposed. Confirm<br>with DoE |
|                      |                                |             |   |           |     |           |              |      |      |          |              |       |                                 |          |           |  |
|                      |                                | 1           | TOTAL sqm STAFF                               |           |     | 168.0     | 0            |      |      | 98.0     | 0            |       |                                 | 0.0      | 0         |  |
|                      |                                |             |   |           |     |           |              |      |      |          |              |       |                                 |          |           |  |
| PS203                |                                |             | HALL, CANTEEN & OSHC                          |           |     |           |              |      |      |          |              |       |                                 |          |           |  |
|                      |                                |             |   | Size      | No. | Total     |              | Size | No.  | Total    |              | Size  | No.                             | Total    | FTS Count |  |
| PS203.01             |                                |             | Communal Hall                                 | 216       | 1   | 216       |              | 214  | 1    | 214      |              |       |                                 |          |           |  |
| PS203.02             |                                |             | Stage   | 50        | 1   | 50        |              | 36   | 1    | 36       |              |       |                                 |          |           |  |
| PS203.03             |                                |             | Chair Store Room                              | 14        | 1   | 14        |              | 16   | 1    | 16       |              |       |                                 |          |           |  |
| PS203.04             |                                |             | PE Store Room                                 | 16        | 1   | 16        |              |      |      |          |              |       |                                 |          |           |  |
| PS203.05             |                                |             | Sports Store Room                             | 13        | 1   | 13        |              | 15   | 1    | 15       |              |       |                                 |          |           |  |
| PS203.06             |                                |             | Performance Store Room                        | 11        | 1   | 11        |              |      |      |          |              |       |                                 |          |           |  |
| PS203.07             |                                |             | Sound Cupboard                                | 2         | 1   | 2         |              | 1    | 1    | 1        |              |       |                                 |          |           |  |
| PS203.08             |                                |             | Toilets                                       | 20        | 1   | 20        |              |      |      |          |              |       |                                 |          |           | 3M + 3F  |
|                      |                                |             | Toilets girls - number of pans                |           |     |           |              | 8    | 0    | 0        |              |       |                                 |          |           | requires site validation   |
|                      |                                |             | Toilet boys - number of pans                  |           |     |           |              | 7    | 0    | 0        |              |       |                                 |          |           | requires site validation   |
|                      |                                |             | Toilet boys - Linear metreage of urinals      |           |     |           |              | 0    | 0    | 0        |              |       |                                 |          |           | requires site validation   |
| PS203.09             |                                |             | Accessible Toilet / Shower                    | 8         | 1   | 8         |              | 0    | 0    | 0        |              |       |                                 |          |           | requires site validation   |
| PS203.10             |                                |             | OSHC office                                   | 21        | 1   | 21        |              |      |      |          |              |       |                                 |          |           | requires site validation   |
| PS203.11             |                                |             | OSHC store                                    | 26        | 1   | 26        |              |      |      |          |              |       |                                 |          |           | requires site validation   |
| PS203.12             |                                |             | OSHC Kitchenette                              | 20        | 1   | 20        |              |      |      |          |              |       |                                 |          |           | requires site validation   |
| PS203.13             |                                |             | Canteen Office / Store Room                   | 15        | 1   | 15        |              | 21   | 1    | 21       |              |       |                                 |          |           |  |
| PS203.14             |                                |             | Canteen                                       | 38        | 1   | 38        |              | 4    | 1    | 4        |              |       |                                 |          |           |  |
| PS203.15             |                                |             | Servery Covered Area                          |           | 1   | 0         |              |      |      |          |              |       |                                 |          |           |  |
|                      |                                |             | included in PS501.01 COLA (36sqm min)         |           |     |           |              |      |      |          |              |       |                                 |          |           |  |
| PS203.16             |                                |             | Staff Accessible Toilet                       | 8         | 1   | 8         |              |      |      |          |              |       |                                 |          |           |  |
| PS203.17             |                                |             | Garden Store Room                             | 13        | 1   | 13        |              |      |      |          |              |       |                                 |          |           |  |
| PS203.18             |                                |             | Bulk Store Room                               | 16        | 1   | 16        |              |      |      |          |              |       |                                 |          |           |  |
| PS203.19             |                                |             | Cleaning Supplies Store Room                  | 10        | 1   | 10        |              |      |      |          |              |       |                                 |          |           |  |
| PS203.20             |                                |             | Internal Circulation                          | 56.75     | 1   | 56.75     |              |      |      |          |              |       |                                 |          |           |  |
|                      |                                |             |   |           |     |           |              |      |      |          |              |       |                                 |          |           |  |
|                      |                                | 1           | TOTAL sqm HALL, CANTEEN + OSHC (min.)         |           |     | 573.8     | 0            |      |      | 307.0    | 0            |       |                                 | 0.0      | 0         |  |
| DC304                |                                |             |   |           |     |           |              |      |      |          |              |       |                                 |          |           |  |
| PS204                |                                |             | LIBRARY HUB                                   |           | ••  | <b>T</b>  |              | C    |      | <b>T</b> |              |       |                                 | <b>T</b> | LTC Cr    |  |
| DC204.04             |                                |             |   | Size      | No. | Total     |              | Size | No.  | Total    |              | Size  | No.                             | Total    | FTS Count |  |
| PS204.01<br>PS204.02 |                                |             | Library Main Area<br>Shared Office / Workroom | 270<br>27 | 1   | 270<br>27 |              | 90   | 1    | 90       |              |       |                                 |          |           |  |
|                      |                                |             |   |           |     |           |              |      |      |          |              |       |                                 |          |           |  |
| PS204.03<br>PS204.04 |                                |             | KLA Resource Store Room<br>Staff Toilet       | 20        | 1   | 20        |              |      |      |          |              |       |                                 |          |           |  |
|                      | +                              |             |   | 22        |     | ,         |              |      | -    |          |              |       |                                 |          |           |  |
| PS204.05             |                                |             | Special Programs Room                         | 33        | 2   | 66        |              | 46   | 2    | 91       |              |       |                                 |          |           |  |
| PS204.06             |                                |             | Special Programs Storage                      | 0         | 1   | 0         |              |      |      |          |              |       |                                 |          |           |  |
|                      |                                |             | Included within the GLS as cabinetry          |           |     |           |              |      |      |          |              |       |                                 |          |           |  |



|                      |                                |             | Stream                                     |      |     |       |              |      | Exis | ting  |              |       |           |            |           |  |
|----------------------|--------------------------------|-------------|--|------|-----|-------|--------------|------|------|-------|--------------|-------|-----------|------------|-----------|--|
|                      |                                |             |  |      | EFS | SG    |              |      |      | Data  |              | New a | nd Refurb | ished Area | as Total  |  |
| EFSG Unit ID         | Proposed<br>AMS Room<br>Number | Room Number | Space                                      | Size | No. | Total | FTS<br>Count | Size | No.  | Total | FTS<br>Count | Size  | No.       | Total      |           | Comments   |
| PS204.07             |                                |             | Store                                      | 6    | 1   | 6     |              |      |      |       |              |       |           |            |           |  |
| PS204.08             |                                |             | Student Toilets                            | 9    | 1   | 9     |              |      |      |       |              |       |           |            |           |  |
| PS204.09             |                                |             | Circulation                                |      | 0   | 0     |              |      |      |       |              |       |           |            |           | Not standard inclusion. Footprint could be utilised for other purposes. Confirm with DoE |
|                      |                                |             | TOTAL sqm LIBRARY                          |      |     | 405.0 | 0            |      |      | 181.0 | 0            |       |           | 0.0        | 0         |  |
|                      |                                |             |  |      |     |       |              |      |      |       |              |       |           |            |           |  |
| PS 400               |                                |             | STUDENT AMENITIES + STORAGE + SERVIC       | CES  |     |       |              |      |      |       |              |       |           |            |           |  |
| PS401                |                                |             | STUDENT AMENITIES                          |      |     |       |              |      |      |       |              |       |           |            |           |  |
|                      |                                |             |  | Size | No. | Total |              | Size | No.  | Total |              | Size  | No.       | Total      | FTS Count |  |
| PS401.01             |                                |             | Toilets - Girls - WCs                      | 4    | 17  | 68    |              | 44   | 0    | 0     |              |       |           |            |           | requires site validation   |
| PS401.02             |                                |             | Toilets - Boys - WCs                       | 4    | 15  | 60    |              | 43   | 0    | 0     |              |       |           |            |           | requires site validation   |
| PS401.03             |                                |             | Toilets - Boys - Urinals                   |      |     | 0     |              |      | 0    | 0     |              |       |           |            |           | Urinals are replaced by cubicals at 1 cubical per<br>600mm of urinal                     |
| PS401.04             |                                |             | Drinking Facilities                        |      | 17  | 0     |              |      | 0    |       |              |       |           |            |           | requires site validation   |
| PS401.05             |                                |             | Hand Washing Outlets                       |      | 18  | 0     |              |      | 0    |       |              |       |           |            |           | requires site validation   |
| PS401.06             |                                |             | Access Toilet                              | 8    | 3   | 24    |              |      | 0    |       |              |       |           |            |           | to code requirements   |
|                      |                                |             | Shower / Change                            |      |     |       |              | 2    | 1    | 2     |              |       |           |            |           |  |
|                      |                                |             |  |      |     |       |              |      |      |       |              |       |           |            |           |  |
|                      |                                |             | TOTAL sqm STUDENT AMENITIES                |      |     | 152.0 | 0            |      |      | 2.0   | 0            |       |           | 0.0        | 0         |  |
| PS402                |                                |             | OTHER STORAGE / SERVICES                   |      |     |       |              |      |      |       |              |       |           |            |           |  |
|                      |                                |             |  | Size | No. | Total |              | Size | No.  | Total |              | Size  | No.       | Total      | FTS Count |  |
| PS402.01             |                                |             | Cleaning Distributed Store Room            | 3    | 1   | 3     |              | 1    | 1    | 1     |              |       |           |            |           |  |
| PS402.02             |                                |             | Main Communications Room                   | 15.5 | 1   | 15.5  |              |      | 0    |       |              |       |           |            |           | requires site validation   |
| PS402.03             |                                |             | Building Communications Room               | 8.4  | 2   | 16.8  |              |      | 0    |       |              |       |           |            |           | requires site validation   |
| PS402.04             |                                |             | Laundry                                    | 8    | 1   | 8     |              |      | 0    |       |              |       |           |            |           | requires site validation   |
| PS402.05             |                                |             | Kiln                                       | 6    | 1   | 6     |              |      |      |       |              |       |           |            |           |  |
| PS402.06             |                                |             | Main Switchboard Cupboard                  | 8    | 1   | 8     |              |      | 0    |       |              |       |           |            |           | Size to Statutory Requirements.  |
| PS402.07             |                                |             | Distribution Board Cupboard                |      |     | 0     |              |      | 0    |       |              |       |           |            |           | Size to Statutory Requirements.  |
| PS402.08             |                                |             | Other services + Circulation Area Estimate | 90.7 | 1   | 90.7  |              |      |      |       |              |       |           |            |           |  |
|                      |                                |             | Garden Store                               |      |     |       |              | 5    | 3    | 15    |              |       |           |            |           |  |
|                      |                                |             | Bulk Store                                 |      |     |       |              | 24   | 9    | 217   |              |       |           |            |           |  |
|                      |                                |             | Cleaning supplies store                    |      |     |       |              | 2    | 1    | 2     |              |       |           |            |           |  |
|                      |                                | GR104       | Building Control Room (BCR)                |      |     |       |              |      |      |       |              | 6     | 1         | 6          |           |  |
|                      |                                | GR105       | Airlock                                    |      |     |       |              |      |      |       |              |       | 1         | 0          |           |  |
|                      |                                |             |  |      |     |       |              |      |      |       |              |       |           |            |           |  |
|                      |                                |             | TOTAL sqm OTHER STORAGE / SERVICES         |      |     | 148   | 0            |      |      | 235   | 0            |       |           | 6.0        | 0         |  |
| PS403                |                                | I           | OTHER MOVEMENT / SERVICES                  |      |     |       |              |      |      |       |              |       |           |            |           |  |
| - 3403               |                                |             |  | Cinc | Ne  | Total |              | Cine | Ne   | Tatal |              | Cinc  | Ne        | Tatal      | FTS Count |  |
| DS 402 01            |                                | T           | Mechanical Services Pad                    | Size | No. | Total |              | Size | No.  | Total |              | Size  | No.       | Total      |           | excluded   |
|                      | 1                              | 1           | IVIECHAIIICAI SEI VICES PAU                | 0    | 0   | 0     |              |      |      |       |              | 0     | 1         | 0          |           |  |
| PS403.01<br>PS403.02 |                                |             | Movement External (within 9x7.5 grid)      | 0    | 1   | _     |              |      |      |       |              |       |           |            |           |  |



|              |                                |             | Stream  |            |       |        |                       |      | Exis | sting  |              |       |            |            |          |
|--------------|--------------------------------|-------------|---|------------|-------|--------|-----------------------|------|------|--------|--------------|-------|------------|------------|----------|
|              |                                |             |   |            | EF    | SG     |                       |      | AMS  | Data   |              | New a | nd Refurbi | ished Area | is To    |
| EFSG Unit ID | Proposed<br>AMS Room<br>Number | Room Number | Space   | Size       | No.   | Total  | FTS<br>Count          | Size | No.  | Total  | FTS<br>Count | Size  | No.        | Total      | FTS      |
| PS403.04     |                                |             | External Circulation (PS401- within 9x7.5 grid) | 125        | 1     | 125    |                       |      |      |        |              |       |            |            |          |
| PS403.05     |                                |             | Staircase                                       | 396        | 1     | 396    |                       |      |      |        |              | 0     | 1          | 0          |          |
| PS403.06     |                                | GR106       | Lifts   |            | 2     | 0      |                       |      |      |        |              | 0     | 1          | 0          |          |
|              |                                | GR107       | Movement External                               |            |       |        |                       |      |      |        |              | 0     | 1          | 0          |          |
|              |                                | GR117       | Walkway   |            |       |        |                       |      |      |        |              | 0     | 1          | 0          |          |
|              |                                | G1007       | Movement External                               |            |       |        |                       |      |      |        |              | 0     | 1          | 0          |          |
|              |                                |             |   |            |       |        |                       |      |      |        |              |       |            |            |          |
|              |                                |             | TOTAL sqm OTHER MOVEMENT / SERVICES             |            |       | 1748   | 0                     |      |      | 0      | 0            |       |            | 0.0        |          |
|              |                                |             | TOTAL AREA (FECA + UCA)                         |            |       | 6637.8 | (includes<br>PS501.1) |      |      | 3133.0 |              |       |            | 380.0      |          |
|              |                                |             |   |            |       |        |                       |      |      |        |              |       |            |            |          |
| PS 500       |                                |             | OUTDOOR AREAS                                   |            |       |        |                       |      |      |        |              |       |            |            |          |
| P\$501       |                                |             | OUTDOOR AREAS                                   |            |       |        |                       |      |      |        |              |       |            |            |          |
|              |                                |             |   | Size       | No.   | Total  |                       | Size | No.  | Total  |              | Size  | No.        | Total      | FTS      |
| PS501.01     | -                              |             | Covered Outdoor Space (COLA)                    | 236        | 1     | 236    |                       | 5120 |      | Total  |              | 5120  |            | Total      |          |
|              |                                |             | Servery Covered Area                            |            |       |        |                       |      | 0    |        |              |       |            |            | $\vdash$ |
| PS501.02     |                                |             | Tiered Outdoor Learning Space                   |            | 1     | 0      |                       |      |      |        |              |       |            |            |          |
| PS501.03     |                                |             | Assembly Court                                  | 630        | 1     | 630    |                       |      | 1    |        |              |       |            |            |          |
| PS501.04     |                                |             | Assembly Court - Flagpole                       |            | 3     | 0      |                       |      | 0    |        |              |       |            |            |          |
| PS501.05     |                                |             | Games Court                                     | 576        | 1     | 576    |                       |      | 0    |        |              |       |            |            |          |
| PS501.06     |                                |             | Open Play Space                                 | 10sqm / st | udent |        |                       |      | 0    |        |              |       |            |            |          |
| PS501.07     |                                |             | Bulk Waste Pad                                  | Variable   |       |        |                       |      | 0    |        |              |       |            |            |          |
| PS501.08     |                                |             | Bicycle Parking / Enclosure                     | Variable   |       |        |                       |      | 0    |        |              |       |            |            |          |
| PS501.09     |                                |             | Car Parking                                     | Variable   |       |        |                       |      | 0    |        |              |       |            |            |          |
| PS501.10     |                                |             | Kiss and Drop Zone                              | Variable   |       |        |                       |      | 0    |        |              |       |            |            |          |
| PS501.11     |                                |             | Bus Zone /s                                     | Variable   |       |        |                       |      |      |        |              |       |            |            |          |
|              |                                |             | TOTAL sqm OUTDOOR AREAS                         |            |       | 1442   | 0                     |      |      | 0      | 0            |       |            | 0          |          |

Note

NUFA excludes horizontal and vertical circulation; structure, walls or other engineering; services and plant rooms

Note

EFSG reference codes may vary depending on size of school

| otal    |                          |
|---------|--------------------------|
|         |                          |
| Count   | Commente                 |
| S Count | Comments                 |
|         |                          |
|         | x4 up to 3 storeys       |
|         | 2 Lifts                  |
|         |                          |
|         |                          |
|         |                          |
|         |                          |
| 0       |                          |
|         |                          |
|         |                          |
|         |                          |
|         |                          |
|         |                          |
| S Count |                          |
| 5 Count |                          |
|         | requires site validation |
|         |                          |
|         |                          |
|         | requires site validation |
|         |                          |
|         |                          |
| 0       |                          |
| 0       |                          |
|         |                          |

# Appendix 3 ARCHITECTURAL SCHEMATIC DESIGN

# CAMMERAY PUBLIC SCHOOL FOR SCHOOL INFRASTRUCTURE NSW 7068CY01



|            |          |          |            | Drawing Name<br>COVER SHEET + DRAWING LIST   | Rev      |
|------------|----------|----------|------------|--|----------|
| CPS        | FTA XX   | ΧХ       | DR A 0000  | COVER SHEET + DRAWING LIST   | 04       |
| CPS        | FTA XX   | ΧХ       | DR A 0001  | SPECIFICATION SCHEDULE & MATERIAL SELECTIONS   | 04       |
| CPS        | FTA XX   | ХΧ       | DR A 0002  | SIGNAGE SCHEDULE   | 02       |
| CPS        | FTA 00   | 00       | DR A 1001  | EXISTING SITE PLAN   | 04       |
| CPS        | FTA 00   | 00       | DR A 1002  | DEMOLITION SITE PLAN   | 04       |
| CPS        | FTA 00   | 00       | DR A 1003  | SITE ANALYSIS PLAN   | 04       |
| CPS        | FTA 00   | 00       | DR A 1101  | PROPOSED SITE PLAN   | 05       |
| CPS        | FTA 00   | 00       | DR A 1201  | SITE SECTIONS  | 04       |
| CPS        | FTA 00   | 00       | DR A 1401  | EXTERNAL WORKS PLAN  | 04       |
| CPS        | FTA 00   | 00       | DR A 1501  | STAGING PLAN   | 04       |
| CPS        | FTA 00   | 00       | DR A 1601  | PLAYSCAPE CALCULATION  | 02       |
| CPS        | FTA 00   | 00       | DR A 1602  | AMENITIES STRATEGY   | 02       |
| CPS        | FTA 00   | 00       | DR A 1603  | ACCESS STRATEGY  | 02       |
| CPS        | FTA 00   | 00       | DR A 1604  | TREE REMOVAL PLAN  | 02       |
| CPS        | FTA 00   | 00       | DR A 1610  | INDIGENOUS ARTWORK STRATEGY  | 03       |
| CPS        | FTA 00   | 00       | DR A 1630  | EXTERNAL MATERIAL AND FINISHES   | 03       |
| CPS        | FTA 00   | 00       | DR A 1640  | SHADOW DIAGRAM   | 03       |
| CPS        | FTA 00   | 00       | DR A 1650  | CONSTRUCTION MANAGEMENT STRATEGY   | 02       |
| CPS        | FTA BOOE | GF       | DR A 2001  | BUILDING E - DEMOLITION GROUND FLOOR PLAN  | 06       |
| CPS        | FTA BOOE | L1       | DR A 2002  | BUILDING E - DEMOLITION LEVEL 1 PLAN   | 05       |
| CPS        | FTA BOOE | LR       | DR A 2003  | BUILDING E - DEMOLITION ROOF PLAN  | 04       |
| CPS        | FTA BOOG | LG       | DR A 2100  | BUILDING G - UNDERCROFT LEVEL  | 06       |
| CPS        | FTA BOOG | GF       | DR A 2102  | BUILDING G - PROPOSED GROUND FLOOR PLAN  | 06       |
| CPS        | FTA BOOG | L1       | DR A 2103  | BUILDING G - PROPOSED LEVEL 1 FLOOR PLAN   | 06       |
| CPS        | FIA BOOG | LR       | DR A 2104  | BUILDING G - PROPOSED ROOF PLAN  | 06       |
| CPS        | FIA BOOG | GF       | DR A 2201  | BUILDING G - GROUND FLOOR RCP  | 05       |
| CPS        | FIA BOOG | L1       | DR A 2202  | GROUND FLOOR - LEVEL 1 RCP   | 05       |
| CPS        | FIA BOOG | GF       | DR A 2301  | GROUND FLOOR - GROUND FLOOR FINISHES PLAN  | 03       |
| CPS        | FIA BOOG | L1       | DR A 2302  | GROUND FLOOR - LEVEL 1 FINISHES PLAN   | 03       |
| CPS        | FIA BOOG | 44       | DR A 3001  | BUILDING G - ELEVATIONS 01   | 05       |
| CPS        | FIA BUUG | 44       | DR A 3101  | BUILDING G - SECTIONS 01   | 05       |
| CPS        | FIA BUUG | 44       | DR A 4001  |  | 04<br>04 |
| CPS        | FIA BUUG | 44       | DR A 4201  |  | 04<br>04 |
| CPS<br>CPS | FIA BUUG | 44       | DR A 4202  |  | 04<br>04 |
| CPS        | FTA DUUG | 22       | DR A 4203  |  | 04       |
| CPS        | FTA BUUG | 44       | DR A 4401  |  | 03       |
| CPS        | FTA BUUG | 22       | DR A 4501  | BALUSTRADE AND HANDRAIL DETAILS  | 04<br>04 |
| CPS        | FTA BUUG | 22<br>77 |            |  | 04<br>04 |
| CPS        | FIA BUUG | 22<br>77 | DR A 4901  |  | 04<br>04 |
| CPS        | ETA DOUG | 22<br>77 |            |  | 04       |
| CPS        | ETA BOOG | 22<br>77 |            |  | 04       |
| CPS        | ETA BOOG | <u></u>  |            |  | 01       |
| CPS        | ETA BOOG | 77       |            | DEDQDECTIVES 1   | 02       |
| CPS        | ETA BOOG | 77       |            |  | 03       |
| CPS        | ETA BOOG | 77       |            |  | 03       |
| CPS        |          | 77       |            | COVER SHEET + DRAWING LIST<br>SPECIFICATION SCHEDULE & MATERIAL SELECTIONS<br>SIGNAGE SCHEDULE<br>EXISTING SITE PLAN<br>DEMOLITION SITE PLAN<br>SITE ANALYSIS PLAN<br>PROPOSED SITE PLAN<br>SITE SECTIONS<br>EXTERNAL WORKS PLAN<br>STAGING PLAN<br>PLAYSCAPE CALCULATION<br>AMENITIES STRATEGY<br>ACCESS STRATEGY<br>ACCESS STRATEGY<br>TREE REMOVAL PLAN<br>INDIGENOUS ARTWORK STRATEGY<br>EXTERNAL MATERIAL AND FINISHES<br>SHADOW DIAGRAM<br>CONSTRUCTION MANAGEMENT STRATEGY<br>BUILDING E - DEMOLITION GROUND FLOOR PLAN<br>BUILDING G - DEMOLITION GROUND FLOOR PLAN<br>BUILDING G - DEMOLITION ROF PLAN<br>BUILDING G - POPOSED ROOF PLAN<br>BUILDING G - POPOSED ROOF PLAN<br>BUILDING G - PROPOSED ROOF PLAN<br>BUILDING G - PROPOSED ROOF PLAN<br>BUILDING G - PROPOSED ROOF PLAN<br>BUILDING G - ROONDF LOOR RCP<br>GROUND FLOOR - LEVEL 1 FLOR FINISHES PLAN<br>GROUND FLOOR - LEVEL 1 FINISHES PLAN<br>BUILDING G - SECTIONS 01<br>BUILDING G - SECTIONS 01<br>WALL TYPES 01<br>SECTION DETAILS 02<br>SECTION DETAILS 02<br>SECTION DETAILS 02<br>SECTION DETAILS 03<br>STAIR DETAILS<br>IFT DETAILS<br>TYPICAL FASCIA DETAILS<br>ROOM ELEVATIONS 01<br>ROOM ELEVATIONS 02<br>EXTERNAL DOOR & WINDOW SCHEDULE<br>INTERNAL DOOR & WINDOW SCHEDULE<br>PERSPECTIVES 2<br>PERSPECTIVES 3<br>PERSPECTIVES 4 | 02       |
|            | ITA DUUG | ~~       | DIX A 3004 |  | 02       |



# DESIGN CRITERA SCHEDULE

Design wind criteria The design wind criteria applied in accordance with AS 1170.2, 'Structural Design Actions Part 2: Wind Actions', are: Region: A2 Building Importance Level: 3 Regional Wind Speed: 46 m/sec. Terrain Category: 3

Atmospheric corrosivity category The atmospheric corrosivity category in accordance with AS/NZS 2312.2 is: C3 Unless noted otherwise the minimum category applicable is to be category C. Categories D, E and F to apply if deemed appropriate by the relevant manufacturers.

Design Rainfall intensity to AS/NZS 3500.3 : Eaves Gutters = 1 in 20 year storm, 5 minute duration (240mm/hr)

Insulation design requirements The insulation design criteria are: Building Climate Zone: 6 BCA Building Type: 9b Roof system R value: 4.5 downwards Wall system min R value: 1.4 Floor system min R value: not required

# MATERIALS + FINISHES SELECTIONS

# **322 CONCRETE**

Refer to specification for concrete selections and finishes.

332 MASONRY

MA01- BRICKS - FACEWORK - TYPE 1 BK08 - PGH Monash Grev Finishes Code:

# 332 STRUCTURAL STEEL

SS02 - STRUCTURAL STEEL - HOT DIPPED GALVANISED COATING

# 442 METAL ROOFING + CLADDING

MR02 - METAL ROOF SHEETING - RIBBED Finishes Code: CB24 - Colorbond Surfmist

MR42 - GUTTER EAVES - 200mm HALF ROUND Finishes Code CB18 - Colorbond Monument

MR51 - DOWNPIPE - METAL - 100DIA ZINCALUME Finishes Code: CB18 - Colorbond Monument

MR52 - DOWNPIPE - METAL - 150DIA ZINCALUME Finishes Code: CB18 - Colorbond Monument

MR61 - DP PROTECTION - SMALL Finishes Code CB18 - Colorbond Monument

MR62 - DP PROTECTION - LARGE CB18 - Colorbond Monument Finishes Code

MR71 - FASCIA - METAL FACED CFC Finishes Code CB18 - Colorbond Monument

MR91 - FLASHINGS & TRIMS CB18 - Colorbond Monument Finishes Code:

MR92 - GUTTER GUARD CB18 - Colorbond Monument Finishes Code:

# 442 CLADDING

CL41 - PREFINISHED SHEETS - FC TYPE 1 - CEMINTEL IC02 - CEMINTEL\_Barestone -Finish: Original IC09 - CEMINTEL Surround - Truss Grev CL52 - FC SOFFIT- PREFINISHED to match CB24 Surfmist Finishes Code:

# 452 GLAZING

GL03 - LAMINATED GLASS - CLEAR GL04 - LAMINATED GLASS - TINTED Finishes Code: Grey Tint GL06 - TOUGHENED GLASS - CLEAR **GL07 - TOUGHENED GLASS - TINTED** Finishes Code: Grev Tint GL33 - VINYL FILM - PRINTED refer Signage schedule Finishes Code:

## 462 DOORS.WINDOWS & HARDWARE

ALUMINIUM FRAMED DOORS & WINDOWS MF05 - AFF-Anodised-Satin Charcoal Finishes Code: Grev

SOLID LEAF TYPES PC43 - DULUX\_Bay Retreat Finishes Code:

DW33 LOUVRES - 150MM PC43 - INTERPON Bleu Sable Finishes Code:

# **472 INSULATION & SARKING**

Refer to specification for insulation and sarking selections

# **512 LININGS & CEILINGS**

PLASTERBOARD - WALLS, GENERALLY inishes Code: PF01 - DULUX Lexicon Quarter

PLASTERBOARD - CEILINGS, GENERALLY PF02 - DULUX Ceiling White Finishes Code:

FC LINING - WALLS, GENERALLY Finishes Code: PF01 - DULUX\_Lexicon Quarter

FC LINING - CEILING - GENERALLY PF02 - DULUX\_Ceiling White Finishes Code:

LC42 - EXPOSED GRID CEILING - ACOUSTIC Finishes Code: Standard White

LC59 - TRIM TIMBER PF03 - DULUX\_Smokebush Finishes Code:

LC81 - ACOUSTIC CEILING PANEL SYSTEM AF12 - WOVEN Finishes Code: IMAGE\_EchoPanel\_Cinnamon AF31 - INSTYLE\_Ecoustic Felt\_Artic LC86 - ACOUSTIC WALL FABRIC AF01 - INSTYLE\_Ecoustic Felt\_Lunar AF11 - WOVEN IMAGE\_EchoPanel\_Wine Finishes Code: Scheme 1 AF12 - WOVEN IMAGE EchoPanel Cinnamon AF31 - INSTYLE Ecoustic Felt Artic Scheme 3: AF32 - INSTYLE\_Ecoustic Felt\_Nautical AF34 - AUTEX\_Composition\_Stonewash LC87 - ACOUSTIC WALL FABRIC - PATTERNED Finishes Code: AF02 - INSTYLE\_Ecoustic Yalgu Stringybark AF13 - INSTYLE\_Ecoustic Scheme 1 Yalgu\_Tamarind AF33 - INSTYLE\_Ecoustic Scheme 3 Yalgu\_Nightsky

# **522 JOINERY**

JY01 - 18MM HIGH PRESSURE LAMINATE - MR E0 MDF Generally doors, drawers and gables Locations:

JY02 - 18MM LOW PRESSURE LAMINATE - MR E0 MDF JY03 - 25MM HIGH PRESSURE LAMINATE - MR E0 MDF Locations: Generally full height doors and open

shelvina JY04 - 38MM HIGH PRESSURE LAMINATE - MR E0 MDF JY05 - 38MM POSTFORM HIGH PRESSURE LAMINATE

**BENCHTOP - MR EO MDF** JY07 - WRITABLE SURFACE

.IY08 - CARCASS / WHITEBOARD JY09 - 18MM RAW MR E0 MDF BOARD JY11 - 13MM COMPACT LAMINATE

LAMINATE SELECTIONS Finishes Code/Decor: LAM01 -FORESTONE\_Egger\_Premium White Gloss LAM06 - FORESTONE\_Egger\_White Linen LAM11 - FORESTONE\_Egger\_Rusty Scheme 1: Red, U335 ST9 LAM12 -FORESTONE\_Egger\_Antique Rose, U325 ST9 LAM13 - FORESTONE\_Egger\_Sand Yellow, U125 ST9 Scheme 3 LAM31 - FORESTONE Egger Ocean Blue, U565 ST9 LAM32 - FORESTONE\_Egger\_Misty Blue U502 ST9 LAM33 - FORESTONE\_Egger\_Almond

JY21 - 25MM MILD STEEL - POWDERCOAT FRAME Finishes Code PC04 - Black

Beige, U211 ST9

# **532 METALWORK**

MW01 - BALUSTRADE - GALV STEEL Finish: hot dip galvanised

MW54 - AWNING ALUMINIUM TYPE 2 - VERTICAL FINS PC12 - DULUX DURATEC -Finishes Code: Intensity\_Desert Satin

MW59 - FACADE FRAMING ELEMENT - ALUMINIUM Finishes Code: CB18 - COLORBOND\_Monument

MW72 - ACOUSTIC LOUVRES PLANT SERVICES STORES -**TYPE 1 (150 WIDE)** CB18 - COLORBOND Monument **Finishes Code** 

# 542 SIGNS AND DISPLAY

Refer to Specification for Statutory Signage requirements Refer to Signage Schedule for all other sign types.

# 552 MISCELLANEOUS FIXTURES

FX91 - ROLLER BLINDS - MANUAL BLOCKOUT FB01 - HUNTER DOUGLAS Paperbark Finishes Code:

04 100% SCHEMATIC DESIG

03 100% SCHEMATIC DESIGN

02 100% SCHEMATIC DESIG

01 80% SCHEMATIC DESIGN

# 582 HYDRAULIC FIXTURES

Refer Specification Volume 1 for Hydraulic Fixtures Selections and associated fixtures.

The quanities of the fixtures are listed below

HY19 - TROUGH - PRACTICAL ACTIVITIES QTY: 2

# **652 RESILIENT FINISHES**

**RF01 - MAIN FLOOR VINYL** VN01 - TARKETT\_Granit\_Warm Gr Finishes Code: Scheme 1: VN11 - TARKETT iQ Granit Red B RF02 - ANTI-STATIC FLOOR VINYL

VN02\_GERFLOR\_Mipolam Affinity Finishes Code: EL7\_Grey Storm 4159

# 662 CARPETS & MATS

### CM01 - CARPET TILE TYPE 1 CP01 - SIGNATURE Raw Finishes Code: Elements\_Bedrock\_Shale\_3-000-0 CP11 - SIGNATURE\_Raw Scheme 1: Elements\_Gemstone\_Shale Ruby\_3-133-134-01 CP12 - SIGNATURE Raw Elements\_Gemstone\_Shale Sunstone 3-135-136-01 CP13 - SIGNATURE Raw Elements\_Gemstone\_Shale Ametrine\_3-133-134-01 CP31 - SIGNATURE Raw Scheme 3: Elements\_Gemstone Shale Sodalite\_3-129-130-01 CP32 - SIGNATURE\_Raw Elements\_Gemstone\_Shale Angelite\_3-131-132-01

CM26 - ENTRY MAT - INTERNAL Finishes Code:

CP06 - FORBO\_Coral Classic\_472 Mouse Grey

|           |            |       | fuiton  |
|-----------|------------|-------|---|
|           |            |       | ARCHITECTS E<br>www.fultontro   |
|           |            |       | SYDNEY Suite 904, Level 9, 28-36<br>t. (02) 8383 5151 e. sy   |
|           |            |       | Fulton Trotter Architects ACN 67<br>To be used for authorised work only. It<br>in whole or in part, nor shall it be use |
| - REVISED | 11/02/2025 | NK    | DIRECTORS   |
| 4         | 29/01/2025 | NK    | Greg Isaac raia   |
| 4         | 10/01/2025 | NK    | Justine Ebzery fraia<br>John Ward raia  |
|           | 13/12/2024 | NK    | Katerina Dracopoulos fraia<br>Paul Sekava fraia   |
|           | DATE       | INIT, | Ryan Loveday fraia  |





rotter STANE SYDNEY tter.com.au

# weaux Street, Surry Hills, NSW 2010 av@fultontrotter.com.au 264 550 ABN 57 677 264 550 to be copied directly or indirectly, for any other building purposes.

QLD 2920 QLD 3313 QLD 3847 QLD 4529 QLD 3108 QLD 4500

| .             | DRAWING & SPECIFIC/<br>MATERIAL CODE LEGE                                   |   |
|---------------|---|---|
| ,             | selection information is to be obtain                                       | ecification Trade Section where detailed<br>ed for elements nominated in the drawings. The<br>vo / three numeric trade selection reference for                          |
|               | TRADE SECTION   | CODE  |
|               | GENERAL<br>Fire Stopping  | FS  |
|               | Termite Management  | TM  |
|               | Access Safety Systems   | AS  |
| irey<br>Brick | <b>SITE</b><br>Landscape  | LD  |
|               | STRUCTURE   |   |
| .             | Concrete  | CN  |
| ′             | Brick & Block Construction  | MA  |
|               | Structural Steel  | SS  |
|               | Light Steel Framing   | SF  |
|               | Timber Framing<br>Decking & Flooring  | TF<br>FD  |
|               |   |   |
|               | ENCLOSURE<br>Waterproofing External   | WE  |
|               | Metal Roofing & Cladding  | MR  |
|               | Roof Tiling   | RT  |
| 000-01        | Cladding  | CL  |
|               | Glazing   | GL  |
|               | Doors, Windows & Hardware   | DW  |
|               | Insulation & Sarking Membranes  | IS  |
|               | INTERIOR  |   |
|               | Linings & Ceilings  | LC  |
|               | Joinery   | JY  |
|               | Metalwork   | MW  |
|               | Signs and display   | SD  |
|               | Miscellaneous Fitures   | FX  |
|               | Equipment & Appliances<br>Furnishings & Furniture                           | EQ<br>FF  |
|               | Hydraulic Fixtures  | HY  |
|               | FINISH  |   |
|               | Rendering & Plastering  | RP  |
| 21            | Cementitious Toppings   | CT  |
|               | Waterproofing - Wet Areas   | W   |
|               | Tiling  | TG  |
|               | Resilient finishes  | RF  |
|               | Carpets   | CM  |
|               | Painting  | PG  |
|               |   |   |
|               | Patternbook Interior Design Com   | ponents: Reference Documentation  |
|               | Finish Design intent to the Learning  | W Patternbook, Volume 2, section 5.2 for Floor<br>g Commons and GLS / Multi-Purpose Room.<br>found on the SINSW GLS and SLU GA PLAN                                     |
|               | Wall Finishes - refer to the S/NSW indicative extents of wall applied fin   | / GLS and SLU GA PLAN & FFE drawing for<br>ishes.   |
|               | Ceiling Finish Design intent to the L                                       | NSW Patternbook, Volume 2, section 5.3 for<br>earning Commons and GLS / Multi-Purpose<br>can be found on the SINSW GLS and SLU GA                                       |
|               | Design intent to the Learning Comm<br>Additional detail on joinery can be f | rnbook, Volume 2, section 5.4 for Joinery<br>nons and GLS / Multi-Purpose Room.<br>ound in the SINSW Design Guide Note<br>Equipment (joinery) in Primary School General |
|               | <b>Furniture</b> - refer to the SINSW GLS indicative furniture layouts.     | S and SLU GA PLAN & FFE drawing for   |
|               |   |   |

## SCHEMATIC DESIGN SCHOOL INFRASTRUCTURE

CAMMERAY PUBLIC SCHOOL

68 PALMER STREET CAMMERAY, NSW

# **SPECIFICATION SCHEDULE &** MATERIAL SELECTIONS

DIRECTOR

Figured dimensions take precedence all dimensions on site before co

PROJECT NUMBER 7068CY01

JW RAWING NUMBER

CHECKED NK

CPS-FTA-XX-XX-DR-A-0001

04

## SN21 – SIGN EXTERNAL – Decorative Building ID Letters/ AMS building identification

| Property              | Description   |
|-----------------------|---|
| Drawing Code:         | SN21  |
| Item:                 | Decorative Building Identification Letters  |
| Details:              | Aluminium powder coated sign plate with either laser cut 3M vinyl film (strong adhesive<br>to avoid pealing and students picking) or printed directly onto sign<br>Aluminium panel with engraved and paint filled lettering screw fixed to wall |
| Sign Text:            | Letters created with diagonally angled lines. Area between lines increases halfway through the letter.  |
| Font:                 | Gill Sans MT Regular (As per EFSG Details)  |
| Size:                 | 600mm H (Width according to letter proportion)<br>Exact size to be confirmed  |
| Fixing:               | Pre-drilled holes in each corner at a maximum of 300mm intervals<br>Screw and adhesive fix to wall through pre-drilled holes with compatible noncorrosive<br>screws.  |
| Finish:               | Powder Coat Aluminium – Colour to be as per the selected colour scheme<br>Vinyl - white   |
| Colour Scheme:        | Scheme 1 and Scheme 3   |
| Mock Up &<br>Example: |   |
| Notes:                | ACM (Aluminium Composite Material) will <u>NOT</u> be accepted as an alternative to<br>aluminium.   |
| Quantity:             | 1   |

## SN23 – ROOM ID SIGN – AMU Room Numbers

| Propert       | у          | Description  |  |  |  |  |
|---------------|------------|--|--|--|--|--|
| Drawing Code: |            | SN23   |  |  |  |  |
| Name:         |            | Fixed Room Identification System (AMS Signage)   |  |  |  |  |
| Sign De       | tails:     | Changeable Plate System within Aluminium Holder  |  |  |  |  |
| Plate De      | etails:    | Laminated plastic with contrasting-coloured layers contrasting coloured layers with<br>engraved characters. Depth of engraving sufficient to cut through top layer to reveal lower<br>laminate colour. (as per EFSG Details)   |  |  |  |  |
| Holder [      | Details:   | Extruded aluminium in natural satin finish to 10 microns (minimum)   |  |  |  |  |
| Typefac       | e:         | Folio Medium Extended (As per EFSG Details)  |  |  |  |  |
|               | Plate:     | (Text width + 30mm each end) W x 30mm H (As per EFSG Details)  |  |  |  |  |
| Size:         | Holder:    | (Text width + 32mm each end) W x 32mm H (As per EFSG Details)  |  |  |  |  |
|               | Text:      | Characters 16mm H  |  |  |  |  |
| Install L     | ocation:   | Centre of door frame at top of the door  |  |  |  |  |
| Fixing:       |            | Screw Fixed on flat section in 3 places. Glue and screw fix with 3mm diameter<br>countersunk screws (EFSG requirement)   |  |  |  |  |
|               | Plate:     | Silver (as shown in example below)   |  |  |  |  |
| Finish:       | Text:      | Black Letters (as shown in example below)  |  |  |  |  |
| EFSG D        | )etails:   | Ensure EFSG approval before ordering or manufacturing sign   |  |  |  |  |
| Example       | e:         | MR0048   |  |  |  |  |
| Notes:        |            | Existing doors with existing door number plates to be reviewed. If the sign is missing or<br>damaged, to be replaced with the specification note above. If the sign is in good condition<br>and the room function is the same no sign required. If the sign is in good condition but the<br>room's purpose has changed only new sign plate is require with new purpose as listed<br>below. |  |  |  |  |
| Locatior      | 1:         | ALL DOORS MUST have AMS Room Number Displayed in accordance with EFSG<br>requirements.   |  |  |  |  |
| Quantity      | <i>/</i> : | 9  |  |  |  |  |
|               |            |  |  |  |  |  |

SN24 – ROOM ID SIGN – BOH Ro

| Property   | r       | Description  |  |  |  |  |
|------------|---------|--|--|--|--|--|
| Drawing    | Code:   | SN2  |  |  |  |  |
| Name:      |         | Fixed Room Identification (AMS Door Signs)   |  |  |  |  |
| Details:   |         | Changeable Plate System within Aluminium Holder  |  |  |  |  |
| Typeface   |         | Folio Medium Extended (As per EFSG Details)  |  |  |  |  |
|            | Plate:  | (Text width + 30mm each end) W x 30mm H (As per EFSG Details)  |  |  |  |  |
| Size:      | Holder: | (Text width + 32mm each end) W x 32mm H (As per EFSG Details)  |  |  |  |  |
|            | Text:   | Characters 16mm H  |  |  |  |  |
| Install Lo | cation: | 1000mm AFFL to centre, centred on door.  |  |  |  |  |
| Fixing:    |         | Screw Fixed on flat section in 3 places. Glue and screw fix with 3mm diameter<br>countersunk screws (EFSG requirement)           |  |  |  |  |
|            | Plate:  | Silver   |  |  |  |  |
| Finish:    | Text:   | Black Letters  |  |  |  |  |
| Example    |         | RECEPTION  |  |  |  |  |
| Notes:     |         |  |  |  |  |  |
| Location   |         | To ALL timber doors and to rooms which are not identified under SN020 or SN021.<br>Exact Room names to be confirmed with School. |  |  |  |  |
| Quantity   |         | 3  |  |  |  |  |

### SN32 – NOTICE SIGNAGE, Size Type 01

| Property        | Description                                 |   |                              |     |  |  |  |
|-----------------|---|---|------------------------------|-----|--|--|--|
| Drawing Code:   | SN32  |   |                              |     |  |  |  |
| Name:           | Notice Signage – Size Type                  | D1  |                              |     |  |  |  |
| Details:        | The panels to have rounded                  | Screen-printed lettering and symbols on 1.6mm thick powder coated finish aluminium.<br>The panels to have rounded corners and mount holes in each corner. (extract from<br>EFSG guidelines. Type A sign was selected) |                              |     |  |  |  |
| Fixing:         | Screw or bolt fixed to a solid              | base  |                              |     |  |  |  |
| Size (nominal): | 300 W x 225mm H                             |   |                              |     |  |  |  |
| Letters:        | To AS 1319                                  |   |                              |     |  |  |  |
| Description:    | "NOTICE" printed on top of s                | White background<br>"NOTICE" printed on top of sign with blue background and white text<br>Sign wording (as listed below) in black print under "NOTICE"   |                              |     |  |  |  |
|                 | Text Example                                |   | Symbol & Text Example        |     |  |  |  |
| Mock Up:        | GUARDS MUST<br>IN PLACE BEFO<br>SWITCHING C | BE  | NOTICE<br>NOSTICE<br>SMOKING |     |  |  |  |
| Note:           | Vinyl Cut signs are not accept              | table   |                              |     |  |  |  |
|                 | LEVEL                                       | Room  | SIGN TEXT                    | QTY |  |  |  |
| Location:       | First Floor                                 | EDB   | NOT TO BE USED FOR STORAGE   | 1   |  |  |  |

| Property      | Description  |
|---------------|--|
| Drawing Code: | SN5  |
| Name:         | Classroom Artwork Decal  |
| Details:      | Art decal to dimensions shown as per the Pattern Book to provide privacy and visual<br>contrast requirements   |
| Size (mm):    | Refer to the Pattern Book  |
| Artwork:      | To be confirmed by the school  |
| Finish:       | High-quality, durable vinyl with anti-fade and anti-scratch properties.  |
| Fixing:       | Directly installed on Glazed Sliding doors and panels. Professional installation to ensure<br>no air bubbles, misalignments, or defects.                             |
| Mock Up:      | Pevetor-Door doted   |
| Location:     | Decals on External & Internal Glazing required as per the Pattern Book.<br>Refer to Architectural Drawing:<br>CPS-FTA-B00G-ZZ-DR-A-5001<br>CPS-FTA-B00G-Z7-DR-A-5002 |

|      |                                 |            |          | fulton trotter  |
|------|---------------------------------|------------|----------|---|
|      |                                 |            |          | ARCHITECTS BRISBANE SYDNEY<br>www.fultontrotter.com.au  |
|      |                                 |            |          | SYDNEY Suite 904, Level 9, 28-36 Foveaux Street, Surry Hills, NSW 2010<br>t. (02) 8383 5151 e. sydney@fultontrotter.com.au  |
|      |                                 |            |          | Fulton Trotter Architects ACN 677 264 550 ABN 57 677 264 550<br>To be used for authorised work only. Not to be copied directly or indirectly,<br>in whole or in part, nor shall it be used for any other building purposes. |
|      |                                 |            | <u> </u> | DIRECTORS<br>Greg base raia NSW 6855 QLD 2920   |
| 02   | 100% SCHEMATIC DESIGN - REVISED | 11/02/2025 | NK       | Justine Ebzery fraia QLD 3313<br>John Ward raia VIC 18804 NSW 8371 QLD 3847   |
| 01   | 100% SCHEMATIC DESIGN           | 29/01/2025 | NK       | Katerina Dracopoulos fraia NSW 7434 QLD 4529<br>Paul Sekava fraia NSW 7180 QLD 3108   |
| REV. | DESCRIPTION                     | DATE       | INIT,    | Ryan Loveday fraia QLD 4500   |

plot date: Tuesday, 11 February 2025 9:47 AM file location: BIMoloud: FTA-SYD-BIM26- BIMoloud Basic for Archicad 26/7068CY01 Cammeray Public School

# SCHEMATIC DESIGN

NSW

CAMMERAY PUBLIC SCHOOL

268 PALMER STREET, CAMMERAY, NSW

## SIGNAGE SCHEDULE

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

 PROJECT NUMBER
 DIRECTOR


 7068CY01
 JW

DRAWING NUMBER

CPS-FTA-XX-XX-DR-A-0002



CHECKED



# SITE PLAN LEGEND

- BOUNDARY LINE
- MINOR CONTOUR
- ---- MAJOR CONTOUR
- EXISTING BUILDING
- EXTENT OF HARD SURFACES
- LINE OF ROOF ABOVE
- FENCE LINE
- EXISTING TREE




Figured dimensions take precedence all dimensions. Contractors must all dimensions on site before comm any work or making shop drawings.

PROJECT NUMBER DIRECTOR 7068CY01 JW

04

-)-

DRAWING NUMBER CPS-FTA-00-00-DR-A-1001



# SITE PLAN LEGEND

BOUNDARY LINE

- MINOR CONTOUR
- ---- MAJOR CONTOUR
- EXISTING BUILDING
- EXTENT OF HARD SURFACES
- LINE OF ROOF ABOVE
- FENCE LINE
- EXISTING TREE
- TO BE DEMOLISHED
- DEMOLISHED TREE

---- TO BE DEMOLISHED

A DEMOLITION SITE PLAN


Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings. PROJECT NUMBER DIRECTOR

7068CY01 JW

DRAWING NUMBER

CPS-FTA-00-00-DR-A-1002










Figured dimensions take precedence scale dimensions. Contractors must all dimensions on site before comme any work or making shop drawings. PROJECT NUMBER

DIRECTOR 7068CY01 JW DRAWING NUMBER

04


CPS-FTA-00-00-DR-A-1003




# SITE PLAN LEGEND


- BOUNDARY LINE
- MINOR CONTOUR
- MAJOR CONTOUR
- EXISTING BUILDING
- EXTENT OF HARD SURFACES
- LINE OF ROOF ABOVE
- FENCE LINE
- EXISTING TREE
- PROPOSED TREE

CAMMERAY PUBLIC SCHOOL









# SITE WORKS PLAN LEGEND

- SLAB LABEL MATERIAL CODE (REFER TO MATERIAL LEGEND) MATERIAL CODE (REFER TO MATERIAL LEGE XX00 : XX00 FINISH CODE (REFER TO FINISHES LEGEND) RL: 0.000 FALL IN CEILING (IF RAKING)
- PROPOSED SPOT LEVEL
- ◆ 0.000 + EXISTING SPOT LEVEL
- STORMWATER PIT
- SWP SEWER -6----
- -w STORMWATER
- GAS LINE **--**•---

# EXTERNAL WORKS PLAN

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.


PROJECT NUMBER 7068CY01

DIRECTOR JW

CPS-FTA-00-00-DR-A-1401



СНЕСКЕ



# STAGING PLAN

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

PROJECT NUMBER 7068CY01

RAWING NUMBER


CPS-FTA-00-00-DR-A-1501


DIRECTOR


JW




CHECKED











- BOUNDARY LINE
- MINOR CONTOUR
- --- MAJOR CONTOUR
- EXISTING BUILDING
- EXTENT OF HARD SURFACES
- LINE OF ROOF ABOVE
- FENCE LINE
- EXISTING TREE

| AMENITIES                          | EXISTING No. | POST<br>DEMOLITION No. | EFSG No. | GAP |
|------------------------------------|--------------|------------------------|----------|-----|
| DILETS - GIRLS                     | 15           | 15                     | 20       | -5  |
| DILETS - BOYS<br>ICLUDING URINALS) | 24           | 24                     | 18       | +6  |
| DILETS - ACC                       | 0            | 0                      | 1        | -1  |
| ILETS - STAFF                      | 6            | 6                      | 5        | +1  |
| UBBLER                             | 14           | 14                     | 12       | +2  |

### -AMENITIES STRATEGY

Figured dimensions take precedence over scale dimensions. Contractors must verify scale dimensions. Contractors in all dimensions on site before con any work or making shop drawing


PROJECT NUMBER DIRECTOR 7068CY01 JW

RAWING NUMBER

CPS-FTA-00-00-DR-A-1602



CHECKEI







ACCESSIBLE PATHWAY

ALTERNATIVE NON-ACCESSIBLE PATHWAY

STEPS


CAMMERAY PUBLIC SCHOOL





# CHECKED

VISION 02



| _   |                                 |            | <u> </u> | fulto  | ntr                                     | Jtt                  | GL                   | SE      |
|-----|---------------------------------|------------|----------|--|---|----------------------|----------------------|---------|
|     |                                 |            |          | ARCHITECTS<br>www.fultor   | -                                       |                      |                      | SCH     |
|     |                                 |            |          |  | 9, 28-36 Foveaux St<br>e. sydney@fultor |                      | NSW 2010             | NSV     |
|     |                                 |            |          | Fulton Trotter Architects<br>To be used for authorised wor<br>in whole or in part, nor shall | only. Not to be cop                     | pied directly or i   | ndirectly,           | Lect    |
| 03  | 100% SCHEMATIC DESIGN - REVISED | 11/02/2025 | NK       | DIRECTORS<br>Grep Isaac raia   |   | NSW 6855             | QLD 2920             | ੂ ਨAM   |
| 2   | 100% SCHEMATIC DESIGN           | 10/01/2025 | NK       | Justine Ebzery fraia<br>John Ward raia   | VIC 18804                               | NSW 8371             | QLD 3313<br>QLD 3847 | S CO D/ |
| D1  | 80% SCHEMATIC DESIGN            | 13/12/2024 | NK       | Katerina Dracopoulos fraia<br>Paul Sekava fraia  |   | NSW 7434<br>NSW 7180 | QLD 4529<br>QLD 3108 |         |
| EV. | DESCRIPTION                     | DATE       | INIT,    | Ryan Loveday fraia   |   |                      | QLD 4500             |         |

# PROPOSED LOCATION FOR **INDIGENOUS ARTWORK STRATEGY:**

# CWC LANDSAPE FEATURE


AT THE BELLEVUE STREET ENTRANCE

plot date: Tuesday, 11 February 2025 9:47 AM file location: BIMcloud: FTA-SYD-BIM26 - BIMcloud Basic for Archicad 26/7068CY01 Cammeray Public School

# SCHEMATIC DESIGN

CAMMERAY PUBLIC SCHOOL

8 PALMER STREET, AMMERAY, NSW



DIRECTOR

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

PROJECT NUMBER 7068CY01


JW DRAWING NUMBER


CPS-FTA-00-00-DR-A-1610



03







## CMP LEGEND

EMERGENCY VEHICLE ACCESS ROUTE


CONSTRUCTION ZONE


CONSTRUCTION BIN AREA


TRUCK TURNING ZONE

# SCHOOL INFRASTRUCTURE











plot date: Tuesday, 11 February 2025 9:47 AM file location: BIMcloud: FTA-SYD-BIM26 - BIMcloud Basic for Archicad 26/7068CY01 Cammeray Public School

# SCHEMATIC DESIGN

# CAMMERAY PUBLIC SCHOOL

8 PALMER STREET, CAMMERAY, NSW

### BUILDING E - DEMOLITION ROOF PLAN

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.


PROJECT NUMBER DIRECTOR 7068CY01

JW

CHECKED


DRAWING NUMBER CPS-FTA-B00E-LR-DR-A-2003





CHECKED

06



# PLAN LEGEND TYPE DOOR + WINDOW LABEL E00/ EXTERNAL WALL TYPE LABEL 100 INTERNAL WALL TYPE LABEL FINISHES APPLYING TO BUIDING G -GROUND FLOOR ARE SCHEME 3, UNLESS SPECIFICALLY NOTED OTHERWISE. REFER TO SPECIFICATION AND MATERIAL SCHEDULE DRAWINGS FOR SELECTIONS.

# SCHEMATIC DESIGN

CAMMERAY PUBLIC SCHOOL

68 PALMER STREET, CAMMERAY, NSW

### **BUILDING G - PROPOSED** GROUND FLOOR PLAN


Figured dimensions take precedend scale dimensions. Contractors in all dimensions on site before cor any work or making shop drawir

PROJECT NUMBER 7068CY01

HECKED 06

DIRECTOR RAWING NUMBER





### Patternbook Interior Design Components: Reference Documentation


Ceilings Finishes and Layout - refer to the SINSW Patternbook, Volume 2, section 5.3 for Ceiling Finish Design intent to the Learning Commons and GLS / Multi-Purpose Room. Additional detail on finishes can be found on the SINSW GLS and SLU GA PLAN & FFE drawings.


FINISHES APPLYING TO BUIDING G - GROUND FLOOR ARE SCHEME 3, UNLESS SPECIFICALLY NOTED OTHERWISE. REFER TO SPECIFICATION AND MATERIAL SCHEDULE DRAWINGS FOR SELECTIONS.


# SCHEMATIC DESIGN


CAMMERAY PUBLIC SCHOOL

8 PALMER STREET, CAMMERAY, NSW











FINISHES APPLYING TO BUIDING G - LEVEL1 ARE SCHEME 1, UNLESS SPECIFICALLY NOTED OTHERWISE. REFER TO SPECIFICATION AND MATERIAL SCHEDULE DRAWINGS FOR SELECTIONS.

# SCHEMATIC DESIGN


CAMMERAY PUBLIC SCHOOL

8 PALMER STREET, CAMMERAY, NSW





|                                       | 3        | FOM BELOW LEVEL | VE BUILDING E OUTLINE                  |   |  |  |
|---------------------------------------|----------|-----------------|--|---|--|--|
| 1 PLAN<br>PROPOSED RO<br>SCALE: 1:100 | DOF PLAN |                 |  |   |  |  |
|                                       |          |                 | 1                                      |   | 1 1  | (ultan trattar   |
|                                       |          |                 | 06<br>05<br>04<br>03                   | 100% SCHEMATIC DESIGN - REVISED<br>100% SCHEMATIC DESIGN<br>100% SCHEMATIC DESIGN<br>80% SCHEMATIC DESIGN | 11/02/2025 NK<br>29/01/2025 NK<br>10/01/2025 NK<br>13/12/2024 NK | ARCHITECTS BRISBANE SYDNEY<br>www.fultontrotter.com.au |
|                                       |          |                 | 06<br>04<br>03<br>02<br>01<br>P5<br>P4 | 100% SCHEMATIC DESIGN<br>100% SCHEMATIC DESIGN  | 29/01/2025 NK<br>10/01/2025 NK                                   | ARCHITECTS BRISBANE SYDNEY                             |




# SCHEMATIC DESIGN SCHOOL INFRASTRUCTURE


NSW


CAMMERAY PUBLIC SCHOOL

68 PALMER STREET, CAMMERAY, NSW



CPS-FTA-B00G-LR-DR-A-2104





## BUILDING G - SECTIONS 01

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

PROJECT NUMBER 7068CY01 DRAWING NUMBER

DIRECTOR JW

CHECKED

CPS-FTA-B00G-ZZ-DR-A-3101



| L TYPES    | SUBSU 92 1/13<br>External<br>CL41 - PREFINISHED SHEETS - FC TYPE 1<br>SF22 - STEEL FURRING CHANNEL - 35MM<br>SF22 - STEEL FURRING CHANNEL - 15MM<br>ISQL - 35RMIO - WALL HEAVINO UTIY<br>SF02 - STEEL WALL FRAMING - 22M WTH (IS )<br>THERMAL INSULATON<br>LC09 - PLASTERBOARD - 13MM IMPACT RESISTANT<br>Internal  | Biggs bit         92         W13           External         External         External           \$922.5         STEEL FURRING CHAINEL - 350M           \$923.5         STEEL FURRING CHAINEL - 350M           \$924.5         STEEL FURRING CHAINEL - 350M           \$925.5         STEEL FURRING CHAINEL - 350M           \$92.5         STEEL FURRING CHAINEL - 50M           \$92.5         STEEL FURRING CHAINEL - 350M           \$92.5         STEEL WALL FRAINING - 220M WITH (IS           THERMAL INSULATION         LC09 - PLASTERBOARD - 130M IMPACT           RESISTANT         Internal | Statistics of the second state of the second s   | Busice of the second se | MAS1-BLOCKWORK-200 SERIES-<br>STANDARD<br>Isternal  | IS - AIR CAVITY<br>IS04 - SARKING - WALL HEAVY DUTY<br>MA41 - BLOCKWORK - 150 SERIES - | External<br>CND1 - CONCRETE - INSTU - NATURAL GRE                | SF22 - STEEL FURRING CHANNEL-<br>30Mul<br>ISD - SARING-WALL HEAVY DUTY<br>OND - COXCRETE - INSTU - NATURAL<br>Internal |
|------------|---|---|--|--|---|--|--|--|
| VAL        | E07 Frie Rating - NOTE:<br>Rev4ulue - Rev+Ctr -<br>Smcke Rating False   | E07A Fire Rating - NOTE:<br>RV-Value -<br>RV+ Ctr -<br>Smoke Rating False   | E08 Fire Rating - NOTE:<br>Revelue - Revelue - R | E08A Fire Rating - NOTE:<br>Rvaue -<br>Rvi + Otr -<br>Smoke Rating False   | E23<br>R-Value - NOTE:<br>R+Vr - Smoke Rating False | E23A Fire Rating - NOTE:<br>RValue - Rv+Ctr - Stroke Rating False                      | E24A Fire Rating - NOTE:<br>RValue - Rvare - Stroke Rating False | E24B   |
| EXTERNAL V | 20     19,25%     External     External     External     External     External     External     Sr22     STELE FURPING     CHANNEL     SRRNNC     VNALL     HEAVY DUTY     HEAVY DUTY | External<br>MAT - BLOCKWORK - 150 SERIES - STANDARD<br>Internal   |  |  |   |  |  |  |
|            | E24C  | E32 R.+Value -<br>R.w.+Ctr -<br>Smoke Rating False  |  |  |   |  |  |  |

| ALL TYPES  | 1388/4676         110         7014/4/453           Image: Constraint of the straint of th   | 1300195         110         7619/013           1300195         110         7619/013           1300195         FCI         SE21           1300195         SF21         STEEL FURRING CHANNEL - 196/013           1300195         SF13         STEEL WALL FRAINS CHANNEL - 196/013           1300195         SF13         STEEL WALL FRAINS - 76MM           130195         SF13         STEEL WALL FRAINS - 76MM           130196         SF13         STEEL WALL FRAINS - 76MM           13019         SF13         STEEL WALL FRAINS - 76MM           13019         SF13         SF10           13019         SF13         SF10           13010         SF13         SF13           13010         SF13         SF10           < | 134         92.20, 75         16           134         92.20, 75         16           105         FLASTERBOARD - 13MM IMPACT<br>RESISTANT<br>RESISTANT         FLASTERBOARD - 13MM IMPACT<br>RESISTANT           101         FLASTERBOARD - 13MM IMPACT<br>RESISTANT         FLOSTERWALL FRAINGS - 52MM WITH<br>(S) ACOUSTIC INSULATION<br>(S) ACOUSTIC INSULATION           101         FLOSTERBOARD - 13MM IMPACT<br>RESISTANT         FLOSTERBOARD - 13MM IMPACT<br>RESISTANT           103         FLOSTERBOARD - 13MM IMPACT<br>RESISTANT           103         FLOSTERBOARD - 13MM IMPACT<br>RESISTANT  | 130         92         #13           EC09 - PLASTERBOARD - 13MM IMPACT RESISTANT           SF03 - STEEL WALL FRAMING - 32MM WITH (IS )           ACOUSTIC INSULATION           LC09 - PLASTERBOARD - 13MM IMPACT RESISTANT           LC09 - PLASTERBOARD - 13MM IMPACT RESISTANT           MOTE           Residence           NOTE:   | 130         92         HP           LC09         PLASTERBOARD         13MM IMPACT RESISTANT           SF03         STEEL WALL FRAMING         52MW WTH (IS )           ACOUSTIC INSULATION         LC23         FC LINING - 9MM FLUSH JOINTS           Image: State of the state o | 91         92         MP           LC23 - FC LNING - 9MM FLUSH JOINTS         SF03 - STELL WALL FRAMING - 92MM WITH (IS ) ACOUSTIC NORULATION           SF03 - STELL WALL FRAMING - 92MM FLUSH JOINTS         LC23 - FC LNING - 90M FLUSH JOINTS           LC23 - FC LNING - 90M FLUSH JOINTS         LC23 - FC LNING - 90M FLUSH JOINTS           MOTE         Revision           MOTE         Revision |
|------------|---|---|---|---|---|--|
| INTERNAL W | Image: Part of the state in the st | IOZ revetor           Revetor           Implementation           Implementatin           Implem   | Ror - Cor :           Ror - Cor :           134 7524 r 75 4/13           L C08 - PLASTERBOARD - 13MM IMPACT<br>RESISTANT           SF13 - STEL: WALL FRAMING - 76MM WITH (JS )<br>ACUSTIC INSULATION           SF13 - STEL WALL FRAMING - 76MM WITH (JS )<br>ACUSTIC INSULATION           SF13 - STEL WALL FRAMING - 76MM WITH (JS )<br>ACUSTIC INSULATION           SF13 - STEL WALL FRAMING - 76MM WITH (JS )<br>ACUSTIC INSULATION           L C08 - PLASTERBOARD - 13MM WITH (JS )<br>ACUSTIC INSULATION           L C08 - PLASTERBOARD - 13MM WITH (JS )<br>ACUSTIC INSULATION           L C08 - PLASTERBOARD - 13MM WITH (JS )<br>ACUSTIC INSULATION           L C08 - PLASTERBOARD - 13MM IMPACT           RESISTANT           NOTE:           RESISTANT           NOTE:           ROM IN PACT           RESISTANT           NOTE:           ROM IN PACT           ROM IN PACT           RESISTANT           NOTE:           ROM IN PACT | INC         Rev Cor         False           13/85/         250         #55/4/3           Impact Reside Revolution Revolutina Revolutina Revolution Revolutina Revolution Revolutina Revolu | Rovice Ratind False   | IV / Re+Cr Smoon Rated Fale  |

|      |                                 |            |       | ARCHITECTS<br>www.fultor   | BRISBA              | NE SY                | DNEY                 |
|------|---------------------------------|------------|-------|--|---------------------|----------------------|----------------------|
|      |                                 |            |       | SYDNEY Suite 904, Level 9<br>t. (02) 8383 5151   |                     |                      | NSW 2010             |
|      |                                 |            |       | Fulton Trotter Architects /<br>To be used for authorised work<br>in whole or in part, nor shall it | only. Not to be cop | pied directly or i   | ndirectly,           |
| 04   | 100% SCHEMATIC DESIGN - REVISED | 11/02/2025 | NK    |  | De used for any or  | ner bonang par       | puesa.               |
| 03   | 100% SCHEMATIC DESIGN           | 10/01/2025 | NK    | DIRECTORS<br>Greg Isaac raia   |                     | NSW 6855             | QLD 2920             |
| 02   | 80% SCHEMATIC DESIGN            | 13/12/2024 | NK    | Justine Ebzery fraia<br>John Ward raia   | VIC 18804           | NSW 8371             | QLD 3313<br>QLD 3847 |
| 01   | 50% SCHEMATIC DESIGN            | 03/12/2024 | NK    | Katerina Dracopoulos fraia<br>Paul Sekava fraia  |                     | NSW 7434<br>NSW 7180 | QLD 4529<br>QLD 3108 |
| REV, | DESCRIPTION                     | DATE       | INIT. | Ryan Loveday fraia   |                     |                      | QLD 4500             |

 Image: Image in the second s

# SCHEMATIC DESIGN

ISW

AMMERAY PUBLIC SCHOOL

3 PALMER STREET, AMMERAY, NSW

### WALL TYPES 01

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

 PROJECT NUMBER
 DIRECTOR

 7068CY01
 JW

CHECKED

DRAWING NUMBER






 Image: Image shows a state of the state of the

|      | CPS-FTA-B00G-ZZ-DR-A-4201   | 04       |
|------|---|----------|
|      | DRAWING NUMBER  | REVISION |
| HOOL | PROJECT NUMBER         DIRECTOR           7068CY01         JW   | CHECKED  |
|      | Figured dimensions take precedence over<br>scale dimensions. Contractors must verify<br>all dimensions on site before commencing<br>any work or making shop drawings. |          |

| IEMATIC DESIGN     |
|--------------------|
| OOL INFRASTRUCTURE |
| /                  |
|                    |


### CAMMERAY PUBLIC SCH

68 PALMER STREET, CAMMERAY, NSW

### SECTION DETAILS 01

SCALE: 1:20

2 DETAIL SECTION SECTION DETAIL 02 - STREET SIDE WALL



05 TENDER ADDENDUM 04 100% SCHEMATIC DESIGN - REVISED

03 100% SCHEMATIC DESIGN 02 80% SCHEMATIC DESIGN 01 50% SCHEMATIC DESIGN REV. DESCRIPTION

28/02/2025 NK

11/02/2025 NK

10/01/2025 NK 13/12/2024 NK

03/12/2024 NK DATE INIT,

DIRECTORS Greg Isaac raia Justine Ebzery fraia John Ward raia Katerina Dracopoulo Paul Sekava fraia Ryan Loveday fraia

plot date: Friday, 28 February 2025 11:29 AM file location: BIMcloud: FTA-SYD-BIM26 - BIMcloud Basic for Archicad 26/7068CY01 Cammeray Public School

SYDNEY Suite 904, Level 9, 28-36 Foveaux Street, Surry Hills, NSW 2010 t. (02) 8383 5151 e. sydney@fultontrotter.com.au

Fulton Trotter Architects ACN 677 264 550 ABN 57 677 264 550 To be used for authorised work only. Not to be copied directly or indirectly, in whole or in part, nor shall it be used for any other building purposes.

VIC 18804

 NSW 6855
 QLD 2920


 QLD 3313
 QLD 3313


 NSW 8371
 QLD 3847

 NSW 7454
 QLD 4529

 NSW 7160
 QLD 3108

 QLD 4500
 QLD 4500





| ARCHITECTS BRISBANE SYDNEY WWW.fultontrotter.com.au SYDNEY Suite 94, Level 9, 28-36 Foresaux Street, Suny Hills, INSW 2010 L (22) 3835 1515 - experime gillulariterites accentrates accent | CHEMATIC DESIGN - REVISED     11022025     NK     WK     MALE     MALE | EMATIC DESIGN - REVISED 11/02/025 NK EMATIC DESIGN - REVISED 10/02/025 NK EMATIC DESIGN - 1001/2025 NK EMATIC DESIGN - 1001/2025 NK EMATIC DESIGN - 1001/2025 NK  |
|--|---|---|
| SYDNEY         Suite 904. Level 9, 28-36 Foresoux Street, Suny Hills, NSW 2010           L (22) 8383 5151         e. sydney@tlubritotler.com.au           Futtorn Trotter Architects ACN 877 264 550         Tobe used for authrolined work only. Not to be copied directly or indirectly.   | SYDNEY Sub 904, Lovel 8, 22-36 Foxeau Sheet, Suny Hills, NSW 2010<br>1, (02) 3033 3151 = sydney[dillamination:nau<br>Feature Architects ACM CT 24 450 All 37 677 24 450<br>CheMATIC DESIGN - REVISED 11022022 NK  | SYDNEY Suite 904, Level 8, 28-36 Foreaux Street, Surry Hills, NSW 2010 L (2) 2835 5151 e. sprohegi@ildottritter.com.au Feltor Torter Architects ACN 677 254 500 ABS 7 677 254 550 To be used for authorised verkin only. Nat to be copied directly in directly, in which or in part, nor shall it be used for any three building or indexed, in which or in part, nor shall it be used for any three building or indexed, in which or in part, nor shall it be used for any tensors. BENATIC DESIGN - REVISED 1002/225 NK Gree Toesa or the three building or indexed, in which or in part, nor shall it be used for any tensors. BENATIC DESIGN - NEVISED 1002/225 NK Gree Toesa or the three building or indexed, in which or in part, nor shall it be used for any tensors. BENATIC DESIGN - NEVISED 1002/225 NK   |
| Fulton Trotter Architects ACN 677 264 550 ABN 57 677 264 550<br>Tobe used for authorised work only. Not to be copied directly or indirectly,   | Fibon Trotter Architeck ACN 677 254 569 AMP 517 254 559 AMP 517 254 557 AMP 517 254 559 AMP 517 254 557 AMP 517 AMP 517 AMP 517 AMP 517 A | Falton Trates Architects ACM 577 355 ABIN 57 77 254 550     Tobe used for authorised work only. Not to be capied directly on indicetly,     In whole or in part, nor shall it be used for any other building purposes.      WEMATIC DESIGN 1001/2025 NK     Gree Example     Tobe used for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purposes.      The Comparison of the second for any other building purpose.      The Comparison of the second for any other building purpose.      The Comparison of the second for any other building purpose.      The Comparison of the second for any other building purpose.      The Comparison of the second for any other building purpose.      The Comparison of the second for any other building purpose.      The Comparison of the second for any other building purpose.      The Comparison of the second for any other building purpose.      The Comparison of the second for any other building purpose.      The Comparison of the second for any other building purpos |
|  | SCHEMATIC DESIGN - REVISED 11/02/2025 NK  | IEMATIC DESIGN - REVISED 11/02/2025 NK<br>IEMATIC DESIGN 10/01/2025 NK Gire base rate NSW 6855 QLD 2920   |
| CHEMATIC DESIGN         10/01/2025         NK         Greg teasc rais         NSW 6855         QLD 2920           Justine Ebsay frais         Justine Ebsay frais         OLD 3937         QLD 3937         QLD 3947   | CHEMATIC DESIGN 13/12/2024 NK John Ward raia VIC 18804 NSW 8371 QLD 3847  |   |
| % SCHEMATIC DESIGN 10/01/2025 NK Greg taxas rain NSW 6855 QLD 2920<br>Ustine Ebzery frain OLD 2313   | CHEMATIC DESIGN         13/12/2024         NK         John Ward raia         VIC 18804         NSW 3371         QLD 38/7           CHEMATIC DESIGN         03/12/2024         NK         Katerina Dracopoulos finia         NSW 7434         QLD 4529           CHEMATIC DESIGN         03/12/2024         NK         Paul Stewar finia         NSW 7160         QLD 3106   | EMATIC DESIGN 03/12/2024 NK Paul Sekava fraia NSW 7180 QLD 3108   |

plot date: Tuesday, 11 February 2025 9:48 AM file location: BIMcloud: FTAmeray Put

| IEMATIC DESIGN     | SEC                                      |
|--------------------|--|
| OOL INFRASTRUCTURE | Figured dir<br>scale dime<br>all dimensi |

CAMMERAY PUBLIC SCHOOL

68 PALMER STREET, CAMMERAY, NSW

imensions take precedence over ensions. Contractors must verify sions on site before commencing or making shop drawings. l any wo

PROJECT NUMBER 7068CY01

SNING


JW DRAWING NUMBER

DIRECTOR

CHECKED


CPS-FTA-B00G-ZZ-DR-A-4203






С










XPX



|     |                                 |            |       | ulton t  | <b>ro</b> tt              | er                   |
|-----|---------------------------------|------------|-------|--|---------------------------|----------------------|
|     |                                 |            |       | RCHITECTS BR   |                           |                      |
|     |                                 |            |       | YDNEY Suite 904, Level 9, 28-36 Fov<br>t. (02) 8383 5151 e. sydner   | veaux Street, Surry Hills |                      |
|     |                                 |            |       | Fulton Trotter Architects ACN 677 20<br>To be used for authorised work only. Not to<br>in whole or in part, nor shall it be used for | to be copied directly or  | indirectly,          |
| 04  | 100% SCHEMATIC DESIGN - REVISED | 11/02/2025 | NK    |  | or any other building pu  | puese.               |
| 03  | 100% SCHEMATIC DESIGN           | 10/01/2025 | NK    | ECTORS<br>3 Isaac raia   | NSW 6855                  | QLD 2920             |
| 02  | 80% SCHEMATIC DESIGN            | 13/12/2024 | NK    |  | 18804 NSW 8371            | QLD 3313<br>QLD 3847 |
| 01  |                                 | 03/12/2024 |       | rina Dracopoulos fraia<br>I Sekava fraia   | NSW 7434<br>NSW 7180      | QLD 4529<br>QLD 3108 |
| EV. | DESCRIPTION                     | DATE       | INIT. | n Loveday fraia  |                           | QLD 4500             |

plot date: Tuesday, 11 February 2025 9:48 AM file location: BIMcloud: FTA-SYD-BIM26 - BIMcloud Basic for Archicad 26/7068CY01 Cammeray Public School

# HEMATIC DESIGN

IMERAY PUBLIC SCHOOL

ALMER STREET, MERAY, NSW

### BALUSTRADE AND HANDRAIL DETAILS

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

DIRECTOR

CPS-FTA-B00G-ZZ-DR-A-4501



PROJECT NUMBER

7068CY01


DRAWING NUMBER


JW

CHECKED

REVISION

75MM MINX 12MM GALV. MS TOP RAIL -@10° TO FACILITATE DRAINING AND SELF CLEANING TOP OF BALUSTRADE





|     |            |                          |           | -   |
|-----|------------|--------------------------|-----------|-----|
| _   |            |                          |           |     |
|     |            |                          |           |     |
| ١K  | 21/02/2025 | HEMATIC DESIGN - REVISED |           |     |
| ۱K  | 11/02/2025 | HEMATIC DESIGN - REVISED | % SCHEMAT | D4  |
| ٩K  | 10/01/2025 | HEMATIC DESIGN           | % SCHEMAT | 13  |
| ۹K  | 13/12/2024 | EMATIC DESIGN            | SCHEMATI  | 02  |
| 4K  | 03/12/2024 | EMATIC DESIGN            | SCHEMATI  | 01  |
| UT. | DATE       | TION                     | CRIPTION  | EV. |

plot date: Friday, 21 February 2025 12:49 PM file location: BIMcloud: FTA-SYD-BIM26 - BIMcloud Basic for Archicad 26/7068CY01 Cammeray Public School

# SCHEMATIC DESIGN SCHOOL INFRASTRUCTURE

NSW

CAMMERAY PUBLIC SCHOOL

68 PALMER STREET, CAMMERAY, NSW

# TYPICAL FASCIA DETAILS


Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

PROJECT NUMBER

JW








CHECKED





| <br>Ph+A |
|----------|
|          |
|          |

# SCHEMATIC DESIGN

CAMMERAY PUBLIC SCHOOL

8 PALMER STREET, CAMMERAY, NSW

### ROOM ELEVATIONS 02

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

PROJECT NUMBER DIRECTOR 7068CY01

JW DRAWING NUMBER

CHECKED

REVISION 04 CPS-FTA-B00G-ZZ-DR-A-5002

| TYPE CODE                      | TYPE E01  | TYPE E02  | TYPE E03  | TYPE E05   | TYPE E07   | TYPE E12  |
|--------------------------------|---|---|---|--|--|---|
| TYPE<br>DESCRIPTION            | FIXED GLAZING   | SLIDING WINDOW  | GLAZED DOUBLE DOOR  | SOLID DOOR WITH VISION PANEL   | SOLID DOOR (NO VISION PANEL, NO FANLIGHT)                          | FIXED LOUVRE WITH INSULATED DOOR BEHIND                 |
| OVERALL & LEAF<br>SIZE (W X H) | Overall: WIDTH VARIES x 2,050mm H   | Overall: WIDTH VARIES x 2,050mm H   | Overall: 2,265mm W x 2,750mm H<br>Leaves: 2 x 970 mm x 2040 mm,                   | Overall: WIDTH VARIES x 2,750mm H<br>Leaves: 1 x 1,070 mm x 2040 mm      | Overall: WIDTH VARIES x 2,100mm H<br>Leaves: 1 x 1,070 mm x 2040 m | Overall: WIDTH VARIES x 2,050mm H                       |
| FRAME                          | Type: DW01 - FRAME - ALUMINIUM 100MM POCKET GLAZED<br>Notes:                      | Type: DW01 - FRAME - ALUMINIUM 100MM POCKET GLAZED<br>Notes:                      | Type: DW07 - DOOR FRAME - ALUMINIUM<br>Notes:                                     | Type: DW07 - DOOR FRAME - ALUMINIUM<br>Notes:                            | Type: DW07 - DOOR FRAME - ALUMINIUM<br>Notes:                      | Type: DW03 - FRAME - ALUMINIUM 100MM POCKET G<br>Notes: |
| FRAME FINISH                   |   |   |   |  |  |   |
| LEAF                           | Type: N/A<br>Notes:   | Type: DW21 - WINDOW - SLIDING ALUMINIUM<br>Notes:                                 | Type: DW41 - LEAF - HINGED ALUMINIUM<br>Notes:                                    | Type: DW52 - LEAF - EXTERNAL SOLID CORE PAINTED w VISION<br>PANEL Notes: | Type: DW51 - LEAF - EXTERNAL SOLID CORE PAINTED<br>Notes:          | Type: N/A<br>Notes:                                     |
| LEAF FINISH                    |   |   |   |  |  |   |
| GLAZING                        | Glazing: GL04 - LAMINATED GLASS TYPE 2 - TINTED<br>Film: GL30 == GLAZING FILMS == | Glazing: GL04 - LAMINATED GLASS TYPE 2 - TINTED<br>Film: GL30 == GLAZING FILMS == | Glazing: GL04 - LAMINATED GLASS TYPE 2 - TINTED<br>Film: GL30 == GLAZING FILMS == | Glazing: GL04 - LAMINATED GLASS TYPE 2 - TINTED<br>Film: N/A             | Glazing: GL04 - LAMINATED GLASS TYPE 2 - TINTED<br>Film: N/A       | Glazing: N/A<br>N/A                                     |
| NOTES                          |   |   |   |  |  |   |
|                                |   |   |   |  |  |   |

|  | : |      |                                 |            |       | fultont   |  |   |                                  |
|--|---|------|---------------------------------|------------|-------|---|--|---|----------------------------------|
|  |   |      |                                 |            |       | ARCHITECTS BRISBANE SYDI<br>www.fultontrotter.com.a<br>sydney Suite 904, Level 9, 28-36 Foregaux, Street, Suny Hills, NS  |  | au  |                                  |
|  |   | _    |                                 |            |       | SYDNEY Suite 904, Level 9, 28-36 Fo<br>t. (02) 8383 5151 e. sydne<br>Fulton Trotter Architects ACN 677 2<br>To be used for authorised work only. Not<br>in whole or in part, nor shall it be used f | ey@fultontrotte<br>264 550 ABN 5<br>t to be copied d | er.com.au<br>57 677 264 5<br>firectly or indi | 50<br>rectly,                    |
|  |   | 01   | 100% SCHEMATIC DESIGN - REVISED | 11/02/2025 | NK    | DIRECTORS<br>Greg Isaac raia  | N  | SW 6855                                       | QLD 2920                         |
|  | - | P2   | 100% SCHEMATIC DESIGN           | 10/01/2025 | NK    | Justine Ebzery fraia<br>John Ward raia VIC<br>Katerina Dracopoulos fraia  |  | SW 8371                                       | QLD 3313<br>QLD 3847             |
|  |   | P1   | 80% SCHEMATIC DESIGN            | 13/12/2024 | NK    | Katerina Uracopoulos traia<br>Paul Sekava fraia<br>Ryan Loveday fraia   | N  | SW 7434<br>SW 7180                            | QLD 4529<br>QLD 3108<br>QLD 4500 |
| 100 150mm @ A1<br>McJoud: FTA-SYD-BIM26 - BIMcJoud Basic for Archicad 26/7068CY01 Cammeray Public School |   | REV. | DESCRIPTION                     | DATE       | INIT, | ingen surrougy new  |  |   | 4.0 4.00                         |

| OUVRES<br>DJACENT TO<br>IALKWAY TO<br>E FULL HEIGHT |       |
|---|-------|
|   |       |
|   |       |
|   |       |
| ET GLAZED   |       |
|   |       |
|   |       |
|   |       |
|   | Film: |
|   |       |
|   |       |

# SCHEMATIC DESIGN

NSW

CAMMERAY PUBLIC SCHOOL

68 PALMER STREET, CAMMERAY, NSW

EXTERNAL DOOR & WINDOW SCHEDULE

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

 PROJECT NUMBER
 DIRECTOR

 7068CY01
 JW

CHECKED

DRAWING NUMBER



| TYPE CODE                      | TYPE IN01  | TYPE IN04  | TYPE IN06  |  |
|--------------------------------|--|--|--|--|
| TYPE<br>DESCRIPTION            | GLS ENTRY LARGE SLIDING DOOR   | MULTIPURPOSE SLIDING DOOR  | SINGLE LEAF HINGED DOOR  |  |
| OVERALL & LEAF<br>SIZE (W X H) | Overall: 4,100mm W x 2,750mm H<br>Leaves: 3 x 1,333mm x 2,690mm                    | Overall: 7,200mm W x 2,750mm H<br>Leaves: 2 x 1,775mm + 2 x 1,775mm x 2,690mm      | Overall: WIDTH VARIES x 2,100mm H<br>Leaf: 1 x 970mm x 2,040mm |  |
| FRAME                          | Type: BY SUPPLIER<br>Notes:  | Type: BY SUPPLIER<br>Notes:  | Type: DW07 - DOOR FRAME - ALUMINIUM<br>Notes:                  |  |
| FRAME FINISH                   |  |  |  |  |
| LEAF                           | Type: BY SUPPLIER<br>Notes:  | Type: BY SUPPLIER<br>Notes:  | Type: DW53 - LEAF - INTERNAL SOLID CORE PAINTED<br>Notes:      |  |
| LEAF FINISH                    |  |  |  |  |
| GLAZING                        | Glazing: GL03 - LAMINATED GLASS TYPE 1 - CLEAR<br>Film: GL33 - VINYL FILM - TYPE 3 | Glazing: GL03 - LAMINATED GLASS TYPE 1 - CLEAR<br>Film: GL33 - VINYL FILM - TYPE 3 | Glazing: N/A<br>Film: N/A                                      |  |
| NOTES                          |  |  |  |  |

|                                |            |       | ARCHITECT:  | S BRISBA                                  | ANE SY               | DNEY                 |
|--------------------------------|------------|-------|---|---|----------------------|----------------------|
|                                |            |       |   | 9, 28-36 Foveaux St<br>1 e. sydney@fultor |                      | NSW 2010             |
|                                |            |       | Fulton Trotter Architect<br>To be used for authorised wo<br>in whole or in part, nor shal | rk only. Not to be cop                    | pied directly or i   | ndirectly,           |
| 00% SCHEMATIC DESIGN - REVISED | 11/02/2025 | NK    | DIRECTORS<br>Greg Isaac raia  |   | NSW 6855             | QLD 2920             |
| 00% SCHEMATIC DESIGN           | 10/01/2025 | NK    | Justine Ebzery fraia<br>John Ward raia  | VIC 18804                                 | NSW 8371             | QLD 3313<br>QLD 3847 |
| 0% SCHEMATIC DESIGN            | 13/12/2024 | NK    | Katerina Dracopoulos fraia<br>Paul Sekava fraia   |   | NSW 7434<br>NSW 7180 | QLD 4529<br>QLD 3108 |
| ESCRIPTION                     | DATE       | INIT, | Ryan Loveday fraia  |   |                      | QLD 4500             |

02 01 P1 REV.

 Image: International Control of the Internatinternatintereeee Control of the International Control of the Int

# SCHEMATIC DESIGN

NSW

CAMMERAY PUBLIC SCHOOL

68 PALMER STREET, CAMMERAY, NSW


### INTERNAL DOOR & WINDOW SCHEDULE

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

 PROJECT NUMBER
 DIRECTOR

 7068CY01
 JW

CHECKED











/02/2025 NK

 03
 100% SCHEMATIC DESIGN - REVISED

 02
 100% SCHEMATIC DESIGN

 01
 80% SCHEMATIC DESIGN

 P2
 100% CONCEPT DESIGN

 P1
 80% CONCEPT DESIGN

 REV.
 DESCRIPTION

### fulton trotter ARCHITECTS BRISBANE SYDNEY www.fultontrotter.com.au SYDNEY Suite 904, Level 9, 28-36 Foveaux Street, Surry Hills, NSW 2010 t. (02) 8383 5151 e. sydney@fultontrotter.com.au Fulton Tro To be used for in whole or it (a) 605 5151 E sydneygalionione.comai otter Architects ACN 677 264 550 ABN 57 677 264 550 authorised work only. Not to be copied directly or indirectly, n part, nor shall it be used for any other building purposes. 10/01/2025 NK 10101/2023 NK 13112/2024 NK 14/11/2024 NK 18/10/2024 NK DATE INIT. DIRECTORS Greg Isaac raia Justine Ebzery fraia John Ward raia Katerina Dracopoul Paul Sokava fraia Ryan Loveday fraia NSW 6855 QLD 2920 QLD 3313 NSW 8371 QLD 3847 NSW 7434 QLD 4529 NSW 7180 QLD 3108 QLD 3108 QLD 4500 VIC 18804

🖞 68 PALMER STREET, CAMMERAY, NSW

# SCHEMATIC DESIGN

NSW


CAMMERAY PUBLIC SCHOOL

### PERSPECTIVES 1

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

PROJECT NUMBER 7068CY01

DIRECTOR JW











|                | <u> </u> | fu                                  | Iton  | tr               | ott                  | er                   |
|----------------|----------|-------------------------------------|---|------------------|----------------------|----------------------|
|                |          | ARCH                                | HITECTS   | BRISBA           | ANE SY               | DNEY                 |
|                |          | SYDNEY                              | Suite 904, Level 9, 2<br>t. (02) 8383 5151              |                  |                      | NSW 2010             |
| 11/02/2025     | NK       | To be used                          | d for authorised work or<br>or in part, nor shall it be | y. Not to be cop | pied directly or i   | ndirectly,           |
| 10/01/2025     | NK       |                                     |   |                  |                      |                      |
| 13/12/2024     | NK       | DIRECTORS<br>Greg Isaac raia        |   |                  | NSW 6855             | QLD 2920             |
| <br>14/11/2024 | NK       | Justine Ebzery fr<br>John Ward raia | raia  | VIC 18804        | NSW 8371             | QLD 3313<br>QLD 3847 |
| 18/10/2024     | NK       | Katerina Dracop<br>Paul Sekava frai | a   |                  | NSW 7434<br>NSW 7180 | QLD 4529<br>QLD 3108 |
| DATE           | INIT,    | Ryan Loveday fr                     | aia   |                  |                      | QLD 4500             |

\_

\_\_\_\_

 00%
 SCHEMATIC DESIGN - REVISED

 02
 100%
 SCHEMATIC DESIGN

 01
 00%
 SCHEMATIC DESIGN

 P2
 100%
 CONCEPT DESIGN

 P1
 80%
 CONCEPT DESIGN

 REV,
 DESCRIPTION



plot date: Tuesday, 11 February 2025 9:48 AM file location: BIMcloud: FTA-SYD-BIM26 - BIMcloud Basic for Archicad 26/7068CY01 Cammeray Public School

# SCHEMATIC DESIGN

CAMMERAY PUBLIC SCHOOL

88 PALMER STREET, CAMMERAY, NSW

### PERSPECTIVES 2

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

CPS-FTA-B00G-ZZ-DR-A-9002

PROJECT NUMBER 7068CY01

DRAWING NUMBER

DIRECTOR JW












|      |                                 |            |       | ARCHITECTS BRISBANE SYDNEY<br>www.fultontrotter.com.au  |
|------|---------------------------------|------------|-------|---|
|      |                                 |            |       | SYDNEY         Suite 904, Level 9, 28-36 Foresack Street, Sumy Hills, NSW 2010<br>L (02) 5335 5151         e. sydme/git/stimutotex.com.au           Fullon Totter Architect SAN R7 274 5450 ABM S7 77 264 550<br>To be used for authorised work only. Not be copied directly or indirectly,<br>in where or in part, nor shall it be used for any other building purposes. |
| 02   | 100% SCHEMATIC DESIGN - REVISED | 11/02/2025 | NK    | In million of the plant, hold answer und used und any outries building publicless.     Interception     Generg basis: mail     Juniore Except finite     ULD 3397     Juniore Except finite     VIC 18804     NSW 5371     ULD 3397     Kertime Darcoordea finite     NSW 7434     ULD 3397   |
| 01   | 100% SCHEMATIC DESIGN           | 29/01/2025 | NK    | Paul Sekava fraia NSW 7180 QLD 3108   |
| REV. | DESCRIPTION                     | DATE       | INIT, | Ryan Loveday fraia QLD 4500   |



# SCHEMATIC DESIGN

CAMMERAY PUBLIC SCHOOL

88 PALMER STREET, CAMMERAY, NSW

### PERSPECTIVES 3

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

PROJECT NUMBER DIRECTOR 7068CY01


JW DRAWING NUMBER



CPS-FTA-B00G-ZZ-DR-A-9003









|      |                                 |            |       | ARCHITECTS BRISBANE SYDNEY<br>www.fultontrotter.com.au  |
|------|---------------------------------|------------|-------|---|
|      |                                 |            |       | SYDNEY Suite 904, Level 9, 28-36 Foveaux Street, Surry Hills, NSW 201<br>t. (02) 8383 5151 e. sydney@fullontrotter.com.au   |
|      |                                 |            |       | Fulton Trotter Architects ACN 677 264 550 ABN 57 677 264 550<br>To be used for authorised work only. Not to be copied directly or indirectly,<br>in whole or in part, nor shall it be used for any other building purposes. |
| 02   | 100% SCHEMATIC DESIGN - REVISED | 11/02/2025 | NK    | DIRECTORS<br>Greg Isaac rata NSW 6855 QLD 293<br>Justime Ebzery traile QLD 333<br>John Werd rate VIC 18804 NSW 8371 QLD 38  |
|      |                                 |            |       | Katerina Dracopoulos fraia VIC 10004 NSW 0371 GLD 304<br>Katerina Dracopoulos fraia   |
| 01   | 100% SCHEMATIC DESIGN           | 29/01/2025 | NK    | Paul Sekava fraia NSW 7180 QLD 310<br>Byan Loveday fraia QLD 450  |
| REV. | DESCRIPTION                     | DATE       | INIT. | Ryan Loveday fraia. QLD 450   |



# SCHEMATIC DESIGN

### CAMMERAY PUBLIC SCHOOL

88 PALMER STREET, CAMMERAY, NSW

### PERSPECTIVES 4

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

PROJECT NUMBER DIRECTOR 7068CY01

DRAWING NUMBER

JW

REVISION 02



CPS-FTA-B00G-ZZ-DR-A-9004

# Appendix 4 LANDSCAPE SCHEMATIC DESIGN

# **CAMMERAY PUBLIC SCHOOL** SCHOOL INFRASTRUCTURE NSW LANDSCAPE DOCUMENTATION

## **DRAWING REGISTER**


| DRAWING NUMBER          | DRAWING NAME              | SCALE / SIZE | REVISION |
|-------------------------|---------------------------|--------------|----------|
| CPS-GIL-00-00-DR-L-0001 | COVER SHEET               | _            | G        |
| CPS-GIL-00-00-DR-L-2001 | LANDSCAPE MASTERPLAN      | 1:300 @ A1   | L        |
| CPS-GIL-00-00-DR-L-3001 | DETAILED LANDSCAPE PLAN 1 | 1:100 @ A1   | J        |
| CPS-GIL-00-00-DR-L-3002 | DETAILED LANDSCAPE PLAN 2 | 1:100 @ A1   | С        |
| CPS-GIL-00-00-DR-L-6001 | PLANTING PLAN 1           | 1:100 @ A1   | В        |
| CPS-GIL-00-00-DR-L-6002 | PLANTING PLAN 2           | 1:100 @ A1   | A        |
| CPS-GIL-00-00-DR-L-9001 | LANDSCAPE DETAILS         | 1:20 @ A1    | C        |

## **PLANT SCHEDULE**

|         | BOTANICAL NAME                 | COMMON NAME         | MATURE HEIGHT | NATIVE       | INSTALL SIZE | SPACING            | QUANTITY |
|---------|--------------------------------|---------------------|---------------|--------------|--------------|--------------------|----------|
| TREES   |                                |                     |               |              |              |                    | -        |
| COR MAC | CORYMBIA MACULATA              | SPOTTED GUM         | 14-16M        | 1            | 100L         | AS SHOWN           | 1        |
| TRI LUS | TRISTANIOPSIS 'LUSCIOUS'       | WATERGUM            | 6-8M          | $\checkmark$ | 100L         | AS SHOWN           | 1        |
| SHRUBS  |                                |                     |               |              |              |                    |          |
| ACM SMI | ACMENA SMITHII 'MINOR'         | LILLY PILLY         | 2-4M          | 1            | 300MM        | AS SHOWN           | 10       |
| BAN BIR | BANKSIA 'BIRTHDAY CANDLES'     | HAIRPIN BANKSIA     | 1M            | $\checkmark$ | 200MM        | AS SHOWN           | 19       |
| DOR EXC | DORYANTHES EXCELSA             | GYMEA LILY          | 1.5M          | 1            | 300MM        | AS SHOWN           | 3        |
| SYZ AUS | SYZYGIUM AUSTRALE 'RESILIENCE' | LILY PILLY          | 2-4M          | $\checkmark$ | 300MM        | AS SHOWN           | 20       |
| RHA COS | RHAPHIOLEPIS 'COSMIC PINK'     | INDIAN HAWTHORN     | 0.8M          |              | 300MM        | AS SHOWN           | 9        |
| GROUNDC | OVERS & GRASSES                |                     |               |              |              |                    |          |
| DIA CAE | DIANELLA CAERULEA              | BLUE FLAX LILY      | 0.8-1M        | $\checkmark$ | 140MM        | 3 / M <sup>2</sup> | 18       |
| HAR VIO | HARDENBERGIA VIOLACEA          | FALSE SARSAPARILLA  | 0.3M          | $\checkmark$ | 140MM        | 6 / M <sup>2</sup> | 26       |
| HIB SCA | HIBBERTIA SCANDENS             | GUINEA FLOWER       | 0.3M          | $\checkmark$ | 140MM        | 8 / M <sup>2</sup> | 58       |
| IMP CYL | IMPERATA CYLINDRICA            | COGONGRASS          | 0.8M          | 1            | 140MM        | 5 / M <sup>2</sup> | 11       |
| LIR JUS | LIRIOPE 'JUST RIGHT'           | LILY TURF           | 0.5M          |              | 140MM        | 5 / M <sup>2</sup> | 29       |
| LOM LIM | LOMANDRA 'LIME TURF'           | MATT RUSH           | 0.5M          | 1            | 140MM        | 5 / M <sup>2</sup> | 28       |
| LOM LON | LOMANDRA LONGIFOLIA            | BASKET GRASS        | 0.6M-1M       | 1            | 140MM        | 5 / M <sup>2</sup> | 6        |
| PEN NAF | PENNISETUM NAFRAY              | SWAMP FOXTAIL GRASS | 0.8M          |              | 140MM        | 5 / M <sup>2</sup> | 24       |
| PRA PUR | PRATIA PURPURASCENS            | WHITE ROOT          | 0.15M         | 1            | 140MM        | 5 / M <sup>2</sup> | 3        |
| THE AUS | THEMEDA AUSTRALIS              | KANGAROO GRASS      | 0.3-0.5M      | √            | 140MM        | 5 / M <sup>2</sup> | 4        |
| TRA ASI | TRACHELOSPERMUM ASIATICUM      | ASIAN STAR JASMINE  | 0.15M         |              | 140MM        | 5 / M <sup>2</sup> | 20       |
| VIO HED | VIOLA HEDERACEA                | NATIVE VIOLA        | 0.3M          | 1            | 140MM        | 5 / M <sup>2</sup> | 6        |



NOTE VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK. REPORT ALL DISCREPANCIES TO LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION. FIGURED DIMENSIONS TO DE TAKEN IN PREFERENCE TO SCALED DRAWINGS. ALL WORK IS TO CONFORM TO RELEVANT AUSTRALIAN STANADRASS AND OTHER CODES AS APPLICABLE LOCATION OF UNDERGROUND SERVICES TO BE PROVEN ON SITE AND PROTECTED IF NECESSARY PRIOR TO CONSTRUCTION DIAL BEFORE YOU DIG. PLANT SPECIES AND QUARTITIES SHOWN ARE INDICATIVE ONLY AND ARE SUBJECT TO CHANGE BASED ON FUTURE PROJECT REQUIREMENTS.




**COVER SHEET** 

CAMMERAY PUBLIC SCHOOL CAMMERAY, NSW 2062 PALMER STREET, CAMMERAY NSW 2062 SCALE N/A

## DRAWING NUMBER CPS-GIL-00-00-DR-L-0001

## <sup>REV</sup>






VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK. REPORT ALL DISCREPANCIES TO LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION. FIGURED DIMENSIONS TO DE TAKEN IN PREFERENCE TO SCALED DRAWINGS. ALL WORK IS TO CONFORM TO RELEVANT AUSTRALIAN STANADRASS AND OTHER CODES AS APPLICABLE LOCATION OF UNDERGROUND SERVICES TO BE PROVEN ON SITE AND PROTECTED IF NECESSARY PRIOR TO CONSTRUCTION DIAL BEFORE YOU DIG. PLANT SPECIES AND QUARTITIES SHOWN ARE INDICATIVE ONLY AND ARE SUBJECT TO CHANGE BASED ON FUTURE PROJECT REQUIREMENTS.

NOTE



ING TITLE

### LEGEND




#### EXISTING TREE SCHEDULE

| ID  | BOTANICAL NAME                                   | EXISTING<br>HEIGHT | PROPOSED<br>ACTION |
|-----|--|--------------------|--------------------|
| T26 | EUCALYPTUS BOTRYOIDES (BANGALAY)                 | 12M                | RETAINED           |
| T27 | EUCALYPTUS SALIGNA (SYDNEY BLUE GUM)             | 23M                | REMOVE             |
| T28 | CORYMBIA MACULATA (SPOTTED GUM)                  | 16M                | REMOVE             |
| T29 | ACACIA MEARNSII (BLACK WATTLE)                   | 4M                 | RETAINED           |
| T30 | PHOENIX CANARIENSIS<br>(CANARY ISLAND DATE PALM) | 5M                 | RETAINED           |
| T31 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T32 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T33 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T34 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T35 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T12 | CASUARINA GLAUCA (SWAMP SHE OAK)                 | 18M                | RETAINED           |
| T13 | CASUARINA GLAUCA (SWAMP SHE OAK)                 | 12M                | RETAINED           |
| T14 | CASUARINA GLAUCA (SWAMP SHE OAK)                 | 12M                | RETAINED           |
| T15 | CASUARINA GLAUCA (SWAMP SHE OAK)                 | 18M                | RETAINED           |
| T16 | CASUARINA GLAUCA (SWAMP SHE OAK)                 | 12M                | RETAINED           |

"EXISTING TREE HEIGHTS AND SPECIES SOURCED FROM PRELIMINARY ARBORICULTURAL REPORT BY L&CO CONSULTANCY ARBORICULTURE PLANT PATHOLOGY DATED 2/<sup>ST</sup>FEBRUARY 2023

## LANDSCAPE MASTERPLAN

|  | CPS-GIL-00-00-DR-L-2001 |  |  |  |  |
|--|-------------------------|--|--|--|--|
| PROJECT  | NORTH                   |  |  |  |  |
| CAMMERAY PUBLIC SCHOOL<br>CAMMERAY, NSW 2062<br>PALMER STREET, CAMMERAY NSW 2062 |                         |  |  |  |  |
| SCALE 1:300 @A1  | REV                     |  |  |  |  |
| 0 3 6 9M   | L                       |  |  |  |  |



**GROUND INK** LANDSCAPE ARCHITECTS SUITE 15, SNERIDAHST, CHATSWOOD NSW 2067 PH. (02) 9411 3279 WWW.BROUNDINK.COMAU ABIN 55 163 205 456 ACIN 163 025 456 erodukein Mkr.UID Theis Belsink and Daramine is Protectible to Corporate VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK. REPORT ALL DISCREPANCIES TO LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION. FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED DRAWINGS. ALL WORK IS TO CONFORM TO RELEVANT AUSTRALIAN STANDARDS AND OTHER CODES AS APPLICABLE LOCATION OF UNDERGROUND SERVICES TO BE PROVEN ON SITE AND PROTECTED IF NECESSARY PRIOR TO CONSTRUCTION. DIAL BEFORE YOU DIE. FLANT SPECIES AND QUANTIES SHOWN ARE INDICATIVE ONLY AND ARE SUBJECT TO CHANGE BASED ON FUTURE PROJECT REQUIREMENTS.



### LEGEND


| FFL 00.00   | FINISHED FLOOR LEVEL  |
|-------------|---|
| + EX 00.00  | EXISTING SPOT LEVEL   |
| + RL 00.00  | PROPOSED SPOT LEVEL   |
| + TW 00.00  | PROPOSED TOP OF WALL LEVEL  |
| + ETW 00.00 | EXISTING TOP OF WALL LEVEL  |
|             | EXTENT OF WORKS BOUNDARY  |
|             | STRUCTURAL ROOT ZONE LINE   |
| TPZ-        | TREE PROTECTION ZONE LINE   |
|             | PROPOSED GARDEN BED   |
|             | PROPOSED CONCRETE PATHWAY   |
|             | PROPOSED VERANDAH   |
| •           | EXISTING TREES TO BE RETAINED<br>REFER TO EXISTING TREE SCHEDULE FOR<br>TREE SPECIES AND HEIGHTS        |
| •           | EXISTING TREES TO BE REMOVED  |
|             | PROPOSED TREES<br>REFER TO INDICATIVE PLANT SCHEDULE ON DRA<br>CPS-GIL-00-00-DR-L-0001 FOR TREE SPECIES |
|             | PROPOSED MASONRY WALL   |
|             | EXISTING WALL   |
|             | STORMWATER PIT<br>TO ENGINEER'S DETAILS   |

#### EXISTING TREE SCHEDULE

| ID  | BOTANICAL NAME                                   | EXISTING<br>HEIGHT | PROPOSED<br>ACTION |
|-----|--|--------------------|--------------------|
| T26 | EUCALYPTUS BOTRYOIDES (BANGALAY)                 | 12M                | RETAINED           |
| T27 | EUCALYPTUS SALIGNA (SYDNEY BLUE GUM)             | 23M                | REMOVE             |
| T28 | CORYMBIA MACULATA (SPOTTED GUM)                  | 16M                | REMOVE             |
| T29 | ACACIA MEARNSII (BLACK WATTLE)                   | 4M                 | RETAINED           |
| Т30 | PHOENIX CANARIENSIS<br>(CANARY ISLAND DATE PALM) | 5M                 | RETAINED           |
| T31 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T32 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T33 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T34 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T35 | CORYMBIA MACULATA (SPOTTED GUM)                  | 18M                | RETAINED           |
| T12 | CASUARINA GLAUCA (SWAMP SHE OAK)                 | 18M                | RETAINED           |
| T13 | CASUARINA GLAUCA (SWAMP SHE OAK)                 | 12M                | RETAINED           |
| T14 | CASUARINA GLAUCA (SWAMP SHE 0AK)                 | 12M                | RETAINED           |
| T15 | CASUARINA GLAUCA (SWAMP SHE OAK)                 | 18M                | RETAINED           |
| T16 | CASUARINA GLAUCA (SWAMP SHE OAK)                 | 12M                | RETAINED           |

### DETAILED LANDSCAPE PLAN 1

|   | DRAWING NUMBER          |
|---|-------------------------|
|   | CPS-GIL-00-00-DR-L-3001 |
| PROJECT   | NORTH                   |
| CAMMERAY PUBLIC SCH<br>CAMMERAY, NSW 2062<br>PALMER STREET, CAMMERAY NS | ( –)                    |
| SCALE 1:100   | REV                     |
| 0 1 2 3M  | 1                       |



|  |        |         | CPS  | -GIL-00-00- | DRAWING NUMBER |
|--|--------|---------|------|-------------|----------------|
| PROJECT<br>CAMMER<br>CAMMER<br>PALMER ST | RAY, N | SW 2062 | HOOL |             | NORTH          |
| SCALE 1:100                              | 2      | зм      |      |             | REV<br>B       |

Appendix 5 EFSG DEPARTURE SCHEDULE



| PROJECT   | INFORMATION                     |  |  |  |  |            |          |  |
|-----------|---------------------------------|--|--|--|--|------------|----------|--|
| SCHOOL    | NAME                            | Group 2 Program  | _  | Prepared By: John Ward   | Revision: A  | 18.12.24   |          | EFSG Edition at Tender Date: <vxx.xx.xx></vxx.xx.xx> |
| PROJECT   | TFAM                            | · · ·  |  |  |  | •          |          |  |
|           | SI Project Directo<br>Contracto |  |  | :: Fulton Trotter Architects<br>r: RP Infrastructure   |  |            |          |  |
| Contracto | or/Architect/Consult            | ant Input  |  |  |  |            |          | Stakeholder Input                                    |
|           | EFSG #                          | EFSG Requirement   | Proposed Departure   | Reason for Departure   | Supporting Appendix or RFI<br>Details Issued   | Request by | Date     | Stakeholder(s)<br>Response                           |
| C1        |                                 | Acoustic Requirements - sliding doors  | All sliding doors and internal walls<br>to hub teaching spaces to achieve<br>RW 32 in liue of RW 45 as per EFSG                              | Standard departure - functionality   | -  | FTA        | 24.10.24 | XX<br>XX<br>XX<br>XX<br>XX                           |
| C2        |                                 | Ceiling Void Ventilation   | REMOVE REQUIREMENT FOR ROOF<br>VENTILATORS<br>option for not using require<br>installation of roof<br>ventilators/"whirly birds"             | F Standard departure - functionality - Roof ventilators should not be<br>provided as they are leaky, reducing the effectiveness of air<br>conditioning and energy consumption due to uncontrolled infiltration<br>of outdoor air and allow large amounts of noise in from outside. | -  | FTA        | 24.10.24 | XX   |
| C3        | DG45                            | Ceilings - FC Sheeting to Wet Areas  | DG45 nominates fibre cement<br>sheeting to all wet area ceilings. It<br>is proposed to use moisture<br>resistant plasterboard.               | Standard departure - moisture resistant plasterboard is cheaper and<br>quicker to install  | -  | FTA        | 24.10.24 | XX   |
| C4        |                                 | Coloured Concrete  | Standard grey concrete to be used for paving areas   | Standard departure - functionality - coloured concrete is prone to<br>cracking and requires smaller pours hence more cost.   | -  | FTA        | 24.10.24 | XX   |
| C5        |                                 | Concrete Classification  | Require class 3 concrete finish to al<br>unexposed areas and class 2 for<br>exposed concerete  | II Standard departure - functionality  | -  | FTA        | 24.10.24 | XX   |
| C6        |                                 | hot dip glvanising to internal steel   | Alternative paint system to<br>structural steel (internal – external<br>to remain as HDG)  | Standard departure - functionality   | -  | FTA        | 24.10.24 | XX   |
| С7        |                                 | Ventilation System to Comms<br>Rooms   | Remove requirement for exhaust<br>ventilation system to the Comms<br>Rooms.  | Standard Departure - SINSW ICT/ITD always require A/C spilt systems to all comms rooms and as such exhaust systems are redundant and a waste of time & money.  | -  | FTA        | 24.10.24 | ХХ   |
| C8        |                                 | Internal Sliding Door Acoustics  | Internal GLS sliding doors are<br>required to meet RW45 acoustic<br>values under the EFSG<br>requirements. Slidng doors to<br>acheive RW 32. | Standard Departure - This requirement is not achievable with the current EFSG Hub layouts with the GLS spaces often designed with operable shared walls for maximum flexibility.   | -  | FTA        | 24.10.24 | XX   |
| C9        |                                 | Warranties   | Rationalise warranty periods in<br>general - accept warraties available<br>to industry   | Standard departure - functionality   | -  | FTA        | 24.10.24 | XX   |
| C10       |                                 | Rain noise barrier   | Delete rain noise layers to ceilings<br>(Wavebar or solid lining above<br>acoustic ceiling) where there are<br>metal roofs above             | Standard departure - functionality   | -  | FTA        | 24.10.24 | XX   |
| C11       |                                 | Smart lighting   | Remove Smart Lighting Control e.g<br>C-Bus revert back to 240V and<br>sensors  | Standard departure - functionality   | -  | FTA        | 24.10.24 | XX   |
| C12       |                                 | Windows  | Remove requirement to use "PWD<br>SUITE NO2" - accept semi<br>commercial alternative suite   | Standard departure - functionality   | -  | FTA        | 24.10.24 | XX   |
| C13       | Pattern Book                    | 3400mm high ceiling in front of<br>windows to the GLS                                | Additional bulkheads are provided<br>to the edges of the GLS reducing<br>the width of the 3400mm high<br>ceiling                             | The additional bulkheads are required to allow for mechanical ductwork and vents to connect to the external wall of the building   | The changes is noted as<br>acceptable in principle in the<br>Pattern Book documentation. | FTA        | 18.12.24 | XX   |
| C14       | DG40.01                         | Clear anoused aluminium<br>window framing ("no colour<br>anodising or powder coating | The Pattern Book design includes<br>colours (powdercoat) for external<br>aluminium framing (doors,   | Compliance with Dattern Deals see down   |  | FTA        | 19.12.24 | XX   |

|                           |                     |            | EFSG D        | DEPARTURES         | SCHEDULE |
|---------------------------|---------------------|------------|---------------|--------------------|----------|
|                           |                     |            |               |                    |          |
|                           |                     |            |               |                    |          |
|                           |                     |            |               |                    |          |
|                           |                     |            |               |                    |          |
|                           |                     |            |               |                    |          |
|                           |                     |            | Proj          | ject Managemei     | nt Input |
| Other Stakehold<br>review | ler(s) to<br>Issuer | Date       | Closed<br>Y/N | ESC Approval<br>by | Date     |
| XX, XX                    | xx                  | XX.XX.XX   |               | XX, XX             |          |
|                           |                     |            | Ν             |                    |          |
| XX, XX                    | xx                  | XX.XX.XX   |               | хх                 |          |
|                           |                     |            | N             |                    |          |
|                           |                     |            |               |                    |          |
| XX, XX                    | xx                  | XX.XX.XX   |               | хх                 |          |
|                           |                     |            | N             |                    |          |
| XX, XX                    | xx                  | XX.XX.XX   | N             | хх                 |          |
| XX, XX                    | хх                  | XX.XX.XX   |               | хх                 |          |
|                           |                     |            | N             |                    |          |
| XX, XX                    | XX                  | XX.XX.XX   | N             | хх                 |          |
| XX, XX                    | xx                  | XX.XX.XX   |               | хх                 |          |
|                           |                     |            | N             |                    |          |
| XX, XX                    | xx                  | XX.XX.XX   |               | хх                 |          |
|                           |                     |            | N             |                    |          |
|                           |                     |            |               |                    |          |
| XX, XX                    | xx                  | XX.XX.XX   | N             | хх                 |          |
| XX, XX                    | xx                  | XX.XX.XX   |               | хх                 |          |
|                           |                     |            | N             |                    |          |
|                           |                     |            |               |                    |          |
| XX, XX                    | xx                  | XX.XX.XX   | N             | хх                 |          |
| VV VV                     |                     |            | IX .          | vv                 |          |
| XX, XX                    | XX                  | XX.XX.XX   | N             | хх                 |          |
| XX, XX                    | xx                  | XX.XX.XX   |               | хх                 |          |
|                           |                     |            | N             |                    |          |
|                           |                     | WY 107 107 |               | ××                 |          |
| XX, XX                    | XX                  | XX.XX.XX   | N             | хх                 |          |
|                           |                     |            |               |                    |          |

|  | Education<br>School Infrastru |
|--|-------------------------------|
|--|-------------------------------|

|            | Educat<br>School II                                 | <b>ion</b><br>nfrastructure   |   |   |   |                |          |  |                             |                  |                     | EFSG D        | EPARTURES          | SCHEDULE |
|------------|---|---|---|---|---|----------------|----------|--|-----------------------------|------------------|---------------------|---------------|--------------------|----------|
| PROJECT I  |   | Cammeray Public School  |   | Prepared By: John Ward  | Revision: A   | Date: 24.10.24 |          | EFSG Edition at Tender Date: <vxx.xx.xx></vxx.xx.xx> |                             |                  |                     |               |                    |          |
| PROJECT 1  |   |   |   | Prepared by. John Ward  | REVISION. A   | Date: 24.10.24 |          | EFSG Edition at Tender Date. <vxx.xx.xx></vxx.xx.xx> |                             |                  |                     |               |                    |          |
|            | SI Project Director<br>Contractor                   |   |   | : Fulton Trotter Architects<br>: RP Infrastructure  |   |                |          |  |                             |                  |                     |               |                    |          |
| Contractor | r/Architect/Consulta                                | nt Input  | -   |   |   |                |          | Stakeholder Input                                    |                             |                  |                     | -             | ect Managemen      | nt Input |
| ltem #     | EFSG #  | EFSG Requirement  | Proposed Departure  | Reason for Departure  | Supporting Appendix or RFI<br>Details Issued                            | Request by     | Date     | Stakeholder(s)<br>Response                           | Other Stakeholder<br>review | (s) to<br>Issuer | Date                | Closed<br>Y/N | ESC Approval<br>by | Date     |
| 1          | Pattern Book  | Standard Hub Layout Configuration   | Teaching spaces are not in<br>compliance with the configuration<br>of the Pattern Book and the<br>Standard Hub Layouts  | Existing site restrictions and space limitations  | -   | FTA            | 24.10.24 | XX<br>XX<br>XX<br>XX<br>XX                           | XX, XX                      | XX               | XX.XX.XX            | N             | XX, XX             |          |
| 2          | Pattern Book  | Roof Configuration  |   | The roof has been arranged to be a continuation of the existing<br>Building E roof - as this project is an expansion to that building   | -   | FTA            | 24.10.24 | XX   | ХХ, ХХ                      | xx               | XX.XX.XX            | N             | хх                 |          |
| 3          | Pattern Book  | Height of Roof  | The clear height under the roof at-<br>the edge of the verandah is-<br>2100mm   | This is due to the extension of the existing roof form and the wider-<br>verandah in the proposed building  | -   | FTA            | 24.10.24 | ×  | <del>xx, xx</del>           | ××               | <del>XX.XX.XX</del> | N             | XX                 |          |
| 4          | DoE Structured<br>Cabling Systems<br>Specifications | One (1x) Building Communications<br>Room to be included in the core of<br>each level of the proposed building   | Proposed building is to have one<br>BCR only located on the ground  | Based on the EFSG pattern book, only one BCR is required in the core<br>of a building of up to three levels.  | Patternbook_Vol_2<br>_Building_Components<br>_Rev_4, 3.4 comms strategy | NDY            | 25.10.24 | XX   | XX, XX                      | xx               | XX.XX.XX            | N             | хх                 |          |
| 5          | DoE Structured<br>Cabling Systems<br>Specifications | The Building Communications Room<br>(BCR) is required to have minimum<br>internal dimensions 3000mm x<br>2800mm with a 2700mm minimum<br>ceiling height.            | 2800mm, but will have a ceiling<br>height reduction where it extends  | The plan area (3000mm x 2800mm) complies with the EFSG<br>requirements. Rack location can be adjusted to ensure adequate<br>overhead clearance and access to the sides and rear.<br>Additionally, the proposed new block comprises only four (4x) new<br>teaching spaces. Smaller equipment can be used than those specified<br>in the Cabling Systems Specification. |   | NDY            | 25.10.24 |  | xx, xx                      | xx               | XX.XX.XX            | N             | xx                 |          |
| 6          | DoE Structured<br>Cabling Systems<br>Specifications | MCR specifications as per section<br>6.4 of the DoE Structured Cabling<br>Systems Specifications.   | Existing MCR within block A shall<br>be maintained with upgrades as<br>per the ICT summary.   | Block A is a heritage building which would make replacement of the MCR difficult. Existing location and racks (with upgrades as per the ICT summary) are still fit-for-purpose and maintaining them would be more cost-effective.   |   | NDY            | 25.10.24 | xx   | XX, XX                      | xx               | XX.XX.XX            | N             | хх                 |          |
| 7          | -   | Campus backbone security and<br>communications fibre is to be run<br>within separate conduits and pits.   | Communications and security fibre<br>to be reticulated together using<br>existing in-ground conduit routes.   | Conduit route is located in an area where trenching would be difficult.<br>Utilising existing conduits would reduce costs.  |   | NDY            | 25.10.24 | XX   | XX, XX                      | xx               | XX.XX.XX            | N             | хх                 |          |
| 8          | 0001C Design<br>Checklist - Electrical<br>Services  | At least one (1x) EDB per level.  | One (1x) EDB serving both floors, to be located in a cupboard on the ground floor.  | The proposed building comprises only 4 learning spaces, which can be supplied from a single EDB. Additionally, avoiding a second EDB on the first floor will provide adequate space for inverter(s) and a riser.  |   | NDY            | 25.10.24 | XX   | XX, XX                      | xx               | XX.XX.XX            | N             | xx                 |          |
|            | 0001C Design<br>Checklist - Electrical<br>Services  | EDBs should be located such that all<br>equipment supplied is within a 25m<br>radius of the EDB.  |   | Based on the EFSG patternbook, a single EDB in the core of the level 1 is appropriate for supplying the entire building. This also allows EDBs to be away from student areas and improves maintenance personnel access.   |   | NDY            | 25.10.24 | XX   | XX, XX                      | XX               | XX.XX.XX            | N             | xx                 |          |
| 10         | 0001C Design<br>Checklist - Electrical<br>Services  | The Main Switchboard (MSB) is to<br>be located in a Main Switchroom<br>required to have one straight wall<br>of minimum length 3m for a MSB<br>length of up to 2.4m | Installation of a new Main<br>Switchboard located in situ to<br>existing (to be demolished), within<br>Main Switchroom of dimensions<br>2000mm (W) x 1000mm (D) | MSB can be located internally and avoids works to Block A (heritage) to expand MSR  | 0001C Design Checklist -<br>Electrical Services                         | NDY            | 25.10.24 | - xx   | XX, XX                      | xx               | XX.XX.XX            | N             | xx                 |          |
| 11         | Pattern Book  | Downpipes should be avoided on<br>the verandah side of the building   | Downpipes are proposed to the verandah side of the roof.  | Due to the form of the roof - in order to match to Building E -<br>downpipes are required on the verandah side of the building.<br>Additional protection is proposed to be provided to avoid climbing<br>risks.   | -   | FTA            | 25.10.24 | XX   | XX, XX                      | XX               | XX.XX.XX            |               | xx                 |          |

# Appendix 6 **RFI TRACKER**

| Cammeray Public School<br>Item Title                              | Description  | Date Raised                 | Raised By (Org)                  | Raised By (Contact)               | Action Required By               | Due Date                         | Sta                        |
|---|--|-----------------------------|----------------------------------|-----------------------------------|----------------------------------|----------------------------------|----------------------------|
| 1 Design Review   | Test Master plan reivew options against standard hub layout + connection   | <del>7/23/202</del> 4       | SINSW IP Team                    | Ant Courtman                      | Architect - FTA                  | 7/31/2024                        | Com                        |
|   | to existing building E modification to stairs / location   |                             |                                  |                                   |                                  |                                  |                            |
| 2 Design  | New building options:  | 7/23/2024                   | BCA/DDA                          | Daniel Murrow (DM)                | Architect - FTA                  | 7/31/2024                        | In progress                |
|   | * connect to existing levels of Building E + stair modifications   |                             |                                  |                                   |                                  |                                  |                            |
|   | * move stair closer to western boundary to improved access/egress to-  |                             |                                  |                                   |                                  |                                  |                            |
|   | GLS  | 7/00/0004                   |                                  |                                   | SINSW IP Team                    | 0/0/0004                         |                            |
| 3 Stakeholders<br>4 Site Investigations / Due Diligence-          | Transport Working Group meeting dates / membership<br>* Gap analysis ICT capacity / capability of existing services vs new build-      |                             | SINSW IP Team<br>Project Manager | Matt Spooner                      | Electrical - NDY                 | 8/8/2024<br>8/7/2024             | In progress                |
| 4 One investigations? Due Diagenee                                | EFSG scope   | 772072024                   | Troject Hanager                  | Flatt optioner                    | 20001001 1101                    | 0/7/2024                         | 010                        |
|   | * Capacity of Building E to serve the new build for power, ICT and   |                             |                                  |                                   |                                  |                                  |                            |
|   | mechanical supply  |                             |                                  |                                   |                                  |                                  |                            |
|   | * Preliminary enquiry request to energy authority for current capacity of  |                             |                                  |                                   |                                  |                                  |                            |
| 5 <del>Design</del>   | the school.<br>Pan/ amenities count  | 23/07/2024                  | BCA/DDA                          | Daniel Murrow (DM)                | Architect - FTA                  | 23/07/2024                       | Clos                       |
| 5 5 5 5 5 F   |  | <del>8/07/2024 Design</del> |                                  | Damot Harron (Drif)               |                                  |                                  |                            |
|   |  | meet                        |                                  |                                   |                                  |                                  |                            |
| 6 Due Diligence   | Survey review by all design consultants & advise of any additional scope   | 7/23/2024                   | SINSW IP Team                    | Carolina Vuoso (CV)               | Other                            | 8/7/2024                         | Clo                        |
| 7 Docign DDA  | required   | 7/22/2024                   | Project Manager                  | Matt Spooper                      | BCA / DDA                        | 8/15/2024                        | Com                        |
| 7 Design - DDA  | Advice re compliance of site for principal entry point following master<br>plan review   | //23/2024                   | Project Manager                  | Matt Spooner                      | BCAT DDA                         | 6/15/2024                        | COIII                      |
|   |  |                             |                                  |                                   |                                  |                                  |                            |
| 8 Due Diligence - existing hydrant booster                        | Non-compliance of existing hydrant booster information to be issued for  | 7/23/2024                   | Fire - ACOR                      | Burt de Keyzer (BdK)              | SINSW AMU                        | 7/26/2024                        | Com                        |
|   | AMU action.  |                             | Chrysterral Mainten 1            |                                   | SINGW ID Toopt                   |                                  | 0                          |
| 9 Due Diligence - arborist tree root mapping                      | * Tree root mapping required, western and southern boundary of the<br>construction zone, to support structural system for new building | //23/2024                   | Structural - Meinhardt           |                                   | SINSW IP Team                    | 8/8/2024                         | Open/To be                 |
|   | construction zone, to support structural system for new building   |                             |                                  |                                   |                                  |                                  |                            |
| 10 Cost Plan  |  | 7/23/2024                   | Cost Manager - Arcadis           | Vincent Caspe (VC)                | Cost Manager - Arcadis           | 8/30/2024                        | In progress                |
|   | * Allowance for suspended slab to be advised following arborist tree root  |                             | Sector Sector Sector             |                                   |                                  |                                  | 1.28.000                   |
| 11 Cost Plan  | mapping completed * Current allowance scope 4 GLS over 2 levels  | 7/22/2024                   | Cost Manager - Arcadis           | Vincent Caspe (VC)                | Other                            | 8/30/2024                        | In progress                |
|   | * No new major upgrade to existing services included: return advice to be  |                             | Cost Hanager - Areadis           | Vincent baspe (VO)                |                                  | 0/00/2024                        | in progress                |
|   | provided following inspections and design development  |                             |                                  |                                   |                                  |                                  |                            |
|   |  |                             |                                  |                                   |                                  |                                  |                            |
| 12 Off Site Scope (infrastructure)                                | * Review RTA for scope for costing \$250k allowance  |                             | Cost Manager - Arcadis           | Vincent Caspe (VC)                | SINSW IP Team<br>Architect - FTA | 8/8/2024<br><del>7/31/2024</del> | In progress                |
| 13 Design Documentation           14 Waste Management information | Remove reference to demountables as they are no longer on site-<br>Planner to advise on requirements                                   |                             | Town Planner<br>Project Manager  | Lauren Daley (LD)<br>Matt Spooner | Town Planner                     | 8/8/2024                         | In progress<br>In progress |
| 15 Acoustic advice requirements                                   | Statutory planning requirements  |                             | Town Planner                     | Debra Barr (DB)                   | Electrical - NDY                 | 8/7/2024                         | In progress                |
| 16 Building services maintenance                                  | Clearance requirements   | 7/23/2024                   | Fire - ACOR                      | Burt de Keyzer (BdK)              | SINSW AMU                        | 8/7/2024                         | In progress                |
| 17 As-built drawings  | Buildings E and F - hydraulics are not currently available:  | 7/23/2024                   | Fire - ACOR                      | Burt de Keyzer (BdK)              | SINSW IP Team                    | 8/22/2024                        | In progress                |
|   | * Check directly with the school<br>* Town Planner GIPA request  |                             |                                  |                                   |                                  |                                  |                            |
|   | * SINSW to check with Public Works   |                             |                                  |                                   |                                  |                                  |                            |
| 18 Design   | Existing Building E ventilation to western edge to be considered - mould   | 7/23/2024                   | Project Manager                  | Matt Spooner                      | Mechanical - NDY                 | 8/30/2024                        | Clos                       |
|   | noted in the underfloor area.  |                             |                                  |                                   |                                  |                                  |                            |
| 19 Design   | Option 1 stair to the left + remove central shared stair   | 8/5/2024                    | SINSW IP Team                    | Ant Courtman                      | BCA/DDA                          | 8/7/2024                         | Clos                       |
|   | Option 3 central stair extended and extended; external access for each GLS; internal access to PAA from each GLS                       |                             |                                  |                                   |                                  |                                  |                            |
|   | * Travel distances to be reviewed by BCA for each option - closed all  |                             |                                  |                                   |                                  |                                  |                            |
|   | compliant  |                             |                                  |                                   |                                  |                                  |                            |
| 20 PCG  | Options 1 + 3 as updated ( 5/08/2024) to be reviewed by DEL / School   | 8/7/2024                    | Architect - FTA                  |                                   | SINSW IP Team                    | 8/16/2024                        | Com                        |
|   | with m2 removed from plans   |                             |                                  |                                   |                                  |                                  |                            |
|   |  |                             |                                  |                                   |                                  |                                  |                            |
|   |  |                             |                                  |                                   |                                  |                                  |                            |
|   |  | +                           |                                  |                                   | +                                |                                  |                            |
| 21 Due Diligence  | Existing Toilet Pan count is under the requirement specified in the EFSG   | 8/7/2024                    | Architect - FTA                  | Niloo K                           | Architect - FTA                  | 8/29/2024                        | Com                        |
| 22 Capital works  |  | 16/08/2024                  | Project Manager                  | Jeanette Carney                   | SINSW AMU                        | 23/08/2024                       | Clos                       |
| 22 Latest look  | Query upcoming/planned capital works by AMU/school for consideration.  | 10/00/0001                  | Designation                      | Matthews                          | CINCM/ID Toom                    | #VALUE!                          | Onon /Tak                  |
| 23 Latest look<br>24 Annual Fire Saftey Statement                 | Photos of latest teaching spaces to show the PRG Please provide a valid ASFF for 2024  | 16/08/2024<br>10/9/2024     | Project Manager<br>Fire - ACOR   | Matthew Spooner                   | SINSW IP Team<br>SINSW AMU       | #VALUE!<br>9/24/2024             | Open/To be<br>Com          |
| Press tab in the last cell of Column J to create a new l          |  | 10/0/2024                   |                                  |                                   | 1 <u></u>                        |                                  |                            |
| 26 Heritage and Planning pathway                                  | The direction from SINSW Stat Planning is to pursue a REF pathway  | 9/18/2024                   | SINSW Statutory Planning         |                                   |                                  |                                  |                            |
| 27 Existing Electrical Conduits                                   | It's proposed that the cabling to the new building runs within existing  | 22/10/2024                  | Electrical - NDY                 | Beau Carner                       | Project Manager                  | 11/1/2024                        | Open/To be                 |
|   | communications and power conduits behind Block C.<br>We need confirmation that these conduits have sufficient spare capacity           |                             |                                  |                                   |                                  |                                  |                            |
|   | to accommodate new cables.   |                             |                                  |                                   |                                  |                                  |                            |
| 28 Emergency Power Requirement                                    |  | 22/10/24                    | Electrical - NDY                 | Peter Santamaria                  | SINSW AMU                        |                                  | Clos                       |
| 0 .,  | EFSG "0001c Design Checklist - Electrical Services" indicates emergency  |                             |                                  |                                   |                                  |                                  |                            |
|   | power supply requirements for schools that "are at risk of power loss due  |                             |                                  |                                   |                                  |                                  |                            |
|   | to bushfire, flood, adverse weather events and schools identified as a   |                             |                                  |                                   |                                  |                                  |                            |
|   | community evacuation facility (CEF)". Could you please indicate whether  |                             |                                  |                                   |                                  |                                  |                            |
|   | the school meets any of the criteria listed above and hence whether the  |                             |                                  |                                   |                                  |                                  |                            |
|   | emergency power supply requirements are to be included.  |                             |                                  |                                   |                                  |                                  |                            |

| status         | Comments   |
|----------------|--|
| omplete        | Meeting with EFSG (DAIS) for feedback 5/08/2024.<br>* Preference for independent access from corridor for each GLS-                          |
|                | * Plus access from PAA to each GLS   |
| ess/Assigned   | Refer to Design Tracker  |
| coo/Acolgiicu  |  |
|                |  |
|                |  |
| ess/Assigned   |  |
| Closed         | Refer to Design Tracker  |
|                |  |
|                |  |
|                |  |
|                |  |
|                |  |
| Closed         | Gap analysis required  |
|                | Refer to design Tracker  |
|                |  |
| Closed         | All comments received. Update Survey plan issued with services inform  |
|                | DCA advised that new building is an ladd and to evicting Duilding Floors   |
| omplete        | BCA advised that new building is an "add on" to existing Building E as a<br>United Building, no new compliant access is required to be built |
|                | onited partning, no new compliant access is required to be built   |
| omplete        | Issued via email to SI 26/07/2024  |
| mprete         |  |
| be assigned    | Arborist site inspection 15.08.24.   |
| 20 ababalou    | Meeting with Arborist 26.08.24 identified trees TPZ impacted, Building   |
|                | location to be reviewed by SINSW/Project team  |
| acc/Accidenced |  |
| ess/Assigned   |  |
|                |  |
| ess/Assigned   | All services consultants   |
|                |  |
|                |  |
|                |  |
| ess/Assigned   |  |
| ess/Assigned   | Refer to Design Register   |
| ess/Assigned   |  |
| ess/Assigned   |  |
| ess/Assigned   | 15.08.24: SINSW to seek further information from Public Works  |
| ess/Assigned   | Planner awaiting Council response to GIPA  |
|                | 26.08.24: Design team responded with comments for surveyor scope   |
|                |  |
| Closed         | 7/08/2024 RPI issued Photos to SINSW Delivery for issuing to AMU for   |
|                | existing issue. (copy issued to NDY).  |
| Closed         | 6/08/2024 BCA endorsed travel distances for both Options 1 + 3   |
|                | 7/08/2024 Naming convention for options - maintain Options 1 + 2   |
|                | Refer to Design Register   |
|                |  |
|                |  |
| omplete        | 7/08/2024 PCG Endorsed Option 1  |
|                | * external corridor space maximised for inpromtu learning space  |
|                | * PAA space to include multi-purpose/withdrawal space if possible<br>* Scope and budget alignment required with priority to maximise         |
|                | teaching space spend   |
|                | 0  |
|                | SINSW issued out information on Pan Count. FT to reference this  |
| omplete        | document when finalising the Masterplan Validation Report  |
| Closed         | Project now delivered by the AMU team.   |
| bo assigned    |  |
| be assigned    |  |
| mprete         |  |
|                |  |
| be assigned    | Scope request / drawing to NDY 25/10/2024  |
| 20000010U      |  |
|                |  |
|                |  |
| Closed         | RFI to SI AMU 28/10/2024   |
|                | EFSG confirmed school doesn'y need emergency power   |
|                | ,  |
|                |  |
|                |  |
|                |  |
|                |  |
|                | 1  |

# Appendix 7 SAFETY IN DESIGN REGISTER

|                 | Name: Cammeray Public School<br>n Design Risk Assessment |   |   |  |              |                        |             |                      | Developed & Assessed By:<br>Reviewed & Approved By:  |            |                      | n             | Project Commence<br>Project Commence | ement - Project & D<br>ement - HCA/Desio | Design Team<br>Iners/HKA |  |             |                            |         |          |
|-----------------|--|---|---|--|--------------|------------------------|-------------|----------------------|--|------------|----------------------|---------------|--------------------------------------|--|--------------------------|--|-------------|----------------------------|---------|----------|
| Surcity         |  | HAZARD & HARM IDENTI<br>HAZARD  | IFICATION<br>RISK   | ENTITY AFFECTED                            | INITIAL A    | NALYSIS<br>CONSEQUENCE | RISK RATING | HIERARCHY OF CONTROL | CONTROLS<br>ACTION FOR MITIGATION  | LIKELIHOOD | INITIAL ANALYSIS - 1 | RESIDUAL RISK |                                      | CONSEQUENCE                              |                          | ACTIONS REQUIRED   | BY WHOM     | RESPONSIBILITY<br>DATE DUE | REMARKS | STATUS   |
| SITE HAZ        | ARDS<br>Hazardous Materials                              | Asbestos has been identified in   | If disrupted causes a hazard  | Staff / Students / Construction            |              |                        |             | HIERARCHY OF CONTROL | Contractors to review soils in areas   |            |                      |               |                                      | Concequence                              |                          | Existing hazardous materials   | RPL/SINSW   | 15.02.25                   |         |          |
|                 |  | ground elsewhere on the site.   | those in the surrounding area.  | Workers                                    | Possible     | Major                  | HM-8        |                      | that are being disrupted as part of the works.   | Possible   | Moderate             | M-13          |                                      |  |                          | register to be provided to<br>contractors.                                     |             |                            |         |          |
|                 | ION OF EXISTING  | Deconstruction and removal off  | Potential injury to others in the   | Staff / Students / Construction            |              |                        |             |                      | Demountable Contractors to   |            |                      |               |                                      |  |                          | Confirm timing for   | RPI / SINSW | 01.06.25                   |         |          |
| 0.01            | Removal of Existing Demountables                         | site of Existing Demountables<br>from site.   | proximity of the demountables<br>while being relocated or to                              | Workers                                    |              |                        |             |                      | provide safe work methodology  |            |                      |               |                                      |  |                          | demountable removal  | KI 17 30399 | 01.08.23                   |         |          |
|                 |  |   | construction workers due to<br>restricted access to                                       |  | Very Likely  | Major                  | H-7         |                      |  | Possible   | Moderate             | M-13          |                                      |  |                          |  |             |                            |         |          |
| D.02            | Demolition of Existing Elements of<br>Building E         | Demolition of existing stairs and   | demountables.<br>Damage to the existing building  | Staff / Students / Construction<br>Workers |              |                        |             |                      | Work to be undertaken when<br>Building E is vacated.   |            |                      |               |                                      |  |                          | Contractor to consider in<br>construction management                           | RPI / SINSW | 01.06.25                   |         | -        |
|                 | boliang e  | eaves overhang to Existing<br>Building E  | and potential injury of students<br>and staff in proximity.                               | workers                                    | Possible     | Severe                 | H-3         |                      | Consideration to be given to<br>completing the work outside of   | Possible   | Moderate             | M-13          |                                      |  |                          | plan.  |             |                            |         |          |
|                 |  |   |   |  |              |                        |             |                      | school hours. Contractors to<br>provide safe work methodology  |            |                      |               |                                      |  |                          |  |             |                            |         |          |
| D.03            | Demolition of Existing Trees                             | Demolition of Existing Trees to<br>Miller Street Frontage                                     | Potential injury of students and<br>staff in proximity.                                   | Staff / Students / Construction<br>Workers |              |                        |             |                      | Contractors to provide safe work<br>methodology. Consideration to be   |            |                      |               |                                      |  |                          | Contractor to consider in<br>construction management                           | RPI / SINSW | 01.06.25                   |         |          |
|                 |  |   |   |  | Possible     | Severe                 | H-3         |                      | given to completing the work<br>outside of school hours.<br>Contractors to provide safe work                 | Possible   | Moderate             | M-13          |                                      |  |                          | plan.  |             |                            |         |          |
|                 |  |   |   |  |              |                        |             |                      | methodology  |            |                      |               |                                      |  |                          |  |             |                            |         |          |
| CONSTRU<br>C.01 | ICTION<br>Traffic and Pedestrian Management              | Works outside builder's   | Student and Staff safety  | Students and Staff                         |              |                        |             |                      | Out of hours works.  |            |                      | _             |                                      |  |                          | Confirm requriement for  | RPI         | 17.01.25                   |         |          |
|                 |  | compound.   | encountering works within Schoo<br>grounds outside builder's<br>compound. Eg Site Service |  | Very Likely  | Major                  | H-7         |                      |  | Unlikely   | Moderate             | L-14          |                                      |  |                          | construction management<br>plan from D&C contractor                            |             |                            |         |          |
|                 |  |   | upgrades.   |  |              |                        |             |                      |  | -          |                      |               |                                      |  |                          |  |             |                            |         |          |
| C.02            | Traffic and Pedestrian Management                        | Before and After School access<br>during construction   | before and after School care as   | r Staff/ Students/ Parents                 |              |                        |             |                      | Contractor to establish safe<br>working practices as part of   |            |                      |               |                                      |  |                          | Confirm requriement for<br>construction management                             | RPI         | 17.01.25                   |         | 1        |
|                 |  |   | well as vacation care. New path/route to be considered.                                   |  | Very Likely  | Major                  | H-7         |                      | construction management plan.  | Unlikely   | Moderate             | L-14          |                                      |  |                          | plan from D&C contractor   |             |                            |         |          |
| C.03            | Traffic Routes and Control                               | Construction access off Miller  | Construction access from Miller<br>Street creates potential clashes                       | Pedestrians / Staff / Students             |              |                        |             |                      | Contractors to impliment<br>appropriate fencing and traffic  |            |                      |               |                                      |  |                          | Confirm requriement for<br>construction management                             | RPI         | 17.01.25                   |         | -        |
|                 |  |   | with vehicles and pedestrians.<br>Also need to manage                                     |  | Very Likely  | Major                  | H-7         |                      | control measures.  | Unlikely   | Moderate             | L-14          |                                      |  |                          | plan from D&C contractor   |             |                            |         |          |
|                 |  |   | emergency vehicle access<br>through the construction site.                                |  |              |                        |             |                      |  |            |                      |               |                                      |  |                          |  |             |                            |         | <u> </u> |
| C.04            | Adjoining Areas - Block E                                | New work is located close to<br>exsiting Block E. Structure to be                             | Collapse of existing structure  | Staff / Students / Construction<br>Workers |              |                        |             |                      | Structural engineers to review<br>footing and temporary shoring  |            |                      |               |                                      |  |                          | Structural engineers to<br>review footing and                                  | RPI         | 01.06.25                   |         |          |
|                 |  | reviewed to ensure it doesn't<br>impact on existing structures.                               |   |  |              |                        |             |                      | requirements prior to construction.<br>Contractor to provide appropriate<br>dust control measures during the |            |                      |               |                                      |  |                          | temporary shoring<br>requirements  |             |                            |         |          |
|                 |  |   |   |  | Possible     | Major                  | HM-8        |                      | construction phase. Building E<br>classrooms to be vacated during  | Unlikely   | Moderate             | L-14          |                                      |  |                          |  |             |                            |         |          |
|                 |  |   |   |  |              |                        |             |                      | the construction period - if possible.   |            |                      |               |                                      |  |                          |  |             |                            |         |          |
| C.05            | Adjoining Areas  | New work adjacent to existing<br>trees - Tree Protection Zones to be                          | Damage to existing trees leading  | Staff / Students / Construction<br>Workers |              |                        |             |                      | Contractor to review impact on TPZ<br>- including impact of scaffolding.                                     |            |                      |               |                                      |  |                          | Confirm requriement for TPZ<br>from D&C contractor. Refer                      | RPI         | 15.02.25                   |         | -        |
|                 |  | maintained during construction.   | e lo colidpse   | workers                                    | Possible     | Major                  | HM-8        |                      | - including impact of scattolding.   | Unlikely   | Moderate             | L-14          |                                      |  |                          | to the mitigation measures<br>highlighted in the REF                           |             |                            |         |          |
| C.06            | Noise Impact   | Construction noise could impact   | Impact on classroom   | Staff / Students / Neighbouring            |              |                        |             |                      | Noise impacts to be considered in  |            |                      |               |                                      |  |                          | package.<br>Confirm requriement for  | RPI         | 01.06.25                   |         |          |
|                 |  | on neighbouring residential<br>properties as well as classrooms.                              | functionality or hearing of<br>students and staff   | properties                                 | Possible     | Moderate               | M-13        |                      | Construction Management plan.<br>Consider removing classes from  | Unlikely   | Moderate             | L-14          |                                      |  |                          | Noise management from<br>D&C contractor  |             |                            |         |          |
|                 |  |   |   |  |              |                        |             |                      | Building E (and potentially F) during the construction preriod.  |            |                      |               |                                      |  |                          |  |             |                            |         |          |
| C.07            | Trenching  | Trenching works will be required<br>through school areas - outside of                         | Risk of saff / students or public<br>falling into open trenches                           | Staff / Students / Public                  | Very Likely  | Major                  | H-7         |                      | Construction Management Plan to<br>be prepared to allow for trenching  | Unlikely   | Moderate             | L-14          |                                      |  |                          | Confirm requriement for<br>construction management                             | RPI         | 17.01.25                   |         |          |
|                 |  | the construction zone.  |   |  | Very Likely  | Major                  | n-7         |                      | to be completed outside of school hours.   | Unlikely   | Moderdie             | L-14          |                                      |  |                          | plan from D&C contractor   |             |                            |         |          |
| C.08            | Electrical Shutdown                                      | Changeover of Electrical<br>Substation / Power Supply could<br>impact on operations of School |   | Staff / Students                           |              |                        |             |                      | Construction Management Plan to<br>be prepared to allow for electrical<br>shutdown to be completed outside   |            |                      |               |                                      |  |                          | Confirm requriement for<br>construction management<br>plan from D&C contractor | RPI         | 17.01.25                   |         |          |
|                 |  | impact on operations of school  |   |  | Very Likely  | Moderate               | M-12        |                      | of school hours and that<br>appropriate notice is provided to  | Unlikely   | Moderate             | L-14          |                                      |  |                          | partion bac contactor  |             |                            |         |          |
| C.09            | Working at Heights                                       | WAP replacement in existing   | Risk of falling during operation  | Contractors                                |              |                        |             |                      | the school.<br>Contractor to establish safe  |            |                      |               |                                      |  |                          | Confirm requriement for  | RPI         | 17.01.25                   |         |          |
|                 |  | areas will need to be completed<br>on high ceilings   |   |  | Possible     | Major                  | HM-8        |                      | working practices as part of<br>construction management plan.  | Possible   | Minor                | L-18          |                                      |  |                          | construction management<br>plan from D&C contractor                            |             |                            |         |          |
| C.10            | Emergency Egress During Construction                     | Emergency Egress Paths to be<br>Reviewed in Building E during                                 | Risk of restrictions to students and staff being able to evacuate                         | Staff / Students                           | Vandlinte    | Sauce                  |             |                      | Contractor to establish temporary<br>egress paths for the construction                                       | Deschola   | Minar                | 1.10          |                                      |  |                          | Confirm requriement for<br>construction management                             | RPI         | 17.01.25                   |         | 1        |
|                 |  | Construction - following removal<br>of existing stair.  | building  |  | Very Likely  | Severe                 | H-2         |                      | period.  | Possible   | Minor                | L-18          |                                      |  |                          | plan from D&C contractor   | 221         | 15 00 05                   |         | _        |
| C.11            | Adjoining Areas - Retaining Wall                         | New work is located close to the<br>existing retaining wall to the<br>South                   | Collapse of existing structure and trees  | Staff / Students / Construction<br>Workers |              |                        |             |                      | Contractor to review the footings to<br>the retaining wall on site. Any<br>demolition in the area to be      |            |                      |               |                                      |  |                          | Confirm requriement for<br>construction management<br>plan from D&C contractor | KPI         | 15.02.25                   |         |          |
|                 |  |   |   |  | Possible     | Major                  | HM-8        |                      | undertaken carefully and reviewed<br>with a structural engineer prior to                                     | Unlikely   | Moderate             | L-14          |                                      |  |                          | plan ion pac confideror  |             |                            |         |          |
|                 |  |   |   |  |              |                        |             |                      | commencing.  |            |                      |               |                                      |  |                          |  |             |                            |         | <u></u>  |
|                 | PURPOSE (FOR WHICH IT IS DESIGNED)<br>Finger Entrapment  | Finger Entrapment   | Finger entrapment in sliding doors  | s Students                                 | Very Likely  | Moderate               | M-12        |                      | Ensure operation of sliding doors<br>doesn't create entrapment zones at                                      | Unlikely   | Minor                | L-19          |                                      |  |                          | Details of sliding doors to be<br>reviewed in greater detail at                | Architect   | 01.06.25                   |         |          |
|                 |  |   |   |  | - GIY LINCIY | moundle                |             |                      | handles or framing.  | Grinkely   |                      |               |                                      |  |                          | DD phase   |             |                            |         | <u> </u> |
|                 | MANAGEMENT AND OPERATIONS - OPER<br>Out of Bounds Areas  | The location of the new building  | Could pose a risk to child safety   | Students                                   |              |                        |             |                      | School to develop new out of   |            |                      |               |                                      |  |                          | School to update out of  | SINSW       | 01.06.26                   |         |          |
|                 |  | creates new areas of low visibility<br>to the rear of the building.                           | ()  |  | Possible     | Moderate               | M-13        |                      | bounds policies to suit the new<br>building.   | Unlikely   | Moderate             | L-14          |                                      |  |                          | bounds and play time policy  |             |                            |         |          |
| F.02            | Maintenance at Heights                                   | Risk of falling while servicing the<br>Solar Panels on the roof                               | Falling from roof   | Staff / Contractors                        | Devili       |                        |             |                      | Supply Safe Roof Access system<br>along with a management plan   | 11-17      |                      |               |                                      |  |                          | Details of Safe Roof Access<br>system to be confirmed with                     | Contractor  | 01.06.26                   |         | 1        |
|                 |  |   |   |  | Possible     | Major                  | HM-8        |                      | with appropriate connection points<br>around PV cells  | Unlikely   | Moderate             | L-14          |                                      |  |                          | contractor during DD phase   |             |                            |         | <u> </u> |
| F.03            | Maintenance at Heights                                   | Maintenance requried for leaf<br>fall affecting the gutters                                   | Falling from roof while servicing gutters   | Staff / Contractors                        | Dowihi -     | Major                  |             |                      | Supply gutter guard to keep leaves<br>out of gutters and downpipes. A  | Indian .   | Medarat              |               |                                      |  |                          | Confirm requirements for<br>contractor in<br>documentation                     | FTA         | 17.01.25                   |         |          |
|                 |  |   |   |  | Possible     | Major                  | HM-8        |                      | safe roof access system should also<br>be provided to allow access to the<br>autters                         | Unlikely   | Moderate             | L-14          |                                      |  |                          | documentation  |             |                            |         |          |
| F.04            | Maintenance of Drainage Pits                             | Maintenance requried for leaf<br>fall affecting draingage pits                                | Leaf fall blocking drainige pits<br>causing overflow water                                | Staff / Contractors                        |              |                        |             |                      | Pit baskets or liners to be provided within drains in the area under the                                     |            |                      |               |                                      |  |                          | Confirm requirements for<br>contractor in                                      | FTA         | 17.01.25                   |         | 1        |
|                 |  |   |   |  | Possible     | Moderate               | M-13        |                      | trees. A maintenance regime<br>should be developed to keep the   | Unlikely   | Minor                | L-19          |                                      |  |                          | documentation  |             |                            |         |          |
|                 |  |   |   |  |              |                        |             |                      | drains cleared.  |            |                      |               |                                      |  |                          |  |             |                            |         | <u> </u> |
| DECOMA          | AISSIONING (END OF LIFE)                                 |   |   |  |              |                        |             |                      |  |            |                      |               |                                      |  |                          |  |             |                            |         |          |
|                 |  |   |   |  |              |                        |             |                      |  |            |                      |               |                                      |  |                          |  |             |                            |         |          |

Appendix 8
DESIGN COMMENTS TRACKER

Design Comments Tracker - Consultants are to ensure comments captured are addressed in future design submissions/packages. - Consultants to status their progress in the relevant column to confirm they have addressed the item. The Item Status is to remain open until the item has been presented to the relevant stakeholders for review and closeout. The overall status will be confirmed by RPI/FT/SINSW.

## Cammeray Public School

| ltem | Team  | Date Raised | Phase   |   | Subject              | ltem   | Actions  | Action<br>Required By                 | Date Due  | Item Status<br>DO NOT ADJUST.<br>FT/RPI TO AMEND<br>FOLLOWING MEETING<br>REVIEWS | Consultant's recommended status | Further Actions/Upda<br>If the item is closed, thi<br>how it was closed and |
|------|-------|-------------|---------|---|----------------------|--|--|---------------------------------------|-----------|--|---------------------------------|---|
| 1    | DTM   | 7-Aug-24    | Phase 2 | Amenities<br>Requirement                    | Existing             | Existing Amenities count and gap study to be done  | Toilet count of the existing amenities on site to be confirmed in<br>need to be done<br>SI to validate the counts based on AMU references (Due Date:<br>14/08/2024)  | Architect - FTA                       | 14-Aug-24 |  |                                 | SI and RP to provide fu   |
| 3    | DTM   | 7-Aug-24    | Phase 2 | General/<br>Architectural                   | Naming               | Options naming convention to be considered for more clarity -<br>Option 1&3 to be updated to 1&2 for further reviews   | Updating the options to new naming order (Due Date: 08/08/2024)  | Architect - FTA                       | 8-Aug-24  | Complete   | Complete                        | Updates captured  |
| 4    | DTM   | 7-Aug-24    | Phase 2 | General/<br>Architectural                   | Survey               | Existing Site plan including all existing items based on Survey  | To be issued to services<br>(Due Date: 09/08/2024)   | Architect - FTA                       | 9-Aug-24  | Complete   | Complete                        | Site plan is issued as a  |
| 5    | DTM   | 7-Aug-24    | Phase 2 | Survey Issue                                | Survey               | Demountables to be removed from survey file  | Updated DWG to be provided for teams   | SINSW IP Team                         | 9-Aug-24  | Complete   | Complete                        | Updated survey is on sl   |
| 6    | DTM   | 7-Aug-24    | Phase 2 | General/<br>Architectural                   | Layout               | Option 1 to be reviewed for stairs and lift layout for possibility of<br>having an external PAA as directed on PCG   | (Due Date: 09/08/2024)<br>Architecture to work on the layout<br>(Due Date: 09/08/2024)   | Architect - FTA                       | 9-Aug-24  | Hold / Deferred  |                                 | To be developed as a p  |
| 7    | DTM   | 7-Aug-24    | Phase 2 | Planning Issue                              | Cost Plan            | Existing cost plan is for 72sqm PAA for both levels  | Next Key action is to revalidating cost plans and considering<br>where can be found more fund incorporating to have bigger<br>PAA (Due Date: 12/08/2024)   | SINSW IP Team                         | 12-Aug-24 |  |                                 |   |
| 8    | DTM   | 7-Aug-24    | Phase 2 | Arborist Issue                              | Arborist             | Arborist to confirm tree strategies on areas of TPZ clashing to the building footprint   | SI to manage and organise a meeting with Arborist<br>(Due Date: 09/08/2024)  | SINSW IP Team                         | 9-Aug-24  | Complete   | In progress/Assigned            | SI organised meeting w<br>provided and coordinati<br>process                |
| 9    | DTM   | 7-Aug-24    | Phase 2 | Project Admin/<br>Master plan<br>Validation | Due diligence        | Requesting for information from other disciplines / Reporting of<br>Due Diligence for Master plan Validation.  | Requesting for information from other disciplines<br>Consultant team to provide initial recommendations and risks<br>from due diligence for inclusion in Maser Plan Validation report<br>by Thursday 8th August (Due Date: 08/08/2024) | All                                   | 8-Aug-24  | Complete   | Complete                        |   |
| 10   | DTM   | 7-Aug-24    | Phase 2 | Electrical / ICT                            | Electrical           | Allocation to IT budget & ICT upgrade  | Confirm budget support for upgrade (Due Date: 12/08/2024)  | SINSW IP Team                         | 5-Sep-24  | Complete   |                                 | Allow for no upgrades t<br>for the new building onl                         |
| 11   | DTM   | 7-Aug-24    | Phase 2 | Electrical / ICT                            | Electrical           | Existing IT structure to be reviewed and investigated for option   |  | Electrical - NDY                      | 8-Aug-24  | Complete   |                                 |   |
| 12   | DTM   | 7-Aug-24    | Phase 2 | Electrical / ICT                            | Electrical           | of upgrades<br>Existing electrical doesn't have the capacity for the expansion ,   | (Due Date: 08/08/2024)<br>Separated system needs to run for the new scope  | Electrical - NDY                      | -         | Complete   |                                 | Substation upgrade ma   |
|      |       |             |         |   |                      |  | (Due Date: TBC)  |                                       |           |  |                                 | capacity requirements r<br>MSB to be upgraded.                              |
|      |       |             |         |   |                      |  |  |                                       | TBC       |  |                                 | NDY to consult with Arc   |
| 13   | DTM   | 07-Aug-24   | Phase 2 | Mechanical                                  | Mechanical           | Air conditioning and Mechanical system   | Separated system needs to run for the new scope<br>(Due Date: TBC)   | Mechanical -<br>NDY                   | ТВС       | Closed   |                                 | Mechanical confirmed i<br>addressed in the design                           |
| 14   | DTM   | 7-Aug-24    | Phase 2 | Civil Issue                                 | Civil                | Existing drainage channel is an issue  | Further Investigation and solutions to be provided<br>(Due Date: 08/08/2024)   | Civil - Meinhardt                     |           | Complete   |                                 | Outside of scope of this  |
|      | 0.744 | 7.4 0/      |         |   |                      |  |  | <b>D</b> : (M                         | 8-Aug-24  |  |                                 | Meinhardt to detail issu  |
| 15   | DTM   | 7-Aug-24    | Phase 2 | Hydraulic                                   | Hydraulic            | As built document of the school for the existing capacity of the services  | Following up from SI to get more information<br>SI to get back and confirm all in ground pipe works and sizes<br>(Due Date: 09/08/2024)  | Project Manager<br>/ SINSW IP<br>Team | 9-Aug-24  | Complete   |                                 | Pipe sizes shown on su  |
| 16   | DTM   | 23-Jul-24   | Phase 2 | General/<br>Architectural                   | Layout               | Master Plan options presented 1, 2 + 3 & feedback  | Update and meet with DAIS for feedback + cost plan areas<br>comparisons + review by School   | Project Manager<br>/ SINSW IP<br>Team | 12-Aug-24 | Complete   | Complete                        | Updates captured  |
| 17   | DAIS  | 05-Aug-24   | Phase 2 | General/<br>Architectural                   | Layout               | Master Plan options<br>* Preference for independent access from corridor for each<br>GLS<br>* Plus access from PAA to each GLS<br>* Options for School remove m2         | Options prepared for PCG 7/08/2024   | SINSW IP Team                         | 7-Aug-24  | Complete   | Complete                        | Updates captured  |
| 18   | DTM   | 23-Jul-24   | Phase 2 | General/<br>Architectural                   | BCA                  | New building options:<br>* connect to existing levels of Building E + stair modifications<br>* move stair closer to western boundary to improved<br>access/egress to GLS | Update options - completed 7/08/2024   | Architect - FTA                       | 7-Aug-24  | Complete   | Complete                        | Updates captured  |
| 19   | PCG   | 07-Aug-24   | Phase 2 | General/<br>Architectural                   | Layout               | Option 1 endorsed:<br>* external corridor space maximised for impromptu learning<br>space<br>* PAA space to include multi-purpose/withdrawal space if<br>possible        | Review Option 1 for PRG meeting 12/08/2024   | Architect - FTA                       | 12-Aug-24 | Complete   | Complete                        | Reviewed on PRG and<br>Captured on master pla                               |
| 20   | DTM   | 14-Aug-24   | Phase 2 | DTS   | Meeting Time         | Meeting time to be extended to 1.5 hour  | RP to manage and updating the invite   | Project Manager                       | 21-Aug-24 | Complete   | Complete                        | RP actioned.  |
| 21   | DTM   | 14-Aug-24   | Phase 2 | Masterplan<br>validation                    | Amenities            | Amenities study should be done as a part of this masterplan<br>validation  | SI and RP to investigate for further details on that to be<br>provided   | Project Manager                       | 15-Aug-24 | Complete   | Complete                        | Added based on provid   |
| 22   | DTM   | 14-Aug-24   | Phase 2 | Masterplan<br>validation                    | BCA/DDA              | Copliant accessible path   | As it's an extention of the building E and we only required<br>compliant access to the building and conncetion to the existing.<br>It's not mandatory to do any upgrade to the school pathway.   | Architect - FTA                       | 16-Aug-24 | Complete   | Complete                        | Updated on Masterplan   |
| 23   | DTM   | 14-Aug-24   | Phase 2 | Masterplan<br>validation                    | Risk Section         | To be reviewed and updated   | Having analysis and register both are confusing<br>Register to be aligned with SI format - RP to investigate further<br>required update  | Project Manager                       | 15-Aug-24 | Complete   | Complete                        | Updated on Masterplan   |
| 24   | DTM   | 14-Aug-24   | Phase 2 | Masterplan validation                       | Airquality and noise | Updating to notes  | Air quality and noise and other details noted to be undertaken<br>and will be reviewed as a part of concept design.  | Architect - FTA                       | 16-Aug-24 | Complete   | Complete                        | Updated on Masterplan   |
| 25   | DTM   | 14-Aug-24   | Phase 2 | Masterplan<br>validation                    | Design issues        | Updating to notes  | Rewording of the design issues to mentioning the building<br>design incorporate them as moving forward   | Architect - FTA                       | 16-Aug-24 | Complete   | Complete                        | Updated on Masterplan   |
| 26   | DTM   | 14-Aug-24   | Phase 2 | Masterplan<br>validation                    | Arborist             | Updating to notes  | Arborist doing site visite<br>Furthur arborist advise will be able to be included to the report.<br>Rewording that tree relative design issue to indicates intention<br>of retention.  | Architect - FTA                       | 16-Aug-24 | Complete   | Complete                        | Updated on Masterplan   |

| s/Updates/Comments.<br>sed, this section is to include a reference on<br>ed and drawing/report reference. | Date Closed<br>DO NOT AMEND.<br>FT/RPI TO<br>AMEND<br>FOLLOWING<br>MEETING | Consultant's comments |
|---|--|-----------------------|
| ovide further details from GA   |  |                       |
| ed  |  |                       |
| ed as a part of masterplan  |  |                       |
| is on share point   |  |                       |
| d as a part of concept  |  |                       |
|   |  |                       |
|   |  |                       |
| eeting with Arborist , further information being<br>ordination will be occured on the the design          |  |                       |
|   |  |                       |
| grades to existing infrasture - just providing ICT ding only.   |  |                       |
|   |  |                       |
| ade may be required, but exception from spare ments may be possible with SINSW.                           |  |                       |
| aded.   |  |                       |
| with Arcadis to review cost plan allowances.  |  |                       |
| firmed it's same strategy as existings and will be<br>e design development                                |  |                       |
| e of this project.  |  |                       |
| tail issue to SINSW to be raised with the school  |  |                       |
| vn on survey  |  |                       |
| ed  |  |                       |
| ed  |  |                       |
| ed  |  |                       |
| RG and endoresed<br>aster plan validation   |  |                       |
|   |  |                       |
| n provided information.   |  |                       |
| sterplan report   |  |                       |
|   |  |                       |
|   |  |                       |

| Item | Team | Date Raised | Phase     |                           | Subject                  | ltem   | Actions   |                       |           | Item Status<br>DO NOT ADJUST.                   | Consultant's recommended status | Further Actions/Updates/Comments.   | Date Closed                                | Consultant's comments |
|------|------|-------------|-----------|---------------------------|--------------------------|--|---|-----------------------|-----------|---|---------------------------------|---|--|-----------------------|
|      |      |             |           |                           |                          |  |   | Action<br>Required By | Date Due  | FT/RPI TO AMEND<br>FOLLOWING MEETING<br>REVIEWS | Sidido                          | how it was closed and drawing/report reference.   | FT/RPI TO<br>AMEND<br>FOLLOWING<br>MEETING |                       |
| 27   | DTM  | 14-Aug-24   | Phase 2   | Masterplan<br>validation  | Vehicle access           | Updating to notes  | Vehicle access is the ambulance access to the site and adding<br>the note in terms of emergency access to be provided on<br>construction phase - Access during construction | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 28   | DTM  | 14-Aug-24   | Phase 2   | Masterplan<br>validation  | Vehicle access           | Updating to notes  | Any stuff about services issues that impacting the cost to be<br>raised as a part issues for any further consideration Rebuilding<br>the booster with additional pump       | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 29   | DTM  | 14-Aug-24   | Phase 2   | Masterplan<br>validation  | Checklist                | Due diligance check table  | Due diligance check table to be reviewed and advised by RP  | Project Manager       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 30   | DTM  | 14-Aug-24   | Phase 3   | Masterplan<br>validation  | KoP                      | Updating to notes  | Removing the KoP section or simplifying that saying SINSW standard  | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 31   | DTM  | 14-Aug-24   | Phase 4   | Masterplan<br>validation  | Heritage                 | Updating to notes  | European has an impact on planning pathway as some of the<br>buildingas are heritage , additional notes to say not impacting<br>the new building and planning pathway       | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 32   | DTM  | 14-Aug-24   | Phase 5   | Masterplan<br>validation  | Site                     | Updating to notes  | Not found any contamination on norther part test pits   | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 33   | DTM  | 14-Aug-24   | Phase 6   | Masterplan<br>validation  | Biodiversity             | Updating to notes  | Getting more clear with the trees addressed on the<br>recommendation. BDAR impacting the plan so need to be<br>clarified.   | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 34   | DTM  | 14-Aug-24   | Phase 7   | Masterplan<br>validation  | Arborist                 | Updating to notes  | Just to include trees on the impacted area  | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 35   | DTM  | 14-Aug-24   | Phase 8   | Masterplan<br>validation  | Traffic                  | Updates to be reviewed   | SI Internaly reviewed on transport report and need RP to make<br>sure if upgrading those will affect the scope  | Project Manager       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 36   | DTM  | 14-Aug-24   | Phase 2   | Masterplan<br>validation  | Playspace<br>calculation | Playspace calulation update  | Furthur advise from design advisory - SI to provide right person  | SINSW IP Team         | 15-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 37   | DTM  | 14-Aug-24   | Phase 2   | Masterplan<br>validation  | Playspace<br>calculation | Playspace calulation update  | Number of the students to be updated as 644 on Left and 667<br>on the right calculation   | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 38   | DTM  | 14-Aug-24   | Phase 2   | Masterplan<br>validation  | Playspace<br>calculation | Playspace calulation update  | Showing the previous existing demountable on site and<br>deducting the area of that from existings  | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 39   | DTM  | 14-Aug-24   | Phase 2   | Masterplan<br>validation  | Report                   | Report update based on comments and feedbacks  | SI to send their comment on masterplan draft report<br>FTA to capture the comments and rewordings   | Architect - FTA       | 16-Aug-24 | Complete  | Complete                        | Updated on Masterplan report  |  |                       |
| 40   | DTM  | 21-Aug-24   | Phase 2   | Masterplan<br>validation  | Report                   | Cost plan, Programme, Risk register need to be attached to the<br>report as a deliverable  |   | SINSW IP Team         | 2-Oct-24  | Complete  | Complete                        | Awaiting CV feedback. MVP Design review meeting scheduled<br>for 25.09.24   |  |                       |
| 41   | DTM  | 21-Aug-24   | Phase 2   | Masterplan<br>validation  | Report                   | Cammeray core size is large but keeping gap analysis based on<br>the 667 capacity and medium core  | FTA to keep the calculation as is in the report   | Architect - FTA       | 23-Aug-24 | Complete  | Complete                        |   |  |                       |
| 42   | DTM  | 21-Aug-24   | Phase 2   | Cost plan                 | Fire Hydrant             | Consideration of united building or Fire sepration option with<br>performance solution against fire hydrant requirement  | Acor and BCA to review options with Cost team   | Various - list        | 23-Aug-24 | Complete  |                                 | Building will be considered a united building. Flow and<br>pressure from alternative connection is sufficient so tanks and<br>pumps should not be required.   |  |                       |
| 43   | DTM  | 21-Aug-24   | Phase 2   | Masterplan<br>validation  | Playspace<br>calculation | Confirmation of the play space calculation from EFSG   | FTa to send the email and cc SI and RP team   | Architect - FTA       | 23-Aug-24 | Complete  | Complete                        | EFSG approved the way that calculation is done on the<br>drawings.  |  |                       |
| 44   | DTM  | 22-Aug-24   | Phase 2   | Masterplan<br>validation  | Survey                   | Building E scope/extent of survey  | Design Team to provide a scope of works required to complete<br>a full survey of Building E<br>2- With SINSW IP for procurement   | SINSW IP Team         | 16-Oct-24 | Complete  | In progress/Assigned            | Should be attending site in the School Holidays report should<br>be available the following week.   |  |                       |
| 45   | DTM  | 27-Aug-24   | Phase 2   | Masterplan<br>validation  | PAPS                     | Comments received from SINSW Stat Planning   | Planners to review and update PAPS  | Town Planner          | 25-Sep-24 | Closed  |                                 | Likely to be a REF following latest SINSW advice<br>- Meeting on 26.09.24 to review<br>Confirmed that PAPS is not required. REF deliverable list will<br>be provided.   |  |                       |
| 46   |      | 28-Aug-24   | Phase 2   |                           | Options                  | Options comments:<br>- Option 1 is limmiting the access to vehicle height on not   | SI to send the options to school for their review and comments<br>on finalising the location and the layout.  | Architect - FTA       |           | Complete  |                                 | Proceed with original building location. Masterplan Validation<br>Report to provide commentary on why other options weren't   |  |                       |
|      | DTM  |             |           | General/<br>Architectural |                          | working - Option 3 is not viable as they have lack of play spafe at the moment   |   |                       | 11-Sep-24 |   |                                 | viable.   |  |                       |
| 47   |      | 20. Aug 24  | Dhase 2   |                           | Tree Demovel             | - Option 4,5,6 to be raised for disscussion to the school  | PD to investigate and undete  | Droiget Manager       |           | Complete  |                                 | DDI discussed DDAD with Advants and Water Technology and  |  |                       |
| 47   |      | 28-Aug-24   | Phase 2   |                           |                          | The programme impact on removing the trees relative to BDAR process  | KP to investigate and update  | Project Manager       |           | Complete  |                                 | RPI discussed BDAR with Arborist and Water Technology and<br>both confirmed that there is no high value biodiversity on site,<br>hence no requirement for a BDAR.   |  |                       |
|      | DTM  |             |           | Programme                 |                          |  |   |                       | 3-Sep-24  |   |                                 | RP to arrange for meeting with the Arborist and Planner to<br>confirm impact of removing trees.   |  |                       |
| 48   |      | 28-Aug-24   | Phase 2   |                           | Civil                    | OSD tank requirement to be confirmed   | RP to clarify that with planners and council  | Project Manager       |           | Complete  | Complete                        | OSD confirmed, modular tank sizes 3m x 5m and the Quality   |  |                       |
|      | DTM  |             |           | Cost plan                 |                          |  |   | _                     | 3-Sep-24  |   |                                 | tank about the same size. Required volume about 75m3 (tbc) -<br>We could leave the OSD off the drgs and await Council<br>comments?  |  |                       |
| 49   | DTM  | 28-Aug-24   | Phase 2   | Cost plan                 | Structure                | Ground floor slab requirement  | RP to investigate and update  | Project Manager       | 3-Sep-24  | Complete  |                                 | Suspended slab to be pursued to align with existing levels of<br>adjacent building E  |  |                       |
| 50   | DTM  | 04-Sep-24   | Phase 2   | General/<br>Architectural |                          | Send details of tree removal to SINSW for discussion with Sharon Sands.  | FTA to send the document / SI to communicate with comunity<br>and school on that  |                       | 11-Sep-24 | Complete  |                                 | FTA provided the support document related to that   |  |                       |
| 51   | DTM  | 04-Sep-24   | Phase 2   | Landscape                 | Tree replacement         | Seek advice from Landscape Architect regarding replacement<br>of trees being removed.  | FTA to get the landscape advice on that   | Architect - FTA       | 11-Sep-24 | Complete  | Complete                        | Advice from Landscape Architect - We would recommend that<br>we provide supplementary tree planting to other locations within<br>the school due to the extensive root systems within the garden<br>beds where the trees are being removed not providing the best<br>of growing conditions for younger trees. IF we were to replant<br>within the zone around the new school building, then this would<br>be along the Miller Street fenceline. However, Tree root<br>investigation in this area would be recommended to ascertain |  |                       |
| 52   | DT11 | 04-Sep-24   | Phase 2   | General/                  | Options                  | FTA to issue copies of the options analysis for the building   |   | Architect - FTA       |           | Complete  |                                 | the viability of replanting in this location. Any new planting to the<br>south or behind the new building will not have access to the<br>necessary sunlight so planting within the garden bed is not<br>recommended.  |  |                       |
| 53   | DTM  | 04-Sep-24   | Phase 2   | Architectural             | Bike park                | location to SINSW.<br>RTA requires 50 bicycle parking spaces.  | FTA / GI to review locations.   | Architect - FTA       | 11-Sep-24 | Complete  | Complete                        | FTA proposed location - in replacement of demountables on   |  | i                     |
| 54   | DTM  | 04-Sep-24   | Phase 2   | RTA<br>Mastervalidation   | Tree removal             | Additional notes to be included to the report, summary of the  | FTA to add after finalising the trees decision  | Architect - FTA       | 11-Sep-24 | Complete  | Complete                        | Bellevue St frontage.<br>Added to report - final version to be issued.  |  |                       |
|      | DTM  | 0-7-00p*24  | 1 11036 2 | report                    | nee removal              | revised options and the most viable one and mentioning the<br>revised options and the most viable one and mentioning the<br>removal of the trees is the outcome of managing the risk to the<br>building and kids involved areas. |   | a or mouth of the PTA | 13-Sep-24 | Joinpiere                                       | Teenihiere                      |   |  |                       |
| 55   | DTM  | 11-Sep-24   | Phase 2   | Landscape                 | Tree removal             | and CV for inclusion in presentation to school and stakeholders  | notes with tree numbers.  |                       | 18-Sep-24 | Complete  | Complete                        |   |  |                       |
| 56   | DTM  | 11-Sep-24   | Phase 2   | Landscape                 | Replacement<br>Planting  | FTA to add replacement tree planting to the proposed site plan<br>in the masterplan Validation Report  | Trees to be shown to the North East of the site - adjacent to the<br>playing field with a note to indicate final location to be<br>determined.                              | Architect - FTA       | 18-Sep-24 | Complete  | Complete                        |   |  |                       |

| ltem | Team         | Date Raised | Phase     |                           | Subject                             | Item   | Actions   |                           |           |   | Consultant's recommended status | Further Actions/Updates/Comments.<br>If the item is closed, this section is to include a reference on   | Date Closed<br>DO NOT AMEND.    | Consultant's comments |
|------|--------------|-------------|-----------|---------------------------|-------------------------------------|--|---|---------------------------|-----------|---|---------------------------------|---|---------------------------------|-----------------------|
|      |              |             |           |                           |                                     |  |   | Action<br>Required By     | Date Due  | FT/RPI TO AMEND<br>FOLLOWING MEETING<br>REVIEWS |                                 | how it was closed and drawing/report reference.   | FT/RPI TO<br>AMEND<br>FOLLOWING |                       |
| 57   |              | 11-Sep-24   | Phase 2   |                           | PAA Planning                        | Meeting to be held to review detailed layout of PAA area with  | FTA to prepare sketch for discussion.   | Project Manager           |           | Complete  | In progress/Assigned            | RP to schedule a meeting with the school to review following  | MEETING                         |                       |
|      |              |             |           |                           |                                     | Jasna and school to agree on how the space should be fitout  |   |                           |           |   |                                 | school holidays<br>Jasna reviewed the current layout and sent the markup on ,   |                                 |                       |
|      | DTM          |             |           | General/<br>Architectural |                                     |  |   |                           | 16-Oct-24 |   |                                 | FTA to integrate the markup on the next package   |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | Jasna's Markup to be addressed in the design development<br>phase in regards to furniture and internal finishes   |                                 |                       |
| 58   |              | 11-Sep-24   | Phase 2   |                           | Bag Storage                         | Jasna noted that the current standards allow for more area in the classrooms to accommodate bag storage.   | FTA to review classroom layouts to confirm bag storage can be incorporated.   | Project Manager           |           | Complete  | In progress/Assigned            | RP to schedule a meeting with the school to review following<br>school holidays   |                                 |                       |
|      | DTM          |             |           | General/                  |                                     |  |   |                           | 16-Oct-24 |   |                                 | Jasna advised for allocation of 30 bag storage in peagon hole<br>strategy into internal layout, FTAm to integrate that in the next  |                                 |                       |
|      |              |             |           | Architectural             |                                     |  |   |                           |           |   |                                 | package<br>Updated on the architecture package  |                                 |                       |
| 59   |              | 11-Sep-24   | Phase 2   | ICT                       | Existing ICT Audit                  | NDY to complete audit of existing ICT infrastructure and   |   | SINSW ICT                 |           | Complete  | In progress/Assigned            | RO'H to provide existing audit  |                                 |                       |
|      | DTM          |             |           |                           |                                     | systems.   | the SINSW ICT rep to review details and agree on extent of<br>work.   |                           | 18-Sep-24 |   |                                 |   |                                 |                       |
| 60   |              | 18-Sep-24   | Phase 2   | Heritage                  | Heritage Impact<br>Statement        | RP to commence the process of engaging heritage consultant<br>to provide heritage impact statement to support planning   | RP to advise on scope of works required to issue to SINSW   | SI Heritage               |           | Complete  | In progress/Assigned            | Draft already completed - Gyde to review and confirm if it<br>satisfies planning requirements   |                                 |                       |
|      | DTM          |             |           |                           |                                     | approval   |   |                           | 25-Sep-24 |   |                                 | Updated Statement of Heritage impact in progress pending<br>design assessment of the roof and façade treatment.   |                                 |                       |
| 61   |              | 18-Sep-24   | Phase 2   | Procurement               | Tree Removal -                      | RP to confirm the next steps required to progress the removal  | RP to advise on consultants requried and scope of works   | Project Manager           |           | Complete  |                                 | RP to confirm   |                                 |                       |
|      | DTM          |             |           |                           |                                     | of trees and confirm what additional consultant procurement<br>may be required.  | required to issue to SINSW  | , ,                       | 25-Sep-24 |   |                                 | Arborist got updated with the approach and progressing the<br>process for those tree removals.  |                                 |                       |
| 62 C | esign Review | 25/09/24    | Phase 2   | Existing building         | Works to existing                   | SI Heritage queried extent of works in MSB room to inform  | NDY to provide scope of works to be carried out in MSB room   | Electrical - NDV          |           | Closed  |                                 | Tree replanting on site to be confirmed with Arborist NDY to go on site visit 04.10.24  |                                 |                       |
| 02 0 | Meeting      | 25/03/24    | 1 11036 2 | Existing building         |                                     | them of any heritage issues that it may trigger  | for SI Heritage review  | Liectrical - ND I         |           | Closed  |                                 | Site visit conducted by NDY on 04.10.24 clocluded that there is<br>no substation required. Layut for the main comms room to be  |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           | 8-Oct-24  |   |                                 | discussed with Duncan (SI Heritage)<br>NDY Confirmed that no additional works required based on site  |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | inspection  |                                 |                       |
| 63   | DTM          | 25-Sep-24   | Phase 3   | General/<br>Architectural | Gutter Guard                        | It was noted that the gutters (including valley gutters) to the<br>new roof should be specified to be fixed with gutter guard to<br>protect form loaf for  | FTA to include details in the specifications in Schematic Design  | Architect - FTA           | 29-Nov-24 | Complete  |                                 | Additional details to be provided on the specification<br>EFSG requirement to be addressed on the design.   |                                 |                       |
| 64   |              | 25-Sep-24   | Phase 2   | Alonitootara              | Lift to Roof                        | protect from leaf fall.<br>FTA proposed that the roof to the lift should be reversed to  | Both proposals were considered acceptable. Acor advised this  | Architect - FTA           |           | Complete  | Complete                        | Further detail in roof connections to be addressed and  |                                 |                       |
|      | DTM          |             |           | General/<br>Architectural |                                     | allow the gutter to spread water onto the main roof. It was also<br>proposed that a small hip roof be created at the back of the lift<br>shaft to avoid a box gutter in this area.   |   |                           | 30-Sep-24 |   |                                 | coordinated movinf forward  |                                 |                       |
| 65   |              | 25-Sep-24   | Phase 2   | Acoustics                 | Plant Room                          | FTA proposed a plant room along the Miller Street frontage.  | NDY to provide an acoustic assessment and advice regarding  | Acoustic - NDV            |           | Complete  |                                 | NDY to provide further information  |                                 |                       |
| 05   | DTM          | 23-060-24   | 111036 2  | Acoustics                 | Acoustics                           | Acoustic implications of this location to be reviewed.   | this location.  | Acoustic - NDT            | 9-Oct-24  | Complete  |                                 |   |                                 |                       |
| 66   | DTM          | 25-Sep-24   | Phase 2   | General/<br>Architectural | BCR Location -<br>Departure         | FTA and NDY proposed that the BCR for the building could be located under the new stair.   | This was considered acceptable. However, it was noted that the size of the BCR is not the standard EFSG sizing. NDY to          | Electrical - NDY          | 0.0-1.04  | Complete  |                                 | Departure register to be setup and reviewed   |                                 |                       |
|      | DTM          |             |           |                           |                                     |  | provide details of the proposed layout to SINSW to request approval for a departure.  |                           | 2-Oct-24  |   |                                 |   |                                 |                       |
| 67   | DTM          | 25-Sep-24   | Phase 2   | General/<br>Architectural | BCR Location - Fire<br>Rating       | MBC advised that fire rated walls and ceilings would be<br>required to the BCR because of it's location under the stair.   | MBC to provide advice regarding the FRL required for this area<br>to allow FTA to detail.                                       | BCA - MBC                 | 2-Oct-24  | Complete  |                                 | BCA advised fo 60/60/60 Fire rating requirement to be<br>considered on the BCR location under the stair   |                                 |                       |
| 68   |              | 25-Sep-24   | Phase 2   | Hydraulic                 | Fire Hydrant                        | Acor advised that a review of the Fire Hydrant coverage has  | Acor to provide details of proposed additional hydrant location   | Project Manager           |           | Complete  |                                 | Additional informmation from the surveyor required.   |                                 |                       |
|      | DTM          |             |           | ,                         | Coverage                            | shown that the proposed works (and Existing Building E) can't be serviced by the existing hydrant locations.   | to provide coverage to Building E and the new works.  |                           | 2-Oct-24  |   |                                 | RP to investigate and provide further direction .<br>BCA to provide advice on the latent and preexisting non<br>compliances,  |                                 |                       |
| 69   | PMG          | 10-Mar-24   | Phase 2   | Architectural             | Heritage                            | Heritage advice façade / roof colour etc design in heritage<br>precinct  | SI Heritage invited to design meeting 9/10/2024   | Project Manager           | 4-Oct-24  | Closed  |                                 |   |                                 |                       |
| 70   | DTM          |             |           | Services<br>Coordination  | Initial Consultant<br>Concept Issue | All consultants to progress Concept Design for coordination<br>with the architectural plans  | All consultants to issue initial concept drawings for review<br>ahead of the next DTM   | All                       |           | Complete  |                                 | Civil & structure concept drawings to be issued by 4th of Oct.<br>Electrical & Mechanical & Hydraulic to be issued by 11th of Oct   |                                 |                       |
|      |              | 2-Oct-24    | Phase 2   |                           |                                     |  |   |                           | 11-Oct-24 |   |                                 |   |                                 |                       |
| 71   | DTM          | 2-Oct-24    | Phase 2   | Structure                 | Shear Walls                         | Location of the Shear wall to be over Grid line A in half size f<br>grid 2&3   | ST to capture that on their design, FTA to icorporate that in the drawings update   | Structural -<br>Meinhardt | 11-Oct-24 | Complete  |                                 |   |                                 |                       |
| 72   | DTM          | 2-Oct-24    | Phase 2   | Landscape                 | New trees location                  | Location of the new proposed trees to be investigated to may or<br>may not having asbestos contamination   | •   | Landscape                 | 18-Oct-24 | Complete  |                                 | Locations were reviewed with the school and changed to<br>adjacent to Building C to avoid asbestos area.  |                                 |                       |
| 73   | DTM          | 2-Oct-24    | Phase 2   | Landscape                 | Bike parking                        | Bike parking requirement to be confirmed the numbers<br>Location of the bike parking infron of the new building to be  | RP to investigate<br>Landscape to review and update   | Project Manager           |           | Complete  |                                 | Bike parking numbers to be confirmed; No change to bike parking quantity.   |                                 |                       |
|      |              |             |           |                           |                                     | access   |   |                           | 18-Oct-24 |   |                                 | 50Bike park advised to be allocated there   |                                 |                       |
| 74   | DTM          | 9-Oct-24    | Phase 2   | Civil / Hydraulic         | Downpipes location                  | Downpipes Location to be reviewed to move to the Northern side or corners to not splitting to retaining wall side  | Civil, Architecture and Hydraulic to have a workshop through.<br>- Civil to update drawings to show downpipes connecting into a | Various - list            |           | Complete  |                                 | It was noted that the drawings should incorporate a<br>replacement of the existing pipe to the Southern edge of the   |                                 |                       |
|      |              |             |           |                           |                                     |  | new in-ground pipework along the Southern edge of the building  |                           | 16-Oct-24 |   |                                 | building. This will need to be reviewed further once the<br>contractor uncovers the pipework etc. This will need to be  |                                 |                       |
| 75   | DTM          | 0.0~+ 0.4   | Dhase 0   | Analitaat                 | Llaritar -                          | Horitogo Accocoment  | CL Horitogo to Appage design input in britten and inter   | SI Horitage               |           | Complet-  |                                 | noted as a risk.  |                                 |                       |
| 75   | DTM          | 9-Oct-24    | Phase 2   | Architectural             | Heritage                            | Heritage Assessment  | SI Heritage to Assess design input in heritage precinct   | SI Heritage               |           | Complete  |                                 | SI Heritage to do a site visite and sending following directions<br>on their assessment of current design package.<br>Items raised by SI Heritage:                                      |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | Items raised by SI Heritage:<br>•The mechanical plant location is not suitable for development<br>in a Heritage Conservation Area – this would not be permissible                       |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | if we were installing in this location as a stand-alone AC project.   |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | Mechanical plant location needs to be reconsidered<br>•Trees which are located on the western side of the school<br>(fronting Wilde) need to be prepared as provide an encoded          |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | (fronting Miller) need to be preserved as much as possible, as<br>the screening they provide is helpful to minimise impacts to new<br>development within the heritage conservation area |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | development within the heritage conservation area<br>•The façade treatment was identified as a poor outcome in the<br>heritage conservation area and needs to be reconsidered – the     |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           | 23-Oct-24 |   |                                 | perforated metal screen is not considered a 'recessive' design.<br>In addition, the removal of trees used to screen the site with   |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | potential decorative representations of trees on the perforated<br>metal screen is considered an even poorer outcome: the   |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | removal of screening trees and replacing them with a strongly<br>visible design of tree silhouettes is exactly the opposite of a  |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | discreet/recessive design which is needed when developing on<br>a street frontage in a heritage conservation area - It is noted   |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | that the design team have a large number of places and<br>opportunities to incorporate decorative design elements – but   |                                 |                       |
|      |              |             |           |                           |                                     |  |   |                           |           |   |                                 | the frontage to Miller Street is not one of them.   |                                 |                       |
| 70   | DTM          | 22.0-4-04   | Dharan    | 504                       | Mashari                             | Automatic chuideus of succession and the state of the sta |   | Mashering                 |           | Constat   |                                 |   |                                 |                       |
| 76   | DTM          | 23-Oct-24   | Phase 2   | BCA                       | Mechanical                          | Automatic shutdown of mechanical ventilation - NDY to confirm how this will function   | requirement through Schematic Design  | Mechanical -<br>NDY       | 13-Nov-24 | Complete  |                                 |   |                                 |                       |

| Item | Team | Date Raised | Phase   |                            | Subject                 | Item   | Actions  | Action<br>Required By | Date Due  | Item Status<br>DO NOT ADJUST.<br>FT/RPI TO AMEND<br>FOLLOWING MEETING<br>REVIEWS | status | Further Actions/Updates/Comments.<br>If the item is closed, this section is to include a reference on<br>how it was closed and drawing/report reference. | Date Closed<br>DO NOT AMEND.<br>FT/RPI TO<br>AMEND<br>FOLLOWING<br>MEETING | Consultant's comments |
|------|------|-------------|---------|----------------------------|-------------------------|--|--|-----------------------|-----------|--|--------|--|--|-----------------------|
| 77   | DTM  | 23-Oct-24   | Phase 2 | General/<br>Architectural  | Verandah Roof<br>Height | FTA noted that the roof height at the edge of the verandah is<br>only 2100mm due to aligning with the existing roof              | FTA to note height of roof at edge of verandah as departure - 2100 high  | Architect - FTA       | 25-Oct-24 | Complete   |        |  |  |                       |
| 78   | PRG  | 28-Oct-24   | Phase 2 | General /<br>Architectural | EFSG                    | The DEL has requested a comparison between the standard<br>Learning Commons space and the proposed Practical Activities<br>Area. | FTA to provide a PAA size comparison to North Sydney PS as<br>part of the discussions to be held with the users.                   | Architect - FTA       | 31-Oct-24 | Complete   |        | FTA to send e-mail to RPI to send to DEL   |  |                       |
| 79   | PRG  | 28/10/2024  | Phase 2 | General /<br>Architectural | EFSG                    | The DEL has requested an enclosed Withdrawal space be<br>considered in the PAA area.   | FTA to review options for creating a withdrawal space<br>(preferably enclosed) within each PAA area for review with the<br>school. | Architect - FTA       | 31-Oct-24 | Complete   |        |  |  |                       |
| 80   | DTM  | 13-Nov-24   | Phase 2 | General /<br>Architectural | Building<br>Arrangement | Review of lift location as requested by DIAS / Pattern Book team   | FTA to send sketches for SI and EFSG review , RP to follow up<br>for their comments  | Project Manager       | 20-Nov-24 | Complete   |        | Proposed sketch presented to SI and received comments back<br>from Jasna to be proceed incoorporating couple of changes.                                 |  |                       |
| 81   | DTM  | 13-Nov-24   | Phase 2 | General /<br>Architectural | 3D Images               | Coloured renders needed by DPO for public communications   | RP and FTA to  | Architect - FTA       | 20-Nov-24 | Complete   |        | Updated renders to be issued with the 80% package  |  |                       |