



Suite 2, Level 1  
33 Herbert Street  
ST. LEONARDS NSW 2066

T 02 9438 5098

# CIVIL AND STRUCTURAL ENGINEERING DESIGN DEVELOPMENT REPORT

WORLD CLASS END OF LIFE PROGRAM

TAMWORTH HOSPITAL

Prepared for: Health Infrastructure NSW

Document no: WCP-ACR-TAM- RPT-MEPF-005



Revision no: 005

Confidential and Commercial in Confidence

Disclaimer

This Report has been prepared in accordance with the scope of services described in the agreement between ACOR Consultants and the Client. The Report relies upon data, surveys, measurements and results based on instructions from, and in consultation with, the Client. Except as otherwise stated, ACOR Consultants has not attempted to verify the accuracy or completeness of any information provided by the Client. If the information is subsequently determined to be false, inaccurate or incomplete then it is possible that changes may be required to the Report. Changes in circumstances or facts, the passage of time, manifestation of latent conditions or impacts of future events may also impact on the accuracy, completeness or currency of the information or material set out in this Report. This Report has been prepared solely for use by the Client, ACOR Consultants Pty Ltd and its related body corporates accepts no responsibility for its use by any third parties without the specific authorisation of ACOR Consultants. ACOR Consultants reserves the right to alter, amend, discontinue, vary or otherwise change any information, material or service at any time without subsequent notification. All access to, or use of, the information or material is at the user's risk and ACOR Consultants Pty Ltd and its related body corporates accepts no responsibility for the results of any actions taken on the basis of information or material provided, nor for its accuracy, completeness or currency. For the reasons outlined above, however, no other warranty or guarantee, whether expressed or implied, is made as to the data, observations and findings expressed in this Report, to the extent permitted by law.

Revisions

Revision	Description	Date	Prepared by	Approved by	Signature
001	DRAFT Master Planning Report	03/04/2024	TDL/GL	Dale Lenden	
002	DRAFT Master Planning Report	24/04/2024	TDL/GL	Dale Lenden	
003	Concept Report	24/07/2024	TDL/GL	Dale Lenden	
004	Draft Schematic Report	18/10/2024	TDL/GL	Dale Lenden	
005	Draft Design Development Report	07/03/2025	JY/GL	Dale Lenden	

Review Panel

Division/ Office	Name
Structural / St Leonards	Dale Lenden

Unless otherwise advised, the parties who have undertaken the Review and Endorsement confirm that the information contained in this document adequately describes the conditions of the site located at Tamworth Hospital, NSW.

COPYRIGHT

This document, including the concepts and information contained within it, are the property of ACOR Consultants Pty Ltd or any of its related or associated entities. Use or copying of this document in whole or in part without the written permission of ACOR Consultants Pty Ltd constitutes an infringement of copyright. No part of this document may be copied, reproduced, adapted, transmitted or stored in a retrieval system in any form or by any means without written permission or unless otherwise permitted under the Copyright Act 1968. Removal or modification of any copyright or other proprietary protection from this document will be a breach of copyright.

© ACOR Consultants Pty Limited

All intellectual property and copyright reserved.

## Table of Contents

<b>1</b>	<b>Executive Summary.....</b>	<b>4</b>
1.1	Civil Services .....	4
1.2	Structural Services .....	4
<b>2</b>	<b>Introduction.....</b>	<b>4</b>
<b>3</b>	<b>Standards and Design Guides.....</b>	<b>5</b>
3.1	Australian Standards and Codes .....	5
3.1.1	Design Loads .....	5
3.1.2	Deflection limits .....	6
3.2	Authority and Regulatory Bodies .....	6
3.3	NSW Health Policy and Health Infrastructure Engineering Guidelines.....	6
<b>4</b>	<b>Scope of Services .....</b>	<b>6</b>
4.1	Civil.....	6
4.2	Structural.....	6
<b>5</b>	<b>Description of the Civil Engineering Services .....</b>	<b>6</b>
5.1	Existing Civil Infrastructure .....	6
<b>6</b>	<b>Description of the Existing Structural Framing.....</b>	<b>6</b>
6.1	Existing Structural Framing .....	6
<b>7</b>	<b>Proposed Engineering Works.....</b>	<b>7</b>
7.1	Civil.....	7
7.2	Structural.....	7
7.2.1	Permanent batters and gabion baskets .....	7
7.2.2	Raft slab on ground.....	7
7.2.3	Roof and wall structure .....	7
<b>8</b>	<b>Project Risks .....</b>	<b>7</b>
<b>9</b>	<b>Budget Estimate Costs .....</b>	<b>7</b>
9.1	Civil Engineering .....	7
9.2	Structural Engineering .....	7
<b>Appendix A - Structural Drawings .....</b>		<b>8</b>

<b>Appendix B - Civil Drawings.....</b>	<b>9</b>
---	----------

## List of Tables

<b>Table 1 - Typical Design Loads.....</b>	<b>5</b>
Table 2 - Wind Load Design Parameters .....	5
Table 3 - Earthquake Load Design Parameters.....	6
Table 4 – Deflection Limits.....	6

## 1 Executive Summary

ACOR Consultants Pty Ltd (ACOR) has been engaged by Health Infrastructure NSW (HINSW) to assist the design team with the Design Development design of the World Class End of Life Care Program (WCEoLP) relating to Civil and Structural Services. The development consists of the additional of a new facility adjacent to the existing Palliative Care unit at Tamworth Hospital for this part of the proposed WCEoLP works.

ACOR has investigated, through on-site investigations, review of existing documentation and consultation with the hospital engineering staff, the existing structural framing and civil infrastructure.

The Design Development design report, where information is available, will describe the existing infrastructure, structural framing, strategies, enabling works and diversions, staging requirements, and details of proposed civil and structural services to the new development.

Throughout the development of the design, we will assess several options and the final selected design parameters preferred by the project team, HINSW and the Hunter New England (LHD) will be detailed in each report for master planning, concept and schematic phases.

The overall design strategies for the project will consider and review key design strategies including:

- Existing Civil infrastructure
- Existing Structural framing
- Enabling works (if required)
- Environmentally Sustainable Design (ESD) Options and environmental best practice
- Safety in Design for construction and maintenance
- Risk assessment

In carrying out our preliminary assessments we have found:

### 1.1 Civil Services

The existing infrastructure:

- There are currently several stormwater pits immediately adjacent the proposed works location that will be utilised for any upgrades to the existing downpipe locations and stormwater requirements:
  - These have been coordinated with Hydraulics
- There is no grading required as the building is existing infrastructure and will be retained as is
  - Any additional footpaths can be provided and graded accordingly

The main design objective for us is to confirm the availability and compliance of the existing stormwater infrastructure for the proposed building works and that the structure can accommodate the proposed alterations and additions. As well as to ensure minimal disruption to existing hospital operations, cost effective construction methodology is used and compliance with statutory building codes and health facility best practice is achieved.

### 1.2 Structural Services

The proposed works include the excavation and construction of a new single level building adjoining the existing hospital. The proposed works will include permanent retaining and batter to accommodate the change in levels to the surrounding areas. The new building will be a raft on ground.

The building wall and roof will be a lightweight steel frame.

## 2 Introduction

The development is the extension of the existing Palliative Care Unit adjoining the existing Hospital, refer to Appendix A for the Design Development documentation as prepared by *Architectus*. The below image represents the location of the proposed extension.




Image 1 – Proposed floor plan

The purpose of this document is to establish an engineering design strategy and highlight potential risks and opportunities for Civil and Structural Engineering services for the project.

This report will consider:

- External site infrastructure location
- Augmentation of existing civil infrastructure to cater for the proposed works
- Staging, interface and hospital disruption issues
- Enabling Works
- Proposed structural engineering design for the new extension
- ESD
- Safety in Design



- Risk Assessments

This report is based on:

- Detailed Design drawings prepared by *Architectus* (refer to Appendix A)
  - Review of existing available documentation provided by Capital Insight to the design team
  - Site visits and discussions with hospital engineers and maintenance staff
  - Liaison with design team consultants and project managers
  - HINSW requirements
  - Site Visit attendance:
    - Site Visit 1 (6 October 2023) by Steven Wilson (Building Services)
    - Site visit 2 (31 January 2024) by Kevin Wong, Shebak Khan, William Maiwald, and Aaron Townsend
      - Site inspection to review latent conditions
      - Met with Fiona Ostini – LHD Project Officer Tamworth Redevelopment
      - Met with Rina Roderiguez, Sneha Bokade – Project Managers (Capital Insight)
- Site Visit 3 (November 2024) by Dale Lenden

### 3 Standards and Design Guides

#### 3.1 Australian Standards and Codes

The following lists the primary standards and codes our design approaches are reliant upon:

In particular, the structural design will be in accordance with the following relevant Australian Standards:

- AS/NZS 1170.0 (2002) – Structural Design Actions Part 0 General Principles
- AS/NZS 1170.1 (2002) – Structural Design Actions Part 1 Permanent, Imposed and Other Actions
- AS/NZS 1170.2 (2011) – Structural Design Actions Part 2 Wind Loads
- AS 1170.4 (2007) – Structural Design Actions Part 4 Earthquake Actions in Australia
- AS 3600 (2018) – Concrete Structures
- AS 3700 (2018) – Masonry Code
- AS 4100(1998) – Steel Structures
- AS 4600(2018) – Cold-formed Steel Structures
- AS/NZS 2312.1 (2014) Protection of Structural Steel Part 1: Paint Coatings
- AS/NZS 2312.2 (2014) Protection of Structural Steel Part 2: Hot Dipped Galvanising

##### 3.1.1 Design Loads

The design loads are as per the table below.

Floor Type	Live Load (kPa)	Imposed Point Load (kN)	Superimposed Dead Load (kPa)	40mm Sacrificial Concrete Toppings
Stairs, ramps	4.0	4.5	0.0	0.0
Corridors, circulation areas and foyer spaces	5.0	4.5	1.3	1.0

Floor Type	Live Load (kPa)	Imposed Point Load (kN)	Superimposed Dead Load (kPa)	40mm Sacrificial Concrete Toppings
Wards (General)	3.0	4.5	1.8	1.0
Clinical areas (General)	3.0	4.5	1.8	1.0
Plant rooms	5.0	4.5	2.4	0.0
Roof (typical)	0.25	1.4	1.0	0.0
Roof (green roof)	5.0 (250mm soil)	1.4	1	0.0

**Table 1 - Typical Design Loads**

The loads above (excluding the Imaging, MRI and Façade loads) have generally been adopted as per AS1170.1 (2002).

#### Wind Loads

The following design parameters have been adopted for the Wind Actions as per AS1170.2 (2011).

Item	Value
Location	Region A3
Importance Level	4
Vu	48m/s
Vs	37m/s
Ms	1.0
Mt	1.05
Md	1.0
Terrain Category	2.5

**Table 2 - Wind Load Design Parameters**

#### Earthquake Loads

The following design parameters have been adopted for the Earthquake Actions as per AS1170.4 (2021).

Item	Value
Importance Level	4
Probability Factor, Kp	1.5
Hazard Factor, Z	0.08
Sub-Soil Class	TBC
Earthquake Design Category	III
Structural Ductility Factor, $\mu$	3*
Structural Performance Factor, Sp	0.67

Table 3 - Earthquake Load Design Parameters

### 3.1.2 Deflection limits

Structural element	Maximum deflection
Supporting face masonry walls	Span / 1000
Supporting rendered masonry walls	Span / 800
Stud walls under lateral loading	Span / 500
Roof members:	
Dead load	Span / 360
Live load	Span / 250
Wind Service load	Span / 300

Table 4 – Deflection Limits

### 3.2 Authority and Regulatory Bodies

The following lists the primary authorities and regulatory bodies our design approaches are reliant upon:

- EP&A – ACT & Regulation
- Tamworth City Council (Council)
- Department of Fair Trading

### 3.3 NSW Health Policy and Health Infrastructure Engineering Guidelines

This report will rely upon the following guidelines and policies, however, the full suite of the HI guides and policies will be applicable:

- Design Guidance Note No.001 – Structural Design Criteria Guidelines
- Design Guidance Note No.006 – General Design Principles
- Design Guidance Note No.024 – Building Importance Levels for NSW Health Projects
- Design Guidance Note No.030 – Site Investigations: Project Opportunities and Constraints
- Design Guidance Note No.058 – Environmentally Sustainable Development dated 18 March 2021
- NSW Health – Engineering Services Guidelines GL2016\_020
- Australasian Health Facilities Guideline (AHFG)

## 4 Scope of Services

ACOR will include the following aspects:

### 4.1 Civil

- Stormwater design (surface and in-ground external to the building envelope) including connection in an approved manner to the existing Authority stormwater system;
- On-site detention system
- Stormwater quality treatment system;
- Design and grading of surface levels external to the building envelope;
- Preparation of a Soil Erosion and Sedimentation Control plan for Authority approval;

### 4.2 Structural

- Permanent batter and gabion baskets
- Foundations
- GF floor slab
- Interface with existing building
- New light weight steel framing to new walls and roof.

## 5 Description of the Civil Engineering Services

### 5.1 Existing Civil Infrastructure

Existing stormwater drainage is located adjacent the proposed site works area. Care should be taken around these areas if excavation is to occur to minimise disturbance and settlement to the system. The existing stormwater from the road needs to be realigned to run down the proposed footpath connection.

The existing pavement in the area appears to be relatively new and likely does not need to be upgraded.



Photograph 01 – existing stormwater drain and pavement along the street adjacent to the hospital.

## 6 Description of the Existing Structural Framing

### 6.1 Existing Structural Framing

The existing structure was completed in 2014-2015. TTW were the structural engineers for the building. A set of as-built documents have been received from the LHD. The geotechnical engineer's report No. 75393 dated April 2012 by Douglas Partners was not sighted.

The existing building is a reinforcement concrete (RC) structure on pad footings on 2,000kPa allowable bearing material (ex. TTW drawing ST-ASB-S0102).

The adjoining ground floor is a 120mm RC slab on ground. Refer to extract from TTW drawing ST-ASB-S0402 below.

The adjoining Level 1 slab is a PT band beam and slab configuration.

The civil works will also include localised hardstands and ramps to accommodate the new DDA access requirements.

Civil works include the detention of stormwater flows via an on-site detention tank. Walls and batters are also appropriately treated and capture for the detention of water. Refer to Appendix B for the Civil drawings.

## 7.2 Structural

The proposed structural engineering works includes the following (refer to Appendix C for the Structural sketches):

### 7.2.1 Permanent batters and gabion baskets

Due to the existing site topography, we are required to excavate to match the existing building ground floor finished floor levels.

It is proposed to have a combination of 1:3 permanent batters and gabion baskets retaining structures along the northern edge adjoining the existing road. Ther permanent batters will be protected from erosion with landscaping.

### 7.2.2 Raft slab on ground

It is proposed that the new ground floor slab will be a raft type construction, for both new palliative care units and linkways. The geotechnical report notes a site classification of Class P (abnormal conditions) due to deep fill, removed trees and structures. However, as we are excavating up to 2.5m, we will encounter natural sandy silty clay material to gravelly sandy clay material with a minimum safe allowable bearing capacity ranging from approximately 150kPa to 300kPa.

The new structure will be tied into the existing structure.

### 7.2.3 Roof and wall structure

The roof and wall structure will be a lightweight steel roof including steel rafters, steel beams, steel posts and bracings with light weight steel framing to the walls. The steel posts will be found on the RC raft. The linkway adjacent to the palliative care units and the ASB main building has the same lightweight steel roof and framing system.

## 8 Project Risks

The list below outlines current project risks:

- Unknown capacities and invert levels of civil infrastructure
- Structural as-built drawings and documentation are not accurate.
- Unknown services in the ground where there is proposed excavation
- The existing concrete PT slab and concrete blades between grid 6 and 7 on level 1 will be demolished due to the architectural changes. There are some risks of removing the PT slab and strengthening the remaining concrete PT slab

## 9 Budget Estimate Costs

### 9.1 Civil Engineering

The estimated cost for the Civil Engineering is prepared by the Project Cost Planner.

### 9.2 Structural Engineering

The estimated cost for the Structural Engineering is prepared by the Project Cost Planner.




Image 2– Extract from *TTW* drawing ST-ASB-S0402

## 7 Proposed Engineering Works

This section sets out to describe the proposed works associated with the new systems for the building. Staging and interface with the existing building is typically a key factor in considering the structural form and civil strategy ensuring minimal disruption to the existing Hospital.

### 7.1 Civil

Civil works include the connection of any new roof changes, in-ground stormwater pits, on-site detention systems and storm water quality systems to the existing drainage system as well as additional internal floor wastes which are being coordinated with the hydraulic engineer. The existing stormwater pit on the no-through-road adjacent to the hospital appears to be able to service the proposed stormwater system, although as there is no survey of the site this cannot be confirmed.

**Appendix A - Structural Drawings**



WORLD CLASS END OF LIFE PROGRAM TAMWORTH HOSPITAL  
DEAN STREET, NORTH TAMWORTH NSW 2340  
STRUCTURAL

DRAWING LIST	
DRAWING No	DRAWING TITLE
01A-000000	COVER SHEET
01A-000001	GENERAL NOTES - SHEET 1
12B-0000100	EXTERNAL WORKS GENERAL ARRANGEMENT PLAN
12B-0000110	GABION WALL DETAILS - SHEET 1
12B-0000200	GROUND FLOOR GENERAL ARRANGEMENT PLAN
12B-0000210	LEVEL 01 GENERAL ARRANGEMENT PLAN
12B-0000300	ROOF FRAMING GENERAL ARRANGEMENT PLAN
12E-0000305	ROOF FRAMING ELEVATIONS - SHEET 1
12E-0000306	ROOF FRAMING ELEVATIONS - SHEET 2 - NOT USED



Issue	Description	Date	Drawn	Approved
A	DRAFT SCHEMATIC DESIGN	15.10.2024	TL	DL
B	SCHEMATIC DESIGN	25.10.2024	DL	DL
C	00 ENGINEERING PUG PRESENTATION	21.07.2025	AJ	DL
D	00 ENGINEERING PUG PRESENTATION	14.02.2025	AJ	DL
E	DRAFT DESIGN DEVELOPMENT	07.02.2025	DL	DL

Drawing Key

PRINT IN COLOUR

North

Scale

Client

Managing Contractor

Architect

Project

WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL

DEAN STREET, NORTH  
TAMWORTH NSW 2340

NOT FOR CONSTRUCTION

**AcOR** CONSULTANTS  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T: +61 2 9438 5098

Drawn	Designed	G.A. Check	Date	Scale @ A0
TL	CMR	DL	15.10.2024	
Project No.	Drawing No.	Issue		
NA230258	WCP-ACR-DRW-STR-TAM-01A-0000000	E		



# GENERAL NOTES

G1. THE WORD ENGINEER USED IN THESE NOTES REFERS TO AN EMPLOYEE OR NOMINATED REPRESENTATIVE OF ACOR CONSULTANTS PTY LTD.

G2. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL AND OTHER CONSULTANTS DRAWINGS, SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE ENGINEER AND ARCHITECT.

G3. DO NOT COMMENCE CONSTRUCTION USING THESE STRUCTURAL DRAWINGS UNTIL A CONSTRUCTION CERTIFICATE IS ISSUED BY THE ENGINEER'S AUTHORITY.

G4. ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE RELEVANT CURRENT STANDARDS IN AUSTRALIA AND WITH THE BUILDING CODE OF AUSTRALIA INCLUDING, BUT NOT LIMITED TO:  
AS1594-SAA WELDING CODE (ALL PARTS)  
AS1594-SAA NATIONAL TIMBER FRAMING CODE (ALL PARTS)  
AS1720-SAA TIMBER CODE (ALL PARTS)  
AS1870-SAA RESIDENTIAL SLABS AND FOOTINGS  
AS3600-SAA CONCRETE STRUCTURE CODE  
AS3610-SAA FORMWORK FOR CONCRETE CODE  
AS3700-SAA MASONRY STRUCTURE CODE  
AS3798-GUIDELINES FOR DESIGN FOR COMMERCIAL AND RESIDENTIAL DEVELOPMENT  
AS4100-SAA STEEL STRUCTURES CODE

G5. ALL DIMENSIONS RELATIVE TO SETTING OUT AND OFF-SITE WORK SHALL BE VERIFIED BY THE CONTRACTOR BEFORE CONSTRUCTION AND FABRICATION IS COMMENCED.

G6. DIMENSIONS SHALL NOT BE OBTAINED BY SCALING THE STRUCTURAL DRAWINGS.

G7. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS STATED OTHERWISE. ALL LEVELS ARE EXPRESSED IN METERS, THE RLS SHOWN ON THESE DRAWINGS ARE FOR THE SOLE PURPOSE OF ASSISTING THE CONTRACTOR TO PROVIDE DESIGN, VERIFICATION, THEY MUST NOT BE USED FOR CONSTRUCTION, ALL SET-OUT DIMENSIONS AND LEVELS, INCLUDING ANY SHOWN ON THESE DRAWINGS SHALL BE IN ACCORDANCE WITH THE ARCHITECT'S DRAWINGS. ANY DISCREPANCIES IN THE DOCUMENTS MUST BE RESOLVED BEFORE ORDERING OR PLACING ANY MATERIALS.

G8. DURING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STRUCTURE IN A STABLE CONDITION AND ENSURING NO PART SHALL BE OVER STRESSED UNDER CONSTRUCTION ACTIVITIES. THE CONTRACTOR SHALL PROVIDE TEMPORARY BRACING, SHORING AND PROPPING IN ORDER TO KEEP THE BUILDING WORKS AND EXCAVATIONS STABLE AT ALL TIMES. TEMPORARY WORKS ELEMENTS NOTED IN THESE DRAWINGS ARE INTENDED AS A NOMINAL ALLOWANCE FOR TENDERING PURPOSES ONLY AND DOES NOT CONSTITUTE A CERTIFIED STRUCTURAL DESIGN.

G9. THE BUILDER IS RESPONSIBLE FOR THE ADEQUACY OF ALL TEMPORARY WORKS INCLUDING SHORING, PROPPING AND BRACING, WHERE NECESSARY THE CONTRACTOR IS TO ENGAGE A STRUCTURAL ENGINEER TO PROVIDE DESIGN, CERTIFICATION AND DEVELOP A SAFE WORK METHODOLOGY FOR THE TEMPORARY WORKS. APPROPRIATE ALLOWANCE SHALL BE MADE DURING TENDERING.

G10. THE METHOD OF CONSTRUCTION AND THE MAINTENANCE OF SAFETY DURING CONSTRUCTION ARE THE RESPONSIBILITY OF THE BUILDER. IF ANY STRUCTURAL ELEMENT PRESENTS A POTENTIAL RISK TO THE SAFETY OF THE BUILDING OR THE SAFETY OF THE MATTER SHALL BE REFERRED TO THE STRUCTURAL ENGINEER FOR RESOLUTION BEFORE PROCEEDING WITH THE WORK.

G11. IF THERE IS A DISCREPANCY IN MEASURES FOR ANY COMPONENT, ASSUME FOR PRICING PURPOSE ONLY THAT THE LARGER SIZE OR MORE EXPENSIVE SIZE IS CORRECT. REFERR TO THE ENGINEER FOR DESIGN BEFORE ORDERING OR PLACING ANY MATERIALS.

G12. THE APPROVAL OF A SUBSTITUTION SHALL BE SOUGHT FROM THE ENGINEER BUT IS NOT AN AUTHORIZATION FOR A VARIATION. ANY VARIATIONS INVOLVED MUST BE TAKEN UP WITH THE ARCHITECT OR PROJECT MANAGER BEFORE THE WORK COMMENCES.

G13. THE WRITTEN CONSENT OF ADJOINING PROPERTY OWNERS SHALL BE OBTAINED BEFORE INSTALLATION OF UNDERPINNING, ANCHORING WORKS, DRAINAGE LINES OR ANY OTHER WORKS BEYOND THE PROPERTY BOUNDARY.

G14. UNLESS AGREED OR SPECIFIED OTHERWISE, THE BUILDER IS REQUIRED TO NOTIFY AND ALLOW TIME FOR THE STRUCTURAL ENGINEER TO INSPECT THE WORKS AT THE FOLLOWING POINTS: COMPLETED EXCAVATION, FORMWORK, REINFORCEMENT, MEMBRANES AND EMBEDMENTS PRIOR TO PLACEMENT OF CONCRETE, COMPLETED ERECTED STRUCTURAL ELEMENTS PRIOR TO COVERING WORK COMMENCES.

G15. THE BUILDER SHALL GIVE 48 HOURS OR AT LEAST 7 BUSINESS DAYS NOTICE FOR ALL ENGINEERING INSPECTIONS. NOTICE OF 5 WORKING DAYS SHALL BE GIVEN WHERE A CERTIFICATE OF INSPECTION IS REQUIRED UNDER THE ENGINEER. WHERE INSPECTION CERTIFICATES ARE REQUIRED FOLLOWING EACH INSPECTION, A PRELIMINARY INSPECTION WILL BE UNDERTAKEN BY THE PROJECT ENGINEER AND A REGISTERED ENGINEER WILL CONDUCT AN ADDITIONAL FOLLOW-UP INSPECTION ONCE ALL DEFECTS ARE CORRECTED BY THE BUILDER AS HAVING BEEN RECTIFIED. IT IS THE RESPONSIBILITY OF THE BUILDER TO ENSURE SUFFICIENT TIME IS ALLOWED FOR IN PROGRAMME TO FACILITATE THE ABOVE.

G16. SITE INSPECTIONS DO NOT RELIEVE THE BUILDER OF RESPONSIBILITY FOR THE COMPLETENESS AND CORRECTNESS OF THEIR WORK.

G17. WHERE STRUCTURAL ELEMENTS ARE DESIGNED AND CERTIFIED BY OTHER PARTIES, THE CONTRACTOR SHALL OBTAIN WRITTEN CERTIFICATION PRIOR TO PROCEEDING WITH ANY CONSTRUCTION WORK WHICH WOULD PREVENT INSPECTION OR REMEDIAL WORKS TO BE UNDERTAKEN. ALL CERTIFICATIONS ARE TO BE ISSUED TO THE STRUCTURAL ENGINEER FOR REVIEW PRIOR TO WORK COMMENCING.

G18. THE CONTRACTOR SHALL ENSURE THAT ALL STRUCTURAL MEMBERS ARE PROTECTED FROM THE WEATHER AND THAT STRUCTURAL PROPERTIES ARE NOT IMPAIRED IN ANY WAY DURING THE CONSTRUCTION PERIOD.

G19. THE STRUCTURAL DRAWINGS DO NOT SHOW DETAILS OF ALL FIXTURES, SLEEVES, OPENINGS, ETC., REQUIRED BY THE VARIOUS TRADES. ALL SUCH DETAILS, INCLUDING OPENINGS FOR CONSTRUCTION FROM THE VARIOUS TRADES AND SHALL BE APPROVED BY THE ENGINEER BEFORE PROCEEDING WITH CONSTRUCTION.

G20. ALL PENETRATIONS AND SET DOWN'S SHOWN ON STRUCTURAL DRAWINGS ARE INDICATIVE ONLY. THE PENETRATIONS ARE CONFIRMED BY THE APPROPRIATE SUB-CONTRACTOR. FINAL DETAILS TO BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR APPROVAL.

G21. ALL PROPRIETARY PRODUCTS SPECIFIED ON THESE DRAWINGS SHALL BE USED STRICTLY IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATION. ALTERNATIVE PRODUCTS MAY ONLY BE USED WITH THE APPROVAL OF THE ENGINEER. FOLLOWING SUBMISSION OF EVIDENCE OF EQUIVALENCE.

G22. DETAILED SET OUT OF NEW WORKS ON SITE MUST BE UNDERGONE PRIOR TO DEMOLITION OF ANY EXISTING ASSETS. SITE MEASUREMENTS MUST BE UNDERTAKEN PRIOR TO DEMOLITION OF ANY EXISTING ASSETS TO VERIFY THAT THE DOCUMENTED EXTENT OF THE EXISTING ASSETS MATCHES THE ACTUAL EXTENT.

G23. THE BUILDER SHALL MAKE ALLOWANCE IN THEIR CONSTRUCTION PROGRAMME FOR ACOR TO RESPOND TO ALL REASONABLE GENERAL REQUESTS FOR INFORMATION WITHIN 5 WORKING DAYS.

G24. THE BUILDER SHALL MAKE ALLOWANCE IN THEIR CONSTRUCTION PROGRAMME FOR ACOR TO RESPOND TO SHOP DRAWING REVIEWS WITHIN 10 WORKING DAYS. ALL SUBMITTED SHOP DRAWINGS SHALL BE COMPLETE (I.E. NO OUTSTANDING QUERIES, DESIGN CHANGES PENDING ETC.), AND SHALL INCLUDE A 30 MODEL (IF/ OR RVT FORMAT) IN THE SUBMISSION. ACOR HAS AN ALLOWANCE FOR A SINGLE REVIEW OF SHOP DRAWINGS FOR EACH OF STEELWORK AND PRECAST ELEMENTS, AND THE BUILDER SHALL BE LIABLE FOR ADDITIONAL COSTS ARISING FROM INCOMPLETE OR MULTIPLE SHOP DRAWING REVIEWS.

## STRUCTURAL INSPECTION DURING CONSTRUCTION

SIN1. UNLESS AGREED OR SPECIFIED OTHERWISE, THE BUILDER IS REQUIRED TO HOLD CONSTRUCTION AND NOTIFY THE STRUCTURAL ENGINEER FOR INSPECTION AT THE FOLLOWING POINTS:

A) COMPLETED EXCAVATION, FORMWORK, REINFORCEMENT, MEMBRANES AND EMBEDMENTS PRIOR TO PLACING CONCRETE.

B) COMPLETED ERECTED STRUCTURAL, TIMBER FRAMING PRIOR TO COVERING (UNLESS COVERED BY AS1594 NATIONAL TIMBER FRAMING CODE).

C) COMPLETED ERECTED STRUCTURAL STEELWORK PRIOR TO COVERING.

SIN2. 48 HOURS OR AT LEAST 7 BUSINESS DAYS NOTICE IS REQUIRED FOR INSPECTION. ALL WORK TO BE INSPECTED MUST BE COMPLETED PRIOR TO THE TIME OF INSPECTION.

SIN3. SITE INSPECTIONS DO NOT RELIEVE THE BUILDER OF RESPONSIBILITY FOR THE COMPLETENESS AND CORRECTNESS OF HIS WORK.

SIN4. INSPECTIONS WILL BE PERIODIC AND REPRESENTATIVE AND WILL NOT NECESSARILY BE MADE OF ALL WORKS. ELECTION TO INSPECT OR OTHERWISE WILL BE AT THE ENGINEERS DISCRETION. THE BUILDER IS TO ALLOW TIME AND PROVIDE SITE ACCESS FOR THE INSPECTION TO TAKE PLACE AND IS TO HAVE A RESPONSIBLE SITE FOREMAN AVAILABLE TO RECEIVE ANY COMMENT OR DIRECTION FROM THE ENGINEER.

SIN5. WHERE STRUCTURAL ELEMENTS ARE DESIGNED AND CERTIFIED BY OTHER PARTIES, THE BUILDER SHALL OBTAIN WRITTEN CERTIFICATION PRIOR TO PROCEEDING WITH ANY CONSTRUCTION WHICH MAY PREVENT INSPECTION OR REMEDIAL WORKS BEING UNDERTAKEN TO THESE ITEMS.

SIN6. WHERE INSPECTION CERTIFICATES ARE REQUIRED FOLLOWING EACH INSPECTION, A PRELIMINARY INSPECTION WILL BE UNDERTAKEN BY THE PROJECT ENGINEER AND A REGISTERED ENGINEER WILL CONDUCT AN ADDITIONAL FOLLOW-UP INSPECTION ONCE ALL DEFECTS ARE CONFIRMED BY THE BUILDER AS HAVING BEEN RECTIFIED. IT IS THE RESPONSIBILITY OF THE BUILDER TO ENSURE SUFFICIENT TIME IS ALLOWED FOR IN THE PROGRAMME TO FACILITATE THE ABOVE.

## EARTHWORKS

E1. THE CONTRACTOR SHALL MAKE PROVISION FOR THE EFFECTIVE DIVERSION OR REMOVAL OF ALL SURFACE WATER FROM THE PREPARED SUBGRADE. FROM ANY SOURCE. TEMPORARY DRAINS SHALL BE INSTALLED TO REMOVE SURFACE WATER FROM THE EARTHWORKS SHALL BE PROVIDED BY THE CONTRACTOR.

E2. THE CONTRACTOR SHALL PROVIDE ALL REQUIRED ENVIRONMENTAL TREATMENT OF RUNOFF FROM THE CONSTRUCTION SITE.

E3. STRIP THE AREA OF THE BUILDING FOOTPRINT OF ANY GRASS, ROOT AFFECTED SOIL OR ANY OTHER DELETERIOUS MATERIAL TO A MINIMUM DEPTH OF 150mm. UNLESS NOTED OTHERWISE.

E4. PROOF ROLL THE EXPOSED SUBGRADE WITH A STATIC SMOOTH STEEL WHEELED ROLLER WITH A MINIMUM MASSES OF 10 TONNES. TO REVEAL SOFT, WEI, LOOSE, OR UNSTABLE AREAS. ALL SUCH AREAS WHICH DO NOT IMPROVE WITH ROLLING SHALL BE EXCAVATED AND REPLACED WITH APPROVED MATERIAL, COMPACTED TO 98% OF STANDARD MVD DRY DENSITY. RAISE THE SUBGRADE LEVEL FOR THE BUILDING FOOTPRINT TO THE DESIGN LEVEL USING APPROVED FILL MATERIAL. PLACED IN LAYERS NOT EXCEEDING 150mm AND COMPACTED TO 98% STANDARD MAXIMUM DRY DENSITY BEFORE BUILDING THE NEXT LAYER.

## EARTHWORKS NOTES CONTINUED

E5. MATERIAL WORK FROM SITE SHALL NOT BE USED AS ENGINEERING FILL MATERIAL WITHOUT APPROVAL FROM THE ENGINEER.

E6. SUBGRADE PREPARATION, FILL REPLACEMENT AND COMPACTION SHALL BE SUPERVISED BY A GEOTECHNICAL ENGINEER. THE FREQUENCY OF FIELD DENSITY TESTING SHALL BE IN ACCORDANCE WITH TYPE 1 EARTHWORKS AS NOTED IN TABLE 8.1 OF AS 3788.

E7. ALLOWANCE IS TO BE MADE FOR SOFT SPOTS: AT A MINIMUM, TO REPLACE 10% OF THE SURFACE AREA BELOW ALL CONCRETE AND ASPHALT PAVEMENTS, AND ALL CONCRETE SUBGRADE SLABS ON GROUND. TENDERER IS TO MAKE ALLOWANCE FOR THIS REPLACEMENT TO A DEPTH OF 600mm AND TO PROVIDE A RAY FOR ACTUAL QUANTITY.

E8. ONLY HANDHELD COMPACTION EQUIPMENT PERMITTED FOR USE OVER INSTALLED UNDERGROUND SERVICES UNLESS OTHERWISE APPROVED BY THE ENGINEER.

## FOUNDATION NOTES

F1. REFER TO THE GEOTECHNICAL REPORT NUMBER R4478g BY ENVIRONMENT CONSULTING PTY LTD DATED 07 JULY 2024.

F2. EDGE BEAMS / THICKENINGS / FOOTINGS TO BE FOUNDED 100 mm MINIMUM INTO NATURAL SANDY TO SILTY CLAY AT A MINIMUM DEPTH OF 1000mm BELOW NATURAL GROUND LEVEL WITH A MINIMUM BEARING CAPACITY AS FOLLOWS:

FOUNDATION TYPE	SAFE BEARING CAPACITIES (kPa)
STRIP FOOTING	250 kPa
PAD FOOTING	200 kPa
BORED PIER END BEARING	320 kPa
BORED PIER SIDE FRICION	32 kPa

IF A GEOTECHNICAL INVESTIGATION HAS NOT BEEN MADE, THE FOUNDATION CONDITIONS AND REACTIVITY CLASS ARE AN ASSUMPTION AND MUST BE CONFIRMED BY TRIAL EXCAVATIONS BY THE BUILDER.

FOUNDATION MATERIAL SHALL BE APPROVED FOR THIS BEARING PRESSURE BEFORE PLACING MEMBRANE, REINFORCEMENT OR CONCRETE.

F3. THE BUILDER IS TO ENGAGE A GEOTECHNICAL CONSULTANT OR SUITABLY QUALIFIED PERSONNEL TO ASSESS THE SUITABILITY OF THE FOUNDATION MATERIAL PRIOR TO PLACING CONCRETE.

F4. THE BUILDER IS TO IMPLEMENT ALL RECOMMENDATIONS OUTLINED IN THE GEOTECHNICAL REPORT AND RELEVANT RECOMMENDATIONS FROM BUILDING TECHNOLOGY FILE 19 (FORMERLY KNOWN AS CSIRO NOTE 10-91)


F5. SITE CLASSIFICATION IN ACCORDANCE WITH AS2870 IS CLASS- P

F6. REFER TO STRUCTURAL DESIGN LOAD NOTE L4 FOR SITE SUB-SOIL CLASS IN ACCORDANCE WITH AS1170.4.

F7. BEARING MATERIAL AT BASES OF PIERS TO BE CONFIRMED BY AN EXPERIENCED GEOTECHNICAL ENGINEER OR ENGINEERING GEOLOGIST.

F8. BUILDER IS TO MAKE APPROPRIATE ALLOWANCE FOR BUILDING CONCRETE TO ENSURE ABOVE FOUNDING DEPTHS ARE ALLOWED FOR BELOW ALL STRIP, INTERNAL, EXTERNAL, EDGE AND PAD FOOTINGS. BUILDER TO PROVIDE RATE TO ALL ADJACENT BUILDING CONCRETE QUANTITY REQUIRED. A MINIMUM DEPTH OF BUILDING OF 300mm BELOW ALL FOOTINGS SHOULD BE ALLOWED FOR BY THE TENDERER.

F9. UNLESS NOTED OTHERWISE, WHEREVER A NEW FOOTING IS LOCATED CLOSE TO AN EXCAVATION, BATTER, EXISTING FOOTING, EXISTING SERVICE OR NEW SERVICE WHICH IS DEEPER THAN THE NEW FOOTING, THE EXCAVATION OR THE NEW FOOTING SHALL BE DEEPENED AND BACKFILLED WITH BUILDING CONCRETE AS INDICATED BELOW.



F10. THE BASE OF ALL SERVICE TRENCHES SHALL BE WORKED UP FROM THE BUILDING. TRENCHES SHALL BE BACKFILLED WITH CLAY IN THE TOP 300mm WITHIN 1.5m OF THE BUILDING. THE CLAY USED FOR BACKFILLING SHALL BE COMPACTED.

F11. WHERE PIPES PASS UNDER THE FOOTING SYSTEM, THE TRENCH SHALL BE BACKFILLED FULL DEPTH WITH CLAY OR CONCRETE TO RESTRICT THE INGRESS OF WATER BENEATH THE FOOTING SYSTEM.

F12. SET OUT TO IN AS 2870 CL 5.6 INCLUDING MASONRY DETAILING, VARIATIONS IN FOUNDATION MATERIAL, DRAINAGE AND PLUMBING REQUIREMENTS.

F13. ALL FOOTINGS SHALL BE LOCATED CENTRALLY UNDER WALLS AND COLUMNS UNLESS NOTED OTHERWISE.

F14. DO NOT BACKFILL RETAINING WALLS (OTHER THAN CANTILEVER WALLS) UNTIL FLOOR CONSTRUCTION AT TOP AND BOTTOM IS COMPLETED.

F15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ANY EXCAVATION IN A STABLE CONDITION WITHOUT ADVERSELY AFFECTING SURROUNDING PROPERTY INCLUDING SERVICES. THIS INCLUDES OBTAINING ALL NECESSARY APPROVALS FOR SHORING AND ANCHOR SYSTEMS.

F16. ANY OVER EXCAVATION SHALL BE BACKFILLED WITH CONCRETE GRADE N15 FOUNDATIONS ADJACENT TO SERVICES ETC. SHALL BE EXTENDED DOWN SUCH THAT THE INFLUENCE LINE OF THE FOUNDATION IS BELOW THE ADJACENT SERVICE.

## CONCRETE NOTES

C1. ALL WORKMANSHIP AND MATERIALS SHALL COMPLY WITH AS 3600 CURRENT EDITIONS WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.

C2. ALL CONCRETE SUPPLY SHALL COMPLY WITH AS1379 CONCRETE PROPERTIES AND COVER TO REINFORCING:

ELEMENTS	COVER (mm)	f <sub>ck</sub> (MPa)	(28 DAYS)	MAX 56 DAY SHRINKAGE
BORED PILES	70	8	50	800
SLAB ON GROUND	EXTERNAL: 70 INTERNAL: 70	8 50	32	800
STRIP FOOTINGS	70	50	40	800
PAD FOOTINGS	50	40	800	

		EXTERNAL	120	620		
BEAMS		EXTERNAL	N/A	N/A	N/A	N/A
		INTERNAL	N/A	N/A		
COLUMN		EXTERNAL	40	40	40	800
		INTERNAL	40	40		
		EXTERNAL	40	40		

COLUMNS	EXTERNAL: 40 INTERNAL: 40 <td>40</td> <td>800</td>	40	800
CONCRETE WALLS	EXTERNAL: 40 INTERNAL: 20 <td>40</td> <td>800</td>	40	800

PRECAST WALLS	EXTERNAL: N/A INTERNAL: N/A	N/A N/A	N/A	N/A
---------------	--------------------------------	------------	-----	-----

MAXIMUM AGGREGATE SIZE = 20  
SLUMP DURING PLACEMENT = 80  
EXPOSURE CLASSIFICATION AS PER STRUCTURAL DESIGN LOAD NOTE L7.

C3. COVER TO CONCRETE TO BE 50mm.

C4. CEMENT TO BE TYPE SL TO AS 3672 UNLESS NOTED OTHERWISE THIS IS A MODIFIED TYPE OF CEMENT. SEE AGGREGATE SPECIFICATION.

C5. NO BREXCA TYPE AGGREGATE IS TO BE USED.

C6. NO ADMIXTURES SHALL BE USED IN CONCRETE UNLESS NOTED IN WRITING BY THE ENGINEER.

C7. PROJECT ASSESSMENT OF CONCRETE SHALL BE CARRIED OUT IN ACCORDANCE WITH AS 1979.

C8. PROJECT CONTROL TESTING SHALL BE CARRIED OUT IN ACCORDANCE WITH AS1979. A META-REGISTERED TESTING LABORATORY. SAMPLES SHALL BE TAKEN FOR TESTING OF SLUMP, COMPRESSIVE STRENGTH AND ANY OTHER TEST SPECIFIED.

SLUMP SHALL BE SAMPLED FOR EACH TRUCK AT THE TIME OF POURING.

THE MINIMUM FREQUENCY OF SAMPLING FOR COMPRESSIVE TESTING OF EACH TYPE AND GRADE SHALL BE IN ACCORDANCE WITH THE FOLLOWING TABLE:

NUMBERS OF BATCHES PER DAY	NUMBERS OF SAMPLES (4 CYLINDERS FOR POST TENSIONED CONCRETE)
1 TO 5	1 SAMPLE
6 TO 10	2 SAMPLES
11 TO 20	3 SAMPLES
21 TO 30	4 SAMPLES
FOR EACH ADDITIONAL 10	1 ADDITIONAL SAMPLE

SAMPLES SHALL BE TESTED FOR COMPRESSIVE STRENGTH AS FOLLOWS:  
ONE CYLINDER AT 3 DAYS (POST TENSIONED CONCRETE ONLY)  
ONE CYLINDER AT 7 DAYS  
TWO CYLINDERS AT 28 DAYS

C9. BEAM DEPTHS ARE WRITTEN FIRST AND INCLUDE SLAB THICKNESS. UNLESS NOTED/ DETAILED OTHERWISE ON DRAWINGS.

C10. SIZES OF CONCRETE ELEMENTS DO NOT INCLUDE THICKNESS OF APPLIED FINISHES.

C11. NO HOLES, CHASES OR EMBEDMENT OF PIPES OTHER THAN THOSE SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE MADE IN CONCRETE MEMBERS WITHOUT PRIOR APPROVAL OF THE ENGINEER.

C12. CONSTRUCTION JOINTS SHALL BE PROPERLY FORMED AND USE ONLY WHERE SHOWN OR SPECIFICALLY APPROVED BY THE ENGINEER.

C13. ALL CONCRETE COLUMNS ARE TO BE POURED A MINIMUM OF 4 HOURS PRIOR TO SLAB OR BEAM POUR.

C14. DRIP GROOVES ARE TO BE PROVIDED AT ALL EXPOSED EDGES. COVER TO REINFORCEMENT IS TO BE MAINTAINED.

C15. CONDUITS, PIPES AND THE LIKE SHALL NOT BE PLACED WITHIN THE CONCRETE COVER.

C16. ALL CONCRETE (INCLUDING FOOTINGS AND SLABS ON GROUND) SHALL BE MECHANICALLY VIBRATED TO ACHIEVE FULL COMPACTION.

## CONCRETE NOTES CONTINUED

C17. SAWN JOINTS ARE TO BE CUT AFTER THE CONCRETE HAS SUFFICIENTLY HARDENED THAT WILL NOT BE DAMAGED BY THE SAWING BUT BEFORE SHRINKAGE CRACKING CAN OCCUR.

C18. CURING OF JOINTS SHALL BE IN ACCORDANCE WITH AS3600 AND SHALL COMMENCE WITHIN 2 HOURS OF FINISHING OPERATIONS. CURING SHALL BE BY CONTINUAL SATURATION WITH POTABLE WATER FOR 7 DAYS FOLLOWED BY PREVENTION OF MOISTURE LOSS FOR THE NEXT 4 DAYS USING POLYTHENE SHEETING OR WET HESSIAN PROTECTED FROM WIND OR TRAFFIC AND THEN ALLOWING GRADUAL DRYING OUT. CURING COMPOUNDS MAY BE USED PROVIDED THAT THEY COMPLY WITH AS3678 AND DO NOT AFFECT FLOOR FINISHES. THE COMPATIBILITY OF CURING COMPOUNDS WITH PROPOSED APPLIED FINISHES SHALL BE VERIFIED PRIOR TO APPLICATION. CURING COMPOUNDS ARE TO BE APPLIED UNIFORMY IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATION. PVA BASED CURING COMPOUNDS ARE NOT ACCEPTABLE.

C19. ALIPHATIC ALCOHOL WHEN SHADE TEMPERATURE EXCEEDS 35° C SPRAY THE EXPOSED SURFACE OF CONCRETE SLAB DURING THE PLACING AND FINISHING OPERATION WITH A FINE FLM OF APPROVED ALIPHATIC ALCOHOL. REPEAT THE SPRAY IF THE SPRAYED SURFACE HAS BEEN REWORKED.

C20. ENSURE ADEQUATE SUPPLY OF ALIPHATIC ALCOHOL ON SITE BEFORE COMMENCING CONCRETE WORK.

C21. SLIP JOINTS ARE TO BE USED ON ALL LOAD BEARING MASONRY WALLS. USE TWO LAYERS OF GALVANIZED ZINC PLATE WITH GRAPHITE GREASE BETWEEN IN INTERNAL SKINS. TWO LAYERS OF STAINLESS STEEL WITH GRAPHIC GREASE BETWEEN EXTERNAL SKINS. PROVIDE MORTAR LAYERS STRIP AS REQUIRED.

C22. NON LOAD BEARING MASONRY SHALL BE SEPARATED FROM THE SOFFIT OF SLABS AND BEAMS BY 20mm.

C23. MASONRY WALLS MUST NOT BE CONSTRUCTED ON SUSPENDED CONCRETE UNTIL ALL TEMPORARY SUPPORTS ARE REMOVED AND ALL MASONRY TO BE LAD HAS BEEN STACKED ADJACENT TO PROPOSED POSITION.

C24. CEMENT STABILISED BACKFILL MATERIAL SHALL CONSIST OF BASE COURSE MATERIAL, OR OTHER SUITABLE MATERIAL APPROVED BY THE ENGINEER. STABILISED IN THE PROPORTION OF 10% OF TYPE GP PORTLAND CEMENT TO ONE CUBIC METER OF BACKFILL. BACKFILL MATERIAL SHALL BE OF CONCRETE STABILISATION SHALL BE CLEAN AND POTABLE.

### TYPICAL OPENINGS IN SLABS


C25. LOCATION OF ALL OPENINGS TO BE TO THE APPROVAL OF ACOR.

C26. FOR OPENINGS LESS THAN 300 x 300mm BARS TO BE RE-ARRANGED AROUND HOLE.


C27. FOR PENETRATIONS GREATER THAN 1000 x 1000mm REFER TO ENGINEERS PLANS. WHERE OPENINGS ARE NOT DETAILED, CONTACT ENGINEER IMMEDIATELY.

C28. TOP BARS FOR EVERY TWO BARS THAT ARE TERMINATED BY OPENINGS, ADD ONE BAR EACH SIDE USING SAME GRADE AND SIZE OF REINFORCEMENT. WHERE NO TOP BARS ARE SHOWN, ADD 1/4th TOP EACH SIDE OF OPENING.

C29. FOR PENETRATIONS GREATER THAN 300 x 300mm BUT LESS THAN 1000 x 1000mm USE DETAILS BELOW.



C30. FOR PENETRATIONS GREATER THAN 1000 x 1000mm USE DETAILS BELOW.




C31. LOCATION OF HOLES TO BE TO THE APPROVAL OF THE STRUCTURAL ENGINEER.

C32. FOR PIPES UP TO 100mm DIAMETER, ADD ONE ROW OF TIES EACH SIDE OF PIPE.

C33. FOR PIPES 90mm TO 120mm DIAMETER, ADD TWO ROWS OF TIES EACH SIDE OF PIPE AND 1/4th HORIZONTAL BAR 150mm LONG TOP AND BOTTOM OF PIPE AT EVERY VERTICAL TIE LEG.

C34. FOR HOLES GREATER THAN 100mm REFER TO ENGINEERS DETAILS. WHERE PENETRATIONS ARE NOT DETAILED, CONTACT STRUCTURAL ENGINEER IMMEDIATELY.

C35. LOCATION OF HOLES TO BE TO THE APPROVAL OF THE STRUCTURAL ENGINEER.



C36. THESE NOTES ARE INTENDED AS A GUIDE. THERE IS ALWAYS A POSSIBILITY OF SITE CONDITIONS REQUIRING VARIATION TO THESE PROCEDURES. IN SUCH CASES, THE STRUCTURAL ENGINEER MUST BE CONSULTED.

C37. PORTLAND CEMENT CONTENT SHOULD BE REDUCED BY A MINIMUM 3% MEASURED BY MASS ACROSS ALL CONCRETE USED IN THE PROJECT COMPARED TO A REFERENCE CASE. FOR DETAILS OF DEFINING THE REFERENCE, REFER TO BSH SECTION 5.6.4.

C38. MIX WATER USED FOR ALL CONCRETE IN THE PROJECT MUST BE DEMONSTRATED TO CONTAIN AT LEAST 50% CAPTURED OR RECLAIMED WATER. REFER TO BSH SECTION 5.6.4 FOR DETAILS.

C39. AT LEAST 25% OF FINE AGGREGATE (SAND) INPUTS IN THE CONCRETE ARE MANUFACTURED SAND OR OTHER ALTERNATIVE MATERIALS (MEASURED BY MASS ACROSS ALL CONCRETE MIXES IN THE PROJECT) PROVIDED THAT THE USE OF SUCH MATERIALS DOES NOT INCREASE THE USE OF PORTLAND CEMENT MORE THAN 50% OF CONCRETE.

ACCEPTABLE TYPES OF ALTERNATIVE COURSE AND FINE AGGREGATE ARE LISTED IN THE CEMENT CONCRETE AND AGGREGATE AUSTRALIAN PUBLICATIONS. USE OF RECYCLED IN CONSTRUCTION AND GUIDE TO THE SPECIFICATION AND USE OF MANUFACTURED SAND IN CONCRETE.

C40. JOINTS AS DETAILED, UNLESS NOTED OTHERWISE.

C41. IN CASE OF DOUBT - ASK.

C42. BOND BREAKER TO BE TWO (2) 10mm UNIFORM COATS OF BITUMEN EMULSION ALL OVER THE EXPOSED SURFACE AND ON ENDS.

C43. DOWELS AND THE BARS TO MEET STRIPPING REQUIREMENTS OF STRUCTURAL GRADE STEEL IN ACCORDANCE WITH AS 1302. DOWELS AND THE BARS SHALL BE:

- A) STRAIGHT.
- B) TO LENGTH SPECIFIED.
- C) CLEAN AND FREE FROM MILL SCALE, RUST AND OIL.
- D) SAWN TO LENGTH NOT CROPPED.

C44. JOINT TO BE SAWN AS SOON AS CONCRETE HAS HARDENED SUFFICIENTLY THAT IT WILL NOT BE DAMAGED BY SAWING. IF AN UNPLANNED CRACK OCCURS THE CONTRACTOR SHALL REPLACE THE WHOLE SLABS EITHER SIDE OF THE CRACK, UNLESS DIRECTED OTHERWISE.

C45. DIMENSIONS OF SEALANT RESERVOIR DEPENDENT ON THE SEALANT TYPE ADOPTED. ENGINEERS APPROVAL TO BE OBTAINED FOR SEALANT. RESERVOIR DIMENSIONS AND DETAIL PROPOSED BY THE CONTRACTOR. REFER TO DETAILS 'A' AND 'B' FOR TYPICAL ARRANGEMENT AND SEALANT.

C46. REFER TO COMPACTING NOTES FOR PREPARATION OF SUB-BASE AND SUB-GRADE.

## STIFFENED RAFT SLAB NOTES

SRI. THE RAFT SLABS ARE TO BE CONSTRUCTED IN ACCORDANCE WITH AS 2870-2011 'RESIDENTIAL SLABS AND FOOTINGS' AND ACCEPTED TENDERING PRACTICE. PARTICULAR ATTENTION IS DRAWN TO SECTIONS 5 AND 6 OF THE CODE.

SRI2. THESE SLABS HAVE BEEN DESIGNED IN ACCORDANCE WITH AS2870 'RESIDENTIAL SLABS & FOOTINGS'. PARTICULAR ATTENTION IS DRAWN TO CLAUSE 1.3.3 APPENDIX C OF AS2870, WHICH REFER TO THE PROBABILITIES OF THE VARIOUS CATEGORIES OF DAMAGE OCCURRING.

SRI3. TERMITES PROTECTION, IF REQUIRED BY THE BUILDING SURVEYOR, SHALL BE INSTALLED IN ACCORDANCE WITH AS 3661-1:98 AND OTHER RELEVANT AUSTRALIAN STANDARDS AND LOCAL AUTHORITY REQUIREMENTS.

SRI4. ALL VEGETATION AND TOPSOIL SHALL BE REMOVED FROM THE SLAB AREA.

SRI5. THE GROUND BELOW SLAB SHALL BE PROOF ROLLED WITH A HEAVY DUTY ROLLER. PRIOR TO ANY COMPACTED FILLING BEING PLACED, ANY HOT SPOTS ENCOUNTERED SHALL BE DUG OUT AND REPLACED WITH COMPACTED CRUSHED ROCK OR APPROVED FILL IN ACCORDANCE WITH AS 2870 AND AS 3796.

SRI6. FILLING USED IN THE CONSTRUCTION OF SLAB EXCEPT WHERE THE SLAB IS SUPERSEDED TO SILTY CLAY AT A MINIMUM DEPTH OF 1000mm BELOW NATURAL GROUND LEVEL WITH A MINIMUM BEARING CAPACITY AS FOLLOWS:


FOUNDATION TYPE	SAFE BEARING CAPACITIES (kPa)
STRIP FOOTING	250 kPa
PAD FOOTING	200 kPa
BORED PIER END BEARING	320 kPa
BORED PIER SIDE FRICION	32 kPa

SRI7. WHERE DEPTH OF CONTROLLED FILL IS THICKER THAN THAT SPECIFIED ABOVE, FILL MATERIAL SHALL BE SPREAD AND COMPACTED IN UNIFORM LAYERS NOT EXCEEDING 0.2m THICK. TOP SURFACE LAYER SHALL BE COMPACTED TO MINIMUM 98% STANDARD DRY DENSITY DETERMINED BY METHODS IN ACCORDANCE WITH AS 1289. LOWER LAYERS SHALL BE COMPACTED TO 95% STANDARD DRY DENSITY. THE MOISTURE CONTENT OF THE FILL MATERIAL SHALL BE ADJUSTED TO WITHIN 2% OF THE OPTIMUM MOISTURE CONTENT DURING COMPACTION TO ENSURE THAT THE SPECIFIED COMPACTION IS OBTAINED.


SRI8. A 0.3mm POLYTHENE MEMBRANE SHALL BE PLACED UNDER SLAB AND RISBS IN ACCORDANCE WITH SECTION 5.3.3 OF AS 2870. LAP SHEETS BY 200mm MINIMUM AT JOINTS AT TAPED AT ALL SERVICE PENETRATIONS, LAPS & PUNCTURES.

SRI9. EXCAVATIONS






EXTERNAL WORKS GENERAL ARRANGEMENT PLAN  
SCALE: 1:100



TYPE A AND TYPE B - PERMANENT BATTER  
SCALE: 1:20


Issue	Description	Date	Drawn	Approved
A	DRAFT SCHEMATIC DESIGN	15.10.2024	TL	DL
B	SCHEMATIC DESIGN	26.10.2024	DL	DL
C	DO ENGINEERING PUG PRESENTATION	27.07.2025	AJ	DL
D	DO ENGINEERING PUG PRESENTATION	14.02.2025	AJ	DL
E	DRAFT DESIGN DEVELOPMENT	07.02.2025	DL	DL

Drawing Key




PRINT IN COLOUR

North



Scale



Client



Managing Contractor



Architect

architectus

Project

WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL

DEAN STREET, NORTH  
TAMWORTH NSW 2340

NOT FOR CONSTRUCTION



ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2055  
T: +61 2 9438 5098

CONSULTANTS

Drawing Title

STRUCTURAL

EXTERNAL WORKS GENERAL ARRANGEMENT PLAN

Drawn

TL

Designed

CMR

C.A. Check

DL

Date

15.10.2024

Scale

AS indicated

Project No.

NA230258

Drawing No.


WCP-ACR-DRW-STR-TAM-12B-0000100

Issue

E



Issue	Description	Date	Drawn	Approved
A	DRAFT SCHEMATIC DESIGN	15.10.2024	TL	DL
B	SCHEMATIC DESIGN	26.10.2024	DL	DL
C	DO ENGINEERING PUG PRESENTATION	21.07.2023	AJ	DL
D	DO ENGINEERING PUG PRESENTATION	14.02.2025	AJ	DL
E	DRAFT DESIGN DEVELOPMENT	07.03.2025	DL	DL



NOTE INSTALLATION OF BASKETS  
(INCLUDING SPECIFICATION OF ROCK FILL)  
TO BE CARRIED OUT IN ACCORDANCE WITH  
GEOFABRICS SPECIFICATIONS AND DETAILS


#### GABION RETAINING WALL - MAX 1.5m

SCALE 1:20

NOTE GEOTECHNICAL INVESTIGATION TO BE CARRIED OUT TO CONFIRM DESIGN ASSUMPTIONS AND CONFIRM SUITABILITY OF GABION CAGE RETAINING WALL ON EXISTING GROUND AND SLOPE. FINAL DESIGN OF WALL TBC UPON RECEIPT OF GEOTECHNICAL REPORT AND ADVICE.

ASSUMED IN-SITU MATERIAL - 150 kPa ALLOWABLE BEARING PRESSURE, INTERNAL FRICTION ANGLE  $\phi = 30^\circ$   
ASSUMED RETAINED MATERIAL - INTERNAL FRICTION ANGLE  $\phi = 30^\circ$   
ASSUMED INFILL MATERIAL - CONTROLLED FILL CLASS

PROPERTIES AND COMPOSITION OF THE IN-SITU MATERIAL, RETAINED MATERIAL AND INFILL MATERIAL TO BE INSPECTED / CONFIRMED BY A SUITABLY QUALIFIED GEOTECHNICAL ENGINEER PRIOR TO CONSTRUCTION OF ANY RETAINING WALLS.



NOTE INSTALLATION OF BASKETS  
(INCLUDING SPECIFICATION OF ROCK FILL)  
TO BE CARRIED OUT IN ACCORDANCE WITH  
GEOFABRICS SPECIFICATIONS AND DETAILS


#### GABION RETAINING WALL - MAX 2.0m

SCALE 1:20

NOTE GEOTECHNICAL INVESTIGATION TO BE CARRIED OUT TO CONFIRM DESIGN ASSUMPTIONS AND CONFIRM SUITABILITY OF GABION CAGE RETAINING WALL ON EXISTING GROUND AND SLOPE. FINAL DESIGN OF WALL TBC UPON RECEIPT OF GEOTECHNICAL REPORT AND ADVICE.

ASSUMED IN-SITU MATERIAL - 150 kPa ALLOWABLE BEARING PRESSURE, INTERNAL FRICTION ANGLE  $\phi = 30^\circ$   
ASSUMED RETAINED MATERIAL - INTERNAL FRICTION ANGLE  $\phi = 30^\circ$   
ASSUMED INFILL MATERIAL - CONTROLLED FILL CLASS

PROPERTIES AND COMPOSITION OF THE IN-SITU MATERIAL, RETAINED MATERIAL AND INFILL MATERIAL TO BE INSPECTED / CONFIRMED BY A SUITABLY QUALIFIED GEOTECHNICAL ENGINEER PRIOR TO CONSTRUCTION OF ANY RETAINING WALLS.



NOTE INSTALLATION OF BASKETS  
(INCLUDING SPECIFICATION OF ROCK FILL)  
TO BE CARRIED OUT IN ACCORDANCE WITH  
GEOFABRICS SPECIFICATIONS AND DETAILS


#### GABION RETAINING WALL - MAX 2.5m

SCALE 1:20

NOTE GEOTECHNICAL INVESTIGATION TO BE CARRIED OUT TO CONFIRM DESIGN ASSUMPTIONS AND CONFIRM SUITABILITY OF GABION CAGE RETAINING WALL ON EXISTING GROUND AND SLOPE. FINAL DESIGN OF WALL TBC UPON RECEIPT OF GEOTECHNICAL REPORT AND ADVICE.

ASSUMED IN-SITU MATERIAL - 150 kPa ALLOWABLE BEARING PRESSURE, INTERNAL FRICTION ANGLE  $\phi = 30^\circ$   
ASSUMED RETAINED MATERIAL - INTERNAL FRICTION ANGLE  $\phi = 30^\circ$   
ASSUMED INFILL MATERIAL - CONTROLLED FILL CLASS

PROPERTIES AND COMPOSITION OF THE IN-SITU MATERIAL, RETAINED MATERIAL AND INFILL MATERIAL TO BE INSPECTED / CONFIRMED BY A SUITABLY QUALIFIED GEOTECHNICAL ENGINEER PRIOR TO CONSTRUCTION OF ANY RETAINING WALLS.



NOTE INSTALLATION OF BASKETS  
(INCLUDING SPECIFICATION OF ROCK FILL)  
TO BE CARRIED OUT IN ACCORDANCE WITH  
GEOFABRICS SPECIFICATIONS AND DETAILS

#### GABION RETAINING WALL - MAX 3.0m


SCALE 1:20

NOTE GEOTECHNICAL INVESTIGATION TO BE CARRIED OUT TO CONFIRM DESIGN ASSUMPTIONS AND CONFIRM SUITABILITY OF GABION CAGE RETAINING WALL ON EXISTING GROUND AND SLOPE. FINAL DESIGN OF WALL TBC UPON RECEIPT OF GEOTECHNICAL REPORT AND ADVICE.

ASSUMED IN-SITU MATERIAL - 150 kPa ALLOWABLE BEARING PRESSURE, INTERNAL FRICTION ANGLE  $\phi = 30^\circ$   
ASSUMED RETAINED MATERIAL - INTERNAL FRICTION ANGLE  $\phi = 30^\circ$   
ASSUMED INFILL MATERIAL - CONTROLLED FILL CLASS

PROPERTIES AND COMPOSITION OF THE IN-SITU MATERIAL, RETAINED MATERIAL AND INFILL MATERIAL TO BE INSPECTED / CONFIRMED BY A SUITABLY QUALIFIED GEOTECHNICAL ENGINEER PRIOR TO CONSTRUCTION OF ANY RETAINING WALLS.


Drawing Key



PRINT IN COLOUR

North

Scale



Client



Managing Contractor



Architect

architectus

Project

WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL

DEAN STREET, NORTH  
TAMWORTH NSW 2340

NOT FOR CONSTRUCTION



ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2055  
T: +61 2 9438 5098

CONSULTANTS

Drawing Title

STRUCTURAL

GABION WALL DETAILS - SHEET 1

Drawn

TL

Designed

CMR

C.A. Check

DL

Date

15.10.2024

Scale @ A0

1:20

Project No.

NA230258


Drawing No.

WCP-ACR-DRW-STR-TAM-12B-0000110

Issue

E



SCALE: 1 : 100

150	ALL SLABS ON GROUND TO BE MIN. 150/200mm THICK U.N.O
S.O.G.	ALL SLABS ON GROUND ARE TO BE POURED ON 300mm WATERPROOF MEMBRANE OVERLAYING A 80mm LAYER OF 20mm SINGLE SIZED FREE DRAINING COMPACTED GRANULAR MATERIAL.
200	SLAB TO BE REINFORCED WITH S162 MESH TOP AND BOTTOM.
S.O.G.	f <sub>c</sub> =32MPa.

DJ DENOTES DOWEL JOINT. REFER DETAIL.

- REFER TO ARCHITECTURAL DRAWINGS FOR ALL CONCRETE SETOUT INFORMATION.
- ALL FALLS, SETDOWNS & WATERPROOFING ARE TO ARCHITECT'S DETAILS U.N.O.
- UNLESS NOTED OTHERWISE ALL WET AREA SETDOWNS ARE TO BE A MAXIMUM 50mm.
- NON STRUCTURAL KERBS AND HOBBS ARE NOT SHOWN. REFER TO ARCHITECTURAL DRAWINGS FOR EXTENT AND LOCATIONS.
- VERTICAL JOINTS IN WALLS ARE TO MATCH SLAB JOINT LOCATIONS.

NOTE:  
ALLOW 150kg/m<sup>3</sup> FOR ALL GROUND BEAMS U.N.O.  
ASSUMED STIFF CLAY WITH MINIMUM BEARING CAPACITY 320KPA TO BE CONFIRMED BY GEOTECHNICAL ENGINEER\* PILES MAY BE REQUIRED IF ALLOWABLE BEARING CAPACITY IS CAN NOT BE ACHIEVED

SLAB THICKENING SCHEDULE								
MARK	LENGTH (A) x WIDTH (B) x DEPTH (C)			REINFORCEMENT				COMMENTS
	A	B	C	LAY 1ST	LAY 2ND	LAY 3RD	LAY 4TH	
TH1	600	600	400					

SLAB THICKENING SCHEDULE								
MARK	LENGTH (A) x WIDTH (B) x DEPTH (C)			REINFORCEMENT				COMMENTS
	A	B	C	LAY 1ST	LAY 2ND	LAY 3RD	LAY 4TH	
TH1	600	600	400					

PRINT IN COLOUR 

Architect

**architectus**

DEAN STREET, NORTH  
TAMWORTH NSW 2340

**NOT FOR CONSTRUCTION**


**ACOR Consultants Pty Ltd**  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T: +61 2 9438 5098




Drawing Title  
STRUCTURAL  
GROUND FLOOR GENERAL ARRANGEMENT PLAN

Drawn TL	Designed CMR	Q.A. Check DL	Date 15.10.2024	Scale @ A0 1 : 100
Project No. NA230258		Drawing No. WCP-ACR-DRW-STR-TAM-12B-0000200		Issue E






LEVEL 01 GENERAL ARRANGEMENT PLAN  
SCALE: 1 : 100

STEEL COLUMN SCHEDULE		
MARK	SIZE	COMMENTS
SC1	89 x 89 x 5 SHS	
SC2	100 x 100 x 5 SHS	
SC3	150 x 150 x 6 SHS	


STEEL FRAMING SCHEDULE		
MARK	SIZE	COMMENTS
BEAMS & RAFTER		
R1	250UB31.4	
R2	250 PFC	
R3	200UB16.2	
SB1	200 PFC	
SB3	250UB31.4	
PURLINS		
P1	Z20019	PURLINS AT 900 MAX. CTS. WITH 2 ROWS OF BRIDGING AND MIN. 900 LAPPING
P2	C15015	PURLINS AT 900 MAX. CTS. WITH 2 ROWS OF BRIDGING.
P3	C20015	PURLINS AT 900 MAX. CTS. WITH 2 ROWS OF BRIDGING.
STRUT & BRACING		
BR1	16 ROD	ROOF BRACING WITH TURNBUCKLES.
ST1	89 x 89 x 5 SHS	
ST2	100 x 100 x 5 SHS	
ST3	125 x 125 x 4 SHS	
ST4	125 x 125 x 5 SHS	
ST5	150 x 150 x 6 SHS	
VB1	89 x 89 x 5 SHS	

NOTE:  
ALL EXTERNAL STEELWORK TO BE HOT DIPPED GALVANISED U.N.O.




Issue	Description	Date	Drawn	Approved
A	DRAFT SCHEMATIC DESIGN	15.10.2024	TL	DL
B	SCHEMATIC DESIGN	25.10.2024	DL	DL
C	DO ENGINEERING PUG PRESENTATION	27.07.2025	AJ	DL
D	DO ENGINEERING PUG PRESENTATION	14.02.2025	AJ	DL
E	DRAFT DESIGN DEVELOPMENT	07.03.2025	DL	DL

Drawing Key




PRINT IN COLOUR

North



Scale



Client



Managing Contractor



Architect

architectus

Project

WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL

DEAN STREET, NORTH  
TAMWORTH NSW 2340

NOT FOR CONSTRUCTION



ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T: +61 2 9438 5098

CONSULTANTS

Drawing Title

STRUCTURAL  
LEVEL 01 GENERAL ARRANGEMENT PLAN

Drawn

TL

Designed

CMR

C.A. Check

DL

Date

Scale @ A0

1: 100

Project No.

NA230258


Drawing No.

WCP-ACR-DRW-STR-TAM-128-0000210

Issue

E






ROOF FRAMING GENERAL ARRANGEMENT PLAN

SCALE: 1 : 100  
ALL PURLINS TO BE TYPE 'P1' UNLESS NOTED OTHERWISE

STEEL COLUMN SCHEDULE		
MARK	SIZE	COMMENTS
SC1	89 x 89 x 5 SHS	
SC2	100 x 100 x 5 SHS	
SC3	150 x 150 x 6 SHS	


STEEL FRAMING SCHEDULE		
MARK	SIZE	COMMENTS
BEAMS & RAFTER		
R1	250UB31.4	
R2	250 PFC	
R3	200UB18.2	
SB1	200 PFC	
SB3	250UB31.4	
PURLINS		
P1	Z20019	PURLINS AT 900 MAX. CTS. WITH 2 ROWS OF BRIDGING AND MIN. 900 LAPPING
P2	C15015	PURLINS AT 900 MAX. CTS. WITH 2 ROWS OF BRIDGING.
P3	C20015	PURLINS AT 900 MAX. CTS. WITH 2 ROWS OF BRIDGING.
STRUT & BRACING		
BR1	16 ROD	ROOF BRACING WITH TURNBUCKLES.
ST1	89 x 89 x 5 SHS	
ST2	100 x 100 x 5 SHS	
ST3	125 x 125 x 5 SHS	
ST4	125 x 125 x 5 SHS	
ST5	150 x 150 x 6 SHS	
VB1	89 x 89 x 5 SHS	

NOTE:  
ALL EXTERNAL STEELWORK TO BE HOT DIPPED GALVANISED U.N.O.




Issue	Description	Date	Drawn	Approved
A	DRAFT SCHEMATIC DESIGN	15.10.2024	TL	DL
B	SCHEMATIC DESIGN	25.10.2024	CG	DL
C	DO ENGINEERING PUG PRESENTATION	27.07.2025	AJ	DL
D	DO ENGINEERING PUG PRESENTATION	14.02.2025	AJ	DL
E	DRAFT DESIGN DEVELOPMENT	07.03.2025	CG	DL

Drawing Key




PRINT IN COLOUR

North



Scale



Client



Managing Contractor



Architect

architectus

Project

WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL

Client

DEAN STREET, NORTH  
TAMWORTH NSW 2340

NOT FOR CONSTRUCTION



ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T: +61 2 9438 5098

CONSULTANTS

Drawing Title

STRUCTURAL  
ROOF FRAMING GENERAL ARRANGEMENT PLAN

Drawn

TL

Designed

CMR

G.A. Check

DL

Date

15.10.2024

Scale @ A0

1:100

Project No.

NA230258

Drawing No.



WCP-ACR-DRW-STR-TAM-128-0000300

Issue


E



Issue	Description	Date	Drawn	Approved
A	DRAFT SCHEMATIC DESIGN	15.10.2024	TL	DL
B	SCHEMATIC DESIGN	25.10.2024	DL	DL
C	DO ENGINEERING PUG PRESENTATION	27.07.2023	AJ	DL
D	DO ENGINEERING PUG PRESENTATION	14.02.2025	AJ	DL
E	DRAFT DESIGN DEVELOPMENT	07.03.2025	DL	DL



PRINT IN COLOUR



Project:  
WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL  
DEAN STREET, NORTH  
TAMWORTH NSW 2340

**NOT FOR CONSTRUCTION**

**AcOR**  
CONSULTANTS

ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T: +61 2 9438 5098

Drawing Title:  
STRUCTURAL  
ROOF FRAMING ELEVATIONS - SHEET 1

Drawn: TL	Designed: CMR	Q.A. Check: DL	Date: 15.10.2024	Scale @ A0: 1:100
Project No: NA230258	Drawing No: WCP-ACR-DRW-STR-TAM-12E-0000305	Issue: E		

**Appendix B - Civil Drawings**







1. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL AND STRUCTURAL CONSULTANTS DRAWINGS AND SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED.
2. ALL DIMENSIONS RELEVANT TO SETTING OUT AND OFF-SITE WORK SHALL BE VERIFIED BY THE CONTRACTOR BEFORE CONSTRUCTION
3. DIMENSIONS SHALL NOT BE OBTAINED BY SCALING THE DRAWINGS.
4. ALL DIMENSIONS ON DETAILS ARE IN MILLIMETRES UNLESS STATED OTHERWISE. ALL PLANS AND LEVELS ARE EXPRESSED IN METRES.
5. DURING CONSTRUCTION THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE STRUCTURAL STABILITY OF THE WORKS AND ENSURE NO PARTS BE OVER STRESSED UNDER CONSTRUCTION ACTIVITIES.
6. WORKMANSHIP AND MATERIALS ARE TO BE IN ACCORDANCE WITH THE RELEVANT CURRENT S.A.A. CODES INCLUDING ALL AMENDMENTS, AND THE LOCAL STATUTORY AUTHORITIES, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
7. THE APPROVAL OF A SUBSTITUTION SHALL BE SOUGHT FROM ACOR CONSULTANTS / PRINCIPAL'S REPRESENTATIVE BUT IS NOT AN AUTHORISATION FOR A VARIATION. ANY VARIATIONS INVOLVED MUST BE TAKEN UP WITH ACOR CONSULTANTS / PRINCIPAL'S REPRESENTATIVE BEFORE THE WORK COMMENCES.
8. ANY DISCREPANCIES OR OMISSIONS SHALL BE REFERRED TO THE ENGINEER FOR A DECISION BEFORE PROCEEDING WITH THE WORK.
9. THE CONTRACTOR SHALL GIVE 48 HOURS NOTICE FOR ALL ENGINEERING INSPECTIONS. ALL INSPECTIONS AND CERTIFICATIONS TO BE INCLUDED IN CONTRACTORS COST.
10. BUILDING FROM THESE DRAWINGS IS NOT TO COMMENCE UNTIL APPROVED BY THE PRINCIPAL CERTIFYING AUTHORITY.
11. THE WORD 'ENGINEER' USED IN THESE NOTES REFER TO AN EMPLOYEE OR NOMINATED REPRESENTATIVE OF **ACOR CONSULTANTS PTY LTD**.
12. ALL CONSTRUCTION ACTIVITIES SHALL COMPLY WITH THE RELEVANT CURRENT WORKPLACE HEALTH AND SAFETY LEGISLATION.

1. THE CONTRACTOR SHALL ALLOW FOR THE CAPPING OFF, EXCAVATION, REMOVAL AND DISPOSAL IF REQUIRED OF ALL EXISTING SERVICES IN AREAS AFFECTED BY WORKS WITHIN THE CONTRACT AREA, AS SHOWN ON THE DRAWINGS UNLESS DIRECTED OTHERWISE BY THE PRINCIPAL'S REPRESENTATIVE.
2. THE CONTRACTOR SHALL ENSURE THAT AT ALL TIMES SERVICES TO ALL BUILDINGS NOT AFFECTED BY THE WORKS ARE NOT DISRUPTED.
3. PRIOR TO COMMENCEMENT OF ANY WORKS THE CONTRACTOR SHALL GAIN WRITTEN APPROVAL OF THEIR PROGRAMME FOR THE RELOCATION/CONSTRUCTION OF TEMPORARY SERVICES.
4. EXISTING BUILDINGS, EXTERNAL STRUCTURES, AND TREES SHOWN ON THESE DRAWINGS ARE FEATURES EXISTING PRIOR TO ANY DEMOLITION WORKS.
5. CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES TO MAINTAIN EXISTING SUPPLY TO BUILDINGS REMAINING IN OPERATION DURING WORKS TO THE SATISFACTION AND APPROVAL OF THE PRINCIPAL'S REPRESENTATIVE. ONCE DIVERSION IS COMPLETE AND COMMISSIONED THE CONTRACTOR SHALL REMOVE ALL SUCH TEMPORARY SERVICES AND LEAVE GOOD TO THE SATISFACTION OF THE PRINCIPAL'S REPRESENTATIVE.
6. INTERRUPTION TO SUPPLY OF EXISTING SERVICES SHALL BE DONE SO AS NOT TO CAUSE ANY INCONVENIENCE TO THE PRINCIPAL. CONTRACTOR TO GAIN APPROVAL OF PRINCIPAL'S REPRESENTATIVE FOR TIME OF INTERRUPTION.

THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS, AND ANY OTHER PLANS OR WRITTEN INSTRUCTIONS THAT MAY BE ISSUED AND RELATING TO DEVELOPMENT AT THE SUBJECT SITE.

E2. THE PRINCIPAL'S REPRESENTATIVE WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE GUIDELINES OF 'MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION', DEPT OF HOUSING 2004 (BLUE BOOK).

E3. ALL BUILDERS AND SUB-CONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS.

CONSTRUCTION SEQUENCE

E4. THE SOIL EROSION POTENTIAL ON THIS SITE SHALL BE MINIMISED. HENCE WORKS SHALL BE UNDERTAKEN IN THE FOLLOWING SEQUENCE :

a. INSTALL SEDIMENT FENCES. TEMPORARY CONSTRUCTION EXIT AND SANDBAG KEBB INLET SEDIMENT TRAP.

b. UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

E5. DURING WINDY CONDITIONS, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.

E6. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

FENCING

E7. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARDOUS AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.

OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.

E9. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.

E10. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

OTHER MATTERS

E11. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.

E12. RECEPTORS FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER ARE TO BE EMPTIED AS NECESSARY. DISPOSAL OF WASTE SHALL BE IN A MANNER APPROVED BY THE PRINCIPAL'S REPRESENTATIVE.

SITE INSPECTION & MAINTENANCE

E13. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED AFTER RAINFALL EVENTS TO ENSURE THAT THEY OPERATE EFFECTIVELY. REPAIR AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED.

1. ALL 375 DIA. DRAINAGE PIPES AND LARGER SHALL BE CLASS "2" APPROVED SPIGOT AND SOCKET FRC OR RCP PIPES WITH RUBBER RING JOINTS. (U.N.O.) ALL DOWNPIPE DRAINAGE LINES SHALL BE SEWER GRADE uPVC WITH SOLVENT WELD JOINTS. (U.N.O.)
2. EQUIVALENT STRENGTH REINFORCED CONCRETE PIPES MAY BE USED.
3. ALL PIPE JUNCTIONS UP TO AND INCLUDING 450 DIA. AND TAPERS SHALL BE VIA PURPOSE MADE FITTINGS.
4. MINIMUM GRADE TO STORMWATER LINES TO BE 1%. (U.N.O.)
5. CONTRACTOR TO SUPPLY AND INSTALL ALL FITTINGS AND SPECIALS INCLUDING VARIOUS PIPE ADAPTORS TO ENSURE PROPER CONNECTION BETWEEN DISSIMILAR PIPEWORK.
6. ALL CONNECTIONS TO EXISTING DRAINAGE PITS SHALL BE MADE IN A TRADESMAN-LIKE MANNER AND THE INTERNAL WALL OF THE PIT AT THE POINT OF ENTRY SHALL BE CEMENT RENDERED TO ENSURE A SMOOTH FINISH.
7. PRECAST PITS SHALL NOT BE USED UNLESS WRITTEN APPROVAL IS OBTAINED FROM THE ENGINEER.
8. WHERE TRENCHES ARE IN ROCK, THE PIPE SHALL BE BEDDED ON A MIN. 50MM CONCRETE BED (OR 75MM THICK BED OF 12MM BLUE METAL) UNDER THE BARREL OF THE PIPE. THE PIPE COLLAR AT NO POINT SHALL BEAR ON THE ROCK. IN OTHER THAN ROCK, PIPES SHALL BE LAID ON A 75MM THICK SAND BED. IN ALL CASES BACKFILL THE TRENCH WITH SAND TO 200MM ABOVE THE PIPE. WHERE THE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH WITH SAND OR APPROVED GRANULAR BACKFILL COMPACTED IN 150MM LAYERS TO 98% STANDARD MAX. DRY DENSITY.
9. BEDDING SHALL BE (U.N.O.) TYPE HS2, IN ACCORDANCE WITH CURRENT RELEVANT AUSTRALIAN STANDARDS.
10. WHERE STORMWATER LINES PASS UNDER FLOOR SLABS SEWER GRADE RUBBER RING JOINTS ARE TO BE USED.
11. WHERE SUBSOIL DRAINAGE LINES PASS UNDER FLOOR SLABS AND VEHICULAR PAVEMENTS UNLINED UPVC SEWER GRADE PIPE SHALL BE USED.
12. PROVIDE 3.0M LENGTH OF 100 DIA. SUBSOIL DRAINAGE PIPE WRAPPED IN FABRIC SOCK, AT UPSTREAM END OF EACH PIT.

1. CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS, SERVICES AND STRUCTURES ON SITE PRIOR TO COMMENCEMENT OF WORK.
2. ALL WORK SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE DETAILS SHOWN ON THE DRAWINGS AND THE SPECIFICATION.
3. ON COMPLETION OF PROPOSED WORKS ALL DISTURBED AREAS MUST BE RESTORED TO ORIGINAL, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL, GRASSED & LANDSCAPE AREAS AND ROAD PAVEMENTS. (U.N.O.)
4. CONTRACTOR TO OBTAIN ALL AUTHORITY APPROVALS.
5. MAKE SMOOTH TRANSITION TO EXISTING SERVICES AND MAKE GOOD.
6. WHERE NEW WORKS ADJUT EXISTING THE CONTRACTOR SHALL ENSURE THAT A SMOOTH EVEN PROFILE, FREE FROM ABRUPT CHANGES IS OBTAINED.
7. CARE IS TO BE TAKEN WHEN EXCAVATING NEAR EXISTING SERVICES. NO MECHANICAL EXCAVATIONS ARE TO BE UNDERTAKEN OVER THESE SERVICES. HAND EXCAVATE IN THESE AREAS.
8. THESE PLANS SHALL BE READ IN CONJUNCTION WITH APPROVED ARCHITECTURAL, STRUCTURAL, HYDRAULIC, AND OTHER SERVICES DRAWINGS AND SPECIFICATIONS.
9. EQUIVALENT STRENGTH FRC PIPES MAY BE USED.
10. ALL PIPE JOINTS, BENDS AND TAPERS UP TO AND INCLUDING 450 DIA SHALL BE VIA PURPOSE MADE FITTINGS.
11. MINIMUM GRADE TO STORMWATER LINES TO BE 1%. (U.N.O.)
12. CONTRACTOR TO SUPPLY AND INSTALL ALL FITTINGS AND SPECIALS INCLUDING VARIOUS PIPE ADAPTORS TO ENSURE PROPER CONNECTION BETWEEN DISMILLAR PIPEWORK.
13. ALL CONNECTIONS TO EXISTING DRAINAGE PITS SHALL BE MADE IN A TRADESMAN LIKE MANNER AND THE INTERNAL WALL OF THE PIT AT THE POINT OF ENTRY SHALL BE CEMENT RENDERED TO ENSURE A SMOOTH FINISH.
14. WHERE TRENCHES ARE IN ROCK, THE PIPE SHALL BE BEDDED ON A MIN. 50mm CONCRETE BED (OR 75mm THICK BED OF 12mm BLUE METAL) UNDER THE BARREL OF THE PIPE. THE PIPE COLLAR AT NO POINT SHALL BEAR ON THE ROCK. IN OTHER THAN ROCK, PIPES SHALL BE LAID ON A 75mm THICK SAND BED. IN ALL CASES BACKFILL THE TRENCH WITH SAND TO 200mm ABOVE THE PIPE. WHERE THE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH WITH SAND OR APPROVED GRANULAR BACKFILL COMPACTED IN 150mm LAYERS TO 98% STANDARD MAX. DRY DENSITY.
15. BEDDING SHALL BE (U.N.O.) TYPE H1, IN ACCORDANCE WITH CURRENT RELEVANT AUSTRALIAN STANDARDS.
16. WHERE STORMWATER LINES PASS UNDER FLOOR SLABS SEWER GRADE RUBBER RING JOINTS ARE TO BE USED.
17. PROVIDE 3.0M LENGTH OF 100 DIA. SUBSOIL DRAINAGE PIPE WRAPPED IN FABRIC SOCK, AT UPSTREAM END OF EACH PIT.

1. ALL WORKMANSHIP AND MATERIALS SHALL COMPLY WITH AS 3600 CURRENT EDITIONS WITH AMENDMENTS, AND THE ACCE CONCRETE SPECIFICATION EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.
2. VERIFY ALL SETTING OUT DIMENSIONS WITH THE ARCHITECT AND/OR THE SURVEYOR.
3. DO NOT OBTAIN DIMENSIONS BY SCALING THE DRAWINGS.
4. IN CASE OF DOUBT - ASK.

**CONCRETE**

1. PLACE CONCRETE OF THE FOLLOWING CHARACTERISTIC COMPRESSIVE STRENGTH  $f_{ck}$  AS DEFINED IN AS 3600 OR M.R. FORM 609 ADD WATER REDUCING ADMIXTURE EQUAL TO WRDA

LOCATION	AS 3600 $f_{ck}$ MPa AT 28 DAYS	SPECIFIED SLUMP	NOMINAL AGG. SIZE
ALL KERB PITS ETC.	25	80	20
VEHICULAR PARKINGS	32	80	20

2. USE "A.C.S.E. SPECIFICATION TYPE A" CEMENT.
3. ALL CONCRETE SHALL BE SUBJECT TO PROJECT CONTROL SAMPLE AND TESTING TO AS 3600.
4. CONSOLIDATE BY VIBRATION.

FIX REINFORCEMENT AS SHOWN ON DRAWINGS. THE TYPE AND GRADE IS INDICATED BY A SYMBOL AS SHOWN BELOW. ON THE DRAWING N IS FOLLOWED BY A NUMERICAL, WHICH INDICATES THE SIZE IN MILLIMETRES. A MARK NUMERAL (IF USED) FOLLOWS THIS NUMERICAL.

N: HOT ROLLED DEFORMED BARS, GRADE 500N  
R: HOT ROLLED PLAIN BARS, GRADE 250R  
W: COLD DRAWN PLAIN ROUND WIRE, GRADE 500L  
SL: SQUARE WELDED MESH, GRADE 500L  
RL: RECTANGULAR WELDED MESH, GRADE 500L  
LTM: RECTANGULAR WELDED TRENCH MESH, GRADE 500L

**CURING**

1. CURING OF ALL CONCRETE SHALL BE IN ACCORDANCE WITH AS3600 AND SHALL COMMENCE WITHIN 2 HOURS OF FINISHING OPERATIONS.
2. CURING SHALL BE CONTINUAL SATURATION WITH POTABLE WATER FOR 3 DAYS FOLLOWED BY PREVENTION OF MOISTURE LOSS FOR THE NEXT 4 DAYS, USING POLYTHENE SHEETING OR WET HESSIAN PROTECTED BY WIND OR TRAFFIC AND THEN ALLOWING GRADUAL DRYING OUT.
3. CURING COMPOUNDS MAY BE USED PROVIDED THAT THEY COMPLY WITH AS3799 AND NOT AFFECT THE PROPOSED FINISH.
4. THE COMPATIBILITY OF CURING COMPOUNDS WITH THE PROPOSED FINISH AND OTHER CONCRETE ADMIXTURES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO ORDERING AND APPLICATION.
5. CURING COMPOUNDS ARE APPLIED UNIFORMLY IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS.  
PVA - BASED CURING COMPOUNDS ARE NOT ACCEPTABLE.
6. CURING SHALL BE UNDERTAKEN BY AN EXPERIENCED CONTRACTOR FAMILIAR WITH THE PROPOSED COMPOUNDS AND THE MANUFACTURER'S SPECIFICATIONS.
7. WHERE SHADE TEMPERATURE EXCEEDS 35°C, SPRAY THE EXPOSED SURFACE OF THE CONCRETE PAVEMENT / SLAB DURING THE PLACING OF FINISHING OPERATION WITH A FINE FILM OR APPROVED ALIPHATIC ALCOHOL. REPEAT THE SPRAY IF THE SPRAY SURFACE HAS BEEN RE-WORKED.
8. ENSURE ADEQUATE SUPPLY OF ALIPHATIC ALCOHOL ON-SITE PRIOR TO CONCRETE WORKS.

CONCRETE MIX PARAMETERS ;

- MAXIMUM AGGREGATE SIZE 20mm
- FLEXURAL STRENGTH AT 28 DAYS = 3.5MPa
- FLEXURAL STRENGTH AT 90 DAYS = 3.85 MPa
- MAXIMUM WATER / CEMENT RATIO = 0.55
- MAXIMUM SHRINKAGE LIMIT = 650 MICRON STRAINS (AS 1012 P1 13)
- MINIMUM CEMENT CONTENT = 300kg/m3
- CEMENT TO BE TYPE "A" (NORMAL CEMENT) TO AS 1315
- SLUMP = 50mm

PJ.2. JOINT TO BE SAWN AS SOON AS CONCRETE HAS HARDENED SUFFICIENTLY THAT IT WILL NOT BE DAMAGED BY SAWING. IF AN UNPLANNED CRACK OCCURS THE CONTRACTOR SHALL REPLACE WHOLE SLABS EITHER SIDE OF THE UNPLANNED CRACK, UNLESS DIRECTED OTHERWISE.

PJ.3.

- a. CONSTRUCT JOINTS AS DETAILED
- b. CONSTRUCTION JOINTS WHERE REQUIRED BUT NOT SHOWN, SHALL BE LOCATED TO THE APPROVAL OF THE ENGINEER AND CONSTRUCTED AT THE CONTRACTORS EXPENSE.
- c. ALL LONGITUDINAL CONSTRUCTION JOINTS SHALL BE FORMED AND INCLUDE DOWEL BARS AS SPECIFIED. ALL TRANSVERSE CONSTRUCTION JOINTS SHALL BE FORMED AND INCLUDE DOWEL BARS AS SPECIFIED.
- d. BOND BREAKER TO BE TWO (2) UNIFORM COATS OF BITUMEN EMULSION ALL OVER THE EXPOSED SURFACE AND ON END.

PJ.4. DOWELS AND THE BARS TO MEET STRENGTH REQUIREMENTS OF STRUCTURAL GRADE STEEL IN ACCORDANCE AS. 1302. DOWELS AND THE BARS SHALL BE :-

- STRAIGHT
- TO LENGTH SPECIFIED
- CLEAN AND FREE FROM MILL SCALE, RUST AND OIL.
- SAWN TO LENGTH NOT CROPPED.

PJ.5. DIMENSIONS OF SEALANT RESERVOIR DEPENDANT ON THE SEALANT TYPE ADOPTED. ENGINEERS APPROVAL TO BE OBTAINED FOR SEALANT AND RESERVOIR DIMENSIONS AND DETAIL PROPOSED BY THE CONTRACTOR. REFER DETAIL "B" FOR TYPICAL ARRANGEMENT AND SEALANT.

PJ.6. PRIOR TO THE PLACEMENT OF CONCRETE IN THE ADJACENT SLAB, SELF EXPANDING CORK FILLER SHALL BE ADHERED TO THE ADDED CAST AND CLEAVED CONCRETE FACE USING AN APPROVED WATERPROOF OLEAGINEOUS ADHESIVE. SHALL BE LIBERALLY APPLIED TO THE FULL FACE OF THE CONCRETE SLAB TO BE COVERED BY THE FILLER, AND ON THE FULL FACE OF THE FILLER TO BE ADHERED.

PJ.7. REFER TO COMPACTION NOTES FOR PREPARATION OF SUB-BASE AND SUB-GRADE.

PJ.8. ALL WORK TO BE BROOM FINISH.

1. ALL VEHICULAR PAVEMENT TO BE JOINED AS SHOWN ON DRAWINGS.
2. KEYED CONSTRUCTION JOINTS SHOULD GENERALLY BE LOCATED AT A MAXIMUM OF 6m CENTRES.
3. SAWN JOINTS SHOULD GENERALLY BE LOCATED AT A MAXIMUM OF 6m CENTRES OR 1.5 x THE SPACING OF KEYED JOINTS, WHERE KEY JOINT SPACING IS LESS THAN 4m, WITH DOWELLED EXPANSION JOINTS AT MAXIMUM OF 30m CENTRES.
4. PROVIDE 10mm WIDE FULL DEPTH ISOLATION JOINTS BETWEEN BUILDINGS AND ALL CONCRETE OR UNIT PAVERS.
5. VEHICULAR PAVEMENT JOINTING AS FOLLOWS.

FACE OF KERB									
3	CJ	DDU		3	3	3	CJ	DDU	3
	CJ			3m MAX U.N.O.			3m MAX U.N.O.		
	CJ			30m MAX U.N.O.					
	U								

EDGE OF POUR  
CJ = CONTRACTION JOINT (SCJ OR CDJ AS NOTED ON PLAN)

1. DOWELED JOINTS ARE TO BE LOCATED WHERE POSSIBLE AT TANGENT POINTS OF CURVES AND ELSEWHERE AT MAX 6.0m CENTRES.
2. TOOLED JOINTS ARE TO BE LOCATED AT A MAX 1.5 x WIDTH OF THE PAVEMENT.
3. WHERE POSSIBLE JOINTS SHOULD BE LOCATED TO MATCH KERBING AND/OR ADJACENT PAVEMENT JOINTS.
4. ALL PEDESTRIAN FOOTPATH JOINTING LAYOUTS AS FOLLOWS (UNO)

FACE OF KERB

1.5 x W  
(1.5m MAX)

6.0m MAX  
OR EVERY THIRD JOINT

5. ALL RAMPED CROSSINGS SHALL BE DOWELED INTO ADJOINING PATH PAVEMENT

[illegible]





Issue	Description	Date	Drawn	Approved
A	NOT ISSUED	-	-	-
B	NOT ISSUED	-	-	-
C	NOT ISSUED	-	-	-
D	DRAFT DESIGN DEVELOPMENT	07.03.25	RP	GL

**PRINT IN COLOUR**

North Scale

Client

Managing Contractor

Architect **architectus™**  
**Conrad Gargett**

Project  
WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL  
DEAN STREET, NORTH TAMWORTH  
NSW, 2340

**NOT FOR CONSTRUCTION**


**ACOR Consultants Pty Ltd**  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T +61 2 9438 5098

Drawing Title  
CIVIL SERVICES  
EXISTING SERVICES AND DEMOLITION PLAN

Drawn	Designed	C.A. Check	Date	Scale @ A0
RP	GL	GL	07.03.25	1:100

Project No.	Drawing No.	Issue
NA230258	WCP-ACR-DRW-CIV-TAM-01A-0000003	D





Issue	Description	Date	Drawn	Approved
A	DRAFT SCHEMATIC DESIGN	17/10/24	JM	GL
B	ISSUE FOR SCHEMATIC DESIGN	22/01/25	DW	GL
C	DO ENGINEERING PLUS PRESENTATION	17/03/25	RP	GL
D	DRAFT DESIGN DEVELOPMENT	07/03/25	RP	GL

Drawing Key

**PRINT IN COLOUR**

North

Scale

Client

Managing Contractor

Architect

**architectus™**  
**Conrad Gargett**

Project

WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL  
DEAN STREET, NORTH TAMWORTH  
NSW, 2340

**NOT FOR CONSTRUCTION**

**AcOR CONSULTANTS**

ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T +61 2 9438 5098

Drawing Title

CIVIL SERVICES  
SOIL EROSION AND SEDIMENT CONTROL PLAN

Drawn	Designed	C.A. Check	Date	Scale @ A0
JM	GL	GL	07/03/25	N.T.S.

Project No.	Drawing No.	Issue
NA230258	WCP-ACR-DRW-CIV-TAM-01A-0000004	D



EROSION AND SEDIMENT CONTROL NOTES

GENERAL INSTRUCTIONS

- E1. THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS, AND ANY OTHER PLANS OR WRITTEN INSTRUCTIONS THAT MAY BE ISSUED AND RELATING TO DEVELOPMENT AT THE SUBJECT SITE.
- E2. THE PRINCIPAL'S REPRESENTATIVE WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE GUIDELINES OF "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION", DEPT OF HOUSING, 2004 (BLUE BOOK).
- E3. ALL BUILDERS AND SUB-CONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS.

CONSTRUCTION SEQUENCE

- E4. THE SOIL EROSION POTENTIAL ON THIS SITE SHALL BE MINIMISED. HENCE WORKS SHALL BE UNDERTAKEN IN THE FOLLOWING SEQUENCE :
- a. INSTALL SEDIMENT FENCES, TEMPORARY CONSTRUCTION EXIT AND SANDBAG KERB INLET SEDIMENT TRAP.
- b. UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

- E5. DURING WINDY CONDITIONS, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- E6. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

FENCING


- E7. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- E8. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- E9. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- E10. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

OTHER MATTERS

- E11. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- E12. RECEPTORS FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER ARE TO BE EMPTIED AS NECESSARY. DISPOSAL OF WASTE SHALL BE IN A MANNER APPROVED BY THE PRINCIPAL'S REPRESENTATIVE.

SITE INSPECTION & MAINTENANCE

- E13. EROSION AND SEDIMENT CONTROL MEASURES SHALL BE INSPECTED AFTER RAINFALL EVENTS TO ENSURE THAT THEY OPERATE EFFECTIVELY. REPAIR AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED.




INLET TRAP

N.T.S.

NOTE

TO BE USED IN PAVED AREAS WHERE TRAFFIC ACCESS IS REQUIRED




CONSTRUCTION NOTES

1. LOCATE STOCKPILE AT LEAST 5 METRES FROM EXISTING VEGETATION, CONCENTRATED WATER FLOWS, ROADS AND HAZARD AREAS.
2. CONSTRUCT ON THE CONTOUR AS A LOW, FLAT, ELONGATED MOUND.
3. WHERE THERE IS SUFFICIENT AREA TOPSOIL STOCKPILES SHALL BE LESS THAN 2 METRES IN HEIGHT.
4. REHABILITATE IN ACCORDANCE WITH THE SWAMPIESCP.
5. CONSTRUCT EARTH BANK (STANDARD DRAWING 5-2) ON THE UPSLOPE SIDE TO DIVERT RUN OFF AROUND THE STOCKPILE AND A SEDIMENT FENCE (STANDARD DRAWING 6-7) 1 TO 2 METRES DOWNSLOPE OF STOCKPILE.

STOCKPILES

N.T.S.



PLAN

SECTION DETAIL

CONSTRUCTION NOTES


1. CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE.
2. DRIVE 1.5m LONG STAR PICKETS INTO GROUND, 2.5 METRES APART (MAX). ENSURE STAR PICKETS ARE FITTED WITH SAFETY CAPS.
3. DIG A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
4. BACKFILL TRENCH OVER BASE OF FABRIC.
5. FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
6. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP.

SEDIMENT CONTROL FENCE

N.T.S.

Issue	Description	Date	Drawn	Approved
A	DRAFT SCHEMATIC DESIGN	17/10/24	JM	GL
B	ISSUE FOR SCHEMATIC DESIGN	22/01/25	DW	GL
C	DO ENGINEERING PLUS 2 PRESENTATION	07/03/25	RP	GL
D	DRAFT DESIGN DEVELOPMENT	07/03/25	RP	GL

Drawing Key



PRINT IN COLOUR

North

Scale

Client



Managing Contractor



Architect



Project

WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL  
DEAN STREET, NORTH TAMWORTH  
NSW, 2340

NOT FOR CONSTRUCTION



ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T +61 2 9438 5098

Drawing Title

CIVIL SERVICES  
SOIL EROSION AND SEDIMENT CONTROL DETAILS

Drawn

Designed

C.A. Check

Date

Scale @ A0

JM

GL

GL

07/03/25

1:100

Project No.

Drawing No.

Issue

NA230258

WCP-ACR-DRW-CIV-TAM-01A-0000005

D



ADDITIONAL SCOPE HAS BEEN ADDED  
LATE IN THE DESIGN DELIVERABLE  
PROCESS, THIS WILL BE  
INCORPORATED IN THE NEXT  
ITERATION.

EXISTING STORMWATER  
KERB INLET PIT  
CL413.95  
IL412.90

EXISTING STORMWATER PIPE TO  
BE RE-ROUTED AND CONNECTED  
INTO DOWNSTREAM  
STORMWATER SYSTEM

TW 413.30  
BW 412.90

EXISTING STORMWATER PIPE TO BE  
RE-ROUTED AND CONNECTED INTO  
DOWNSTREAM STORMWATER PIT.  
MAKE GOOD CONNECTION TO EXISTING  
STORMWATER PIT (IL411.00)

ON SITE DETENTION TANK  
22.5m<sup>3</sup>

PROPOSED GABION WALL TO  
STRUCTURAL ENGINEER'S DETAIL

200mm WIDE SPOON DRAIN AS  
SHOWN AROUND EXTENTS OF  
BATTER

FFL 413.00

PROPOSED STORMWATER OVERFLOW LINE  
TO BYPASS ON-SITE DETENTION SYSTEM  
AND CONNECT INTO THE EXISTING  
STORMWATER NETWORK DOWNSTREAM


450x450 CLASS B GRATE AND  
FRAME STORMWATER PIT.  
CL412.89  
PIT DEPTH APPROX 400mm

450x450 CLASS B GRATE AND  
FRAME STORMWATER PIT.  
CL412.81  
PIT DEPTH APPROX 400mm

200mm WIDE GRATED DRAIN.  
COVER LEVEL = 412.95  
DRAIN DEPTH = 150mm WITH  
INTERNAL DROPPER TO IL412.55


Rev	Description	Date	Drawn	Approved
A	DRAFT SCHEMATIC DESIGN	17/10/24	JM	GL
B	ISSUE FOR SCHEMATIC DESIGN	22/01/25	DW	GL
C	DO ENGINEERING PRESENTATION	17/03/25	RP	GL
D	DRAFT DESIGN DEVELOPMENT	07/03/25	RP	GL

Drawing Key



PRINT IN COLOUR

North



Scale

Client



Managing Contractor



Architect



Project  
WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL  
DEAN STREET, NORTH TAMWORTH  
NSW, 2340

NOT FOR CONSTRUCTION



ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T +61 2 9438 5098


Drawing Title  
CIVIL SERVICES  
GENERAL ARRANGEMENT PLAN

Drawn	Designed	C.A. Check	Date	Scale @ A0
JM	GL	GL	07/03/25	1:100
Project No.	Drawing No.	Issue		
NA230258	WCP-ACR-DRW-CIV-TAM-01A-0000006	D		










LEGEND				
-999	to	-1.40	m	
-1.40	to	-1.20	m	
-1.20	to	-1.00	m	
-1.00	to	-0.80	m	
-0.80	to	-0.60	m	
-0.60	to	-0.40	m	
-0.40	to	-0.20	m	
-0.20	to	0.00	m	
0.00	to	0.20	m	
0.20	to	0.40	m	
0.40	to	0.60	m	
0.60	to	0.80	m	
0.80	to	1.00	m	
1.00	to	1.20	m	
1.20	to	1.40	m	
1.40	to	999	m	

NOTE: ALL EARTHWORKS QUANTITIES ARE THEORETICAL AND INDICATIVE ONLY, BASED UPON BANKED VOLUMES WITH NO ALLOWANCE FOR BULKING FACTORS. CONTRACTOR TO MAKE THEIR OWN ASSESSMENT OF EARTHWORKS QUANTITIES


CUT / FILL QUANTITIES	
TOTAL CUT	-1,245m³
TOTAL FILL	135m³
TOTAL BALANCE	-1,110m³ (CUT)

- EARTHWORKS CUT AND FILL NOTES:**
- BULKING AND COMPACTION FACTORS HAVE NOT BEEN APPLIED TO THE CUT AND FILL QUANTITIES.
  - DETAILED BULKING AND CUT / FILL QUANTITIES FOR STRIP TOPSOIL, FOOTINGS, PAVEMENT BOXING, TRENCHING AND THE LIKE HAS NOT BEEN INCLUDED IN THE CUT AND FILL ASSESSMENT.
  - NO ALLOWANCE FOR TOPSOIL AND FRIABLE SOIL LAYERS HAS BEEN ALLOWED FOR IN LANDSCAPED AREAS. REUSE OF STRIPPED TOPSOIL HAS BEEN ASSUMED.
  - ALL TOPSOIL SHALL BE RETAINED ON THE DEVELOPMENT SITE AND UTILISED EFFECTIVELY TO ENCOURAGE APPROPRIATE RE-VEGETATION.
  - NO ALLOWANCE HAS BEEN MADE TO QUANTIFY ROCK EXCAVATION. CONTRACTOR TO ENSURE APPROPRIATE ALLOWANCES FOR EXCAVATION IN ROCK, CRUSHING AND REUSE ON SITE AND/OR DISPOSAL OFF SITE.

Issue	Description	Date	Drawn	Approved
A	NOT ISSUED			
B	ISSUE FOR SCHEMATIC DESIGN	12/11/24	DW	GL
C	DO ENGINEERING P&ID PRESENTATION	17/03/25	RP	GL
D	DRAFT DESIGN DEVELOPMENT	07/03/25	RP	GL



PRINT IN COLOUR



Scale

Client



Managing Contractor



Architect



Project

WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL  
DEAN STREET, NORTH TAMWORTH  
NSW, 2340

NOT FOR CONSTRUCTION




ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T +61 2 9438 5098


Drawing Title  
CIVIL SERVICES  
BULK EARTHWORKS PLAN

Drawn	Designed	C.A. Check	Date	Scale @ A0
JM	GL	GL	07/03/25	1:100
Project No:	Drawing No:	Issue		
NA230258	WCP-ACR-DRW-CIV-TAM-01A-0000008	D		





Issue	Description	Date	Drawn	Approved
A	NOT ISSUED	-	-	-
B	NOT ISSUED	-	-	-
C	DO ENGINEERING PLUG 2 PRESENTATION	17.03.25	RP	GL
D	DRAFT DESIGN DEVELOPMENT	07.03.25	RP	GL



PRINT IN COLOUR

North

Scale

Client

Managing Contractor

Architect

Project  
WORLD CLASS END OF LIFE PROGRAM  
TAMWORTH HOSPITAL  
DEAN STREET, NORTH TAMWORTH  
NSW, 2340

NOT FOR CONSTRUCTION

ACOR Consultants Pty Ltd  
Suite 2, Level 1, 33 Herbert Street  
St Leonards NSW 2065  
T +61 2 9438 5098

Drawn	Designed	S.A. Check	Date	Scale @ A0
JM	GL	GL	07.03.25	1:100
Project No:	Drawing No:	Issue		
NA230258	WCP-ACR-DRW-CIV-TAM-01A-0000009	D		