FEATURE PLANTING- REFER TO PLANT SCHEDULE

PROPOSED SYNTHETIC TURF AREA

PEBBLES

PROPOSED CONCRETE PATHS AS PER ARCHITECTS DRAWINGS

EXISTING TURF TO REMAIN

PROPOSED NEW TURF

MULCH

NEW TREES- REFER TO PLANT SCHEDULE


EXISTING TREES TO BE RETAINED AND PROTECTED

EXISTING TREES TO BE REMOVED- REFER TO ARBORISTS REPORT

TREE PROTECTION ZONE

		PROPOSED PUBLIC DOMAIN PLANT SCHEDULE					
	KEY	BOTANICAL NAME	COMMON NAME	QTY	MATURE HGT	POT SIZE	
#	ВС	TREES BUCKINGHAMIA CELSISSIMA	IVORY CURL FLOWER	14	6m	100Ltr	


^{*} Parramatta City Council Public Domain Guidelines Species for Street Verges with Overhead Wires











FEATURE PLANTING- REFER TO PLANT SCHEDULE

PROPOSED SYNTHETIC TURF AREA



PEBBLES



PROPOSED CONCRETE PATHS AS PER ARCHITECTS DRAWINGS



EXISTING TURF TO REMAIN



PROPOSED NEW TURF

PROTECTED



NEW TREES- REFER TO PLANT SCHEDULE

EXISTING TREES TO BE RETAINED AND



EXISTING TREES TO BE REMOVED- REFER TO




TREE PROTECTION ZONE

ARBORISTS REPORT

KEY	BOTANICAL NAME	COMMON NAME	QTY	MATURE HGT	POT SIZE
	TREES				
BM	BACKHOUSIA MYRTIFOLIA	CINNAMON MYRTLE	7	5m	45Ltr
	SHRUBS				
BS	BANKSIA SPINULOSA	HAIRPIN BANKSIA	2	1.5m	250mm
CE	CALLISTEMON CITRINUS 'ENDEAVOUR'	RED BOTTLEBRUSH	5	3m	200mm
DE	DORYANTHES EXCELSA	GYMEA LILY	8	2m	250mm
PT	PHORMIUM TENAX	NEW ZEALAND FLAX	5	1.5m	200mm
	GRASSES / GROUND COVERS				
AF	ACACIA COGNATA 'FETTUCCINI'	ACACIA 'FETTUCCINI'	6	0.7m	200mm
CA	CAREX APPRESSA	CAREX	18	1m	200mm
DC	DIANELLA CAERULEA 'LITTLE JESS'	LITTLE JESS	24	0.4m	140mm
GS	GAHNIA SIEBERIANA	SAW SEDGE	4	1.5m	140mm
IN	ISOLEPIS NODOSA	KNOBBY CLUBRUSH	35	0.6m	140mm
JU	JUNCUS USITATUS	COMMON RUSH	27	0.8m	140mm
LL	LOMANDRA LONGIFOLIA	SPINY-HEADED MAT-RUSH	1	1m	200mm
TA	THEMEDA AUSTRALIS	KANGAROO GRASS	10	0.4m	140mm
WL	WESTRINGIA FRUTICOSA 'LOW HORIZON'	COASTAL ROSEMARY	16	0.3m	140mm

Australian native species



Contractors to check and verify all dimensions and all levels on site prior to any works.
 Any discrepancies should be immediately referred to Space Landscape Designs.
 All work to comply with B.C.A. Salutory Authorities and relevant Australian Standards.
 Dimensions recognised over scaling. All measurements are in millimetres.







ARC HI TEC TS.






PROJECT:
Parramatta East Public School Upgrade

DRN: T.Browne (B.L.Arch) North Parramatta 2150

| SITE ADDRESS: 30-32 Brabyn Street, | SCALE: 1:100@A1 | PROJECT NO: 242195



PLANTING PLAN - ZONE 1 PEPS-SLD-ZZ-GF-DR-L-0002



FEATURE PLANTING- REFER TO PLANT SCHEDULE

PROPOSED SYNTHETIC TURF AREA





PROPOSED CONCRETE PATHS AS PER ARCHITECTS DRAWINGS



EXISTING TURF TO REMAIN



PROPOSED NEW TURF

PROTECTED

MULCH



NEW TREES- REFER TO PLANT SCHEDULE

EXISTING TREES TO BE RETAINED AND




EXISTING TREES TO BE REMOVED- REFER TO ARBORISTS REPORT

TREE PROTECTION ZONE


PROPOSED PLANT SCHEDULE						
KEY	BOTANICAL NAME	COMMON NAME	QTY	MATURE HGT	POT SIZE	
	TREES					
CC	CYATHEA COOPERI	AUSTRALIAN TREE FERN	7	4m	250mm	
ER	ELAEOCARPUS RETICULATUS 'PRIMA DONNA'	BLUEBERRY ASH	6	6m	45Ltr	
	SHRUBS					
CP	CRINUM PEDUNCULATUM	RIVER LILY	9	2m	200mm	
	GRASSES / GROUND COVERS					
AA	ASPLENIUM AUSTRALASICUM	BIRDS NEST FERN	47	1m	200mm	
AM	ARTHROPODIUM 'MATAPOURI BAY'	RENGA RENGA LILY	59	0.8m	200mm	
DC	DIANELLA REVOLUTA	MAUVE FLAX LILY	123	0.4m	140mm	
VH	VIOLA HEDERACEA	NATIVE VIOLET	46	0.1m	140mm	

Parramatta City Council indigenous/low water use species
 Australian native species



ARC HI TEC TS.





Contractors to check and verify all dimensions and all levels on site prior to any work
 Any discrepancies should be immediately referred to Space Landscape Designs.
 All work to comply with B.C.A. Statutory Authorities and relevant Australian Standard.
 Dimensions recognised over scaling. All measurements are in millimetres.

| Rev. | Date | Issue | A | 06/08/24 | Preliminary Issue | B | 16/08/24 | DA Issue | C | 30/09/24 | DA Issue | D | 02/10/24 | DA Issue | E | 27/11/24 | DA Issue | F | 21/02/25 | DA Issue | G | 26/02/25 | REF Issue |

JD ARC HI TEC TS.

S P A C E

Space Landscape Designs Pty Ltd
ABN 60 799 663 674 ACN 139 316 251
info@spacedesigns.com.au
spacedesigns.com.au
P 02 9905 7870 F 02 9905 7657

Suite 138, 117 Old Pittwater Rd,

PROJECT:
Parramatta East Public School Upgrade
SITE ADDRESS: 30-32 Brabyn Street,
North Parramatta 2150

CLIENT: DoE

DRN: T.Browne (B.L.Arch)

SCALE: 1:100@A1

PROJECT NO: 242195

FEATURE PLANTING- REFER TO PLANT SCHEDULE

PROPOSED SYNTHETIC TURF AREA

PEBBLES

PROPOSED CONCRETE PATHS AS PER ARCHITECTS DRAWINGS

EXISTING TURF TO REMAIN

PROPOSED NEW TURF

MULCH

NEW TREES- REFER TO PLANT SCHEDULE


EXISTING TREES TO BE RETAINED AND PROTECTED

> EXISTING TREES TO BE REMOVED- REFER TO ARBORISTS REPORT


TREE PROTECTION ZONE







SITE KEY PLAN
SCALE 1:1500.





→Mulched garden

Sandstone billets


Bush tucker/ healing garden

New turf area - existing soil removed 300mm deep with

imported fill

by students

to form a yarning circle





HGT

15m 75Ltr


1.5m 250mm









O1 TYPICAL TREE PLANTING
SCALE 1:20 SCALE 1:20




TYPICAL TIMBER EDGE DETAIL



TYPICAL GARDEN BED DETAIL SCALE 1:10



TYPICAL SPADE EDGE DETAIL



ARTIFICIAL TURF DETAIL

01/09/24 DA Issue

30/09/24 DA Issue 02/10/24 DA Issue 26/02/25 REF Issue

crepancies should be immediately referred to Space Landscape Designs.

k to comply with B.C.A. Statutory Authorities and relevant Australian Standards.
sions recognised over scaling. All measurements are in millimetres.



Space Landscape Designs Pty Ltd ABN 60 799 663 674 ACN 139 316 25 info@spacedesigns.com.au

P 02 9905 7870 F 02 9905 7657

Suite 138, 117 Old Pittwater Rd,

Brookvale NSW 2100

Parramatta East Public School Upgrade

DRN: T.Browne (B.L.Arch) SCALE: As Shown@A1 North Parramatta 2150 PROJECT NO: 242195

DRAWING TITLE: LANDSCAPE DETAILS AND

weeding and rubbish removal from tree surrounds

adjustment, removal or replacement of stakes & ties

formative and selective pruning to AS 4373, and mulching to maintain and reinstate to depth specified.

LANDSCAPE SPECIFICATION NOTES

WORKMANSHIP AND MATERIAL QUALITY

caused to adjoining existing and retained works.

structural integrity of all items shall be the sole responsibility of landscape contractor.

spraying is to be used to eliminate all existing weeds 30 days prior to planting.

ractured, deformed or slumped during transit or unloading should not be accepted

Plant stock to be supplied by production nurseries in accordance with AS 2303:2018 Tree Stock for Landscape Use.

Curving: Space the pegs to hold edging to a uniform curve. Reduce edging thickness to 15 mm if required to enable it to be bent.

Finish: Free from kinks in alignment with one curve grading evenly into the next, and free of straight sections.

cell (or approved alternative) installed & connected to stormwater in accordance with Sydney Water regulations.

Install sandstone rocks to align dry creek bed. Rocks to be of various sizes and textures between 300 -700mm wide.

Plant stock to be supplied by production nurseries in accordance with AS 2303:2018 Tree Stock for Landscape Use.

axis, +/- 20%. Stock selection should also be based on NATSPEC Guide Specifying Trees: a Guide to Assessment of Tree Quality.

intermediate very coarse sand or fine gravel. Do not use geotextile fabrics over the drainage layer to prevent soil migration.

Before installing specified tree pit backfill soil, the following subgrade treatment must be applied to all finished subgrade areas:

matter by volume, may be used. The use of site reclaimed topsoil may be permitted, subject to investigation and testing.

the ameliorants to 200 mm depth to incorporate. Break up clods but do not smooth (leave the surface 'keved' to accept the subsoil/topsoil

days exceeding temperatures of 300 Celsius. Generally tree planting is preferred during the cooler months from March to October.

backfill soil is not paced over the top of the potted root ball. The top of the root ball and plant stem must be kept level with the top of the backfill.

Throughout the tree establishment period, the installer must continue to maintain new trees and carry out maintenance work including, but not limited to:-

Watering shall be incorporated into the regular maintenance schedule with the soil moisture content of the tree pits to be maintained above 60%.

rubbish or other deleterious material brought to the surface during cultivation. Grade the base of tree holes to the required design levels and shapes after cultivation.

the root zone to field capacity. Ensure potted root ball is thoroughly wet through the entire soil profile. Continue watering at a rate and frequency as required to avoid water stress in the plant

mix. Do not use the trunk of the tree as a lever in positioning or moving the tree in the planting hole. Position the tree at the set out distances as indicated in the details. Ensure trunks are set

discontinue if excessive root ball soil begins to fall away. Do not leave the root balls exposed for extended periods. Cover the root ball with moist hessian if backfilling cannot occur immediately

during transport. Root balls that have been unreasonably fractured, deformed or slumped during transit or unloading shall not be accepted.

Imported rock: Provide rock which has been selected before delivery. Rocks selected to minimize sharp and protruding edges.

turf become established within the maintenance period and are kept in a healthy and tidy state in accordance with best horticultural practices.

Topping: White kiln dried sand free from vegetable matter or any other impurities to depth of 12 mm.

approved alternative. Keep mulch 100mm away from plant stem & form a well to stop excessive water runoff. Finish flush with adjacent surfaces.

70° to vertical. Remove sods from garden beds and spread throughout grassed areas.

- Required finished levels and contours after light compaction.

Locate any underground and overground services & ensure no damage occurs. Levels on plan are nominal only & all dimensions to be checked on site prior to commencement. Final

Materials and workmanship are to conform to the current applicable Australian Standard Specifications and Codes. Any work or materials, which, in the opinion of the Site Manager do not meet appropriate industry standards should be rejected. Where works are adjacent to existing works, make proper junctions between new and existing works and make good any damage

Remove all existing weeds by hand, wiping or spraying with a glyphosate based herbicide. Weed control shall never be performed by mechanical cultivation or by scraping. Herbicide

All construction must comply with AS 4419-2018 Soils for Landscaping and Garden Use. Spread the topsoil on the prepared subsoil and grade evenly, making allowances, if appropriate,

- Compact lightly and uniformly in 150 mm layers. Avoid differential subsidence and excess compaction and produce a finished topsoil surface which has the following characteristics: Finished to design levels, smooth and free from stones or lumps of soil. Graded to drain freely, without ponding, to catchment points. Grade evenly into adjoining ground surfaces ready

Remove weeds, rubbish, mulch and other debris. Do not disturb tree roots or services and if necessary cultivate these areas by hand. Spread topsoil on the prepared subsoil and grade evenly, making the necessary allowance to permit the required finished levels and contours after a light compaction. Spread topsoil to the typical depth of 300mm. Feather edges into

Health & Vigour: Supply plants with foilage size, texture & colour consistent with that shown in healthy specimens of the species. Balance of Crown: Supply plants with max. variation in crown bulk on opposite sides of stem axis, +/- 20%. Stock selection should also be based on NATSPEC Guide Specifying Trees: a Guide to Assessment of Tree Quality.

Carefully load, transport and unload, at the nominated site, the specified trees. All trees are to be delivered in such a way to prevent in transit wind damage. All trees shall be watered prior to loading for delivery. Plants shall not be contained within delivery vehicles for a period longer than 24hrs. Trees shall be carefully unloaded using methods appropriate to the size and

weight of the trees. Damage to trees sustained during transport or unloading will result in those plants being rejected. Plants shall conform to the requirements at the time of delivery to the planting site. Transpiration shall be minimised during transport to prevent subsequent wilting or unseasonal defoliation. Plants that have been allowed to wilt or dry out during transport shall be rejected, irrespective of any previous acceptance. The soil mass of the root ball shall be securely contained and supported during transport. Root balls that have been unreasonably

When the tree pit is excavated and the hole is the correct size, place the rootball in its final position. Ensure the trees are centred and plumb and the top of the rootball level with the finished surface of the surrounding soil mix. Do not use the trunk of the tree as a lever in positioning or moving the tree in the planting hole. Position the tree at the set out distances as indicated in the details. Ensure trunks are set vertically and aligned with other new or existing trees. Orientate the trees trunk north where indicated by supplied markings where applicable.

All trees shall have the outer 10-25mm of the external root ball faces pruned or sliced away using secateurs or a sharp and clean spade. Avoid excessive disturbance to the remaining root ball during this trimming and discontinue if excessive root ball soil begins to fall away. Do not leave the root balls exposed for extended periods. Cover the root ball with moist hessian if

Install 3 x 2100mm (H) x 50mm x 50mm hardwood timber stakes with hessian ties to all trees. Provide appropriate support considering exposure to prevailing winds. Stakes and hessian

Backfill with soil mix as specified in soil mixes and in accordance with the details and specification. Lightly compact the soil to ensure all voids around root balls are filled and that no air

pockets are retained. Ensure that the backfill soil is not paced over the top of the potted root ball. The top of the root ball and plant stem must be kept level with the top of the backfill.

Fertiliser to be applied at time of planting. Slow release landscape fertiliser suitable for trees and shrubs, 9 to 12 months release time. Osmocote or approved equivalent applied according

Installation: Set edgings flush with adjoining surfaces. Drive pegs into the ground at 1200 mm centres on the planting side of the edging and on both sides of joints between boards, with peg tops 15 mm below top of edging. Fix

Provide a spade edge to separate grassed area from planted areas and to provide a mowing edge. Define trees planted in turf by cutting through soil with garden spade at approximately

All landscaping must comply with AS 4454-2012 Compost, soil conditioners and mulches. All planting areas to receive 50-75mm of garden Mulch, Droughtmaster, ANL p: 02 9450 1444 or

Water in immediately after plant installation & allow for soil settlement. Watering program: Minimum 3 complete waterings, soaking to a depth of 150 mm at fortnightly intervals for the first 6 weeks of plant establishment irrespective of natural rainfall. Manually water all lawn and planting areas in absence of an irrigation system or until the proposed irrigation system is fully operational. Avoid frequent dampening of the surface. Allow the surface of the soil to partially dry out between waterings.

All retaining walls & planter boxes more than 600mm high to be constructed to Engineer's details. Ensure all internal surfaces are waterproofed. Geotextile wrapped ag. drainage line backfilled with aggregate is to be installed behind all retaining walls & connected to stormwater in accordance with Sydney Water regulations. All planter boxes are to have Atlantis drainage

Stabilise: Bury rock one third by volume so that no movement occurs as children travel across them. Ensure height of boulders above ground are under 400mm. Position rocks to ensure

The Contractor shall monitor and maintain all planting and associated landscaping works for the duration of the maintenance period. This shall generally include lawn mowing, watering, failed plant replacements, pest and disease control, weed control and monitoring. Maintenance to be carried out to all areas where new planting is installed. Weeding shall extend around and in between individual plants and up to paths, kerns or other defining edges. Carry out all maintenance activities for all new garden and lawn areas as required to ensure the plants and

allowance to permit the required finished levels and contours after a light compaction. Spread topsoil to the typical depth of 300mm. Feather edges into adjoining undisturbed ground

Trees planted in grass or garden beds with organic mulch surface treatment (100L - 200L nominal size) 600mm total drained soil depth, 200mm topsoil depth 400mm subsoil depth

Remove weeds, rubbish, mulch and other debris. Do not disturb tree roots or services and if necessary cultivate these areas by hand. Spread topsoil on the prepared subsoil and grade evenly, making the necessary

Health & Vigour: Supply plants with foilage size, texture & colour consistent with that shown in healthy specimens of the species. Balance of Crown: Supply plants with max. variation in crown bulk on opposite sides of ster

Carefully load, transport and unload, at the nominated site, the specified trees. All trees are to be delivered in such a way to prevent in transit wind damage. All trees shall be watered prior to loading for delivery. Plants shall not be contained within delivery vehicles for a period longer than 24hrs. Trees shall be carefully unloaded using methods appropriate to the size and weight of the trees. Damage to trees sustained during transport or unloading will result in those plants being rejected. Plants shall conform to the requirements at the time of delivery to the planting site. Transpiration shall be minimised during transport to prevent subsequent wilting or

unseasonal defoliation. Plants that have been allowed to wilt or dry out during transport shall be rejected, irrespective of any previous acceptance. The soil mass of the root ball shall be securely contained and supported

For normal tree planting work there shall be no stockpiling of soils on site. Typically, all materials are to be moved directly from the carrier to the hole or only stockpiled for a very short period of time. Adjoining pavement

Where a drainage layer is coarser particle size than around 5mm diameter, a transition layer may be needed between it and the soil media to prevent soil migrating into the drainage gravel. Generally, this will be an

Use appropriate hand tools when working on smaller sites / individual tree pits or around underground services. If size permits use an excavator with a tyne attachment to loosen the subgrade and mix

Topsoil - A suitable commercially available product such as ANL Organic Garden Mix, or Benedicts SMARTMIX 6 native Garden Mix, or an approved equivalent manufactured garden soil with a maximum 20% organic

Subsoil - A suitable commercially available product such as ANL 80:20 Washed Sand and Screened Soil Blend, or Benedicts SMARTMIX 7 Native garden subsoil mix, or an approved equivalent manufactured soil with a

The installer shall take all practical precautions to ensure that dust and noise caused by the works are kept to a minimum. The installer shall take all practical precautions to prevent the spread of dirt and mud along roads and paths. The installer shall be responsible for all localised sediment and erosion control of work and stockpiles under their control and use. Review of underground services plans sourced from Dial Before You Dig by

Cultivate or rip the subgrade at the base and sides of tree pits to a depth of 100mm. During cultivation, thoroughly mix in any materials required to be incorporated into the subsoil. Remove stones exceeding 70mm and any

Do not plant in unsuitable weather conditions such as extreme heat, cold wind or rain. Avoid planting where unseasonable and adverse weather is forecast within 24 hours of the operations. No trees are to be planted on

Thoroughly water the tree root balls before planting and then immediately after planting. Prevent the root balls from drying out during the planting phase. Apply water so as not to disturb the soil. Raise the moisture within

It is preferred that all trees are carried or slung via the root ball. In the event that the trees have to be repositioned or lifted by the trunk, the installer shall provide adequate soft padding to the trunk in the form of underfelt,

When the tree pit is excavated and the hole is the correct size, place the rootball in its final position. Ensure the trees are centred and plumb and the top of the rootball level with the finished surface of the surrounding soil

vertically and aligned with other new or existing trees. Orientate the trees trunk north where indicated by supplied markings where applicable. (+or20o). Adjust within the above tolerances so that the primary lowest

All trees shall have the outer 10-25mm of the external root ball faces pruned or sliced away using secateurs or a sharp and clean spade. Avoid excessive disturbance to the remaining root ball during this trimming and

Install 3 x 2100mm (H) x 50mm x 50mm hardwood timber stakes with hessian ties to all trees. Provide appropriate support considering exposure to prevailing winds. Stakes and hessian ties to be removed as soon as the

Backfill with soil mix as specified in soil mixes and in accordance with the details and specification. Lightly compact the soil to ensure all voids around root balls are filled and that no air pockets are retained. Ensure that the

Fertiliser to be applied at time of planting. Slow release landscape fertiliser suitable for trees and shrubs, 9 to 12 months release time. Osmocote or approved equivalent applied according to manufacturers directions. Any soil conditioners and mulch shall comply with AS4454-2012 Composts, Soil Conditioners and Mulches. Unless otherwise noted the mulch shall be a minimum of 50mm depth and a maximum of 75mm depth. Mulch

types shall be: 15mm graded aged horticultural pine bark fines or 50mm minus recycled urban wood waste. Mulch shall be free of deleterious and extraneous matter, including soil, weeds, rocks twigs and the like. Place

Preparation: Excavate to required levels and compact subgrade. Place and compact minimum 50 mm cement stabilised crusher dust as bedding layer for synthetic grass.

SITE PREPARATION

for the following:

PLANTING AREA

TREE DELIVERY

adjoining undisturbed ground. PLANT STOCK

TREE PLACEMENT AND ALIGNMENT

backfilling cannot occur immediately.

TIMBER GARDEN EDGING

the pegs with galvanised nails, two per fixing.

RETAINING WALLS & PLANTER BOXES

Install Synthetic Turf as shown on Plan.

Laying: Cut to shape and spread without wrinkles. Joints: To the manufacturer's detail.

there is no potential limb entrapment hazards or gaps.

Placing rock: Place while ground formation work is being carried out.

and road surfaces are to be maintained in a clean and tidy state at all times.

If required by soil testing, apply any necessary soil ameliorants

Fair and trim to relative level to accommodate the required overall soil depths

Remove rubbish such as construction generated waste, plastics, metals and glass

ties to be removed as soon as the tree is self supporting.

STAKING

BACKFILLING

SPADE EDGING

MULCHING

WATERING

SYNTHETIC TURF

SOIL STOCKPILING

DRAINAGE LAYER

TREE PLANTING SUBGRADE PREPARATION

Remove rocks > 70 mm diameter

maximum 5% organic matter by volume, may be used.

carpet or rubber wrapping and use only soft slings during the lifting.

branches are generally aligned parallel with the kerb and road way (NOT extending into roadway).

the mulch so that it is not in direct contact with the trunk. Feather mulch layers away from trunk at the root crown.

Define beds around trees planted in grassed areas by cutting through soil with garden spade at approximately 70° to vertical.

ENVIRONMENTAL CONTROLS

contractor before installation. SUBGRADE PREPARATION

LIFTING OF TREES

ROOT TRIMMING

tree is self supporting. BACKFILLING

SPADE EDGING

fertilising pest and disease control

TREE ESTABLISHMENT PERIOD


PLACEMENT AND ALIGNMENT

SOIL DEPTH

SITE ADDRESS: 30-32 Brabyn Street,

PEPS-SLD-ZZ-GF-DR-L-0007 E

IMPORTED FILL AND NEW TURF OVER)



LANDSCAPE SPECIFICATION NOTES

01 NEW TURF DETAIL
SCALE 1:10

SITE PREPARATION

Locate any underground and overground services & ensure no damage occurs. SOIL REMOVAL

Eradicate larger debris and waste. Remove 300mm of existing topsoil as shown on plans. IMPORTED TOPSOIL

All construction must comply with AS 4419-2018 Soils for Landscaping and Garden Use. Spread the topsoil on the prepared subsoil and grade evenly,

making allowances, if appropriate, for the following:

- Required finished levels and contours after light compaction.

- Finished to design levels, smooth and free from stones or lumps of soil. Graded to drain freely, without ponding, to catchment points. Grade evenly into adjoining


TURFING New turf - Sir Walter Softed Leafed Buffalo (Stenotaphrum Secundatum type Sir Walter PBR 1996/226) sourced from a licensed supplier. Sir walte should be weed

free and free of any other foreign grasses, disease or pests. Excavate all areas to be turfed and remove 300mm of existing topsoil and dispose of appropriately offsite. Further rip the subgrade to 150mm.

Import new topsoil to a depth of 200mm. Install 100mm of imported turf underlay. Rolls to be closely butted and laid in a brickwork pattern. Fill any small gaps with topsoil and water thoroughly. Ensure that all surface runoff is directed away from buildings. Ensure that no pooling or ponding will occur.

ground surfaces.

Immediately after installation, water in to soaker depth of 200mm. Watering program: Daily complete waterings in the morning and keep moist, until it is firmly rooted (about 2 weeks). As the root establish, less frequent and deeper watering up to 6 weeks after installation. Weather conditions will dictate the amount and frequency of watering. Ensure the newly laid turf has enough moisture to survive hot, dry and windy conditions.





Name: Parramatta East Public School Upgrade

Address: ZONE 1



BUCKINGHAMIA CELSISSIMA



Name: Parramatta East Public School Upgrade

Address: ZONE 1







BACKHOUSIA MYRTIFOLIA BANKSIA SPINULOSA CALLISTEMON CITRINUS 'ENDEAVOUR'







DORYANTHES EXCELSA PHORMIUM TENAX ACACIA COGNATA 'FETTUCCINI'







CAREX APPRESSA DIANELLA CAERULEA 'LITTLE JESS' GAHNIA SIEBERIANA







ISOLEPIS NODOSA JUNCUS USITATUS LOMANDRA LONGIFOLIA





THEMEDA AUSTRALIS

WESTRINGIA FRUTICOSA 'LOW HORIZON'



Name: Parramatta East Public School Upgrade

Address: ZONE 2







CYATHEA COOPERI

ELAEOCARPUS RETICULATUS 'PRIMA DONNA'

CRINUM PEDUNCULATUM







ARTHROPODIUM CIRRATUM 'MATAPOURI BAY'



DIANELLA REVOLUTA



VIOLA HEDERACEA