

ROUSE HILL HIGH SCHOOL UPGRADE CIVIL ENGINEERING REVIEW OF ENVIRONMENTAL FACTORS REPORT





Prepared for: Department of Education By: **en**struct group pty ltd

ROUSE HILL HIGH SCHOOL CIVIL ENGINEERING REVIEW OF ENVIRONMENTAL FACTORS REPORT

ISSUE AUTHORISATION


PROJECT: Rouse Hill High School Project No: 6746

Rev	Date	Purpose of Issue / Nature of Revision	Prepared by	Reviewed by	lssue Authorised by
А	21/01/25	REF Design Report	MZV	PAL	PAL
В	18/02/25	REF Design Report Updated	PAL	PAL	PAL
С	10/03/25	REF Design Report Updated	PAL	PAL	PAL

COPYRIGHT ©

This report is the property of enstruct group pty Itd and is licensed to the Client for use on this project. Reproduction of this document for this project shall only be undertaken in full. Reproduction for other purposes without the permission of enstruct group pty Itd is prohibited.





Executive Summary

enstruct have been engaged by Department of Education to provide civil engineering advice for the design for upgrades to Rouse Hill High School (hereafter RHHS). This report relates to the civil elements of the works with a specific focus on the Environmental Factors associated with the civil design, such as flooding, erosion and sediment control, and water quality and quantity. The full list of areas this Review of Environmental Factors (REF) report covers is listed below.

This REF report covers:

- Onsite Stormwater Detention (OSD)
- Water Sensitive Urban Design
- Flooding
- Stormwater Overland Flow
- Ground conditions
- Earthworks
- Pavement design
- Erosion and Sediment control

Contents

1	Introduction
	1.1 Significance of Environmental Impacts
	1.2 Mitigation Measures
2	Site Description
	2.1 Previous Site Uses
	2.2 Existing Stormwater
	2.3 Existing Geotechnical Conditions and Soil Contami
3	Stormwater Design
	3.1 Environmental Flows
	3.2 Onsite Stormwater Detention (OSD)
	3.2.1 DRAINS Modelling
	3.3 Flooding
	3.4 Overland Flow Paths
	3.5 Stormwater Quality
	3.5.1 MUSIC Modelling
	3.6 Integrated Water Management Plan
4	Erosion and Sediment Control
5	Civil Design
	5.1 Earthworks
	5.2 Pavements
6	Conclusion
Su	pporting Information and External References
	, , , , , , , , , , , , , , , , , , ,
AF	PENDIX A – Civil Drawings

enstruct MEMBER OF WSP

	4
	5
	5
	5
nination	6
	6
	6
	7
	8
	8
	9
	10
	10
	10
	10
	11
	11
	12

1 Introduction

This Civil Engineering report has been prepared by enstruct to accompany a Review of Environmental Factors (REF) for the Department of Education (DoE) for upgrades to Rouse Hill High School (the activity) under Part 5 of the Environmental Planning and Assessment Act 1979 (EP&A Act) and State Environmental Planning Policy (Transport and Infrastructure) 2021 (SEPP TI).

This document has been prepared in accordance with the Guidelines for Division 5.1 assessments (the Guidelines) by the Department of Planning, Housing and Infrastructure.

This report examines and takes into account the relevant environmental factors in the Guidelines and Environmental Planning and Assessment Regulations 2021 under Section 170, Section 171 and Section 171A of the EP&A Regulation as outlined in Table 1.

Table 1 – Summary of Relevant Section of the Part 5 Guidelines and EP&A Regulation			
Regulation / Guideline Section	Requirement	Response	Report Section
2a	Any environmental impact on the community	The proposed development will have negligible environmental effect on the community during construction and post construction.	2-4
2h	Any long term effects on the environment	The proposed development will have negligible long term impacts on the environment	2-4
2j	Risk to safety of the environment	The proposed development will have negligible impacts to the safety of the environment	2-4
21	Any pollution of the environment	The proposed development will have negligible pollution impacts	2-4

1.1 Proposed Activity Description

The proposed activity for the alterations and additions to Rouse Hill High School including:

- Demolition of existing footpaths, stairs, and the relocation of an existing seating shelters towards the west of Block F;
- Removal of nine (9) trees;
- Construction of a two (2) storey classroom building (known as Building L), comprising eleven (11) general learning spaces (GLS) and 2 Science Labs;
- Construction of new footpaths and a new covered bicycle parking space;
- New emergency vehicle accessway; and
- Landscaping, including the planting of trees.

1.2 Activity Site

The project site is located on Withers Road in Rouse Hill and is legally described as Lot 105 in Deposited Plan (DP) 1108407. Rouse Hill High School is located on the western side of Withers Road.

Figure 1 provides an aerial photograph of the site.



Figure 1: Aerial Photograph

The school development is aimed at meeting the Educational Facilities Standards and Guidelines (EFSG) and strengthen the curriculum to improve the quality of educational outcomes and improve the efficiency of educational delivery at the school to support student development. The proposed Building L will comprise ten General Learning Spaces (GLS), one enhanced Multi-Purpose Space, and two science laboratories. Additionally, the proposed upgrade will provide a new covered bicycle parking area, a new emergency vehicle accessway, and landscaping. The proposed Site Plan is shown in **Figure 2**.





Figure 2: Proposed Site Plan (Source: djrd architects)

1.3 Significance of Environmental Impacts

Based on the identification of potential issues, and an assessment of the nature and extent of the impacts of the proposed development, it is determined that:

- The extent and nature of potential impacts are low and will not have a significant impact on the locality, community or the environment, and
- Potential impacts can be appropriately mitigated or managed to ensure that there is no significant impact on the environment or community.

1.4 Mitigation Measures

As all the mitigation measures designed to alleviate the environmental impacts are described in future chapters, the following table provides a summary:

Table 1: Environmental Impact Mitigation Measures related to Civil Engineering

Project Stage D – Design C – Construction O - Operation	Mitigation Measures	Relevant section of the report
D, C	Erosion and Sediment control measures	Section 4
D, C, O	Stormwater Quantity Control measures (OSD)	Section 3.2
D, C, O	Stormwater Quality Control measures (WSUD)	Section 3.5
D	Flood analysis and planning measures	Section 3.3

2 Site Description

Rouse Hill High School is located at 240 Withers Road, Rouse Hill, within the Hills Shire Local Government Area (LGA). It is situated within a well-established residential area. The site is bordered by Withers Road to the east and Caballo Street to the west. Kanebridge Oval is located to the north of the school and Ironbark Ridge Public School along the southern boundary. Furthermore, Caddies Creek lies to the west which leads into Caddies Boulevard Lake. Further, there is a dedicated bus zone along Withers Road, which is in the shape of a dedicated slip lane. The built form and land use character surrounding the site is predominantly low scale, 1-2 storey dwelling houses. The site has a total area of approximately 2.2 hectares. The site is legally described as Lot 105 DP 1108407. The site is currently occupied by eleven, one and two storey, brick and timber panelled, buildings which appear to be in good external condition. **Figure 3** shows a typical example of the two-storey building.



Figure 3: Two Storey Building at the Site

2.1 Previous Site Uses

Prior to the RHHS's opening in 2009, the site featured a golf course as can be seen at the school's site, refer to **Figure 4**. The golf course was across Caddies Creek and into now neighbouring plots that have since been redeveloped into Rouse Hill Town Centre and commercial plots. Before the creation of the golf course, the site was farmland.



Figure 4: Golf Course at Site, circa 2005 (Source: Google Earth)



2.2 Existing Stormwater

The site has several existing stormwater pits located between the buildings, draining to the north west and drains into Caddies Creek. The existing drawings received by enstruct are based on the construction drawings from the school's initial construction circa 2007 and are shown in **Figure 5**.

Four above ground tanks exist on the campus. Two tanks on the eastern boundary are understood to collect roof water off the adjacent buildings and COLA and are used for reuse. The existing tanks on the northern boundary are understood to be part of the Rouse Hill recycled water scheme used for the oval irrigation.




Figure 5: As Built Stormwater System (Bonacci, 2007)

2.3 Existing Geotechnical Conditions and Soil Contamination

A geotechnical investigation has been undertaken by Douglas Partners (ref: Project 215851.00). The soil conditions at the site are typically topsoil/fill, up to 300mm depth, overlying by clay, down to around 1.5m depth. Below the clay lies weathered sandstone rock, down to about 2.3m depth with hard bedrock below. A CBR of 4.5 and 5% was returned for clay samples tested. A CBR of no greater than 3.0% will be adopted for the pavement design. The clay is noted as moderately dispersive. Fill exists in the western portion through the fields and COLA, as well down to the western boundary.

Being constructed in 2007, the school campus is not expected to be contaminated. Advice from Douglas Partners (ref: Project 215851.00, R.003.Rev0, PF:TW) indicates that excavated material can be disposed of as General Solid Waste (GSW). It is noted that PFAS has been detected in soil samples, however the amount detected was less than the NSW EPA, 2014,

Waste Classification Guidelines Part 1; Classifying Waste, Maximum values for leachable concentration (TCLP) and specific contaminant concentration (SCC) when used together: General solid waste and NSW EPA, 2014, Waste Classification Guidelines Part 1; Classifying Waste, Maximum values for leachable concentration (TCLP) and specific contaminant concentration (SCC) when used together: General solid waste.

3 Stormwater Design

The stormwater design must be in accordance with Australian Standards, Hills Shire Council Standards, Australian Rainfall and Runoff (2016), and School Infrastructure NSW's Educational Facilities Standards & Guidelines (hereafter EFSG) section DG95 Stormwater.

In general, all new roof stormwater will be collected in roof gutters and downpipes and conveyed to a 5kL rainwater tank as designed by the Hydraulic Engineer. Surface stormwater will be collected in stormwater drainage pits. The in-ground stormwater and the rainwater tank overflow will be connected to water quality controls and the Onsite Stormwater Detention (hereafter OSD).

Pipes and pits will need to be designed to satisfy the minimum provisions of AS 3500.2 and EFSG. They must be designed to convey at least the 5% Annual Exceedance Probability (AEP) flows. Where pipe capacity is exceeded i.e., greater than 5% AEP, stormwater will be conveyed as overland flow. Overland flow paths are to be designed to convey at the minimum 1% AEP stormwater flows with a Depth x Velocity to be less than $0.4m^2/s$.

3.1 Environmental Flows

Industry standard best practice require water sensitive design principles be incorporated into new developments. All works are to minimise runoff, maximise treatment of stormwater by directing stormwater to landscape-based treatment systems, maximise capture and reuse of runoff and ensure the is no impact on receiving water during construction. Environmental Flows are included as part of Water Sensitive Urban Design system which is discussed in following sections.

enstruct MEMBER OF WSP

3.2 Onsite Stormwater Detention (OSD)

The Hills Shire Council Design Guidelines for Subdivisions and Developments, Section 4.22, describes the OSD requirements for the Site. Appendix A identifies Rouse Hill as part of the Hawkesbury River Major River Catchment, and hence, the OSD design is to be in accordance with the respective guidelines for this catchment. The Major River Catchments map is shown in **Figure 6** below.

MAJOR RIVER CATCHMENTS




Figure 6: Major River Catchments Map (Source: The Hills Shire Council Design Guidelines for Subdivisions and Developments, Appendix A)

The Permissible Site Discharge (PSD) and Site Storage Volume (SSV) requirements for the Site are dictated in the Hills Shire Council Design Guidelines for Subdivisions and Developments, Section 4.22. The requirements are based on the site slope, as can be seen in **Figure 7**.

Site Slope	PSD (l/s/ha)	SSV (m ³ /ha)
Greater than 15%	136	298
Between 10% and 15%	115	336
Between 6% and 10%	104	362
Between 3% and 6%	92	396
Between 0% and 3%	87	412

Figure 7: PSD and SSV Requirements for the Hawkesbury River Catchment (Source: The Hills Shire Council Design Guidelines for Subdivisions and Developments)

The slope across the development area of the site is an average of 5.1%. Hence, the requirements for sites with a slope between 3% and 6% apply. The development area has been highlighted in red and purple in **Figure 8** below, with runoff from the red area bypassing the OSD, and runoff from the purple area being directed to the OSD. The total area is 1,921m². The path to the rear entry has not been included in the OSD calculation as it is an existing path. The OSD is therefore designed to a minimum SSV of 76.07m³ and with a PSD of 17.67L/s (including bypass discharge).




Figure 8: OSD Calculation Development Area



The OSD must be designed and constructed to control stormwater runoff from development sites such that, for all peak stormwater events up to and including 1%AEP discharges from the site does not exceed pre-development stormwater discharges. The ESFG notes the preference for open and absorption storage systems, this is equivalent to a fenced pond. While this might sound effective for a big site, this Site is unsuitable for an open storage system to due to the size of the development and gradient of the surrounding land. Additionally, the fencing and signage can impact the aesthetics of the site. Therefore, an underground OSD is proposed, which also reduces the risks of kids accessing the structure.

3.2.1 DRAINS Modelling

A DRAINS Model was created and analysed to ensure the discharge from the Site does not exceed the PSD or the pre-development flow rates, and to confirm the OSD size. The model confirmed the ability of an 88.12m³ OSD tank with a 65mm orifice plate to meet these requirements. A comparison of the post-development flow rates from the site, including the flows bypassing the OSD tank, compared to the predevelopment flow rates and PSD across a range of storm events is shown in Table 2.

Table 2: Site Discharge Rate Comparison

Storm Event	Pre-development Discharge Rate	Post-development Discharge Rate
		(PSD = 17.67L/s)
20% AEP	48L/s	12L/s
10% AEP	62L/s	12L/s
5% AEP	76L/s	14L/s
1% AEP	102L/s	17L/s

Flooding 3.3

The school site is located east of Caddies Creek. As part of the Kellyville Station development in 2015, Hyder produced a flood study showing the 1% AEP flood extents/heights along Caddies Creek. Below in Figure 9 is an excerpt from Hyder's report showing the 1% AEP flood extent and the Rouse Hill High School campus indicating that flooding is not a concern for the campus including the proposed works, as the site is elevated and away from Caddies Creek.



Figure 9: Peak 1% AEP flood extent (Source: Kellyville Station Upgrade, Hyder Consulting 2015)

Overland Flow Paths 3.4

Any stormwater overflow from the gutters of proposed buildings shall be collected by inlet pits on the ground and/or drained via overland flows paths into the existing stormwater system. Where this is not possible, the gutter and stormwater system shall be designed to convey the 1% AEP storm event to the detention system.

Stormwater Quality 3.5

Stormwater discharged from the development will be treated in accordance with Hills Shire Council's Stormwater Management, Water Sensitive Urban Design (WSUD) and Environmental Flows. The site stormwater will pass through suitable pollution control devices to achieve the required water quality removal rates noted in Table 3.



Table 3: General Stormwater quality requirements (Source: Hills Shire City Council DCP 2011)

Pollutant	Hills Shire Annual Reduction Requirement
Total Suspended Solids (TSS.)	85%
Total Phosphorous (TP)	65%
Total Nitrogen (TN)	45%
Gross Pollutants (GP)	90%

As site constraints permit, Water Sensitive Urban Design practices can be easily accommodated into the campus. However, the safety to the school population needs to be considered. Therefore, mechanical (in lieu of natural removal) pollutant removal devices are to be incorporated to remove gross pollutants, suspended solids, reduce nutrient runoff including nitrogen and phosphorous. The pollution control devices will require on-going maintenance, with at least yearly inspection and maintenance. Further advice should be sought from the manufacturer.

It is proposed that a series of pollution control devices will need to be provided to remove contamination from stormwater runoff to the required level prior to discharge. It is expected that the devices will include, litter screens in all pits, detention tank trash screen and an end of line treatment device to remove nitrogen and phosphorus contaminants etc., prior to discharge to the Authority's stormwater system. This system is preferred as it will be able to achieve pollutant reductions required, is easily maintained, and does not require large open areas or pose safety risk to the school population. The ESFG notes the preference for open and absorption storage systems.

Pollutant removal rates as required by Council are to be in accordance with best practice. The removal rates will be in accordance with:

- The EPA's manual on Managing Urban Stormwater (Treatment Techniques)
- Stormwater Treatment Devices User Guide (NSW Supply) Government Contract No.019, July 1999, Department of Public Works and Services
- The relevant Australian Standards for pollution control devices

The ESFG notes that stormwater is to be treated to remove foreign matter and ensure minimal impact.

MUSIC Modelling 3.5.1

A MUSIC Model has been developed in accordance with Hills Shire Council requirements to indicate the suitability of the proposed pollution removal measures for the site. The proposed water quality control devices for the site are:

- One 5kL rainwater tank collecting run-off from Building L roof,
- footpaths, and
- 4 690mm Psorb OceanProtect Stormfilter cartridges within the OSD tank.

The results of the MUSIC model confirmed the ability of the above devices to reduce the pollutants discharged from the site to below the requirements described by council, as can be seen inTable 4.

Table 4: MUSIC Modelling Results

Pollutant	Reduction Requirement	Annual Pollutant Reduction Results
Total Suspended Solids (TSS.)	85%	86%
Total Phosphorous (TP)	65%	79%
Total Nitrogen (TN)	45%	54%
Gross Pollutants (GP)	90%	96%

Integrated Water Management Plan 3.6

The integrated water management plan is a holistic and collaborative approach of the water cycle and consider elements such as: Potable water, Rainwater reuse, Recycled water, Surface stormwater, Groundwater, Stormwater detention, Water quality, among others.

In this report, civil has covered the elements related to surface stormwater, stormwater quality and stormwater detention. For potable water, and rainwater storage and reuse, refer to the Hydraulics engineering drawing which is included with the civil plans.



At least 7 OceanProtect OceanGuard pit inserts across the pits on the driveway and

Erosion and Sediment Control 4

During construction and while the site is disturbed, erosion prevention and sediment control measures will be required. Erosion prevention generally involves managing stormwater by diverting overland flow around construction areas as well as collecting stormwater within the construction zone and directing to sediment control devices. Devices likely to be incorporated are silt capture fences, hay bales, and grass lined swales; water flow dissipation and discharge control devices such as sand bags, pollution mattresses, and basins.

Erosion prevention and sediment removal strategies need to be inspected regularly during service and construction works, cleaned, and maintained after storm events, and modified to suit construction work progress, decanting, and demolition.

Erosion and sediment control is to be provided in accordance with the "Blue Book" Part 1 [Landcom (2004) Managing Urban Stormwater: Soils and Construction, 4th edition].

5 Civil Design

Earthworks 5.1

Careful consideration should be given to the floor level for the proposed building to reduce excavation or filling.

The location of the proposed buildings and the impact buildings being retained need to be considered. Therefore, the importance of a detail geotechnical investigation is needed to assess the existing ground conditions.

Earthworks volumes will be confirmed as the design progresses. Due to the significant level difference across all sites, cut/fill with retaining walls may be required.

5.2 **Pavements**

Pavements are to meet the requirements of the geotechnical investigation and the ESFG. The following items are applicable:

- All pavements to be designed for a 25-year life.
- All pavements trafficked by buses and trucks to be designed for a minimum 5 x 10⁵ repetitions of a standard axle load, as defined by AUSTROADS.
- For other vehicular traffic areas design for 1.0 x 10⁵ repetitions of a standard axle load, as defined by AUSTROADS.
- Allow for movements in the foundations caused by moisture variations and mine . subsidence.

- at joints.
- reinforced concrete surface.
- construction finish with a surface coat of asphaltic concrete.
- Breccia or dolerite is not to be used in road base or concrete mix.
- trafficked pavements.
- or greater as the design requires.
- Limit fly ash content to 20% of cementitious content of mix by weight. ٠
- compressive strength.
- with not less than SL92 mesh at top and 100 mm thick road base.
- less than SL72 mesh at top.
- ٠ durability requirements for minimum cover to reinforcement.
- For flexible construction finish with a surface coat of asphaltic concrete.

Design rigid pavements so there is no vertical differential movement between panels

• For truck turning areas pavements shall be rigid in construction and finished with a

For other areas pavements may be either flexible or rigid in construction. For flexible

Non-skid finish for vehicular trafficked pavements and non-slip finish for pedestrian

AC for the emergency accessway to be AC10 and have minimum thickness of 40mm

For the emergency accessway, concrete shall have minimum 32 MPa characteristic

For rigid method of construction finish with a reinforced concrete surface.

Concrete pavements for vehicles shall be a minimum 150mm thick and reinforced

Other concrete pavements shall be a minimum 100mm thick and reinforced with not

Provide a thicker pavement and heavier mesh as the design requires and to meet

Conclusion 6

The civil works associated with the design and construction of the upgrade at RHHS will be carried out in accordance with normal engineering practice and will meet the requirements of relevant standards.

After consideration of the Council requirements for the site and the existing conditions, an 88.12m³ OSD tank will be required at the site to ensure the downstream stormwater drainage system will not be over capacity post-development. A combination of a rainwater tank, pit inserts, and stormfilter cartridges will work in tandem to remove pollutants from the stormwater collected from the upgrade to below the requirements outlined by Council.

Erosion and sediment control measures are to be in place during construction to prevent contamination of the downstream stormwater system and tracking of grit and sediment onto the roadway.

Subject to implementing the recommendations/mitigation measures such as erosion control, water quantity management and water quality management of this report, the conclusion of this assessment is that the proposed Activity is not likely to significantly affect the environment in relation to stormwater and soil matters.

Supporting Information and External References

Bonacci Group Rouse Hill Secondary School Drawing Set, for construction 07/11/07 Project code: 8029

Hyder Kellyville Station Precinct Flooding and Drainage Precinct Planning, Rev1 14/08/15 https://www.planning.nsw.gov.au/sites/default/files/2023-03/kellyville-station-precinct-appendix-kflooding-and-drainage.pdf

Douglas Partners Report on Geotechnical Investigation, Rev0 16/11/2022 215851.00.R.001.Rev0

Project Surveyors Detail Survey Revision B, 07/05/2024 Job reference: 5289

Before You Dig Australia https://www.byda.com.au/

ESFG https://efsg.det.nsw.edu.au/design https://efsg.det.nsw.edu.au/spec https://education.nsw.gov.au/about-us/efsg/design-framework

NSW LGA boundaries map

https://portal.spatial.nsw.gov.au/portal/home/webmap/viewer.html



APPENDIX A – Civil Drawings



ROUSE HILL HIGH SCHOOL 240 WITHERS ROAD, ROUSE HILL, NSW 2155



LOCALITY PLAN SCALE: 1:2000

TO BE PRINTED IN FULL COLOUR

06	04/03/25	ISSUE FOR CONTRACT DOCUMENTS	NTV	PAL
05	21/01/25	ISSUE FOR REF	MZV	PAL
04	14/01/25	ISSUE FOR 100% SCHEMATIC DESIGN	MZV	PAL
03	13/12/24	ISSUE FOR 50% SCHEMATIC DESIGN	MZV	PAL
02	08/05/23	FOR 100% SCHEMATIC DESIGN	BEJ	KEH
01	04/04/23	ISSUE FOR 50% SD TENDER	BEJ	KEH
rev	date	description	drn	ch'k

07	10/03/25	REISSUE FOR REF	NTV	PAL	
rev	date	description	drn	ch'k	



Education School Infrastructure

enstruct **CIVIL ENGINEERING WORKS**

CIVIL ENGINEERING WORKS DRAWING LIST:

6746-CV-0000 6746-CV-0001	COVER SHEET NOTES SHEET
6746-CV-0101 6746-CV-0151	SEDIMENT AND EROSION CONTROL PLAN SEDIMENT AND EROSION CONTROL DETAI
6746-CV-0201	BULK EARTHWORKS PLAN
6746-CV-0301	SITEWORKS PLAN
6746-CV-0401	PAVEMENT PLAN
6746-CV-0501 6746-CV-0502 6746-CV-0503	DETAILS SHEET 1 DETAILS SHEET 2 DETAILS SHEET 3

enstruct group pty Itd

Level 4, 2 Glen Street Milsons Point NSW 2061 Australia

Telephone (02) 8904 1444 Facsimile (02) 8904 1555 www.enstruct.com.au enstruct

ROUSE HILL HIGH SCHOOL UPGRADE

240 WITHERS ROAD, ROUSE HILL NSW 2155

CO LOC

drawing title

status									
FOR REVIEW									
scale at A1	drawn	checked	approv	/ed					
AS SHOWN	ВЕЈ КЕН			ΈH					
project no.	sheet			rev.					
6746	6746-)	07						

NOT FOR CONSTRUCTION

AILS

DESIGN & CONSTRUCT DOCUMENTATION

- 1. The level of detail / design reflected in these documents is based on the understanding this will be built as part of a design & construct contract.
- 2. The contractor shall retain the responsibility to undertake detailed design, confirm compliance with relevent standards, concent conditions & the specification.
- 3. The contractor shall be responsible for ensuring the final design is co-ordinated fully with other consultants.
- 4. No variation will be accepted for design amendments required to meet the functional objective of this documentation.

CIVIL SAFETY IN DESIGN

enstruct (NSW) Pty Ltd operates under Safe Work Australia's code of Conduct for the Safe Design of Structures. These drawings shall be read in conjunction with the enstruct Civil

risk and Solutions Register Under the Code of Conduct it is the Client's responsibility to provide a copy of the Civil Risk and Solutions Register to the Principal

Contractor. It is the Principal Contractor's responsibility to review the hazards and risks identified during the design process to ensure a safe workplace is maintained for the construction, maintenance and eventual demolition of the civil infrastructure.

DBYD SERVICES NOTE

"Public Service Utility information shown on plan has been complied from information received from Dial Before You Dig inquiry, reference Number 31056628, which was obtained on 10/12/21 Unless specifically shown otherwise, this location and depth of services shown on this plan have not been verified.

The location of services shown on this drawing have been plotted as accurately as possible from diagrams provided by service authorities and should be confirmed by site inspection."

SURVEY AND SERVICES INFORMATION SURVEY

: GNSS RTK OBSERVATIONS Origin of levels : A.H.D. AUSTRALIAN HEIGHT DATUM Datum of levels Coordinate system : GDA2020 Survey prepared by : PROJECT SURVEYORS : CONTACT THE SURVEYOR Setout Points

enstruct does not guarantee that the survey information shown on these drawings is accurate and will accept no liability for any inaccuracies in the survey information provided to us from any cause whatsoever.

UNDERGROUND SERVICES - WARNING The locations of underground services shown on enstruct drawings have been plotted from diagrams provided by service authorities. This information has been prepared solely for the authorities own use and may not necessarily be updated or accurate. The position of services as recorded by the authority

at the time of installation may not reflect changes in the physical environment subsequent to installation.

enstruct does not guarantee that the services information shown on these drawings shows more than the presence or absence of services, and will accept no liability for inaccuracies in the services information shown from any cause whatsoever.

The Contractor must confirm the exact location and extent of services prior to construction and notify any conflict with the drawings immediately to the Engineer/Superintendent.

The contractor is to get approval from the relevant state survey department, to remove/adjust any survey mark. This includes but is not limited to; State Survey Marks (SSM), Permanent Marks (PM), cadastral reference marks or any other survey mark which is to be removed or adjusted in any way.

enstruct plans do not indicate the presence of any survey mark. The contractor is to undertake their own search.

BOUNDARY AND EASEMENT NOTE

The property boundary and easement locations shown on enstruct drawing's have been based from information received from: No boundary information received.

Refer architect for boundary information and locations enstruct makes no guarantees that the boundary or easement information shown is correct, enstruct will accept no liabilities for boundary inaccuracies. The contractor/builder is advised to check/confirm all boundaries in relation to all proposed work prior to the commencement of construction. Boundary inaccuracies found are to be reported to the superintendent prior to construction starting.

SITEWORKS NOTES

1. All basecourse material to comply with RMS specification No 3051 and compacted to minimum 98% modified dry density in accordance with AS 1289

2. All trench backfill material shall be compacted to the same density as the adjacent material. 3. All service trenches under vehicular pavements

shall be backfilled with an approved select material and compacted to a minimum 98% standard maximum dry density in accordance with AS 1289 5.1.1

GENERAL NOTES

- 1. Contractor must verify all dimensions and existing levels on site prior to commencement of works. Any discrepancies to be reported to the Engineer
- 2. Strip all topsoil from the construction area. All stripped topsoil shall be disposed of off-site unless directed otherwise.
- 3. Make smooth connection with all existing works. 4. Compact subgrade under buildings and pavements to minimum 98% standard maximum dry density in accordance with AS 1289 5.1.1. Compaction under buildings to extend 2m minimum beyond building footprint.
- 5. All work on public property, property which is to become public property, or any work which is to come under the control of the Statutory Authority; the Contractor is to ensure that the drawings used for construction have been approved by all relevant authorities prior to commencement site.
- 6. All work on public property, property which is to become public property, or any work which is to come under the control of the Statutory Authority is to be carried out in accordance with the requirements of the relevant Authority. The Contractor shall obtain these requirements from the Authority. Where the requirements of the Authority are different to the drawings and specifications, the requirements of the Authority shall be applicable. 7. For all temporary batters refer to geotechnical recommendations.
- 8. The approval of a substation shall be sought from the superintendant but is not an authorisation of a cost variation. The superintendant must approve any cost variation before any work starts

STORMWATER DRAINAGE NOTES

- 1. Stormwater Design Criteria:
- (A) Average exceedance probability 1% AEP for roof drainage to first external pit
- 5% AEP for paved and landscaped areas (B) Rainfall intensities -
- Time of concentration: 5 minutes
- 1% AEP = 235 mm/hr
- 5% AEP = 177 mm/hr (C) Rainfall losses -
- Impervious areas: IL= 1.0 mm, CL = 0 mm/hr Pervious areas: IL= 29mm , CL=1.0 mm/hr
- 2. Pipes 300 dia and larger to be reinforced concrete Class 2" approved spigot and socket with rubber ring joints U.N.O. Pipes in public roadways (including public domain) to be class 4 reinforced concrete.
- 3. Pipes up to 300 dia may be sewer grade uPVC with solvent welded joints, subject to approval by the
- engineer
- 4. Equivalent strength VCP or FRP pipes may be used subject to approval.
- 5. Pits in roadways (including public domain) are to be
- insitu to council details. 6. Enlargers, connections and junctions to be manufactured
- fittings where pipes are less than 300 dia. 7. Where subsoil drains pass under floor slabs and
- vehicular pavements, unslotted uPVC sewer grade pipe is to be used.
- 8. Grates and covers shall conform with AS 3996-2006, and AS 1428.1 for access requirements.
- 9. Pipes are to be installed in accordance with AS 3725. All bedding to be type H2 U.N.O.
- 10. Care is to be taken with invert levels of stormwater lines. Grades shown are not to be reduced without approval
- 11. All downpipe connections are to be 150mm DIA or the same size as the downpipe (whichever is larger) laid at 1% minimum fall connection to the nearest pit. Minimum cover 450mm in landscaped areas. 12. Subsoil drains to be slotted flexible uPVC U.N.O.
- 13. Adopt invert levels for pipe installation (grades shown are only nominal).

CONCRETE NOTES

EXPOSURE CLASSIFICATION : External :B1

CONCRETE

Place concrete of the following characteristic compressive strength f'c as defined in AS 1379.

Location	AS 1379 f'c MPa	Specified	Nominal
	at 28 days	Slump	Agg. Size
Kerbs	S20	80	20
Pavements	S32	80	20
Retaining wall footing	S40	80	20

1. Use Type 'GP' cement, unless otherwise specified. 2. All concrete shall be subject to project assessment and testing to AS

- 1379 3. Consolidate by mechanical vibration. Cure all concrete surfaces as directed in the Specification.
- 4. For all falls in slab, drip grooves, reglets, chamfers etc. refer to Architects drawings and specifications.
- 5. The location of all construction joints shall be submitted to Engineer for review.
- 6. No holes or chases shall be made in the slab without the approval of the Engineer.
- 7. Slurry used to lubricate concrete pump lines is not to be used in any concrete members. 8. All building slabs cast on ground require sand blinding with a
- Concrete Underlay. Refer to structural drawings. FORMWORK
- 1. The design, certification, construction and performance of the formwork, falsework and backpropping shall be the responsibility of the contractor. Proposed method of installation and removal of formwork is to be submitted to the superintendent for comment prior to work being carried out.

CONCRETE FINISHING NOTES

- 1. All exposed concrete pavements are to be broomed finished. 2. All edges of the concrete pavement including keyed and dowelled
- joints are to be finished with an edging tool. 3. Concrete pavements with grades greater than 10 % shall be
- heavily broomed finished.
- 4. Carborundum to be added to all stair treads and ramped crossings U.N.O.

TO BE PRINTED IN FULL COLOUR

06	21/01/25	ISSUE FOR REF	MZV	PAL
05	14/01/25	ISSUE FOR 100% SCHEMATIC DESIGN	MZV	PAL
04	13/12/24	FOR 50% SCHEMATIC DESIGN	MZV	PAL
03	08/05/23	FOR 100% SCHEMATIC DESIGN	BEJ	KEH
02	04/04/23	ISSUE FOR 50% SD TENDER	BEJ	KEH
01	10/03/23	ISSUE FOR INFORMATION	BEJ	KEH
rev	date	description	drn	ch'k

						4
						r
08	10/03/25	REISSUE FOR REF	NTV	PAL		GC
07	03/04/25	ISSUE FOR CONTRACT DOCUMENTS				
rev	date	description	drn	ch'k		
•					•	

CONCRETE REINFORCEMENT NOTES

- N. Hot rolled rib R. Plain round I SL. Square mes
- RL. Rectangular 2. Provide bar suppo
- noted on drawings. Footings - 50 top, 50 bottom, 50 sides. Walls - 30 generally.

- 4. Provide N12-450 support bars to top reinforcement as

- FABRIC LAPS · · · · · ·

as per table below.


KERBING NOTES

- match the joint locations in slabs.

- 6. Existing allotment drainage pipes are to be built into the new kerb with a 100mm dia hole.
- shown

JOINTING NOTES VEHICULAR PAVEMENT JOINTING SHOWN ON DRAWINGS. MAXIMUM OF 30M CENTRES. UNIT PAVERS.

5. THE TIMING OF THE SAW CUT IS TO BE CONFIRMED BY THE CONTRACTOR ON SITE. SITE CONDITIONS WILL DETERMINE HOW MANY HOURS AFTER THE CONCRETE POUR BEFORE THE SAW CUTS ARE COMMENCED. REFER TO THE SPECIFICATION FOR WEATHER CONDITIONS AND TEMPERATURES REQUIRED. 6. VEHICULAR PAVEMENT JOINTING AS FOLLOWS.



1. Fix reinforcement as shown on drawings. The type and grade is indicated by a symbol as shown below. On the drawings this is followed by a numeral which indicates the size in millimetres of the reinforcement.

obed bar	grade D500N
bar	grade R250N
sh	grade 500L
r mesh	grade 500L
orts or spa	acers to give the following

concrete cover to all reinforcement unless otherwise

30 when cast in forms but later exposed to

weather or ground.

 50 when cast directly in contact with ground. 3. Cover to reinforcement ends to be 50 mm u.n.o.

required, Lap 500 U.N.O. 5. Maintain cover to all pipes, conduits, reglets, drip grooves

6. All cogs to be standard cogs unless noted otherwise . Fabric end and side laps are to be placed strictly in accordance with the manufacturers requirements to

achieve a full tensile lap. Fabric shall be laid so that there is a maximum of 3 layers at any location.

_____25

8. Laps in reinforcement shall be made only where shown on the drawings unless otherwise approved. Lap lengths

Includes all kerbs, gutters, dish drains, crossings and edges.

1. All kerbs, gutters, dish drains and crossings to be constructed on minimum 75mm granular basecourse compacted to minimum 98% modified maximum dry density in accordance with AS 1289 5.2.1. 2. Expansion joints (EJ) to be formed from 10mm compressible cork filler board for the full depth of the section and cut to profile. Expansion joints to be located at drainage pits, on tangent points of curves and elsewhere at 12m centres except for integral kerbs where the expansion joints are to match the joint locations in slabs. 3. Weakened plane joints to be min 3mm wide and located at 3m

centres except for integral kerbs where weakened plane joints are to

4. Broomed finished to all ramped and vehicular crossings, all other kerbing or dish drains to be steel float finished.

5. In the replacement of kerbs - Existing road pavement is to be sawcut 900mm from: Lip of gutter, invert of kerb, or edge of dish drain. Upon completion of new kerbs, new basecourse and surface is to be laid 900mm wide to match existing materials and thicknesses.

7. Existing kerbs are to be completely removed where new kerbs are

1. ALL VEHICULAR PAVEMENTS TO BE JOINTED AS

2. KEYED CONSTRUCTION JOINTS SHOULD GENERALLY BE LOCATED AT A MAXIMUM OF 6M CENTRES. 3. SAWN JOINTS SHOULD GENERALLY BE LOCATED AT A MAXIMUM OF 6M CENTRES OR 1.5 X THE SPACING OF KEYED JOINTS, WHERE KEY JOINT SPACING IS LESS THAN 4M, WITH DOWELLED EXPANSION JOINTS AT

4. PROVIDE 10MM WIDE FULL DEPTH EXPANSION JOINTS BETWEEN BUILDINGS AND ALL CONCRETE OR


FACE OF KERB

SJ				DEJ	SJ		
		ôm MAX	m MAX				
		0m MAX		•		_	
FACE OF BUILDING							

PEDESTRIAN FOOTPATH JOINTING

1. EXPANSION JOINTS ARE TO BE LOCATED WHERE POSSIBLE AT TANGENT POINTS OF CURVES AND **ELSEWHERE AT MAX 6.0M CENTRES** 2. WEAKENED PLANE/SAWCUT JOINTS ARE TO BE LOCATED AT A MAX 1.5 X WIDTH OF THE PAVEMENT. 3. WHERE POSSIBLE JOINTS SHOULD BE LOCATED TO MATCH KERBING AND / OR ADJACENT PAVEMENT JOINTS.

4. ALL PEDESTRIAN FOOTPATH JOINTINGS AS



CATCHMENT NOTES

The site is within the Hawkesbury River Major River Catchment as noted in the Hills Shire Council Design Guidelines for Subdivisions and Developments, Appendix A, resulting in the on-site detention design being based on these guidelines.

Education School Infrastructure

enstruct group pty ltd

Level 4, 2 Glen Street Milsons Point NSW 2061 Australia

Telephone (02) 8904 1444 Facsimile (02) 8904 1555 www.enstruct.com.au

enstruci

ROUSE HILL HIGH SCHOOL UPGRADE


240 WITHERS ROAD, ROUSE HILL NSW 2155

NOTES SHEET

drawing title

FOR REVIEW scale at A1 approved AS SHOWN BEJ KEH KEH project no. sheet 6746 6746-CV-0001 80

NOT FOR CONSTRUCTION



06	21/01/25	ISSUE FOR REF	MZV	PAL	
05	14/01/25	ISSUE FOR 100% SCHEMATIC DESIGN	MZV	PAL	
04	13/12/24	ISSUE FOR 50% SCHEMATIC DESIGN	MZV	PAL	
03	08/05/23	FOR 100% SCHEMATIC DESIGN	BEJ	KEH	
02	04/04/23	ISSUE FOR 50% SD TENDER	BEJ	KEH	
01	10/03/23	ISSUE FOR INFORMATION	BEJ	KEH	
rev	date	description	drn	ch'k	

					_	
08	10/03/25	REISSUE FOR REF	NTV	PAL		
07	04/03/25	ISSUE FOR CONTRACT DOCUMENTS	NTV	PAL		
rev	date	description	drn	ch'k		



Education School Infrastructure

enstruct group pty Itd

enstruct

Level 4, 2 Glen Street Milsons Point NSW 2061 Australia

Telephone (02) 8904 1444 Facsimile (02) 8904 1555 www.enstruct.com.au

ROUSE HILL HIGH SCHOOL UPGRADE

240 WITHERS ROAD, ROUSE HILL NSW 2155

EROSION AND SEDIMENT CONTROL NOTES

- 1. All work shall be generally carried out in accordance with (A) Local authority requirements, (B) EPA - Pollution control manual for urban stormwater, (C) LANDCOM NSW - Managing Urban Stormwater: Soils and
- Construction ("Blue Book"). 2. Erosion and sediment control drawings and notes are provided for the whole of the works. Should the Contractor stage these works then the design may be required to be modified. Variation to these

A1

- details may require approval by the relevant authorities. The erosion and sediment control <u>plan</u> shall be implemented and adapted to meet the varying situations as work on site progresses. 3. Maintain all erosion and sediment control devices to the satisfaction of the superintendent and the local authority.
- 4. When stormwater pits are constructed prevent site runoff entering the pits unless silt fences are erected around pits.
- 5. Minimise the area of site being disturbed at any one time. 6. Protect all stockpiles of materials from scour and erosion. Do not stockpile loose material in roadways, near drainage pits or in watercourses.
- 7. All soil and water control measures are to be put back in place at the end of each working day, and modified to best suit site conditions.
- 8. Control water from upstream of the site such that it does not enter the disturbed site.
- 9. All construction vehicles shall enter and exit the site via the temporary construction entry/exit. 10. All vehicles leaving the site shall be cleaned and inspected before
- leaving. 11. Maintain all stormwater pipes and pits clear of debris and
- sediment. Inspect stormwater system and clean out after each storm event. 12. Clean out all erosion and sediment control devices after each

Sequence Of Works

storm event.

- 1. Prior to commencement of excavation the following soil
- management devices must be installed:
- 1.1. Construct silt fences below the site and across all potential runoff sites. 1.2. Construct temporary construction entry/exit and divert runoff to

suitable control systems. 1.3. Construct measures to divert upstream clean flows into existing

stormwater system. 1.4. Construct sedimentation traps/basin (if any) including outlet control and overflow; otherwise allocate a place for the runoff and temporary sediment storage.

1.5. Construct turf lined swales.

1.6. Provide sandbag sediment traps upstream of existing pits. 2. Construct geotextile filter pit surround around all existing pits and proposed pits as they are constructed.


- 3. On completion of pavement provide sand bag kerb inlet sediment traps around pits.
- 4. Provide and maintain a strip of turf on both sides of all roads after the construction of kerbs.

WATER QUALITY TESTING REQUIREMENTS

Prior to discharge of site stormwater, groundwater and seepage water into council's stormwater system, contractors must undertake water quality tests in conjunction with a suitably qualified environment consultant outlining the following:

- Compliance with the criteria of the Australian and New Zealand Guidelines for Fresh and Marine Water Quality (2000)
- If required subject to the environmental consultants advice, provide remedial measures to improve the quality of water that is to be discharged into Councils storm water drainage system. This should include comments from a suitably qualified environmental consultant confirming the suitability of these remedial measures to manage the water discharged from the site into Councils storm water drainage system. Outlining the proposed, ongoing monitoring, contingency plans and validation program that will be in place to continually monitor the quality of water discharged from this site. This should outline the frequency of water quality testing that will be undertaken by a suitably qualified environmental consultant.


EROSION AND SEDIMENT CONTROL LEGEND



NOT FOR CONSTRUCTION

drawing title SEDIMENT AND EROSION CONTROL PLAN

FOR REVIEW									
scale at A1	drawn	approved							
1:200	BEJ	KEH	ĸ	ΈH					
project no.	sheet			rev.					
project no.	Sheet								
6746	6746		08						



TO BE PRINTED IN FULL COLOUR

					_			1		,	
06	04/03/25	ISSUE FOR CONTRACT DOCUMENTS	NTV	PAL							
05	21/01/25	ISSUE FOR REF	MZV	PAL							
04	14/01/25	ISSUE FOR 100% SCHEMATIC DESIGN	MZV	PAL							202
03	13/12/24	ISSUE FOR 50% SCHEMATIC DESIGN	MZV	PAL							NS
02	08/05/23	FOR 100% SCHEMATIC DESIGN	BEJ	KEH							GOVERN
01	04/04/23	ISSUE FOR 50% SD TENDER	BEJ	KEH		07	10/03/25	REISSUE FOR REF	NTV	PAL	
rev	date	description	drn	ch'k		rev	date	description	drn	ch'k	





enstruct group pty Itd

Level 4, 2 Glen Street Milsons Point NSW 2061 Australia

Telephone (02) 8904 1444 Facsimile (02) 8904 1555 www.enstruct.com.au

enstruct

project

ROUSE HILL HIGH SCHOOL UPGRADE

240 WITHERS ROAD, ROUSE HILL NSW 2155

SED DE


drawing title

DIMENT AND EROSION	
TAILS SHEET	


status	FOR R	EVIEW		
scale at A1 AS SHOWN	drawn BEJ	checked KEH	approv K	ved ŒH
project no. 6746	sheet 67/6	-CV-0151	1	rev. 07
0740	0/40	-0.012	I	01

NOT FOR CONSTRUCTION

SCAL	E 1:	20									
0 2	200	40	00	60	00	80	00	1(000m	۱m	



06	21/01/25	ISSUE FOR REF	MZV	PAL						
05	14/01/25	ISSUE FOR 100% SCHEMATIC DESIGN	MZV	PAL						
04	13/12/24	ISSUE FOR 50% SCHEMATIC DESIGN	MZV	PAL						4
03	08/05/23	FOR 100% SCHEMATIC DESIGN	BEJ	KEH						N GOV
02	04/04/23	ISSUE FOR 50% SD TENDER	BEJ	KEH	08	10/03/25	REISUE FOR REF	NTV	PAL	GOV
01	10/03/23	ISSUE FOR INFORMATION	BEJ	KEH	07	04/03/25	ISSUE FOR CONTRACT DOCUMENTS	NTV	PAL	
rev	date	description	drn	ch'k	rev	date	description	drn	ch'k	



BULK EARTHWORKS CONSTRUCTION LEGEND



enstruct group pty ltd

Level 4, 2 Glen Street Milsons Point NSW 2061 Australia


Telephone (02) 8904 1444 Facsimile (02) 8904 1555 www.enstruct.com.au

enstruct

ROUSE HILL HIGH SCHOOL UPGRADE

240 WITHERS ROAD, ROUSE HILL NSW 2155

drawing title



1. * Bulk Earthworks level = Finish surface - Pavement/slab thickness

3. Bulk Earthwork drawings are for bulk excavation only. They are not to be used for detailed excavation such as: lift shafts, footings, pits etc. 4. Bulk Earthwork setout refers to bulk excavation only. They are not to be used for building, kerb or any other setout.

BULK EARTHWORKS LEGEND

Batter

Finished floor level Bulk earthworks platform level

Flat platforms shown with dots

BULK EARTHWORKS GENERAL NOTES

A1

1. All bulk earthworks setout from grid lines U.N.O. 2. (i) All permanent batter at slope of 4(H) :1(V) U.N.O.

(ii) All temporary batter at slope of 2(H) :1(V) U.N.O.

3. Excavated material may be used as structural fill provided, (i) it complies with the specification requirements for fill material,

(ii) the placement moisture content complies with the

Geotechnical Consultants requirements, and allows filling to be placed and proofrolled in accordance with the specification. Where necessary the Contractor must moisture condition the excavated material to meet these requirements.

4. Compact fill areas and subgrade to not less than:

Location	Standard dr (AS 1289		
Under building slab	s on ground:	98%	±2%
Under roads and ca	arparks:	98%	±2%
Landscaped areas:		95%	±2%

5. Before placing fill, proof roll exposed subgrade with a 10 tonne minimum roller to test subgrade and then remove soft spots (areas with more than 3mm movement under roller). Soft spots to be replaced with select fill U.N.O.

6. Contractor to provide proof roll compaction evidence for signoff.

7. Contractor shall place safety barriers around excavations in accordance with relevant safety regulations. 8. For interpretation of bulk earthworks foot print line shown on the bulk earthworks drawings refer to the bulk earthworks


construction legend. 9. Bulk earthwork drawings are not to be used for detailed excavation

10. Refer to Geotechnical Report prepared by -

Douglas Partners 215851.00 | R.001.Rev0

BULK EARTHWORKS MODEL NOTES


- 1. THIS DRAWING IS AN ESTIMATE FOR INFORMATION ONLY WHICH SHOULD NOT BE TAKEN AS AN ACCURATE MEASUREMENT AND SHOULD NOT BE USED FOR CONSTRUCTION.
- 2. THIS MODEL REPRESENTS A LEVEL COMPARISON BETWEEN: A) THE EXISTING SURFACE LEVELS MINUS AN
- AVERAGED TOPSOIL 200mm STRIP, AND **B) THE FORMATION LEVELS OF THE PROPOSED** DEVELOPMENT 3. THE FORMATION LEVELS ARE BASED ON
- 330 TBC INCLUDING 100mm VOID FORMER. THE EXISTING SURFACE LEVELS ARE BASED ON THE TIN MODEL FROM THE SURVEY FILE. REFER TO SURVEY NOTES.
- 4. THIS ESTIMATE DOES NOT INCLUDE EXCAVATION FOR ANY BELOW GROUND SERVICES INCLUDING STORMWATER INFRASTRUCTURE.
- 5. NO ALLOWANCE HAS BEEN CONSIDERED FOR SERVICE TRENCHES, IN GROUND TANKS, STRUCTURAL FOOTINGS, PILING, FLOOR SLABS OR LIFT PITS.
- 6. NO BULKING FACTOR HAVE BEEN APPLIED TO THE BULK EXCAVATION VOLUMES.
- 7. IT HAS BEEN ASSUMED THAT ALL EXCAVATED MATERIAL IS NOT CONTAMINATED AND CAN BE USED AS FILL MATERIAL ON SITE (NOT INCLUDING TOPSOIL). IF CONTAMINATION IS PRESENT, A SEPARATE ASSESSMENT SHOULD TAKE PLACE.
- 8. ANY DAMAGE TO EXISTING ROADS OR EXISTING BUILDINGS WILL BE RECTIFIED BY THE CONTRACTOR AT HIS EXPENSE.
- 9. ALL ENVIRONMENTAL MEASURES INCLUDING VEGETATION PROTECTION AND EROSION AND SEDIMENT CONTROLS SHALL BE PLACE PRIOR TO THE COMMENCEMENT OF ANY WORK.
- 10. EROSION PLANS AND BUILDING REPRESENTATIVE FAMILIAR WITH THE PLAN MUST BE ON SITE AT ALL TIMES DURING CONSTRUCTION.
- 11. ALL ARCHITECTURAL FINISHED SURFACE LEVELS SUPERSEDE THOSE INDICATED ON THE BULK EARTHWORKS PLAN. THE CONTRACTOR SHALL CONFIRM THE FINAL BUILDING PAD LEVEL REQUIRED TO SUIT THE STRUCTURAL DESIGN WITH THE STRUCTURAL DRAWINGS PRIOR TO COMMENCEMENT OF WORK.
- 12. REFER GEOTECHNICAL REPORT / ENGINEER FOR SUITABILITY OF MATERIAL WON FROM EXCAVATION BACKFILL.
- 13. NOT TO BE USED FOR DETAILED EXCAVATION, WHICH INCLUDES: LIFT PITS, TRENCHING, FOOTINGS AND OTHER EXCAVATION OF SIMILAR NATURE



NOT FOR CONSTRUCTION

FOR REVIEW scale at A1 approved KEH KEH 1:200 BEJ project no. sheet 6746 6746-CV-0201 80

BULK EARTHWORKS PLAN



	- FROFUSED L		VALL	ATDACK IC	1 22
	HILLS SHIRE	COUN	CIL ST	ANDARD	Þ
4.28	DRAWING SE).15.			
1.20		15		V 1 10	

06	14/01/25	ISSUE FOR 100% SCHEMATIC DESIGN	MZV	PAL					
05	13/12/24	ISSUE FOR 50% SCHEMATIC DESIGN	MZV	PAL					
04	08/05/23	FOR 100% SCHEMATIC DESIGN	BEJ	KEH					
03	04/04/23	ISSUE FOR 50% SD TENDER	BEJ	KEH	09	10/03/25	REISSUE FOR REF	NTV	PAL
02	10/03/23	ISSUE FOR INFORMATION	BEJ	KEH	08	04/03/25	ISSUE FOR CONTRACT DOCUMENTS	NTV	PAL
01	02/03/23	ISSUE FOR INFORMATION	BEJ	KEH	07	21/01/25	ISSUE FOR REF	MZV	PAL
rev	date	description	drn	ch'k	rev	date	description	drn	ch'k

enstruct group pty ltd

Level 4, 2 Glen Street Milsons Point NSW 2061 Australia

Education School Infrastructure

NSW GOVERNMENT

Telephone (02) 8904 1444 Facsimile (02) 8904 1555 www.enstruct.com.au enstruct

ROUSE HILL HIGH SCHOOL UPGRADE

240 WITHERS ROAD, ROUSE HILL NSW 2155

50.23	SITEWO	ORKS	LEG	END	
P 0.3D/75/9H	\bullet	XX.XXX	Property b Finished s	oundary urface level	
ExSW ExSW	КО		Kerb only		
+50.07	SW	SW m	Stormwate	er line with I upstream	
	Ø600 RCP 1.25% IL9.65		Pipe size a Pipe grade	and material	
TG GM 162,59 CGM	Exsw Exsw	xSW		ormwater line r line by hydrau	lic
50.29 50 50.29 50 50.36 500 5000000000000000000000000000000000		\boxtimes	Redundant Stormwate	-	
	GD 		Grated dra subsoil dra	ain ainage line (100	dia)
BLOCK B 1 STOREY	— ss —o ^{IR}	ss —		te riser with sub ne (100 dia)	osoil
BRICK BUILDING		OFP	drainage li	oint with subsoi ne (100 dia)	I
	RW1		Down pipe Blockwork	retaining wall	
50.29		· \		-	
	= (Trees to b	e removed	
49.94	STORMWAT		SCHED	ULF	
50.03 50.03	Note:Grate size do Refer pit type Final internal				3500
	Pit Type	Pit Size	Lid Type	Water Quality	Number
S	Surface inlet pit	600x 600		OceanProtect OceanGuard	<u>B2, C1, D</u> 1
		600x 900	Class D, galvanised mild steel grate hinged to frame U.N.O.	OceanProtect OceanGuard	A8, A9, A10,
	OSD surcharge lid	900x 900			A3
	Junction pit	900x 900	Cast iron concrete I U.N.O.		A1, A2, E1, E2, E3, F1
49.6	OSD access lid	900x 900	Class D, Cast iron cover with concrete infill U.N.O.		A4, A5, A6, A7
COVERED SPORTS COURTS					
48.48					
Q 49.48					
1924 I (1997)	1				
	0/ ا				
48.68 0 a.30/ 55/ 10H					
48.11 .48.68					
D.5D/ 105/ 19H					
			SCALE	1:200	
			0 1 2	5	10m
	NC	DT FO	R CO	NSTRU	CTION
	status	F			,
SITEWORKS PLAN	scale at A1				approved
	scale at A1		vn BEJ	KEH	Approved KEH

project no.


6746

sheet

6746-CV-0301

09

A1



					_	
rev	date	description	drn	ch'k		



Education School Infrastructure

Level 4, 2 Glen Street Milsons Point NSW 2061 Australia


Telephone (02) 8904 1444 Facsimile (02) 8904 1555 www.enstruct.com.au enstruct

ROUSE HILL HIGH SCHOOL UPGRADE

240 WITHERS ROAD, ROUSE HILL NSW 2155



status	FOR F	REVIEW		
scale at A1 1:200	drawn MZV	checked PAL	approv JA	ved N-25
project no.	sheet			rev.
6746	6746	6-CV-040	1	04



06	21/01/25	ISSUE FOR REF	MZV	PAL					
05	14/01/25	ISSUE FOR 100% SCHEMATIC DESIGN	MZV	PAL					
04	13/12/24	ISSUE FOR 50% SCHEMATIC DESIGN	MZV	PAL					
03	08/05/23	FOR 100% SCHEMATIC DESIGN	BEJ	KEH					
02	04/04/23	ISSUE FOR 50% SD TENDER	BEJ	KEH	08	10/03/2	25 REISSUE FOR REF	NTV	PAL
01	10/03/23	ISSUE FOR INFORMATION	BEJ	KEH	07	04/03/2	25 ISSUE FOR CONTRACT DOCUMENTS	NTV	PAL
rev	date	description	drn	ch'k	rev	date	description	drn	ch'k

enstruct group pty ltd

Level 4, 2 Glen Street Milsons Point NSW 2061 Australia

Education

School Infrastructure

NSW

Telephone (02) 8904 1444 Facsimile (02) 8904 1555 www.enstruct.com.au


enstruct

ROUSE HILL HIGH SCHOOL UPGRADE

240 WITHERS ROAD, ROUSE HILL NSW 2155

DE

	NUTE		NSIRUC		JN
9	status				
TAILS SHEET 1		FOR F	REVIEW		
	scale at A1 AS SHOWN	drawn BEJ	checked	approv	ved ŒH
	project no.	sheet			rev.
	6746	6746	-CV-050 ⁻	1	08



TO BE PRINTED IN FULL COLOUR

06	21/01/25	ISSUE FOR REF	MZV	PAL					
05	14/01/25	ISSUE FOR 100% SCHEMATIC DESIGN	MZV	PAL					
04	13/12/24	FOR 50% SCHEMATIC DESIGN	MZV	PAL					
03	08/05/23	FOR 100% SCHEMATIC DESIGN	BEJ	KEH					
02	04/04/23	ISSUE FOR 50% SD TENDER	BEJ	KEH	08	10/03/25	REISSUE FOR REF	NTV	PAL
01	10/03/23	ISSUE FOR INFORMATION	BEJ	KEH	07	04/03/25	ISSUE FOR CONTRACT DOCUMENTS	NTV	PAL
rev	date	description	drn	ch'k	rev	date	description	drn	ch'k

Education School Infrastructure Level 4, 2 Glen Street Milsons Point NSW 2061 Australia

Telephone (02) 8904 1444 Facsimile (02) 8904 1555 www.enstruct.com.au

enstruct group pty Itd

enstruct

ROUSE HILL HIGH SCHOOL UPGRADE

240 WITHERS ROAD, ROUSE HILL NSW 2155

drawing title DETAIL

S SHEET 2	FOR REVIEW							
	scale at A1 AS SHOWN	drawn BEJ	checked KEH	approved KEH				
	^{project no.} 6746	^{sheet} 6746	-CV-0502	2 rev. 08				

NOT FOR CONSTRUCTION

SC	ALE	E 1:	10							
										-
0 SC	10 ALE	•	20 20	0	30	0	40	0	500)mm
										-
0	20	00	4(00	60	00	80	00	1(000mm

SURROUNDED WITH 100mm OF NOM 20mm COARSE FILTER MATERIAL IN GEOTEXTILE

- 10 THICK COMPRESSIBLE CORK

FILLER BOARD BOTH ENDS

- SL62 FABRIC CENTRAL

BLINDED SAND LAYER

SCALE 1:20

ALLOW FOR

SURCHARGE AT TOP OF WALL

WITH THE SPECIFICATION


- 100 DIA SUBSOIL DRAINAGE LINE

X Bars

FILTER FABRIC (BIDIM A24 OR SIMILAR

- COMPACTED SELECT FILL IN ACCORDANCE

A1




TO BE PRINTED IN FULL COLOUR

									_		
05	10/03/25	REISSUE FOR REF	NTV	PAL							
04	04/03/25	ISSUE FOR CONTRACT DOCUMENTS	NTV	PAL							AN
03	21/01/25	ISSUE FOR REF	MZV	PAL							NSV
02	14/01/25	ISSUE FOR 100% SCHEMATIC DESIGN	MZV	PAL							GOVERNME
01	13/12/24	FOR 50% SCHEMATIC DESIGN	MZV	PAL							
rev	date	description	drn	ch'k	re	v c	date	description	drn	ch'k	



 $\widehat{1}$






06	02/09/24	ISSUE FOR INFORMATION	MZV	PAL
05	30/08/24	ISSUE FOR INFORMATION	MZV	PAL
04	09/07/24	ISSUE FOR INFORMATION	MZV	PAL
03	18/06/24	ISSUE FOR INFORMATION	MZV	PAL
02	28/05/24	ISSUE FOR INFORMATION	MZV	PAL
01	14/03/24	ISSUE FOR INFORMATION	MZV	PAL
rev	date	description	drn	ch'k

08	12/03/25	ISSUE FOR REF	NTV	PAL	
07	27/02/25	ISSUE FOR INFORMATION	SCO	PAL	
rev	date	description	drn	ch'k	



A1



G

Н

F

D

С

Autodesk Docs://Rouse Hill HS [P211001]/RHHS-JHA-ZZ-ZZ-M3-H-000000.rvt

Α

В

J

10/01/2025 4:09:06 PM