
DEVELOPMENT DATA **JOB REFERENCE** LOCALITY / SUBURB WARRAWONG STREET ADDRESS 12-16 Stuart Road **LOT NUMBER &** Lots 10, 11 & 12 in DP 35004 DEPOSITED PLAN SITE AREA (sqm) 1985 m2 – sourced from Survey NUMBER OF EXISTING LOTS 3 PROPOSED GFA (sqm) 1225sqm NUMBER OF DWELLINGS 16 DWELLINGS UNIT NO. TYPE BEDROOMS Area Ground 56.2 Ground 10.7 Ground Ground 54.5 10.3 Ground 56.0 10.2 Ground 50.7 10.4 Ground Level 1 86.4 10.1 Level 1 54.4 Level 1 10.4 77.4 Level 1 54.5 10.3 Level 1 10.3 50.0 Level 1 1109.8 CONTROL **REQUIREMENT PROPOSED** Housing SEPP s.42 (1)(b) 9.9m BUILDING HEIGHT 2B - 0.5 carspace 1 space per 3+ bedrooms Housing SEPP s.42 (1)(c) WLEP 2009 ^{Cl. 4.4} FRONT SETBACK Housing SEPP generally inline with existing 6m WLEP 2009 Cl. 4.2.2, 6.4.2 WLEP 2009 ^{Cl. 4.2.2, 6.4.2} REAR SETBACKS 6m - habitable room/ balcony 6m SIDE SETBACKS 3.5m - non-habitable room/ 3.5m blank wall Housing SEPP part 18(d) **DEEP SOIL ZONE** 15% of site area.(297.75m²) 319.5m² 16% if practicable, 65% at rear (193.54m²) Min.3m. Housing SEPP part 19 (2) Lesser of 35 sqm PER LANDSCAPE 604.4m² 30.4% DWELLING or 30% or site area(595.5m²) **SOLAR COMPLIANCE** Housing SEPP 70% of dwellings have 3 hours sunlight between 9am and 3pm in mid-Winter i. Living Rooms ii. Private open space LAHC* - Development data for LAHC new housing supply. For details refer to current version of LAHC Design Requirements EC* - Entry Corridor AREA* - Dwelling floor area includes internal walls but excludes external walls POS* - Private Open Space - In compliance with SLUDG Type* - E.g. Universal / Non-Universal Solar Orientation* - % with min. 3 hours of direct sunlight into living areas and private open space

GENERAL HOUSING DEVELOPMENT 12-16 Stuart Road Warrawong





BASIX Comm	itments Summary
WATER	
Rainwater Tank	10000L central tank
Rainwater-Re-use	Rainwater used for garden irrigation of 610sqm on common landscaped area
Star Rating	4 star toilet suite, 6 star taps throughout, 4 star showerheads with flowrate > 4.5 but <=6L/min
Planting	Indigenous or low water use species of vegetation min 100m ²
ENERGY	
Lighting	Provide dedicated energy efficient lighting (fluoros, compact fluoros or LEDs) throughout
Ceiling Fans	Ceiling fans required in each living room and bedroom
Appliances	Electric cooktop & electric oven, well ventilated fridge space
Mechanical Ventilation	Bathroom / Kitchen / Laundry - Individual fan, ducted to facade or roof. Manual switch on / off interlocked to light
Clothes Lines	Private outdoor or unsheltered cloths drying line
Lift	Gearless traction with V V V F motor
Hot Water System	Mechanical Heat Pump for Ground Floor Units, Electric Instantaneous for First Floor Units
Alternative Energy Source	Photovoltaic system: Rated electrical output (min): 8.0 peak kW

		External Walls					
Mall Time	Insulation	Colour	Comments				
Wall Type Cavity brick	R4.0 (Firemax A10 Plus)	Light - SA < 0.475 Med - SA 0.475 - 0.70 Dark - SA > 0.70	Throughout - As per elevations				
		SA - Solar Absorptance					
		Internal Walls					
Wall Type	Insulation		Comments				
Single skin brick	None		Ground floor internal walls				
Plasterboard stud (Steel studs)	None		L1 internal walls				
Cavity brick	None		Party walls between units				
Cavity brick	None		Shared walls with lobby/stairs/lift				
		Floors					
Floor Type	Insulation		Comments				
Suspended concrete slab	Ametalin Silverfloor	Ground floor, throughout					
Concrete	None	All units with adjoining unit below					
		Ceilings					
Ceiling Type	Insulation	Comments					
Plasterboard	None	Unit above					
Plasterboard	R2.5		Roof/air above				
Insulation loss due to downlights ha	as not been modelled in this asse	essment. A sealed exhaust fan Roof	has been included in every kitchen, bathroom, laundry and ensuite.				
Roof Type	Insulation	Colour	Comments				
Metal (Steel studs)	R1.3 foil-faced blanket	Med - SA 0.475 - 0.70	Throughout (Unventilated roof space)				
	•	SA - Solar Absorptance					
		Glazing					
Opening type	U-Value	SHGC	Glazing & Frame Type				
Sliding + Fixed (Throughout)	4.3	0.53	e.g. Single glazed high performing Low-E clear Aluminium frame				
Awning (Throughout)	4.8	0.51	e.g. Single glazed high performing Low-E clear Aluminium frame				
U and SHGC values are based on the AFRO	Default Windows Set. Glazing sy	vstems to be installed must hav values.	e an equal or lower U value and a SHGC value ± 10% of the above specified				
		Skylights					
Skylight Type	Frame	Туре	Comments				
na	n	a	na				
		Ceiling fan					
Size	Loca	tion	Comments				
JIEC .							



DRAWING LIST

A000	COVER PAGE & DRAWING LIST	Н	16/05/25	
A001	CONTEXT BLOCK ANALYSIS	Н	16/05/25	
A100	SITE ANALYSIS	Н	16/05/25	
A101	DEMOLITION PLAN	Н	16/05/25	
A102	CUT AND FILL PLAN	Н	16/05/25	
A103	SEDIMENT EROSION & CONTROL PLAN	Н	16/05/25	
A104	area calculations	Н	16/05/25	
A105	natural ventilation plans	Н	16/05/25	
A200	SITE PLAN	Н	16/05/25	
A201	GROUND FLOOR PLAN	Н	16/05/25	
A202	FIRST FLOOR PLAN	Н	16/05/25	
A203	ROOF PLAN	Н	16/05/25	
A300	ELEVATIONS EAST & WEST	Н	16/05/25	
A301	elevations north & south	Н	16/05/25	
A302	material & finish schedule	Н	16/05/25	
A303	SECTIONS - SHEET 1	Н	16/05/25	
A304	SECTIONS - SHEET 2	Н	16/05/25	
A401	VIEW FROM SUN STUDY	Н	16/05/25	
A402	SHADOW DIAGRAMS	Н	16/05/25	
A500	AERIAL PERSPECTIVES	Н	16/05/25	

Project Name
GENERAL HOUSING UNITS 12 - 16 STUART ROAD, WARRAWONG LOTS 10 - 12 | DP 35004 Sheet Title

16/05/25 Drawn: Checked Authorised Drawing No.

Project No.

Approver A000





PORT KEMBLA NORTH STATION 1.9km 4mins driving

COMMERCIAL STORES 6mins walking

5 PROJECT SITE

6 NSW AMBULANCE

KULLY BAY SPORTS 4min walking

<u>LEGEND:</u>

- 1. HILLVIEW CHILD CARE CENTRE
- 2. LEE PARK
- 3. PORT KEMBLA NORTH STATION
- 4. COMMERCIAL STORES
- 5. PROJECT SITE
- 6. NSW AMBULANCE
- 7. POST OFFICE
- 8. KULLY BAY SPORTS





7/30 Kembalawarra, Warrawong NSW 2502



99 Parkes, Warrawong NSW 2502



15 Holman Street, Warrawong NSW 2502



SITE CONTEXT ANALYSIS

Lot patterns are regular, with consistent dimensions

The block has preserved its original lot configurations,

characterized by predominantly single-storey buildings

- Lots are predominatly oriented parallel to the street.

ANALYSIS - KEY MATTERS

and spacing.

Predominant Block and Lot Patterns

Block and lot pattern change over time

and consistent setback distances.

- Lot sizes are small to medium. - Blocks are rectangular in shape.

- South East to North West.

Typical Lot Size, Shape, Orientation

23/08/24 STAGE B 16/10/24 STAGE C PRELIM 18/11/24 STAGE C

10/01/25 STAGE C 16/05/25 STAGE C

Which Lots better for Intensification and which are not

As the lots are symmetrical, boundaries can easily be combined into larger rectangle to be amalgamated into unit / town house development.

Is amalgamation necessary to support future development.

Amalgamation is required for densification for low rise unit and townhouse developments.

Are better Sites Available

The proposed site is the most appropriate site for this development. It is on a relatively flat streetscape with northerly aspects. The site is close to surrounding parks, shops and various local services.

Suite 4, 7 Ridge Stre North Sydney NSW 206 p +61 2 9922 27 f +61 2 9922 27 e architects@sarm.cor ABN 26 000 663 6

SARM Architects Stephen Arl reg. no. 764 Robert McNar


Project Name

GENERAL HOUSING UNITS WARRAWONG

CONTEXT BLOCK ANALYSIS

16/05/25 Drawn: Checked

Project No. Authorised Drawing No. A001









Street View 12-16 Stuart Rd







Street View 12-16 Stuart Rd



Street View 5-9 Stuart Rd



Street View 5-9 Stuart Rd



















DEMOLITION PLAN







TREE T2, T3 _ TO BE RETAINED



DEMOLITION NOTES

DEMOLITION WORKS TO BE CONDUCTED IN ACCORDANCE WITH AS2601-2011: THE DEMOLITION OF STRUCTURES AND WORKERCOVER REQUIREMENTS

REMOVE EXISTING TREES. SHRUBS AND THE LIKE WHERE INDICATED ON THE DRAWINGS TO BE REMOVED AND AS NECESSARY TO CONSTRUCT THE WORKS, INCLUDING THE GRUBBING OUT OF THE TREE STUMPS

REMOVAL OF EXISTING PAVING, ACCESS PATHWAYS, STAIRS, CONCRETE SLABS ASPHALTIC SURFACES, FOOTINGS, CONCRETE KERB SURROUNDS, FENCING, RETAINING WALLS, GARDEN BEDS, CHAIN WIRE BARRIERS, AND ASSOCIATED

REMOVE ALL EXISTING BOUNDARY FENCING OR WALLING TO PROPERTY

ALL REDUNDANT INGROUND SERVICES AND ALL EXISTING FOOTINGS FROM REMOVED STRUCTURES TO BE REMOVED.

THE CONTRACTOR SHALL ARRANGE FOR A QUALIFIED HYGIENIST TO INSPECT, REPORT AND CERTIFY CLEARANCE OF ALL MATERIAL REMOVED FROM SITE PRIOR TO DEMOLITION AND TO PROVIDE A CLEARANCE CERTIFICATE AFTER DEMOLITION IS COMPLETED

O MINIMISE UNDUE LOSS OF AMENITY, HOURS OF WORK FOR DEMOLITION/ EXCAVATION/ CONSTRUCTION ARE TO BE RESTRICTED ABSOLUTELY TO THE HOURS INDICATED IN THE CONDITIONS OF CONSENT.

O LIMIT DISTURBANCE TO THE SITE AND TRACKING OF MATERIAL ONTO THE

STREET, ALL VEHICLES AND PLANT EQUIPMENT WILL USE A SINGLE ENTRY / EXIT A SEDIMENT CONTROL DEVICE IS TO BE PLACED AT THE SITE ACCESS POINT TO

PREVENT SEDIMENT DEPOSITION ON ADJOINING ROADS. THE CONTRACTOR IS RESPONSIBLE TO REMOVE ANY MATERIAL DEPOSITED OFFSITE AS A RESULT OF SPILLAGE OR VEHICLE MOVEMENT. RESTORE AREA TO PREVIOUS STANDARD OR EQUAL. FORM VEHICLE CROSSING FROM 150X50 HARDWOOD PLANKS, CHAMFERED AT

ENDS. LAY OVER 150mm ROAD BASE. TIE WITH HOOP IRON STRAPS AT 600C/C.

DISPOSAL OF CONTAMINANTS AND HAZARDOUS MATERIALS THE MANAGEMENT AND DISPOSAL OF CONTAMINANTS AND HAZARDOUS

MATERIALS, INCLUDING ASBESTOS, CHEMICALS, OILS SHALL BE IN ACCORDANCE WITH THE CURRENT RELEVANT LEGISLATION INCLUDING:

WORK HEALTH AND SAFETY ACT 2011 WORK HEALTH AND SAFETY REGULATION 2011

PROTECTION OF ENVIRONMENT OPERATIONS ACT 1997 PROTECTION OF ENVIRONMENT OPERATIONS (WASTE) REGULATION 1997 ENVIRONMENTALLY HAZARDOUS CHEMICALS ACT 1985 AS2601 CLAUSE 1.6.2

THESE PROPERTIES WERE BUILT BEFORE 31.12.1987 AND IS LIKELY TO HAVE ASBESTOS

CONTAINING MATERIAL. IF DEMOLITION INVOLVES THE DEMOLITION OF BUILDINGS OR PART OF A BUILDING THAT MAY CONTAIN ASBESTOS, A HAZMAT REPORT DOCUMENTING THE EXTENT OF ASBESTOS REMOVAL REQUIRED AND CONFIRMING THAT THE REMOVAL WILL BE UNDERTAKEN IN ACCORDANCE WITH WORKCOVER NSW REQUIREMENTS MUST BE PROVIDED. - ROOFING AND CLADDING MATERIALS MUST BE CHECKED FOR THE PRESENCE OF

ASBESTOS BEFORE ANY SUCH MATERIAL IS DISTURBED OR REPLACED. ALL WORK, WHICH INVOLVES THE REMOVAL OF PRODUCTS CONTAINING ASBESTOS OR BRINGS PERSONS INTO CONTACT WITH ASBESTOS, MUST ONLY BE PERFORMED BY PERSONS LICENSED BY AND HOLDING A PERMIT ISSUED BY WORKCOVER AUTHORITY UNDER

WORK HEALTH AND SAFETY REGULATION 2011. A COPY OF LICENCE MUST BE SUBMITTED TO THE SUPERINTENDENT/AUTHORISED PERSON PRIOR TO COMMENCEMENT OF THIS WORK. IF ASBESTOS MATERIALS ARE ENCOUNTERED (I.E IN THE GROUND) DURING CONSTRUCTION WORKS, THE CONTRACTOR MUST IMMEDIATELY NOTIFY THE SUPERINTENDENT / AUTHORISED PERSON AND SEEK

REMOVAL - TAKE POSSESSION OF DEMOLISHED MATERIALS AND REMOVE THEM FROM THE SITE EXCEPT FOR ITEMS TO BE RECOVERED FOR RE-USE. BURNING OR BURYING DEMOLISHED MATERIALS ARE STRICTLY PROHIBITED ON THE SITE. PREVENT SPILLAGE OF DEMOLISHED MATERIALS IN TRANSIT

RECYCLE - DISMANTLE BUILDING COMPONENTS FOR OFF-SITE RECYCLING

REMOVE CLEARED AND GRUBBED MATERIAL FROM THE SITE AND DISPOSE OF

NOTICE OF COMPLETION GENERAL

GIVE AT LEAST 5 WORKING DAYS' NOTICE OF COMPLETION OF DEMOLITION SO THAT ADJACENT STRUCTURES MAY BE INSPECTION FOLLOWING COMPLETION OF DEMOLITION

PROTECT EXISTING TREES AS SPECIFIED AND NOTED IN ARBORIST REPORT - TREE PROTECTION ZONE (TPZ) IN ACCORDANCE WITH AS4970-2009 SECTION 3 - TREE PROTECTIVE MEASURES TO BE CONDUCTED IN ACCORDANCE WITH AS4970

HARMFUL MATERIALS - KEEP AREA WITHIN DRIPLINE FREE OF SHADES AND PATHS, CONSTRUCTION MATERIAL AND DEBRIS HAND METHODS - USE HAND METHODS TO LOCATE, EXPOSE AND CLEANLY REMOVE

THE ROOTS ON THE LINE OF EXCAVATION WORK UNDER TREES - DO NOT REMOVE TOPSOIL FROM, OR ADD TOPSOIL TO, AREAS WITHIN DRIPLINE OF TREES



PROTECTION OF TREES ON DEVELOPMENT SITES

PROTECTION OF TREES ON DEVELOPMENT SITES: THE TREE PROTECTION PLAN INDICATES THAT TREES T1, AND T7 LOCATED WITHIN THE SITE ARE TO

BE REMOVED. TREES T2, T3 ARE TO BE RETAINED AND PROTECTED FOR THE DURATION OF DEVELOPMENT CONSENT.

TREES THAT HAVE A TPZ-TREE PROTECTION ZONE AND SRZ -STRUCTURAL ROOT ZONE, REFER TO SITE PLAN AND ARBORIST REPORT

PROTECTIVE FENCING AROUND TREE T2 AND T3 ARE INSTALLED IN ACCORDANCE WITH AS 4970-2009 REQUIREMENTS, AND THE PROTECTIVE MEASURES FOLLOWS THE RECOMMENDATIONS OF THE ARBORIST REPORT.

THE ALIGNMENT OF THE DEVELOPMENT IS AN ENCROACHMENT TO THIS SPECIMEN. THE SECTION OF THE DEVELOPMENT WITHIN THE TPZ OF THESE SPECIMENS IS TO BE CONSTRUCTED USING TREE SENSITIVE EXCAVATION AND CONSTRUCTION TECHNIQUES SUCH AS PIER AND BEAM CONSTRUCTION WITH A SUSPENDED SLAB TO REDUCE ANY IMPACT ON THEIR STABILITY WITH PIERS TO BE DUG BY HAND WITH NON-MOTORISED MACHINERY TO FURTHER ASSIST IN THEIR PROTECTION.

PRUNING STANDARDS

- ANY PRUNING RECOMMENDED IN THIS REPORT IS TO BE TO THE AUSTRALIAN STANDARD® AS4373 PRUNING OF AMENITY TREES. AND CONDUCTED IN ACCORDANCE WITH THE NSW WORK COVER AUTHORITY CODE OF PRACTICE, TREE WORK, 2007.

- ALL PRUNING OR REMOVAL WORKS ARE TO BE IN ACCORDANCE WITH THE APPROPRIATE TREE MANAGEMENT POLICY WHERE APPLICABLE, OR TREE MANAGEMENT ORDER (TMO), OR TREE PRESERVATION ORDER (TPO).

TREE MAINTENANCE WORK IS SPECIALISED AND IN ORDER TO BE UNDERTAKEN SAFELY TO ENSURE THE WORKS CARRIED OUT ARE NOT DETRIMENTAL TO THE SURVIVAL OF A TREE BEING RETAINED, AND TO ASSIST IN THE SAFE REMOVAL OF ANY TREE, SHOULD BE UNDERTAKEN BY A QUALIFIED ARBORICULTURIST WITH APPROPRIATE COMPETENCIES RECOGNISED WITHIN THE AUSTRALIAN QUALIFICATION FRAMEWORK, WITH A MINIMUM OF 5 YEARS OF CONTINUAL EXPERIENCE WITHIN THE INDUSTRY OF OPERATIONAL AMENITY ARBORICULTURE, AND COVERED BY APPROPRIATE AND CURRENT TYPES OF INSURANCE TO UNDERTAKE SUCH WORKS.

GENERAL - TREE PROTECTION WORKS - PRIOR TO DEMOLITION

- MILESTONE - PRIOR TO DEMOLITION WORKS, A SITE ARBORIST SHALL BE APPOINTED TO SUPERVISE ALL TREE PROTECTION PROCEDURES DETAILED IN THIS SPECIFICATION. THE SITE ARBORIST SHALL HAVE A MINIMUM LEVEL 5 AQF QUALIFICATION IN ARBORICULTURE. MILESTONES ARE TO BE ADHERED TO THROUGHOUT THE DURATION OF THIS DEVELOPMENT AND ALL RELEVANT

DOCUMENTATION IS TO BE SUBMITTED TO THE LOCAL AUTHORITY. THE TREE PROTECTION ZONE FOR EACH TREES IS TO BE INCORPORATED INTO THE CONSTRUCTION WORKS FOR THE SITE AND THE PROTECTION FENCING OR WORKS AS SPECIFIED IN THE REPORT . THE SETBACKS FROM BUILDING WORKS ON THE SIDE CLOSEST TO EACH TREE ARE TO BE CARRED. OUT IN ACCORDENCE TO THE TREE PROTECTION ZONE. THE TREES WILL BE SUSTAINED WITHIN THE CONSTRAINTS OF THE MODIFICATIONS TO THE SITE BY THE PROPOSED DEVELOPMENT WORKS.TREES AS NOTED TO BE RETAINED AND PROTECTED AND INCORPORATED INTO THE LANDSCAPE WHERE APPROPRIATE AND INSTALLED PRIOR TO ANY DEMOLITION OR CONSTRUCTION. GROUND PROTECTION - IF TEMPORARY ACCESS FOR MACHINERY IS REQUIRED WITHIN THE TPZ GROUND PROTECTION MEASURES WILL BE REQUIRED. THE PURPOSE OF GROUND PROTECTION IS TO PREVENT ROOT DAMAGE AND SOIL COMPACTION WITHIN THE TPZ. MEASURES MAY INCLUDE A PERMEABLE MEMBRANE SUCH AS GEOTEXTILE FABRIC BENEATH A LAYER OF MULCH OR CRUSHED ROCK BELOW RUMBLE BOARDS. THESE MEASURES MAY BE APPLIED TO ROOT ZONES BEYOND THE

WHERE APPLICABLE, ANY EXCAVATION FOR THE ESTABLISHMENT OF A BATTER SLOPE OR BENCHING FOR REASONS OF SAFETY AND TO COMPLY WITH WORK COVER AUTHORITY SAFETY REGULATIONS SHOULD BE RESTRICTED AS FAR AS IS SAFELY POSSIBLE NEAR TO TREES TO BE RETAINED TO PREVENT ROOT DAMAGE. IF THE EXCAVATIONS CANNOT BE UNDERTAKEN NEAR TO VERTICAL THE STABILITY OF THESE TREES AND THEIR LONG-TERM VIABILITY MAY BE COMPROMISED AND THEIR RETENTION IN A SAFE AND HEALTHY CONDITION JEOPARDIZED AND THEY MAY NEED TO BE REVISED AND POSSIBLY REMOVED.

SPECIFIC - TREE PROTECTION WORKS - PRIOR TO DEMOLITION AND TREE REMOVAL

ALL OTHER TREES/SHRUBS; PRIOR TO DEMOLITION AND TREE REMOVAL WORKS THESE TREE/S ARE TO BE PLACED WITHIN A TREE PROTECTION ZONE WITH PROTECTIVE FENCING AND MAINTAINED AND RETAINED UNTIL THE COMPLETION OF ALL BUILDING WORKS. PROTECTIVE FENCING IS TO BE INSTALLED AS SHOWN IN APPENDIX F - TREE PROTECTION PLAN

THE PROTECTIVE FENCING WHERE REQUIRED MAY DELINEATE THE TREE PROTECTION ZONE (TPZ)

AND SHOULD BE SITUATED AS DETERMINED BY THE PROJECT ARBORIST IN ACCORDANCE WITH AS4970 PROTECTION OF TREES ON DEVELOPMENT SITES, "FENCING SHOULD BE ERECTED BEFORE ANY MACHINERY OR MATERIALS ARE BROUGHT ONTO THE SITE AND BEFORE THE COMMENCEMENT OF WORKS INCLUDING DEMOLITION, ONCE ERECTED, PROTECTIVE FENCING MUST NOT BE REMOVED. OR ALTERED WITHOUT APPROVAL BY THE PROJECT ARBORIST. THE TPZ MUST BE SECURED TO RESTRICT ACCESS. AS4687 TEMPORARY FENCING AND HOARDINGS SPECIFIES APPLICABLE FENCING REQUIREMENTS. SHADE CLOTH OR SIMILAR SHOULD BE ATTACHED TO REDUCE THE TRANSPORT OF DUST OTHER PARTICULATE MATTER AND LIQUIDS INTO THE PROTECTED AREA. FENCE POSTS AND SUPPORTS SHOULD HAVE A DIAMETER GREATER THAN 20 MM AND BE LOCATED CLEAR OF ROOTS. EXISTING PERIMETER FENCING AND OTHER STRUCTURES MAY BE SUITABLE AS PART OF THE PROTECTIVE FENCING" OR SIMILAR

TREE PROTECTION SIGNAGE IS TO BE ATTACHED TO EACH TPZ AND DISPLAYED FROM WITHIN THE DEVELOPMENT SITE IN ACCORDANCE WITH AS4970 2009 PROTECTION OF TREES ON DEVELOPMENT

THE AREA OF THE TREE PROTECTION ZONE TO BE MULCHED TO A DEPTH OF 100 MM WITH ORGANIC MATERIAL BEING 75% LEAF LITTER AND 25% WOOD, AND THIS BEING COMPOSTED MATERIAL PREFERABLY FROM THE SAME GENUS AND SPECIES OF TREE AS THAT TO WHERE THE MUI CH IS TO BE APPLIED, I.E. SPECIES-SPECIFIC MULCH WHERE POSSIBLE. THE DEPTH OF MULCH AND TYPE AS INDICATED. TO BE MAINTAINED FOR THE DURATION OF THE PROJECT, WHERE DEEP EXCAVATION WILL EXPOSE THE SOIL PROFILE TO DRYING OUT THE ROOT PLATE IS TO BE PROTECTED BY PEGGING JUTE MATTING ACROSS THE GROUND SURFACE 2 M BACK FROM THE EDGE OF THE PROFILE AND 2 M DOWN THE FACE OF THE PROFILE AND IS TO BE IN ONE CONTINUOUS SHEET OR LAYERS UP TO 5 MM THICK AND OVERLAPPED 300 MM AND PEGGED. PEGS ARE TO BE A MINIMUM LENGTH OF 200 MM AND SPACED AT 500 MM INCREMENTS IN A GRID PATTERN. ONCE INSTALLED MULCH IS TO BE PLACED ON

TOP OF THE JUTE MATTING PREVIOUSLY DESCRIBED. THERE IS TO BE NO STORAGE OF MATERIALS, RUBBISH, SOIL, EQUIPMENT, STRUCTURES, OR GOODS OF ANY TYPE TO BE KEPT OR PLACED WITHIN 5 METRES FROM THE TRUNK OR WITHIN THE DRIPLINE OF ANY TREE FOR THE DURATION OF THE DEVELOPMENT. THIS WILL ENSURE PROTECTION OF THE

TREE/S TO BE RETAINED ON OR ADJACENT TO SITE. MILESTONE - PROJECT/SITE ARBORIST IS TO INSPECT/ASSESS ALL RETAINED SPECIMENS PRIOR TO DEMOLITION TO INSPECT TREE PROTECTION MEASURES TO MONITOR THAT THEY HAVE BEEN CARRIED OUT AS PER THE APPROVED D/A CONDITIONS FOR THE SITE. DOCUMENTATION IS TO BE SUBMITTED TO THE CONSENTING AUTHORITY AFTER EACH INSPECTION

DEMOLITION AND TREE REMOVAL/S

REMOVAL OF A TREE WITHIN 6 M OF A TREE TO BE RETAINED SHOULD BE UNDERTAKEN ONLY BY CUTTING DOWN SUCH A TREE WITHOUT DAMAGING THE TREES TO BE RETAINED, AND BY GRINDING OUT ITS STUMP. WHERE POSSIBLE THE STRUCTURAL ROOTS OF 20 MM DIAMETER OR GREATER OF THE TREE TO BE CUT DOWN SHOULD NOT BE REMOVED. TO MINIMISE SOIL DISTURBANCE AND TO REDUCE THE IMPACT ON THE ROOTS OF ANY TREE TO BE RETAINED NEARBY. WHERE STRUCTURAL ROOTS ARE TO BE REMOVED THIS SHOULD BE UNDERTAKEN MANUALLY BY THE USE OF NON-MOTORISED HAND TOOLS AFTER THE STUMP HAS BEEN GROUND OUT WHEN SUCH ROOTS ARE OFTEN EASIER TO LOCATE FROM THE SITE OF THE STUMP FROM WHICH THEY HAVE BEEN SEVERED. GROUND PROTECTION IN ACCORDANCE WITH AS4970 MAY REQUIRE STEEL PLATES TO PROTECT THE GROUND SURFACE FROM COMPACTION TO PROTECT ROOTS BETWEEN THE STAGES OF DEMOLITION

SPECIFIC - TREE PROTECTION WORKS - DURING DEMOLITION

DEMOLITION OF EXISTING BUILDINGS SHOULD BE UNDERTAKEN WITH ACCESS RESTRICTED TO THE DRIVEWAY AND THE BUILDING PLATFORM FOR EACH OF THE EXISTING BUILDINGS, OR TO AREAS OF THE LAND WHERE NO TREES ARE GROWING WITHIN 6M OF ANY TREE TO BE RETAINED. WHERE ACCESS OR SPACE FOR A SAFE WORKING ENVIRONMENT IS RESTRICTED. OR WHERE THE AREA OF THE 6M SET BACK MUST BE COMPROMISED, A 100 MM LAYER OF WOOD MULCH MUST BE LAID OVER THE AREA OF ENCROACHMENT. WHERE VEHICULAR ACCESS IS REQUIRED ACROSS THE MULCH LAYER FURTHER ROOT PROTECTION SHOULD BE PROVIDED BY LAYING A TEMPORARY PATHWAY OVER THE MULCH. THE TEMPORARY PATHWAY SHOULD BE CONSTRUCTED OF A GRATED STEEL MATERIAL CAPABLE OF SUPPORTING THE VEHICLES USED DURING DEMOLITION E.G., LIKE RAMPS USED TO LOAD VEHICLES ONTO THE BACKS OF TRUCKS. TRUNKS OF TREES MAY REQUIRE PROTECTION FROM VEHICULAR DAMAGE.

DEMOLITION OF LANDSCAPE STRUCTURES: THE DEMOLITION OF WALLS, DRIVEWAYS RETAINING WALLS, PATHS, AND POOLS ETC. WITHIN 6 M OF A TREE TO BE RETAINED SHOULD BE UNDERTAKEN MANUALLY USING HAND TOOLS. WHERE A DRIVEWAY IS TO BE DEMOLISHED BEING OF CONCRETE STRIP OR SLAB TYPE CONSTRUCTION, IT SHOULD BE UNDERTAKEN BY WORKING FROM THE END OF THE DRIVEWAY CLOSEST TO THE BUILDING BACK TOWARDS THE STREET BY UTILISING THE DRIVEWAY AS A STABLE PLATFORM TO PREVENT SOIL COMPACTION. WHERE A CONCRETE SLAB DRIVEWAY PASSES LESS THAN 1 M FROM THE BASE OF A TREE AND THE AREA BENEATH THE DRIVEWAY IS TO BE UNDISTURBED AND INCORPORATED INTO THE LANDSCAPE WORKS FOR THE SITE, THE VOLUME OF SPACE PREVIOUSLY OCCUPIED BY THE DRIVEWAY MUST BE REPLACED WITH LOCAL TOP SOIL FROM THE SITE OR OTHERWISE A LOAMY SAND, TO REPLACE THE MASS OF THE CONCRETE ON THE ROOT PLATE WHICH MAY BE CRITICAL TO THE BALLAST AND CENTRE OF MASS FOR THE STABILITY OF THE TREE. IF THE TREE BECOMES UNSTABLE IMMEDIATELY CONTACT THE CONSULTANT ARBORICULTURIST

PROTECTION OF TREES ON DEVELOPMENT SITES

SPECIFIC - TREE PROTECTION WORKS - POST DEMOLITION AND PRIOR TO CONSTRUCTION MILESTONE - PROJECT/SITE ARBORIST IS TO INSPECT/ASSESS ALL RETAINED SPECIMENS PRIOR TO CONSTRUCTION IN RELATION TO TREE PROTECTION MEASURES TO MONITOR THAT THEY HAVE BEEN CARRIED OUT AS PER THE APPROVED D/A CONDITIONS FOR THE SITE. DOCUMENTATION IS TO BE SUBMITTED TO THE CONSENTING AUTHORITY AFTER EACH INSPECTION

LOCATION OF UNDERGROUND UTILITIES WITHIN A TREE PROTECTION ZONE OF A RETAINED

SPECIMEN. ANY UTILITY SERVICES TO BE SITUATED UNDERGROUND WITHIN THE TPZ ARE TO BE UNDERTAKEN UTILISING EXCAVATION TECHNIQUES THAT PREVENT OR MINIMISE DAMAGE TO STRUCTURAL ROOTS (ROOTS GREATER THAN >20 MM DIAMETER). TO PREVENT SOIL COMPACTION AND ROOT DAMAGE THESE WORKS SHOULD BE CONDUCTED WITH NON-

MOTORISED HAND TOOLS, AIR KNIFE OR DIRECTIONAL DRILLING. REGARDING OF SITE NEAR RETAINED TREES: GRADING &/OR RE-GRADING OF SITES/SLOPE: WITHIN TREE PROTECTION ZONES OR NEAR RETAINED SPECIMENS IS TO BE UNDERTAKEN **ONLY** IF AT ALL, AFTER CONSULTATION WITH THE PROJECT ARBORIST, THIS IS TO PROTEC ALL STRUCTURAL ROOTS SYSTEMS FROM DAMAGE OR COMPACTION FROM MACHINERY. PLACEMENT OF RELOCATABLE BUILDINGS: CONSIDERATION SHOULD BE GIVEN TO TREE SENSITIVITY SUCH AS THE BUILDINGS BEING PLACED ON PIER AND BEAM OR SKIDS CONSTRUCTION AS THEY ARE TO BE POSITIONED ON THEIR DRIPLINES WITHIN THE TREE PROTECTION ZONE (TPZ). THE AREA OF THE TREE PROTECTION ZONE UNDER THE BUILDINGS IS TO BE MULCHED TO A DEPTH OF 200 MM (IF INSTALLED ON SKIDS) WITH ORGANIC MATERIAL TO FURTHER REDUCE COMPACTION. THE MULCH IS TO BE COMPOSTED MATERIAL, I.E. SPECIES-SPECIFIC MULCH. ALTERNATIVELY, IF INSTALLED ON A PIER & BEAM CONSTRUCTION. PIERS ARE TO BE UNDERTAKEN MANUALLY BY USING NON-MOTORISED HAND TOOLS TO DETERMINE THE LOCATION OF FIRST ORDER AND LOWER ORDER STRUCTURAL ROOTS WITH A DIAMETER OF 20 MM (STRUCTURAL WOODY ROOTS) OR GREATER, WITHOUT DAMAGING THEM.

SPECIFIC - TREE PROTECTION WORKS - DURING CONSTRUCTION

MILESTONE - PROJECT/SITE ARBORIST IS TO INSPECT/ASSESS ALL RETAINED SPECIMENS DURING CONSTRUCTION IN RELATION TO TREE PROTECTION MEASURES TO MONITOR THAT THEY HAVE BEEN CARRIED OUT AS PER THE APPROVED D/A CONDITIONS FOR THE SITE. DOCUMENTATION IS TO BE SUBMITTED TO THE CONSENTING AUTHORITY AFTER EACH INSPECTION

WHERE ANY STRUCTURAL ROOTS (ROOTS WITH A DIAMETER OF GREATER THAN >20 MM) ENCOUNTERED BY EXCAVATION ARE TO BE PRUNED AND IT IS TO BE UNDERTAKEN WITH CLEAN SHARP PRUNING TOOLS, WITH A FINAL CUT TO UNDAMAGED WOOD TO PREVENT INFESTATION BY PATHOGENS AND ASSIST CONTINUED ROOT GROWTH AND UNDERTAKEN IN CONSULTATION WITH THE CONSULTING ARBORICULTURIST. TREE PROTECTION ZONE FENCES ARE TO BE MAINTAINED DURING THESE WORKS. GROUND PROTECTION IN

ACCORDANCE WITH AS4970 MAY REQUIRE STEEL PLATES TO PROTECT THE GROUND SURFACE FROM COMPACTION TO PROTECT ROOTS BETWEEN THE STAGES OF DEMOLITION AND CONSTRUCTION OF THE NEW PAVEMENT ALL TREE PROTECTION ZONES OF RETAINED TREES ARE TO BE MONITORED FOR THE DURATION OF THE CONSTRUCTION PHASE OF THE DEVELOPMENT. THE THREE MAIN AREAS REQUIRING MONITORING ARE; MULCHING - MULCH MUST BE MAINTAINED TO A DEPTH OF

50-100 MM USING MATERIAL THAT COMPLIES WITH AS 4454. WHERE THE EXISTING LANDSCAPE WITHIN THE TPZ IS TO REMAIN UNALTERED (E.G. GARDEN BEDS OR TURE) MULCH MAY NOT BE REQUIRED, WATERING - SOIL MOISTURE LEVELS SHOULD BE REGULARLY MONITORED BY THE PROJECT ARBORIST. TEMPORARY IRRIGATION OR WATERING MAY BE REQUIRED WITHIN THE TPZ. AN ABOVE-GROUND IRRIGATION SYSTEM COULD BE INSTALLED AND MAINTAINED BY A COMPETENT INDIVIDUAL AND WEEDING -WEEDS SHOULD BE REMOVED BY HAND WITHOUT DISTURBING SOIL OR SHOULD BE CONTROLLED WITH WEEDICIDE.

TREES TO BE REMOVED ARE TO BE REPLACED WITH ADVANCED SPECIMENS BEING MINDFUL OF THE SPACE LIMITATIONS OF THE NEW USE OF THE SITE. THE ADVANCED TREES SHOULD BE SITUATED IN AREAS ALONG THE BOUNDARIES OF THE SITE. THE PLANTING IN THESE LOCATIONS WILL PROVIDE THE MAXIMUM BENEFIT TO THE SURROUNDING PROPERTIES BY SCREENING VIEWS TO AND FROM THE SITE AND THE PLANTINGS INCLUDED IN THE PROPOSED LANDSCAPE PLAN. THE REPLACEMENT TREES WILL BE SITUATED IN POSITIONS WHERE THEY MAY GROW TO MATURITY UNHINDERED AND WILL NOT CONFLICT WITH BUILT STRUCTURES OR UTILITY SERVICES AND IN GREATER NUMBERS THAN THE TREES REMOVED SHOULD PROVIDE A NET INCREASE IN THE LOCAL AMENITY.


SPECIFIC - TREE PROTECTION WORKS - POST CONSTRUCTION

MILESTONE - AT COMPLETION OF CONSTRUCTION WORK THE SITE/PROJECT ARBORIST SHOULD CARRY OUT AN ASSESSMENT OF ALL TREES RETAINED &/OR AFFECTED BY WORKS THIS ASSESSMENT IS TO DOCUMENT ANY REQUIRED ON-GOING REMEDIAL CARE NEEDED TO ENSURE VIABLE RETENTION OF TREES AFFECTED. DOCUMENTATION IS TO BE SUBMITTED TO THE CONSENTING AUTHORITY.

NOTE: REFER TO ARBORIST REPORT














GENERAL HOUSING UNITS WARRAWONG 12 - 16 STUART ROAD, WARRAW Lots 10 - 12 | DP 35004 Sheet Title

DEMOLITION PLAN


16/05/25 Drawn: Checked Checker










Section 1



Section 2





















18/11/24 STAGE C

10/01/25 STAGE C

16/05/25 STAGE C

MAIN WORKS


TEMPORARY FENCE



UNDISTURBED

— PROTECT BASE FROM SCOURING WITH BUILD UP OF GRAVEL

_ STAR PICKET AT 2M CENTRES



GROUND FLOOR AREA


INTERNAL FLOOR AREA 1270m²

AREA EXCLUDED FROM GFA 45.2m²

TOTAL GFA: 1225m² FSR: 0.61:1

LANDSCAPE 604.4m²

(30.4% PROPOSED > 30% HSEPP REQUIRED)




FIRST FLOOR AREA
1:200



















NATURAL VENTILATION GROUND FLOOR PLAN

18/11/24 STAGE C 10/01/25 STAGE C 16/05/25 STAGE C



NATURAL VENTILATION FIRST FLOOR PLAN 1: 200







Certificate No. 0011746560

Property Address 12-16 Stuart


hstar.com.au/QR/Generate?p=fdCqCsnpQ

Scan QR code or follow website link for rating details.

Street, Warrawong

NSW,2502









16/05/25 Checked NATURAL VENTILATION PLANS Authorised Drawing No. Approver A105

Project No.






16/10/24 STAGE C PRELIM 18/11/24 STAGE C 10/01/25 STAGE C 16/05/25 STAGE C --- DEMOLISHED --- EXISTING/ RETAINED LB LETTERBOXES – OVERHEAD HWU INSTANTANEOUS ELECTRIC

HOT WATER UNIT

CL A/C UNIT
FEN-1 FENCE - COS/ HWU's
FEN-2 BOUNDARY FENCE FW FLOOR WASTE WM WAER METER
SP SOLAR PANELS
SS SUN SHROUD
ST STORAGE










Project No. Checked Revision Checker H Authorised Drawing No. Approver A201





























Drawn: Project No. Author Checked Revision Checker H Authorised Drawing No. Approver A203



EASTERN ELEVATION STUART RD




WESTERN ELEVATION

1:100

PROPOSED NEW TREES ARE SHOWN AT THEIR MINIMUM MATURE HEIGHT.


REFER TO LANDSCAPE PLANT LIST SCHEDULE.












1 NORTHERN ELEVATION 1: 100



SOUTHERN ELEVATION

BOUNDARY 06/08/24 TO CONSULTANT 23/08/24 STAGE B NGL NATURAL GROUND LINE 16/10/24 STAGE C PRELIM - - HEIGHT LIMIT CONTROL 18/11/24 STAGE C 10/01/25 STAGE C 16/05/25 STAGE C

AC A/C UNIT ALUMINIUM WINDOW FRAME A/C UNIT FEN-1 FENCE - COS/ HWU's FEN-2 BOUNDARY FENCE HOT WATER UNIT SOLAR PANELS SUN SHROUD ALUMINIUM CLADDING WATER METER WPF PERFORATED BRICK WALL

PROPOSED NEW TREES ARE SHOWN AT THEIR MINIMUM MATURE HEIGHT. REFER TO LANDSCAPE PLANT LIST SCHEDULE.







Project No.

Revision



ELEVATION - STUART ST

23/08/24 STAGE B 16/10/24 STAGE C PRELIM 18/11/24 STAGE C 10/01/25 STAGE C 16/05/25 STAGE C







Robert McNama

16/05/25 Drawn: Authorised Drawing No. Approver A302

Date: Scale Project No. Checked Revision Checker H



Material Exterior Schedule

CODE Material: Image Material: Description COLOUR

Height: 1200mm/ Front

Boundary Fence - 1.8m Colorbond Fence

Aluminium Battens metallic-look powdercoat

Boarded Finish

Colour to match WFC-V

Vertical Boarded Finish


Retaining Wall Block


Light Beige

Shale Grey

FEN-2

WFC-V





PROPOSED NEW TREES ARE SHOWN AT THEIR MINIMUM MATURE HEIGHT.

REFER TO LANDSCAPE PLANT LIST SCHEDULE.

AC A/C UNIT

HWU SP

CL A/C UNIT FEN-1 FENCE - COS/ HWU's FEN-2 BOUNDARY FENCE

HOT WATER UNIT

ALUMINIUM CLADDING

SOLAR PANELS

SUN SHROUD

WM WATER METER
WPF PERFORATED BRICK WALL

ALUMINIUM WINDOW FRAME

BOUNDARY

SETBACK

- - HEIGHT LIMIT CONTROL

NGL NATURAL GROUND LINE

06/08/24 TO CONSULTANT

16/10/24 STAGE C PRELIM

23/08/24 STAGE B

18/11/24 STAGE C


10/01/25 STAGE C


16/05/25 STAGE C












SECTION 02

PROPOSED NEW TREES ARE SHOWN AT THEIR MINIMUM MATURE HEIGHT. BOUNDARY AC A/C UNIT 06/08/24 TO CONSULTANT REFER TO LANDSCAPE PLANT LIST SCHEDULE. ALUMINIUM WINDOW FRAME SETBACK 23/08/24 STAGE B CL A/C UNIT FEN-1 FENCE - COS/ HWU's FEN-2 BOUNDARY FENCE NGL NATURAL GROUND LINE 16/10/24 STAGE C PRELIM - - HEIGHT LIMIT CONTROL 18/11/24 STAGE C 10/01/25 STAGE C HOT WATER UNIT 16/05/25 STAGE C SOLAR PANELS SUN SHROUD ALUMINIUM CLADDING WATER METER WPF PERFORATED BRICK WALL


















VIEW FROM SUN STUDY - JUNE 3pm


1 VIEW FROM SUN STUDY - JUNE 9am


5 VIEW FROM SUN STUDY - JUNE 11am



	9am	9:30am	10am	10:30am	11am	11:30am	12pm	12:30pm	1pm	1:30pm	2pm	2:30pm	3pm
Unit 1													
Unit 2					√	√	✓	√	√	√	√	√	√
Unit 3								√	√	√	√	√	√
Unit 4								√	√	√	√	√	√
Unit 5	√	√	√	√	✓	√							
Unit 6	√	√	√	√	√	√	✓	√	√	√	√	√	√
Unit 7	√	√	√	√	✓	√							
Unit 8													
Unit 9													
Unit 10					✓	√	√	√	√	✓	✓	√	√
Unit 11								√	√	✓	✓	√	√
Unit 12								√	√	√	✓	√	√
Unit 13	√	✓	✓	✓	✓	✓	✓	√	✓	✓	✓	✓	√
Unit 14	√	✓	✓	✓	✓	✓	✓	√	√	√	√	√	√
Unit 15	√	✓	✓	✓	✓	✓	✓						
Unit 16													











8 VIEW FROM SUN STUDY - JUNE 1230pm

4 VIEW FROM SUN STUDY - JUNE 1030am





VIEW FROM SUN STUDY - JUNE 930am








10 VIEW FROM SUN STUDY - JUNE 130pm VIEW FROM SUN STUDY - JUNE 2pm


VIEW FROM SUN STUDY - JUNE 230pm

12pm	12:30pm	1pm	1:30pm	2pm	2:30pm	
✓	√	√	√	√	√	


3 VIEW FROM SUN STUDY - JUNE 10am

7 VIEW FROM SUN STUDY - JUNE 12pm

































Sketch Perspective - Front



Sketch Perspective - Rear







