



# ACOUSTIC REPORT

## Noise & Vibration Impact Assessment

Greenway Park Public School Upgrade and New Public Pre  
School

NSW Department of Education

CONFIDENTIAL

Revision: 5.0 – Planning Report | Issued: 23 April 2025

Document name: GPPS-NDY-XX-XX-RP-Y-0001

**NDY**  
A TETRA TECH COMPANY

## VERIFICATION

| REVISION | DATE ISSUED | PREPARED BY                     | VERIFIED BY   | AUTHORISED BY    | COMMENT         |
|----------|-------------|---------------------------------|---------------|------------------|-----------------|
| 1.0      | 31-10-2024  | Rohith Vincent & Kanvin Chen    | Thomas Warren | Jarrad Underwood | DA Report Draft |
| 2.0      | 13-12-2024  | Rohith Vincent & Kanvin Chen    | Thomas Warren | Jarrad Underwood | Planning Report |
| 3.0      | 27-02-2025  | Victoria Rastelli               | Thomas Warren | Jarrad Underwood | Planning Report |
| 4.0      | 07-04-2025  | Victoria Rastelli & Kanvin Chen | Thomas Warren | Jarrad Underwood | Planning Report |
| 5.0      | 23-04-2025  | Victoria Rastelli               | Thomas Warren | Jarrad Underwood | Planning Report |

## STAKEHOLDERS

| ROLE                           | TEAM MEMBER     | ORGANISATION      |
|--------------------------------|-----------------|-------------------|
| Client Representative          | Paul Nickson    | SI                |
| Architect                      | Jimmy He        | Fulton Trotter    |
| Project Manager                | Nicholas Lau    | RPIInfrastructure |
| Planner                        | Alaine Roff     | Urbis             |
| Hydraulic and fire Engineering | Rhys Edwards    | ACOR Consultants  |
| Services Engineer – Mechanical | Chia Halim      | NDY               |
| Services Engineer – Electrical | Shrinivas Sapre | NDY               |

# Table of contents

|          |                                                                        |           |
|----------|------------------------------------------------------------------------|-----------|
| <b>1</b> | <b>INTRODUCTION</b>                                                    | <b>1</b>  |
| 1.1      | Authors                                                                | 2         |
| 1.2      | Purpose                                                                | 2         |
| 1.3      | Authority                                                              | 2         |
| 1.4      | Documentation Review                                                   | 2         |
| <b>2</b> | <b>ACTIVITY INFORMATION</b>                                            | <b>4</b>  |
| 2.1      | Proposed Activity Description                                          | 4         |
| 2.2      | Activity Site                                                          | 4         |
| 2.3      | Site zoning                                                            | 5         |
| 2.4      | School operation hours                                                 | 5         |
| 2.5      | Sensitive receivers                                                    | 6         |
| <b>3</b> | <b>METHODOLOGY</b>                                                     | <b>7</b>  |
| <b>4</b> | <b>ACOUSTIC ASSESSMENT OF THE EXISTING ENVIRONMENT</b>                 | <b>8</b>  |
| 4.1      | Meteorological Data                                                    | 8         |
| 4.2      | Instrumentation                                                        | 8         |
| 4.3      | Noise Loggers' locations                                               | 8         |
| <b>5</b> | <b>NOISE AND VIBRATION CRITERIA</b>                                    | <b>10</b> |
| 5.1      | Local city council rules                                               | 10        |
| 5.2      | NSW Development near Rail Corridors and Busy Roads                     | 10        |
| 5.3      | NSW Noise Policy for Industry (NPfI) 2017                              | 10        |
| 5.4      | Construction Noise and Vibration Criteria                              | 13        |
| <b>6</b> | <b>OPERATIONAL NOISE &amp; VIBRATION IMPACT ASSESSMENT</b>             | <b>21</b> |
| 6.1      | Noise emission from PA systems and school bells                        | 21        |
| 6.2      | Noise emissions from carpark                                           | 21        |
| 6.3      | Noise emissions from services                                          | 22        |
| 6.4      | Operational vibration                                                  | 25        |
| <b>7</b> | <b>CONSTRUCTION NOISE &amp; VIBRATION IMPACT ASSESSMENT</b>            | <b>26</b> |
| 7.1      | Construction plant noise levels                                        | 26        |
| 7.2      | Predicted construction noise                                           | 27        |
| 7.3      | Predicted construction vibration                                       | 30        |
| 7.4      | General recommendations on construction noise and vibration management | 31        |
| <b>8</b> | <b>NOISE MITIGATION STRATEGIES</b>                                     | <b>32</b> |
| <b>9</b> | <b>EVALUATION OF ENVIRONMENTAL IMPACTS</b>                             | <b>34</b> |

# 1 INTRODUCTION

This Noise and Vibration Impact assessment has been prepared to accompany a Review of Environmental Factors (REF) prepared for the Department of Education (DoE) relating to upgrades to Greenway Park Public School (the development) under Part 5 of the Environmental Planning and Assessment Act 1979 (EP&A Act) and State Environmental Planning Policy (Transport and Infrastructure) 2021 (SEPP TI).

This document has been prepared in accordance with the Guidelines for Division 5.1 assessments – Consideration of environmental factors for health services facilities and schools, October 2024 (the Guidelines) by the Department of Planning, Housing and Infrastructure.

This report examines and takes into account the relevant environmental factors in the Guidelines and Section 170, Section 171 and Section 171A of the Environmental Planning and Assessment Regulations 2021 (EP&A Regulation) as outlined in Table 1.

TABLE 1: SUMMARY OF RELEVANT SECTION OF THE PART 5 GUIDELINES AND EP&A REGULATION

| REGULATION / GUIDELINE SECTION                                                                                                                            | REQUIREMENT                                                                                                     | RESPONSE                                                                                                     | REPORT SECTION                   |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------|----------------------------------|
| <b>Noise policy for Industry NPFI</b>                                                                                                                     | Meet PNTL levels for day, evening and night time for operational noise sources at receivers                     | Operational noise and vibration impact assessment for PA and school bells, carpark Services                  | Section 6                        |
| <b>Interim construction noise guideline</b>                                                                                                               | Meet the NML and maximum noise level 75 dBA at affected properties during construction                          | Construction noise and vibration impact assessment                                                           | Section 7                        |
| <b>Guidelines for Division 5.1 assessments Considerations of environmental factors for health services facilities and Schools / Addendum October 2024</b> | a) Environmental impact of the community                                                                        | (a1) assessing impact during construction<br>(a2) impact post construction                                   | Section 7 (a1)<br>Section 6 (a2) |
|                                                                                                                                                           | d) reduction of the aesthetic, recreational, scientific or other environmental quality or value of the locality | (d1) impacts onto adjoining properties and spaces such as acoustic, noise and vibration                      | Section 6 and 7 (d1)             |
|                                                                                                                                                           | l) pollution of the environment                                                                                 | l1) Any pollution during construction and post construction including noise and vibration                    | Section 6 and 7 (l1)             |
|                                                                                                                                                           | r) other relevant factors                                                                                       | r3) noise / air pollution, vibration and safety impacts from roads, rail, drop off and pickup areas, parking | Sections 5.2, 6.2 (r3)           |

This report shall not be relied upon as providing any warranty or guarantee of the building, its services or equipment.

## 1.1 AUTHORS

This report was prepared by Rohith Vincent and Kanvin Chen. Quality assurance was carried out by Thomas Warren. NDY holds a Sydney membership of the Australasian Association of Acoustical Consultants, and Kanvin Chen and Thomas Warren are Members of the Acoustical Society of New Zealand / Australia.

## 1.2 PURPOSE

The purpose of this report is to provide acoustic design input into the following areas:

- Baseline noise survey of the area
- Review of the zoning, type of area, LEP, DCP plans and assessment to obtain Project trigger noise levels
- Statement of operational and construction noise environmental effects such as noise emissions to the boundary from onsite plant equipment and from construction.

## 1.3 AUTHORITY

Authority to undertake this report was provided by Paul Nickson of NSW Department of Education.

## 1.4 DOCUMENTATION REVIEW

The following plans/ reports identified in Table 2 have been reviewed to inform the assessment contained within this report. Where a standard or guideline is listed, this does not necessarily mean that the standard has been adopted in its entirety, as it may not all apply to this site.

TABLE 2: PLAND AND REPORTS REVIEWED

| DISCIPLINE                   | DOCUMENT NAME                                                          | REVISION  | DATE             |
|------------------------------|------------------------------------------------------------------------|-----------|------------------|
| <b>Planning</b>              | Greenway Park Public School Upgrade Planning Approval Pathway Strategy | Version 2 | dated 17.08.2023 |
| <b>SINSW</b>                 | Greenway Park Public School Detailed Due Diligence checklist           |           | dated 17.05.2023 |
| <b>Transport</b>             | Greenway Park Public School Upgrade Draft Rapid Transport Assessment   | Version 2 | dated 19.10.2024 |
| <b>Architecture</b>          | Greenway Park Public School Tender Issue Package, by Fulton Trotter    | Tender    | dated 14.03.2025 |
| <b>Services – mechanical</b> | NDY Mechanical Services Drawings and Schedules                         | rev.5.0   | dated 24.02.2025 |
| <b>Services – electrical</b> | Greenway Park Public School Upgrade Electrical Drawing Set             |           | dated 06.12.2024 |
| <b>Geotechnical</b>          | Geotechnical Interpretive Report                                       |           | dated 17.09.2023 |

| DISCIPLINE | DOCUMENT NAME                       | REVISION | DATE |
|------------|-------------------------------------|----------|------|
|            | 'PS206292-SYD-GEO-REP-Rev 01 by WSP |          |      |

The below standards were used in this report:

- NSW Noise Policy for Industry (NPfI) 2017
- NSW Interim Construction Noise Guideline (ICNG) 2009
- NSW Road Noise Policy (RNP) 2011
- NSW Government Department of Planning Development Near Rail Corridors and Busy Roads – Interim Guidelines (2008)
- NSW EPA Assessing Vibration: A Technical Guideline 2006
- State Environmental Planning Policy (Transport and Infrastructure) 2021
- AS / NZS 2107:2016 Acoustics, Recommended design sound levels and reverberation times for building interiors
- NSW Department of Environment & Climate Change (DECC)
- DEFRA 2005 Data base, including the existing construction noise database on BS 5228-1:2009+A1:2014 Code of Practice for Noise and Vibration control on construction and open sites Part 1 Noise and Part 2 Vibration
- NSW Interim Construction Noise Guideline 2009
- German DIN 4150: Part 3 – 1999 "Effect of Vibration on Structure" (DIN 1999)
- Australian Standard AS 2670.2 1990 – Evaluation of Human Exposure to Whole Body Vibration – Part 2: Continuous and Shock Induced Vibration in Building (1 Hz to 80 Hz)
- British Standard BS 6472 – 2008 – Evaluation of Human Exposure Vibration in Buildings (1 Hz to 80 Hz)
- Liverpool Local Environmental Plan LEP 2008
- Liverpool Development Control Plans DCP 2008

## 2 ACTIVITY INFORMATION

### 2.1 PROPOSED ACTIVITY DESCRIPTION

The proposed activity for the Greenway Park Public School upgrade includes:

#### 2.1.1 DEMOLITION / EARTHWORKS

- Demolish part of boundary fence on Chapman Street for new vehicular crossover;
- Demolish parts of boundary fence on Chapman Street for new gates;
- Demolish shade structure and associated concrete slab and footpath;
- Demolish footpaths;
- Removal of two trees;
- Trenching for underground services; and
- Earthworks associated with new buildings and landscaping.

#### 2.1.2 CONSTRUCTION

- Construction and operation of single storey classroom building with associated covered walkways;
- Construction and operation of a new preschool building, including covered walkways, new carpark (12 spaces and one (1) accessible space) and vehicular crossover to Chapman Street;
- Installation of artwork on Block H and Block J façades, as well as a preschool retaining wall;
- Laying of services within trenches;
- New pedestrian entry points;
- Fencing and gates;
- Underground OSD tanks;
- Rainwater tanks;
- Shed for preschool;
- Outdoor play equipment for the preschool;
- New fire hydrant booster & associated building services connections;
- Retaining walls associated with the preschool;
- Signage;
- Landscaping; and
- Associated earthworks

#### 2.1.3 WORKS UNDER SEPARATE PLANNING PATHWAY (NOT PART OF THIS REF)

To enable the proposed activity to proceed, the existing seven (7) portable classrooms, associated walkways, a shade structure and associated concrete slab will be removed from site and five (5) new portable classrooms and associated walkways will be installed adjacent to Block F under a separate planning pathway. A tree removal permit for the removal of three (3) trees will also be sought separately. These works do not form part of this REF application and have not been assessed in this report.

### 2.2 ACTIVITY SITE

The activity site is located on Wyattville Drive, West Hoxton and is legally described as:

- Lot 11 DP 858025; and
- Lot 20 DP 867282

Greenway Park Public School is located on the south eastern side of Chapman Street and the north eastern side of Wyattville Drive. The surrounding context of the site is predominantly low density residential as well as a childcare centre to the north. Figure 1 below depicts an aerial photograph of the site.



FIGURE 1: AERIAL PHOTOGRAPH OF SITE

## 2.3 SITE ZONING

The site is zoned R2 Low Density Residential on Liverpool City Council's LEP. As observed in Figure 2, the site is surrounded by residential areas. In addition, the Detailed Due Diligence reports states that the built form in the area is mostly residential, two storey, detached dwellings.




FIGURE 2: SITE LOCATION OBTAINED FROM NSW PLANNING PORTAL SPATIAL VIEWER

## 2.4 SCHOOL OPERATION HOURS

School facilities will operate during daytime (7:00 am – 6:00pm) with limited/no activities during evening time (6:00 pm to 10:00pm) and no activities during the nighttime (after 10 pm).

## 2.5 SENSITIVE RECEIVERS

The most sensitive receivers for this activity have been identified, depicted in Figure 3 and listed in Table 3 below:

TABLE 3: SENSITIVE RECEIVERS FOR STAGE 1

| RECEIVER                               | RECEIVER ADDRESS                    | RECEIVER DISTANCE, (APPROXIMATE) M       | TYPE OF RECEIVER |
|----------------------------------------|-------------------------------------|------------------------------------------|------------------|
| <b>R1</b>                              | 17 Chapman St, West Hoxton NSW 2171 | 22                                       | Residential      |
| <b>R2</b>                              | 1 Cook Pl, West Hoxton NSW 2171     | 15                                       |                  |
| <b>R3</b>                              | 8 Chapman St, West Hoxton NSW 2171  | 4m from boundary near proposed preschool |                  |
| <b>Existing school buildings H / I</b> |                                     |                                          | School buildings |



FIGURE 3: LOCATION OF SENSITIVE RECEIVERS

### 3 METHODOLOGY

This report was prepared using the below methodology:

- Review of the NSW standards, NPfl regulations and local requirements for noise and vibration (local council DCP / LEP).
- Review of the site location, zoning and most affected receivers for all stages.
- Review of possible busy roads near the site and location of rail corridors.
- Selection of logger's location was based on:
  - Critical receivers
  - Location of the receivers
  - A prelim. meeting with planners discussing the proposed location
- Assessment of operating noise and vibration sources, by coordinating with mechanical, electrical, and fire protection designers to establish noise sources and operating times. Other consultants involved were included such as traffic and garbage collection.
- To assess the construction noise and vibration sources, coordination was done with the client, project manager to understand the approximate construction programme and phases.

## 4 ACOUSTIC ASSESSMENT OF THE EXISTING ENVIRONMENT

### 4.1 METEOROLOGICAL DATA

To verify that the noise data was obtained during suitable meteorological conditions, weather data such as rain and wind speed were obtained from the Weather station 'Edmondson Park' (Latitude / Longitude: 33.965° S, 150.851° E), Station ID **ISYDNE3595** as a representative site located approximately 5km away from the site.

Noise data is excluded (as per the NSW NPfI methodology) from the results in case of:

- Rain observed during any 15-minute noise measurement period and/or;
- Wind speeds exceeded 5 m/s during any 15-minute noise measuring period.

### 4.2 INSTRUMENTATION

Noise levels were measured using noise loggers. Table 4 provides information relating to each noise loggers/sound level meter.

TABLE 4: NOISE LOGGER AND SOUND LEVEL METER INFORMATION

| NOISE LOGGER/SOUND LEVEL METER | TYPE    | SERIAL NUMBER |
|--------------------------------|---------|---------------|
| <b>SVAN 977A</b>               | Class 1 | SN 99057      |
| <b>SVAN 977A</b>               | Class 1 | SN 99761      |

The equipment calibration was checked prior to, and after the noise survey using a 94 dB external calibration tone at 1 kHz.

The noise loggers were configured to record all relevant noise parameters including background noise ( $L_{A90}$ ) and equivalent continuous noise levels  $L_{Aeq}$ . Samples were recorded at 15-minute A-weighted continuous intervals. The noise monitor responses were set to fast response. The analysers are Class 1 and Class 2 compliant with AS IEC 61672.2-2004.

### 4.3 NOISE LOGGERS' LOCATIONS

The noise logger locations that were agreed with the team are as follows, which were selected to represent the most affected sensitive receivers:

- **Logger 1:** SN 99057 at west side school boundary near sensitive receivers R1 and R2
- **Logger 2:** SN 99761 at north side school boundary near sensitive receivers R3

Below figures depicts the noise loggers installed at site and their measurement locations, which based on our assessment is appropriate in representing noise levels of sensitive receivers surrounding the site.



FIGURE 4: LOGGERS DEPLOYMENT LOCATIONS

## 5 NOISE AND VIBRATION CRITERIA

### 5.1 LOCAL CITY COUNCIL RULES

The Liverpool Local Environmental Plan 2014 (LEP 2008) and Liverpool Development Control Plan (DCP 2008) have been reviewed and have no particular requirements for noise.

### 5.2 NSW DEVELOPMENT NEAR RAIL CORRIDORS AND BUSY ROADS

The site and use fall under the category of a sensitive activity under the NPfI as it is an educational facility. However, upon review of planning maps and Google Maps, the roads in the vicinity such Chapman St, Wyattville Dr, Greenway Dr and Cowpasture Rd are not busy with light and fast-moving traffic. In addition, the location is not located close to rail lines. Therefore, no rail or road noise or vibration assessment is required for this report.

### 5.3 NSW NOISE POLICY FOR INDUSTRY (NPfI) 2017

For the purpose of the assessment, the measured noise data was processed into the following time periods:

- Daytime: 0700 to 1800 hrs.
- Evening: 1800 to 2200 hrs.
- Night-time: 2200 to 0700 hrs.

The measured noise indexes are the background ( $L_{A90}$ ) and equivalent continuous ( $L_{Aeq}$ ) noise levels during these defined time periods. The  $L_{A90}$  noise levels presented are *Rating Background Levels* (RBLs), being the median of the background  $L_{A90}$  (i.e. of the lowest 10<sup>th</sup> percentile of samples) in each daytime, evening and night-time measurement period, for each 24-hour period during the noise survey.

The  $L_{Aeq}$  noise levels presented are the logarithmic average of all the  $L_{Aeq}$  samples taken in each of the daytime, evening and night-time periods.

TABLE 5: MEASURED NOISE LEVELS FOR NOISE LOGGERS, DBA

| LOCATION | NOISE INDEX      | NOISE LEVEL, dB RE 20 $\mu$ Pa |              |              |
|----------|------------------|--------------------------------|--------------|--------------|
|          |                  | DAYTIME                        | EVENING      | NIGHT - TIME |
|          |                  | 0700 TO 1800                   | 1800 TO 2200 | 2200 TO 0700 |
| Logger 1 | $L_{A90}$ (RBL)  | 35*                            | 35           | 33           |
|          | $L_{Aeq,period}$ | 56                             | 49           | 48           |
| Logger 2 | $L_{A90}$ (RBL)  | 36*                            | 34           | 31           |
|          | $L_{Aeq,period}$ | 61                             | 51           | 49           |

\* RBL obtained from noise logging was very low (35dBA and 36dBA for Logger 1 and Logger 2 respectively) compared with the average noise level of the area (56 dBA and 61 dBA for Logger 1 and Logger 2 respectively). According to the NSW NPfI Table 2.2 Amenity Noise levels, a suburban area R2 should have a Daytime RBL of around 45 dBA and evening RBL of approximately 40 dBA, hence the measured 35 dBA is not representative of the existing area type and probably will drag the estimated PTNL to an unrealistically low value. For this reason, values of day and evening RBL have been adjusted to what table 2.2 recommends for this type of area during PTNL determination.

### 5.3.1 AMENITY AND INTRUSIVENESS CRITERIA

The NSW NPfI provides assessment methodologies, criteria and detailed information on the assessment of environmental noise emissions in NSW. The NSW NPfI criteria for noise sources consider two (2) components:

- Controlling intrusive noise impacts for residential receivers. Assessing intrusiveness generally requires noise measurements to quantify background (LA90) noise levels at a location considered representative of the most potentially affected residential receiver(s). The intrusiveness criterion essentially means that the equivalent continuous noise level (LAeq) of the source(s) under consideration should be controlled to not exceed background noise levels by more than 5 dB(A).
- Maintaining noise amenity for various categories of land use (including residential receivers and other sensitive receivers). The amenity criterion is based on the sensitivity of a particular land use to industrial-type noise. The recommended amenity noise levels detailed in Table 2.2 of NSW NPfI represent the objective for total industrial noise at a receiver location, whereas the project amenity noise level represents the objective for noise from a single industrial development at a receiver location. This is to ensure that industrial noise levels (existing plus new) remain within the recommended amenity noise levels for an area. The project amenity criteria for each new source of industrial noise is equalled to recommended amenity noise level minus 5dB(A).
- A +3dB(A) to be added to project amenity noise level for conversion from a period level to a 15-minutes level. Where the resultant project amenity noise level is 10dB or more below the existing industrial noise level, the project amenity noise levels can be set at 10 dB below existing industrial noise levels if it can be demonstrated that existing industrial noise levels are unlikely to reduce over time.

The NSW NPfI characterise the above areas as per the below description:

| Receiver category    | Typical planning zoning – standard instrument*                                                                                                                                         | Typical existing background noise levels                                | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |
|----------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Rural residential    | RU1 – primary production<br>RU2 – rural landscape<br>RU4 – primary production small lots<br>R5 – large lot residential<br>E4 – environmental living                                    | Daytime RBL <40 dB(A)<br>Evening RBL <35 dB(A)<br>Night RBL <30 dB(A)   | <b>Rural</b> – an area with an acoustical environment that is dominated by natural sounds, having little or no road traffic noise and generally characterised by low background noise levels. Settlement patterns would be typically sparse.<br><br>Note: Where background noise levels are higher than those presented in column 3 due to existing industry or intensive agricultural activities, the selection of a higher noise amenity area should be considered.                                                  |
| Suburban residential | RU5 – village<br>RU6 – transition                                                                                                                                                      | Daytime RBL <45 dB(A)<br>Evening RBL <40 dB(A)                          | <b>Suburban</b> – an area that has local traffic with characteristically intermittent traffic flows or with some limited commerce or industry. This area often has the                                                                                                                                                                                                                                                                                                                                                 |
|                      | R2 – low density residential<br>R3 – medium density residential<br>E2 – environmental conservation<br>E3 – environmental management                                                    | Night RBL <35dB(A)                                                      | following characteristic: evening ambient noise levels defined by the natural environment and human activity.                                                                                                                                                                                                                                                                                                                                                                                                          |
| Urban residential    | R1 – general residential<br>R4 – high density residential<br>B1 – neighbourhood centre (boarding houses and shop-top housing)<br>B2 – local centre (boarding houses)<br>B4 – mixed use | Daytime RBL > 45 dB(A)<br>Evening RBL > 40 dB(A)<br>Night RBL >35 dB(A) | <b>Urban</b> – an area with an acoustical environment that:<br><ul style="list-style-type: none"> <li>is dominated by 'urban hum' or industrial source noise, where urban hum means the aggregate sound of many unidentifiable, mostly traffic and/or industrial related sound sources</li> <li>has through-traffic with characteristically heavy and continuous traffic flows during peak periods</li> <li>is near commercial districts or industrial districts</li> <li>has any combination of the above.</li> </ul> |

FIGURE 5: NPfI EXTRACT – TABLE 2.3 DETERMINING WHICH OF THE RESIDENTIAL RECEIVER CATEGORIES APPLIES

As most of the neighbourhood comprises of low-density R2 residential zoning, we believe the suburban area description above is the one more suitable for this activity.

TABLE 6: NSW NPFI AMENITY CRITERIA / TAKEN FROM TABLE 2.2 NPFI

| TYPE OF RECEIVER | INDICATIVE NOISE AMENITY AREA | PERIOD OF TIME         | $L_{Aeq}$ DB(A) | AMENITY CRITERIA $L_{Aeq}$ DB(A) – 5 DB + 3 DB |
|------------------|-------------------------------|------------------------|-----------------|------------------------------------------------|
| Residence        | Suburban Area                 | Day 7:00 to 18:00      | 55              | 53                                             |
|                  |                               | Evening 18:00 to 22:00 | 45              | 43                                             |
|                  |                               | Night 22:00 to 7:00    | 40              | 38                                             |

The NPFI recommends “Intrusive noise levels are only applied to residential receivers (residences)”. For other receiver types identified in Table 2.2, only the amenity levels apply. The amenity and intrusive noise levels are listed below.

TABLE 7: INTRUSIVENESS AND AMENITY NOISE CRITERIA

| LOGGER             | NOISE LEVEL, $L_{eq,15mins}$ [dBA]         |              |              |
|--------------------|--------------------------------------------|--------------|--------------|
|                    | DAYTIME                                    | EVENING      | NIGHT - TIME |
|                    | 0700 TO 1800                               | 1800 TO 2200 | 2200 TO 0700 |
| Receiver R1 and R2 | Amenity Assessment, $L_{Aeq, 15min}$       |              |              |
|                    | 53                                         | 43           | 38           |
|                    | Intrusiveness Assessment, $L_{Aeq, 15min}$ |              |              |
|                    | 50                                         | 40           | 38           |
| Receiver R3        | Amenity Assessment, $L_{Aeq, 15min}$       |              |              |
|                    | 53                                         | 43           | 39           |
|                    | Intrusiveness Assessment, $L_{Aeq, 15min}$ |              |              |
|                    | 50                                         | 39           | 36           |

### 5.3.2 DETERMINATION OF PROJECT SPECIFIC NOISE TRIGGER LEVEL (PNTL)

The Project Noise Trigger Levels (PNTL) are the most stringent noise levels of the NSW NPfI project intrusiveness and project amenity noise levels for day, evening and night-time periods and are project specific, as shown below:

TABLE 8: EXTERNAL PROJECT NOISE TRIGGER LEVEL (PNTL) FOR OPERATION NOISE

| LOCATION / AFFECTED | TIME         | DESCRIPTOR                 | EXTERNAL PNTL [DBA] |
|---------------------|--------------|----------------------------|---------------------|
| Receiver R1 and R2  | 0700 to 1800 | L <sub>Aeq</sub> , Day     | 50                  |
|                     | 1800 to 2200 | L <sub>Aeq</sub> , Evening | 40                  |
|                     | 2200 to 0700 | L <sub>Aeq</sub> , Night   | 38                  |
| Receiver R3         | 0700 to 1800 | L <sub>Aeq</sub> , Day     | 50                  |
|                     | 1800 to 2200 | L <sub>Aeq</sub> , Evening | 39                  |
|                     | 2200 to 0700 | L <sub>Aeq</sub> , Night   | 36                  |

## 5.4 CONSTRUCTION NOISE AND VIBRATION CRITERIA

### 5.4.1 INTERIM CONSTRUCTION NOISE GUIDELINE

The NSW Interim Construction Noise Guideline was developed by the NSW-Department of Environment & Climate Change DECC, NSW which incorporates the EPA. The Guideline contains detailed procedures for the assessment and management of construction noise impacts.

The guideline presents two ways of assessing construction noise impacts – the quantitative method, which is generally suited to longer term construction works and the qualitative method, which is generally suited to short term works (usually not more than 3 weeks) such as infrastructure maintenance.

It is expected that the length of the construction works associated with the activity would be more than 3 weeks and therefore a quantitative method has been used for this assessment.

Table 9 set out the management levels for noise at residence and sensitive land uses, respectively. Restrictions to the hours of construction may apply to activities that generate noise at residences above the 'highly noise affected management level' which is >75dBA.

The interim construction noise guideline states that if affected properties receive construction noise below 75 dBA, they do not require community consultation and a Construction Noise & Vibration Management Plan (CNVMP). This will be estimated and confirmed in this report.

Based on the daytime RBL values, the recommended noise management levels during all stages of the construction program are summarised in table below.

Table 9: NOISE AT AFFECTED USING QUANTITATIVE ASSESSMENT

| RECOMMENDED HOURS | EXTERNAL NOISE<br>MANAGEMENT LEVEL (NML)<br><br>L <sub>Aeq</sub> ,15MIN [DBA] | HOW TO APPLY                                                                                             |
|-------------------|-------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
|                   | Noise Affected                                                                | The noise affected level represents the point above which there may be some community reaction to noise. |

| RECOMMENDED HOURS                                                                                                               | EXTERNAL NOISE<br>MANAGEMENT LEVEL (NML)        | HOW TO APPLY                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|---------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                                                                                                                                 | LAEQ,15MIN [DBA]                                |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| Recommended<br>standard hours<br><br>Monday – Friday 7am to 6pm<br>Saturday 8am to 1pm<br>No work on Sundays or Public Holidays | <b>55 dB(A)</b><br>(45 +10)                     | Where the predicted or measured LAeq (15 minutes) noise level is greater than the affected level, the proponent should apply all feasible and reasonable* work practices to meet the noise affected level.<br><br>The proponent should also inform all potentially impacted residents of the nature of works to be carried out, the expected noise levels and duration, as well as contact details                                                                                                                                                                                                                                                                                                                          |
|                                                                                                                                 | Highly noise affected<br><b>75 dB(A)</b>        | The highly noise affected level represents the point above which there may be strong community reaction to noise.<br><br>Where noise is above this level, the relevant authority (consent, determining or regulatory) may require respite period by restricting hours that the very noisy activities can occur, taking into account: <ul style="list-style-type: none"> <li>– Times identified by the community when they are less sensitive to noise (such as before and after school for works near schools, or mid-morning or mid-afternoon for works near residences).</li> <li>– If the community is prepared to accept a longer period of construction in exchange for restrictions on construction times.</li> </ul> |
| Outside Recommended<br>standard hours                                                                                           | <b>40 dBA</b><br>(35 + 5)<br>RBL from nighttime | A strong justification would typically be required for works outside the recommended standard hours.<br><br>The proponent should apply all feasible and reasonable work practices to meet the noise affected level.<br><br>Where all feasible and reasonable practices have been applied and noise is more than 5 dB(A) above the noise affected level, the proponent should negotiate with the community.<br><br>For guidance on negotiating agreements see section 7.22                                                                                                                                                                                                                                                   |

\*Section 6, 'work practices' of the *Interim Construction Noise Guideline*, states: "there are no prescribed noise controls for construction works. Instead, all feasible and reasonable work practices should be implemented to minimise noise impacts. This approach gives construction site managers and construction workers the greatest flexibility to manage noise".

Definitions of the terms feasible and reasonable are given in Section 1.4 of the Guideline.

The Interim Construction Noise Guideline recommends the following noise levels for land uses other than residential, as shown in Table 10 below. The external noise levels should be assessed at the most affected occupied point on the premises. A conservative estimate of 10 dB is generally applied as the difference between the external and internal level for noise sensitive uses that require internal noise measurement.

For other sensitive land users different from residential, the below table applies:

**Table 3:** Noise at sensitive land uses (other than residences) using quantitative assessment

| Land use                                                                                                                                                                                         | Management level, $L_{Aeq}$ (15 min)<br>(applies when properties are being used)                                              |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------|
| Classrooms at schools and other educational institutions                                                                                                                                         | Internal noise level<br>45 dB(A)                                                                                              |
| Hospital wards and operating theatres                                                                                                                                                            | Internal noise level<br>45 dB(A)                                                                                              |
| Places of worship                                                                                                                                                                                | Internal noise level<br>45 dB(A)                                                                                              |
| Active recreation areas (characterised by sporting activities and activities which generate their own noise or focus for participants, making them less sensitive to external noise intrusion)   | External noise level<br>65 dB(A)                                                                                              |
| Passive recreation areas (characterised by contemplative activities that generate little noise and where benefits are compromised by external noise intrusion, for example, reading, meditation) | External noise level<br>60 dB(A)                                                                                              |
| Community centres                                                                                                                                                                                | Depends on the intended use of the centre.<br>Refer to the recommended 'maximum' internal levels in AS2107 for specific uses. |

FIGURE 6: EPA CONSTRUCTION NOISE AND VIBRATION GUIDELINE, 2016 / EXTRACT NOISE AT SENSITIVE USERS

## 5.4.2 NOISE MANAGEMENT LEVELS

Noise Management Levels (NML) associated with the construction works on the site are presented in Table 10.

TABLE 10: CONSTRUCTION NOISE MANAGEMENT LEVELS, LEQ 15MIN

| RECEIVERS                                   | RECOMMENDED HOURS                         | PERIOD      | RBL $LA_{90,15mins}$ [dBA] | EXTERNAL NOISE MANAGEMENT LEVEL [dBA]                                               |
|---------------------------------------------|-------------------------------------------|-------------|----------------------------|-------------------------------------------------------------------------------------|
| <b>All Sensitive Receivers (R1, R2, R3)</b> | Day time<br>(standard construction hours) | When in use | 45 dBA                     | (45 + 10) = 55 dB(A)<br>(Noise affected)<br><br>75 dB(A)<br>(highly noise affected) |
| <b>School receivers</b>                     | Day time<br>(standard construction hours) | When in use | -                          | 45 dBA (internal) / ~55 dBA* at façade, externally                                  |

\*Note that the ~55dBA external criteria is a conservative approach, as some building facades may achieve greater performance.

## 5.4.3 CONSTRUCTION VIBRATION CRITERIA

The effects of construction vibration upon buildings can be separated into three main categories:

- Perceptibility of the occupants to the vibration and the possibility of them being disturbed or annoyed.
- Vulnerability of the building structures to vibration induced damaged.
- Vulnerability of the contents of the building that includes types of equipment, activities and processes.

#### 5.4.3.1 Human Response to Vibration

Humans are very sensitive to vibration, and they can be disturbed, annoyed and have their work activities interfered with if the levels are too high. The Interim Construction Noise Guideline references "Assessing Vibration: a technical guideline" (Vibration Guideline) issued by the Department of Environment and Conservation NSW for measurement and assessment of vibration. The Vibration Guideline provides vibration criteria for continuous, impulsive and intermittent vibration

| Continuous vibration                                                                                | Impulsive vibration                                                                                                                                                                                                       | Intermittent vibration                                                                                                                                                                                                                                                      |
|-----------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Machinery, steady road traffic, continuous construction activity (such as tunnel boring machinery). | Infrequent: Activities that create up to 3 distinct vibration events in an assessment period, e.g. occasional dropping of heavy equipment, occasional loading and unloading.<br>Blasting is assessed using ANZECC (1990). | Trains, nearby intermittent construction activity, passing heavy vehicles, forging machines, impact pile driving, jack hammers. Where the number of vibration events in an assessment period is three or fewer this would be assessed against impulsive vibration criteria. |

The criteria are discussed in more detail in the following sections.

#### 5.4.3.2 Continuous and impulsive vibration (1-80 Hz)

According to the Vibration Guideline for continuous and impulsive vibration, assessment of impact should be considered on the basis of weighted root-mean-square acceleration values and results are to be compared against the following preferred and maximum values given for each orthogonal axis. The frequency weightings as per BS6841:1987 (reproduced in Appendix B3 of the guideline) are to be applied to the RMS measurement values (1-80Hz).

The criteria in the Vibration Guideline are derived from the limiting values of the assessment curves and multiplying factors from BS 6472:1992 (the curves are no longer referenced in the superseded version of the standard BS 6472:2008).

**Table 2.2 Preferred and maximum weighted rms values for continuous and impulsive vibration acceleration (m/s<sup>2</sup>) 1–80 Hz**

| Location                                                         | Assessment period <sup>1</sup> | Preferred values |               | Maximum values |               |
|------------------------------------------------------------------|--------------------------------|------------------|---------------|----------------|---------------|
|                                                                  |                                | z-axis           | x- and y-axes | z-axis         | x- and y-axes |
| Continuous vibration                                             |                                |                  |               |                |               |
| Critical areas <sup>2</sup>                                      | Day- or night-time             | 0.0050           | 0.0036        | 0.010          | 0.0072        |
| Residences                                                       | Daytime                        | 0.010            | 0.0071        | 0.020          | 0.014         |
|                                                                  | Night-time                     | 0.007            | 0.005         | 0.014          | 0.010         |
| Offices, schools, educational institutions and places of worship | Day- or night-time             | 0.020            | 0.014         | 0.040          | 0.028         |
| Workshops                                                        | Day- or night-time             | 0.04             | 0.029         | 0.080          | 0.058         |
| Impulsive vibration                                              |                                |                  |               |                |               |
| Critical areas <sup>2</sup>                                      | Day- or night-time             | 0.0050           | 0.0036        | 0.010          | 0.0072        |
| Residences                                                       | Daytime                        | 0.30             | 0.21          | 0.60           | 0.42          |
|                                                                  | Night-time                     | 0.10             | 0.071         | 0.20           | 0.14          |
| Offices, schools, educational institutions and places of worship | Day- or night-time             | 0.64             | 0.46          | 1.28           | 0.92          |
| Workshops                                                        | Day- or night-time             | 0.64             | 0.46          | 1.28           | 0.92          |

<sup>1</sup> Daytime is 7.00 am to 10.00 pm and night-time is 10.00 pm to 7.00 am

<sup>2</sup> Examples include hospital operating theatres and precision laboratories where sensitive operations are occurring. There may be cases where sensitive equipment or delicate tasks require more stringent criteria than the human comfort criteria specified above. Stipulation of such criteria is outside the scope of this policy, and other guidance documents (e.g. relevant standards) should be referred to. Source: BS 6472–1992

The Vibration Guideline notes “Activities should be designed to meet the preferred values where an area is not already exposed to vibration. Where all feasible and reasonable measures have been applied, values up to the maximum value may be used if they can be justified. For values beyond the maximum value, the operator should negotiate directly with the affected community. Situations exist where vibration above the preferred values can be acceptable, particularly for temporary disturbances and infrequent events of short-term duration. An example is a construction or excavation project.”

#### 5.4.3.3 Intermittent vibration (1-80 Hz)

According to the Vibration Guideline for intermittent vibration, assessment of impact should be considered on the basis of vibration dose values (VDV). Acceptable values of vibration dose are given as follows.

**Table 2.4 Acceptable vibration dose values for intermittent vibration (m/s<sup>1.75</sup>)**

| Location                                                         | Daytime <sup>1</sup> |               | Night-time <sup>1</sup> |               |
|------------------------------------------------------------------|----------------------|---------------|-------------------------|---------------|
|                                                                  | Preferred value      | Maximum value | Preferred value         | Maximum value |
| Critical areas <sup>2</sup>                                      | 0.10                 | 0.20          | 0.10                    | 0.20          |
| Residences                                                       | 0.20                 | 0.40          | 0.13                    | 0.26          |
| Offices, schools, educational institutions and places of worship | 0.40                 | 0.80          | 0.40                    | 0.80          |
| Workshops                                                        | 0.80                 | 1.60          | 0.80                    | 1.60          |

1 Daytime is 7.00 am to 10.00 pm and night-time is 10.00 pm to 7.00 am.

2 Examples include hospital operating theatres and precision laboratories where sensitive operations are occurring. These criteria are only indicative, and there may be a need to assess intermittent values against the continuous or impulsive criteria for critical areas.

Source: BS 6472-1992

#### 5.4.3.4 Vibration Criteria – Building Contents and Structure

The vibration effects on the building itself are assessed international standards as follows:

- **For transient vibration:** British Standard BS 7385: Part 2 – 1993 “Evaluation and measurement for vibration in buildings Part 2: Guide to damage levels from ground borne vibration” (BSI 1993); and
- **For continuous or repetitive vibration:** German DIN 4150: Part 3 – 1999 “Effects of Vibration on Structure” (DIN 1999).

#### 5.4.3.5 Standard BS 7385 Part 2 – 1993

For transient vibration, as discussed in standard BS 7385 Part 2- 1993, the criteria are based on peak particle velocity (mm/s) which is to be measured at the base of the building. These are summarised in Table 11 and illustrated in FIGURE 7.

**TABLE 11: TRANSIENT VIBRATION CRITERIA AS PER STANDARD BS 7385 PART 2 – 1993**

| LINE IN | TYPE OF BUILDING                                                                          | PEAK COMPONENT PARTICLE VELOCITY IN FREQUENCY RANGE OF PREDOMINANT PULSE |                                                              |
|---------|-------------------------------------------------------------------------------------------|--------------------------------------------------------------------------|--------------------------------------------------------------|
|         |                                                                                           | 4 HZ TO 15 HZ                                                            | 15 HZ AND ABOVE                                              |
| 1       | Reinforced or framed structures<br>Industrial and heavy commercial buildings              | 50 mm/s at 4 Hz and above                                                | -                                                            |
| 2       | Unreinforced or light framed structures<br>Residential or light commercial type buildings | 15 mm/s at 4 Hz<br>increasing to 20 mm/s at 15 Hz                        | 20 mm/s at 15 Hz<br>increasing to 50 mm/s at 40 Hz and above |

Standard BS 7385 Part 2 – 1993 states that the value in Table 11 relate to transient vibration which does not cause resonant response in buildings. Where the dynamic loading caused by continuous vibration events is

such that it results in dynamic magnification due to resonance (especially at the lower frequencies where lower guide values apply), then the values in Table 11 may need to be reduced by up to 50% (refer to Line 3 in FIGURE 7).




FIGURE 7 – BS 7385 PART 2 – 1993, GRAPH OF TRANSIENT VIBRATION VALUES FOR COSMETIC DAMAGES

In the lower frequency region where strains associated with a given vibration velocity magnitude are higher, the recommended values corresponding to Line 2 are reduced. Below a frequency of 4 Hz, where a high displacement is associated with the relatively low peak component particle velocity value, a maximum displacement of 0.6 mm (zero to peak) is recommended. This displacement is equivalent to a vibration velocity of 3.7 mm/s at 1 Hz.

The standard also states that minor damage is possible at vibration magnitudes which are greater than twice those given in Table 11, and major damage to a building structure may occur at values greater than four times the tabulate values.

Fatigue considerations are also addressed in the standard and it is concluded that unless the calculation indicated that the magnitude and number of load reversals is significant (in respect of the fatigue life of building materials) then the values in Table 11 should not be reduced for fatigue considerations.

#### 5.4.3.6 Structural Response to Vibration - German Standard DIN 4150-3:1999

The German Standard DIN 4150-3 Structural Vibration Part 3: Effects on building and structures is commonly used in Australia to evaluate the effects of vibration on structures primarily used for static loading.

The response of a building to vibration is affected by several factors that include its type of foundation, the underlying ground conditions, its construction and the state of the building. Please note the construction vibration limits are designed to ensure the structural integrity of nearby buildings and are not for human comfort. the limits are well above perceptibility.

According to DIN 4150 short term vibration refers to vibration which does not occur often enough to cause structural fatigue, and which does not produce resonance in the structure being evaluated. Long-term vibration refers to all types of vibration not covered by the definition of 'short-term vibration'. The criteria for short-term and long-term vibration are listed in the following.

#### 5.4.3.7 Guideline Values for evaluation of short-term vibration - DIN 4150-3:1999

The vibration limits of table 1 in DIN 4150-3:1999 (replicated in Table 12 below) refer to the evaluation of the effects of short-term vibration on structures.

It should however be noted that compliance with the vibration limits to avoid structural damage of buildings, cannot provide certainty. If damage occurs despite compliance with the standard, it is to be assumed that other causes are responsible, however, further investigations are necessary. And on the other hand, exceeding the limits does not necessarily lead to damage.

TABLE 12: DIN 4150-3 CONSTRUCTION VIBRATION LIMITS – SHORT TERM

| TYPES OF STRUCTURES                                                                                                                                                                          | GUIDELINE VALUES FOR VIBRATION VELOCITY (MM/S) |             |                         |                                                                   |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------|-------------|-------------------------|-------------------------------------------------------------------|
|                                                                                                                                                                                              | VIBRATION AT THE FOUNDATION AT A FREQUENCY OF: |             |                         | VIBRATION AT HORIZONTAL PLANE OF HIGHEST FLOOR AT ALL FREQUENCIES |
|                                                                                                                                                                                              | 1Hz TO 10Hz                                    | 10 TO 50 Hz | 50 TO 100Hz (AND ABOVE) |                                                                   |
| <b>Buildings for commercial purposes, Industrial building and building of similar design</b>                                                                                                 | 20                                             | 20 to 40    | 40 to 50                | 40                                                                |
| <b>Dwellings and buildings of similar design and/or occupancy</b>                                                                                                                            | 5                                              | 5 to 15     | 15 to 20                | 15                                                                |
| <b>Structures that because of their particular sensitivity to vibration, cannot be classified as above and are of great intrinsic value (e.g. listed buildings under preservation order)</b> | 3                                              | 3 to 8      | 8 to 10                 | 8                                                                 |

#### 5.4.3.8 Guideline Values for evaluation of long-term vibration - DIN 4150-3:1999

The vibration limits of Table 3 in DIN 4150-3:1999 refer to the evaluation of the effects of long-term vibration on structures.

The criteria are the peak particle velocities measured on the uppermost full storey of any building not related to the site and are listed in Table 13.

According to the standard, *exceeding the values listed below does not necessarily lead to damage.*

If a building is subject to harmonic vibration, then maximum values can occur in floors other than the top floor, or in the foundation. The values given also apply in these cases.

TABLE 13: DIN 4150-3 CONSTRUCTION VIBRATION LIMITS – LONG TERM

| TYPES OF STRUCTURES                                                                                                                                                                          | GUIDELINE VALUES FOR VIBRATION VELOCITY (MM/S) OF VIBRATION IN HORIZONTAL PLANE OF FIRST FLOOR, AT ALL FREQUENCIES |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------|
| <b>Buildings for commercial purposes, Industrial building and building of similar design</b>                                                                                                 | 10                                                                                                                 |
| <b>Dwellings and buildings of similar design and/or occupancy</b>                                                                                                                            | 5                                                                                                                  |
| <b>Structures that because of their particular sensitivity to vibration, cannot be classified as above and are of great intrinsic value (e.g. listed buildings under preservation order)</b> | 2.5                                                                                                                |

## 5.4.4 SUMMARY OF CONSTRUCTION NOISE AND VIBRATION CRITERIA

Construction noise criteria are NML levels (between 55 dBA and max. 75 dBA) for standard construction hours for the below sensitive receivers:

- **Receiver 1:** 17 Chapman St, West Hoxton NSW 2171

- **Receiver 2:** 1 Cook Pl, West Hoxton NSW 2171
- **Receiver 3:** 8 Chapman St, West Hoxton NSW 2171

We consider that for this activity, the vibration criteria will be as per DIN 4150 – 3:1999 construction vibration limits – long term. Residential receivers in the area will have a peak particle velocity criterion of 5 mm/s and commercial buildings of 10 mm/s peak particle velocity criteria.

## 6 OPERATIONAL NOISE & VIBRATION IMPACT ASSESSMENT

The following sections present our assessment of noise emission impacts from operational noise sources from the activity. Predicted noise levels and associated mitigation measures are also provided according to the noise assessment and criteria.

## 6.1 NOISE EMISSION FROM PA SYSTEMS AND SCHOOL BELLS

A public address (PA) system will be installed on the site. Appropriate design and commissioning controls will be implemented to minimise noise spill from the PA to receiving locations outside the school. These will be addressed with the design team during the detailed design stage but may include:

- The PA system will be for voice announcements only (no music)
- Speakers to be located away from the school boundary and oriented away from sensitive receivers.
- The PA system use to be limited to school hours only (Preferably only between 7 am 6 pm)
- This system should have installed sound power level noise limiting devices to adjust the speakers if needed.

Both the PA system and the school bell should be installed and adjusted such that the PNTL during school hours are met at the noise sensitive receivers.

## 6.2 NOISE EMISSIONS FROM CARPARK

The latest drawings include a carpark for the proposed Preschool with a capacity of approximate 12 car spaces + 1 accessible space. Sensitive receivers were identified, the closest being - 7 Chapman St at approximately 19m from car park. A noise prediction of carpark noise propagation to receivers was performed using the daytime PTNL limit of 50 dBA. The assessment was conducted assuming the preschool childcare will only be operational during the day period from 7am to 6pm and only 75% of car park would be occupied on normal operations.

An exceedance was predicted during the assessment with no mitigation. To mitigate the noise a 1.5m high solid barrier along the carpark is required to provide noise reduction to the receivers at Chapman St and Watts Pl, shown in Figure 8 below (min height 1.5 m, density of construction to ensure the noise levels will meet PNTL levels). The predictions from the noise assessment with and without the solid barrier are depicted in the Table 14 below.




FIGURE 8: INDICATIVE CARPARK BARRIER LOCATION

TABLE 14: CARPARK NOISE PROPAGATED INTO CRITICAL RECEIVERS

| RECEIVER                                        | NOISE LIMIT                    | ESTIMATED UNTREATED NOISE LEVEL (OUTSIDE) / (SPL) | ESTIMATED NOISE LEVEL (OUTSIDE) / (SPL) AFTER ACOUSTIC TREATMENT |
|-------------------------------------------------|--------------------------------|---------------------------------------------------|------------------------------------------------------------------|
| 7 Chapman St at approximately 19m from car park | 50 dB(A)<br>(PTNL for Daytime) | 52 dB(A)                                          | 43 dB(A)                                                         |

Note: carpark operates during daytime (7 am – 6 pm) with a limited capacity during evening time (6pm to 10 pm), no operations after 10pm.

In addition to the recommended solid barrier, management practices such as the installation of visual signage to discourage raised voices in the carpark and minimal use of the carpark during the evening and night need to be introduced.

The above levels are propagated outside to the closest receiver's façade. With the recommended acoustic treatment measures utilizing solid barriers, we will achieve adequate sound reduction to meet the recommended internal noise levels as per AS / NZS 2107.

## 6.3 NOISE EMISSIONS FROM SERVICES

### 6.3.1 MECHANICAL SERVICES

As per NDY mechanical sketches and mechanical spatial designs, there is an intention of locating a plant room as per below:

- Plant A on ground level adjacent to new GLS building, 16 sqm for ODU units. The plant would be on the east side of the proposed building facing Chapman St.
- Plant B on ground level of proposed preschool, 12sqm for ODU units. The plant would be on the side of the proposed building facing Chapman St.




FIGURE 9: LOCATION FOR MECHANICAL PLANT IN NEW BUILDINGS

The current locations being considered for the mechanical plant can be seen in Figure 9. The plant is assumed to be operational during the assumed school operation hours which is during daytime (7:00 am – 6:00pm) with limited to no activities during evening time (6:00 pm to 10:00pm) and no activities during the nighttime.

We have coordinated with the updated mechanical drawings and selections. For the assessment, we have allowed the following:

- **Plant A** consists of 4 Outdoor units (ODU) + 1 side discharge ODU unit. Near this plant room there will be an EAF fan, OAF fan and a TEF fan.
- **Plant B** consists of 3 Outdoor units (ODU) + 1 side discharge ODU unit. Near this plant room there will be 2 x OAF fan, 3 x GEF fan and a TEF fan.

Sound data for each plant room is listed in Table 15 and Table 16.

TABLE 15: SOUND POWER LEVELS FOR ASSUMED MECHANICAL UNITS (ODU)

| EQUIPMENT          | SWL SOUND POWER LEVEL (dB) PER FREQUENCY BAND (HZ) |     |     |     |      |      |      |      |     |
|--------------------|----------------------------------------------------|-----|-----|-----|------|------|------|------|-----|
|                    | 63                                                 | 125 | 250 | 500 | 1000 | 2000 | 4000 | 8000 | dBA |
| <b>Plant A ODU</b> | 88                                                 | 86  | 85  | 83  | 77   | 73   | 70   | 62   | 84  |
| <b>Plant B ODU</b> | 87                                                 | 84  | 84  | 82  | 75   | 72   | 69   | 61   | 83  |

TABLE 16: SOUND POWER LEVELS FOR ASSUMED MECHANICAL UNITS (FANS)

| EQUIPMENT           | MAX CUMULATIVE SWL SOUND POWER LEVEL (dB) |
|---------------------|-------------------------------------------|
| <b>Plant A FANS</b> | 69                                        |
| <b>Plant B FANS</b> | 70                                        |

The noise impact assessment was conducted for to sensitive receivers. The closest possible receivers were identified and their approximate distances to the proposed plant room were determined. The PTNLs for evening period have been used as the noise limits (as the school will not be operational during nighttime). The closest possible sensitive receivers identified are:

- **School building H & Receiver R1:** at approximately 25 m from Plant A. (based on current layout of new building location).
- **Receiver R3:** at approximately 6 m from Plant B. (based on current layout of new building location).

In addition to noise assessments to residential sensitive receivers, the NPfI categorises classrooms as sensitive spaces and requires a maximum internal noise limit of 45dBA to be met by the activity. To ensure that the mechanical plant does not impact the existing classrooms and comply with the NPfI limit of internal noise 45dBA.

Without any noise mitigation measures both plants exceed the PNTL levels and the internal noise levels in the school building H. For the mechanical plant to meet the criteria the below noise mitigation measures are necessary:

- **Plant A**
  - Acoustic louvres Type IAC SL 300 or equivalent as tall as the ODU units (two louvered walls). The acoustic louvres are to be minimum 300mm deep that can provide the below sound transmission loss in Table 17.
  - 1 side wall of this ODU plant room with outdoor acoustic absorption (type reapor 50 mm or similar, with NRC 0.95).
  - All Fans treatment for inlet / outlets with min 50 mm thick internal lining ducts and bends as coordinated with mechanical consultant.

• **Plant B**

- Acoustic louvres Type IAC SL 600 or equivalent as tall as the ODU units (two louvered walls). The acoustic louvres are to be minimum 300mm deep that can provide the below sound transmission loss in Table 17.
- 1 side wall of this ODU plant room with outdoor acoustic absorption (type reapor 50 mm or similar, with NRC 0.95).
- All Fans treatment for inlet / outlets with min 50 mm thick internal lining ducts and bends as coordinated with mechanical consultant.

For both louvres and lined ductwork, the final mechanical design must be assessed to select appropriate louvres and lined ductwork to meet the noise limits. Depending on final selections, the required performance may be higher or lower than stated here.

TABLE 17: ASSESSED NOISE TRANSMISSION LOSSES FROM ACOUSTIC LOUVRES

| LOUVER PROPOSED                        | MIN. LOUVER TL PER OCTAVE BAND FREQUENCY BAND (HZ) |     |     |     |      |      |      |      |
|----------------------------------------|----------------------------------------------------|-----|-----|-----|------|------|------|------|
|                                        | 63                                                 | 125 | 250 | 500 | 1000 | 2000 | 4000 | 8000 |
| <b>300mm Acoustic Louver – Plant A</b> | 6                                                  | 7   | 10  | 12  | 18   | 18   | 14   | 13   |
| <b>600 mm louver – Plant B</b>         | 7                                                  | 9   | 12  | 24  | 31   | 33   | 29   | 30   |

With the above noise mitigation measures noise levels at critical receivers including the closest existing school buildings will meet the activity criteria.

If the mechanical service plant is to operate outside of the daytime period, it is recommended that the operating loads / speeds are reduced to minimise noise emissions. If louder equipment is selected or added to the existing plant conditions, an updated acoustic review will be required.

We understand that a solid fence (min 1.8 m tall, min construction density to ensure the noise levels will meet PNTL levels, no gaps between fence panels) will be installed between the New Preschool building and receiver R3 as per below markup.




FIGURE 10: LOCATION FOR SOLID FENCE

### 6.3.2 ELECTRICAL SERVICES

As per NDY electrical concept sketches and designs, no new substations are being introduced as the existing 315kVA substation is estimated to be sufficient for the proposed works. Hence no additional noise sources are being introduced that requires noise assessment.

## 6.4 OPERATIONAL VIBRATION

For controlling vibration emissions on mechanical plant (VRF, condensers and similar), it would be recommended that all condensers are installed on isolation pads by Mason Industries, Embelton, or equal to ensure compliance with the NSW EPA document Assessing Vibration: A technical guideline. However, as the current assumed plant equipment units are small, we do not consider this will be a noticeable impact on school grounds or residential areas.

Note that acoustic and vibration impact to internal areas is not considered in REF scope.

## 7 CONSTRUCTION NOISE & VIBRATION IMPACT ASSESSMENT

We understand the critical construction activities proposed in the activity involves the removal and relocation of demountable classrooms, the construction of a new two storey building and refurbishment works to upgrade the existing buildings. The proposed construction plan and equipment for the activity is still subject to further development. For preliminary assessment purposes and based on previous experience on similar projects, we have assumed that the following plant and equipment will be used in the following phases:

- Excavation Demolition (only for new buildings.
- Structural Phase (only for new buildings.
- Construction and internal works for both new buildings.

We assume the hours of construction will be standard as per below:

- Weekdays 0700 to 1800
- Saturdays 0800 to 1300
- Sundays and public holidays: no work

### 7.1 CONSTRUCTION PLANT NOISE LEVELS

Minimum construction equipment for the estimated construction phases is described below:

TABLE 18 TYPICAL EXTERNAL NOISE LEVELS OF DEMOLITION AND CONSTRUCTION MACHINERY/ACTIVITY

| ITEM #                                   | ACTIVITY/MACHINERY                                             | SOURCE AND REFERENCE NUMBER (BS 5228 – 1:2009) | L <sub>eq</sub> SOUND PRESSURE LEVEL AT 10m (dBA) |
|------------------------------------------|----------------------------------------------------------------|------------------------------------------------|---------------------------------------------------|
| <b>Excavation and Demolition</b>         |                                                                |                                                |                                                   |
| 1                                        | Tracked excavator 14t / 66kW                                   | Table C2 Ref 25                                | 69                                                |
| 2                                        | Dumper truck 9T / 75 kW                                        | Table C4 / Ref 4                               | 76                                                |
| <b>Structural Phase</b>                  |                                                                |                                                |                                                   |
| 3                                        | Tracked excavator 14t / 66kW                                   | Table C2 Ref 25                                | 69                                                |
| 4                                        | Dumper truck 9T / 75 kW                                        | Table C4 / Ref 4                               | 76                                                |
| 5                                        | Mini piling rig (rock bolt) 250mm auger                        | Table C3 / Ref 18                              | 74                                                |
| 6                                        | Concrete pump + cement mixer truck (discharging) 8 T / 350 bar | Table C4/ Ref24                                | 68                                                |
| <b>Construction &amp; internal works</b> |                                                                |                                                |                                                   |
| 7                                        | Handheld circular saw 3 Kw                                     | Table C4 / Ref 72                              | 79                                                |
| 8                                        | Handheld cordless nail gun                                     | Table C4 / Ref 95                              | 73                                                |
| 9                                        | Diesel generator                                               | Table C4 / Ref 76                              | 61                                                |

**Notes:**

- The above equipment shows every equipment noise level as per BS 5228 – 1:2009, the equipment inclusion in each phase is the general equipment that is used in this type of construction. A more detailed assessment will only be done if the preliminary assessment exceeds 75 dBA, if not, the above assessment is adequate for this type of report.
- NSW DECC 2009 Construction noise Guideline quotes on Appendix B Equipment Noise levels, the DEFRA 2005 database, which includes the above referenced BS 5228 – 1:2009 noise levels.

## 7.2 PREDICTED CONSTRUCTION NOISE

Based upon the above plant sound power levels, predicted construction noise levels for the various works phases are presented below:

TABLE 19 PREDICTED CONSTRUCTION NOISE  $L_{EQ,15MIN}$

| RECEIVERS                                                         | RECOMMENDED HOURS                                                                        | PERIOD | PREDICTED CONSTRUCTION NOISE LEVEL | EXTERNAL NOISE MANAGEMENT LEVEL                              |
|-------------------------------------------------------------------|------------------------------------------------------------------------------------------|--------|------------------------------------|--------------------------------------------------------------|
| Excavation and Demolition Phase                                   |                                                                                          |        |                                    |                                                              |
| Receiver 1-<br>17 Chapman St<br>(~35m from construction)          | Monday Friday 7am to 6pm<br>Saturday 8am to 1pm<br>No work on Sundays or Public Holidays | Day    | 68 dB(A)                           | 55 dB(A) (noise affected)<br>75dB(A) (highly noise affected) |
| Receiver 2-<br>1 Cook Pl<br>(~30m from construction)              |                                                                                          |        | 70 dB(A)                           |                                                              |
| Receiver 3-<br>8 Chapman St<br>(~11m from preschool construction) |                                                                                          |        | 74 dB(A)                           |                                                              |
| Structural Phase                                                  |                                                                                          |        |                                    |                                                              |
| Receiver 1-<br>17 Chapman St<br>(~35m from construction)          | Monday Friday 7am to 6pm<br>Saturday 8am to 1pm<br>No work on Sundays or Public Holidays | Day    | 70 dB(A)                           | 55 dB(A) (noise affected)<br>75dB(A) (highly noise affected) |
| Receiver 2-<br>1 Cook Pl<br>(~30m from construction)              |                                                                                          |        | 72 dB(A)                           |                                                              |
| Receiver 3-<br>8 Chapman St<br>(~11m from preschool construction) |                                                                                          |        | 74 dB(A)                           |                                                              |
| Construction & internal Works Phase                               |                                                                                          |        |                                    |                                                              |
| Receiver 1-<br>17 Chapman St<br>(~35m from construction)          | Monday Friday 7am to 6pm<br>Saturday 8am to 1pm<br>No work on Sundays or Public Holidays | Day    | 72 dB(A)                           | 55 dB(A) (noise affected)<br>75dB(A) (highly noise affected) |
| Receiver 2-<br>1 Cook Pl<br>(~30m from construction)              |                                                                                          |        | 73 dB(A)                           |                                                              |


| RECEIVERS                                                                  | RECOMMENDED HOURS | PERIOD | PREDICTED CONSTRUCTION NOISE LEVEL | EXTERNAL NOISE MANAGEMENT LEVEL |
|----------------------------------------------------------------------------|-------------------|--------|------------------------------------|---------------------------------|
| <b>Receiver 3-<br/>8 Chapman St<br/>(~11m from preschool construction)</b> |                   |        | 74 dB(A)                           |                                 |

NB: Noise levels apply at the property boundary that is most exposed to construction noise, and at a height of 1.5 m above ground level. If the property boundary is more than 30 m from the residence, the location for measuring or predicting noise levels is at the most noise-affected point within 30 m of the residence. Noise levels may be higher at upper floors of the noise affected residence.

## 7.2.1 CONSTRUCTION NOISE MITIGATION MEASURES

- Construction hours will only be during day-time.
- As preschool construction is within close proximity to receivers, time managed use of equipment is required, and it is recommended to perform all pre works/ cutting/ fabrication activities away from this location and only the finals work to be conducted here to minimize construction noise impact.
- Excavation and Demolition phase for the Preschool assumed working on the following time-managed machinery:
  - 80% of the construction time for the Tracked excavator 14t / 66kW
  - 30% of the construction time for the Dumper truck 9T / 75 kW
- Structural phase for the Preschool assumed working on the following time-managed machinery:
  - 40% of the construction time for the Tracked excavator 14t / 66kW
  - 20% of the construction time for the Dumper truck 9T / 75 kW
  - 25% of the construction time for the Mini piling rig (rock bolt) 250mm auger
  - 40% of the construction time for the Concrete pump + cement mixer truck (discharging) 8 T / 350 bar
- Construction and internal works phase for the Preschool assumed working on the following time-managed machinery:
  - 10% of the construction time for the handheld circular saw 3 Kw
  - 30% of the construction time for the handheld cordless nail gun
- Construction site is large and not all machinery is expected to be located at the same distance when assessing to a particular boundary.
- Not all machinery is to be working simultaneously.
- The above estimations are the critical scenario for construction noise.
- Fitout works are expected to be substantially less than shown in the table, assuming noise sources (builders, handheld tools, etc) will be kept inside the new building and shielded from other receivers.

A perimeter hoarding (min 2 m tall, construction density to ensure the noise levels will meet NML levels) will be required as per below, to meet noise levels on critical receivers (including closest school buildings) during excavation and piling phases. This hoarding includes the solid fence (min 1.8 m tall, min construction to ensure the noise levels will meet PNTL levels no gaps between fence panels) installed between the New Preschool building and receiver R3 as per Figure 10Figure 8.



**Acoustic solid fence  
(min. 1.8 m tall)**

### PREDICTED CONSTRUCTION NOISE INSIDE THE SCHOOL

Greenway Park Public School Upgrade and New Public Pre School | Noise & Vibration Impact Assessment Acoustic Report 29

## 7.3 PREDICTED CONSTRUCTION VIBRATION

It is important to note that construction vibration levels depend on several factors, such as: activity, type of machine, geology of the ground and the distance between the affected buildings and the source. Surface works are expected to have a lower vibration impact than ground compacting/breaking works.

For the proposed activity, construction activities likely to cause some vibrations are piling, earthworks, reinstatement works for roads pavement construction and earth compaction, etc.

As per the findings of Geotechnical Investigations by WSP in their report, the topsoil typically comprised of fine to coarse grained clayey sand, overlying and the fill was typically fine to coarse grained clayey sand & sandy gravel, overlying. Based on these findings, we have assumed the soil type to be cohesive for our assessments.

Compliance with vibration limits for building damage is expected based on ensuring ground compacting equipment is selected to adhere to minimum safe working distances. While these magnitudes do not predict cosmetic/structural damage, it is anticipated that human response/comfort would be impacted at these distances.

The current RMS Construction Noise and Vibration Guideline sets safe working distances for vibrating plant and equipment. These are summarised below in Table 20. For this size of works, the use of large hydraulic hammers would not be recommended for these works. Hence it is recommended that the use of smaller rock breakers and handheld jackhammers are used for activity close to the nearest affected residential receivers.

TABLE 20 RMS PLANT VIBRATION SAFE OPERATING DISTANCES - Construction Noise and Vibration Guideline 2016

| PLANT ITEM                    | RATING/DESCRIPTION            | MINIMUM WORKING DISTANCE     |                                              |
|-------------------------------|-------------------------------|------------------------------|----------------------------------------------|
|                               |                               | COSMETIC DAMAGE<br>(BS 7385) | HUMAN RESPONSE<br>(OH&E VIBRATION GUIDELINE) |
| <b>Small Hydraulic Hammer</b> | (300 kg - 5 to 12t excavator) | 2 m                          | 7 m                                          |
| <b>Jackhammer</b>             | Handheld                      | 1 m (nominal)                | 2 m                                          |

Vibration predictions for piling and reinstatement works are included below, using Table E.1 Empirical Predictors for ground-borne vibration arising from mechanized construction works of the BS 5228 – 2.2009-part II Vibration.

TABLE 21 PILING AND REINSTATEMENT WORKS ESTIMATED VIBRATION LEVELS AS PER TABLE E.1 OF THE BS 5228-2.2009

| EQUIPMENT                                                                                                                                    | VIBRATION LEVEL PPV (mm/s) | SOURCE                   |
|----------------------------------------------------------------------------------------------------------------------------------------------|----------------------------|--------------------------|
| <b><u>New GLS Building</u></b><br>Percussive piling, piles at 10 m depth with cohesive soils.<br>distance to closest receiver R2 = 30m       | 0.06 mm/s                  | Table E1. BS 5228-2:2009 |
| <b><u>New Preschool Building</u></b><br>Percussive piling, piles at 10 m depth with cohesive soils.<br>distance to closest receiver R3 = 10m | 0.24 mm/s                  |                          |
| <b><u>Existing School block H</u></b>                                                                                                        | 0.6 mm/s                   |                          |

Notes: These levels were calculated based on the below:

- Piling at 10 m depth with a W factor of 85Kj for percussive piling (no vibratory piling)

- As per the FTA masterplan, geotechnical section, the soil is mainly consisting of fills, hence it would be a soft soil. This means that the above vibration is a conservative value, calculated for cohesive soils.
- For existing school buildings (blocks H and I), vibration levels during piling will be approximately 0.6 mm/s, we recommend previous notification to the school building when piling occurs close to this boundary.

The above levels meet the construction vibration criteria (sensitive structures to vibration, 2.5 mm/s) as per DIN 4150 – 3. These values are not likely going to produce complains from the neighbours and are below all the maximum recommended vibration values as depicted in the criteria section.

## 7.4 GENERAL RECOMMENDATIONS ON CONSTRUCTION NOISE AND VIBRATION MANAGEMENT

Predicted construction noise levels were determined not to exceed the 'Highly Noise Affected' noise levels, which have been specified in the Interim Guide for Construction Noise (ICNG). However, the Interim Guide for Construction Noise (IGCN) list several typical best practice measures which can be used to reduce construction related impacts. In addition, Australian Standards 2436-2010 provides best practice measures to mitigate construction noise and vibration.

The following recommendations should be also considered in the development of a construction noise and vibration management plan for the site, when details of the contractor work methodology become finalised.

### 7.4.1 GENERAL/SITE MANAGEMENT ISSUES

- All employees, contractors and subcontractors are to receive an environmental induction and should instruct all persons at the site with regard to all relevant project specific and standard noise mitigation measures, including but not limited to permissible hours or work, limitation of high noise generating activities, location of nearest affected noise receivers, construction employee parking areas, designated loading/unloading areas and procedures, site opening/closing times (including deliveries) and environmental incident procedures.
- A dedicated person will form a point of contact for dissemination of general information regarding site operations. Contact persons will also be defined to receive comment or complaints from the community.

### 7.4.2 CONSTRUCTION ACTIVITIES AND NOISE MITIGATION

The following general construction noise source control measures may be required:

- No extended construction hours.
- Activities that approach the highly noise affected criteria for the residential receivers to be carried out during times where receivers are less sensitive to noise
- Avoid unnecessary revving of engines and turn off plant that is not being used/required
- Where possible organise the site so that delivery trucks and haulage trucks only drive forward to avoid the use of reversing alarms
- Where possible, avoid using tonal reverse alarm outside standard construction hours
- Organise and schedule the equipment operations to limit the noisiest machines operating simultaneously
- Site set up/ movement of plant / delivery of material/ waste removal to site should generally be restricted to day period
- Truck drivers are to be informed of site access routes, acceptable delivery hours and must minimise extended periods of engine idling
- Ensure there is no unnecessary shouting or loud stereo/radios on site. There must be no dropping of metal from heights, throwing of metal items or slamming of doors
- Use less noise intensive equipment where reasonable and feasible
- Where practical fixed plant should be positioned as far as possible from the sensitive receivers
- Use temporary site buildings and material stockpile as noise barrier

## 8 NOISE MITIGATION STRATEGIES

This section compiles the proposed recommended treatments and strategies mentioned throughout the report to mitigate noise from the activity.

TABLE 22: PROPOSED NOISE MITIGATION STRATEGIES

| STAGE | MITIGATION MEASURES                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | REASON FOR MITIGATION MEASURE                                                | SECTION OF REPORT |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------|-------------------|
| D & O | <ul style="list-style-type: none"> <li>The PA system will be for voice announcements only (no music)</li> <li>Speakers to be located away from the school boundary and oriented away from sensitive receivers.</li> <li>The PA system use to be limited to school hours only (Preferably only between 7 am 6 pm)</li> <li>This system should have installed sound power level noise limiting devices to adjust the speakers if needed.</li> </ul>                                                                                                                                           | Minimise PA noise and meet PNTL levels to nearest receivers.                 | 6.1               |
| D & O | <ul style="list-style-type: none"> <li>For carpark it is required a minimum 1.5m high solid barrier along the carparks to provide noise reduction to the receivers at Chapman St and Watts Pl, (min construction density to ensure the noise levels will meet PNTL levels).</li> <li>carpark operates during daytime with a limited capacity during evening time (6pm to 10 pm), no operations after 10pm.</li> <li>Installation of visual signage to discourage raised voices in the carpark and minimal use of the carpark during the evening and night need to be introduced.</li> </ul> | Minimise carpark noise and meet PNTL levels to nearest receivers.            | 6.2               |
| D     | <ul style="list-style-type: none"> <li>We understand that a solid fence (min 1.8 m tall, min construction density to ensure the noise levels will meet PNTL levels, no gaps between fence panels) will be installed between the New Preschool building and receiver R3.</li> </ul>                                                                                                                                                                                                                                                                                                          | Minimise carpark noise / mechanical plant noise and meet PNTL levels to R3.  | 6.3.1             |
| D     | <ul style="list-style-type: none"> <li>Mechanical plant (such as outdoor units and fans) will need to be acoustically treated as per Section 6.3.1 of the NVIA prepared by NDY dated 27 March 2025</li> <li>Alternatively, as the design is yet to be finalised, mechanical plant will need to be further analysed and treated as per the acoustic design report prior to construction.</li> </ul>                                                                                                                                                                                          | To minimise plant noise emissions and meet PNTL levels to nearest receivers. | 6.3.1             |
| D / O | <ul style="list-style-type: none"> <li>Mechanical plant should only be operational during daytime (7:00 am – 6:00pm).</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                            | To minimise plant noise emissions and meet PNTL levels to nearest receivers. | 6.3.1             |

| STAGE | MITIGATION MEASURES                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | REASON FOR MITIGATION MEASURE                                                          | SECTION OF REPORT |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------|-------------------|
|       | <ul style="list-style-type: none"> <li>If the mechanical plant is to operate outside these hours, the operating modes / speeds will need to be further analysed (when the information is made available) in an acoustic design report.</li> </ul>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |                                                                                        |                   |
| C     | <ul style="list-style-type: none"> <li>Equipment time management per construction phase need to be as per Section 7.2.1 of the NVIA prepared by NDY dated 2025.</li> <li>A construction perimeter hoarding will need to be built (min height 2 m, min construction density to ensure the noise levels will meet NML levels). As per Figure 11 of the NVIA prepared by NDY dated 27 March 2025.</li> <li>Best practices on construction noise and vibration management are as per section 7.4 of the NVIA prepared by NDY dated 27 March 2025.</li> <li>Alternatively, as the construction methodology is yet to be finalised, construction activities will need to be further analysed and effects mitigated as per a Construction Noise and Vibration Management Plan prior to construction.</li> </ul> | To minimise construction noise and vibration levels and meet NML to nearest receivers. | 7.0, 7.2.1, 7.4   |

Notes:

- D: Design
- O: Operation
- C: construction

## 9 EVALUATION OF ENVIRONMENTAL IMPACTS

The Noise and vibration impact assessment prepared by NDY confirms that the activity will not have a 'significant affect on the environment' (refer to Section 5.7 of the EP&A Act).

Noise and vibration impacts of the activity can be adequately mitigated or minimised through the required mitigation measures included in this report.

# CONTACT US

## AUSTRALIA

### ADELAIDE

T: +61 8 8290 6800  
E: [adelaide@ndy.com](mailto:adelaide@ndy.com)

### BRISBANE

T: +61 7 3120 6800  
E: [brisbane@ndy.com](mailto:brisbane@ndy.com)

### CANBERRA

T: +61 2 6295 1788  
E: [canberra@ndy.com](mailto:canberra@ndy.com)

### GOLD COAST

T: +61 7 5512 1235  
E: [goldcoast@ndy.com](mailto:goldcoast@ndy.com)

### MELBOURNE

T: +61 3 9862 6800  
E: [melbourne@ndy.com](mailto:melbourne@ndy.com)

### PERTH

T: +61 8 9281 6800  
E: [perth@ndy.com](mailto:perth@ndy.com)

### SYDNEY

T: +61 2 9928 6800  
E: [sydney@ndy.com](mailto:sydney@ndy.com)

## CANADA

### VANCOUVER

T: +1 604 734 9338  
E: [vancouver@ndy.com](mailto:vancouver@ndy.com)

## NEW ZEALAND

### AUCKLAND

T: +64 9 307 6596  
E: [auckland@ndy.com](mailto:auckland@ndy.com)

### WELLINGTON

T: +64 4 471 0151  
E: [wellingtonadmin@ndy.com](mailto:wellingtonadmin@ndy.com)

## UNITED KINGDOM

### LONDON

T: +44 20 7553 9494  
E: [london@ndy.com](mailto:london@ndy.com)

## IRELAND

### DUBLIN

T: +353 1 264 6995  
E: [dublin@ndy.com](mailto:dublin@ndy.com)

To find out more about NDY go to  
**[ndy.com](https://www.ndy.com)** or follow us on LinkedIn



**CONFIDENTIAL INFORMATION:** This document is given with the understanding that the information within is private. Please keep it confidential and don't share with anyone else. Take proper care to make sure that others can't see or access this document. It's meant only for you.

**DISCLAIMER OF LIABILITY:** The information in this document is provided under direction of the client and follows their instructions. Any third party reviewing the content should make their own assessment on whether the information is appropriate to them. NDY makes no assurance the information meets the needs of a third party and does not accept liability for any loss or damage incurred by third parties as a result of using the information.

**COPYRIGHT © NDY Group 2025:** No part of this document can be copied or sent without written permission from NDY. All rights are reserved.