



CONSULTANCY
ARBORICULTURE
PLANT PATHOLOGY

**Arboricultural Impact Assessment
& Tree Protection Report**

REF: L&Co24012 | 3 April 2025 | v1.3

SITE ADDRESS | Greenway Public School, Wyattville Dr, Carnes Hill NSW

PREPARED FOR | The Department of Education (DoE)

PREPARED BY |

Dr Matthew Laurence

BSc. (Hons)

PhD (Plant Pathology)

Grad Cert (Arboriculture)

Ms Emma Clark

BA (Hons)

info@laurenceco.com.au

0404 282 825

ABN: 61 625 300 530

www.laurenceco.com.au

1.0	EXECUTIVE SUMMARY 	2
3.0	RESULTS 	4
4.0	ARBORICULTURAL IMPACT ASSESSMENT 	5
5.0	REFERENCES 	8
6.0	APPENDIX 1 METHODOLOGY	9
7.0	APPENDIX 2 TREE ASSESSMENT SCHEDULE	13
8.0	APPENDIX 3 TREE LOCATION PLAN.....	20
9.0	APPENDIX 4 PROPOSED DEVELOPMENT PLANS	24
10.0	APPENDIX 5 ARBORICULTURAL IMPACT ASSESSMENT PLANS.....	40
11.0	APPENDIX 6 TREE RETENTION/REMOVAL PLAN	53
12.0	APPENDIX 7 TREE PROTECTION PLAN	56
13.0	APPENDIX 8 TYPICAL TREE PROTECTION DETAIL	59
14.0	APPENDIX 9 TREE PROTECTION SPECIFICATION	62
15.0	APPENDIX 10 MITIGATION MEASURES.....	65
16.0	APPENDIX 11 PLATES.....	66
17.0	APPENDIX 11 LIMITATIONS & DISCLAIMERS	67

1.0 EXECUTIVE SUMMARY |

- 1.1 This Arboricultural Impact Assessment and Tree Protection report has been prepared to accompany a Review of Environmental Factors (REF) prepared for the Department of Education (DoE) relating to upgrades to Greenway Park Public School (the development) under Part 5 of the Environmental Planning and Assessment Act 1979 (EP&A Act) and State Environmental Planning Policy (Transport and Infrastructure) 2021 (SEPP TI).
- 1.2 This document has been prepared in accordance with the Guidelines for Division 5.1 assessments – Consideration of environmental factors for health services facilities and schools, October 2024 (the Guidelines) by the Department of Planning, Housing and Infrastructure. This report examines and takes into account the relevant environmental factors in the Guidelines and Section 170, Section 171 and Section 171A of the Environmental Planning and Assessment Regulations 2021 (EP&A Regulation).
- 1.3 A total of sixty (60) trees were assessed that were a mix of Australian native and exotic species.
- 1.4 In total, eleven (11) trees will need to be removed to accommodate the proposed activities. Details on impacts as follows.
- 1.5 The supplied plans show no works are proposed within the TPZs of Trees 1, 31, 32, 34, 35, 36, 37, 41, 42, 43, 47, 49, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 66, 67, 68, 69, 70, 72, 73, 74, 76, 77, 81, 101, 102, 104 & 106 and the trees can be retained. However, the tree protection measures outlined in this report should be implemented to avoid indirect impacts.
- 1.6 The proposed GLS building, Early Learning Centre and trenching activities represent a *Minor Encroachment* (as defined by AS4970) on Trees 39, 45, 49, 65, 82 & 103. However, a minor encroachment is considered acceptable by the standard when it is compensated for elsewhere and contiguous within the TPZ, as in the current cases. Further, the tree protection measures outlined in this report will reduce the likelihood of negative impacts on Trees 39, 45, 49, 65, 82 & 103 and the trees can be retained.
- 1.7 The proposed landscaping activities are within the TPZ/SRZ of Trees 30, 33, 38, 40, 46 & 80 and represent a *Major Encroachment* (as defined by AS4970). However, the proposed activities can be constructed using either tree sensitive construction methods or installed at or above grade and the trees can be retained if the tree sensitive construction methods and protection measures outlined in this report are implemented under supervision of the Project Arborist. The activities are therefore considered acceptable under the Australian Standard AS4970, Clause 3.3.4.
- 1.8 The proposed activities are within the TPZ/SRZs of Trees 44, 50, 62, 71, 75, 78 & 79 and also represents a *Major Encroachment* (as defined by AS4970). However, these trees will need to be removed as the TPZ encroachment is too large for their long-term viability, based on a consideration of their health, structure and the size of the encroachment. Trees 50, 71, 75 & 78 Moderate Landscape Significance Values and Trees 44, 62 & 79 High Landscape Significance Values.
- 1.9 Trees 48, 63, 64 & 105 are within the proposed building footprint and will need to be removed. These trees were assigned Low, High, Low and Moderate Landscape Significance Values.
- 1.10 No Construction Management Plan (CMP) was provided and the impact from site access could not be assessed. The impacts from the CMP must be reviewed by the Project Arborist prior to the issue of the Construction Certificate to minimise indirect impacts on the tree population.

2.0 INTRODUCTION |

2.1 Background

- 2.1.1 This Arboricultural Impact Assessment and Tree Protection report has been prepared to accompany a Review of Environmental Factors (REF) prepared for the Department of Education (DoE) relating to upgrades to Greenway Park Public School (the development) under Part 5 of the Environmental Planning and Assessment Act 1979 (EP&A Act) and State Environmental Planning Policy (Transport and Infrastructure) 2021 (SEPP TI).
- 2.1.2 This document has been prepared in accordance with the Guidelines for Division 5.1 assessments – Consideration of environmental factors for health services facilities and schools, October 2024 (the Guidelines) by the Department of Planning, Housing and Infrastructure. This report examines and takes into account the relevant environmental factors in the Guidelines and Section 170, Section 171 and Section 171A of the Environmental Planning and Assessment Regulations 2021 (EP&A Regulation).
- 2.1.3 In preparing this report, the author is aware of and has considered the objectives of the Liverpool City Council's- Liverpool Development Control Plan Part 2: Tree Preservation (2008), Liverpool Local Environment Plan (2008); Liverpool City Council Tree Management Policy (2016), Australian Standard 4970 Protection of Trees on Development Sites (2009), Australian Standard 4373 Pruning of Amenity Trees (2007) and Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal Work (2016).
- 2.1.4 Further methodology used in the preparation of this report is detailed in Appendix 1.
- 2.1.5 This Arboricultural Impact Assessment was based on an assessment of the following supplied documentation/plans only (Appendix 4):

- Existing Site Plan Prepared by Fulton Trotter Architects. Dated 14.03.2025
- Demolition Site Plan Prepared by Fulton Trotter Architects. Dated 06.03.2025
- Proposed Site Plan Prepared by Fulton Trotter Architects. 14.03.2025
- External Works Plan Prepared by Fulton Trotter Architects. Dated 14.03.2025.
- External Works Plan Preschool Prepared by Fulton Trotter Architects. Dated 14.03.2025.
- Proposed Preschool Carpark Prepared by Fulton Trotter Architects. Dated 14.03.2025.
- Landscape Plan Final State Prepared by Ground Ink Landscape Architects. Dated 31.03.2025
- Landscape Plan Early Learning Prepared by Ground Ink Landscape Architects. Dated 20.02.2025
- Bulk Earthworks Plan Prepared by Meinhardt. Dated 13.03.2025
- Bulk Earthworks Plan Sheet 1 Prepared by Meinhardt. Dated 14.03.2025
- Bulk Earthworks Plan Sheet 2 Prepared by Meinhardt. Dated 14.03.2025
- Civil Siteworks Plan Prepared by Meinhardt. Dated 13.03.2025
- Civil Siteworks Plan Sheet 1 Prepared by Meinhardt. Dated 14.03.2025
- Electrical Services Site Plan Prepared by NDY Consultants. Dated 28.02.2025
- Hydraulic Services Existing Site Plan & Demolition Prepared by ACOR. Dated 18.03.2025
- Hydraulic Services Proposed Site Plan & Demolition Prepared by ACOR. Dated 18.03.2025
- Topographical Survey and Utility Mapping in Accordance with AS4588.1-2019 Prepared by Astrea. Dated 18.10.2023

2.2 The Proposal

2.2.1 The proposed activity for the Greenway Park Public School upgrade includes:

2.2.2 Demolition/ earthworks:

- Demolish part of boundary fence on Chapman Street for new vehicular crossover;
- Demolish parts of boundary fence on Chapman Street for new gates;
- Demolish shade structure and associated concrete slab and footpath;
- Demolish footpaths;
- Tree removal;
- Trenching for underground services; and

- Earthworks associated with new buildings and landscaping

2.2.3 Construction:

- Construction and operation of single storey classroom building with associated covered walkways;
- Construction and operation of a new preschool building, including covered walkways, new carpark (12 spaces and one (1) accessible space) and vehicular crossover to Chapman Street;
- Installation of artwork on Block H and Block J façades, as well as a preschool retaining wall;
- Laying of services within trenches;
- New pedestrian entry points;
- Fencing and gates;
- Underground OSD tanks;
- Rainwater tanks;
- Shed for preschool;
- Outdoor play equipment for the preschool;
- New fire hydrant booster & associated building services connections;
- Retaining walls associated with the preschool;
- Signage;
- Landscaping; and Associated earthworks

3.0 RESULTS |

3.1 The Site

3.1.1 The activity site is located on Wyattville Drive, West Hoxton and is legally described as:

- Lot 11 DP 858025; and
- Lot 20 DP 867282

3.1.2 Greenway Park Public School is located on the south eastern side of Chapman Street and the north eastern side of Wyattville Drive. The surrounding context of the site is predominantly low density residential as well as a childcare centre to the north.

Figure 1 is an aerial photograph of the site.



3.2 The Trees

3.2.1 A Visual Tree Assessment (VTA) (Mattheck & Breloer, 2003) has been undertaken on trees growing within the site to determine their health and structural condition (Appendix 2). A full VTA of trees located outside of the site boundaries was not undertaken due to limited access. The species and trunk diameter were recorded for the purposes of determining Tree Protection Zone (TPZ) and Structural Root Zone (SRZ) calculations only. The distance of each tree from the site boundary is an approximation due to limited access.

3.2.2 The Australian Standard 4970: *Protection of Trees on Development Sites* (2009) Clause 2.3.2, requires the allocation of a Tree Retention Value. This value is based on the Useful Life Expectancy (ULE) and Landscape Significance, which considers the tree's health, structural condition and site suitability. The Retention Value does not consider any proposed development works and is not a schedule for tree retention or removal. The trees have been allocated one of the following Retention Values:

- Priority for Retention
- Consider for Retention
- Consider for Removal
- Priority for Removal

3.2.3 The Australian Standard 4970: *Protection of Trees on Development Sites* (2009) also requires the calculation of the Tree Protection Zone (TPZ) and Structural Root Zone (SRZ) for each tree (Appendix 1).

3.2.4 A total of sixty (60) trees and group trees were assessed which were a mix of Australian native and exotic species.

3.2.5 A search of the BioNet Atlas of NSW Wildlife Database was undertaken in March 2025. No individual threatened tree species that were listed within this database for the area were identified during the current field investigations of the site. The ecological significance and habitat value of the trees has not been assessed and is beyond the scope of this report.

3.2.6 Trees 1, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 101, 102, 103, 105 & 106 were within the site boundary and covered by the council's tree management controls.

3.2.7 Tree 104 is exempt from the council's tree management controls based on dimensions/species and can be removed without Council consent.

4.0 ARBORICULTURAL IMPACT ASSESSMENT |

4.1 **Trees 1, 31, 32, 34, 35, 36, 37, 41, 42, 43, 47, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 66, 67, 68, 69, 70, 72, 73, 74, 76, 77, 81, 101, 102, 104 & 106**

4.1.1 Trees 1, 31, 32, 34, 35, 36, 37, 41, 42, 43, 47, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 66, 67, 68, 69, 70, 72, 73, 74, 76, 77, 81, 101, 102, 104 & 106 are not directly impacted by the proposed activities. Refer to Appendix 2 for species identifications and further details.

4.1.2 The following TPZ protection must be installed to avoid indirect impacts.

4.1.3 TPZ fencing should be installed prior to any site works (including demolition) and remain in place for the duration of the demolition and construction processes.

4.1.4 The area within the TPZ fencing should be mulched to a depth of 50mm with a non-toxic product (i.e. woodchips) with no fines.

4.1.5 Coir logs should be installed on the perimeter of the TPZ fencing to prevent runoff from the building works into the TPZ.

4.1.6 Materials, waste storage and temporary services should not be located within the TPZ fenced area. If works are required within the TPZ fenced area, then they should be supervised by the Project Arborist.

4.1.7 The tree protection measures must be inspected by the Project Arborist prior to the start prior of site works, including demolition.

4.1.8 Refer to AS4970 and Appendices 5, 6, 7, 8 & 9 for further details for further details.

4.2 **Trees 39, 45, 49, 65, 82 & 103**

4.2.1 The proposed GLS building, Early Learning Centre and trenching activities are within the TPZs of Trees 39, 45, 49, 65, 82 & 103. The overall TPZ encroachments ranged from 1% to 9%, which represents a *Minor Encroachment* as defined by AS4970 and is considered acceptable by the standard when it is compensated for elsewhere and contiguous within the TPZ, as in the current cases.

4.2.2 Given the good physiological condition of the trees and the size of the encroachment, the proposed activities can be accommodated without affecting the long term structural and physiological viability of Trees 39, 45, 49, 65, 82 & 103 if the following tree sensitive construction methods and protection measures are carefully implemented under the supervision of the Project Arborist

4.2.3 TPZ fencing should be installed prior to any site works (including demolition) and remain in place for the duration of the demolition and construction processes.

4.2.4 The area within the TPZ fencing should be mulched to a depth of 50mm with a non-toxic product (i.e. woodchips) with no fines.

4.2.5 Coir logs should be installed on the perimeter of the TPZ fencing to prevent runoff from the building works into the TPZ.

- 4.2.6 Materials, waste storage and temporary services should not be located within the TPZ fenced area. If works are required within the TPZ fenced area, then they should be supervised by the Project Arborist.
- 4.2.7 The tree protection measures must be inspected by the Project Arborist prior to the start prior of site works, including demolition.
- 4.2.8 Refer to AS4970 and Appendices 5, 6, 7, 8 & 9 for further details for further details.
- 4.3 **Trees 30, 33, 38, 40, 46 & 80**
- 4.3.1 The proposed landscaping and trenching activities are within the TPZ/SRZ of Trees 30, 33, 38, 40, 46 & 80. Refer to Appendix 2 for species identifications and further details.
- 4.3.2 The TPZ encroachment for the proposed grade changes associated with the landscaping was estimated to be 14%, 12%, 16%, 13% and 16% for Trees 30, 38, 40, 46 & 80 respectively and represents a *Major Encroachment* as defined by AS-4970.
- 4.3.3 The proposed fencing transects the TPZ of Tree 33 and was within the SRZ. Works within the SRZ represent a *Major Encroachment* as defined by AS-4970 as root severance within the SRZ can lead to the destabilisation of the tree. The overall TPZ encroachment was estimated to be 22% and also represents a *Major Encroachment* as defined by AS-4970.
- 4.3.4 Given the size and location of the proposed encroachment, the proposed activities represent a significant risk to the trees long term structural and physiological viability. However, However, Clause 3.3.4 of AS-4970 does allow for major encroachments if design factors (e.g. tree sensitive construction methods) are used to minimise negative impacts.
- 4.3.5 Trees 30, 33, 38, 40, 46 & 80 can be retained under Clause 3.3.4 of AS-4970 if the following tree sensitive construction methods and protection measures are carefully implemented under the supervision of the Project Arborist. Significant departures from the detailed tree sensitive construction methods and protection measures are likely to result in a shortened ULE and/or tree removal.
- 4.3.6 The proposed grade changes associated with turfing should be avoided within the TPZ of Trees 30 & 33.
- 4.3.7 The proposed paving within the TPZ of Tree 80 must be installed at or above grade (including sub-base) using a permeable material.
- 4.3.8 The fence within the SRZ of Tree 33 must be constructed using the following tree sensitive methods. The fence footings must be minimal or span the SRZ. The locations for the footings must be hand excavated and placed around structural roots (greater than 40mmØ). The activities must be supervised by the Project Arborist.
- 4.3.9 The following TPZ protection must be installed to avoid indirect impacts.
- 4.3.10 TPZ fencing should be installed prior to any site works (including demolition) and remain in place for the duration of the demolition and construction processes.
- 4.3.11 The area within the TPZ fencing should be mulched to a depth of 50mm with a non-toxic product (i.e. woodchips) with no fines.
- 4.3.12 Coir logs should be installed on the perimeter of the TPZ fencing to prevent runoff from the building works into the TPZ.
- 4.3.13 Materials, waste storage and temporary services should not be located within the TPZ fenced area. If works are required within the TPZ fenced area, then they should be supervised by the Project Arborist.
- 4.3.14 The tree protection measures must be inspected by the Project Arborist prior to the start prior of site works, including demolition.
- 4.3.15 Refer to AS4970 and Appendices 5, 6, 7, 8 & 9 for further details for further details.
- 4.4 **Trees 44, 50, 62, 71, 75, 78 & 79**
- 4.4.1 Trees 44, 50, 62, 71, 75, 78 & 79 were assigned a Low, Moderate and High Landscape Significance Values. Refer to Appendix 2 for species identifications and further details.
- 4.4.2 The proposed footpath activities associated with the GLS are within the TPZ/SRZ of Trees 44 & 50. Works within the SRZ represent a *Major Encroachment* as defined by AS-4970 as root severance within the SRZ can lead to the destabilisation of the tree. The overall TPZ encroachment was estimated to be 27% and 23%, respectively and also represents a *Major Encroachment* as defined by AS-4970.
- 4.4.3 The proposed carpark and hydraulic activities associated with the Early Learning Centre are within the TPZ/SRZ of Trees 62, 71, 75, 78 & 79. The overall TPZ encroachment was estimated to be 27%, 63% and 27%, 18% and 23% respectively and also represents a *Major Encroachment* as defined by AS-4970.
- 4.4.4 Given the size and location of the encroachments, the long term structural and physiological viability of Trees 44, 50, 62, 71, 75, 78 & 79 is highly likely to be compromised by the proposed encroachment and the trees will need to be removed to accommodate the activities.
- 4.4.5 Refer to Appendix 5 for further detail.

- 4.4.6 Removal and replacement with a healthy advanced size specimen would replace the loss of amenity within a medium to long timeframe.
- 4.5 **Trees 48, 63, 64 & 105**
- 4.5.1 Trees 48, 63, 64 & 105 were assigned Low, High, Low and Moderate Landscape Significance Values. Refer to Appendix 2 for species identifications and further details.
- 4.5.2 Trees 48, 63, 64 & 105 are within the footprint of the proposed carpark and associated pathway and will need to be removed to accommodate the activities.
- 4.5.3 Removal and replacement with a healthy advanced size specimen would replace the loss of amenity within a medium to long timeframe.
- 4.6 **Removal & Replacement Planting**
- 4.6.1 Removal works should be carried out by a practising arborist. The practising arborist should hold a minimum qualification equivalent (using Australian Qualifications Framework) of Level 3 or above in arboriculture or its recognised equivalent. The practising arborist should have a minimum of 3 years of practical experience. Removal works should be undertaken in accordance with the Australian Standard 4373: Pruning of Amenity Trees (2007), Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal Work (2016) and other applicable legislation and codes.
- 4.6.2 Replacement tree planting should be provided when trees are removed. Replacement trees should be supplied as advanced size stock to help offset the loss of amenity resultant from the tree removals.
- 4.6.3 Replacement planting should be supplied in accordance with Australian Standard 2303: Tree Stock for Landscape Use (2015).



Dr Matthew Laurence

Director

BSc. (Hons), PhD (Plant Pathology), GradCert (Arboriculture)

Institute of Australian Consulting Arboriculturists (Accredited Member – ACM0502016)

Australasian Plant Pathology Society

ResearchGate Profile - https://www.researchgate.net/profile/Matthew_Laurence

5.0 REFERENCES |

Mattheck & Breloer (2003), *The Body Language of Trees – A Handbook for Failure Analysis*.

NSW Office of Environment and Heritage's Atlas of NSW Wildlife (2011), *BioNet Atlas of NSW Wildlife*.

Standards Australia (2009) Protection of Trees on Development Sites AS4970.

Standards Australia (2007) Pruning of Amenity Trees AS4373.

Standards Australia (2015) Tree Stock for Landscape Use AS2303.

6.0 APPENDIX 1 | METHODOLOGY

- 6.1 This report was based on data from a site inspection conducted on the 02.11.2023 & 20.02.2025. The recommendations in this report are based on and limited to observations from these site inspections.
- 6.2 The subject tree(s) was assessed using the Visual Tree Assessment methodology described in *The Body Language of Trees – A Handbook for Failure Analysis* (Mattheck et al., 2003). Subject trees were assessed from the ground only to provide an Arboricultural Impact Assessment and Tree Protection Report report. No internal diagnostic testing was undertaken as part of this assessment. Trees outside the subject site were assessed from the property boundaries only.
- 6.3 The dimensions of the subject tree(s) are an approximation only.
- 6.4 The location of the subject tree(s) was determined from the location plan provided. Trees not shown on this plan have been plotted in their approximate location only.
- 6.5 Tree Protection Zones & Structural Root Zones for the subject tree(s) was based on methods outlined in Australian Standard 4970: *Protection of Trees on Development Sites* (2009).
- 6.6 The health of the subject tree(s) was determined by assessing:
- Foliage size and colour
 - Pest and disease infestation
 - Extension growth
 - Crown density
 - Deadwood size and volume
 - Presence of epicormic growth
- 6.7 The structural condition of the subject tree(s) was assessed by:
- Visible evidence of structural defects or instability
 - Evidence of previous pruning or physical damage
- 6.8 The Useful Life Expectancy (ULE) is used to estimate a tree's longevity in its growing environment. The ULE is based on a tree's species, health, structural condition and site suitability. The tree(s) has been allocated one of the following ULE categories (modified from Barrell, 2001):
- 40 years +
 - 15-40 years
 - 5-15 years
 - Less than 5 years
- 6.9 The Landscape Significance is based on a qualitative assessment of a tree's cultural, environmental and aesthetic value. This provides a relative measure of a tree's Landscape Significance and can be used to determine its Retention Value. Trees are rated under the following categories:
- Very High
 - High
 - Moderate
 - Low
 - Insignificant

LANDSCAPE SIGNIFICANCE	DESCRIPTION
VERY HIGH	The subject tree is listed as a Heritage Item under the Local Environmental Plan with a local or state level of significance.
	The subject tree is listed on Council's Significant Tree Register.
	The subject tree is a remnant tree.
HIGH	The subject tree creates a 'sense of place' or is considered 'landmark' tree.
	The subject tree is of local, cultural or historical importance or is widely known.
	The subject tree has been identified by a suitably qualified professional as a species scheduled as a Threatened or Vulnerable Species or forms part of an Endangered Ecological Community associated with the subject site, as defined under the provisions of the Threatened Species Conservation Act 1995 (NSW) or the Environmental Protection and Biodiversity Conservation Act 1999.
	The subject tree is known to provide habitat to a threatened species.
	The subject tree is an excellent representative of the species in terms of aesthetic value.
	The subject tree is of significant size, scale or makes a significant contribution to the canopy cover of the locality.
	The subject tree forms part of the curtilage of a heritage item with a known or documented association with that item.
MODERATE	The subject tree makes a positive contribution to the visual character or amenity of the area.
	The subject tree provides a specific function such as screening or minimising the scale of a building.
	The subject tree has a known habitat value.
	The subject tree is a good representative of the species in terms of aesthetic value.
LOW	The subject tree is an environmental pest species or is exempt under the provisions of the local Council's Tree Management Controls.
	The subject tree makes little or no contribution to the amenity of the locality.
	The subject tree is a poor representative of the species in terms of aesthetic value.
INSIGNIFICANT	The subject tree is declared a Noxious Weed under the Noxious Weeds Act.

The above table was provided by Anna Hopwood of TreeIQ™ and was modified from the Earthscape Criteria for Assessment of Landscape Significance.

6.10 The Retention Value is based on a tree's ULE and Landscape Significance. The subject tree(s) has been allocated one of the following Retention Values:

- Priority for Retention
- Consider for Retention
- Consider for Removal
- Priority for Removal

ULE	LANDSCAPE SIGNIFICANCE				
	VERY HIGH	HIGH	MODERATE	LOW	INSIGNIFICANT
40 years +	Priority for Retention	Priority for Retention		Consider for Removal	Priority for Removal
15-40 years		Priority for Retention	Consider for Retention		
5-15 years	Consider for Retention				
Less than 5 years	Consider for Removal	Priority for Removal			

The above table was provided by Anna Hopwood of TreeIQ™

- 6.11 The Tree Protection Zone (TPZ) is the area above and below ground required to preserve the vigour and long-term viability of the tree. The TPZ is based on scientific research and is generally considered by the arboricultural industry as the area required to provide adequate tree protection during construction. The TPZ is the primary means of protecting trees on development sites (Australian Standard 4970: *Protection of Trees on Development Sites*, 2009).
- 6.12 Works within the TPZ should be avoided. However, *Minor Encroachments*, defined in AS4970 as less than 10% of the TPZ area, are considered acceptable when it is compensated for elsewhere and contiguous within the TPZ. A *Major Encroachment*, defined in AS4970 as greater than 10% of the TPZ area or within the Structural Root Zone (SRZ), may require root investigations by non-destructive methods and tree sensitive construction methods.
- 6.13 The TPZ is the area within a circle that is centred on the trunk. The radius of the TPZ is calculated by the following formula:

$$TPZ = DBH \times 12$$

where

DBH= Diameter at Breast Height (1.4m)

- 6.14 The SRZ is the minimum area around the base of the tree required for the tree's stability. The SRZ only relates to tree stability and not the vigour and long-term viability of the tree.
- 6.15 The SRZ is the area within a circle that is centred on the trunk. The radius of the SRZ is calculated by the following formula:

$$SRZ = (D \times 50)^{0.42} \times 0.64$$

where

D = Trunk diameter (m) above the root buttress

- 6.16 Encroachment into SRZ (i.e. severance of structural roots >25mmØ) may lead to the destabilisation of the tree and the long-term viability must be demonstrated in such cases. This may require root investigations by non-destructive methods.
- 6.17 For further details on the TPZ and SRZ please refer to Australian Standard 4970: *Protection of Trees on Development Sites* (2009).

7.0 APPENDIX 2 | TREE ASSESSMENT SCHEDULE

Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m ²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
1	<i>Malus sp.</i> (Crab Apple)	4	4	100	2	13	1.5	Good	Good	Mature	5-15	Low	Consider for Removal	Small (<25mmØ) deadwood in moderate volumes.	No Encroachment (Retain)
30	<i>Corymbia maculata</i> (Spotted Gum)	18	8	600	7	163	2.8	Good	Fair	Mature	15-40	High	Priority for Retention	Co-dominant inclusions, major. Wound(s), early signs of decay. Trunk cavity(s), minor. Structures within SRZ. Adaptive growth.	14.1% (TPZ – Retain)
31	<i>Corymbia maculata</i> (Spotted Gum)	12	5	300	4	41	2.1	Good	Fair	Semi-mature	5-15	Moderate	Consider for Retention	Crown density 50-75%. Co-dominant inclusions, major. Structures within SRZ. Adaptive growth.	No Encroachment (Retain)
32	<i>Olea europaea var. europea</i> (European Olive)	4	4	300	4	41	2.1	Good	No access to base. No rating.	Mature	5-15	Low	Consider for Removal		No Encroachment (Retain)
33	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	15	6	500	6	113	2.6	Good	Good	Semi-mature	15-40	Moderate	Consider for Retention	Small (<25mmØ) deadwood in moderate volumes.	22% (SRZ – Retain)
34	<i>Melaleuca stypheloides</i> (Prickly Leaved Paperbark)	5	3	300	4	41	2.1	Good	No access to base. No rating.	Mature	5-15	Low	Consider for Removal		No Encroachment (Retain)
35	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	5	2	100	2	13	1.5	Fair	No access to base. No rating.	Semi-mature	5-15	Low	Consider for Removal		No Encroachment (Retain)
36	<i>Casuarina glauca</i> (Swamp She Oak)	12	4	300	4	41	2.1	Good	No access to base. No rating.	Mature	5-15	Moderate	Consider for Retention	Multiple stems Co-dominant inclusions, minor.	No Encroachment (Retain)

Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m ²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
37	<i>Corymbia maculata</i> (Spotted Gum)	17	8	500	6	113	2.6	Good	Good	Mature	15-40	High	Priority for Retention	Small (<25mmØ) deadwood in low volumes. Structures within SRZ.	No Encroachment (Retain)
38	<i>Casuarina glauca</i> (Swamp She Oak)	16	4	325	4	48	2.1	Fair	Good	Late Mature	5-15	Moderate	Consider for Retention	Crown density 25-50%. Small (<25mmØ) deadwood in high volumes. Wound(s), early signs of decay.	12.1% (TPZ – Retain)
39	<i>Eucalyptus</i> sp. (Gum tree)	16	7	520	6	122	2.6	Good	Poor	Mature	5-15	High	Consider for Retention	Crown density 75-95%. Small (<25mmØ) epicormic growth Co-dominant inclusions, major. Wound(s), early signs of decay. Trunk cavity(s), major.	0.8% (Retain)
40	<i>Casuarina glauca</i> (Swamp She Oak)	15	4	300	4	41	2.1	Good	Good	Mature	15-40	Moderate	Consider for Retention		16.2% (TPZ – Retain)
41	<i>Casuarina glauca</i> (Swamp She Oak)	6	3	125	2	13	1.5	Good	Good	Semi-mature	5-15	Low	Consider for Removal		No Encroachment (Retain)
42	<i>Casuarina glauca</i> (Swamp She Oak)	15	4	266	3	32	2.0	Good	Fair	Mature	15-40	Moderate	Consider for Retention	Co-dominant inclusions, minor. Adaptive growth.	No Encroachment (Retain)
43	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	400	5	72	2.3	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)
44	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	17	6	400	5	72	2.3	Fair	Fair	Late Mature	5-15	High	Consider for Retention	Crown density 50-75%. Previously crown lifted. Wound(s), early signs of decay. Trunk cavity(s), major. Order branch cavity, major.	47.8% (SRZ - Remove)

Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m ²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
45	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	14	4	250	3	28	1.9	Good	Good	Semi-mature	5-15	Moderate	Consider for Retention	Small (<25mmØ) epicormic growth in low volumes.	4% (Retain)
46	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	18	7	425	5	82	2.4	Good	Good	Mature	15-40	Moderate	Consider for Retention	Crossing branches. Co-dominant inclusions, minor.	12.6% (TPZ – Retain)
47	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	20	8	425	5	82	2.4	Good	Good	Mature	15-40	High	Priority for Retention	Previously crown lifted.	No Encroachment (Retain)
48	<i>Eucalyptus</i> sp. (Gum tree)	6	5	340	4	52	2.2	Good	Fair	Semi-mature	5-15	Low	Consider for Removal	Co-dominant inclusions, minor.	Within Development Footprint (Remove)
49	<i>Casuarina glauca</i> (Swamp She Oak)	12	4	200	2	18	1.8	Good	Good	Mature	15-40	Moderate	Consider for Retention		9% (Retain)
50	<i>Casuarina glauca</i> (Swamp She Oak)	12	4	250	3	28	1.9	Good	Good	Mature	15-40	Moderate	Consider for Retention		30.4% (SRZ - Remove)
51	<i>Casuarina glauca</i> (Swamp She Oak)	12	4	200	2	18	1.8	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)
52	<i>Casuarina glauca</i> (Swamp She Oak)	12	4	250	3	28	1.9	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)
53	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	250	3	28	1.9	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)


Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m ²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
54	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	300	4	41	2.1	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)
55	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	300	4	41	2.1	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)
56	<i>Eucalyptus robusta</i> (Swamp Mahogany)	7	4	266	3	32	2.0	Poor	Fair	Senescent	<5	Low	Priority for Removal	Crown density 0-25%. Small (<25mmØ) epicormic growth in high volumes. Co-dominant inclusions, minor.	No Encroachment (Retain)
57	<i>Casuarina glauca</i> (Swamp She Oak)	14	5	225	3	23	1.8	Good	Poor	Mature	5-15	Moderate	Consider for Retention	Trunk cavity(s), major.	No Encroachment (Retain)
58	<i>Eucalyptus robusta</i> (Swamp Mahogany)	10	5	200	2	18	1.8	Poor	Fair	Senescent	<5	Low	Priority for Removal		No Encroachment (Retain)
59	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	15	6	350	4	55	2.2	Good	Fair	Mature	15-40	High	Priority for Retention	Wound(s), early signs of decay.	No Encroachment (Retain)
60	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	16	6	325	4	48	2.1	Good	Poor	Mature	5-15	Moderate	Consider for Retention	Co-dominant inclusions, major. Bark inclusion(s), major. Wound(s), advanced stages of decay.	No Encroachment (Retain)
61	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	17	8	400	5	72	2.3	Good	Fair	Mature	15-40	High	Priority for Retention	Co-dominant inclusions, minor. Bark inclusion(s), minor.	No Encroachment (Retain)
62	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	15	6	375	5	64	2.3	Good	Fair	Mature	15-40	High	Priority for Retention	Co-dominant inclusions, major.	27.2% (TPZ – Remove)

Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m ²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
63	<i>Eucalyptus tereticornis</i> (Forest Red Gum)	18	6	475	6	102	2.5	Fair	Good	Mature	5-15	High	Consider for Retention	Grade change for fence Crown density 50-75%. Large (>75mmØ) deadwood in moderate volumes. Small (<25mmØ) & medium (25-75mmØ) epicormic growth in moderate volumes. Root severance within SRZ.	Within Development Footprint (Remove)
64	<i>Eucalyptus robusta</i> (Swamp Mahogany)	6	4	300	4	41	2.1	Poor	Poor	Semi-mature	<5	Low	Priority for Removal	Crown density 0-25%. Crown consists mainly of epicormic growth. Wound(s), early signs of decay. Trunk cavity(s), minor. Borer.	Within Development Footprint (Remove)
65	<i>Casuarina glauca</i> (Swamp She Oak)	8	3	100	2	13	1.5	Good	Good	Semi-mature	5-15	Low	Consider for Removal		4.8% (Retain)
66	<i>Casuarina glauca</i> (Swamp She Oak)	8	3	100	2	13	1.5	Good	Good	Semi-mature	5-15	Low	Consider for Removal		No Encroachment (Retain)
67	<i>Casuarina glauca</i> (Swamp She Oak)	8	3	135	2	13	1.5	Good	Good	Semi-mature	5-15	Low	Consider for Removal		No Encroachment (Retain)
68	<i>Casuarina glauca</i> (Swamp She Oak)	8	3	150	2	13	1.6	Good	Good	Semi-mature	5-15	Low	Consider for Removal		No Encroachment (Retain)
69	<i>Casuarina glauca</i> (Swamp She Oak)	8	3	225	3	23	1.8	Good	Good	Semi-mature	5-15	Low	Consider for Removal		No Encroachment (Retain)
70	<i>Casuarina glauca</i> (Swamp She Oak)	8	3	75	2	13	1.5	Good	Good	Semi-mature	5-15	Low	Consider for Removal		No Encroachment (Retain)

Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m ²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
71	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	354	4	57	2.2	Good	Fair	Mature	15-40	Moderate	Consider for Retention	Co-dominant inclusions, major. Structures within SRZ.	63.7% (SRZ - Remove)
72	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	250	3	28	1.9	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)
73	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	300	4	41	2.1	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)
74	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	407	5	75	2.4	Good	Fair	Mature	15-40	Moderate	Consider for Retention	Co-dominant inclusions, major.	No Encroachment (Retain)
75	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	300	4	41	2.1	Good	Good	Mature	15-40	Moderate	Consider for Retention		27.0% (SRZ - Remove)
76	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	300	4	41	2.1	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)
77	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	200	2	18	1.8	Good	Good	Mature	15-40	Moderate	Consider for Retention		No Encroachment (Retain)
78	<i>Casuarina glauca</i> (Swamp She Oak)	14	6	275	3	34	2.0	Fair	Good	Mature	15-40	Moderate	Consider for Retention	Crown density 50-75%. Storm damage.	17.8% (SRZ - Remove)
79	<i>Casuarina glauca</i> (Swamp She Oak)	20	8	550	7	137	2.7	Good	Fair	Late Mature	15-40	High	Priority for Retention	Co-dominant inclusions, minor. Structures within SRZ.	23.2% (TPZ - Remove)

Tree No.	Species	Height (m)	Radial Crown Spread (m)	DBH comb. (mm)	Radial TPZ (m)	TPZ Area (m ²)	Radial SRZ (m)	Health Rating	Structural Rating	Age Class	ULE (years)	L/Sign	Retention Value	Comments	TPZ Encroachment (%)
80	<i>Casuarina glauca</i> (Swamp She Oak)	15	6	375	5	64	2.3	Good	Good	Mature	15-40	Moderate	Consider for Retention	Trunk cavity(s), minor.	15.7% (TPZ – Retain)
81	<i>Araucaria cunninghamii</i> (Hoop Pine)	17	6	400	5	72	2.3	Good	Good	Mature	15-40	Moderate	Consider for Retention	Mechanical damage to exposed surface roots. Structures within SRZ.	No Encroachment (Retain)
82	<i>Melaleuca decora</i> (White Feather Honeymyrtle)	6	4	237	3	25	1.9	Good	Good	Mature	5-15	Low	Consider for Removal	Wound(s), no visible sign of decay. Trunk cavity(s), minor.	7% (Retain)
101	<i>Malus sp.</i> (Crab Apple)	5	6	300	4	41	2.1	Good	No access to base. No rating.	Mature	5-15	Moderate	Consider for Retention	Structures within SRZ.	No Encroachment (Retain)
102	<i>Malus sp.</i> (Crab Apple)	5	6	260	3	31	2.0	Good	Good	Mature	5-15	Moderate	Consider for Retention	Small (<25mmØ) epicormic growth in low volumes. Wound(s), early signs of decay. Trunk cavity(s), minor.	No Encroachment (Retain)
103	<i>Malus sp.</i> (Crab Apple)	5	6	300	4	41	2.1	Good	Fair	Mature	5-15	Moderate	Consider for Retention	Mechanical damage to exposed surface roots. Wound(s), early signs of decay. Trunk cavity(s), minor.	4.2% (Retain)
104	<i>Malus sp.</i> (Crab Apple)	3	2	125	2	13	1.5	Poor	Fair	Senescent	<5	Low	Priority for Removal	Crown density 0-25%. Lopped. Wound(s), early signs of decay.	No Encroachment (Retain)
105	<i>Malus sp.</i> (Crab Apple)	5	6	300	4	41	2.1	Good	No access to base. No rating.	Mature	5-15	Moderate	Consider for Retention	Group of two trees	Within Development Footprint (Remove)
106	<i>Malus sp.</i> (Crab Apple)	5	6	300	4	41	2.1	Good	No access to base. No rating.	Mature	5-15	Moderate	Consider for Retention		No Encroachment (Retain)

8.0 APPENDIX 3 | TREE LOCATION PLAN











9.0 APPENDIX 4 | PROPOSED DEVELOPMENT PLANS







1 PLAN
EXTERNAL WORKS SITE PLAN
 SCALE: 1:200

NOTE: SETOUT POINTS & DIMENSIONS TO BE CONFIRMED ON SITE. REFER TO SURVEY.


REV	DESCRIPTION	DATE	BY
01	TENDER ISSUE	14/03/2023	SE
02	100% 90% ISSUE REVISED	08/03/2023	LN
03	100% 90% ISSUE	14/03/2023	SE
04	100% 90% ISSUE	15/12/2024	LN
05	80% 50% ISSUE	08/12/2024	LN

fulton trotter
 ARCHITECTS BRISBANE SYDNEY
 www.fultontrrotter.com.au

PROJECT Greenway Park Public School
CLIENT Department of Education
ADDRESS WYATTVILLE DRIVE, CARNES HILL, NSW

SCHEMATIC DESIGN
CLIENT Department of Education
PROJECT GREENWAY PARK PUBLIC SCHOOL
ADDRESS WYATTVILLE DRIVE, CARNES HILL, NSW

EXTERNAL WORKS PLAN			
PROJECT NUMBER	DIRECTOR	CHECKED	REVISION
7068GR01	JW	LN	
DRAWING NUMBER			
GPPS-FTA-B00J-00-DR-A-1401			05



NOTE: SETOUT POINTS & DIMENSIONS TO BE CONFIRMED ON SITE. REFER TO SURVEY.

NO.	DESCRIPTION	DATE	BY
01	TENDER ISSUE	14/03/2023	SE
02	100% TO ISSUE REVISION	14/03/2023	LN
03	100% TO ISSUE	14/03/2023	LN
04	100% TO ISSUE UPDATE	14/03/2023	LN
05	100% TO ISSUE	14/03/2023	LN

fulton trotter
ARCHITECTS BRISBANE SYDNEY
www.fultontroutter.com.au

BRISBANE: Suite 200 Level 2, 25-30 Fraser Street, Surry Hills, NSW 2010
SYDNEY: Suite 100 Level 1, 100-110 Pitt Street, Sydney, NSW 2000

Fulton Trotter Architects is a registered architectural firm under the Architectural Act 2006 (NSW) and the Architectural Act 2003 (VIC).

This document is the property of Fulton Trotter Architects. It is to be used only for the project and site for which it is prepared. It is not to be used for any other project or site without the written consent of Fulton Trotter Architects.

Drawings are the property of Fulton Trotter Architects. They are to be used only for the project and site for which they are prepared. They are not to be used for any other project or site without the written consent of Fulton Trotter Architects.

SCHEMATIC DESIGN

Department of Education
GREENWAY PARK PUBLIC
SCHOOL

WYATTVILLE DRIVE,
CARNES HILL, NSW

**EXTERNAL WORKS PLAN
PRESCHOOL**

Figured dimensions take precedence over
written dimensions. Contractors must verify
all dimensions on site before commencing
any work or making any drawings.

PROJECT NUMBER: 7068GR01
DRAWING NUMBER: 7068GR01-00-DR-A-1402

DIRECTOR: JW
CHECKED: LN
REVISION: 04



- LEGEND**
- FFL 00.00 FINISHED FLOOR LEVEL
 - EXL 00.00 EXISTING SPOT LEVEL
 - PL 00.00 PROPOSED SPOT LEVEL
 - PROPOSED FENCING
 - PROPOSED FENCING
 - LINE OF BUILDING OVER
 - PROPOSED UNDEVELOPED - REFER TO APPS 06-08 OR 4-00 FOR INDICATIVE SPECIES LIST
 - PROPOSED TURF
 - EXISTING TREES TO BE RETAINED - REFER TO APPENDIX A FOR PROPOSED TREE LIST
 - EXISTING TREES TO BE REMOVED
 - PROPOSED TREES

GROUND INK
LANDSCAPE ARCHITECTS
SUITE 10/100 HUNTER STREET, CLOVELLY NSW 2031
WWW.GROUNDINK.COM.AU

L&C
CONSULTANCY
ARBORICULTURE
PLANT PATHOLOGY

DATE	DESCRIPTION	STATUS	COMMENTS
10/10/2023	DESIGN FOR CONSTRUCTION	REV	
10/10/2023	DESIGN FOR CONSTRUCTION	REV	
10/10/2023	DESIGN FOR CONSTRUCTION	REV	
10/10/2023	DESIGN FOR CONSTRUCTION	REV	
10/10/2023	DESIGN FOR CONSTRUCTION	REV	
10/10/2023	DESIGN FOR CONSTRUCTION	REV	
10/10/2023	DESIGN FOR CONSTRUCTION	REV	

LANDSCAPE PLAN

PROJECT	DATE
GREENWAY PARK PUBLIC SCHOOL	10/10/2023
WATTSVILLE DRIVE, CLOVELLY HILL, NSW 2031	
SCALE 1:500 @ A1	
2 1 1 1 1 1 1 1 1 1	

www.laurenceco.com.au



- LEGEND**
- F.F. 00.00 FINISHED FLOOR LEVEL
 - +F.F. 00.00 EXISTING SPOT LEVEL
 - F.F. 00.00 PROPOSED SPOT LEVEL
 - PROPOSED FENCING
 - TREE PROTECTION ZONE LINE
 - LINE OF BUILDING OVER
 - PROPOSED GARDEN BED - REFER TO GPPS-GIL-00-00-DR-L-3002 FOR INDICATIVE SPECIES LIST
 - PROPOSED TURF
 - EXISTING TREES TO BE RETAINED - REFER TO ARBORIST'S REPORT PREPARED BY LAURENCECO 19.12.23
 - EXISTING TREES TO BE REMOVED
 - PROPOSED TREES

LANDSCAPE ARCHITECT
GROUND INK
LANDSCAPE ARCHITECTS
SUITE 11, 54 NEWMAN ST, CHARTERSWOOD NSW 2837 PH: (02) 943 3279
WWW.GROUNDINK.COM.AU ABN 55 562 525 456 ACN 741 825 546
© 2024 GROUND INK LTD THIS DESIGN AND DRAWING IS PROTECTED BY COPYRIGHT


NOTE

VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK. REPORT ALL DISCREPANCIES TO LANDSCAPE ARCHITECT PRIOR TO CONSTRUCTION. FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED DRAWINGS. ALL WORK IS TO CONFORM TO RELEVANT AUSTRALIAN STANDARDS AND OTHER CODES AS APPLICABLE. LOCATION OF UNDERGROUND SERVICES TO BE PROVIDED ON SITE AND PROTECTED IF NECESSARY PRIOR TO CONSTRUCTION. DIAL BEFORE YOU DIG. PLANT SPECIES AND QUANTITIES SHOWN ARE INDICATIVE ONLY AND ARE SUBJECT TO CHANGE BASED ON FUTURE PROJECT REQUIREMENTS.

ISSUE	DATE	DESCRIPTION	DRAWN	CHECKED	DRAWING TITLE
1	20.12.23	ISSUE FOR REVIEW	100%	100%	
2					
3					
4					
5					
6					
7					
8					
9					
10					

**LANDSCAPE PLAN
EARLY LEARNING**

PROJECT	DRAWING NUMBER
GREENWAY PARK PUBLIC SCHOOL WYATTVILLE DRIVE, CARNES HILL, NSW 2171	GPPS-GIL-00-00-DR-L-3002
SCALE 1:100	REV A
9 1 2 3 4 5 6	



EARTHWORKS SUMMARY

NOTES:

- BULK EARTHWORKS VOLUME IS BULK EARTHWORKS SURFACE MINUS STRIPPED NATURAL SURFACE (150mm)
- EXCLUDES COMPACTION FACTOR
- ALL BATTERS TO BE 1:2 MAX UNLESS NOTED OTHERWISE. THE VOLUMES ARE APPROXIMATE ONLY. IT IS THE RESPONSIBILITY OF THE TENDERERS TO CONFIRM THE SCOPE OF WORKS, CONDUCT OWN EARTHWORK CHECK AND CONFIRM ACCURACY
- ASSUMED BULK EARTHWORKS DEPTH FOR BUILDING IS 420mm (BUILDING SLAB THICKNESS PLUS BEDDING THICKNESS)
- ASSUMED BULK EARTHWORKS DEPTH FOR LANDSCAPE AREAS IS 200mm

EARTHWORKS QUANTITIES

150mm STRIPPED VOLUME	329 m ³
TOTAL CUT VOLUME	803 m ³
TOTAL FILL VOLUME	11 m ³
NET EXPORT VOLUME	792 m ³

EXCESSIVE EXISTING EARTHWORKS ARE TO BE REMOVED FROM SITE

THESE PLANS ARE BASED UPON THE EXISTING CONDITIONS SURVEY PREPARED BY SD3 PTY LTD. REFERENCE No 9010 REV A DATED 11 SEPTEMBER 2024.

THESE DESIGN PLANS SHALL BE READ IN CONJUNCTION WITH GEOTECHNICAL REPORT No A0103/012/03.A-J-19 DATED 28 FEBRUARY 2024 PREPARED BY ADE CONSULTING GROUP. THE PROVISIONS AND RECOMMENDATIONS CONTAINED WITHIN THE REPORT ARE TO BE STRICTLY COMPLIED WITH. ALL COMPACTION REQUIREMENT RESULTS SHALL BE CARRIED OUT IN ACCORDANCE WITH GEOTECHNICAL REPORT RECOMMENDATIONS.

LEGEND

ITEM	DESCRIPTION
---	EXISTING SURFACE CONTOURS
---	PROPOSED SURFACE CONTOURS
BEL 10.000	BULK EARTHWORKS LEVEL
- - -	TITLE BOUNDARY
---	RETAINING WALL. REFER TO STRUCTURAL / LANDSCAPE DRAWINGS
---	PROPOSED SWALE
---	EXISTING STORMWATER DRAIN

LEGEND


ITEM	DESCRIPTION
---	EXISTING STORMWATER PIT
---	EXISTING STORMWATER PIT TO BE MODIFIED
---	EXISTING SEWER
---	EXISTING GAS
---	EXISTING WATER
---	EXISTING RECYCLED WATER
---	EXISTING ELECTRICITY

LEGEND

ITEM	DESCRIPTION
---	EXISTING OVERHEAD ELECTRICITY
---	EXISTING LOW VOLTAGE ELECTRICITY
---	EXISTING HIGH VOLTAGE ELECTRICITY
---	EXISTING TELECOM CABLE
---	EXISTING FIBRE OPTIC CABLE
---	EXISTING NBN COMMS CABLE
X X	EXISTING FEATURES TO BE REMOVED

BULK EARTHWORKS

ID	MIN. ELEVATION	MAX. ELEVATION	COLOR
1	-2.00m	-1.80m	
2	-1.80m	-1.60m	
3	-1.60m	-1.40m	
4	-1.40m	-1.20m	
5	-1.20m	-1.00m	
6	-1.00m	-0.80m	
7	-0.80m	-0.60m	
8	-0.60m	-0.40m	
9	-0.40m	-0.20m	
10	-0.20m	0.00m	
11	0.00m	0.20m	
12	0.20m	0.40m	
13	0.40m	0.60m	




FOR CONTINUATION REFER TO DRAWING C-1071



WARNING
PROPOSED SERVICES
THE LOCATION AND EXTENT OF PROPOSED SERVICES IS INDICATIVE ONLY AND ARE NOT TO BE USED FOR CONSTRUCTION. REFER TO AUTHORIZED DOCUMENTATION BY RELEVANT AUTHORITY FOR CONSTRUCTION DETAILS.

WARNING
BEWARE OF UNDERGROUND SERVICES
THE LOCATIONS OF UNDERGROUND SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.


NO.	DESCRIPTION	BY	CHKD	DATE
01	SEE 'N' SCHEMATIC DESIGN ISSUE	D.H.	M.D.	1/2/2025





MEINHARDT
Meinhardt Infrastructure and Environment PTY. LTD.
A/CN 001 827 581
Level 40, 400 George Street
Sydney NSW 2000
Australia
T +61 2 9250 5500
F +61 2 9250 7500
E info@meinhardt.com.au
www.meinhardt.com.au

NSW
School Infrastructure NSW
TITLE: BULK EARTHWORKS PLAN
SHEET 1

PROJECT: GREENWAY PARK PRE SCHOOL
WYATTVILLE DRIVE, CARNES HILL NSW 2171
STATUS: **SCHEMATIC DESIGN**
NOT TO BE USED FOR CONSTRUCTION
DRAWN: M.D. DESIGNED: G.P. CHECKED: Y.C. APPROVED: DATE: SCALE: A3 1:100
PROJECT NO: 132565 (GPS-MHT-00-00-DR-C-1070) P1








ELECTRICAL DISTRIBUTION BOARD (EDB)
(PROPOSED NEW)
NOMINAL LOCATION OF SUBMAIN CONDUIT ENTRY POINT TO BLOCK J. SEE POWER AND COMMUNICATIONS ARRANGEMENTS FOR DETAILS.

BUILDING COMMUNICATIONS ROOM (BCR)
(PROPOSED NEW)
SEE BLOCK J POWER AND COMMUNICATIONS ARRANGEMENT FOR DETAILS.

WALKWAY & PATH LIGHTING
(PROPOSED NEW)
LIGHTING TO BE PROVIDED ALONG THE ENTIRE LENGTH OF THE NEW EXTERNAL WALKWAYS

MAIN COMMUNICATIONS ROOM (MCR)
(EXISTING - TO BE RETAINED)
THE MCR IS LOCATED WITHIN BLOCK D. ONE COMMUNICATIONS CABINET ACCOMMODATES CAMPUS DISTRIBUTION. NEW 45 RU x 800 x 1000 RACK TO BE PROVIDED. THE EXISTING TELSTRA LEAD IN FROM WYATTVILLE DRIVE COMPLIES WITH DSE ICT REQUIREMENTS. NO UPGRADES TO LEAD IN REQUIRED



BUILDING COMMUNICATIONS ROOM (BCR)
(PROPOSED NEW)
SEE PRESCHOOL POWER AND COMMUNICATIONS ARRANGEMENT FOR DETAILS.

ELECTRICAL DISTRIBUTION BOARD (EDB)
(PROPOSED NEW)
NOMINAL LOCATION OF SUBMAIN CONDUIT ENTRY POINT TO PRESCHOOL. SEE POWER AND COMMUNICATIONS ARRANGEMENTS FOR DETAILS.

MAIN SWITCHBOARD (MSB)
(EXISTING - TO BE DEMOLISHED)
INDICATIVE LOCATION OF EXISTING MAIN SWITCHBOARD TO BE DISCONNECTED AND REMOVED. ALL EXISTING OUTGOING SUBMANS ARE TO BE RETAINED FOR CONNECTION TO NEW MSB.



MAIN SWITCHBOARD (MSB)
(PROPOSED NEW)
EXTERNAL MAIN SWITCHBOARD TO BE PROVIDED GENERALLY IN SITU WITH EXISTING BOARD TO BE 600A RATED WITH CIRCUIT BREAKERS PROVIDED FOR ALL EXISTING LOADS AND ALL NEW LOADS.

AUTHORITY SUBSTATION (210kVA)
(EXISTING - TO BE RETAINED)
INDICATIVE LOCATION OF EXISTING ENDEAVOUR ENERGY SUBSTATION S28507 TO BE RETAINED. TOTAL LOAD OF 400 AMP PER PHASE APPROVED BY ENDEAVOUR ENERGY FOR SCHOOL USE. PENDING DEPARTURE FROM 15% SPARE CAPACITY REQUIRED BY EFSSO. EXISTING CONSUMER MAINS DO NOT HAVE A CURRENT RATING SUITABLE FOR PROPOSED WORKS. EXISTING SPARE CONDUIT TO BE USED TO UPGRADE MAINS TO PARALLEL SET.



GENERAL NOTE
NEW POWER, SECURITY AND COMMUNICATIONS PITS TO BE PROVIDED EVERY 50M OR IN CHANGE OF DIRECTION OF CONDUIT RETICULATION ROUTE.


FOR IMPLEMENTATION OF THE SHOWN MCR KIT OF PARTS, NOTE THE FOLLOWING:
INTELLECTUAL PROPERTY
Refer to: SHOWN MCR Kit of Parts - Introduction, Copyright and Disclaimer
AGREEMENT OF USE
Refer to: SHOWN MCR Kit of Parts - Introduction, Copyright and Disclaimer
SHOWN CONTACT
Refer to: SHOWN MCR Kit of Parts - Introduction, Copyright and Disclaimer

1:500 @ A1

NDY
NORTH DRY
AUSTRIAN
LEVEL 15, 50 ARTHUR ST
NORTH SYDNEY NSW 2060
T +61 2 9554 6666
F +61 2 9554 6666
www.ndy.com.au

fulton trotter
ARCHITECTS
SUITE 104, LEVEL 10, 28-30 FORDHAM STREET
SUNSHINE HILLS, SYDNEY NSW 2125 Australia
T +61 2 8353 5333, W www.fultontritter.com.au

RP INFRASTRUCTURE
Connecting visions to reality




REV BY DATE DESCRIPTION
1 CG 11/12/24 CONCEPT DESIGN
2 CG 24/12/24 CONCEPT DESIGN
3 CG 24/12/24 SCHEMATIC DESIGN
4 CG 11/12/24 SCHEMATIC DESIGN
5 CG 10/12/24 SCHEMATIC DESIGN
6 CG 24/12/24 SCHEMATIC DESIGN
7 CG 24/12/24 SCHEMATIC DESIGN

PROJECT NAME
SHOWN GREENWAY PARK PUBLIC SCHOOL UPGRADE
WYATTVILLE DR, CARRIES HILL NSW 2171
SITE

DRAWING TITLE
ELECTRICAL SERVICES
SITE PLAN

PROJECT NO.
759-0720-0041153-0001
SCALE
1:500 @ A1
DRAWING NO.
GPSS-NDY-00-00-DR-E-001011
REV 7




10.0 APPENDIX 5 | ARBORICULTURAL IMPACT ASSESSMENT PLANS

Impact Assessment Plan

L&Co Legend

- Major Encroachment Tree removal may be required
- SRZ
- TPZ encroachment
- TPZ
- Tree removal required
- Tree retained



1 PLAN
EXTERNAL WORKS SITE PLAN
SCALE 1:200

NOTE: SETOUT POINTS & DIMENSIONS TO BE CONFIRMED
ON SITE. REFER TO SURVEY.

Fulton trotter
ARCHITECTS BRISBANE SYDNEY
www.fultontroutter.com.au

SYDNEY 1000 000 1000
BRISBANE 1000 000 1000
SYDNEY 1000 000 1000
BRISBANE 1000 000 1000

REV	DESCRIPTION	DATE	BY
01	TENDER ISSUE	14/03/2021	ST
02	10% OF ISSUE REQUIRED	14/03/2021	ST
03	10% OF ISSUE REQUIRED	14/03/2021	ST
04	10% OF ISSUE REQUIRED	14/03/2021	ST
05	10% OF ISSUE REQUIRED	14/03/2021	ST
06	10% OF ISSUE REQUIRED	14/03/2021	ST
07	10% OF ISSUE REQUIRED	14/03/2021	ST
08	10% OF ISSUE REQUIRED	14/03/2021	ST
09	10% OF ISSUE REQUIRED	14/03/2021	ST
10	10% OF ISSUE REQUIRED	14/03/2021	ST
11	10% OF ISSUE REQUIRED	14/03/2021	ST
12	10% OF ISSUE REQUIRED	14/03/2021	ST
13	10% OF ISSUE REQUIRED	14/03/2021	ST
14	10% OF ISSUE REQUIRED	14/03/2021	ST
15	10% OF ISSUE REQUIRED	14/03/2021	ST
16	10% OF ISSUE REQUIRED	14/03/2021	ST
17	10% OF ISSUE REQUIRED	14/03/2021	ST
18	10% OF ISSUE REQUIRED	14/03/2021	ST
19	10% OF ISSUE REQUIRED	14/03/2021	ST
20	10% OF ISSUE REQUIRED	14/03/2021	ST
21	10% OF ISSUE REQUIRED	14/03/2021	ST
22	10% OF ISSUE REQUIRED	14/03/2021	ST
23	10% OF ISSUE REQUIRED	14/03/2021	ST
24	10% OF ISSUE REQUIRED	14/03/2021	ST
25	10% OF ISSUE REQUIRED	14/03/2021	ST
26	10% OF ISSUE REQUIRED	14/03/2021	ST
27	10% OF ISSUE REQUIRED	14/03/2021	ST
28	10% OF ISSUE REQUIRED	14/03/2021	ST
29	10% OF ISSUE REQUIRED	14/03/2021	ST
30	10% OF ISSUE REQUIRED	14/03/2021	ST
31	10% OF ISSUE REQUIRED	14/03/2021	ST
32	10% OF ISSUE REQUIRED	14/03/2021	ST
33	10% OF ISSUE REQUIRED	14/03/2021	ST
34	10% OF ISSUE REQUIRED	14/03/2021	ST
35	10% OF ISSUE REQUIRED	14/03/2021	ST
36	10% OF ISSUE REQUIRED	14/03/2021	ST
37	10% OF ISSUE REQUIRED	14/03/2021	ST
38	10% OF ISSUE REQUIRED	14/03/2021	ST
39	10% OF ISSUE REQUIRED	14/03/2021	ST
40	10% OF ISSUE REQUIRED	14/03/2021	ST
41	10% OF ISSUE REQUIRED	14/03/2021	ST
42	10% OF ISSUE REQUIRED	14/03/2021	ST
43	10% OF ISSUE REQUIRED	14/03/2021	ST
44	10% OF ISSUE REQUIRED	14/03/2021	ST
45	10% OF ISSUE REQUIRED	14/03/2021	ST
46	10% OF ISSUE REQUIRED	14/03/2021	ST
47	10% OF ISSUE REQUIRED	14/03/2021	ST
48	10% OF ISSUE REQUIRED	14/03/2021	ST
49	10% OF ISSUE REQUIRED	14/03/2021	ST
50	10% OF ISSUE REQUIRED	14/03/2021	ST
51	10% OF ISSUE REQUIRED	14/03/2021	ST
52	10% OF ISSUE REQUIRED	14/03/2021	ST



SCHEMATIC DESIGN
Department of Education
GREENWAY PARK PUBLIC
SCHOOL
WYATTVILLE DRIVE,
CARNES HILL, NSW

EXTERNAL WORKS PLAN

Figured dimensions take precedence over
written dimensions. Contractors must verify
all dimensions on site before commencing
any work or making their drawings.

PROJECT NUMBER	DIRECTOR	CHECKED
7068GR01	JW	LN

DRAWING NUMBER	REVISION
GPPS-FTA-800J-00-DR-A-1401	05



Impact Assessment Plan

- L&Co Legend**
- Major Encroachment Tree removal may be required
 - SRZ
 - TPZ encroachment
 - TPZ
 - Tree removal required
 - Tree retained

NOTE: SETOUT POINTS & DIMENSIONS TO BE CONFIRMED ON SITE. REFER TO SURVEY.

REV	DESCRIPTION	DATE	BY
04	TENDER ISSUE	14/03/2023	LN
05	100% TO ISSUE REVISION	14/03/2023	LN
06	100% TO ISSUE	14/03/2023	LN
07	100% TO ISSUE	14/03/2023	LN
08	100% TO ISSUE	14/03/2023	LN
09	100% TO ISSUE	14/03/2023	LN
10	100% TO ISSUE	14/03/2023	LN
11	100% TO ISSUE	14/03/2023	LN
12	100% TO ISSUE	14/03/2023	LN
13	100% TO ISSUE	14/03/2023	LN
14	100% TO ISSUE	14/03/2023	LN
15	100% TO ISSUE	14/03/2023	LN
16	100% TO ISSUE	14/03/2023	LN
17	100% TO ISSUE	14/03/2023	LN
18	100% TO ISSUE	14/03/2023	LN
19	100% TO ISSUE	14/03/2023	LN
20	100% TO ISSUE	14/03/2023	LN
21	100% TO ISSUE	14/03/2023	LN
22	100% TO ISSUE	14/03/2023	LN
23	100% TO ISSUE	14/03/2023	LN
24	100% TO ISSUE	14/03/2023	LN
25	100% TO ISSUE	14/03/2023	LN
26	100% TO ISSUE	14/03/2023	LN
27	100% TO ISSUE	14/03/2023	LN
28	100% TO ISSUE	14/03/2023	LN
29	100% TO ISSUE	14/03/2023	LN
30	100% TO ISSUE	14/03/2023	LN
31	100% TO ISSUE	14/03/2023	LN
32	100% TO ISSUE	14/03/2023	LN
33	100% TO ISSUE	14/03/2023	LN
34	100% TO ISSUE	14/03/2023	LN
35	100% TO ISSUE	14/03/2023	LN
36	100% TO ISSUE	14/03/2023	LN
37	100% TO ISSUE	14/03/2023	LN
38	100% TO ISSUE	14/03/2023	LN
39	100% TO ISSUE	14/03/2023	LN
40	100% TO ISSUE	14/03/2023	LN
41	100% TO ISSUE	14/03/2023	LN
42	100% TO ISSUE	14/03/2023	LN
43	100% TO ISSUE	14/03/2023	LN
44	100% TO ISSUE	14/03/2023	LN
45	100% TO ISSUE	14/03/2023	LN
46	100% TO ISSUE	14/03/2023	LN
47	100% TO ISSUE	14/03/2023	LN
48	100% TO ISSUE	14/03/2023	LN
49	100% TO ISSUE	14/03/2023	LN
50	100% TO ISSUE	14/03/2023	LN
51	100% TO ISSUE	14/03/2023	LN
52	100% TO ISSUE	14/03/2023	LN
53	100% TO ISSUE	14/03/2023	LN
54	100% TO ISSUE	14/03/2023	LN
55	100% TO ISSUE	14/03/2023	LN
56	100% TO ISSUE	14/03/2023	LN
57	100% TO ISSUE	14/03/2023	LN
58	100% TO ISSUE	14/03/2023	LN
59	100% TO ISSUE	14/03/2023	LN
60	100% TO ISSUE	14/03/2023	LN
61	100% TO ISSUE	14/03/2023	LN
62	100% TO ISSUE	14/03/2023	LN
63	100% TO ISSUE	14/03/2023	LN
64	100% TO ISSUE	14/03/2023	LN
65	100% TO ISSUE	14/03/2023	LN
66	100% TO ISSUE	14/03/2023	LN
67	100% TO ISSUE	14/03/2023	LN
68	100% TO ISSUE	14/03/2023	LN
69	100% TO ISSUE	14/03/2023	LN
70	100% TO ISSUE	14/03/2023	LN
71	100% TO ISSUE	14/03/2023	LN
72	100% TO ISSUE	14/03/2023	LN
73	100% TO ISSUE	14/03/2023	LN
74	100% TO ISSUE	14/03/2023	LN
75	100% TO ISSUE	14/03/2023	LN
76	100% TO ISSUE	14/03/2023	LN
77	100% TO ISSUE	14/03/2023	LN
78	100% TO ISSUE	14/03/2023	LN
79	100% TO ISSUE	14/03/2023	LN
80	100% TO ISSUE	14/03/2023	LN
81	100% TO ISSUE	14/03/2023	LN
82	100% TO ISSUE	14/03/2023	LN


fulton trotter
ARCHITECTS BRISBANE SYDNEY
www.fultontrrotter.com.au

SCHEMATIC DESIGN
Department of Education
GREENWAY PARK PUBLIC SCHOOL
WYATTVILLE DRIVE, CARNES HILL, NSW

EXTERNAL WORKS PLAN PRESCHOOL
PROJECT NUMBER: 7068GR01
DRAWING NUMBER: GPPS-FTA-B00K-00-DR-A-1402
DIRECTOR: JW
CHECKED: LN
REVISION: 04

L&Co Legend

- Major Encroachment Tree removal may be required
- SRZ
- TPZ encroachment
- TPZ
- Tree removal required
- Tree retained



03	TENDER ISSUE	14/03/2025	BZ
02	100% ID ISSUE REVISED	06/03/2025	UN
01	100% ID ISSUE	14/02/2025	BZ
REV	DESCRIPTION	DATE	INT

fulton trotter
ARCHITECTS BRISBANE SYDNEY
www.fultontrotter.com.au

SYDNEY Suite 904, Level 9, 25-36 Powerhouse Street, Surry Hills, NSW 2010
t: (02) 8363 5151 e: sydney@fulfontrotter.com.au

<p><small>This table is a summary of the work done on the project. It is not a substitute for the full report, which is available in the project file. The work done on the project is described in the project file. The work done on the project is described in the project file. The work done on the project is described in the project file.</small></p>			
DIRECTIONS			
Greg Jones	NEW 5855	QLO 2825	
Andrew Henry	NEW 5855	QLO 3113	
John Ward	VIC 19804	NEW 3371	QLO 5847
Katherine Thompson	NEW 7834	QLO 4529	
Paul Roberts	NEW 7188	QLO 2108	
Ryan Lindsay		QLO 4505	

PHASE SCHEMATIC DESIGN

Department of Education
GREENWAY PARK PUBLIC
SCHOOL

WYATTVILLE DRIVE,
CARNES HILL, NSW

PROPOSED PRESCHOOL CAR PARK

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing work.

PROJECT NUMBER	DIRECTOR
7068GB01	DM

DRAWING NUMBER

CHECKED
LN

5 | **03**

L&Co Legend

- Major Encroachment Tree removal may be required
- SRZ
- TPZ encroachment
- TPZ
- Tree removal required
- Tree retained




LEGEND

- FINISHED FLOOR LEVEL
- EXISTING SPOT LEVEL
- PROPOSED SPOT LEVEL
- PROPOSED FINISHING
- THE LINE OF PROTECTION ZONE LINE
- LINE OF BUILDING OWNER
- PROPOSED GARDENED - KAPPA TO SPEC-46, 48 OR 50-500 FOR INDICATIVE SPECIES LIST
- PROPOSED TUNP
- EXISTING TREES TO BE RETAINED - REFER TO GARDENER'S REPORT PREPARED BY LANDSCAPE CONSULTANT
- EXISTING TREES TO BE REMOVED
- PROPOSED TREES

LANDSCAPE PLAN

ISSUE	DATE	DESCRIPTION	ISSUED	CHECKED
A	13.12.24	ISSUE FOR COORDINATION	NO	NO
B	16.12.24	ISSUE FOR COORDINATION	NO	NO
C	19.12.24	ISSUE FOR COORDINATION	NO	NO
D	13.01.25	ISSUE FOR COORDINATION	NO	NO
E	19.01.25	ISSUE FOR TENDER	NO	NO
F	23.01.25	ISSUE FOR TENDER	NO	NO
G	02.02.25	ISSUE FOR TENDER	NO	NO

LANDSCAPE PLAN

DRAWING NUMBER GPPS-01L-00-00-0R-L-3001	
PROJECT GREENWAY PARK PUBLIC SCHOOL WYATTVILLE DRIVE, CARNES HILL, NSW 2171	NOTES 
SCALE 1:300 @ A1 1 2 3 4 5 6 7 8 10M	REV G

L&Co Legend

- Major Encroachment Tree removal may be required
- SRZ
- TPZ encroachment
- TPZ
- Tree removal required
- Tree retained



LEGEND

- FF/L 00.00 FINISHED FLOOR LEVEL
- +X 00.00 EXISTING SPOT LEVEL
- +R 00.00 PROPOSED SPOT LEVEL
- 10' — PROPOSED FENCING
- 10' — TREE PROTECTION ZONE LINE
- LINE OF BUILDING OVER
- PROPOSED GARDEN BED – REFER TO GPM 01.00-09 OR L 0801 FOR INDICATIVE SPECIES LIST
- PROPOSED TURF
- EXISTING TREES TO BE RETAINED – REFER TO ABILITY REPORT PREPARED BY LAURENCEO N12.23
- EXISTING TREES TO BE REMOVED
- PROPOSED TREES

LANDSCAPE ARCHITECT

GROUND INK

LANDSCAPE ARCHITECTS


SUITE 19, 56 NERIDA ST, CHATSWOOD NSW 2067 PH: (02) 9411 3279
WWW.GROUNDINK.COM.AU AIN 55 163 825 A56 AIN 163 825 A56
© GROUND INK PTY LTD (INNS DESIGN AND DRAWING IS PROTECTED BY COPYRIGHT)

	NOTE
--	------

VERIFY ALL DIMENSIONS ON SITE BEFORE COMMENCING WORK. REPORT ALL DISCREPANCIES TO LAND ARCHITECT PRIOR TO CONSTRUCTION. FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO DIMENSIONS SHOWN ON DRAWINGS. ALL WORK IS TO CONFORM TO RELEVANT AUSTRALIAN STANDARDS AND OTHER CODES OF PRACTICE. APPLICABLE LOCATION OF UNDERGROUND SERVICES TO BE PROVEN ON SITE AND PROTECTED IF NECESSARY. ALL PLANT SPECIES AND QUANTITIES SHOWN ARE INDICATIVE ONLY AND ARE SUBJECT TO CHANGE BASED ON FUTURE PROJECT REQUIREMENTS.

ISSUE	DATE	DESCRIPTION	DRAIN	CHECKED	DRAWING TITLE
A	20.02.25	ISSUE FOR REF	(%)	(%)	

LANDSCAPE PLAN
EARLY LEARNING

		DRAWING NUMBER	
		GPPS-GIL-00-00-DR-L-3002	
PROJECT		NORTH	
GREENWAY PARK PUBLIC SCHOOL			
WYATTVILLE DRIVE, CARNES HILL, NSW 2171			
SCALE 1:150		REV	
0 1 2 3 4 5M		A	

L&L
CONSULTANCY
ARBORICULTURE
PLANT PATHOLOGY

Impact Assessment Plan

EARTHWORKS QUANTITIES

1. BULK EARTHWORKS VOLUME IS BULK EARTHWORKS SURFACE	STRIPPED VOLUME =	329 m³
	FILL VOLUME =	803 m³
	CUT VOLUME =	11 m³
	NET VOLUME =	792 m³

L&Co Legend

- Major Encroachment Tree removal may be required
- SRZ
- TPZ encroachment
- TPZ
- Tree removal required
- Tree retained

REFERENCE No 9010 REV A DATED 11 SEPTEMBER 2024.

THESE DESIGN PLANS SHALL BE READ IN CONJUNCTION WITH GEOTECHNICAL REPORT No 40103.012.03.A-J-19 DATED 28 FEBRUARY 2024 PREPARED BY ADE CONSULTING GROUP. THE PROVISIONS AND RECOMMENDATIONS CONTAINED WITHIN THE REPORT ARE TO BE STRICTLY COMPLIED WITH. ALL COMPACTION REQUIREMENT RESULTS SHALL BE CARRIED OUT IN ACCORDANCE WITH GEOTECHNICAL REPORT RECOMMENDATIONS.

LEGEND


ITEM	DESCRIPTION
---	EXISTING SURFACE CONTOURS
---	PROPOSED SURFACE CONTOURS
---	BULK EARTHWORKS LEVEL
---	TITLE BOUNDARY
---	RETAINING WALL REFER TO STRUCTURAL / LANDSCAPE DRAWINGS
---	PROPOSED SWALE
---	EXISTING STORMWATER DRAIN

ITEM	DESCRIPTION
---	EXISTING STORMWATER PIT
---	EXISTING STORMWATER PIT TO BE MODIFIED
---	EXISTING SEWER
---	EXISTING GAS
---	EXISTING WATER
---	EXISTING RECYCLED WATER
---	EXISTING ELECTRICITY

ITEM	DESCRIPTION
---	EXISTING OVERHEAD ELECTRICITY
---	EXISTING LOW VOLTAGE ELECTRICITY
---	EXISTING HIGH VOLTAGE ELECTRICITY
---	EXISTING TELECOM CABLE
---	EXISTING FIBRE OPTIC CABLE
---	EXISTING NBN COMMS CABLE
X	EXISTING FEATURES TO BE REMOVED

BULK EARTHWORKS

ID	MIN. ELEVATION	MAX. ELEVATION	CLOUR
1	-2.00m	-1.80m	Red
2	-1.80m	-1.60m	Red
3	-1.60m	-1.40m	Red
4	-1.40m	-1.20m	Red
5	-1.20m	-1.00m	Red
6	-1.00m	-0.80m	Red
7	-0.80m	-0.60m	Red
8	-0.60m	-0.40m	Red
9	-0.40m	-0.20m	Red
10	-0.20m	0.00m	Red
11	0.00m	0.20m	Green
12	0.20m	0.40m	Green
13	0.40m	0.60m	Green



FOR CONTINUATION REFER TO DRAWING C-101




WARNING PROPOSED SERVICES

THE LOCATION AND EXTENT OF PROPOSED SERVICES IS INDICATIVE ONLY AND ARE NOT TO BE USED FOR CONSTRUCTION. REFER TO AUTHORIZED DOCUMENTATION BY RELEVANT AUTHORITY FOR CONSTRUCTION DETAILS.

WARNING BEWARE OF UNDERGROUND SERVICES

THE LOCATIONS OF UNDERGROUND SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.

NO	DESCRIPTION	BY	CHKD	DATE
1	REV A SCHEMATIC DESIGN ISSUE	M.D	M.D	10/03/20



MEINHARDT
Meinhardt Infrastructure and Environment PTY. LTD.
A/CN 001 027 001
Level 40, 400 George Street
Sydney NSW 2000
Phone: 7 412 2000
Fax: 7 412 2000
Email: info@meinhardt.com.au
www.meinhardt.com.au

NSW
School Infrastructure NSW

PROJECT: GREENWAY PARK PRE SCHOOL
WYATTVILLE DRIVE, CARNES HILL NSW 2171

TITLE: BULK EARTHWORKS PLAN
SHEET 1


STATUS	THROW	DESIGNED	CHECKED	APPROVED	DATE	SCALE
	M.D	G.P	Y.C			1:100

SCHEMATIC DESIGN
NOT TO BE USED FOR CONSTRUCTION

PROJECT NO: 132565
GPPS-MHT-00-00-DR-C-1010
P1

Impact Assessment Plan

L&Co Legend	
	Major Encroachment Tree removal may be required
	SRZ
	TPZ encroachment
	TPZ
	Tree removal required
	Tree retained



LEGEND	
ITEM	DESCRIPTION
	EXISTING SURFACE CONTOURS
	PROPOSED SURFACE CONTOURS
	EXISTING SURFACE SPOT LEVELS
	TITLE BOUNDARY
	PROPOSED RETAINING WALL
	PROPOSED SWALE
	EXISTING STORMWATER DRAIN
	EXISTING STORMWATER PIT
	EXISTING STORMWATER PIT TO BE MODIFIED
	EXISTING SEWER
	EXISTING GAS
	EXISTING WATER
	EXISTING RECYCLED WATER
	EXISTING ELECTRICITY
	EXISTING ELECTRICAL UNDERGROUND
	EXISTING LOW VOLTAGE ELECTRICITY
	EXISTING HIGH VOLTAGE ELECTRICITY
	EXISTING TELECOM CABLE
	EXISTING FIBRE OPTIC CABLE
	EXISTING NBN COPPER CABLE
	EXISTING FEATURES TO BE REMOVED

EARTHWORKS QUANTITIES	
150mm STORMWATER	30m³
TOTAL CUT VOLUME	246m³
TOTAL FILL VOLUME	87m³
NET EXPORT VOLUME	159m³
NET VOLUME EXCLUDED (TRIMMED TO 1:5) IS ASSUMED TO BE REMOVED FROM SITE	

THESE PLANS ARE BASED UPON THE EXISTING CONDITIONS SURVEY PREPARED BY ASTREA, REFERENCE TO ADAMS REV 9 DATED 18 OCTOBER 2023.

THESE DESIGN PLANS SHALL BE READ IN CONJUNCTION WITH GEOTECHNICAL REPORT NO. P2023010-010-001-001 DATED 17 NOVEMBER 2023 PREPARED BY WSP. THE PROVISIONS AND RECOMMENDATIONS CONTAINED WITHIN THE REPORT ARE TO BE STRICTLY COMPLIED WITH. ALL COMPACTION REQUIREMENT RESULTS SHALL BE CARRIED OUT IN ACCORDANCE WITH GEOTECHNICAL REPORT RECOMMENDATIONS.

BULK EARTHWORKS			
ID	MIN. ELEVATION	MAX. ELEVATION	COLOR
1	-30.000	-1.000	Orange
2	-1.800	-1.400	Dark Red
3	-1.400	-1.200	Red
4	-1.200	-1.000	Dark Red
5	-1.000	-0.800	Red
6	-0.800	-0.600	Dark Red
7	-0.600	-0.400	Red
8	-0.400	-0.200	Dark Red
9	-0.200	0.000	Red
10	0.000	0.200	Dark Red
11	0.200	0.400	Red
12	0.400	0.600	Dark Red
13	0.600	0.800	Red
14	0.800	1.000	Dark Red



WARNING
PROPOSED SERVICES
THE LOCATION AND EXTENT OF PROPOSED SERVICES IS INDICATIVE ONLY AND ARE NOT TO BE USED FOR CONSTRUCTION. REFER TO AUTHORIZED DOCUMENTATION BY RELEVANT AUTHORITY FOR CONSTRUCTION DETAILS.

WARNING
BEWARE OF UNDERGROUND SERVICES
THE LOCATIONS OF UNDERGROUND SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.

EARTHWORKS SUMMARY
NOTES:
1. BULK EARTHWORKS SURFACE IS DESIGN SURFACE MINUS THE FOLLOWING:
2. NATURAL SURFACE (150mm)
3. EXCLUDED COMPACTION FACTORS
4. ALL BATTERS TO BE 1 IN 2 MAX UNLESS NOTED OTHERWISE
5. THE ABOVE VOLUMES ARE APPROXIMATE ONLY. IT IS THE RESPONSIBILITY OF THE TENDERERS TO CONFIRM THE SCOPE OF WORKS, CONDUCT OWN EARTHWORK CHECK AND CONFIRM ACCURACY.
6. ASSUMED BULK EARTHWORKS DEPTH FOR BUILDING IS 250mm (BUILDING SLAB THICKNESS PLUS BEDDING THICKNESS).

NO.	DESCRIPTION	BY	CHKD	DATE
1	REV. SCHEMATIC DESIGN	D.H.	G.P.	12/12/24
2	REV. SCHEMATIC DESIGN	D.H.	G.P.	14/12/24
3	TENDER ISSUE	D.H.	G.P.	27/02/25
4	TENDER ISSUE	D.H.	G.P.	28/02/25
5	TENDER ISSUE	D.H.	G.P.	10/03/25




MEINHARDT
Meinhardt Infrastructure and Environment PTY. LTD.
A/CN 001 827 581
Level 40, 100 Victoria Street
Sydney NSW 2000
Phone: 61 61 2 9290 0000
Fax: 61 61 2 9290 7500
Email: info@meinhardt.com.au
Website: www.meinhardt.com.au

NSW
School Infrastructure NSW
TITLE: BULK EARTHWORKS PLAN

PROJECT: GREENWAY PARK PUBLIC SCHOOL
WYATTVILLE DRIVE, CARNES HILL NSW 2171
STATUS: TENDER ISSUE
NOT TO BE USED FOR CONSTRUCTION
DRAWN: M.D.
DESIGNED: G.P.
CHECKED: Y.C.
APPROVED: [Signature]
DATE: 12/03/25
SCALE: 1:200
PROJECT NO: 132565
SHEET NO: 00-00-DR-C-0070
REV: T3

Impact Assessment Plan


- L&Co Legend**
- Major Encroachment Tree removal may be required
 - SRZ
 - TPZ encroachment
 - TPZ
 - Tree removal required
 - Tree retained



Impact Assessment Plan

L&Co Legend

- Major Encroachment Tree removal may be required
- SRZ
- TPZ encroachment
- TPZ
- Tree removal required
- Tree retained



ITEM	DESCRIPTION
100.0	EXISTING SURFACE CONTOURS
100.0	PROPOSED SURFACE CONTOURS
100.0	EXISTING SURFACE SPOT LEVELS
100.0	PROPOSED SURFACE SPOT LEVELS
100.0	TITLE BOUNDARY
100.0	PROPOSED RETAINING WALL
100.0	EXISTING STORMWATER DRAIN
100.0	PROPOSED STORMWATER DRAIN AND FLOW DIRECTION
100.0	HYDRAULIC CONNECTION PIPES (HYDRAULIC ENGINEERS DRAW)
100.0	PROPOSED 1000 L/D PVC AGRICULTURAL DRAIN CLASS 400
100.0	EXISTING STORMWATER PIT
100.0	EXISTING STORMWATER PIT TO BE MODIFIED
100.0	PROPOSED STORMWATER PIT
100.0	1000 GRATED INLET (UNLESS NOTED OTHERWISE)
100.0	DOWNPIPE
100.0	INSPECTION OPENING
100.0	TRENCH GRATE
100.0	OVERLAND FLOW ARROW
100.0	LIGHT DUTY CONCRETE PAVEMENT PEDESTRIAN
100.0	EXISTING SEWER
100.0	EXISTING GAS
100.0	EXISTING RECYCLED WATER
100.0	EXISTING ELECTRICITY
100.0	EXISTING ELECTRICAL UNDERGROUND
100.0	EXISTING LOW VOLTAGE ELECTRICITY
100.0	EXISTING HIGH VOLTAGE ELECTRICITY
100.0	EXISTING TELECOM CABLE
100.0	EXISTING FIBRE OPTIC CABLE
100.0	EXISTING NBN CABLE
100.0	EXISTING FEATURES TO BE REMOVED

THESE PLANS ARE BASED UPON THE EXISTING CONDITIONS SURVEY PREPARED BY ASTREA, REFERENCE No ADAS REV B DATED 18 OCTOBER 2023.

THESE DESIGN PLANS SHALL BE READ IN CONJUNCTION WITH GEOTECHNICAL REPORT No. 1000000-010-000-000 DATED 17 NOVEMBER 2023 PREPARED BY WSP. THE PROVISIONS AND RECOMMENDATIONS CONTAINED WITHIN THE REPORT ARE TO BE STRICTLY COMPLIED WITH. ALL COMPARISON REQUIREMENT RESULTS SHALL BE CARRIED OUT IN ACCORDANCE WITH GEOTECHNICAL REPORT RECOMMENDATIONS.



WARNING
PROPOSED SERVICES
THE LOCATION AND EXTENT OF PROPOSED SERVICES IS INDICATIVE ONLY AND ARE NOT TO BE USED FOR CONSTRUCTION. REFER TO AUTHORISED DOCUMENTATION BY RELEVANT AUTHORITY FOR CONSTRUCTION DETAILS.

WARNING
BEWARE OF UNDERGROUND SERVICES
THE LOCATIONS OF UNDERGROUND SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.

NO.	DESCRIPTION	BY	CHKD	DATE
1	REV. SCHEMATIC DESIGN	D.H.	G.P.	12/12/23
2	REV. SCHEMATIC DESIGN	D.H.	G.P.	14/12/23
3	TENDER ISSUE	D.H.	G.P.	21/02/24
4	TENDER ISSUE	D.H.	G.P.	26/02/24
5	TENDER ISSUE	D.H.	G.P.	10/03/24



MEINHARDT
Meinhardt Infrastructure and Environment PTY. LTD.
A.C.N. 001 827 981
Level 40, 100 Victoria Street
Sydney NSW 2000
P +61 2 9291 7900
F +61 2 9291 7901
www.meinhardt.com.au
info@meinhardt.com.au


NSW
School Infrastructure NSW
TITLE
CIVIL SITEWORKS PLAN

PROJECT
GREENWAY PARK PUBLIC SCHOOL
WYATTVILLE DRIVE, CARNES HILL NSW 2171
STATUS
TENDER ISSUE
NOT TO BE USED FOR CONSTRUCTION
DRAWN
M.D.
DESIGNED
G.P.
CHECKED
Y.C.
APPROVED
DATE
12/02/24
SCALE @ A1
1:200
PROJECT NO.
132565
GPPS-MHT-00-00-DR-C-0101
REV.
T3


Impact Assessment Plan

LEGEND	
L&Co Legend	
	Major Encroachment Tree removal may be required
	TPZ encroachment
	TPZ
	Tree removal required
	Tree retained

LEGEND	
ITEM	DESCRIPTION
	DOWNPIPE
	INSPECTION OPENING
	TRENCH GRATE
	OVERLAND FLOW ARROW
	EXISTING SEWER
	EXISTING GAS
	EXISTING WATER
	EXISTING RECYCLED WATER
	EXISTING ELECTRICITY
	EXISTING OVERHEAD ELECTRICITY
	EXISTING LOW VOLTAGE ELECTRICITY
	EXISTING HIGH VOLTAGE ELECTRICITY
	EXISTING TELECOM CABLE
	EXISTING FIBRE OPTIC CABLE
	EXISTING NBN COMMS CABLE
	EXISTING FEATURES TO BE REMOVED



ITEM	DESCRIPTION	BY	DATE	DATE
1	100% Schematic Design Issue - RFP	M.D.	1/12	20/12/23
2	100% Schematic Design Issue	M.D.	1/12	19/12/23



ITEM	DESCRIPTION	BY	DATE	DATE
1	100% Schematic Design Issue - RFP	M.D.	1/12	20/12/23
2	100% Schematic Design Issue	M.D.	1/12	19/12/23

ITEM	DESCRIPTION	BY	DATE	DATE
1	100% Schematic Design Issue - RFP	M.D.	1/12	20/12/23
2	100% Schematic Design Issue	M.D.	1/12	19/12/23

ITEM	DESCRIPTION	BY	DATE	DATE
1	100% Schematic Design Issue - RFP	M.D.	1/12	20/12/23
2	100% Schematic Design Issue	M.D.	1/12	19/12/23

ITEM	DESCRIPTION	BY	DATE	DATE
1	100% Schematic Design Issue - RFP	M.D.	1/12	20/12/23
2	100% Schematic Design Issue	M.D.	1/12	19/12/23

ITEM	DESCRIPTION	BY	DATE	DATE
1	100% Schematic Design Issue - RFP	M.D.	1/12	20/12/23
2	100% Schematic Design Issue	M.D.	1/12	19/12/23

ITEM	DESCRIPTION	BY	DATE	DATE
1	100% Schematic Design Issue - RFP	M.D.	1/12	20/12/23
2	100% Schematic Design Issue	M.D.	1/12	19/12/23



WARNING
PROPOSED SERVICES
THE LOCATION AND EXTENT OF PROPOSED SERVICES IS INDICATIVE ONLY AND ARE NOT TO BE USED FOR CONSTRUCTION. REFER TO AUTHORIZED DOCUMENTATION BY RELEVANT AUTHORITY FOR CONSTRUCTION DETAILS.

WARNING
BEWARE OF UNDERGROUND SERVICES
THE LOCATIONS OF UNDERGROUND SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.

THESE PLANS ARE BASED UPON THE EXISTING CONDITIONS SURVEY PREPARED BY ASTREA, REFERENCE NO. A5488 REV B DATED 15 OCTOBER 2023.

THESE DESIGN PLANS SHALL BE READ IN CONJUNCTION WITH GEOTECHNICAL REPORT No. P2006262-010-01-01-01 DATED 17 NOVEMBER 2023 PREPARED BY WSP. THE PROVISIONS AND RECOMMENDATIONS CONTAINED WITHIN THE REPORT ARE TO BE STRICTLY COMPLIED WITH ALL COMPACTION REQUIREMENT RESULTS SHALL BE CARRIED OUT IN ACCORDANCE WITH GEOTECHNICAL REPORT RECOMMENDATIONS.

MEINHARDT
Meinhardt Infrastructure and Environment PTY. LTD.
A.C.N. 001 827 581
Level 40, 100 Victoria Street
Sydney NSW 2000
P +61 2 9250 0000
F +61 2 9250 0700
info@meinhardt.com.au
www.meinhardt.com.au

NSW
School Infrastructure NSW

PROJECT
GREENWAY PARK PRE SCHOOL
WYATTVILLE DRIVE, CARNES HILL NSW 2171

FILE
CIVIL SITEWORKS PLAN
SHEET 1

STATUS
SCHEMATIC DESIGN
NOT TO BE USED FOR CONSTRUCTION

DRAWN	DESIGNED	CHECKED	APPROVED	DATE	SCALE
M.D.	G.P.	Y.C.			1:100
PROJECT NO.	DRAWING NO.	REV.			
132565	GPPS-MHT-00-00-DR-C-1101				P2

ELECTRICAL DISTRIBUTION BOARD (EDB)
(PROPOSED NEW)
NOMINAL LOCATION OF SUBMAIN CONDUIT ENTRY POINT TO BLOCK J. SEE POWER AND COMMUNICATIONS ARRANGEMENTS FOR DETAILS.

BUILDING COMMUNICATIONS ROOM (BCR)
(PROPOSED NEW)
SEE BLOCK J POWER AND COMMUNICATIONS ARRANGEMENTS FOR DETAILS.

Impact Assessment Plan

L&Co Legend

- ✓ Major Encroachment Tree removal may be required
- SRZ
- TPZ encroachment
- TPZ
- ✓ Tree removal required
- ✓ Tree retained

WALKWAY & PATH LIGHTING
(PROPOSED NEW)
LIGHTING TO BE PROVIDED ALONG THE ENTIRE LENGTH OF THE NEW EXTERNAL WALKWAYS

MAIN COMMUNICATIONS ROOM (MCR)
(EXISTING - TO BE RETAINED)
THE MCR IS LOCATED WITHIN BLOCK D. ONE COMMUNICATIONS CABINET ACCOMMODATES CAMPUS DISTRIBUTION. NEW 45 RU x 800 x 1000 RACK TO BE PROVIDED. THE EXISTING TELSTRA LEAD IN FROM WYATTVILLE DRIVE COMPLIES WITH DSE ICT REQUIREMENTS. NO UPGRADES TO LEAD IN REQUIRED.



FOR IMPLEMENTATION OF THE SHIRAZ MCR KIT OF PARTS, NOTE THE FOLLOWING:
INTELLECTUAL PROPERTY
Refer to SHIRAZ MCR Kit of Parts - Introduction, Copyright and Disclaimer
AGREEMENT OF USE
Refer to SHIRAZ MCR Kit of Parts - Introduction, Copyright and Disclaimer
SHIRAZ CONTACT
Refer to SHIRAZ MCR Kit of Parts - Introduction, Copyright and Disclaimer


NSW Education School Infrastructure
SCHOOL INFRASTRUCTURE NEW SOUTH WALES
www.schoolinfrastructure.nsw.gov.au

1:500 @ A1

NDY
NORTH DRY
LEVEL 15, 50 ARTHUR ST
NORTH SYDNEY NSW 2060
AUSTRALIA
T +61 2 9558 8800
F +61 2 9558 8800
www.ndy.com.au

fulton trotter
ARCHITECTS
SUITE 104, LEVEL 10, 28-30 FORDHAM STREET
SUNSHINE HILLS, SYDNEY NSW 2033 Australia
T +61 2 8353 5333 W www.fultontritter.com.au

RP INFRASTRUCTURE
Connecting visions to reality



REV **BY** **DATE** **DESCRIPTION**
1. CG 11/10/2014 CONCEPT DESIGN
2. CG 24/10/2014 CONCEPT DESIGN
3. CG 26/10/2014 SCHEMATIC DESIGN
4. CG 11/10/2014 SCHEMATIC DESIGN
5. CG 10/10/2014 SCHEMATIC DESIGN
6. CG 26/10/2014 SCHEMATIC DESIGN
7. CG 26/10/2014 SCHEMATIC DESIGN

PROJECT NAME
SHIRAZ GREENWAY PARK PUBLIC SCHOOL UPGRADE
WYATTVILLE DR, CARNES HILL NSW 2171
SITE

DRAWING TITLE
ELECTRICAL SERVICES
SITE PLAN

PROJECT NO.
759-0720-0041153-0001
DATE
28/02/2025
SCALE
1:500 @ A1
DRAWING NO.
GPSS-NDY-00-00-DR-E-001011
REV
7

BUILDING COMMUNICATIONS ROOM (BCR)
(PROPOSED NEW)
SEE PRESCHOOL POWER AND COMMUNICATIONS ARRANGEMENTS FOR DETAILS.


ELECTRICAL DISTRIBUTION BOARD (EDB)
(PROPOSED NEW)
NOMINAL LOCATION OF SUBMAIN CONDUIT ENTRY POINT TO PRESCHOOL. SEE POWER AND COMMUNICATIONS ARRANGEMENTS FOR DETAILS.

MAIN SWITCHBOARD (MSB)
(EXISTING - TO BE DEMOLISHED)
INDICATIVE LOCATION OF EXISTING MAIN SWITCHBOARD TO BE DISCONNECTED AND REMOVED. ALL EXISTING OUTGOING SUBMANS ARE TO BE RETAINED FOR CONNECTION TO NEW MSB.



MAIN SWITCHBOARD (MSB)
(PROPOSED NEW)
EXTERNAL MAIN SWITCHBOARD TO BE PROVIDED GENERALLY IN SITU WITH EXISTING BOARD TO BE 650A RATED WITH CIRCUIT BREAKERS PROVIDED FOR ALL EXISTING LOADS AND ALL NEW LOADS.

AUTHORITY SUBSTATION (SUBVA)
(EXISTING - TO BE RETAINED)
INDICATIVE LOCATION OF EXISTING ENDEAVOUR ENERGY SUBSTATION S28507 TO BE RETAINED. TOTAL LOAD OF 400 AMP PER PHASE APPROVED BY ENDEAVOUR ENERGY FOR SCHOOL USE. PENDING DEPARTURE FROM 15% SPARE CAPACITY REQUIRED BY EFSSO. EXISTING CONSUMER MAINS DO NOT HAVE A CURRENT RATING SUITABLE FOR PROPOSED WORKS. EXISTING SPARE CONDUIT TO BE USED TO UPGRADE MAINS TO PARALLEL SET.




GENERAL NOTE
NEW POWER, SECURITY AND COMMUNICATIONS PITS TO BE PROVIDED EVERY 50M OR IN CHARGE OF DIRECTION OF CONDUIT RETICULATION ROUTE.

Impact Assessment Plan


L&Co Legend

- Major Encroachment Tree removal may be required
- SRZ
- TPZ encroachment
- TPZ
- Tree removal required
- Tree retained



NOTES:
1. ALL WATER AND FIRE PIPES TO HAVE MINIMUM 600mm COVER TO TOP OF PIPE.

Rev	Description	Date	By	App'd
E	100% SCHEMATIC DESIGN (UPDATES)	18.03.25	GB	RE
D	100% SCHEMATIC DESIGN (UPDATES)	18.03.25	GB	RE
C	100% SCHEMATIC DESIGN (UPDATES)	18.03.24	GB	RE
B	100% SCHEMATIC DESIGN (UPDATES)	18.03.24	GB	RE
A	100% SCHEMATIC DESIGN (UPDATES)	18.03.24	GB	RE
1	100% SCHEMATIC DESIGN (UPDATES)	18.03.24	GB	RE



Client: FULTON TROTTER ARCHITECTS
Address: SUITE 904, LEVEL 9, 28-36 FIVEAUX STREET, SURRY HILLS NSW 2010
T: 02 8383 5151 E: sydney@fultontritter.com.au

Project: SCHOOL INFRASTRUCTURE NSW
GREENWAY PARK PUBLIC SCHOOL
WYATTVILLE DRIVE, CARNES HILL, NSW
SCHEMATIC DESIGN



ACOR Consultants Pty Ltd
Suite 2, Level 1, 33 Herbert Street
St Leonards NSW 2065
T: +61 2 9438 5098

Drawn: GB
Designed: RE
Checked: RE
Date: 18.03.25
Scale: 1:500
Sheet: 1 of 1

Project No: NA230221
Drawing No: GPPS-ACOR-00-00-DR-H-1200


Impact Assessment

L&Co Legend

- Major Encroachment Tree removal may be required
- SRZ
- TPZ
- TPZ encroachment
- Tree Number
- Tree removal required
- Tree retained

PAVEMENT LEGEND

- LIGHT DUTY CONCRETE PAVEMENT-PEDESTRIAN
- MEDIUM DUTY ASPHALT PAVEMENT
- VEHICLE CROSSING REFER TO COUNCIL STANDARD DRAWINGS FOR PAVEMENT DETAILS
- LANDSCAPING AND NATURE STRIP AREA REFER TO ARCHITECT DRAWINGS FOR LOCATIONS
- KERB RAMP REFER TO COUNCIL STANDARD DRAWING FOR PAVEMENT DETAILS



WARNING PROPOSED SERVICES

THE LOCATION AND EXTENT OF PROPOSED SERVICES IS INDICATIVE ONLY AND ARE NOT TO BE USED FOR CONSTRUCTION. REFER TO AUTHORISED DOCUMENTATION BY RELEVANT AUTHORITY FOR CONSTRUCTION DETAILS.

WARNING

BEWARE OF UNDERGROUND SERVICES
THE LOCATIONS OF UNDERGROUND SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.

NO.	DESCRIPTION	BY	CHKD	DATE	DATE
1	ISSUE TO SCHEMATIC DESIGN ISSUE - RFP	D.H.	M.O.	1/12	28/12/20
2	ISSUE TO SCHEMATIC DESIGN ISSUE	D.H.	M.O.	1/12	28/12/20


0 1 2 3 4 5m
SCALE 1:100 AT ORIGINAL SIZE (A1)

MEINHARDT
Meinhardt Infrastructure and Environment PTY. LTD.
A.C.N. 691 827 581
Level 4, 400 Victoria Street
Sydney NSW 2000
Phone
1 811 2000 000
P 612 2318 7510
info@meinhardt.com.au
info@meinhartinfrastructure.com.au

NSW
School Infrastructure NSW
STATE
PAVEMENT PLAN
SHEET 1

PROJECT
GREENWAY PARK PRE SCHOOL
WYATTVILLE DRIVE, CARNES HILL NSW 2171
STATUS
SCHEMATIC DESIGN
NOT TO BE USED FOR CONSTRUCTION
DRAWN
M.D.
DESIGNED
G.P.
CHECKED
Y.C.
APPROVED
DATE
1/10/21
SCALE & A1
P2


11.0 APPENDIX 6 | TREE RETENTION/REMOVAL PLAN







12.0 APPENDIX 7 | TREE PROTECTION PLAN









13.0 APPENDIX 8 | TYPICAL TREE PROTECTION DETAIL

Tree Protection Detail - TPZ Fencing




Tree Protection Detail - Ground Protection

Required if temporary access for machinery is required within the TPZ to protect roots and prevent soil compaction.



Tree Protection Detail - Scaffolding within TPZ



14.0 APPENDIX 9 | TREE PROTECTION SPECIFICATION

14.1 Appointment of Project Arborist

14.2 Prior to commencement of works a Project Arborist should be engaged to monitor compliance with the protection measures. The Project Arborist will inspect tree protection measures and prepare a compliance certification for the principal certifying authority prior to the release of compliance certification. Contractors and site workers are to receive these specifications at least 3 days prior to commencing works. Contractors and site workers working within the TPZ should sign the site log confirming they have read and understood these specifications prior to commencing works.

14.3 Compliance

14.4 The Project Arborist will conduct regular site visits to certify the works are compliant with this specification. A compliance document will be prepared by the Project Arborist following each site inspection. The compliance document will include evidence of compliance with the tree protection measures detailed in this specification.

14.5 Tree & Vegetation Removal

14.6 Tree and vegetation removal will be undertaken prior to installation of tree protection measures. Tree removal works should be undertaken in accordance with the *Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal Work* (2016).

14.7 Tree and vegetation removal must not damage trees to be retained.

14.8 Tree Protection Zone

14.9 Trees that are to be retained must be protected prior to and during construction from works that could negatively impact their health and structural integrity. The following works should not occur within the TPZ unless authorised by the Project Arborist:

- Modification of existing soil levels, excavations and trenching
- Mechanical removal of vegetation
- Movement of naturally occurring rock
- Storage of materials, plant/equipment and building of sheds
- No signage or hoarding shall be fixed to the trees
- Preparation of building materials, refuelling or disposal of waste materials and chemicals
- No lighting of fires
- No pedestrian or vehicular traffic
- Temporary or permanent location of services, or works required for their installation
- Any other activities that may damage the tree

- 14.11 Tree Protection Fencing
- 14.12 The TPZ fencing must be positioned at the perimeter of the TPZ and may be combined to form a single area where the TPZs of multiple trees overlap. The approximate location of the TPZ fencing is outlined in the Arboricultural Impact Assessment with the exact location determined by consultation between the Principal Contractor/Project Manager and the Project Arborist prior to the commencement of works. Fencing may be setback to allow for demolition/construction access and for the installation of pavements only where appropriate ground protection is installed and approved by the Project Arborist. The TPZ fencing must be at least 1.8m above grade and made of wire mesh panels that are supported by concrete feet and fastened together to prevent sideways movement. Tree damage, including any low branches, must be avoided during the installation of the tree protection fencing. The TPZ fencing must include signage to identify the TPZ fencing and include the Project Arborist contact details.
- 14.13 Site Management
- 14.14 Materials, waste storage and temporary services should not be located within the TPZ.
- 14.15 Works within the Tree Protection Zones
- 14.16 In certain situations, works within the TPZ may be authorised by the determining authority. These works must be supervised by the Project Arborist. When working within the TPZ, special care should be taken to avoid damage to the tree's root system, trunks and lower branches.
- 14.17 If roots (>25mmØ) are encountered during excavation, demolition and construction works, these roots must be retained undamaged and advice sought from the Project Arborist. The design and final levels must remain flexible to enable the retention of roots >25mmØ where deemed necessary by the Project Arborist.
- 14.18 Ground Protection
- 14.19 The movement of machinery should be restricted to existing paved areas or in areas with temporary ground protection (i.e. steel road plates, ground mats) when deemed necessary by the Project Arborist.
- 14.20 Ground protection should be installed as per AS4970 and Appendix 7- *Typical Tree Protection Detail*.
- 14.21 If irrigation is considered necessary, it should be installed first and by a licensed irrigator under the supervision of the Project Arborist with no trenching.
- 14.22 The irrigation should be covered with a layer of geotextile and mulched to a depth of 100mm with a non-toxic product (i.e. woodchips) with no fines.
- 14.23 Once the irrigation, geotextile and mulch are in place then the ground protection boards (steel plates or rumble boards) can in be installed.
- 14.24 Boards should remain in place for the entire build.
- 14.25 Trunk & Branch Protection
- 14.26 If trunk protection is required it should be installed by wrapping the trunk and first order branching with padding (i.e. carpet underlay or 10mm thick geotextile) to a minimum height of 2m. Timber battens (90 x 45mm), spaced at 150mm centres should be strapped together and placed over the padding (Refer to AS4970 for further details).
- 14.27 Branch protection should be installed when considered necessary by the Project Arborist.
- 14.28 Branches should be wrapped with padding (i.e. Ableflex) to provide protection. Where possible, branches should be tied back and construction works to take place around branches (with appropriate branch protection installed as required). If pruning is unavoidable it should be in accordance with AS4373 and supervised by the Project Arborist.
- 14.29 Structure & Pavement Demolition
- 14.30 The Project Arborist should supervise the demolition of existing structures/pavement within the TPZ. Machinery is to be excluded from the TPZ unless operating from existing slabs, pavements or areas of ground protection. Machinery should not contact the tree's roots, trunks, branches and crown.
- 14.31 Existing pavement should be hand lifted to minimise disturbance to the existing sub-base and to prevent damage to tree roots. Wherever possible, the existing sub-base material should remain in situ.
- 14.32 When removing slab sections within the TPZ, machinery must work from the tree outwards to ensure the machinery always remains on the un-demolished section of slab. Wherever possible, footings or elements below grade should be retained to minimise disturbance to the tree's roots.
- 14.33 Structures must be shattered with hand-operated pneumatic/electric breaker before removal when considered necessary by the Project Arborist.
- 14.34 If roots (>25mmØ) are encountered during excavation, demolition and construction works these roots must be retained undamaged and advice sought from the Project Arborist. Exposed roots must be protected from direct sunlight, drying out and extremes of temperature by using 10mm thick jute geotextile fabric. This fabric should be kept moist at all times.
- 14.35 Where the Project Arborist determines that the tree is using underground elements (i.e. footings, pipes, rocks etc.) for support, these elements should be left *in situ*.
- 14.36 Pavement/Kerb Installation

- 14.37 Installation of pavements and sub-base within the TPZ must be supervised by the Project Arborist. New surfaces and sub-base materials should be placed above grade to minimise excavations and retain roots (unless prior root mapping has determined that there are no roots within the area of construction).
- 14.38 If roots (>25mmØ) are encountered during the installation of the new sub-base and surfaces these roots must be retained undamaged and advice sought from the Project Arborist. The design and final levels must remain flexible to enable the retention of roots >25mmØ where deemed necessary by the Project Arborist.
- 14.39 Compaction of the ground prior to the installation of fill is not permitted.
- 14.40 New sub-base material should be a 20mm no-fines road base (i.e. Benedict Sand & Gravel- Product Code 20NF/RB or similar). Recycled concrete aggregates should not be used to avoid raising soil pH levels.
- 14.41 If required, bedding sand should be washed river sand (no crushed paving blends). The bedding sand should be consolidated with a pedestrian operated plate compactor only. If possible, pavement material should be permeable.
- 14.42 Kerbs within the TPZ should be modified to bridge roots (>25mmØ) unless root pruning is approved and undertaken by the Project Arborist.
- 14.43 Underground Services
- 14.44 The installation of underground services should be located outside of the TPZ. Where this is not possible they should be installed around or below roots (>25mmØ) using either hydrovac or hand excavation and supervised by the Project Arborist.
- 14.45 Boring methods may be used for the installation of services 800mm below grade. Excavations for starting and receiving pits for the boring equipment should be located outside of the TPZ or located to avoid roots (>25mmØ, or determined by the Project Arborist).
- 14.46 Excavations, Root Protection & Root Pruning
- 14.47 Excavations and root pruning within the TPZ must be supervised by the Project Arborist and should be avoided where possible.
- 14.48 No over-excavation, battering, or benching should be undertaken beyond the footprint of any structure unless approved by the Project Arborist. Hand excavation and root pruning along the excavation line should be completed prior to the commencement of mechanical excavation to prevent tearing and shattering damage to the roots.
- 14.49 Roots >25mmØ should be pruned by the Project Arborist only. Roots <25mmØ may be pruned by the Principal Contractor. Root pruning should be undertaken with clean, sharp secateurs or a pruning saw to ensure a smooth wound face, free from tears.
- 14.50 Damaged roots should be pruned behind the damaged tissues with the final cut made to the undamaged part of the root.

15.0 APPENDIX 10 | MITIGATION MEASURES

Mitigation Number/ Name	When is Mitigation Measure to be complied with	Mitigation Measure	Reason for Mitigation Measure
Project Arborist	Engage at start of construction prior to CC.	Project Arborist to oversee tree protection measures and ensure compliance.	Ensure compliance with tree protection measures to retain trees.
Tree Removal	Prior to demolition	Removal works should be carried out by a practising arborist. The practising arborist should hold a minimum qualification equivalent (using Australian Qualifications Framework) of Level 3 or above in arboriculture or its recognised equivalent. The practising arborist should have a minimum of 3 years of practical experience. Removal works should be undertaken in accordance with the Australian Standard 4373: Pruning of Amenity Trees (2007), Safe Work Australia Guide for Managing Risks of Tree Trimming and Removal Work (2016) and other applicable legislation and codes.	Safe removal of correct trees.
Tree Protection Fencing & sediment control	Prior to demolition	TPZ fencing should be installed parallel to the proposed building line prior to any site works (including demolition) and remain in place for the duration of the construction. Coir logs should be installed inside of the TPZ fencing to prevent material runoff into the TPZ. Materials, waste storage and temporary services should not be located within the TPZ fenced area. If works are required within the TPZ fenced area, then they should be supervised by the Project Arborist. The tree protection measures must be inspected by the Project Arborist prior to the start of site works, including demolition.	Retain trees and mitigate construction impacts.
Replacement Trees	Post construction	Replacement tree planting should be provided when trees are removed. Replacement trees should be supplied as advanced size stock to help offset the loss of amenity resultant from the tree removals. Replacement planting should be supplied in accordance with Australian Standard 2303: Tree Stock for Landscape Use (2015).	Replace the loss of amenity

16.0 APPENDIX 11 | PLATES



a) Showing Tree 30. b) Showing Tree 37. c) Showing Tree 39. d) Showing Trees 63 & 64. e) Showing Trees 71 & 65. f-g) Showing Tree 75.

17.0 APPENDIX 11 | LIMITATIONS & DISCLAIMERS

- 17.1 Subject trees were assessed from the ground only and for providing an Arboricultural Impact Assessment and Tree Protection Report.
- 17.2 All recommendations in this Arboricultural Impact Assessment and Tree Protection Report report are based on the observations made on the day of inspection (02.11.2023 & 20.02.2025). There is no warranty, expressed or implied, that problems or deficiencies relating to the subject trees, or the subject site may not arise in the future.
- 17.3 Laurence & Co Consultancy takes care to obtain information from reliable sources. However, Laurence & Co Consultancy can neither guarantee nor be responsible for the accuracy of information provided by others. Plans, diagrams, graphs and photographs in this Arboricultural Impact Assessment and Tree Protection Report report are visual aids only and are not necessarily to scale. This report provides recommendations relating to tree management only. Advice should be sought from appropriately qualified consultants regarding design/construction/ecological/heritage etc. issues.
- 17.4 This report has been prepared for exclusive use by the client. This report should not be viewed by others or for any other reason outside its intended target or without the prior written consent of Laurence & Co Consultancy. Unauthorised alteration or separate use of any section of the report invalidates the report.
- 17.5 Many factors may contribute to tree failure and cannot always be predicted. Laurence & Co Consultancy takes care to accurately assess tree health and structural condition. However, a tree's internal structural condition may not always correlate to visible external indicators.
- 17.6 **Limitation of Liability.** Laurence & Co Consultancy shall be liable only for direct damages that result from negligence or wilful misconduct in the performance of its services. Under no circumstances shall Laurence & Co Consultancy be liable for indirect, consequential, special, or punitive damages, or for damages caused by the client's failure to perform its obligations under law or contract. Laurence & Co Consultancy shall not be liable for and Client shall indemnify Laurence & Co Consultancy from and against all claims, demands, liabilities and costs (including attorneys' and expert fees) arising out of or in any way related to our performance or non-performance of services, including all on-site activities except to the extent caused by Laurence & Co Consultancy's negligence or wilful misconduct. In no event shall Laurence & Co Consultancy's liability exceed the amount paid to Laurence & Co Consultancy by the Client for our professional services (net of reimbursable expenses) and Client specifically releases Laurence & Co Consultancy for any damages, claims, liabilities and costs in excess of that amount.
- 17.7 Reference should be made to any relevant legislation including Tree Management Controls. All recommendations contained within this report are subject to approval from the relevant Consent Authority.