

INTEGRATED WATER CYCLE MANAGEMENT REPORT

ROSEBANK COLLEGE

121 Parramatta Road, Five Dock, NSW 2046

Date: 22 May 2020
Revision: 2
Issue: 1
Ref. No.: 20096_C_RPT_IWCM

Prepared for: Midson Group Pty Ltd

Client Details: James Trevena
Email: jtrevena@midsongroup.com.au
Phone: (02) 9868 6923

Disclaimer

This specification (including any enclosures and attachments) has been prepared for the exclusive use and benefit of the addressee(s) and solely for the purpose for which it is provided. Unless we provide express prior written consent, no part of this report should be reproduced, distributed or communicated to any third party. We do not accept any liability if this report is used for an alternative purpose from which it is intended, nor to any third party in respect of this report.

Document Control

Revision	Date	Description	Prepared	Reviewed	Approved
1	15.05.20	Preliminary Issue	JK	BB	BB
2	22.05.20	DA Issue	JK	BB	BB

Prepared by	John Kokkinos	Revision	2
Approved by	Benjamin Barrett	Revision	2

TABLE OF CONTENTS

1.	EXECUTIVE SUMMARY	1
2.	INTRODUCTION	2
2.1	Existing Site.....	2
2.2	Proposed Development.....	3
3.	INTEGRATED WATER MANAGEMENT.....	4
3.1	General.....	4
3.2	Rainwater Reuse	4
3.3	Stormwater Quality	5
3.4	Stormwater Quantity	6
3.5	Maintenance and Monitoring.....	6
	CONCLUSION	7
APPENDIX A.	CONCEPT DRAINAGE PLANS.....	8
APPENDIX B.	MAINTENANCE & MONITORING SCHEDULE	9

1. EXECUTIVE SUMMARY

Sparks & Partners have been engaged by Midson Group Pty Ltd to provide civil engineering services to support the proposed Development Application for Rosebank College, Five Dock. The engineering services include the design and documentation of the stormwater drainage infrastructure for the proposed development.

City of Canada Bay Council (CCB) are the approval authority for the proposed development. An Integrated Water Cycle Management Plan be prepared that takes into consideration the objectives and controls under Appendix 2 of the City of Canada Bay Development Control Plan 2017 (CCBDP). In response to this requirement Sparks and Partners has undertaken modelling of the proposed integrated water management measures and prepared this report to demonstrate that the proposed development identifies and incorporates water conservation and stormwater management measures into its design and operation in accordance with the requirements of Appendix 2 of the CCBDP.

2. INTRODUCTION

2.1 Existing Site

The existing Rosebank College at 121 Parramatta Road, Five Dock currently occupies a total site area of 20,824m² and consist of seven (7) permanent school buildings, several demountable buildings, an existing chapel, hardstand, car parking areas and landscaping. The site is currently developed where majority of the site is occupied by impervious surfaces such as building roofs or hardstand. The site bound by Parramatta Road along its Southern boundary, Harris Road along its Eastern Boundary, Queens Road along its Northern boundary, and neighbouring industrial warehouses along its Western Boundary. The site consists of a gradual fall from the Eastern boundary Western boundary, with the South Western boundary corner being the lowest point. The site is accessible from all three roads. Existing stormwater drainage is located near the North Western boundary corner and along the Southern boundary.



Figure 1. Existing Site – Aerial Image (Source: Six Maps)

2.2 Proposed Development

The proposed development occupies a total site area of 2,704m² within Rosebank College and consists of one (1) new building, located within the South Eastern boundary corner, utilising a small portion of the existing carpark. The new building occupies 2,317m² of the site area and consists of a stormwater drainage network connecting into the existing stormwater drainage towards the Southern boundary. The existing carpark accompanying the development occupies 356m² of the site and will drain into the existing stormwater drainage, whilst 72m² of impervious hardstand throughout the developing site area is considered as stormwater bypass.



Figure 2. Proposed Development – Aerial Image (Source: Six Maps)

3. INTEGRATED WATER MANAGEMENT

3.1 General

The objective of integrated water management is to provide a strategy that brings together the different aspects of the water cycle as a whole rather than an ad hoc approach to water management. This includes the management aspects of freshwater, wastewater and stormwater. The following integrated water management strategies have been considered and addressed for the proposed development:

1. Employ an integrated water collection and recycling system for capturing and recycling roofwater;
2. Control the quality of stormwater that is disposed from the site;
3. Control the quantity of stormwater that is discharged for the site.

To demonstrate the above concept stormwater drainage plans and associated details have been prepared along with detailed modelling using the Council endorsed MUSIC software package. The concept stormwater drainage plans detail the location of the water management infrastructure including pits, pipes, dish drains, grated trench drains, pump out pit, OSD, rainwater tank, OceanGuards and Stormfilters, and are included in Appendix A.

3.2 Rainwater Reuse

Through the reuse of collected roofwater for non-potable reuse the proposed demand on potable water resources is reduced. The proposed development will capture roof water from part of the building roof area (979m²). This collected roofwater will be conveyed to an 12,000 litre tank for storage and reuse throughout the development. Re-use purposes will primarily include toilet flushing and irrigation uses. A water balance of the proposed reuse system has been completed to model the effectiveness and efficiency of the system. The water balance model was constructed using the MUSIC software package with the following inputs:

- Total approximate non-potable reuse based on:
 - Toilet reuse of 0.1kL/day/toilet for 4 days per week (to account for weekends, public and school holidays) for the 5 proposed toilets. This results in a daily demand of 0.1 kL/toilet/day x 5 toilets x 4/7 days per week = 0.29kL/day.
 - 395m² or irrigated area requiring 0.4kL/m²/year resulting in an annual demand of 158kL/yr.

Using the above determined non-potable demand the MUSIC model determines the rainwater tank has an approximate efficiency of 83%. This efficiency results in an approximate reduction in the proposed demand on potable water supplies of 213,000 litres per year.

3.3 Stormwater Quality

To ensure the quality of stormwater leaving the site is acceptable and meets council's requirements specific water quality treatment measures are to be employed. These treatment measures are to treat the collected stormwater runoff prior to discharge to the council drainage system located in Parramatta Road. The treatment measures consist of a Rainwater reuse tank, Ocean Protect OceanGuard and Stormfilters. The combination of these measures provides a treatment train approach to the treatment of stormwater runoff.

Modelling of the proposed treatment measures has been undertaken using the MUSIC software package version 6. The modelling inputs have been based on the pollutant loads within the NSW MUSIC Modelling Guidelines August 2015. The modelling results of the water quality achieved for the site is detailed in Table 1 – MUSIC Model Results below, along with a figure of the prepared model.

	Source Load	Residual Load	% Reduction Achieved	CCB % Reduction Requirement	Compliance with CCB Requirement
Total Suspended Solids (kg/yr)	232	45.6	80.3	80	Y
Total Phosphorus (kg/yr)	0.697	0.241	65.4	45	Y
Total Nitrogen (kg/yr)	7.42	4.07	45.1	45	Y
Gross Pollutants (kg/yr)	82.4	1.96	97.6	70	Y

Table 1. MUSIC Model Results




Figure 3. MUSIC Model Results

3.4 Stormwater Quantity

The proposed development requires the implementation of on-site detention (OSD) as per the CCB Engineering Guide for Development to control stormwater discharge from the site. The proposed development has an approximate area of 97.4% draining to the proposed on-site detention (OSD) facility which includes pavement (356m²) and roof (2,317m²) areas. A catchment plan of the proposed development is included in the Appendix A.

The CCBDCP required a Catchment Method is used to calculate the OSD volume and Permissible Site Discharge for the development. Based on the above catchment areas the storage required for the proposed development is approx. 48.3m³ with a maximum discharge of 48.1L/sec. Refer to the design summary on DA1.02 located in the Appendix A for review.

3.5 Maintenance and Monitoring

To ensure the continued efficient and correct operation of the proposed integrated water management infrastructure a 'maintenance and monitoring schedule' is included in the Appendix B of this plan. The schedule details the frequency of inspections, what is to be inspected and what rectifications to make if required for the water management infrastructure located within the proposed development. The schedule is to be implemented upon commissioning of the water management infrastructure and remain in place for the life of the development; with all records kept on site for inspection should the approval authority deem it necessary.


CONCLUSION

Based on the preparation of the concept stormwater drainage plans and MUSIC modeling results it is demonstrated that the principles of integrated water management have been incorporated into the design and operation of the proposed development at Rosebank College Five Dock in accordance with CCBDCP 2017 Appendix 2. It is demonstrated that the proposed development achieves reductions in potable water import by capturing rainwater on site and reusing this for non-potable uses including irrigation and toilet flushing, achieves pollution reduction targets set by council, and employs OSD for the control of stormwater discharge from the site in accordance with targets set by council. It is also demonstrated that the proposed development will continue to operate effectively and efficiently through the implementation and use of a monitoring and maintenance schedule ensuring the integrity of the system is maintained.

APPENDIX A. CONCEPT DRAINAGE PLANS

ROSEBANK COLLEGE EXTENSION


CONCEPT STORMWATER MANAGEMENT



DRAWING SCHEDULE

- DA1.01 COVER PAGE, LOCALITY PLAN & DRAWING SCHEDULE
- DA1.02 SPECIFICATION NOTES
- DA2.01 EROSION & SEDIMENT CONTROL PLAN SHEET 1
- DA2.02 EROSION & SEDIMENT CONTROL PLAN SHEET 2 AND DETAILS
- DA4.01 CONCEPT STORMWATER MANAGEMENT PLAN SHEET 1
- DA4.02 CONCEPT STORMWATER MANAGEMENT PLAN SHEET 2
- DA4.05 CONCEPT STORMWATER CATCHMENT PLAN
- DA4.11 STORMWATER MANAGEMENT DETAILS SHEET 1
- DA4.12 STORMWATER MANAGEMENT DETAILS SHEET 2
- DA4.13 STORMWATER MANAGEMENT DETAILS SHEET 3

LOCALITY PLAN
NOT TO SCALE - COURTESY OF SIX MAPS



DATE	AMENDMENT	INIT	REV	DATE	AMENDMENT	INIT	REV
07.05.20	ISSUED FOR COORDINATION	JK	1				
15.05.20	PRELIMINARY ISSUE	JK	2				
22.05.20	DA ISSUE	JK	3				

DATE	AMENDMENT	INIT	REV	DATE	AMENDMENT	INIT	REV
07.05.20	ISSUED FOR COORDINATION	JK	1				
15.05.20	PRELIMINARY ISSUE	JK	2				
22.05.20	DA ISSUE	JK	3				

DATE	AMENDMENT	INIT	REV
07.05.20	ISSUED FOR COORDINATION	JK	1
15.05.20	PRELIMINARY ISSUE	JK	2
22.05.20	DA ISSUE	JK	3

CLIENT	
BUILDER	

PROJECT	ROSEBANK COLLEGE EXTENSION
ARCHITECT	

SPARKS+PARTNERS	CONSULTING ENGINEERS HYDRAULIC CIVIL FIRE
Level 1, 91 George Street Parramatta NSW 2150 P 02 9891 5033 F 02 9891 3898 E admin@sparksandpartners.com.au https://sparksandpartners.com.au/	
 	

DRAWING TITLE	CIVIL DESIGN COVER PAGE, LOCALITY PLAN & DRAWING SCHEDULE		
DATE	DRAWN	DESIGNED	CHECKED
MAY 2020	JK	BB	BB
PROJECT No	SCALE	SIZE	REVISION
20096	NTS	A1	
DRAWING No	DA1.01		3

REFER DA2.02 FOR CONTINUATION

LEGEND

SITE SECURITY FENCE

SEDIMENT FENCE

STABILISED SITE ACCESS

SITE STOCKPILE

MESH AND GRAVEL INLET FILTER

EARTH BANK DIVERSION MOUND

GEOTEXTILE INLET FILTER

- NOTES
1. REFER TO DA1.01 FOR GENERAL NOTES AND SPECIFICATIONS

2. REFER TO DA2.11 FOR SEDIMENT AND EROSION CONTROL DETAILS

NOTES

SEDIMENT BASIN CALCULATIONS

SEDIMENT BASIN CATCHMENT AREA= 0.27Ha

SETTLING ZONE VOLUME CALCULATION:
10 x Cv x A x R
(BLUE BOOK 6.3.4 (i))

R = y-percentile, x-day
R = 38.8
(DERIVED FROM BLUE BOOK FIGURE 6.5 FOR 5 DAY 85%ile Ryde Area)

Cv (V=10) = 0.86
(FROM TABLE F2 IN App. F IN BLUE BOOK FOR CONSERVATIVE APPROACH OF HIGH RUNOFF POTENTIAL, AND RAINFALL DEPTH (31-40mm))

10x(38.8x(0.86)x(0.27ha))
SETTLING VOLUME = 90m³

REQUIRED SEDIMENT STORAGE
=SETTLING VOLUME x 0.5 = 45m³

REQUIRED BASIN VOLUME = 90 + 45 = 135m³

VOLUME PROVIDED
70m³ (BASE AREA)
155m³ (TOP AREA)
2m DEPTH (INCLUDING 300mm FREEBOARD ABOVE SEDIMENT STORAGE)
SIDE SLOPE = 1V:1H

= 143m³ VOLUME PROVIDED

3m WIDE EMERGENCY SPILLWAY LOCATED AT THE LOWEST POINT OF THE NATURAL SURFACE TO ALLOW GRAVITY FLOW FROM SITE.

IMPORTANT

DO NOT SCALE OFF THIS DRAWING. USE DIMENSIONS & ARCHITECTURAL DRAWINGS ONLY

DRAWINGS TO BE READ IN CONJUNCTION WITH SPECIFICATION

THE INFORMATION ON THIS DRAWING REMAINS THE PROPERTY OF SPARKS & PARTNERS CONSULTING. UNLESS OTHERWISE STATED, THE INFORMATION IS PROVIDED AS A SERVICE TO THE CLIENT AND DOES NOT CONSTITUTE AN INDEPENDENT VERIFICATION OF THE INFORMATION PROVIDED BY THE CLIENT.

REFERENCES

DATE	AMENDMENT	INIT	REV	DATE	AMENDMENT	INIT	REV
15.05.20	PRELIMINARY ISSUE	JK	1				
22.05.20	DA ISSUE	JK	2				

STRUCTURAL	INIT	REV
MECHANICAL	INIT	REV
ELECTRICAL	INIT	REV
CIVIL	INIT	REV

CLIENT

ROSEBANK COLLEGE EXTENSION

ROSEBANK COLLEGE EXTENSION

BUILDER

ARCHITECT

ALLEANZA ARCHITECTURE

PROJECT

ROSEBANK COLLEGE EXTENSION

ARCHITECT

ALLEANZA ARCHITECTURE

SPARKS+PARTNERS

CONSULTING ENGINEERS
HYDRAULIC/CIVIL/FIRE


Level 1, 91 George Street | Parramatta NSW 2150
P 02 9891 5033 | F 02 9891 3898 | E admin@sparksandpartners.com.au
https://sparksandpartners.com.au/

FPA

Fire Protection Association Australia
CORPORATE MEMBER

DNV-GL

DRAWING TITLE	DATE	DRAWN	DESIGNED	CHECKED	REVISION
CIVIL DESIGN EROSION & SEDIMENT CONTROL PLAN SHEET 1	MAY 2020	JK	BB	BB	
PROJECT No	20096	SCALE	1:200 @ A1	SIZE	A1
DRAWING No	DA2.01				2




DRAWING TITLE

CIVIL DESIGN
CONCEPT STORMWATER
MANAGEMENT PLAN SHEET 1

[illegible]

NOTES
1. REFER TO DRAWING DA4.01 FOR STORMWATER LEGEND AND NOTES



REFER TO DA4.01 FOR CONTINUATION

01200

0

5

10

15

20

IMPORTANT

DO NOT SCALE OFF THIS DRAWING. USE DIMENSIONS & ARCHITECTURAL DRAWINGS ONLY.

DRAWINGS TO BE READ IN CONJUNCTION WITH SPECIFICATION.

THE INFORMATION ON THIS DRAWING REMAINS THE PROPERTY OF SPARKS & PARTNERS CONSULTING ENGINEERS. REPRODUCTION OF THE WHOLE OR PART OF THE DOCUMENT CONSTITUTES AN INFRINGEMENT OF COPYRIGHT.

REFERENCES

DATE

AMENDMENT

INIT

REV

DATE

AMENDMENT

INIT

REV

STRUCTURAL

MECHANICAL

ELECTRICAL

CIVIL

CLIENT



BUILDER

ARCHITECT



PROJECT

ROSEBANK COLLEGE EXTENSION



CONSULTING ENGINEERS
HYDRAULIC | CIVIL | FIRE

Level 1, 91 George Street | Parramatta | NSW 2150
P 02 9891 5033 | F 02 9891 3898 | E admin@sparksandpartners.com.au
https://sparksandpartners.com.au/



FIRE PROTECTION ASSOCIATION AUSTRALIA
CORPORATE MEMBER



DNV-BL

DRAWING TITLE

CIVIL DESIGN
CONCEPT STORMWATER
MANAGEMENT PLAN SHEET 2

DATE

MAY 2020

PROJECT No

20096

DRAWN

JK

DESIGNED

BB

CHECKED

BB

SCALE


1:200 @ A1

SIZE

A1

REVISION

2



LEGEND

IMPERVIOUS EXISTING CATCHMENT
AREA = 356m²

ROOF TO RAINWATER TANK CATCHMENT
AREA = 979m²TOTAL AREA = 2,745m²

NOTES

1. REFER TO DRAWING DA1.02 FOR GENERAL NOTES & SPECIFICATION NOTES.

2. REFER TO DRAWINGS DA4.01 AND DA4.02 FOR STORMWATER MANAGEMENT PLANS.

REPORTANT

DO NOT SCALE OFF THIS DRAWING. USE DIMENSIONS & ARCHITECTURAL DRAWINGS ONLY.

DRAWINGS TO BE READ IN CONJUNCTION WITH SPECIFICATION.

THE INFORMATION ON THIS DRAWING REMAINS THE PROPERTY OF SPARKS & PARTNERS CONSULTING ENGINEERS. REPRODUCTION OF THE WHOLE OR PART OF THE DOCUMENT CONSTITUTES AN INFRINGEMENT OF COPYRIGHT.

REFERENCES

NORTH POINT

DATE	AMENDMENT	INIT	REV	DATE	AMENDMENT	INIT	REV
07.05.20	ISSUED FOR COORDINATION	JK	1				
15.05.20	PRELIMINARY ISSUE	JK	2				
22.05.20	DA ISSUE	JK	3				

STRUCTURAL	
MECHANICAL	
ELECTRICAL	
CIVIL	

CLIENT

BUILDER

PROJECT

ROSEBANK COLLEGE EXTENSION

ARCHITECT

SPARKS+PARTNERS

CONSULTING ENGINEERS
HYDRAULIC | CIVIL | FIRE

Level 1, 91 George Street | Parramatta | NSW 2150
P 02 9891 5033 | F 02 9891 3898 | E admin@sparksandpartners.com.au
https://sparksandpartners.com.au/


DRAWING TITLE

CIVIL DESIGN
CONCEPT STORMWATER
CATCHMENT PLAN


DATE	DRAWN	DESIGNED	CHECKED
MAY 2020	JK	BB	BB
PROJECT No	SCALE	SIZE	REVISION
20096	1:200 @ A1	A1	
DRAWING No	DA4.05		

3


W:\2 - PROJECTS\2020\2009 - ROSEBANK COLLEGE\1-DESIGN FILES\DA-DRAWINGS\DA4.05.DWG




OSD BASE PLAN
SCALE 1:50




OSD LID PLAN
SCALE 1:50




OSD SECTION A
SCALE 1:50



OSD SECTION B
SCALE 1:50




FLAP VALVE
SCALE 1:10



ORIFICE PLATE
SCALE 1:10

NOTES
PROVIDE FIXING CLIPS OR BRACKETS TO WALL OF PIT AT OUTLET. ALLOW FOR EASE OF REMOVAL.



TYPICAL REMOVABLE SCREEN DETAIL
NOT TO SCALE

DEVELOPMENT APPLICATION

DATE	AMENDMENT	INIT	REV	DATE	AMENDMENT	INIT	REV
15.05.20	PRELIMINARY ISSUE	JK	1				
22.05.20	DA ISSUE	JK	2				

STRUCTURAL	-
MECHANICAL	-
ELECTRICAL	-
CIVIL	-

CLIENT	ROSEBANK COLLEGE EXTENSION
BUILDER	

ARCHITECT	ALLEANZA ARCHITECTURE
-----------	-----------------------

PROJECT	ROSEBANK COLLEGE EXTENSION
ARCHITECT	ALLEANZA ARCHITECTURE

DATE	MAY 2020	SCALE	AS SHOWN	SIZE	A1	REVISION	2
PROJECT No	20096	DRAWING No	DA4.11				

A

B


C

D


E

F


G




SURFACE INLET / JUNCTION PIT
(PIPE SIZES ≤ Ø450)




PLAN
SCALE 1:20



PLAN
NOT TO SCALE




PLAN
SCALE 1:5



ELEVATION
NOT TO SCALE




FRONT ELEVATION
SCALE 1:5




SIDE ELEVATION
SCALE 1:5


STEP IRON DETAIL
SCALE 1:5



DETAIL 'A'
SCALE 1:10




DETAIL 'B'
SCALE 1:10




DETAIL 'C'
SCALE 1:10

STEP IRON PLACEMENT TO OSD & PIT WALL
NOT TO SCALE




TYPICAL PIPE TRENCH
SCALE 1:10

- NOTES**
- TRENCH WIDTH MAY NEED TO BE INCREASED SUBJECT TO ACHIEVING ADEQUATE COMPACTION.
 - MINIMUM PIPE COVER NOT UNDER ROADS = 300mm UNO
 - THE CONTRACTOR SHALL ENSURE THAT THE SHORING OF TRENCHES IS INSTALLED AS REQUIRED BY STATUTORY REQUIREMENTS.
 - ENSURE BACKFILLING COMPACTION MEETS THE FOLLOWING STANDARDS
A) TRENCHES UNDER PAVED AREAS & BUILDINGS - 100% SMDD
TRENCHES NOT UNDER PAVEMENTS - 90% SMDD



SW SUMP WITH SILT TRAP & TRASH SCREEN
NOT TO SCALE



DATE	AMENDMENT	INIT	REV
15.05.20	PRELIMINARY ISSUE	JK	1
22.05.20	DA ISSUE	JK	2

DATE	AMENDMENT	INIT	REV
15.05.20	PRELIMINARY ISSUE	JK	1
22.05.20	DA ISSUE	JK	2

DATE	AMENDMENT	INIT	REV
15.05.20	PRELIMINARY ISSUE	JK	1
22.05.20	DA ISSUE	JK	2


DATE	AMENDMENT	INIT	REV
15.05.20	PRELIMINARY ISSUE	JK	1
22.05.20	DA ISSUE	JK	2

DATE	AMENDMENT	INIT	REV
15.05.20	PRELIMINARY ISSUE	JK	1
22.05.20	DA ISSUE	JK	2

DATE	AMENDMENT	INIT	REV
15.05.20	PRELIMINARY ISSUE	JK	1
22.05.20	DA ISSUE	JK	2

DATE	AMENDMENT	INIT	REV
15.05.20	PRELIMINARY ISSUE	JK	1
22.05.20	DA ISSUE	JK	2

G



NOTES	
CARPARK PUMP OUT PIT SIZING	
PUMP SIZING:	AREA = 315m ² COEFFICIENT = 1.00 INTENSITY $(I_{100\% \text{ SQUAD}})$ = 255mm/h INFLOW = 22.3l/s PUMP DUTY = 23l/s
STORAGE SIZING:	AREA = 315m ² COEFFICIENT = 1.00 INTENSITY $(I_{100\% \text{ SQUAD}})$ = 26.6mm/h INFLOW = 2.33l/s VOLUME OVER 5 HOURS = 4.1895m ³
VOLUME PUMPED OUT IN 0.5 HOURS AT 23l/s = 4.14m ³	
PUMP OUT PIT STORAGE REQUIRED = 0.495m ³	
PUMP OUT PIT STORAGE PROVIDED = 3m ³	



- ## NOTES
1. CENTRE LINE OF BRANCH MUST INTERSECT CENTRE LINE OF MAIN.
 2. THE BRANCH IS TREATED AS A 'DEAD END' LINE WITH A MANHOLE TO BE LOCATED WITHIN 50m OF MAIN.
 3. HORIZONTAL ANGLE AT A BREAK INTO MAIN SHOULD NOT BE LESS THAN 45° AND MUST NOT EXCEED 90°.
 4. BRANCH LINE Ø150 MIN. Ø750 MAX.

[illegible]

STRUCTURAL
-
MECHANICAL
-
ELECTRICAL
-
CIVIL
-

CLIENT	
BUILDER	

PROJECT	ROSEBANK COLLEGE EXTENSION
ARCHITECT	

SPARKS+PARTNERS
CONSULTING ENGINEERS
HYDRAULIC | CIVIL | FIRE

Level 1, 91 George Street | Parramatta | NSW 2150
P 02 9891 5033 | F 02 9891 3898 | E admin@sparksandpartners.com.au
<http://sparksandpartners.com.au/>


FPA
AUSTRALIA
Fire Protection Association Australia.
CORPORATE MEMBER


DNV GL

DRAWING TITLE			
CIVIL DESIGN STORMWATER MANAGEMENT DETAILS SHEET 3			
DATE	DRAWN	DESIGNED	CHECKED
MAY 2020	JK	BB	BB
PROJECT No	SCALE	SIZE	REVISION
20096	AS SHOWN	A1	
	DRAWING No		
		DA4 13	2

APPENDIX B. MAINTENANCE & MONITORING SCHEDULE

STORMWATER DRAINAGE SYSTEM MONITORING AND MAINTENANCE SCHEDULE

Author Name & Signature:

Date:

Rosebank College, 121 Parramatta Road, Five Dock

General Notes:

- 1 - Maintenance is to be carried out with regard to relevant occupational health and safety guidelines and standards. This includes all confined space, traffic management, fall arrest and other requirements.
- 2 - Initial monitoring and inspections of the stormwater system post commissioning are to be carried out every 3 months for the first year of operation. The amount and type of debris is to be noted and recorded. This information shall be used to determine if modification of the frequency of inspections is required.
- 3 - The frequency of inspections shown in the stormwater maintenance schedule are the maximum periods. Inspection frequencies may be reduced upon completion of the initial monitoring and inspection program as noted in note 2.
- 4 - Blank copies of the maintenance schedule are to be made and filled out during each subsequent inspection with the details kept on site for future reference.

Inspected by:

Date of Inspection:

Date of Next Inspection:

Item to be Inspected	Frequency	Performed by	Inspected	Maintenance Required	Maintenance Procedure	Maintenance Completed
			Yes/No	Yes/No		Date
General						
Eaves/Box Guttering System and Downpipes	Six Monthly/ After Major Storm	Owner / Maintenance Contractor			Inspect and remove any build up of sediment, debris, litter and vegetation within gutter system.	
Stormwater surface inlet and junction pits	Four Monthly/ After Major Storm	Owner / Maintenance Contractor			Remove grate and inspect internal walls and base, repair where required. Remove any collected sediment, debris, litter and vegetation. (e.g. Vacuum/eductor truck) Inspect and ensure grate is clear of sediment, debris, litter and vegetation. Ensure flush placement of grate on refitment	
General inspection of complete stormwater drainage system (that's visible)	Bi-annually	Owner / Maintenance Contractor			Inspect all drainage structures noting any dilapidation, carry out required repairs.	
Rainwater Tank						
First Flush Device	6 Monthly	Owner / Maintenance Contractor			Inspect first flush device to ensure correct operation. Remove accumulated litter & debris. If device is not functioning properly repair or replace.	
Internal Inspection	6 Monthly	Owner / Maintenance Contractor			Check for evidence of access by animals, birds or insects including the presence of mosquito larvae. If present, identify access point and close. If evidence of algal growth, find and close points of light entry.	
Tank and tank roof	6 Monthly	Owner / Maintenance Contractor			Check structural integrity of tank including roof and access covers. Any dilapidation including holes or gaps are to be noted and repaired.	
Water Quality Devices						
Ocean Protect OceanGuard	Refer Manufactures Manual	Maintenance / Specialised Contractor			Refer to manufacturers operation and maintenance manual.	
Ocean Protect Stormfilter	Refer Manufactures Manual	Maintenance / Specialised Contractor			Refer to manufacturers operation and maintenance manual.	
On-Site Detention Tank						
Trash Screen	Six Monthly/ After Major Storm	Owner / Maintenance Contractor			Inspect trash screen to ensure correct operation. Remove accumulated litter & debris. If device is not functioning properly repair or replace.	
Orifice Plate	Six Monthly/ After Major Storm	Owner / Maintenance Contractor			Inspect orifice plate to ensure correct operation. Check orifice diameter size is correct and no damage is present to orifice edge. Check orifice plate is securely fastened to wall with no gaps present between plate and face of wall. If gaps are present fill with sealant or mortar to provide water tight seal.	
Weep Holes in base of sump	Six Monthly/ After Major Storm	Owner / Maintenance Contractor			Inspect weep holes in base of sump. Ensure weep holes are able to drain effectively and remove accumulated sediment and debris if present.	
Tank and tank roof	6 Monthly	Owner / Maintenance Contractor			Check structural integrity of tank including roof and access covers. Any dilapidation including holes or gaps are to be noted and repaired.	