

-EPA - POLLUTUION CONTROL MANUAL FOR URBAN STORMWATER


- -DEPARTMENT OF CONSERVATION AND LAND MANAGEMENT MANUAL "URBAN EROSION & SEDIMENT CONTROL"

 2. MAINTAIN ALL EROSION AND SEDIMENT CONTROL DEVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE
- 3. WHEN STORMWATER PITS ARE CONSTRUCTED PREVENT SITE RUNOFF ENTERING THE PITS UNLESS SILT FENCES ARE ERECTED AROUND PITS.
- 4. PROTECT ALL STOCKPILES OF MATERIALS FROM SCOUR AND EROSION, DO NOT STOCKPILE LOOSE MATERIAL IN ROADWAYS, NEAR DRAINAGE PITS OR IN WATERCOURSES.
- 5. ALL SOIL AND WATER CONTROL MEASURES ARE TO BE PUT BACK IN PLACE AT THE END OF EACH WORKING DAY, AND MODIFIED TO BEST SUIT SITE CONDITIONS.

6. ALL VEHICLE LEAVING THE SITE SHALL BE CLEANED AND INSPECTED BEFORE LEAVING.

7. MAINTAIN ALL STORMWATER PIPES AND PITS CLEAR OF DEBRIS AND SEDIMENT. INSPECT STORMWATER SYSTEM AND CLEAN OUT AFTER EACH STORM EVENT.

-x-x- SEDIMENT FENCE



SANDBAG KERB INLET SEDIMENT TRAP

R. Balas Consulting P/L

CONSULTING CIVIL / STRUCTURAL ENGINEERS ABN 18 162 652 280

43 AVOCA STREET RANDWICK NSW 2031
TEL: (02) 9399 7762 FAX: (02) 9399 5031 MOB: 0418 477 073
E: raphael@rbalasconsulting.com.au

PROJECT:
PROPOSED ALTERATIONS AND ADDITIONS
AT 9-11 HUME HIGHWAY, GREENACRE

EROSION & SEDIMENT CONTROL PLAN

SCALE:	1:100;1:20	CHECKED:	R.D.	DRAWING No:
DRAWN:	0.K.	APPROVED:		1930-M01
DATE:	07/02/2022	DATE:	07/02/2022	



TEMPORARY CONSTRUCTION

FENCE

GEOTEXTILE MEMBRANE