



SEDIMENT FENCE DETAIL

NOT TO SCALE

SEDIMENT CONTROL NOTES:

1. ALL EROSION AND SEDIMENT CONTROL MEASURES, INCLUDING REVEGETATION AND STORAGE OF SOIL AND TOPSOIL, SHALL BE IMPLEMENTED TO THE STANDARD OF THE SOIL CONSERVATION OF NSW.
2. DRAINAGE SHALL BE CONNECTED TO STORMWATER SYSTEM AS SOON AS POSSIBLE.
3. SEDIMENT TRAPS SHALL BE CONSTRUCTED AROUND ALL INLET PITS, CONSISTING DEEP TRENCH.
4. ALL SEDIMENT BASINS AND TRAPS SHALL BE CLEANED WHEN THE STRUCTURES ARE A MAXIMUM OF 60% FULL OF SOIL MATERIAL.
5. ALL DISTURBED AREA SHALL BE REVEGETATED AS SOON AS THE RELEVANT WORKS TO BE COMPLETED.
6. SOIL AND TOPSOIL STOCKPILES SHALL BE LOCATED AWAY FROM DRAINAGE PIPES AND AREA WHERE WATER MAY CONCENTRATE.
7. SILT FENCE CONSTRUCTED AS PER DETAIL SHOWN OR BY USING AN APPROVED EQUIVALENT MEASURE. THE SILT FENCE IS TO BE CONSTRUCTED PRIOR TO ANY OTHER CONSTRUCTION ACTIVITIES. THE SILT FENCES ARE

EROSION & SEDIMENT CONTROL PLAN 1:200



CLIENT		PROJECT		DRAWING TITLE		
MR. QIN		PROPOSED ALTERATIONS & ADDITIONS AT NO. 30 FORE STREET, CANTERBURY		EROSION & SEDIMENT CONTROL PLAN		
DRAWING NO.	PROJECT NO.	SCALE	DRAWN	CHECKED	DATE	
E34-13		1:200	S.X.	H.Z.	02/05/22	
					01	PRELIMINARY ISSUE
						AMENDMENTS
						DATE

ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO WORK COMMENCEMENT.
ALL DIMENSIONS IN MILLIMETRES. DO NOT SCALE, IF IN DOUBT CONTACT 3D ARCHPLAN.
THESE DRAWINGS SHALL REMAIN THE COPYRIGHT OF 3D ARCHPLAN.