

LANDSC. APING SPECIFICATION

PREPARATION

AFTER THE REMOVAL OF ALL RUBBISH AND BUILDING DEBRIS, SOIL TO BE GRADED BELOW FINISHED FLOOR LEVELS.

GARDENS TO HAVE 325MM DEPTH OF SELECTED SOIL MIX.

SOIL MIX TO COMPRISE: 3 PARTS SANDY LOAM/1 PART MUSHROOM, COMPOST/COASE RIVER SAND ADDED PROPORTION NECESSARY TO MAKE SOIL FREEDRAINING AND ADD SLOW RELEASE FERTILIZER(SMOCOTE OR EQUAL) AT THE RATE RECOMMENDED BY THE MANUFACTURER, BEFORE PLANTING, THOROUGHLY WATER PLANTS AND GARDEN BED HOLES.(TREES PLANTING HOLES TO BE TWICE THE DIAMETER AND 100MM DEEPER THAN THE POT).

2. GARDEN EDGING EXCEPT WHERE SHOWN OTHERWISE ON THE DRAWING, GARDEN TO HAVE 100x50MM HARDWOOD EDGING STACKED AT A MAX 2M. CENTRES TO EACH SIDE. ALLL TIMBER TO BE CRESOTE SOAKED BEFORE PLACEMENT.

 $3.\,\mathrm{FENCES}$ courtyard and boundary fences to be 1800mm high Lapped and capped hardwood palmgs.

4. COURTYARDS GRADE ALL FINISHED COUNTYARD LEVELS TO STORMWATER SUMPS.

5. PLANTS
ALL PLANTS TO BE WELL GROWN, DISEASE FREE NURSERY STOCK AND TRUE TO SPECIES TYPE. NO SPECIES SHALL BE SUBSTITUTED WITHOUT APPROVAL. NO VERIEGATED STRAIN BE USED.

6. PLANTING
TREES TO BE PLACED ON 100MM SOIL MIX.(APPROVED GARDEN MIX): OR SIMILAR, AND POSITIONED CENTRALLY IN HOLE AND THEN BACKFILLED WITH SOIL MIX. ALL TREES AND SCRUBS TO BE PLANTED IN POSITIONS AS SHOWN ON THESE PLANS. GROUNDCOVER PLANTS AS INDICATED GARDEN BED PLANTS MATERIAL, TO BE OF BEST STANDARD AND OPTIMUN SIZE(SHURBS-ADVANCED 5 LITRES CONTAINERS/GROUNDCOVERS-TSOMMDIA. POTS) AND SPACING TO THE PLANT SIZE AND SPREAD.

ALL TREES PLANTED INLAWN AREAS TO BE 15-35 LITRE CONTAINERS.

7. MULCH
IMMEDIATELY AFT
WITH 75MM DEPT TER PLANTING, WATER ALL PLANTS AND THEN MULCH ALL GARDEN BEDS TH EUCALYPTUS SP. WOOD CHIPS(MAX PARTICLE SIZE MUST NOT 15MM).

8. FERTILISER
MASS PLANTED ARE
PLANT AND 1 PER 1
OR EQUIVALENT, API AREAS: ALLOW 2 SHIRLEY'S SLOW RELEASE KOKEL PELLETS PER 5–35 LITRE FR 150MM PLANT. TURFED AREAS. ALLOW SHIRLEY. 5 NO 17 LAWN FERTILISER APPLIED IN ACCORDANCE TO MANUFACTURE'S DETAILS.

LANDSCAPE

PLAN

9. TURF
PENNISERTUM CLANDETINIUM(KIKUYU) SHALL BE GOOD QUALITY AND TREE FROM WEEDS, SUPPLIED BY REPUTABLE DEALER. THATCH TO BE LAID WITH STAGGERED JOINTS, WITH PATHWAYS LEVELS. AFTER LAYING AND WATERING, THE TURF SHALL BE ROLLED AND THE JOINTS FILLED WITH TOP SOIL TOPDRESS WITH TOPSOIL A.B.S. 6 WEEKS AFTER LAYING ALL TURF SHALL BE PLACED ON SOMM OF APPROVED TOPSOIL. ALL TOPSOIL TO BE GRADED FOR ALL WATER TO DRAIN. 10. STAKING
ALL TREES TO BE STACKED WITH 2, 38x38x1500MM LONG HARDWOOD STACKS DRIVEN SECURELY INTO THE GROUND AND TIED WITH 2, 50MM WIDE HESSIAN TIES.

$11.\ \mathrm{COMPLETION}$ all planted areas shall be cleared and surplus materials and rubbish removed.

12. MAINTENANCE
A MAINTENANCE PERIOD OF 13 WEEKS SHALL APPLY TO LANDSCAPING WORKS. WATER AS REQUIRED TO AVOID STREE AND TO MAINTAIN THE BEST POSSIBLE GROWTH RATES OF THE PLANTS. CONTROL INSECT ATTACK AND DISEASE WITH INSECTICIDES OR FUNGICIDES APPROVED BY THE CONSTRUCTION MANAGER PRUNE AS REQUIRED TO IMPROVED THE CONDITION OF PLANTS.

02/05/22 PLANTING LANDSCAPE PLAN DETAILS 2 PREMILIARY ISSUE

ALL DIMENSIONS IN MILLIMETRES. DO NOT SCALE ALL DIMENSIONS TO BE CHECKED TO WORK COMMENCEMENT. ON SITE PRIOR

THESE DRAWINGS SHALL REMAIN THE COPYRIGHT OF 3D ARCHPLAN. IF IN DOUBT CONTACT 3D ARCHPLAN.

02/05/22

2/448 PARRAMATTA RDAD, STRATHFIELD Tel: (02)80218928 Fax: (02)80218807 Email: archplan@optusnet.com.au

BUILDING DESIGNERS AND BUILDING CONSULTANTS **ARCHPL**

CLIENT <u>₹</u>

DRAWING NO.

PROJECT

QIN

BRICK ON EDGE (BE)

PLANTING DETAIL

-100MM DEEP CULTIVATION

BACKFILL PLANTING HOLE SOIL MIX MULCH DISHED AROUND PLANT STEM SLOW RELEASED FERTILISER TABLETS TIMBER EDGE DETAIL (TE)

300

78

MIN. 75MM DEEP MULCH

MAKER STAKE

HESSIAN TILES LOOPED AND STAPLED TO STAKERS

N D PROPOSED AT NO. 30 SCALE PROJECT DRAWN ALTERATIONS & ADDITIONS FORE STREET, CANTERBURY CHECKED H.Z. DATE DRAWING TITLE