

## **MANAGEMENT NOTES SOIL AND WATER:**

- 1. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSPECTED AND MAITAINED DAILY BY SITE MANAGER
- 2. MINIMISE DISTURBED AREAS
- 3. ALL STOCKPILES TO BE CLEAR FROM DRAINS, **GUTTERS AND FOOTPATHS.**
- 4. DRAINAGE TO BE CONNECTED TO
- STORMWATER SYSTEM AS SOON AS POSSIBLE. 5. ROADS AND FOOTPATHS TO BE SWEPT DAILY
- AND KEPT CLEAN AT ALL TIMES.
- 6. INSTALL TEMPORARY SEDIMENT BARRIERS TO ALL INLET PITS LIKELY TO COLLECT SILT LADDEN WATER, TO COUNCILS'S REQUIREMENTS.
- 7. NOT WITHSTANDING DETAILS SHOWN, IT IS THE SITE MANAGERS SOLE RESPONSIBILITY TO ENSURE THAT ALL SITE ACTIVITIES COMPLY WITH THE ACT.

## **EROSION CONTROL NOTES:**

- 1. ALL EROSION & SEDIMENT CONTROL MEASURES ARE TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH 'MANAGING URBAN STORMWATER, 3rd EDITION' PRODUCED BY THE NSW DEPARTMENT OF HOUSING.
- 2. ALL EROSION AND SILTATION CONTROL DEVICES ARE TO BE PLACED PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION WORKS, AND ALL SILT TRAPS ARE TO HAVE DEPOSITED SILT REMOVED REGULARLY DURING CONSTRUCTION
- 3. ALL TREES ARE TO BE PRESERVED UNLESS INDICATED OTHERWISE ON THE ARCHITECT'S OR LANDSCAPE ARCHITECT'S DRAWINGS EXISTING GRASS COVER SHALL BE MAINTAINED EXCEPT IN AREAS CLEARED FOR BUILDINGS,
- 4. INSTALL TEMPORARY SEDIMENT BARRIERS TO ALL INLET PITS LIKELY TO COLLECT SILT LADDEN WATER
- 5. NOT WITHSTANDING DETAILS SHOWN IT IS THE CONTRACTORS SOLE RESPONSIBILITY TO ENSURE THAT ALL SITE ACTIVITIES COMPLY WITH THE REQUIREMENTS OF THE CLEAN WATERS ACT.

BUILDING WORK.
ANY DISCREPANCIES ARE TO BE CONFIRMED BY THE

2. LEVELS SHOWN ARE APPROXIMATE UNLESS ACCOMPANIED BY REDUCED LEVELS BY A REGISTERED TO AS 3500.3.1990

3. FIGURED DIMENSIONS ARE TO BE TAKEN IN


PREFERENCE TO SCALING.


4. ALL BOUNDARY CLEARANCES MUST BE VERIFIED BY WORK

1. ALL DIMENSIONS AND FLOOR AREAS TO BE VERIFIED TO THE COMMENCEMENT OF ANY BUILDING WORK.
BUILDER PRIOR TO THE COMMENCEMENT OF ANY 5. WHERE ENGINEERING OR HYDRAULIC DRAWINGS ARE REQUIRED, SUCH MUST TAKE PREFERENCE TO THIS DRAWING 6. STORMWATER TO BE CONNECTED AND DISCHARGED TO COUNCIL'S REQUIREMENTS AND

7. ALL SERVICES TO BE LOCATED AND VERIFIED BY THE BUILDER WITH THE RELEVANT AUTHORITIES

PRIOR TO THE COMMENCEMENT OF ANY BUILDING







HAY BAIL

STAKES

INTO THE

60mm GRAVEL OR CRUSHED ROCK






1:200

SCALE

**EROSION & SEDIMENT CONTROL PLAN** 



HAY BAIL DETAIL			9,211	SEDIMENT FENCE		TEMPOR	TEMPORARY CONSTRUCTION EXIT	
				PROJECT	PROPOSED ATTACHED DUAL OCCUPANCY 118 FIRST AVENUE BELFIELD NSW 2191 LOT B DP419475		RIDGE	
				CLIENT	ANH DUNG LE - YOU HAO LE		A B N 60 167 981 982	
Α	ΙΤ	ISSUED FOR DA APPROVAL	12.05.2022	TITLE	EROSION & SEDIMENT CONTROL PLAN		G01/ 2A COOKS AVENUE CANTERBURY , NSW 2193	
REV	BY	AMENDMENT	DATE		ENGOIGH & GEBINERY GONTHOLT EAR		PHONE: (02)97871595 FAX:97871095	

CANTERBURY BANKSTOWN CITY COUNCIL						
	DESIGNED G.M	CHECKED G.M				
TRUE NORTH	DRAWN LT					
SURVEY REFERENCE	SCALE 1:200	@ A3				
	JOB No	22009				
DRAWING NUMBER	REVISION	Α				
E.01						