

DESIGNE



D:\Astley Homes\Astley Homes Projects Hub - Documents\Projects\21035 - 13 Hinkler Stt Condell



DESIGNE CLIENT ASTLEY HOMES



ROJECT TITLE DRAWING TITLE TRUE NORTH Landscape Plan Proposed Dual Occupancy  $\oplus$ REVISION NO DRAWING NO 13 Hinkler Av Condell Park, NSW DA 09 2 SHEET SIZE A3 DATE OF ISS 22.06.22 ING SCALE DRAWING SCALE As indicated NOTES

# NOTES AND SPECIFICATIONS

Prior to carrying out any excavations, the contractor is to confirm the locations of all services. Service pits and lids a not to be covered by any materials. Trim and grade area to form a smooth even finish.

GARDEN BED / MULCH The topsoil to all garden bed areas shall be four (4) parts site topsoil to one (1) part organic compost thorough blended together prior to placing into position. Where the site topsoil is considered not suitable, an imported topso blend meeting the requirements of AS4419-1998 shall be used. Garden bed subgrades are to be cultivated to a depth 150mm. Topsoil depths to all garden bed areas in deep soil to be 300mm (min). At the completion of all plantin operations apply a 75mm layer of mulch over entire garden bed taking care not to smother plants. Reduce depth mulch around base of plants to form "watering dish". Mulch used shall be Pine Bark Nuggets as supplied by ANL ismilar. All proposed planting is subject to suitable topsoil depths on site. Where there is insufficient depth due presence of bedrock or other structures, the proposed planting is to be modified to suit in accordance with instruction from landscare architect:

Turf used for this site shall be Sir Walter Buffalo or similar soft leaf variety. Unless specified otherwise, turf shall l laid over 150mm topsoil and finished flush with adjacent surfaces. Water turfed areas immediately after turfit operations. Topdress any excessively undulating areas to form a smooth level surface with a coarse grade washed riv sand. All garden edging as denoted by 'GE' on the plan is to be constructed as per detail.

The plants are to be healthy nursery stock, free from disease, injury, insects all weed or roots of weeds. All plants are be thoroughly soaked thour prior to planting. All plants delivered for use on site shall be fully acclimatized

EXISTING TREES TO BE RELATED The existing trees indicated for retention shall be protected for the duration of the construction period. Insta a 1.8m high temporary protective fence (TPF) to the locations as indicated on the plan. Do not store ( otherwise place bulk or harmful materials under or near a tree which is to be retained. Do not attach stay guys and the like to a tree which is to be retained. Where it is absolutely necessary to prune tree roots / liml contractor to ensure all Council approvals have been obtained. All tree work is to be carried out by a qualific and insured arborist. Where an arborist report has been prepared for the existing tree on site; The landscape ple shall be read in conjunction with this report. All trees identified for retention shall be protected and managed endations of this report. These reco ndations will take precedence over any measures outlin

MAINTENANCE / ON GOING CARE Maintain all landscape areas to ensure plant health and occupant safety for period of 12 months beginning from date -practical completion to the satisfaction of Council. Maintenance will include but is not limited to the followir activities: Mowing and edging lawn areas, fertilizing all plant material, pruning, watering, replacing failed plantin treating for pests and diseases, topping up of mulch areas and weeding graden beds as required. On completion of ti initial 12 month period, all maintenance responsibilities shall be handed over to building management / property own for on-going care. Note: All trees will require ongoing annual observation and maintenance by qualified arborist ensure occupant safety, tree health and to avoid damage to surrounding structures and property.

Should there be any discrepancies on the drawings with existing site conditions; contractor is to notify the landscap architect prior to proceeding with the works

**ISSUED FOR DEVELOPMENT APPLICATION**