

PLANT SCHEDULE

DSG

LM

MYO


Plant Name


Correa alba

Liriope muscari

Duranta 'Sheenas Gold'

Myoporum parvifolium Philodendron 'Xanadu'





SURFACE TREATMENT LEGEND

STF Synthetic Turf

TF Turf

GE Garden Edge (to detail)

Clothes Lines (to client requirements) Colorbond / Timber Paling (1.8 high) CB/TP

Tile (to client requirements)

RWT Rainwater Tank (to Engineers Specifications)

PV

Water Permeable Unit Paver

SC Stenciled Concrete (Charcoal/gunmetal)

DGR Decomposed Granite finish

TPF Temporary Protection Fence (1.8m chainmesh)

Mature Size

Trim to 0.6m

Trim to1.0m

0.5m

0.2m 0.5m

Qty

18No.

10No.

10No.

30No.

12No.

INo.

GVL Gravel Surface / Path (Nepean River Pebble)

TD Timber Deck

Concrete Path

Bench Seat

BT **Table Bench Seating**

Pot Size

200mm

100mm

150mm

200mm

NOTES AND SPECIFICATIONS

Prior to carrying out any excavations, the contractor is to confirm the locations of all services. Service pits and lids a not to be covered by any materials. Trim and grade area to form a smooth even finish.

GARDEN BED / MULCH

The topsoil to all garden bed areas shall be four (4) parts site topsoil to one (1) part organic compost thorough blended together prior to placing into position. Where the site topsoil is considered not suitable, an imported topso blend meeting the requirements of AS4419-1998 shall be used. Garden bed subgrades are to be cultivated to a depth-150mm. Topsoil depths to all garden bed areas in deep soil to be 300mm (min). At the completion of all planti operations apply a 75mm layer of mulch over entire garden bed taking care not to smother plants. Receive depth-mulch around base of plants to form "watering dish". Mulch used shall be Pine Bark Nuggets as supplied by ARI. similar. All proposed planting is subject to suitable topsoil depths on site. Where there is insufficient depth due presence of bedrock or other structures, the proposed planting is to be modified to suit in accordance with instruction from landeson architect.

TURF / GARDEN EDGING

Turf used for this site shall be Sir Walter Buffalo or similar soft leaf variety. Unless specified otherwise, turf shall I laid over 150mm topsoil and finished flush with adjacent surfaces. Water turfed areas immediately after turfut operations. Topdress any excessively undulating areas to form a smooth level surface with a coarse grade washed riv sand. All garden edging as denoted by 'GE' on the plan is to be constructed as per detail.

PLANT MATERIAL

The plants are to be healthy nursery stock, free from disease, injury, insects all weed or roots of weeds. All plants are be thoroughly soaked lhour prior to planting. All plants delivered for use on site shall be fully acclimatized prevailing local Sydney conditions.

EXISTING TREES TO BE RETAINED

The existing trees indicated for retention shall be protected for the duration of the construction period. Insta a 1.8m high temporary protective fence (TPF) to the locations as indicated on the plan. Do not store otherwise place bulk or harmful materials under or near a tree which is to be retained. Do not attach stay guys and the like to a tree which is to be retained. Where it is absolutely necessary to prune tree roots / liml contractor to ensure all Council approvals have been obtained. All tree work is to be carried out by a qualific and insured arborist. Where an arborist report has been prepared for the existing tree on site; The landscape plan shall be read in conjunction with this report. All trees identified for retention shall be protected and managed accordance recommendations of this report. These recommendations will take precedence over any measures outline the landscape plan. the landscape plan.

MAINTENANCE / ON GOING CARE

MAINTENANCE / ON GOING CARE
Maintain all landscape areas to ensure plant health and occupant safety for period of 12 months beginning from datepractical completion to the satisfaction of Council. Maintenance will include but is not limited to the followir
activities: Mowing and edging lawn areas, fertilizing all plant material, pruning, watering, replacing failed plantin
treating for pests and diseases, topping up of mulch areas and weeding garden beds as required. On completion of tl
initial 12 month period, all maintenance responsibilities shall be handed over to building management / property own
for on-going care. Note: All trees will require ongoing annual observation and maintenance by qualified arborist
ensure occupant safety, tree health and to avoid damage to surrounding structures and property.

DISCREPANCIES

Should there be any discrepancies on the drawings with existing site conditions; contractor is to notify the landscal architect prior to proceeding with the works





BDAA Accreditation Number: 6614 Class 2 Registration Number: DEP0001004

> **P**: 0448 923 373 E: info@astleyhomes.com.au



ROJECT TILE	
ROJECT ADDRESS 123 Smith St Sydney, NSW 2200	

Landscape Plan REVISION NO. DA 11 DRAWING SCALE
As indicated

ISSUED FOR DEVELOPMENT APPLICATION

TRUE NORTH