

SPEC NOTES

Planting Procedure: Autumn

- 1. Site soil profile as per typical sections, placement of site rocks and typical fescue seeded revegetation with Thredbo 'bush chippings mulch'or weed-free straw mulching as per specification.
- 2. Place jute mesh over seeded and mulched revegetation with rolls down the slope and pegged into position with non-galvanised pins to manufactures direction.
- 3. Plant grass cells through jute webbing at approx. 200mm centres with off-set layout in alternating rows, refer typical plan layout.
- 4. Plant site specific species specified in random layout indicted, no fertiliser or wetting agents recommended for planting going into freezing winter months.
- 5. Install stakes and rigid black plastic tree guards as per typical detail.
- 6. Water well including 'eco-wet'on a weekly basis for three months allowing for wet conditions or until freezing conditions persist.
- 7. Allow for three months maintenance the following spring, repairing damaged areas, replace any failed seeding or planting, adjusting staking and guards, weeding as required, maintain until well established.

Planting Procedure: Spring

- 1. Site soil profile as per typical sections, placement of site rocks and typical fescue seeded revegetation with Thredbo 'bush chippings mulch'or weed-free straw mulching as per specification.
- 2. Place jute mesh over seeded and mulched revegetation with rolls down the slope and pegged into position with non-galvanised pins to manufactures direction.
- 3. Plant grass cells through jute webbing at approx. 200mm centres with off-set layout in alternating rows, refer typical plan layout.
- 4. Plant site specific species specified in random layout indicted, place 1 cup of rehydrated Álcosorb'in the base of each plant hole. Note manufacturers directions and carful mixing as material expands 300-400 times its volume, no mixing/spillage of dry material left on the ground or near water sources. Allow one slow release plant capsule in base of plant holes suitable for Australian native plants such as 'Langley'or 'Agriform'.
- 5. Install stakes and rigid black plastic tree guards as per typical detail.
- 6. Water well on a weekly basis for three months allowing for wet conditions, replace any failed seeding or planting, adjusting staking and guards, weeding as required.


PROJECT NUMBER

DRAWING NUMBER

21/37

REVISION

400



Planners

SJB

Figured dimensions shown on drawings take precedence

over scaled dimensions. Do not scale off drawings

B For Approval

A For Client Review

01/07/22

27/04/22

CS MR BT


Drawn By

Checked By RA

Legend

Poa fawcettiae/Chewings Fescue grassing

Jute Mesh



Boulders

Extent of detailed area

PLANTS:

Forbs:

Craspedia jamesii
Craspedia lamicola

Craspedia leucantha

Craspedia maxgrayi
Hs
Helichrysum scorpioides

Prodolepis robusta

Stylidium graminifolium

Grasses, rushes Poa costiniana

Ph Poa hiemata

Ga


Shrubs Grevillea australis

Pc


Prostanthera cuneata

NOTE:
- SEE LANDSCAPE PLAN FOR SPECIFIC BOULDER
LAYOUT FOR ALL PLANTING TYPES.
- SEE LEGEND ON LANDSCAPE PLANS AND DETAILS
ON SHEET 400 FOR DETAILS ON RETAINING
BOULDERS

1 Typical Planting Layout - Type 1 (3m2)
Scale 1:40



2 Typical Planting Layout - Type 2 (7m2)
Scale 1:40



Typical Planting Layout - Type 3 (52m2)
Scale 1:40

BOULDERS TO SERVE AS RETAINING EDGE

REVISION

B For Approval

A For Client Review

ISSUE TYPE

01/07/22 27/04/22 FOR DEVELOPMENT APPLICATION ONLY

Drawn By CS MR BT
Checked By RA

SCALE

Figured dimensions shown on drawings take precedence over scaled dimensions. Do not scale off drawings

CONSULTANTS
Architect
DKO

Civic & Structural
Sellicks

Planners SJB CLIENT



Thredbo Lot 768
Landscape Details

Tait Network

REVISION B

21/37

DRAWING NUMBER
401

PROJECT NUMBER





LEGEND

____ CONTOURS

--- SITE BOUNDARY

EXISTING TREE EDGE OF VEGETATION

Drawing List				
Sheet No.	Sheet Title			
100	Reference Plan			
101	Site Analysis / Opportunities & Constraints			
110	Tree Management Plan			
200	Concept Plan			
210	Landscape Plan			
211	Landscape Plan			
212	Landscape Plan			
213	Landscape Plan			
300	Hardscape Palette			
350	00-XXX			
400	100			
401	Landscape Details			
402	Landscape Details			

Thredbo Lot 768 Reference Plan

PROJECT NUMBER 21/37 REVISION

100

DRAWING NUMBER

Tait Network

Scale at A1 1:500 Scale at A3 1:1000 Figured dimensions shown on drawings take precedence over scaled dimensions. Do not scale off drawings

Architect DKO Civic & Structural Sellicks Planners SJB



LEGEND



CONTOURS



TREE TO BE REMOVED



TREE TO BE RETAINED

TREE QUALITY





MEDIUM



TREE GROUP

TREE PROTECTION FENCING

Existing Tree Species			
Code	Name		
Esp	Eucalyptus species		
Evi	Eucalyptus viminalis		
Ера	Eucalyptus pauciflora		
Est	Eucalyptus stellulata		

1.0 GENERAL
ALL WORK MUST BE CONTAINED WITHIN THE SITE EXCEPT FOR APPROVED SERVICE CONNECTIONS IN THE VERGE.

A SUITABLY QUALIFIED LANDSCAPE ARCHITECT OR HORTICULTURALIST SHALL BE EMPLOYED TO OVERSEE WORK IN THE VERGE TO ENSURE ALL WORKS ARE PERFORMED TO INDUSTRY STANDARDS. THEY MUST BE PRESENT DURING ANY CULTIVATION OR RESTORATION OF THE VERGE.

2.0 STANDARD CONDITIONS

THE FOLLOWING CONDITIONS APPLY IF ANY DEVELOPMENT ACTIVITY OCCURS ON THE SITE:

A COPY OF THESE CONDITIONS SHALL BE KEPT ON SITE FROM THE TIME THAT THE PROTECTIVE FENCES ARE ERECTED TO THE TIME THAT ALL WORKS ARE COMPLETED ON SITE

TREE REMOVAL ALL PROTECTED TREES ARE TO BE RETAINED UNLESS OTHERWISE STATED IN THE SPECIFIC CONDITIONS BELOW.

FENCING OF PROTECTED TREES

ALL TREES THAT ARE MARKED TO BE RETAINED SHALL BE FENCED OFF BY A CONTINUOS 1800MM HIGH CHAIN WIRE PROTECTIVE FENCE AT THE EXTENT OF CANOPY DRIP. THE PROTECTIVE FENCES SHALL BE ERECTED PRIOR TO THE COMMENCEMENT OF ANY EARTHWORKS, CONSTRUCTION OR DEMOLITION ACITIVITY ON ANY PART OR STAGE OF A DEVELOPMENT AND SHALL REMAIN IN PLACE UNTIL ALL CONSTRUCTION WORKS ARE COMPLETED. THE PROTECTIVE FENCE SHALL BE MAINTAINED IN GOOD ORDER FOR THE DURATION OF ANY CONSTRUCTION WORKS. A TREE PROTECTION SIGN SHALL BE PROMINENT DISPLAYED ON ANY PROTECTIVE FENCES AROUND PROTECTED TREES. ACTIVITIES ARE NOT PERMITTED IN THE FENCED OFF AREA UNLESS OTHERWISE STATED IN SPECIFIC CONDITIONS BELOW.

3.0 LANDSCAPE MANAGEMENT AND PROTECTION

3.1 EXISTING TREES

CROWN AND APEX OF CANOPIES SHALL NOT BE ALTERED OR REDUCED UNLESS SPECIFIED FOR BUSHFIRE MAINTENANCE. ENSURE LIFTING EQUIPMENT AND LOAD ARE CAPABLE OF OPERATING IN A MANNER THAT IT CLEARS THE HEIGHT AND WIDTH OF THE TREE CANOPY WITHOUT DAMAGING THE CROWN. ENSURE CONSTRUCTION EQUIPMENT CAN PASS BENEATH THE TREES' LOWEST LIMB THROUGH DESIGNATED DRIVEWAY ACCESS. WHERE TREE CANOPIES OVERHANG ROOFLINES, LIGHT PRUNING TO REDUCE THE EDGES OF THE CANOPY EXTENT MAY BE CARRIED OUT

3.2 TREE REMOVAL TREES: 6, 12, 13, 14,16, 30 AND TREE GROUPS 2(PARTIAL) AND 3 ARE THE ONLY TREES TO BE REMOVED.

4.0 TREE ROOT PROTECTION

EXCAVATION WITHIN THE DRIP ZONE OF TREES SHALL BE RESTRICTED TO ONE SIDE OF THE TREE ONLY AND SHALL HAVE PRIOR APPROVAL FROM ENVIRONMENT AND ASSET TEAM DO NOT SEVER LARGE ROOTS (>30MM DIAMETER) CLOSER THAN HALFWAY FROM THE DRIP-LINE TO THE TRUNK. HAND TRENCH TO A DEPTH OF 300MM PRIOR TO ANY MECHANICAL TRENCHING BEING UNDERTAKEN. CUT ALL ROOTS CLEANLY WITH EQUIPMENT SPECIFICALLY DESIGNED FOR THIS PURPOSE OR BY SUITABLE PRUNING EQUIPMENT PROTECT EXPOSED ROOTS FROM DESICCATION BY LIGHTLY WATERING OR COVERING WITH HESSIAN WHICH MUST BE KEPT MOIST. MAINTAIN THE GOOD HEALTH OF THE TREES THAT HAVE HAD DISTURBANCE IN THEIR ROOT ZONE BY CONTINUAL WATERING, AT NO TIME SHALL THE DISTURBED AREA BE ALLOWED TO DRY OUT TO THE DETRIMENT OF THE TREES HEALTH

5.0 BRANCH PROTECTION

ON THE ADVICE OF THE PROJECT ARBORIST AND WITH WRITTEN APPROVAL FROM LESSEE OF THE BLOCK ON WHICH ANY TREE IS LOCATED, REMOVE ANY BRANCHES THAT ARE IMPEDING ACCESS, AND TRUNK WRAP THOSE THAT ARE LIKELY TO BE DAMAGED DURING WORKS AS PER FIGURE 4, AS4970, OR SIMILAR.

REVISION	ISSUE TYPE	SCALE	CONSULTANTS	CLIENT
			Architect	
			DVO	

C For Approval B For Approval A For Client Review

FOR DEVELOPMENT APPLICATION ONLY 04/07/22 01/07/22 Drawn By CS MR BT 27/04/22 Checked By RA

Scale at A1 1:200 Figured dimensions shown on drawings take precedence over scaled dimensions. Do not scale off drawings

DKO Civic & Structural Sellicks Planners


SJB

Thredbo Lot 768 Tree Management Plan

PROJECT NUMBER 21/37 REVISION







Planners

SJB

Figured dimensions shown on drawings take precedence

over scaled dimensions. Do not scale off drawings

C For Approval

B For Approval

A For Client Review

04/07/22

01/07/22

27/04/22

Drawn By CS MR BT

Checked By RA

Tait Network

DRAWING NUMBER

Forbs

- 1. Craspedia jamesii
- 2. Craspedia lamicola
- 3. Craspedia leucantha
- 4. Craspedia maxgrayi
- 5. Helichrysum scorpioides
- 6. Podolepis robusta7. Stylidium graminifolium

Grasses, Rushes


- 8. Poa costiniana
- 9. *Poa fawcettiae
- 10. Poa hiemata


Shrubs

- 11. Grevillea australis
- 12. Prostanthera cuneata
- *Poa fawcettiae is the Dryland Grass. It is also to be planted in to Jute Mesh amongst specified plants

























Planners

SJB





350


DRAWING NUMBER

21/37

PROJECT NUMBER









LEGEND







APPROX LOCATION OF EXISTING SITE RETAINING BOULDERS



___ SLOPE DIRECTION



WATER COURSE EROSION



STEEP DROP TO BATTER WITH EXISTING FENCING





ASSET PROTECTION ZONE



WOODLAND SURROUND







WALKWAY AND STEEP DROP WITH EXISTING FENCING



EXISTING ROCKS ON SITE

Thredbo Lot 768 Site Analysis / Opportunities & Constraints

Tait Network

21/37 REVISION

PROJECT NUMBER

DRAWING NUMBER 101



FOR DEVELOPMENT APPLICATION ONLY Drawn By CS MR BT

Checked By RA

SCALE Scale at A1 1:200 Scale at A3 1:400 Figured dimensions shown on drawings take precedence over scaled dimensions. Do not scale off drawings CONSULTANTS Architect DKO Civic & Structural Sellicks Planners SJB