

Institute HYDRAULIC: DT CIVIL ARCHITECT: MASTER GRANNY FLATS Professional Member

Ph: 9545 5200 info@zenithlandscapes.com.au

22-4720 LO1

DATE: 19.08.2022



TREE No.	TREE	HGT. (m)	CAN. (m)	TNK. (m)	condition	retain/ remove	COMMENTS
1	Bottlebrush	5	3	multi	poor	RETAIN	street tree
2	Bottlebrush	5	4	0.3	fair	RETAIN	street tree
3	Eucalypt	12	8	0.8	fair	remove	in construction zone
4	Eucalypt	10	8	0.4	fair	remove	in construction zone
5	Palm	12	3	0.4	fair	remove	in construction zone
6	Palm	14	3	0.4	fair	remove	in construction zone
7	Eucalypt	15	12	1.0	fair	RETAIN	maintain soil levels
8	Melalueca	12	10	multi	fair	RETAIN	maintain soil levels
9	Eucalypt	13	8	0.5	fair	RETAIN	maintain soil levels
10	Eucalypt	14	8	0.5	fair	RETAIN	maintain soil levels
11	Palm	8	6	1.2	fair	RETAIN	maintain soil levels

- 1.2 The Contractor will be held responsible for any damage to utility services, pipes, building structures, paving surfaces, fencing, footways, 1.3 The site is to be left in a clean and tidy condition at the completion of works to the satisfaction of the Superintendent.
- 1.4 No work involving an extra shall be undertaken unless approval is first obtained from the Superintendent. 1.5 No substitute of material shall be made unless approval is given by the Superintendent.
- 1.6 The Contractor shall continuously maintain all areas of the Contract during progress of the works specified.
- 2.1 Prepared sub-grade is to be free of stones larger than 100mm diameter, cement, rubbish and any other foreign matter that could hinder
- 3.1 Once clear of weed growth, grass and debris, sub-grade should be cultivated to a minimum depth of 150mm incorporating 'Dynamic Lifter'
- or equivalent at the manufacturers recommended rates. 3.2 Weeds shall be controlled by a combination of chemical and hand removal techniques.
- 4.1 All plant material is to be hardened off, disease and insect free and true to species, type and variety. Plants are to be well grown but not root bound and shall comply with Natspec - "Guide to Purchasing Landscape Trees".
- 4.2 All plants are to be removed from their containers prior to planting with as little disturbance to the root system as possible. 4.3 Planting shall not be carried out in dry soil or extreme weather conditions. 4.4 Plants should be planted at the same depth as the plants were in the containers and allow for a shallow saucer of soil to be formed
- around the plant to aid the penetration of water.
- 4.6 The Contractor shall be responsible for the failure of plants during construction, except for acts of vandalism.
- 5.1 Ties should be firmly attached to the stakes, in a way to avoid damage to the stem while allowing a small degree of movement.
- 6.1 Turf areas should be cultivated before turfing by ripping or harrowing.
- 6.2 At the completion of turfing the whole area shall be thoroughly soaked and kept moist till the completion of landscape works.
- 7.1 Mulch for all general mass planted beds shall be 'Droughtmaster' mulch as supplied by A.N.L. or similar.
- 8.1 Soil mix for mass planted areas shall be 3 parts site soil to 1 part 'Organic Garden Mix' as supplied by A.N.L. or equivalent.
- 8.2 Soil mix for street tree planting shall be 1 part site soil to 1 part 'Organic Garden Mix' as supplied by A.N.L. or equivalent

- 1. These works shall be in addition to the construction contract.
- 2. The Contractor shall commence and fully implement the short term maintenance after Practical Completion has been confirmed by the
- 3. The Contractor shall carry out maintenance works for a minimum period of 26 weeks
- a. Mow lawns and trim edges each 10 days in summer and each 14 days in winter.
- c. Remove any weed growth from all planting areas.
- d. Spray and control pests and diseases as required.
- h. Maintain all mulched areas in a clean and tidy condition to the depth as originally specified.
- i. Make good any defects or faults arising from defective workmanship.
- Note: The Contractor is not to be held responsible for the theft or vandalism of any plants during the maintenance period 5. Advanced trees shall be individually inspected at least once a month in order to determine their health and vigour. Should the trees exhibit any signs of disease, pest infestation or poor growth then a qualified arborist shall be consulted within 14 days in order to determine the most appropriate course of action. Recommended treatment shall then be commenced within 7 days and shall continue until the problem is
- satisfaction of the Superintendent the responsibility will be handed over to the Client for on-going maintenance.



- 6. When the maintenance period is completed the Contractor shall notify the Superintendent. The site shall then be inspected and if to the

DIAL 1100 BEFORE YOU DIO www.1100.com.a
---

SYMBOL	SPECIES	No.	Pot Size	Mat. Hgt.	Stake	COMMON NAME
WF	★ Waterhousia floribunda	3	75ltr	8m+	yes	Weeping Lilly Pilly
	Lagerstroemia indica	1	25ltr	6m+	yes	Crepe Myrtle
CV	* Callistemon viminalis	1	25ltr	5m+	yes	Weeping Bottlebrush
SS SS SS		6	25ltr	4m	no	Brush Cherry
LP	* Leptospermum petersonii	5	5ltr	3.5m	no	Lemon Scented Tea Tr
CS CS CS		5	5ltr	2.5m	no	Slim Callistemon
AM		12	5ltr	1.5m	no	Dwarf Lilly Pilly
РР	★ Prostanthera 'Poorinda Ballerina'	14	5ltr	1.5m	no	Mint Bush
COL	* Callistemon 'Little John'	8	150mm	1m	no	Dwarf Bottlebrush
PM		11	150mm	1m	no	Waxflower
на	* Hymenosporum 'Gold Nugget'	24	150mm	0.7m	no	Dwarf Native Frangipar
E State Stat	* Thryptomene saxicola	39	150mm	0.7m	no	Pink Rock Myrtle
<b>****</b> **	* Dianella caerulea 'Breeze'	66	150mm	0.5m	no	Flax Lily
	* Dianella tasmanica 'Tasred'	24	150mm	0.4m	no	Flax Lily
*****	* Lomandra 'Shara'	63	150mm	0.4m	no	Dwarf Mat Rush
(*************************************	* Viola hederacea	16	150mm	g/cover	no	Native Violet
	<b>★</b> ∍Hardenbergia violacea	8	5ltr	climber	trellis	False Sarsparilla

TREE PROTECTION GUIDELINES

- . WORK NEAR TREES
- GENERAL: All existing trees which are to remain undisturbed are indicated on the drawings and shall be adequately protected for the duration of the contract as specified by the client. Any variation from this specification or enquires regarding the protection/health of the trees to be retained must be referred to Council's Landscape Officer or Tree Preservation Officer for approval and/or advice. REQUIREMENTS: Trees shall not be removed or lopped unless specific instruction is given in writing by the Superintendent. All tree protection works shall be carried out before excavation, grading and site works commence.
- 2. PROTECTION

**IRRIGATION NOTE** 

prior to planting.

the time of construction.

testing has been undertaken.

planting works taking place.

1. All mass planted beds will require a fully automated and self timed, commercial

2. The irrigation system shall be designed and installed in accordance with all

4. The irrigation system shall be installed and in full working order prior to any

with the operational requirements of the system prior to planting taking place.

grade, sub-surface irrigation system which is to be designed and installed by an

appropriately gualified irrigation consultant, Landscape Contractor or tradesperson

relevant Australian Standards and the current water restrictions that are in place at

3. The design of the irrigation system shall only be carried out after water pressure

5. The site superintendent and all other relevant personnel shall be fully conversant

Protect trees specified or shown to be retained from damage by ground works. Take necessary precautions, including the following: 2.1.Method: Fence off the root zones of all existing trees to be retained in accordance with the Tree Protection Detail. Protective fencing is to remain in place until the completion of all building and hard landscape construction. Fencing is to be located as shown on the Existing Tree Plan. A layer of organic mulch 100mm thick shall be placed over the protected area where existing garden beds are not already present. Where building works are required within the root zone of existing trees these works must be supervised by a qualified Arborist. 2.2.Harmful materials: Do not store or otherwise place bulk materials and harmful materials under or near trees. Do not place spoil from excavations against tree trunks. Prevent wind-blown materials such as cement from harming trees and plants. Prevent concrete wash or other substances from entering the protection zone.

2.3.Damage: Prevent damage to tree bark. Do not attach stays, guys and the like to trees 2.4. Work under trees: Do not add or remove topsoil within the drip line of the trees. If it is necessary to excavate within the drip line, use hand methods such that root systems are preserved intact and undamaged. Open up excavations under tree canopies for as short a period as

2.5 Roots: Do not cut tree roots exceeding 50mm diameter unless undertaken by a qualified Arborist.

DISCLAIMER Every effort is made to ensure the accuracy of these documents, however they should be thoroughly checked before being issued to any other persons or authority or used for construction purposes. Any inaccuracies, omissions or discrepancies should be referred back to Zenith Landscape Designs immediately.

These drawings maybe printed in whole. The drawings and parts thereof remain the intellectual property of Zenith Landscape Designs and may not be used in part or whole for any other purpose without the prior permission of Zenith Landscape Designs.

NOTES

1. Vehicular pavement, fencing and built structure details shall be to Architect's specification

2. All surface and sub-surface drainage requirements shall be to Engineers details. 3. Numeric dimensions should be taken in preference to scaling. 4. All dimensions should be checked on-site prior to commencing construction.

5. Contractors shall verify the location of all site features prior to commencing works 6. Soil testing has not been undertaken as part of the preparation of this design; Contractors shall determine the need for soil testing prior to any planting works. 7. A search of underground services has not been undertaken as part of the

preparation of this design; it is recommended that Contractors contact DIAL BEFORE YOU DIG ON 1100 prior to commencing any works. 8. This plan is to be read in conjunction with the architectural and engineering plans 9. It is recommended that an approved root barrier be installed to manufacturers

recommendations to all tree planting in the vicinity of structures, walls and hard pavement areas.

## NOT FOR CONSTRUCTION

	TITLE: LANDSCAPE PLAN							
r hill rd	STATUS:	DA		SCALES: 1:10	0, 1:200			
	CHECKED	<sup>):</sup> MFG		SHEET 2 OF 2	<b>REVISION:</b>			
	DRAWN:	MAG		DRAWING No.				
	DATE:	19.08.2022	22-4	4720 LO2				