





Excavate all areas to be turfed to 100mm below required finished levels. Do not excavate within 1500mm of the trunk of any existing tree to be retained. Ensure that all surface water runoff is directed towards the inlet pits, kerbs etc. and away from buildings. Ensure that no pooling or ponding will occur. Rip the subgrade to 150mm. Install 80mm depth of imported topsil. Lay turf rolls closely butted. Fill any small gaps with topsoil. Water thoroughly.



Planting Areas

Ensure that mass planting areas have been excavated to 250mm below finished levels. Rip to a further depth of 100mm. Supply and install 250mm of premium garden mix. Topsoil to be either imported topsoil or stockpiled site topsoil (if suitable ie, no clay). Install 75mm depth of organic Eucalyptus Mulch



Fencing

1.8m high Colorbond boundary fencing







19/3 Brown Street Kiama NSW 2533 **P** 0412 477 240 0405 126 018

1. Do not scale from drawing

- 2. All dimensions to be checked on site
- 3. Any discrepancies to be report to designer 4. Boundaries to be verified by surveyor
- 5. Other consultants drawings take precedence
- 6. Drainage to council requirements and AS3500 7. Copyright of plans and documentation remain the exclusive property of Logico Homes Pty Ltd Builders Licence No. 249513C

'H' class (tbc) LGA: Canterbury Bankstown Lodgement: DA/CC DP No: 30 28103



Cormorant 44 Facade

Finishes:

Lot 30 No. 22 Parkview Avenue Custom Picnic Point NSW 2213 Logico J. & S. Catling

21.026 DWG No: 05 Version No: DA_10 Date:

2/12/2022