

**BUS DEPOT
7A-11 RACECOURSE ROAD, 5-9
FAUNCE STREET & YOUNG STREET
Civil Stormwater Management
Report**

CLIENT/	WALUYA PTY LTD
DATE/	AUGUST 2023
CODE/	22-1063

Commercial in Confidence

All intellectual property rights, including copyright, in designs developed and documents created by AT&L remain the property of this company. Any use made of such design or document without the prior written approval of AT&L will constitute an infringement of the rights of the company which reserves all legal rights and remedies in respect of any such infringement.

The information, including any intellectual property, contained in this proposal is confidential and proprietary to the Company. It may only be used by the person to whom it is provided for the stated purpose for which it is provided and must not be imparted to any third person without the prior written approval of the Company. The Company reserves all legal rights and remedies in relation to any infringement of its rights in respect of its confidential information.

This report has been prepared in accordance with the terms and conditions of appointment. AT&L cannot accept any responsibility for any use of or reliance on the contents of this report by any third party.

This report may be based upon information supplied by other consultants and contractors. To the extent that the report incorporates such material, AT&L takes no responsibility for any loss or damage caused by any error or omission arising from reliance on it.

Document Registration

Document Title	Bus Depot – GOSFORD
Document File Name	REP001-01-22-1043-Civil Report
Section	AT&L PTY LTD – ENGINEERING DIVISION
Document Author	GLEN JAMES

Issue	Description	Date	Author	Checked	Approved
A	FOR APPROVAL	15-12-22	Glen James	☒	☒
B	FOR APPROVAL	10-08-23	Glen James	☒	☒

Contents

1. Introduction.....	1
2. Project Description.....	2
2.1. Scope of Report.....	2
3. Stormwater Management.....	4
3.1. Proposed Site Stormwater Drainage.....	4
3.2. Hydrology	4
3.3. Hydraulics.....	5
3.4. Modelling Software	5
3.5. Overland Flows and Flooding.....	5
4. Stormwater Management.....	6
4.1. OSD Requirement	6
4.2. Proposed OSD Tank Details	6
4.3. Water Sensitive Urban Design (WSUD)	6
4.4. WSUD Modelling - Music Model	7
4.4.1. Results.....	7
4.5. Ocean Protect Maintenance.....	7
5. Sedimentation and Erosion Control	9
5.1. Sedimentation and Erosion Control (Construction)	9
5.1.1. Sources of Pollution	9
5.1.2. Potential Impacts.....	9
5.2. Soil and Water Management Plan	10
5.2.1. Overall Strategy.....	10
5.2.2. Design of Sediment and Erosion Control Measures.....	10
5.3. Site Inspection and Maintenance.....	10
5.4. Conclusion.....	11

APPENDIX

Appendix A–	Detailed Site Survey
Appendix B –	Civil Development Application Drawings
Appendix C –	MUSIC Model Results
Appendix D–	DBYD
Appendix E –	Drains Results
Appendix F –	Flood Impact Assessment

1. Introduction

This Civil Stormwater Management Report supports the proposed redevelopment of 7A-11 Racecourse Road, 5-9 Faunce Street and Young Street 1 in West Gosford. Refer to Figure 1 for location of the proposed development.

AT&L have been engaged by Waluya Pty Ltd to prepare a Development Application (DA) Civil Stormwater Management Report on the civil and stormwater management requirements for the proposed development.

This report is written to comply with Gosford Development Development Control Plan 2013 (DCP), and Gosford City Council Water Cycle Management requirements.




Figure 1 – Site Location (Courtesy of NearMap)

2. Project Description

This development application is for a proposed bus depot with ancillary offices and carparking located at 7A-11 Racecourse Road, 5-9 Faunce Street and Young Street, West Gosford.




Figure 2 - Proposed Site Plan (Courtesy of DEM)

2.1. Scope of Report

This report outlines the design criteria for:

- Stormwater infrastructure;
- How stormwater is managed across the site;
- Identification of existing utility infrastructure; and
- How the future development will be serviced.

Refer to Appendix B for the Civil Development Application Civil Works Package Drawings.

This report has been prepared to satisfy the requirements and conditions of the following documents:

- Gosford City Council DCP 2013;
- Gosford City Council Water Cycle Management Guidelines; and
- OEH's Managing Urban Stormwater: Soils and Construction Guideline.

This civil infrastructure report includes:

- Stormwater Management:

Civil & Structural Engineers | Project Managers | Water Services Coordinator

- Piped and Overland Flows;
- Water Sensitive Urban Design (WSUD);
- Dial Before you Dig (DBYD) information (Appendix D); and

3. Stormwater Management

3.1. Proposed Site Stormwater Drainage

All proposed stormwater drainage from the development will be designed in accordance with Gosford City Council/Central Coast Council requirements.

All stormwater is proposed to connect into the existing stormwater infrastructure located within the adjacent council road network Racecourse Road to the west. Stormwater generated within the proposed site will be detained to ensure post-development flows are less than pre-development flows in accordance with the Gosford City Council stormwater guidelines.

Refer to the Civil Drawings in Appendix B for layout and details for the proposed stormwater network across the site.

Stormwater generated within the proposed site will be treated to the Gosford City Council Council DCP water treatment rates using a combination of proprietary treatment devices and natural WSUD elements.

3.2. Hydrology

- Pipe drainage shall be designed to accommodate the 20-year ARI storm event in accordance with Gosford City Council requirements;
- The combined piped and overland flow paths shall be designed to accommodate the 100-year ARI storm event.
- Where trapped low points are unavoidable and potential for flooding private property is a concern, an overland flowpath capable of carrying the total 100-year ARI storm event shall be provided. Alternatively, the pipe and inlet system may be upgraded to accommodate the 100-year ARI storm event;
- Rainfall intensities shall be as per the Intensity-Frequency-Duration table in accordance with Gosford City Council rainfall data;
- Times of concentration for each sub catchment shall be determined using the kinematic wave equation. Minimum time of concentration is 5 mins and the maximum are 20 mins. Runoff coefficients shall be calculated in accordance with AR&R. The fraction impervious shall be determined from analysis of the sub catchments;
- Runoff coefficients shall be calculated in accordance with the ARR&R. The fraction impervious shall be determined from analysis of the sub-catchments;
- Flow width in gutter shall not exceed 2.5m for the 20-year ARI storm event;
- Velocity depth ratios shall not exceed 0.4 for all storms up to and including the 100-year ARI event;
- Bypass from any pit on grade shall not exceed 10 l/s;
- Blockage factors of 10% and 30% shall be adopted for kerb inlet and grated pits respectively; and
- All pits deeper than 1.8m to be reinforced.

3.3. Hydraulics

- A hydraulic grade line HGL design method shall be adopted for all road pipe drainage design. The HGL shall be shown on all drainage long sections;
- The minimum pipe size shall be 375mm diameter RCP (external) and 150mm uPVC (internal);
- Maximum spacing between pits shall not exceed 75m;
- The minimum pipe grade shall be 1% (external) and 0.5% (internal);
- All pipes shall be Rubber Ring Jointed unless noted otherwise;
- The minimum cover over pipes shall be 450mm in grassed areas and 600mm within carriageways;
- Where minimum cover cannot be achieved due to physical constraints the pipe class shall be suitably increased;
- All trafficable pipes shall be a minimum Class 3 Reinforced Concrete Pipes or Fibre Reinforced Cement/ HDPE equivalent;
- The pipe friction coefficients to be adopted shall be:

Materials	Mannings – n	Colebrook-White – k	Min. Pipe Class
RCP	0.012	0.3	3
FRC	0.011	0.15	3

Table 1 - Pipe Details

- All pipes classes shall be designed for the ultimate service loads and where applicable, construction loads will be designed for;
- Pipes discharging to the overland flow path shall adopt a minimum tailwater level equivalent to respective overland flow level;
- Pit Loss coefficients shall be calculated in accordance with Missouri Charts;
- A minimum 150mm freeboard shall be maintained between pit HGL and pit surface levels;
- Overland flowpaths shall maintain a minimum of 100mm freeboard to all habitable floor levels; and
- Pits deeper than 1.2m shall contain step irons at 300 mm centres.

3.4. Modelling Software

DRAINS modelling for the OSD tanks.

MUSIC modelling software has been used to evaluate pollutant loads from the developed lot. MUSIC data files and output results are attached in Appendix C.

3.5. Overland Flows and Flooding

Refer to AT&L flooding report for flood impact assessment for the proposed development contained within Appendix F.

4. Stormwater Management

4.1. OSD Requirement

As discussed within Section 3.2, OSD is required within the development to ensure the development does not increase the risk of downstream flooding of roads and properties, or erosion of unstable waterways.

The OSD within the site has been designed to achieve the following outcomes:

- Post developed peak flows to be mitigated to pre-developed peak flows for all storm events between and including the 1- and 100-year events. Refer to Table .

Duration	Pre-Developed Flows	Post Developed Flows
	(m3/s)	(m3/s)
1 YR ARI	0.167	0.110
2 YR ARI	0.274	0.135
5 YR ARI	0.447	0.355
10 YR ARI	0.572	0.562
20 YR ARI	0.731	0.665
50 YR ARI	0.957	0.787
100 YR ARI	1.160	0.887

Table 2: Pre-Post Developed Flows from Development Site

4.2. Proposed OSD Tank Details

The proposed OSD tanks will be constructed within the proposed hardstand with WSUD built downstream of the proposed tanks. The outlet pipes from the tank will discharge into the street/swale network to the west of the site refer to Appendix C and D for details.

On Site Detention (OSD)	Catchment to Tank (ha)	2-YR OSD Volume (Min.) (m ³)	100-YR TOTAL OSD Volume (Min.) (m ³)	Primary Outlet	Secondary Outlet
Tank 1	1.16	260.30	432.30	150mm Orifice Plate	330mm Orifice Plate
Tank 2	0.845	188.80	233.70	200mm Orifice Plate	530mm Orifice Plate

Table 1 - OSD Tank Volumes

Note: OSD discharge conditions have been confirmed by detailed site survey refer to Appendix A for details.

4.3. Water Sensitive Urban Design (WSUD)

Water Sensitive Urban Design (WSUD) encompasses all aspects of urban water cycle management, including water supply, wastewater and stormwater management. WSUD is intended to minimise the impacts of development upon the water cycle and to achieve more sustainable forms of urban development.

All stormwater runoff from the buildings only will be directed into water quality measures.

Civil & Structural Engineers | Project Managers | Water Services Coordinator

Proprietary treatment devices will treat the water to satisfy Council's water quality requirements. These devices have been modelled as an Ocean Protect Oceansave, Ocean Protect Oeanguards, Ocean Protect Jellyfish and Swale systems. By utilising these treatment devices, stormwater draining from the development will meet the required Gosford City Council water quality treatment rates before discharge into the existing stormwater network.

A summary of the required number and position of the treatment devices is indicated within the stormwater drainage plans within Appendix B. Refer also to Appendix C for a summary of the MUSIC model undertaken.

4.4. WSUD Modelling - Music Model

The MUSIC Model for Urban Stormwater Improvement Conceptualisation (MUSIC X) was used to evaluate pollutants loads from the site.

A conceptual view of the MUSIC model used in this report can be found in Appendix C.

4.4.1. Results

MUSIC modelling results for each stage are presented as mean annual loads at the receiving node indicate that adopted target reductions (as per the Cumberland Council DCP) are achieved, as shown in Table 6. MUSIC Link results are contained within Appendix C.

Pollutant	Sources (Kg/yr)	Residual Load (Kg/yr)	Reduction (%)	Target Reduction (%)
Total Suspended Solids	5693	660.80	88.39	85
Total Phosphorus	9.952	3.765	62.17	60
Total Nitrogen	47.53	26.09	45.10	45
Gross Pollutants	475.10	227.48	94.22	90

Table 3 – Overall Site Pollutant Loads

4.5. Ocean Protect Maintenance

The maintenance frequency of the Ocean Protect units is dependent upon several factors:

- Catchment area;
- Surrounding land use;
- Vegetation type;
- Traffic loading; and
- Rainfall patterns.

It is recommended that during the first year of operation the units should be monitored monthly, with maintenance as required.

To ensure that the unit performs optimally, the material collected via the filter bag should be emptied when the level of material is no more than approximately half to two thirds of the total bag depth or when there is evidence of material overflow.

Additional monitoring should be conducted following moderate to extreme rainfall events when preceding months have had little to no rainfall. This monitoring is considered necessary to accommodate for higher

Civil & Structural Engineers | Project Managers | Water Services Coordinator

volumes of runoff generated during major rainfall events. It is anticipated greater accumulation of surface contamination during low rainfall periods and to ensure that the units have been damage due to high pipe velocities.

Upon completion of all maintenance the monitoring/maintenance checklist is to be completed and kept for records, as per Ocean Protect manufacturers guidelines.

5. Sedimentation and Erosion Control

5.1. Sedimentation and Erosion Control (Construction)

A Soil and Water Management Plan (SWMP) has been prepared in accordance with the NSW Department of Housing Publication titled: Managing Urban Stormwater – Soils and Construction (2004) for the whole site.

The key objective of the SWMP are:

- Acknowledging the activities on a construction site which may contribute to erosion, sedimentation and water quality impacts;
- The implementation of industry best management practices to minimise adverse water quality and sedimentation impacts brought about through construction activities on waterbodies surrounding the work; and
- Establishment of processes that effectively manage erosion, sedimentation and water quality practices during the life of the project.

5.1.1. Sources of Pollution

The activities and aspects of the works that have potential to lead to erosion, sediment transport, siltation and contamination of natural waters include:

- Earthworks undertaken immediately prior to rainfall periods;
- Work areas that have not been stabilised;
- Extraction of construction water from waterways during low rainfall periods;
- Clearing of vegetation and the methods adopted, particularly in advance of construction works;
- Stripping of topsoil, particularly in advance of construction works;
- Bulk earthworks and construction of pavements;
- Works within drainage paths, including depressions and waterways;
- Stockpiling of excavated materials;
- Storage and transfer of oils, fuels, fertilisers and chemicals;
- Maintenance of plant and equipment;
- Ineffective implementation of erosion and sediment control measures;
- Inadequate maintenance of environmental control measures; and
- Time taken for the rehabilitation / revegetation of disturbed areas.

5.1.2. Potential Impacts

The major potential impacts on the riparian environment relate to erosion of distributed areas or stockpiles and sediment transportation. Potential adverse impacts from erosion and sediment transportation can include:

- Loss of topsoil;
- Increased water turbidity;
- Decreased levels of dissolved oxygen;
- Changed salinity levels;
- Changed pH levels;
- Smothering of stream beds and aquatic vegetation;
- Reduction in aquatic habitat diversity;
- Increased maintenance costs; and
- Decrease in waterway capacity leading to increased flood levels and durations.

5.2. Soil and Water Management Plan

5.2.1. Overall Strategy

The following construction methodology will be followed to minimise the impact of sedimentation due to construction works:

- Diversion of “clean” water away from the disturbed areas and discharge via suitable scour protection;
- Diversion of “clean” upstream flow away from disturbed areas, in-line with construction staging (to be confirmed during detailed design);
- Provision of hay bale type flow diverters to catch drainage and divert to “clean” water drains;
- Collection of sediment-laden water into temporary sediment control basins within basement excavation to capture the design storm volume and undertake flocculation (if required);
- Provision of construction traffic shaker grids and wash-down to prevent vehicles carrying soils beyond the site;
- Provision of silt fences to filter and retain sediments at source;
- Rapid stabilisation of disturbed and exposed ground surfaces with hydro-seeding areas where future construction and building works are not currently proposed/

Refer to AT&L Drawings DAC071 to DAC072 for Erosion and Sediment Control Plans, for all proposed control and protection measures across the site.

5.2.2. Design of Sediment and Erosion Control Measures

Suitable erosion and sediment controls shall be provided by the Contractor and maintained throughout all stages of works, including at completion of the bulk earthworks.

All design, documentation, installation and maintenance of sediment and erosion controls will be in accordance with the requirements of:

- Protection of the Environment Operations Act;
- Cumberland Council specifications; and
- Office of Environment and Heritage’s ‘Managing Urban Stormwater: Soils and Construction. Landcom, (4th Edition) (The “Blue Book”) Volume 1 and Volume 2.

Ultimately, the final temporary sediment basin locations and sizes will be provided to suit development staging requirements, and will be sized and maintained in accordance with the requirements of the above-mentioned authority documents.

5.3. Site Inspection and Maintenance

The inspection and maintenance requirements outlined in this section must be carried out while either earthworks is being conducted, and all areas re-established.

The Contractor will be required to inspect the site after every rainfall event and at least weekly, and will:

- Inspect and assess the effectiveness of the SWMP and identify any inadequacies that may arise during normal work activities or from a revised construction methodology;
- Construct additional erosion and sediment control works as necessary to ensure the desired protection is given to downstream lands and waterways;
- Ensure that drains operate properly and to affect any repairs;
- Remove spilled sand or other materials from hazard areas, including lands closer than 5 metres from areas of likely concentrated or high velocity flows especially waterways and paved areas;

- Remove trapped sediment whenever less than design capacity remains within the structure;
- Ensure rehabilitated lands have affectively reduced the erosion hazard and to initiate upgrading or repair as appropriate;
- Maintain erosion and sediment control measures in a fully functioning condition until all construction activity is completed and the site has been rehabilitated;
- Remove temporary soil conservation structures as the last activity in the rehabilitation.
- Do not dispose of sediment in a manner that will create an erosion or pollution hazard;
- Submerged inflow pipes must be inspected and de-silted (as required) after each inflow event.

5.4. Conclusion

The erosion control measures proposed for the site will comply with the requirements of Gosford City Council Council DCP and The Department of Environment, Climate Change and Water (DECC).

The proposed SWMP will ensure that the best management practice is applied to the development site in controlling and minimising the negative impacts of soil erosion.

Appendix A



Detailed Site Survey

Appendix B

Civil Development Application Drawings

Appendix C

MUSIC Model and Report



Appendix D

Dial Before you Dig (DBYD)

Appendix E

Drains Results

DESIGN	OSD 1						OSD 2						
	TANK RL	7.6	m				TANK RL	8.1	m				
	TANK IL	5	m				TANK IL	6	m				
	VOLUME	see plan					VOLUME	see plan					
	2YR ORIFICE IL	5.1	m				2YR ORIFICE IL	6.1	m				
	2YR ORIFICE D	150	mm				2YR ORIFICE D	200	mm				
	2YR ORIFICE CL	5.175	m				2YR ORIFICE CL	6.2	m				
	2YR WEIR RL	6.35	m	HIGHER THAN DRAINS, OK			2YR WEIR RL	7.35	m	HIGHER THAN DRAINS, OK			
	2YR WEIR L	5	m				2YR WEIR L	5	m				
	100YR ORIFICE IL	5	m				100YR ORIFICE IL	6	m				
	100YR ORIFICE D	330	mm				100YR ORIFICE D	530	mm				
	100YR ORIFICE CL	5.165	m				100YR ORIFICE CL	6.265	m				
	100YR WEIR RL	7.1	m	HIGHER THAN DRAINS, OK			100YR WEIR RL	7.6	m	HIGHER THAN DRAINS, OK			
	100YR WEIR L	5	m				100YR WEIR L	3.8	m				
DRAINS	SITE			OSD 1			OSD 2			SITE			
	AEP	PRE (L/s)	POST (L/s)	OSD DISCHARGE (L/s)	TWL (m)	FB TO SURFACE (m)	OSD DISCHARGE (L/s)	TWL (m)	FB TO SURFACE (m)	BYPASS (L/s)	TOTAL PSD (L/s)	PSD < PRE?	PSD/PRE (%)
	1EY (1YR)	167	417	42	5.92	1.68	58	7.02	1.08	10	110	YES	66
	0.5EY (2YR)	274	550	49	6.2	1.4	70	7.23	0.87	16	135	YES	49
	20%	447	742	166	6.41	1.19	163	7.4	0.7	26	355	YES	79
	10%	572	930	262	6.45	1.15	266	7.43	0.67	34	562	YES	98
	5%	731	1130	290	6.58	1.02	333	7.45	0.65	42	665	YES	91
	2%	957	1410	309	6.79	0.81	424	7.48	0.62	54	787	YES	82
	1%	1160	1660	331	7.05	0.55	490	7.57	0.53	66	887	YES	76

Appendix F

Flood Impact Assessment



SYDNEY

LEVEL 7 153 WALKER STREET
NORTH SYDNEY NSW 2060
02 9439 1777
INFO@ATL.NET.AU

BRISBANE

SUITE A LEVEL 11
127 CREEK STREET
BRISBANE QLD 4000
07 3211 9581
INFO-QLD@ATL.NET.AU

atl.net.au

Caller Details

Contact:	Glen James	Caller Id:	3052001	Phone:	0411 257 008
Company:	AT&L				
Address:	Level 7 153 Walker Street North Sydney NSW 2060	Email:	glen.j@atl.net.au		

Dig Site and Enquiry Details

WARNING: The map below only displays the location of the proposed dig site and does not display any asset owners' pipe or cables. The area highlighted has been used only to identify the participating asset owners, who will send information to you directly.



User Reference:	38 Young Street		
Working on Behalf of:	Private		
Enquiry Date:	Start Date:	End Date:	
15/12/2022	22/01/2023	05/02/2023	

Address:
38 Young Street
West Gosford NSW 2250

Job Purpose:

Excavation

Location of Workplace:

Both

Onsite Activities:

Manual Excavation

Location in Road:

Road, Nature Strip, Footpath

- Check that the location of the dig site is correct. If not you must submit a new enquiry.
- Should the scope of works change, or plan validity dates expire, you must submit a new enquiry.
- Do NOT dig without plans. Safe excavation is your responsibility. If you do not understand the plans or how to proceed safely, please contact the relevant asset owners.

Notes/Description of Works:

Not supplied

Your Responsibilities and Duty of Care

- The lodgement of an enquiry does not authorise the project to commence. You must obtain all necessary information from any and all likely impacted asset owners prior to excavation.
- If plans are not received within 2 working days, contact the asset owners directly & quote their Sequence No.
- ALWAYS perform an onsite inspection for the presence of assets. Should you require an onsite location, contact the asset owners directly. Please remember, plans do not detail the exact location of assets.
- Pothole to establish the exact location of all underground assets using a hand shovel, before using heavy machinery.
- Ensure you adhere to any State legislative requirements regarding Duty of Care and safe digging requirements.
- If you damage an underground asset you MUST advise the asset owner immediately.
- By using this service, you agree to Privacy Policy and the terms and disclaimers set out at www.1100.com.au
- For more information on safe excavation practices, visit www.1100.com.au

Asset Owner Details

The assets owners listed below have been requested to contact you with information about their asset locations within 2 working days.


Additional time should be allowed for information issued by post. It is **your responsibility** to identify the presence of any underground assets in and around your proposed dig site. Please be aware, that not all asset owners are registered with the Before You Dig service, so it is **your responsibility** to identify and contact any asset owners not listed here directly.

** Asset owners highlighted by asterisks ** require that you visit their offices to collect plans.

Asset owners highlighted with a hash # require that you call them to discuss your enquiry or to obtain plans.

Seq. No.	Authority Name	Phone	Status
219360461	Ausgrid	(02) 4951 0899	NOTIFIED
219360462	Central Coast Council	(02) 4350 3111	NOTIFIED
219360463	Jemena Gas North	1300 880 906	NOTIFIED
219360459	NBN Co NswAct	1800 687 626	NOTIFIED
219360460	Nextgen NCC - NSW	1800 262 663	NOTIFIED
219360464	Telstra NSW Central	1800 653 935	NOTIFIED

END OF UTILITIES LIST



Sequence Number: 219360460

Date: 15/12/2022

DISCLAIMER: THIS DRAWING SHOULD NOT BE SCALED TO LOCATE CABLES. NO WARRANTY IS GIVEN THAT THE INFORMATION IS ACCURATE OR COMPLETE. IF YOU REQUIRE INFORMATION REGARDING LOCATING THE CABLE PLEASE CALL NEXTGEN. THIS DOCUMENT HAS BEEN PREPARED SOLELY FOR DIAL BEFORE YOU DIG USE. THIS PLAN CONTAINS COMMERCIAL SENSITIVE INFORMATION AND IS TO BE TREATED ACCORDINGLY. NO SUCH INFORMATION IS TO BE PASSED ONTO OTHER PARTIES WITHOUT WRITTEN CONSENT FROM NEXTGEN PTY LTD.



LEGEND

Digsite



Area

Assets



Cable



3rd Party Duct



Marker Post



Sequence Number: 219360460

Date: 15/12/2022

DISCLAIMER: THIS DRAWING SHOULD NOT BE SCALED TO LOCATE CABLES. NO WARRANTY IS GIVEN THAT THE INFORMATION IS ACCURATE OR COMPLETE. IF YOU REQUIRE INFORMATION REGARDING LOCATING THE CABLE PLEASE CALL NEXTGEN. THIS DOCUMENT HAS BEEN PREPARED SOLELY FOR DIAL BEFORE YOU DIG USE. THIS PLAN CONTAINS COMMERCIALLY SENSITIVE INFORMATION AND IS TO BE TREATED ACCORDINGLY. NO SUCH INFORMATION IS TO BE PASSED ONTO OTHER PARTIES WITHOUT WRITTEN CONSENT FROM NEXTGEN PTY LTD.




LEGEND

Digsite



Assets





Sequence Number: 219360460		Date: 15/12/2022									
DISCLAIMER: THIS DRAWING SHOULD NOT BE SCALED TO LOCATE CABLES. NO WARRANTY IS GIVEN THAT THE INFORMATION IS ACCURATE OR COMPLETE. IF YOU REQUIRE INFORMATION REGARDING LOCATING THE CABLE PLEASE CALL NEXTGEN. THIS DOCUMENT HAS BEEN PREPARED SOLELY FOR DIAL BEFORE YOU DIG USE. THIS PLAN CONTAINS COMMERCIALLY SENSITIVE INFORMATION AND IS TO BE TREATED ACCORDINGLY. NO SUCH INFORMATION IS TO BE PASSED ONTO OTHER PARTIES WITHOUT WRITTEN CONSENT FROM NEXTGEN PTY LTD.											
		LEGEND <table border="0"> <tr> <th>Digsite</th> <th>Assets</th> </tr> <tr> <td> Area</td> <td> Cable</td> </tr> <tr> <td></td> <td> 3rd Party Duct</td> </tr> <tr> <td></td> <td> Marker Post</td> </tr> </table>		Digsite	Assets	 Area	 Cable		 3rd Party Duct		 Marker Post
Digsite	Assets										
 Area	 Cable										
	 3rd Party Duct										
	 Marker Post										

Plant Location Details



14/12/2022

Glen James
AT&L
Level 7, 153 Walker Street
North Sydney NSW 2060
Phone: +61411257008

Nextgen Networks Pty Ltd
Level 6, 333 Collins Street
Melbourne VIC 3000
T 1800 032 532
E Damage.Relocations@vocus.com.au

Dear Glen James

The following is a response to your Dial Before You Dig enquiry

Assets Affected:

Nextgen Assets

Sequence No:

219360460

Location:

38 Young Street, West Gosford NSW 2250

IMPORTANT:

- Please read and understand all the information and disclaimers provided below
- Sketches and Plans provided by Nextgen Networks are circuit diagrams only and indicate the presence of telecommunications plant in the general vicinity of the geographical area shown; exact ground cover and alignments cannot be given with any certainty and cover may alter over time. Telecommunications plant seldom follow straight lines and careful on site investigation is essential to uncover and reveal its exact position
- The accuracy and/or completeness of the information in the plans can not be guaranteed often due to changes in the surrounding land subsequent to Nextgen's deployment and, accordingly the plans are intended to be indicative only

"DUTY OF CARE"

When working in the vicinity of telecommunications plant you have a legal "Duty of Care" that must be observed. The following points must be considered:

1. It is the responsibility of the owner and any consultant engaged by the owner, including an architect, consulting engineer, developer, and head contractor to design for minimal impact and protection of Nextgen Networks plant. Nextgen Networks will provide free plans and sketches showing the presence of its network to assist at this design stage.
2. It is the owner's (or constructor's) responsibility to:
 - a) Request plans of Nextgen Networks plant for a particular location at a reasonable time before construction begins
 - b) Visually locate Nextgen Networks plant by vacuum excavation (pot-holing) where construction activities may damage or interfere with Nextgen Networks plant (see "Essential Precautions and Approach Distances" section for more information)
 - c) Contact Nextgen Networks Network (see below for details) if Nextgen Networks plant is wholly or partly located near planned construction activities

DAMAGE

ANY DAMAGE TO Nextgen Networks NETWORK MUST BE REPORTED TO 1800 032 532 IMMEDIATELY

- The owner is responsible for all plant damage when works commence prior to obtaining Nextgen Networks plans, or failure to follow agreed instructions
- Nextgen Networks reserves all rights to recover compensation for loss or damage to its cable network or other property including consequential losses

CONCERNING NEXTGEN NETWORK PLANS

- Phone 1100. Dial Before You Dig for free plans of Nextgen Networks plant locations. Please give at least 2 business days notice
- Nextgen Networks plans and information provided are valid for 30 days from the date of issue
- Nextgen Networks retains copyright in all plans and details provided in conjunction with your request. These plans and or details should be disposed of by shredding or any other secure disposal method after use
- Nextgen Networks plans or other details are provided for the use of the applicant, its servants, or agents, and shall not be used for any unauthorised purpose
- Please contact the Network Help Desk (see below for details) immediately should you locate Nextgen Networks assets not indicated on these plans
- Nextgen Networks, its servants or agents shall not be liable for any loss or damage caused or occasioned by the use of plans and or details so supplied to the applicant, its servants and agents, and the applicant agrees to indemnify Nextgen Networks against any claim or demand for any such loss or damage
- Please ensure Nextgen Networks plans and information provided remains on-site at all times throughout your construction phase

ESSENTIAL PRECAUTION AND APPROACH DISTANCE

NOTE: If the following clearances cannot be maintained, please contact the Nextgen Network Help Desk (see below for details) for advice on how best to resolve this situation

1. On receipt of plans and sketches and before commencing excavation work or similar activities near Nextgen Networks plant, carefully locate this plant first to avoid damage. Undertake prior exposure (vacuum excavation) such as potholing when intending to excavate or work closer to Nextgen Networks plant than the following approach distances:
 - Where Nextgen Networks plant is in an area where road and footpaths are well defined by kerbs or other features a minimum clear distance of 600mm must be maintained from where it could be reasonably presumed that plant would reside
 - In non established or unformed reserves and terrain, this approach distance must be at least 1.5 metres
 - In country/rural areas which may have wider variations in reasonably presumed plant presence, the following minimum approach distances apply:
 - d) Parallel to major plant: 10 metres (for optic fibre cable)
 - e) Parallel to other plant: 5 metres

Note: Even pot-holing needs to be undertaken with extreme care, common sense and employing techniques least likely to damage cables. For example - vacuum excavation.

 - If construction work is parallel to Nextgen Networks plant, then careful pot-holing at least every 5m is required to establish the location of all plant, hence continuing nominal locations before work can commence
2. Maintain the following minimum clearance between construction activity and actual location of Nextgen Networks Plant.

Jackhammers/Pneumatic Breakers	<i>Not within 1.0m of actual locations</i>
Vibrating Plate or Wackers Packer Compactors	<i>Not within 0.5m of Nextgen Networks ducts 300mm compact clearance cover before compactor can be used across Nextgen Networks ducts, and 600mm clearance across Nextgen Networks cables in the solid</i>
Boring Equipment (in-line, horizontal and vertical)	<i>Not within 2.0m of actual location Constructor to check depth via vacuum excavation (pot-hole)</i>
Heavy Vehicle Traffic (over 3 tonnes)	<i>Not to be driven across Nextgen Networks ducts with less than 600mm cover. Not to be driven across Nextgen Networks fibre with less than 1.2m cover Constructor to vacuum excavate (pot-hole) and expose plant</i>
Mechanical Excavators, Boring and Tree Removal	<i>Not within 1.0m of actual location Constructor to vacuum excavate (pot-hole) and expose plant</i>

- All Nextgen Networks pits and manholes should be a minimum of 1.2m in from the back of kerb after the completion of your work
- All Nextgen Networks conduit should have the following minimum depth of cover after the completion of your work:

Footway 450mm

Roadway 450mm at drain invert and 600mm below the pavement subgrade level invert

- All Nextgen Networks fibre in the solid should have the following minimum depth of cover after the completion of your work:

Footway 600mm

Roadway 1200mm at drain invert and 1200mm below the pavement subgrade level invert

- For clearance distances relating to Nextgen Networks above ground infrastructure please contact the Network Help Desk (see below for details)

FURTHER ASSISTANCE

Over-the-phone assistance can be obtained by calling the Network Help Desk below.

Nextgen require 5 clear business days notice to conduct an on-site location. The initial on site location visit will not normally incur a charge, but at the discretion of Nextgen subsequent site visits may incur a charge to be applied at an hourly rate.

Where an on-site location is provided, the owner is responsible for all vacuum excavation work (pot-holing) to visually locate and expose Nextgen Networks plant.

If plant location plans or visual location of Nextgen Networks plant by vacuum excavation reveals that the location of Nextgen Networks plan is situated wholly or partly where the owner plans to work, then **Nextgen Networks** must be contacted through the **Network Help Desk** to discuss possible engineering solutions.

The contact number for the **Network Help Desk** is 1800 032 532.

NOTE:

If Nextgen Networks relocation or protection works are part of the agreed solution, then payment to Nextgen Networks for the cost of this work shall be the responsibility of the principal developer. The principal developer will be required to provide Nextgen Networks with the details of their proposed work showing how Nextgen Networks plant is to be accommodated and these details must be approved by the Nextgen National Operations Manager prior to the commencement of site works.

RURAL LANDOWNER - IMPORTANT INFORMATION

Where Nextgen Networks owned cable crosses agricultural land Nextgen Networks will provide a one off free-on-site electronic cable location. Please note that the exact location of cables can only be verified by visual proving by pot holing, which is not covered by this service. The Network Integrity HelpDesk Officer will provide assistance in determining whether a free-on-site location is required. Please ring the Nextgen Network Help Desk as listed above.

PRIVACY NOTE

Your information has been provided to Nextgen Networks by DBYD to enable Nextgen Networks to respond to your DBYD request. Nextgen Networks keeps your information in accordance with its privacy statement entitled 'Protecting Your Privacy' which can be obtained from Nextgen Networks either by calling 1800 032 532 or visiting our website www.nextgengroup.com.au

Warning: Nextgen Networks plans show only the presence of cables and plant. They only show their position relative to road boundaries, property fences etc, at the time of installation and Nextgen Networks does not warrant or hold out that such plans are accurate thereafter due to changes that may occur over time.

DO NOT ASSUME DEPTH OR ALIGNMENT of cables or plant as these vary significantly.

The customer has A DUTY OF CARE when excavating near Nextgen Networks cables and plant. Before using machine excavators NEXTGEN PLANT MUST FIRST BE PHYSICALLY EXPOSED BY VACUUM EXCAVATION (potholing) to identify its location.

Nextgen Networks will seek compensation for damages caused to its property and losses caused to Nextgen Networks and its customers.

EXPERIENCED PLANT LOCATORS (for your area)

On-site assistance should be sought from an Experienced Plant Locator if the telecommunications plant cannot be located within 2.5 metres of the locations indicated on the drawings provided. On-site advice should be obtained from a suitably qualified contractor highly skilled in locating Nextgen Networks plant. If there is any doubt whatsoever about the actual location of the telecommunications plant, the best method for locating the telecommunications plant or the correct interpretation of the drawings provided. In the case where Nextgen Networks plant is outside a recognised road reserve Nextgen Networks recommends that the **Network Help Desk** is contacted for assistance prior to engaging an Experienced Plant Locator.


For the assistance of customers Nextgen Networks has established strict criteria to assess the skill of contractors that may be engaged by owners requiring Nextgen Networks plant locating services to perform any of the following activities if requested to do so by the owner:

- Review Nextgen Networks plans to assess the approximate location of Nextgen Networks plant
- Advise owners of the approximate location of Nextgen Networks plant according to the plans
- Advise the owners of the best method for locating Nextgen Networks plant
- Advise owners of the hazard of unqualified persons attempting to find the exact location of Nextgen Networks plant and working in the vicinity of Nextgen Networks plant without first locating its exact position
- Perform trial hole explorations by vacuum excavation (pot-holing) to expose Nextgen Networks plant with a high degree of skill, competence and efficiency and utilising all necessary safety equipment

Nextgen Networks does not accept any liability or responsibility for the performance of or advice given by any Plant Locator engaged by you but we will, if requested, recommend suitably qualified plant locators.

GENERAL DISCLAIMER

While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Nexgen or PelicanCorp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.



Legend


- Watermain
- Watermain (Asbestos)
- - - Watermain - Expired
- - - Watermain - Expired (Asbestos)
- + Water Valve
- Watermain - Recycled
- Water Hydrant
- Sewer Service Connection
- Sewer Pressure Main
- - - Sewer Pressure Main- Expired
- Sewer Network Structures
- Sewer Maintenance Hole
- Sewer Dead End
- Sewer Lamphole
- Sewer Gravity Main
- Sewer Gravity Main (Asbestos)
- - - Sewer Gravity Main - Expired
- Drainage Pit
- Drainage Pipe
- - - Drainage Pipe - Expired
- Drainage Culverts
- - - Drainage Culverts - Expired



Scale: 1:2050
Expires: 12 Jan 2023

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Central Coast Council nor PelicanCorp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

Overview



Legend


- Watermain
- - - Watermain (Asbestos)
- ... Watermain - Expired
- . - Watermain - Expired (Asbestos)
- + Water Valve
- Water Hydrant
- Sewer Service Connection
- Sewer Pressure Main
- ... Sewer Pressure Main- Expired
- Sewer Network Structures
- Sewer Maintenance Hole
- Sewer Dead End
- Sewer Lamphole
- Sewer Gravity Main
- - - Sewer Gravity Main (Asbestos)
- ... Sewer Gravity Main - Expired
- Drainage Pit
- Drainage Pipe
- - - Drainage Pipe - Expired
- Drainage Culverts
- - - Drainage Culverts - Expired



Scale: 1:1000
Expires: 12 Jan 2023

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Central Coast Council nor PelicanCorp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

Tile No: 1



Legend


- Watermain
- Watermain (Asbestos)
- - - Watermain - Expired
- - - Watermain - Expired (Asbestos)
- + Water Valve
- Watermain - Recycled
- Water Hydrant
- Sewer Service Connection
- Sewer Pressure Main
- - - Sewer Pressure Main- Expired
- Sewer Network Structures
- Sewer Maintenance Hole
- Sewer Dead End
- Sewer Lamphole
- Sewer Gravity Main
- Sewer Gravity Main (Asbestos)
- - - Sewer Gravity Main - Expired
- Drainage Pit
- Drainage Pipe
- - - Drainage Pipe - Expired
- Drainage Culverts
- - - Drainage Culverts - Expired



Scale: 1:1000
Expires: 12 Jan 2023

DISCLAIMER: While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Central Coast Council nor PelicanCorp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

Tile No: 2



	Report Damage: https://service.telstra.com.au/customer/general/forms/report-damage-to-telstra-equipment Ph - 13 22 03 Email - Telstra.Plans@team.telstra.com Planned Services - ph 1800 653 935 (AEST bus hrs only) General Enquiries	Sequence Number: 219360464
Generated On 15/12/2022 10:01:53		CAUTION: Fibre optic and/ or major network present in plot area. Please read the Duty of Care and contact Telstra Plan Services should you require any assistance.

WARNING
Telstra plans and location information conform to Quality Level "D" of the Australian Standard AS 5488-Classification of Subsurface Utility Information. As such, Telstra supplied location information is indicative only. Spatial accuracy is not applicable to Quality Level D. Refer to AS 5488 for further details. The exact position of Telstra assets can only be validated by physically exposing it. Telstra does not warrant or hold out that its plans are accurate and accepts no responsibility for any inaccuracy. Further on site investigation is required to validate the exact location of Telstra plant prior to commencing construction work. A Certified Locating Organisation is an essential part of the process to validate the exact location of Telstra assets and to ensure the asset is protected during construction works.

See the Steps- Telstra Duty of Care that was provided in the email response.

If further information is required, please contact:

Ausgrid BYDA

Phone: (02) 4951 0899

Fax: (02) 4951 0729

Emergency Phone Number 131388



Underground Cable Location Search Advice

**-- Ausgrid Assets Not Recorded in the Vicinity --
(Caution Still Required)**

To:	Glen James AT&L Level 7, 153 Walker Street North Sydney NSW 2060		
		Phone No:	+61411257008
		Issue Date:	15/12/2022

In response to your enquiry, Sequence No219360461 the records of Ausgrid **do not** disclose that there are Ausgrid underground cables in the defined search location.

This search is based on the geographical position of the dig site as denoted in the Before You Dig Australia caller confirmation sheet and an overview is provided:

Address:	38 Young Street West Gosford NSW 2250
Job #:	33303719



****Important****

All information provided to you is ONLY VALID FOR **30 DAYS** from the date of issue

YOU MUST READ AND UNDERSTAND THE:

IMPORTANT INFORMATION

AND

**CHECKLIST FOR WORK NEAR OR AROUND UNDERGROUND CABLES
THAT ARE INCLUDED AS PART OF THIS ADVICE**

IMPORTANT INFORMATION

YOU MUST BE AWARE THAT:


1. There may be underground cables owned by other utilities, in the vicinity of your work, about which Ausgrid has no information.
2. Ausgrid does not usually keep plans of privately owned underground cables or its underground service cables on private property. (Refer NS 156 for further information.)

YOU MUST MAKE YOUR OWN ENQUIRIES IN RESPECT OF THESE CABLES.

YOU MUST UNDERSTAND THAT:

1. Ausgrid takes all reasonable care in providing details of its underground cables. However, owing to changes in road and footway alignments and levels, and the age and incompleteness of some records, it is not possible to conclusively specify the location of all of Ausgrid's underground cables. The accuracy and completeness of the information provided to you cannot be guaranteed. It is intended to be indicative only. It must not be **solely** relied upon when undertaking underground works.
2. Except to the extent that liability may not be capable of lawful exclusion, Ausgrid, its servants and agents will be under no liability whatsoever to any person for loss or damage (including indirect or consequential loss or damage) however caused (including without limitation, for breach of contract, negligence and breach of statute) which may be suffered or incurred from or in connection with the advice provided.
3. Due to the inherent dangers associated with **excavation, under boring and directional drilling** in the vicinity of underground cables, precautions must always be taken when undertaking any underground works. Ausgrid's Network Standard NS 156 specifies standards for working in the vicinity of underground cables. It is deemed to be part of this Advice, and it must be read by you.
4. Due to the inherent risk of compromising the stability of Ausgrid's power poles during excavation which could lead to pole movement or collapse, precautions must always be taken. If excavation is to be carried out within 1m from a power pole, Ausgrid must be contacted at construction.works@ausgrid.com.au for advice. Do not proceed until you have received such advice from Ausgrid.

YOU MUST READ [NETWORK STANDARD NS 156](#), WORKING NEAR OR AROUND UNDERGROUND CABLES. IT IS PART OF THIS ADVICE.



For legend details, please refer to the Coversheet attachment provided as part of this DBYD response.



Scale:1:6301

Issue Date: 14/12/2022
DBYD Seq No: 219360463
DBYD Job No: 33303719
Overview Page:



For legend details, please refer to the Coversheet attachment provided as part of this DBYD response.



Scale:1:2000

Issue Date: 14/12/2022

DBYD Seq No: 219360463

DBYD Job No: 33303719

0m 10m 20m 30m 40m 50m 60m 70m80m

WARNING: This is a representation of Jemena Gas Networks underground assets only and may not indicate all assets in the area. It must not be used for the purpose of exact asset location in order to undertake any type of excavation. This plan is diagrammatic only, and distances scaled from this plan may not be accurate. Please read all conditions and information on the attached information sheet. This extract is subject to those conditions. The information contained on this plan is only valid for 28 days from the date of issue.



For legend details, please refer to the Coversheet attachment provided as part of this DBYD response.



Scale:1:2000


Issue Date: 14/12/2022

DBYD Seq No: 219360463


DBYD Job No: 33303719

0m 10m 20m 30m 40m 50m 60m 70m80m

WARNING: This is a representation of Jemena Gas Networks underground assets only and may not indicate all assets in the area. It must not be used for the purpose of exact asset location in order to undertake any type of excavation. This plan is diagrammatic only, and distances scaled from this plan may not be accurate. Please read all conditions and information on the attached information sheet. This extract is subject to those conditions. The information contained on this plan is only valid for 28 days from the date of issue.



For legend details, please refer to the Coversheet attachment provided as part of this DBYD response.



Scale: 1:2000

Issue Date: 14/12/2022

DBYD Seq No: 219360463

DBYD Job No: 33303719

0m 10m 20m 30m 40m 50m 60m 70m 80m



WARNING: This is a representation of Jemena Gas Networks underground assets only and may not indicate all assets in the area. It must not be used for the purpose of exact asset location in order to undertake any type of excavation. This plan is diagrammatic only, and distances scaled from this plan may not be accurate. Please read all conditions and information on the attached information sheet. This extract is subject to those conditions. The information contained on this plan is only valid for 28 days from the date of issue.

NO ASSETS AFFECTED

This information is only valid for 28 days from the date of issue

Please note that there are **No Gas Mains or Services** in the vicinity of your intended work, as generally illustrated on the attached map. For an explanation of the map, please see the legend attached and read the important information below.

Please note that you have duty of care to ensure that Jemena's assets are not compromised or damaged during any digging, future development or construction work.

Excavation Guidelines:


It is essential that the location of gas pipe/s are confirmed by carefully pot-holing by hand excavation prior to proceeding with mechanical excavation in the vicinity of gas pipes. If you cannot locate the pipe, contact the local Jemena depot.

Important Information:

1. The enclosed plans have been prepared solely for the use of Jemena Gas Networks (NSW) Ltd and Jemena Asset Management Pty Ltd (together "Jemena") and show the position of Jemena's underground gas mains and installations in public gazetted roads. If the enclosed plans show gas assets located on private property or other third party property, these are approximate locations.
2. There may be underground assets owned by other utilities in the vicinity of your work and it is your responsibility to identify and locate such assets.
3. The plans may show the position of underground mains and installations relative to fences, buildings and other structures, as they existed at the time the assets were installed and may not have been updated to take account of any subsequent changes in the location or style of those features. Depth of underground assets may also vary as a result of changes to road, footpath or surface levels subsequent to asset installation.
4. While Jemena takes all reasonable care to ensure the accuracy and completeness of the information provided, it makes no warranty as to the accuracy or completeness of the enclosed plans and does not assume any duty of care to you nor any responsibility for the accuracy, adequacy, suitability or completeness of the plans or for any error or omission. It is intended to be indicative only and must not be solely relied upon when undertaking underground works.
5. Except to the extent that liability may not be capable of being lawfully excluded, Jemena, its employees, agents, officers and contractors will not be liable to any person for loss or damage (including indirect and consequential loss or damage) which may be suffered or incurred in connection with the provision of this information.
6. Persons excavating or carrying out other earthworks will be held responsible for any damage caused to Jemena's underground mains, service lines and equipment. In accordance with the *Work Near Underground Assets – Guide* published in 2007 by Work Cover Authority*, Jemena recommends that you carry out potholing by hand to accurately confirm the location of gas mains and installations prior to commencing excavations.

Network Mains

	Proposed New Main (coloured as per kPa)
	Proposed Isolate (coloured as per kPa)
	Unknown kPa
	2kPa Low Pressure gas main
	7kPa Low Pressure gas main
	30kPa Medium pressure gas main
	100kPa Medium Pressure gas main
	210kPa Medium Pressure gas main
	300kPa Medium Pressure gas main
	400kPa Medium Pressure gas main
	1050kPa High Pressure gas main
	3500kPa High Pressure gas main
	7000kPa High Pressure gas main
	>7000kPa Transmission pipeline
	Isolated Service - Former Med/High Pressure
	Isolated Steel Main - Treat as High Pressure

	Conduit or Casing
100 PVC	Size & Material (see conduit material codes)

	Critical Main - Treat as High Pressure (Main coloured as per kPa)
---	---

	Exposed Main section
EXPOSED	



SHALLOW-SP

Shallow Main section: see Protection Code below, no code assume no protection

SP	Steel Plate	CE	Concrete Encased
PP	PE Plate	UNK	Unknown Type
CS	Concrete Slab		

Gas Services

	Gas service – coloured by kPa
	Serviced Site indicator

Jemena has created service pipe features programmatically based on known pipe characteristics and cartographic principles. They may provide guidance to identify assets whilst in the field in addition to existing processes.

Network Assets

	Siphon
	Network Valve
	High Pressure Main Line Valve ($\geq 1050\text{kPa}$)
	High Pressure Automatic Line Break Valve ($> 1050\text{kPa}$)
	Boundary Regulator Set ($\leq 1050\text{kPa}$)
	Distribution Regulator Set ($\leq 1050\text{kPa}$)
	High Pressure Regulating Station ($> 1050\text{kPa}$)

Annotations

Pipe and Conduit Material Codes

NY	Nylon	NB	Nominal Bore – Cast Iron
PE	Polyethylene	ST	Steel
P/PL	Plastic (undefined)	C/CO	Copper
PVC	Polyvinyl Chloride		


Pipe code combinations and dimension references

	NB 50MM NY	50mm Nylon main inserted into 6 inch (Nominal Bore) Cast Iron pipe
---	-------------------	--


	50MM 32MM NY	32mm Nylon main inserted into 50mm Steel pipe
---	---------------------	---

~1.5	Distance (in metres) of main from Boundary Line (MBL)
------	---

MBK	Distance in Metres Back of Kerb
MKL	Distance in Metres from Kerb Line
MEBL	Distance in Metres from Eastern Boundary Line (North/South/West)
MCL	Distance in Metres from Centre Line of Road
MFL	Distance in Metres from Fence Line



Distance (in metres) of service from side Boundary where the service pipe crosses from the road reserve into the private lot
Service placed towards left or right boundary
Service pipe size & material where known



For connected sites with insufficient asset details, service is shown down the centre of the lot with no attributes plotted




Certified Locating Organisations (CLO)

Find the closest CLO to your worksite on: <https://dbydlocator.com/certified-locating-organisation/>

Read the disclaimer and click:

Accept and Search Now

A national map and an A-Z list of Certified Locating Organisations is displayed.



Use the map to zoom to your work area and choose the closest  Locator indicated.

OR search by entering the **postcode** of your work area.

1. Enter the post/zip code
2. Choose your search radius
3. Click filter (If there is no result, you may have to increase the search radius)
4. Click on the closest  for CLO details or view the results displayed below the map



Locator skills have been tested, and the Organisation has calibrated location and safety equipment.

Telstra is aware of each Certified Locating Organisation and their employee locators.

Only a DBYD Certified Locator registered with a Certified Locating Organisation is authorised to access Telstra network for locating purposes.

Each Certified Locator working for a CLO is issued with a photo ID Card, authorising them to access Telstra pits and manholes for the purpose of cable and plant locations.

Please ask to see your Locators' CLO ID Card.

Before You Dig Australia

Think before you dig

This document has been sent to you because you requested plans of the Telstra network through Before You Dig Australia (BYDA).

If you are working or excavating near telecommunications cables, or there is a chance that cables are located near your site, you are responsible to avoid causing damage to the Telstra network.

Please read this document carefully. Taking your time now and following the steps below can help you avoid damaging our network, interrupting services, and potentially incurring civil and criminal penalties.

Our network is complex and working near it requires expert knowledge. Do not attempt these activities if you are not qualified to do so.



1. Plan

Plan your work with the latest plans of our network.

Plans provided through the BYDA process are indicative only*.

This means the actual location of our asset may differ substantially from that shown on the plans.

Refer to steps 2 and 3 to determine actual location prior to proceeding with construction.



2. Prepare

Engage a DBYD Certified Locating Organisation (CLO) via dbydlocator.com to identify, validate and protect Telstra assets before you commence work.



3. Pothole

Validate underground assets by potholing by hand or using non-destructive vacuum extraction methods.

Electronic detection alone (step 2) is not deemed to validate underground assets and must not be used for construction purposes.

If you cannot validate the Telstra network, you must not proceed with construction.



4. Protect

Protect our network by maintaining the following distances from our assets:

- › 1.0m Mechanical Excavators, Farm Ploughing, Tree Removal
- › 500mm Vibrating Plate or Wacker Packer Compactor
- › 600mm Heavy Vehicle Traffic (over 3 tonnes) not to be driven across Telstra ducts or plant
- › 1.0m Jackhammers/Pneumatic Breakers
- › 2.0m Boring Equipment (in-line, horizontal and vertical)



5. Proceed

You can proceed with your work only once you have completed all the appropriate preparation, potholing and protection.

Report any damage immediately



<https://service.telstra.com.au/customer/general/forms/report-damage-to-telstra-equipment>



13 22 03

If you receive a message asking for an account or phone number say "I Don't have one" Then say "Report Damage" then press 1 to speak to an operator.

Relocating assets

If your project requires the relocation of a Telstra asset, please contact the Telstra Network Integrity Group:



[Request Asset Relocation Or Commercial Works \(telstra.com.au\)](https://telstra.com.au)



NetworkIntegrity@team.telstra.com



1800 810 443 (AEST business hours only)

Never try to move or alter our network infrastructure without authorisation. By law, only authorised people can work on our assets or enter a facility owned or operated by us. Any interference, including unauthorised entry or tampering, may result in legal action.

Further information

Plan enquiries



1800 653 935 (AEST business hours only)



Telstra.Plans@team.telstra.com

Information on how to find cables and request asset relocations:

<https://www.telstra.com.au/consumer-advice/digging-construction>

Asset Plan Readers

PDF [Adobe Acrobat Reader DC Install for all versions](#)

DWF [Download Design Review](#) | [DWF Viewer](#) | [Autodesk](#)

Disclaimer and legal details



*Telstra advises that the accuracy of the information provided by Telstra conforms to Quality Level D as defined in AS5488-2013.

It is a criminal offence under the Criminal Code Act 1995 (Cth) to tamper or interfere with telecommunications infrastructure.

Telstra will also take action to recover costs and damages from persons who damage assets or interfere with the operation of Telstra's networks.

By receiving this information including the indicative plans that are provided as part of this information package you confirm that you understand and accept the risks of working near Telstra's network and the importance of taking all of the necessary steps to confirm the presence, alignments and various depths of Telstra's network. This in addition to, and not in replacement of, any duties and obligations you have under applicable law.

When working in the vicinity of a telecommunications plant you have a "Duty of Care" that must be observed. Please read and understand all the information and disclaimers provided below.

The Telstra network is complex and requires expert knowledge to interpret information, to identify and locate components, to pothole underground assets for validation and to safely work around assets without causing damage. If you are not an expert and/or qualified in these areas, then you must not attempt these activities. Telstra will seek compensation for damages caused to its property and losses caused to Telstra and its customers. The 5 P's to prevent damage to Telstra assets are listed above. Construction activities and/or any activities that potentially may impact on Telstra's assets must not commence without first undertaking these steps. Construction activities can include anything that involves breaking ground, potentially affecting Telstra assets.

If you are designing a project, it is recommended that you also undertake these steps to validate underground assets prior to committing to your design.

This Notice has been provided as a guide only and may not provide you with all the information that is required for you to determine what assets are on or near your site of interest. You will also need to collate and understand all of the information received from other Utilities and understand that some Utilities are not a part of the BYDA program and make your own enquiries as appropriate. It is the responsibility of the entities undertaking the works to protect Telstra's network during excavation / construction works.

Telstra owns and retains the copyright in all plans and details provided in conjunction with the applicant's request. The applicant is authorised to use the plans and details only for the purpose indicated in the applicant's request. The applicant must not use the plans or details for any other purpose.

Telstra plans or other details are provided only for the use of the applicant, its servants, agents, or Certified Locating Organisation. The applicant must not give the plans or details to any parties other than these and must not generate profit from commercialising the plans or details.

Telstra, its servants or agents shall not be liable for any loss or damage caused or occasioned by the use of plans and or details so supplied to the applicant, its servants and agents, and the applicant agrees to indemnify Telstra against any claim or demand for any such loss or damage.

Please ensure Telstra plans and information provided always remains on-site throughout the inspection, location, and construction phase of any works.

Telstra plans are valid for 60 days after issue and must be replaced if required after the 60 days.

Data Extraction Fees

In some instances, a data extraction fee may be applicable for the supply of Telstra information. Typically, a data extraction fee may apply to large projects, planning and design requests or requests to be supplied in non-standard formats. For further details contact Telstra Planned Services.

Telstra does not accept any liability or responsibility for the performance of or advice given by a Certified Locating Organisation. Certification is an initiative taken by Telstra towards the establishment and maintenance of competency standards. However, performance and the advice given will always depend on the nature of the individual engagement.

Neither the Certified Locating Organisation nor any of its employees are an employee or agent for Telstra. Telstra is not liable for any damage or loss caused by the Certified Locating Organisation or its employees.

Once all work is completed, the excavation should be reinstated with the same type of excavated material unless specified by Telstra

The information contained within this pamphlet must be used in conjunction with other material supplied as part of this request for information to adequately control the risk of potential asset damage.

When using excavators and other machinery, also check the location of overhead power lines.

Workers and equipment must maintain safety exclusion zones around power lines

WARNING: Telstra plans and location information conform to Quality Level 'D' of the Australian Standard AS 5488 - Classification of Subsurface Utility Information. As such, Telstra supplied location information is indicative only. Spatial accuracy is not applicable to Quality Level D. Refer to AS 5488 for further details. Telstra does not warrant or hold out that its plans are accurate and accepts no responsibility for any inaccuracy shown on the plans. **FURTHER ON SITE INVESTIGATION IS REQUIRED TO VALIDATE THE EXACT LOCATION OF TELSTRA PLANT PRIOR TO COMMENCING CONSTRUCTION WORK.** A plant location service is an essential part of the process to validate the exact location of Telstra assets and to ensure the assets are protected during construction works. The exact position of Telstra assets can only be validated by physically exposing them. Telstra will seek compensation for damages caused to its property and losses caused to Telstra and its customers.

Privacy Note

Your information has been provided to Telstra by BYDA to enable Telstra to respond to your BYDA request. Telstra keeps your information in accordance with its privacy statement. You can obtain a copy at www.telstra.com.au/privacy or by calling us at 1800 039 059 (business hours only).



OPENING ELECTRONIC MAP ATTACHMENTS -

Telstra Cable Plans are generated automatically in either PDF or DWF file types dependant on the site address and the size of area selected. You may need to download and install free viewing software from the internet e.g.



PDF Map Files (max size A3)

Adobe Acrobat Reader (<http://get.adobe.com/reader/>),



DWF Map Files (all sizes over A3)

Autodesk A360 (<https://360.autodesk.com/viewer>) or

Autodesk Design Review (<http://usa.autodesk.com/design-review/>) for DWF files.
(Windows)



Telstra DBYD map related enquiries

email - Telstra.Plans@team.telstra.com

1800 653 935 (AEST Business Hours only)



REPORT ANY DAMAGE TO THE TELSTRA NETWORK IMMEDIATELY

Report online - <https://service.telstra.com.au/customer/general/forms/report-damage-to-telstra-equipment>

Ph: 13 22 03


If you receive a message asking for a phone or account number say:

"I don't have one" then say "Report Damage" then press 1 to speak to an operator.



Telstra New Connections / Disconnections

13 22 00



Telstra asset relocation enquiries: 1800 810 443 (AEST business hours only).

NetworkIntegrity@team.telstra.com

<https://www.telstra.com.au/consumer-advice/digging-construction>


Certified Locating Organisation (CLO)

<https://dbydlocator.com/certified-locating-organisation/>



DBYD Certification

Please refer to attached Accredited Plant Locator.pdf



Telstra Smart Communities


Information for new developments (developers, builders, homeowners)

<https://www.telstra.com.au/smart-community>

LEGEND



For more info contact a [Certified Locating Organisation](#) or Telstra Plan Services 1800 653 935



WARNING: Telstra plans and location information conform to Quality Level 'D' of the Australian Standard AS 5488 - Classification of Subsurface Utility Information. As such, Telstra supplied location information is indicative only. Spatial accuracy is not applicable to Quality Level D. Refer to AS 5488 for further details. Telstra does not warrant or hold out that its plans are accurate and accepts no responsibility for any inaccuracy shown on the plans. FURTHER ON SITE INVESTIGATION IS REQUIRED TO VALIDATE THE EXACT LOCATION OF TELSTRA PLANT PRIOR TO COMMENCING CONSTRUCTION WORK. A plant location service is an essential part of the process to validate the exact location of Telstra assets and to ensure the assets are protected during construction works. The exact position of Telstra assets can only be validated by physically exposing them. Telstra will seek compensation for damages caused to its property and losses caused to Telstra and its customers.

MUSIC-link Report

Project Details		Company Details	
Project:		Company:	
Report Export Date:	10/08/2023	Contact:	
Catchment Name:	Receiving Node	Address:	
Catchment Area:	2.1203ha	Phone:	
Impervious Area*:	75.1473848040372%	Email:	
Rainfall Station:			
Modelling Time-step:	Six minutes		
Modelling Period:	01/01/74 - 31/12/1993 11:54:00 PM		
Mean Annual Rainfall:	1296.513mm		
Evapotranspiration:	1261.206mm		
MUSICX Version:	1.1.0.11940 (5.0.3.11940)		
MUSIC-link data Version:	3.8		
Study Area:	Central Coast Council		
Scenario:	Central Coast Development		

* takes into account area from all source nodes that link to the chosen reporting node, excluding Import Data Nodes

Treatment Train Effectiveness		Treatment Nodes		Source Nodes	
Node:	Reduction	Node Type	Number	Node Type	Number
Flow	-0.002%	Generic Treatment Nodes	4	Urban_Roof Nodes	2
TSS	88.393%	Swale Nodes	4	Urban_SealedRoad Nodes	4
TP	62.167%			Urban_Mixed Nodes	10
TN	45.104%				
GP	94.216%				

Comments

Passing Parameters					
Node Type	Node Name	Parameter	Min	Max	Actual
Generic	1-JellyFish JF2250-10-2	High Flow Bypass	None	99	0.055 m³/s
Generic	1-OceanSave OS-0606	High Flow Bypass	None	99	0.028 m³/s
Generic	2-JellyFish JF2250-8-2	High Flow Bypass	None	99	0.045 m³/s
Generic	2-OceanSave OS-0606	High Flow Bypass	None	99	0.028 m³/s
Receiving	Receiving Node	Flow Reduction	None	None	-0.002 %
Receiving	Receiving Node	GP Reduction	90	None	94.216 %
Receiving	Receiving Node	TN Reduction	45	None	45.104 %
Receiving	Receiving Node	TP Reduction	45	None	62.167 %
Receiving	Receiving Node	TSS Reduction	80	None	88.393 %
Swale	Swale 1	Bed Slope	0.02	0.05	0.02
Swale	Swale 2	Bed Slope	0.02	0.05	0.02
Swale	Swale 3	Bed Slope	0.02	0.05	0.02
Swale	Swale 4	Bed Slope	0.02	0.05	0.02
Urban_Mixed	BYPASS 1 - landscape - (mixed) - 0.0545ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_Mixed	BYPASS 1 - landscape - (mixed) - 0.0545ha - 10% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Mixed	BYPASS 1 - landscape - (mixed) - 0.0545ha - 10% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_Mixed	BYPASS 1 - landscape - (mixed) - 0.0545ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	BYPASS 1 - landscape - (mixed) - 0.0545ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_Mixed	BYPASS 1 - landscape - (mixed) - 0.0545ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Mixed	BYPASS 3 - landscape - (mixed) - 0.0147ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_Mixed	BYPASS 3 - landscape - (mixed) - 0.0147ha - 10% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Mixed	BYPASS 3 - landscape - (mixed) - 0.0147ha - 10% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_Mixed	BYPASS 3 - landscape - (mixed) - 0.0147ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	BYPASS 3 - landscape - (mixed) - 0.0147ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_Mixed	BYPASS 3 - landscape - (mixed) - 0.0147ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Mixed	BYPASS 5 - landscape - (mixed) - 0.0207ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11

NOTE: A successful self-validation check of your model does not constitute an approved model by Central Coast Council
MUSIC-link now in MUSICX by eWater – leading software for modelling stormwater solutions

Node Type	Node Name	Parameter	Min	Max	Actual
Urban_Mixed	BYPASS 5 - landscape - (mixed) - 0.0207ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.85	-0.85	-0.85
Urban_Mixed	BYPASS 5 - landscape - (mixed) - 0.0207ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	BYPASS 5 - landscape - (mixed) - 0.0207ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_Mixed	BYPASS 5 - landscape - (mixed) - 0.0207ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Mixed	WQ1b - landscape - (mixed) - 0.0101ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_Mixed	WQ1b - landscape - (mixed) - 0.0101ha - 10% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Mixed	WQ1b - landscape - (mixed) - 0.0101ha - 10% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_Mixed	WQ1b - landscape - (mixed) - 0.0101ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	WQ1b - landscape - (mixed) - 0.0101ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_Mixed	WQ1b - landscape - (mixed) - 0.0101ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Mixed	WQ1c - landscape - (mixed) - 0.2171ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_Mixed	WQ1c - landscape - (mixed) - 0.2171ha - 10% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Mixed	WQ1c - landscape - (mixed) - 0.2171ha - 10% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85

Only certain parameters are reported when they pass validation

Node Type	Node Name	Parameter	Min	Max	Actual
Urban_Mixed	WQ1c - landscape - (mixed) - 0.2171ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	WQ1c - landscape - (mixed) - 0.2171ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_Mixed	WQ1c - landscape - (mixed) - 0.2171ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Mixed	WQ1d - landscape - (mixed) - 0.0249ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_Mixed	WQ1d - landscape - (mixed) - 0.0249ha - 10% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Mixed	WQ1d - landscape - (mixed) - 0.0249ha - 10% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_Mixed	WQ1d - landscape - (mixed) - 0.0249ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	WQ1d - landscape - (mixed) - 0.0249ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_Mixed	WQ1d - landscape - (mixed) - 0.0249ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Mixed	WQ1e - landscape - (mixed) - 0.1227ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_Mixed	WQ1e - landscape - (mixed) - 0.1227ha - 10% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Mixed	WQ1e - landscape - (mixed) - 0.1227ha - 10% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_Mixed	WQ1e - landscape - (mixed) - 0.1227ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	WQ1e - landscape - (mixed) - 0.1227ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_Mixed	WQ1e - landscape - (mixed) - 0.1227ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Mixed	WQ2d - landscape - (mixed) - 0.0599ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_Mixed	WQ2d - landscape - (mixed) - 0.0599ha - 10% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Mixed	WQ2d - landscape - (mixed) - 0.0599ha - 10% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_Mixed	WQ2d - landscape - (mixed) - 0.0599ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	WQ2d - landscape - (mixed) - 0.0599ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_Mixed	WQ2d - landscape - (mixed) - 0.0599ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Mixed	WQ2e - landscape - (mixed) - 0.0386ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_Mixed	WQ2e - landscape - (mixed) - 0.0386ha - 10% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Mixed	WQ2e - landscape - (mixed) - 0.0386ha - 10% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_Mixed	WQ2e - landscape - (mixed) - 0.0386ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	WQ2e - landscape - (mixed) - 0.0386ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2

NOTE: A successful self-validation check of your model does not constitute an approved model by Central Coast Council
MUSIC-link now in MUSICX by eWater – leading software for modelling stormwater solutions

Node Type	Node Name	Parameter	Min	Max	Actual
Urban_Mixed	WQ2e - landscape - (mixed) - 0.0386ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Mixed	WQ2f - landscape - (mixed) - 0.0223ha - 10% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_Mixed	WQ2f - landscape - (mixed) - 0.0223ha - 10% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Mixed	WQ2f - landscape - (mixed) - 0.0223ha - 10% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_Mixed	WQ2f - landscape - (mixed) - 0.0223ha - 10% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.6	-0.6	-0.6
Urban_Mixed	WQ2f - landscape - (mixed) - 0.0223ha - 10% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_Mixed	WQ2f - landscape - (mixed) - 0.0223ha - 10% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.15	2.15	2.15
Urban_Roof	WQ2a - building 1 - (roof) - 0.2349ha - 100% impervious	Nitrogen Constituents.Base Flow.Mean	0.32	0.32	0.32
Urban_Roof	WQ2a - building 1 - (roof) - 0.2349ha - 100% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Roof	WQ2a - building 1 - (roof) - 0.2349ha - 100% impervious	Phosphorus Constituents.Base Flow.Mean	-0.82	-0.82	-0.82
Urban_Roof	WQ2a - building 1 - (roof) - 0.2349ha - 100% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.89	-0.89	-0.89
Urban_Roof	WQ2a - building 1 - (roof) - 0.2349ha - 100% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.1	1.1	1.1
Urban_Roof	WQ2a - building 1 - (roof) - 0.2349ha - 100% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	1.3	1.3	1.3
Urban_Roof	WQ2b - building 2 - (roof) - 0.0377ha - 100% impervious	Nitrogen Constituents.Base Flow.Mean	0.32	0.32	0.32

Only certain parameters are reported when they pass validation

Node Type	Node Name	Parameter	Min	Max	Actual
Urban_Roof	WQ2b - building 2 - (roof) - 0.0377ha - 100% impervious	Nitrogen Constituents.Storm Flow.Mean	0.3	0.3	0.3
Urban_Roof	WQ2b - building 2 - (roof) - 0.0377ha - 100% impervious	Phosphorus Constituents.Base Flow.Mean	-0.82	-0.82	-0.82
Urban_Roof	WQ2b - building 2 - (roof) - 0.0377ha - 100% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.89	-0.89	-0.89
Urban_Roof	WQ2b - building 2 - (roof) - 0.0377ha - 100% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.1	1.1	1.1
Urban_Roof	WQ2b - building 2 - (roof) - 0.0377ha - 100% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	1.3	1.3	1.3
Urban_SealedRoad	BYPASS 2 - driveway- (sealed road) - 0.0212ha - 100% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_SealedRoad	BYPASS 2 - driveway- (sealed road) - 0.0212ha - 100% impervious	Nitrogen Constituents.Storm Flow.Mean	0.34	0.34	0.34
Urban_SealedRoad	BYPASS 2 - driveway- (sealed road) - 0.0212ha - 100% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_SealedRoad	BYPASS 2 - driveway- (sealed road) - 0.0212ha - 100% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.3	-0.3	-0.3
Urban_SealedRoad	BYPASS 2 - driveway- (sealed road) - 0.0212ha - 100% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_SealedRoad	BYPASS 2 - driveway- (sealed road) - 0.0212ha - 100% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.43	2.43	2.43
Urban_SealedRoad	BYPASS 4 - driveway- (sealed road) - 0.0079ha - 100% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_SealedRoad	BYPASS 4 - driveway- (sealed road) - 0.0079ha - 100% impervious	Nitrogen Constituents.Storm Flow.Mean	0.34	0.34	0.34
Urban_SealedRoad	BYPASS 4 - driveway- (sealed road) - 0.0079ha - 100% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_SealedRoad	BYPASS 4 - driveway- (sealed road) - 0.0079ha - 100% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.3	-0.3	-0.3
Urban_SealedRoad	BYPASS 4 - driveway- (sealed road) - 0.0079ha - 100% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_SealedRoad	BYPASS 4 - driveway- (sealed road) - 0.0079ha - 100% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.43	2.43	2.43
Urban_SealedRoad	WQ1a - hard stand - (sealed road) - 0.7816ha - 100% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_SealedRoad	WQ1a - hard stand - (sealed road) - 0.7816ha - 100% impervious	Nitrogen Constituents.Storm Flow.Mean	0.34	0.34	0.34
Urban_SealedRoad	WQ1a - hard stand - (sealed road) - 0.7816ha - 100% impervious	Phosphorus Constituents.Base Flow.Mean	-0.85	-0.85	-0.85
Urban_SealedRoad	WQ1a - hard stand - (sealed road) - 0.7816ha - 100% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.3	-0.3	-0.3
Urban_SealedRoad	WQ1a - hard stand - (sealed road) - 0.7816ha - 100% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_SealedRoad	WQ1a - hard stand - (sealed road) - 0.7816ha - 100% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.43	2.43	2.43
Urban_SealedRoad	WQ2c - hard stand - (sealed road) - 0.4515ha - 100% impervious	Nitrogen Constituents.Base Flow.Mean	0.11	0.11	0.11
Urban_SealedRoad	WQ2c - hard stand - (sealed road) - 0.4515ha - 100% impervious	Nitrogen Constituents.Storm Flow.Mean	0.34	0.34	0.34
Urban_SealedRoad	WQ2c - hard stand - (sealed road) - 0.4515ha - 100% impervious	Phosphorus Constituents.Base	-0.85	-0.85	-0.85

NOTE: A successful self-validation check of your model does not constitute an approved model by Central Coast Council
MUSIC-link now in MUSICX by eWater – leading software for modelling stormwater solutions

Node Type	Node Name	Parameter	Min	Max	Actual
Urban_SealedRoad	WQ2c - hard stand - (sealed road) - 0.4515ha - 100% impervious	Phosphorus Constituents.Storm Flow.Mean	-0.3	-0.3	-0.3
Urban_SealedRoad	WQ2c - hard stand - (sealed road) - 0.4515ha - 100% impervious	Total Suspended Solids Constituents.Base Flow.Mean	1.2	1.2	1.2
Urban_SealedRoad	WQ2c - hard stand - (sealed road) - 0.4515ha - 100% impervious	Total Suspended Solids Constituents.Storm Flow.Mean	2.43	2.43	2.43

Only certain parameters are reported when they pass validation

TRANSPORT DEPOT



7A-11 RACECOURSE RD,

5-9 FAUNCE ST & YOUNG ST, WEST GOSFORD

CIVIL PACKAGE


STATE SIGNIFICANT DEVELOPMENT

DRAWING NO.	DRAWING TITLE
GENERAL	
22-1063-DAC000	COVER SHEET AND LOCALITY PLAN
22-1063-DAC001	GENERAL NOTES AND LEGENDS
22-1063-DAC003	GENERAL ARRANGEMENT PLAN
SITEWORKS	
22-1063-DAC011	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 1
22-1063-DAC012	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 2
22-1063-DAC013	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 3
22-1063-DAC014	SITEWORKS AND STORMWATER DRAINAGE PLAN SHEET 4
DETAILS	
22-1063-DAC021	SITEWORKS DETAILS SHEET 1
22-1063-DAC022	SITEWORKS DETAILS SHEET 2
22-1063-DAC023	SITEWORKS DETAILS SHEET 3
22-1063-DAC025	STORMWATER DRAINAGE DETAILS SHEET 1
22-1063-DAC026	STORMWATER DRAINAGE DETAILS SHEET 2
22-1063-DAC027	STORMWATER DRAINAGE DETAILS SHEET 3
22-1063-DAC028	STORMWATER DRAINAGE DETAILS SHEET 4
PAVEMENT	
22-1063-DAC031	PAVEMENT PLAN
STORMWATER DRAINAGE	
22-1063-DAC051	STORMWATER DRAINAGE OSD CATCHMENT PLAN
22-1063-DAC052	STORMWATER DRAINAGE MUSIC CATCHMENT PLAN
22-1063-DAC053	STORMWATER DRAINAGE OSD 1 ROOF PLAN
22-1063-DAC054	STORMWATER DRAINAGE OSD 1 BASE PLAN
22-1063-DAC055	STORMWATER DRAINAGE OSD 1 SECTIONS AND DETAILS
22-1063-DAC056	STORMWATER DRAINAGE OSD 2 ROOF PLAN
22-1063-DAC057	STORMWATER DRAINAGE OSD 2 BASE PLAN
22-1063-DAC058	STORMWATER DRAINAGE OSD 2 SECTIONS AND DETAILS
EROSION AND SEDIMENT CONTROL	
22-1063-DAC071	EROSION AND SEDIMENT CONTROL PLAN
22-1063-DAC075	EROSION AND SEDIMENT CONTROL DETAILS




LOCALITY PLAN
NOT TO SCALE

		Bar Scales	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	Client WALUYA PTY LTD	Scales NTS	Drawn	CK	Project TRANSPORT DEPOT 7A-11 RACECOURSE RD 5-9 FAUNCE ST & YOUNG ST WEST GOSFORD	Civil Engineers and Project Managers  Level 7, 153 Walker Street North Sydney NSW 2060 P 02 9439 1777 E info@atl.net.au www.atl.net.au ABN 96 130 882 405		
						Designed	CK				
						Grid	MGA56			Checked	GJ
						Height Datum	AHD			Approved	AT
A	ISSUE FOR APPROVAL	10-08-23									
Issue	Description	Date	Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION Project - Drawing No. 22-1063-DAC000								
			A1 Issue A								



A	ISSUE FOR APPROVAL	10-08-23
Issue	Description	Date



THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L

Client

WALUYA PTY LTD

Scales	1:400	Drawn	CK
		Designed	CK
	Grid MGA56	Checked	GJ
	Height Datum AHD	Approved	AT

Project	TRANSPORT DEPORT 7A-11 RACECOURSE RD 5-9 FAUNCE ST & YOUNG ST WEST GOSFORD
Title	
GENERAL ARRANGEMENT PLAN	

Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 P 02 9439 1777 E info@atl.net.au www.atl.net.au ABN 96 130 882 405		
at&l		
Status	FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1
Project - Drawing No.	22-1063-DAC003	Issue A

LEGEND - EXISTING

SURVEY LEGEND

BENCH MARK	
COMMS UNDERGROUND	
COMMS PIT/MANHOLE	
COMMS PILLAR	
DRAINAGE GRATED PIT	
DRAINAGE KERB INLET PIT	
ELECTRICAL POWER POLE	
ELECTRICAL UNDERGROUND CABLE	
FENCE	
GATE	
ROAD BOLLARD	
SEWER MANHOLE	
SEWER PIPE	
SIGN POST	
TREE (HEIGHT, TRUNK DIAMETER, SPREAD)	
WATER METER	
WATER TAP	
WATER STOP VALVE	
WATER HYDRANT	
BOTTOM OF BANK	
TOP OF BANK	

LEGEND - SITEWORKS

EXISTING


EXISTING BOUNDARY	
EXISTING CONTOUR	
SEWER	
ELECTRICAL	
WATER	
STORMWATER	
TELECOMMUNICATIONS	
RIISING MAIN	
STRUCTURAL ROOT ZONE (SRZ)	
TREE PROTECTION ZONE (TPZ)	

PROPOSED

CONTOUR (MINOR)	
CONTOUR (MINOR)	
FINISHED SURFACE LEVEL	
VEHICULAR CROSSING (REFER TO CCC STD DWG SD0506)	
SWALE, MINIMUM 0.5% FALL	
KERB ONLY	
RETAINING WALL	
BATTER	
STORMWATER JUNCTION PIT & LABEL	
STORMWATER SURFACE INLET PIT	
STORMWATER PIPE	
STORMWATER KERB INLET PIT	
GRATED DRAIN	

NOTE:

EXISTING BOUNDARY TO BE REMOVED SWITCHED OFF ON THIS DRAWING FOR CLARITY.





FOR CONTINUATION REFER TO SHEET 3, DAC013

FOR CONTINUATION REFER TO SHEET 2, DAC012

Issue	Description	Date
A	ISSUE FOR APPROVAL	10-08-23

Bar Scales




Client	WALUYA PTY LTD
--------	----------------

Scales	1:200
Grid	MGA56
Height Datum	AHD

Drawn	JC
Designed	JC
Checked	GJ
Approved	AT

Project	TRANSPORT DEPOT 7A-11 RACECOURSE RD 5-9 FAUNCE ST & YOUNG ST WEST GOSFORD
Title	SITWORKS AND STORMWATER DRAINAGE PLAN SHEET 1

Civil Engineers and Project Managers	Level 7, 153 Walker Street North Sydney NSW 2060 P 02 9439 1777 E info@atl.net.au www.atl.net.au ABN 96 130 882 405
Status	FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION
Project - Drawing No.	22-1063-DAC011
Issue	A



LEGEND - SITEWORKS

EXISTING

EXISTING BOUNDARY

EXISTING CONTOUR

SEWER

ELECTRICAL

WATER

STORMWATER

TELECOMMUNICATIONS

RISING MAIN

STRUCTURAL ROOT ZONE (SRZ)

TREE PROTECTION ZONE (TPZ)

PROPOSED

CONTOUR (MINOR)

CONTOUR (MINOR)

FINISHED SURFACE LEVEL

VEHICULAR CROSSING
(REFER TO CCC STD DWG SD0506)

SWALE, MINIMUM 0.5% FALL

KERB ONLY

RETAINING WALL

BUILDING OUTLINE

BATTER

STORMWATER JUNCTION PIT & LABEL

STORMWATER SURFACE INLET PIT

STORMWATER PIPE

STORMWATER KERB INLET PIT

GRATED DRAIN

• F 44.45

VC

KO

A-1

Ø225

GO

LEGEND - EXISTING

SURVEY LEGEND

BENCH MARK

COMMS UNDERGROUND

COMMS PIT/MANHOLE

COMMS PILLAR

DRAINAGE GRATED PIT

DRAINAGE KERB INLET PIT

ELECTRICAL POWER POLE

ELECTRICAL UNDERGROUND CABLE

FENCE

GATE

ROAD BOLLARD

SEWER MANHOLE

SEWER PIPE

SIGN POST

TREE (HEIGHT, TRUNK DIAMETER, SPREAD)

WATER METER

WATER TAP

WATER STOP VALVE

WATER HYDRANT

BOTTOM OF BANK



TOP OF BANK

NOTE:
EXISTING BOUNDARY TO BE REMOVED SWITCHED OFF ON THIS DRAWING FOR CLARITY.

FOR CONTINUATION REFER TO SHEET 1, DAC011

FOR CONTINUATION REFER TO SHEET 4, DAC014

A	ISSUE FOR APPROVAL	10-08-23
Issue	Description	Date



Client

WALUYA PTY LTD

Scales	1:200	Drawn	JC
		Designed	JC
Grid	MGA56	Checked	GJ
Height Datum	AHD	Approved	AT

Project

TRANSPORT DEPOT
7A-11 RACECOURSE RD
5-9 FAUNCE ST & YOUNG ST
WEST GOSFORD

Title

SITWORKS AND
STORMWATER DRAINAGE
PLAN
SHEET 2

Civil Engineers and Project Managers

Level 7, 153 Walker Street
North Sydney
NSW 2060
P 02 9439 1777
E info@atl.net.au
www.atl.net.au
ABN 96 130 882 405

at&l

Status

FOR APPROVAL
NOT TO BE USED FOR CONSTRUCTION


Project - Drawing No.

22-1063-DAC012

A1

Issue

A



LEGEND - EXISTING

SURVEY LEGEND

- BENCH MARK
- COMMS UNDERGROUND
- COMMS PIT/MANHOLE
- COMMS PILLAR
- DRAINAGE GRATED PIT
- DRAINAGE KERB INLET PIT
- ELECTRICAL POWER POLE
- ELECTRICAL UNDERGROUND CABLE
- FENCE
- GATE
- ROAD BOLLARD
- SEWER MANHOLE
- SEWER PIPE
- SIGN POST
- TREE (HEIGHT, TRUNK DIAMETER, SPREAD)
- WATER METER
- WATER TAP
- WATER STOP VALVE
- WATER HYDRANT
- BOTTOM OF BANK
- TOP OF BANK

LEGEND - SITEWORKS

EXISTING

- EXISTING BOUNDARY
- EXISTING CONTOUR
- SEWER
- ELECTRICAL
- WATER
- STORMWATER
- TELECOMMUNICATIONS
- RIISING MAIN
- STRUCTURAL ROOT ZONE (SRZ)
- TREE PROTECTION ZONE (TPZ)

PROPOSED

- CONTOUR (MINOR)
- CONTOUR (MINOR)
- FINISHED SURFACE LEVEL
- VEHICULAR CROSSING (REFER TO CCC STD DWG SD0506)
- SWALE, MINIMUM 0.5% FALL
- KERB ONLY
- RETAINING WALL
- BATTER
- STORMWATER JUNCTION PIT & LABEL
- STORMWATER SURFACE INLET PIT
- STORMWATER PIPE
- STORMWATER KERB INLET PIT
- GRATED DRAIN


NOTE:

EXISTING BOUNDARY TO BE REMOVED SWITCHED OFF ON THIS DRAWING FOR CLARITY.

Bar Scales

0 5 10 15 20m

1:200 @ A1 1:400 @ A3



Client

WALUYA PTY LTD

Scales

1:200

Grid

MGA56

Height Datum

AHD

Drawn

JC

Designed

JC

Checked

GJ

Approved

AT

Project

TRANSPORT DEPOT
7A-11 RACECOURSE RD
5-9 FAUNCE ST & YOUNG ST
WEST GOSFORD

Title

SITWORKS AND
STORMWATER DRAINAGE
PLAN
SHEET 3

Civil Engineers and Project Managers

Level 7, 153 Walker Street
North Sydney
NSW 2060
P 02 9439 1777
E info@atl.net.au
www.atl.net.au
ABN 96 130 882 405

at&l

Status


FOR APPROVAL
NOT TO BE USED FOR CONSTRUCTION

Project - Drawing No.
22-1063-DAC013

A1

Issue

A



LEGEND - EXISTING

SURVEY LEGEND

- BENCH MARK
- COMMS UNDERGROUND
- COMMS PIT/MANHOLE
- COMMS PILLAR
- DRAINAGE GRATED PIT
- DRAINAGE KERB INLET PIT
- ELECTRICAL POWER POLE
- ELECTRICAL UNDERGROUND CABLE
- FENCE
- GATE
- ROAD BOLLARD
- SEWER MANHOLE
- SEWER PIPE
- SIGN POST
- TREE (HEIGHT, TRUNK DIAMETER, SPREAD)
- WATER METER
- WATER TAP
- WATER STOP VALVE
- WATER HYDRANT
- BOTTOM OF BANK
- TOP OF BANK

LEGEND - SITEWORKS

EXISTING



- EXISTING BOUNDARY
- EXISTING CONTOUR
- SEWER
- ELECTRICAL
- WATER
- STORMWATER
- TELECOMMUNICATIONS
- RISING MAIN
- STRUCTURAL ROOT ZONE (SRZ)
- TREE PROTECTION ZONE (TPZ)

PROPOSED

- CONTOUR (MINOR)
- CONTOUR (MINOR)
- FINISHED SURFACE LEVEL
- VEHICULAR CROSSING (REFER TO CCC STD DWG SD0506)
- SWALE, MINIMUM 0.5% FALL
- KERB ONLY
- RETAINING WALL
- BATTER
- STORMWATER JUNCTION PIT & LABEL
- STORMWATER SURFACE INLET PIT
- STORMWATER PIPE
- STORMWATER KERB INLET PIT
- GRATED DRAIN

NOTE:
EXISTING BOUNDARY TO BE REMOVED SWITCHED OFF ON THIS DRAWING FOR CLARITY.

Bar Scales		
1 : 200 @ A1 1 : 400 @ A3		
A	ISSUE FOR APPROVAL	10-08-23
Issue	Description	Date



Client
WALUYA PTY LTD

Scales 1:200	Drawn	JC
	Designed	JC
	Checked	GJ
	Approved	AT
Grid MGA56		
Height Datum AHD		

Project
**TRANSPORT DEPORT
7A-11 RACECOURSE RD
5-9 FAUNCE ST & YOUNG ST
WEST GOSFORD**


Title
**SITWORKS AND
STORMWATER DRAINAGE
PLAN
SHEET 4**

Civil Engineers and Project Managers
at&l
Level 7, 153 Walker Street
North Sydney
NSW 2060
P 02 9439 1777
E info@atl.net.au
www.atl.net.au
ABN 96 130 882 405


Status
**FOR APPROVAL
NOT TO BE USED FOR CONSTRUCTION**

Project - Drawing No.
22-1063-DAC014


Issue
A




		Bar Scales		THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L		Client WALUYA PTY LTD		Scales NTS Grid MGA56 Height Datum AHD		Drawn Designed CK Checked GJ Approved AT		Project TRANSPORT DEPORT 7A-11 RACECOURSE RD 5-9 FAUNCE ST & YOUNG ST WEST GOSFORD		Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 P 02 9439 1777 E info@atl.net.au www.atl.net.au ABN 96 130 882 405	
A		ISSUE FOR APPROVAL		10-08-23								Title SITWORKS DETAILS SHEET 1		at&l	
Issue		Description		Date								Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION		Project - Drawing No. 22-1063-DAC021	
												Issue A			




STANDARD LAYBACK
SCALE 1:20




HEAVY DUTY LAYBACK
SCALE 1:20




CONTROL JOINT (CJ) IN LAYBACK
SCALE 1:10




EXPANSION JOINT (EJ) KERB AND CHANNEL TO LAYBACK
SCALE 1:10




EXPANSION JOINT (EJ) 150mm to 100mm
VEHICLE ACCESS CROSSING TO FOOTPATH
SCALE 1:10




CONTROL JOINT (CJ) 150mm - TYPE 1
SCALE 1:10



EXPANSION JOINT (EJ) 250mm to 150mm
LAYBACK TO VEHICLE ACCESS CROSSING
SCALE 1:10



EXPANSION JOINT (EJ) 150mm
SCALE 1:10





CONTROL JOINT (CJ) - TYPE 2
SCALE 1:10


					SCALE ON ORIGINAL A3 SIZE DRAWING	DRAWN	T WILLIS		Central Coast Council		STANDARD DRAWING	
					AS SHOWN	CHECKED	M BAMBER		Kerb and Channel Series Industrial and Commercial Vehicle Access Crossing for Roads with Kerb and Channel	DRAWING NUMBER SD0506	REV -	
						DATE	28/4/20					
						UNIT MANAGER APPROVAL						
												
REV	AMENDMENT	DATE	DRAWN	APRVD	ALL DIMENSIONS IN mm UNLESS OTHERWISE SHOWN	ASSETS PLANNING AND DESIGN		ROADS TRANSPORT DRAINAGE AND WASTE		SHEET 2 OF 2		A3

© Central Coast Council 2020

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--



			Bar Scales 01002004006008001000mm 1 : 10 @ A1 1 : 20 @ A3	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	Client WALUYA PTY LTD	Scales AS SHOWN GridMGA56 Height DatumAHD	Drawn Designed Checked Approved	CK CK GJ AT	Project TRANSPORT DEPORT 7A-11 RACECOURSE RD 5-9 FAUNCE ST & YOUNG ST WEST GOSFORD	Civil Engineers and Project Managers at&l Level 7, 153 Walker Street North Sydney NSW 2060 P 02 9439 1777 E info@atl.net.au www.atl.net.au ABN 96 130 882 405	Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1
A	ISSUE FOR APPROVAL	10-08-23										
Issue	Description	Date										




					SCALE ON ORIGINAL A3 SIZE DRAWING	DRAWN	C SHEPPEARD		Central Coast Council		STANDARD DRAWING	
					0 250 500 750 1000 1250	CHECKED	M BAMBER		STORMWATER DRAINAGE SERIES	DRAWING NUMBER	REV	
					 1:25	DATE	28/4/20			SD0401	-	
					UNIT MANAGER APPROVAL				STANDARD GRATED GULLY PIT		SHEET 1 OF 3	A3
ALL DIMENSIONS IN mm UNLESS OTHERWISE SHOWN		ASSETS PLANNING AND DESIGN		ROADS TRANSPORT DRAINAGE AND WASTE								
REV	AMENDMENT		DATE	DRAWN	APRVD							

© Central Coast Council 2020


		Bar Scales	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	Client WALUYA PTY LTD	NTS	Drawn	CK	Project TRANSPORT DEPORT 7A-11 RACECOURSE RD 5-9 FAUNCE ST & YOUNG ST WEST GOSFORD	Civil Engineers and Project Managers Level 7, 153 Walker Street North Sydney NSW 2060 P 02 9439 1777 E info@atl.net.au www.atl.net.au ABN 96 130 882 405 		
							Designed			CK	
							Checked			GJ	
							Height Datum	Approved		AT	Title STORMWATER DRAINAGE DETAILS SHEET 1
A	ISSUE FOR APPROVAL				10-08-23					Status FOR APPROVAL	
Issue	Description	Date				NOT TO BE USED FOR CONSTRUCTION					
						Project - Drawing No. 22-1063-DAC025			Issue A		

F:\22-1063 West Gosford\6.0 Drgs\Civil\Final\22-1063-DAC025.dwg

N
O
T
F
O
R
C
O
N
S
T
R
U
C
T
I
O
N



OCEANSAVE PLAN




LAST MODIFIED: 25-02-19

OCEANSAVE DESIGN TABLE

TO BE INSTALLED ONLINE THE TOTAL INLET PIPE FLOW RATE MUST BE LESS THAN THE SPECIFIED UNITS LISTED MAXIMUM TOTAL FLOW RATE; THE UNIT MUST BE PLACED OFFLINE WHERE THE INLET FLOW RATE EXCEEDS THIS VALUE.

TREATABLE FLOWRATE [L/s]	28
MAXIMUM TOTAL FLOWRATE [L/s]	228
WEIR HEIGHT [mm]	300



SITE SPECIFIC
DATA REQUIREMENTS

TOTAL FLOWRATE THROUGH INLET [L/S]		[]	
PIPE DATA:	I.L.	MATERIAL	DIAMETER
INLET PIPE	[]	[]	[]
OUTLET PIPE	[]	[]	[]
UPPER TANK WEIGHT		TBA	
LOWER TANK WEIGHT		TBA	

NOTE: TANK SUPPLIED IN TWO PARTS; PARTS A & B TO BE JOINED ON SITE

GENERAL NOTES

- OCEANSAVE WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF THE PROJECT.
- PRECAST STRUCTURE SUPPLIED WITH CORE HOLES TO SUIT OUTER DIAMETER OF NOMINATED PIPE SIZE / MATERIAL.
- PRECAST STRUCTURE SHALL MEET W80 WHEEL LOAD RATING ASSUMING A MAXIMUM EARTH COVER OF 2.0m AND A GROUND WATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER TO CONFIRM ACTUAL GROUNDWATER ELEVATION.PRECAST STRUCTURE SHALL BE IN ACCORDANCE WITH AS3600.
- ALL WATER QUALITY TREATMENT DEVICES REQUIRE PERIODIC MAINTENANCE. REFER TO OPERATION AND MAINTENANCE MANUAL FOR GUIDELINES AND ACCESS REQUIREMENTS.
- SITE SPECIFIC PRODUCTION DRAWING WILL BE PROVIDED ON PLACEMENT OF ORDER.
- DRAWING NOT TO SCALE.

INSTALLATION NOTES

- ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE SPECIFIC DESIGN CONSIDERATION AND SHALL BE SPECIFIED BY THE SITE CIVIL ENGINEER.
- CONTRACTOR TO PROVIDE ALL EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STRUCTURE (LIFTING DETAIL PROVIDED SEPARATELY).
- CONTRACTOR TO INSTALL AND LEVEL THE STRUCTURE, APPLY SEALANT TO ALL JOINTS AND TO PROVIDE, INSTALL AND GROUT INLET AND OUTLET PIPES.
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT SCREEN & SEPARATION CYLINDER COMPONENTS DURING INSTALLATION



PHONE: 1300 354 722

www.oceanprotect.com.au

OCEAN PROTECT
OCEANSAVE 0606
SPECIFICATION DRAWING

A	ISSUE FOR APPROVAL	10-08-23
Issue	Description	Date

Bar Scales

THIS DRAWING CANNOT BE
COPIED OR REPRODUCED IN
ANY FORM OR USED FOR ANY
OTHER PURPOSE OTHER THAN
THAT ORIGINALLY INTENDED
WITHOUT THE WRITTEN
PERMISSION OF AT&L

Client

WALUYA PTY LTD

Scales

NTS

Grid

MGA56

Height
Datum

AHD

Drawn

CK

Designed

CK

Checked

GJ

Approved

AT

Project

TRANSPORT DEPORT
7A-11 RACECOURSE RD
5-9 FAUNCE ST & YOUNG ST
WEST GOSFORD

Title

STORMWATER DRAINAGE
DETAILS
SHEET 2

Civil Engineers and Project Managers

Level 7, 153 Walker Street
North Sydney
NSW 2060
P 02 9439 1777
E info@atl.net.au
www.atl.net.au
ABN 96 130 882 405

at&l

Status

FOR APPROVAL
NOT TO BE USED FOR CONSTRUCTION

Project - Drawing No.

22-1063-DAC026


Issue

A1


Issue

A

NOT FOR CONSTRUCTION



JELLYFISH PLAN



JELLYFISH SECTION

LAST MODIFIED: 25-02-19

JELLYFISH DESIGN TABLE

JELLYFISH TREATMENT FLOW IS A FUNCTION OF THE NUMBER OF CARTRIDGES AND THE DEVICE TOTAL HEAD DIFFERENTIAL. IF THE PIPE FLOW EXCEEDS THE TREATMENT FLOW THEN AN UPSTREAM BYPASS STRUCTURE IS REQUIRED.

REQUIRED DEVICE TOTAL HEAD DIFFERENTIAL [mm]	460	230
CARTRIDGE FLOW RATE FOR HIGH-FLOW / DRAINDOWN [L/s]	5 / 2.5	2.5 / 1.25
CARTRIDGE LENGTH [mm]	1375	1375
OUTLET INVERT TO STRUCTURE INVERT [mm]	1985	1985



SITE SPECIFIC DATA REQUIREMENTS

STRUCTURE ID			
WATER QUALITY FLOW RATE (L/S)			
# OF CARTRIDGES REQUIRED (HF - DD)	-		
CARTRIDGE SIZE	1375		
PIPE DATA:	I.L.	MATERIAL	DIAMETER
INLET PIPE			
OUTLET PIPE			
UPPER TANK WEIGHT	4,050kg		
LOWER TANK WEIGHT	6,350kg		

NOTE: TANK SUPPLIED IN TWO PARTS; PARTS A & B TO BE JOINED ON SITE

GENERAL NOTES

- JELLYFISH WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF THE PROJECT.
- PRECAST STRUCTURE SUPPLIED WITH CORE HOLES TO SUIT OUTER DIAMETER OF NOMINATED PIPE SIZE / MATERIAL.
- PRECAST STRUCTURE SHALL MEET W80 WHEEL LOAD RATING ASSUMING A MAXIMUM EARTH COVER OF 2.0m AND A GROUND WATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER TO CONFIRM ACTUAL GROUNDWATER ELEVATION.PRECAST STRUCTURE SHALL BE IN ACCORDANCE WITH AS3600.
- IF THE PEAK FLOW RATE, AS DETERMINED BY THE SITE CIVIL ENGINEER, EXCEEDS THE TREATMENT FLOW RATE OF THE SYSTEM, AN UPSTREAM BYPASS STRUCTURE IS REQUIRE.
- ALL WATER QUALITY TREATMENT DEVICES REQUIRE PERIODIC MAINTENANCE. REFER TO OPERATION AND MAINTENANCE MANUAL FOR GUIDELINES AND ACCESS REQUIREMENTS.
- SITE SPECIFIC PRODUCTION DRAWING WILL BE PROVIDED ON PLACEMENT OF ORDER.
- DRAWING NOT TO SCALE.

INSTALLATION NOTES

- ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE SPECIFIC DESIGN CONSIDERATION AND SHALL BE SPECIFIED BY THE SITE CIVIL ENGINEER.
- CONTRACTOR TO PROVIDE ALL EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STRUCTURE (LIFTING DETAIL PROVIDED SEPARATELY).
- CONTRACTOR TO INSTALL AND LEVEL THE STRUCTURE, APPLY SEALANT TO ALL JOINTS AND TO PROVIDE, INSTALL AND GROUT INLET AND OUTLET PIPES.
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT CARTRIDGES FROM CONSTRUCTION-RELATED EROSION RUNOFF.
- CARTRIDGE INSTALLATION, BY OCEANPROTECT, SHALL OCCUR ONLY AFTER SITE HAS BEEN STABILIZED AND THE JELLYFISH UNIT IS CLEAN AND FREE OF DEBRIS. CONTACT OCEAN PROTECT TO COORDINATE CARTRIDGE INSTALLATION WITH SITE COMPLETION.



PHONE: 1300 354 722

www.oceanprotect.com.au

OCEAN PROTECT
JELLYFISH 2250
STANDARD PRODUCT DRAWING

A	ISSUE FOR APPROVAL	10-08-23
Issue	Description	Date

Bar Scales

THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L

Client

WALUYA PTY LTD

Scales

NTS	Drawn	CK
	Designed	CK
Grid MGA56	Checked	GJ
Height Datum AHD	Approved	AT

Project

TRANSPORT DEPORT
7A-11 RACECOURSE RD
5-9 FAUNCE ST & YOUNG ST
WEST GOSFORD

Title

STORMWATER DRAINAGE
DETAILS
SHEET 3

Civil Engineers and Project Managers

Level 7, 153 Walker Street
North Sydney
NSW 2060
P 02 9439 1777
E info@atl.net.au
www.atl.net.au
ABN 96 130 882 405



Status

FOR APPROVAL
NOT TO BE USED FOR CONSTRUCTION

Project - Drawing No.
22-1063-DAC027

Issue

A






Diagram illustrating a typical corner detail of a reinforced concrete slab. The detail shows the intersection of two slabs at a corner, with reinforcement bars (N/L BARS 500x500) extending into the adjacent slab. The scale is 1:20.




DETAIL "C"

SCALE 1:10




DETAIL "D"

SCALE 1:10




DETAIL "E"


SCALE 1:10



DETAIL "G"
SCALE 1:10



SUBSOIL IN PAVED AREAS



GRATED DRAIN (TD)
SCALE 1:10


SCALE: 1:20

PIPE DIA.	WIDTH	DEPTH	WALL	FABRIC/COV
"Ø"	"W"	"D"	"T"	"SL"
375	AS3500.3	800	150	SL72
	AS3500.3	1200	150	SL72
	AS3500.3	1600	150	SL72
	AS3500.3	2000	150	SL72
	AS3500.3	2400	150	SL72
450	AS3500.3	800	150	SL72
	AS3500.3	1200	150	SL72
	AS3500.3	1600	150	SL72
	AS3500.3	2000	150	SL72
	AS3500.3	2400	150	SL72
525	AS3500.3	800	150	SL72
	AS3500.3	1200	150	SL72
	AS3500.3	1600	150	SL72
	AS3500.3	2000	150	SL72
	AS3500.3	2400	150	SL72


1. FOR PIT SIZE REFER TO TABLE (900 MIN LONG).
2. REINFORCING MESH IS TO BE BENT TO LAP 300 AROUND ALL CORNERS. VERTICAL BARS ARE NOT TO BE CUT. ALTERNATELY PROVIDE N12 "L" BARS (500x500) AT 400 VERTICAL CTS.
3. COMPRESSIVE STRENGTH (F_c) FOR CAST IN SITU CONCRETE SHALL BE A MINIMUM 32 MPa AT 28 DAYS.
4. TOP OF BENCHING SHALL BE $\frac{1}{2}$ OF OUTLET PIPE DIAMETER.
5. 100mm SUBSOIL DRAINAGE PIPE 3000 LONG WRAPPED IN FABRIC SOCK TO BE PROVIDE ADJACENT TO INLET PIPES.
6. ALL PITS SHALL BE PROVIDED WITH A LOCKING CLIP.
7. PIT GRATE TO BE 'WELDLOK' GULLY GRATE G6 78-50 OR APPROVED EQUIVALENT.
8. DURING INSTALLATION OF GRATE AND FRAME CONTRACTOR IS TO ENSURE CLEARANCE BETWEEN LINTEL AND OPENED GRATE (REFER TO INSTALLATION TOLERANCE).
9. PROVIDE STEP IRONS AS INDICATED FOR PITS DEEPER THAN 1200.
10. N12 AT 200 CENTRAL MAY BE USED IN LIEU OF MESH. LAP 500 AT CORNERS

11. CONCRETE STRENGTH - UNLESS NOTED OTHERWISE				
ELEMENT	f _c MPa (28 DAYS)	SLUMP	MAX AGG SIZE	CEMENT TYPE
PITS	32	80mm	20mm	GP


- | ELEMENT | INTERIOR | EXTERIOR |
|-------------|----------|----------|
| PITS | | 45mm |
| SLAB TOP | 45mm | 45mm |
| SLAB BOTTOM | 45mm | 45mm |
| BEAM TOP | | |
| BEAM BOTTOM | | |
| BEAM SIDE | | |
| COLUMNS | | |



--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--



--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--





--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

REFER TO CIVIL REPORT BY AT&L FOR DETAILS.

SITE AREA	= 20.013m ²
CATCHMENT AREA	= 11,564m ² (54.5%)
SITE BYPASS AREA	= 1,190m ² (5.6%)
SURFACE RL	= 7.60-8.10
SOFFIT RL	= TBC AT DETAILED DESIGN STAGE (TO BE HIGHER THAN 100YR TWL THROUGHOUT THE TANK AND HIGHER THAN EMERGENCY TWL ABOVE EMERGENCY WEIR)
AVERAGE IL	= 5.17
2YR TWL	= 6.35
2YR PRO. VOL.	= 260.3m ³ (260.3m ³ DC)
2YR ORIFICE CL	= 5.175
2YR ORIFICE CL	= 150mm
100YR TWL	= 7.10
100YR PRO. VOL.	= 432.3m ³ (425.8m ³ DC + 6.5m ³ DCP)
100YR ORIFICE CL	= 5.165
100YR ORIFICE Ø	= 330mm


ON-GRADE
CAR PARK

[illegible]

NOTE
REFER TO CIVIL REPORT BY AT&L FOR DETAILS.

OSD DESIGN SUMMARY

SITE AREA	= 20,013m ²
CATCHMENT AREA	= 11,564m ² (54.5%)
SITE BYPASS AREA	= 1,190m ² (5.6%)
SURFACE RL	= 7.60-8.10
SOFFIT RL	= TBC AT DETAILED DESIGN STAGE (TO BE HIGHER THAN 100YR TWL THROUGHOUT THE TANK AND HIGHER THAN EMERGENCY TWL ABOVE EMERGENCY WEIR)
AVERAGE IL	= 5.17
2YR TWL	= 6.35
2YR PRO. VOL.	= 260.3m ³ (260.3m ³ DC)
2YR ORIFICE CL	= 5.175
2YR ORIFICE CL	= 150mm
100YR TWL	= 7.10
100YR PRO. VOL.	= 432.3m ³ (425.8m ³ DC + 6.5m ³ DCP)
100YR ORIFICE CL	= 5.165
100YR ORIFICE Ø	= 330mm



A	ISSUE FOR APPROVAL	10-08-23
Issue	Description	Date

Bar Scales
0 1 2 3 4 5m
1 : 50 @ A1 1 : 100 @ A3

THIS DRAWING CANNOT BE
COPIED OR REPRODUCED IN
ANY FORM OR USED FOR ANY
OTHER PURPOSE OTHER THAN
THAT ORIGINALLY INTENDED
WITHOUT THE WRITTEN
PERMISSION OF AT&L

Client
WALUYA PTY LTD

Scales	1:50
Grid	MGA56
Height Datum	AHD
Drawn	CK
Designed	CK
Checked	GJ
Approved	AT

Project	TRANSPORT DEPORT 7A-11 RACECOURSE RD 5-9 FAUNCE ST & YOUNG ST WEST GOSFORD
Title	STORMWATER DRAINAGE OSD 1 BASE PLAN

Civil Engineers and Project Managers	Level 7, 153 Walker Street North Sydney NSW 2060 P 02 9439 1777 E info@atl.net.au www.atl.net.au ABN 96 130 882 405
Status	FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION
Project - Drawing No.	22-1063-DAC054
Issue	A



F:\22-1063 West Gosford\6.0 Drqs\Civil\Final\22-1063-DAC055.dwg

NOTE
REFER TO CIVIL REPORT BY AT&L FOR DETAILS.

OSD DESIGN SUMMARY

SITE AREA = 20,013m²
CATCHMENT AREA = 8,449m² (39.8%)
SITE BYPASS AREA = 1,190m² (5.6%)

SURFACE RL = 8.10-8.30
SOFFIT RL = TBC AT DETAILED DESIGN STAGE
(TO BE HIGHER THAN 100YR TWL
THROUGHOUT THE TANK AND
HIGHER THAN EMERGENCY TWL
ABOVE EMERGENCY WEIR)

AVERAGE IL = 6.17

2YR TWL = 7.35
2YR PRO. VOL. = 188.8m³
(188.8m³ DC)
2YR ORIFICE CL = 6.20
2YR ORIFICE CL = 200mm

100YR TWL = 7.60
100YR PRO. VOL. = 233.7m³
(228.8m³ DC + 4.9m³ DCP)
100YR ORIFICE CL = 6.265
100YR ORIFICE Ø = 530mm

BUS PARKING


PROPOSED OFFICE
FFL 8.10

BUS PARKING


OSD 2
(233.7kL)

OCEAN PROTECT
OCEANSAVE OS-0606

OCEAN PROTECT
JELLYFISH JF2250-8-2



Bar Scales



THIS DRAWING CANNOT BE
COPIED OR REPRODUCED IN
ANY FORM OR USED FOR ANY
OTHER PURPOSE OTHER THAN
THAT ORIGINALLY INTENDED
WITHOUT THE WRITTEN
PERMISSION OF AT&L

Client

WALUYA PTY LTD

Scales

1:50

Grid

MGA56

Height
Datum

AHD

Drawn

CK

Designed

CK

Checked

GJ

Approved

AT

Project

TRANSPORT DEPORT
7A-11 RACECOURSE RD
5-9 FAUNCE ST & YOUNG ST
WEST GOSFORD

Title

STORMWATER DRAINAGE
OSD 2
ROOF PLAN

Civil Engineers and Project Managers

Level 7, 153 Walker Street
North Sydney
NSW 2060
P 02 9439 1777
E info@atl.net.au
www.atl.net.au
ABN 96 130 882 405

Status

FOR APPROVAL
NOT TO BE USED FOR CONSTRUCTION

Project - Drawing No.
22-1063-DAC056

Issue


A


REFER TO CIVIL REPORT BY AT&L FOR DETAILS.

SITE AREA	= 20.013m ²
CATCHMENT AREA	= 8,449m ² (39.8%)
SITE BYPASS AREA	= 1,190m ² (5.6%)
SURFACE RL	= 8.10-8.30
SOFFIT RL	= TBC AT DETAILED DESIGN STAGE (TO BE HIGHER THAN 100YR TWL THROUGHOUT THE TANK AND HIGHER THAN EMERGENCY TWL ABOVE EMERGENCY WEIR)
AVERAGE IIL	= 6.17
2YR TWL	= 7.35
2YR PRO. VOL.	= 188.8m ³ (188.8m ³ DC)
2YR ORIFICE CL	= 6.20
2YR ORIFICE CL	= 200mm
100YR TWL	= 7.60
100YR PRO. VOL.	= 233.7m ³ (228.8m ³ DC + 4.9m ³ DCP)
100YR ORIFICE CL	= 6.265
100YR ORIFICE Ø	= 530mm


BUS PARKING

PROPOSED OFFICE
FFL 8.10



[illegible]




TRASH SCREEN DETAIL
N.T.S




STEP IRON DETAIL
NTS



			Bar Scales 0500100015002000mm 1 : 20 @ A1 1 : 40 @ A3	THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L	Client WALUYA PTY LTD	Scales AS SHOWN	Drawn CK	Project TRANSPORT DEPORT 7A-11 RACECOURSE RD 5-9 FAUNCE ST & YOUNG ST WEST GOSFORD	Civil Engineers and Project Managers at&l Level 7, 153 Walker Street North Sydney NSW 2060 P 02 9439 1777 E info@atl.net.au www.atl.net.au ABN 96 130 882 405
	Grid MGA56	Designed CK							
	Height Datum AHD	Checked GJ							
		Approved AT							
						Title STORMWATER DRAINAGE OSD 2 SECTIONS AND DETAILS			
A	ISSUE FOR APPROVAL	10-08-23				Status FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1		
Issue	Description	Date				Project - Drawing No. 22-1063-DAC058	Issue A		



A	ISSUE FOR APPROVAL	10-08-23
Issue	Description	Date



THIS DRAWING CANNOT BE COPIED OR REPRODUCED IN ANY FORM OR USED FOR ANY OTHER PURPOSE OTHER THAN THAT ORIGINALLY INTENDED WITHOUT THE WRITTEN PERMISSION OF AT&L

Client

WALUYA PTY LTD


Scales	1:400	Drawn	CK
		Designed	CK
Grid	MGA56	Checked	GJ
Height Datum	AHD	Approved	AT

Project	TRANSPORT DEPOT 7A-11 RACECOURSE RD 5-9 FAUNCE ST & YOUNG ST WEST GOSFORD
Title	EROSION AND SEDIMENT CONTROL PLAN

Civil Engineers and Project Managers		Level 7, 153 Walker Street North Sydney NSW 2060 P 02 9439 1777 E info@atl.net.au www.atl.net.au ABN 96 130 882 405
		
Status	FOR APPROVAL NOT TO BE USED FOR CONSTRUCTION	A1
Project - Drawing No. 22-1063-DAC071		Issue A




F:\22-1063 West Gosford\6.0 Drqs\Civil\Final\22-1063-DAC075.dwg



FOR CONTINUATION REFER TO SHEET 2

MGA



KEY PLAN

LEGEND


- Bench Mark
- Comms Underground
- Comms Pit/Manhole
- Comms Pillar
- Drainage Grated Pit
- Drainage Kerb Inlet Pit
- Electrical Power Pole
- Electrical Underground Cable
- Fence
- Gate
- Road Bollard
- Sewer Manhole
- Sewer Pipe
- Sign Post
- Tree (Height, Trunk Diameter, Spread)
- Water Meter
- Water Tap
- Water Stop Valve
- Water Hydrant
- Bottom of Bank
- Top of Bank

NOTES

- HISTORICAL SURVEY DATA USED FROM SURVEY "19881A01L" DATED "23.05.2005"
- BOUNDARIES ARE NOT FINAL AND FURTHER INVESTIGATION REQUIRED FOR BOUNDARIES IF THEY ARE REQUIRED FOR ANY DESIGN PURPOSES.
- THESE NOTES AND LEGEND (IF SHOWN) FORM PART OF THE PLAN AND SURVEY AND MUST REMAIN WITH THE PLAN IN ANY REPRODUCTION IN WHOLE OR PART.
- THE CAD FILE USES METRES AS ITS BASE UNIT AND IS IN A "GROUND" COORDINATE SYSTEM. IF THE SURVEY IS STATED AS MGA, ANY POINT IN THE FILE WILL BE AN APPROXIMATE MGA COORDINATE.
- SOME SYMBOLS REPRESENTING PHYSICAL STRUCTURES SUCH AS POWER POLES AND PITS ARE DIAGRAMMATIC ONLY AND DO NOT NECESSARILY REPRESENT THE ACTUAL SIZE AND EXTENT OF THESE FEATURES.
- THE SURVEY INFORMATION SHOWN HERE WAS PREPARED FOR A SPECIFIC PURPOSE FOR THE CLIENT SHOWN. THIS INFORMATION IS NOT INTENDED TO BE USED FOR ANY OTHER PURPOSE OR BY ANYONE NOT AUTHORISED BY THIS CLIENT.
- BOUNDARY DIMENSIONS AND AREAS HAVE BEEN DETERMINED BY CURRENT CADASTRAL SURVEY AND THE BOUNDARY AND EASEMENT LINES IN THE ELECTRONIC FILE HAVE BEEN INCLUDED USING THOSE SURVEYED DIMENSIONS. THE TITLE DIMENSIONS SHOWN ON THE HARD COPY PLAN TAKE PRECEDENCE OVER THE LINES IN THE ELECTRONIC FILE.
- THE TITLE/S TO THE SUBJECT LAND HAS BEEN REVIEWED AND THE POSITION OF ALL EASEMENTS AFFECTING THE LAND ARE SHOWN. THE TERMS OF ANY EASEMENT, RESTRICTION ON THE USE OF LAND OR COVENANT AFFECTING THE LAND HAVE NOT BEEN INVESTIGATED. LEASES AND OTHER NOTATIONS MAY ALSO EXIST WHICH AFFECT THE LAND.
- UNDERGROUND SERVICES OTHER THAN THOSE SHOWN HAVE NOT BEEN INVESTIGATED. PRIOR TO DEMOLITION, EXCAVATION OR CONSTRUCTION WORK ON THE SITE, THE RELEVANT SERVICE AUTHORITY SHOULD BE CONTACTED TO ESTABLISH DETAILED LOCATION AND DEPTH.
- THIS SURVEY IS LIMITED TO IMPROVEMENTS AND OTHER DETAIL WHICH WERE VISIBLE AND ACCESSIBLE AT THE TIME OF SURVEY. THE LOCATION OF DETAIL SUCH AS PRIVATE UNDERGROUND SERVICE LINES AND BUILDING FOUNDATIONS WITHIN THE SITE IS UNKNOWN.
- THE COORDINATES WITHIN THIS DRAWING RELATE TO THE DATUM SHOWN IN THE TITLE BLOCK. REFER TO A REGISTERED LAND SURVEYOR FOR FURTHER CLARIFICATION. CAUTION SHOULD BE TAKEN WHEN IMPORTING INFORMATION OBTAINED FROM OTHER SUB-CONSULTANTS OR SOURCES TO ENSURE THAT THE DATA IS ON A MATCHING COORDINATE SYSTEM.
- CONTOURS SHOWN HEREON DEPICT THE GENERAL TOPOGRAPHY ONLY. EXCEPT AT SPOT LEVELS SHOWN, THEY DO NOT NECESSARILY REPRESENT THE EXACT LEVEL AT ANY PARTICULAR POINT.
- ANY GUTTER, RIDGE, ROOF AND WINDOW DETAILS AND LEVELS SHOWN HAVE BEEN OBTAINED VIA INDIRECT SURVEY METHODS WHERE VISIBLE FROM GROUND LEVEL AND ARE SHOWN ON THIS PLAN IN THEIR APPROXIMATE LOCATION FOR THE PURPOSE OF GENERAL SITE ANALYSIS ONLY.
- ANY TREE CANOPIES, TRUNK DIAMETERS AND HEIGHTS SHOWN ARE APPROXIMATE ONLY AND SHOULD BE VERIFIED BY FURTHER SURVEY WORKS IF CRITICAL TO DESIGN OR SITE ANALYSIS.
- SMALL TREES, SHRUBS, GARDEN FEATURES, PATHWAYS AND OTHER MINOR DETAIL MAY NOT BE SHOWN ON THIS PLAN, FOR THE PURPOSES OF THIS SURVEY.

ORIGIN OF LEVELS: PM 19232
RL. 14.428 (AHD)

FOR CONTINUATION REFER TO SHEET 3



VER	BY	AMENDMENTS	DATE
A	M.W.	NEW DETAIL ADDED TO EXISTING SURVEY	08.12.22
B	M.W.	ADDITIONAL DRAINAGE ADDED	21.07.23
C			
D			
E			
F			
G			

- THE POSITION OF SERVICES SHOWN ON THIS DRAWING ARE INDICATIVE ONLY AND HAVE BEEN PLOTTED FROM PLANS AND DRAWINGS SUPPLIED BY RELEVANT AUTHORITIES.
- SERVICE AUTHORITY PITS, MANHOLES, POLES, MARKER POSTS, ETC., WHERE SIGHTED AT TIME OF SURVEY, HAVE BEEN LOCATED. THE SURVEY DOES NOT INCLUDE INVESTIGATION OR LOCATION OF UNDERGROUND INFRASTRUCTURE.
- SERVICES INFORMATION SHOWN ON THIS DRAWING HAS BEEN OBTAINED THROUGH A DIA. BEFORE YOU DIG SEARCH AND IS VALID FOR THE PERIOD OF TIME FROM THE DATE OF ISSUE NOMINATED BY THE AUTHORITY.
- PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION ON OR ADJACENT TO THE SITE IT IS THE RESPONSIBILITY OF THE DEVELOPER AND CONTRACTORS TO APPLY FOR AND OBTAIN UP TO DATE PLANS THROUGH A NEW DIA BEFORE YOU DIG SEARCH AND TO CONTACT ALL THE RELEVANT AUTHORITIES TO ESTABLISH AND CONFIRM THE DETAILED LOCATION AND DEPTH OF ALL UNDERGROUND SERVICES.



CLIENT:
BUSWAYS GROUP PTY LTD



Beveridge Williams
Land Development Consultants
Registered Surveyors

Central Coast (02) 4351 2233 www.beveridgewilliams.com.au

DETAILS:
DETAIL SURVEY PLAN FOR
DEVELOPMENT APPLICATION PURPOSES
RACECOURSE ROAD
WEST GOSFORD

ORIGINAL SHEET SIZE
SCALE 1:400
A1
CAD REFERENCE: 2202624-DET-001-B
0 8 16 24
SCALE ON ORIGINAL DRAWING AT 1:400

SURVEYOR: J.C. & P.K.
DRAWN: C.A. & M.W.
CHECKED: R.P.
SURVEY DATE: 23.09.05 & 06.12.22
VERTICAL DATUM: AHD
HORIZONTAL DATUM: MGA

PROJECT No.
2202624
DRAWING REF.
DET-001
VERSION B
SHEET 4 OF 4