Archer Consultants Pty Ltd

PH: 02 7227 9360

ABN: 79 661 164 683

324 Hume Highway, Bankstown NSW 2200

OPERATIONAL WASTE MANAGEMENT PLAN

Proposed Commercial Development

Business Office Premises

Client - Omar Rahman

Revision - 1A

Prepared for - City of Canterbury Bankstown - December 2022

CONTENTS

INTRODUCTION	. 4
BACKGROUND & EXISTING CONDITIONS	. 4
PROPOSED DEVELOPMENT	. 6
ANTICIPATED WASTE GENERATION, STORAGE & COLLECTION	. 6
WASTE GENERATION	. 6
TABLE 1: TYPICAL GENERAL AND RECYCLING WASTE GENERATION RATES FOR COMMERCIAL	. 6
WASTE WITHIN OVERALL DEVELOPMENT	. 7
WASTE STORAGE AND HANDLING OF WASTE STREAMS	. 7
TABLE 2: TYPICAL MEASUREMENTS FOR CANTERBURY BANKSTOWN (MOBILE GARBAGE BINS) MGB'S	. 7
WASTE COLLECTION	13
AMENITY	14
NOISE	14
VENTILATION	14
SECURITY & COMMUNICATION STRATEGY	14
WASTE STORAGE ENCLOSURES & CLEANING FACILITIES	14
PREVENTION OF VERMIN	14
MISCELLANEOUS	15
COMMUNAL COMPOSTING FACILITY	15
INTERNAL WASTE STORAGE	15
Organic (Food/Green) Waste	15
BULKY WASTE	15
E-WASTE	15
APPENDIX A – SITE PLANS	16

FIGURES

FIGURE 1: LOCATION OF THE SUBJECT SITE	5
FIGURE 2: AERIAL VIEW OF THE SUBJECT SITE	5
FIGURE 3: GUIDELINES FOR WASTE PLACEMENT WITHIN THE MGB'S	8
FIGURE 4: SCALED DIAGRAM OF THE BASEMENT WASTE STORAGE ROOM	9
FIGURE 5: SCALED DIAGRAM OF THE GROUND LEVEL WASTE COLLECTION POINT	. 10
FIGURE 6: TYPICAL 60L - 240L BIN LIFT	. 11
FIGURE 7: TYPICAL LARGE BIN TUG	. 12
FIGURE 8: DIAGRAM OF A TYPICAL HRV WASTE COLLECTION VEHICLE (REQUIRED BY COUNCIL)	. 13

INTRODUCTION

Archer Consultants Pty Ltd was engaged by Omar Rahman to prepare a Waste Management Plan (WMP) for approval of a proposed commercial development at 324 Hume Highway, Bankstown NSW.

The proposed development consists of;

DEVELOPMENT DETAILS			
Ground Floor: Office Space (119.03m ²), (135.99m ²).			
First Floor: Office Space (241.58m ²), (423.92m ²).			
Second Floor: Office Space (498.29m ²), (417.75m ²).			

In the course of preparing this WMP, the subject site and its environs have been inspected, plans of the development examined, and all relevant council requirements and documentation collected and analysed.

This WMP has been prepared based on the following information:

- Architectural Plans provided by FLDC Architects.
- Canterbury Bankstown Waste Management Guide for New Developments.

BACKGROUND & EXISTING CONDITIONS

The subject site is located at 324 Hume Highway, Bankstown NSW, on the north side of Hume Highway through to Davis Lane with the nearby land uses mostly commercial with residential to the south.

Figure 1 provides an overview of the area and its surrounding land uses whilst **Figure 2** provides an aerial view of the immediate area surround the subject site.




Figure 1: Location of the Subject Site



Figure 2: Aerial View of the Subject Site

PROPOSED DEVELOPMENT

The proposed development consists of a commercial development. Access to the proposed front entrance of the building will be provided via a paved walkway off Hume Highway and walkway and driveway via Davis Lane. The Mobile Garbage bins (MGB's) will be stored on basement level 1. (Refer Appendix A).

ANTICIPATED WASTE GENERATION, STORAGE & COLLECTION

Waste collection should be provided by private waste contracted services.

Waste Generation

As per the Canterbury Bankstown Waste Management Guide for New Developments,

The waste entitlement for the development consists of: Offices is 16L/100m² of floor area per day general waste and, 12L/100m² of floor area per day recycling waste (Inclusive of paper & cardboard waste).

The following table illustrates the typical garbage and recycling generation rates.

Table 1: Typical General and Recycling Waste Generation Rates for Commercial.

Type of Premises	General Land Waste	Commingled Recycling Waste
Offices	16L/100m ² floor area/day	12L/100m ² floor area/day

NOTE: Generation rates based on weekly rates within the Canterbury Bankstown Waste Management Guide for New Developments. Actual usage can vary and may be generated at a reduced rate. Management will monitor all waste requirements and handling. Accessing any needs for waste management plan revisions.

Waste within Overall Development

Using the garbage and recycling generation rates above, the following can be calculated;

Office Space: (1,836.56m²) (7 Day Week)

- 16L/100m² of floor area per day general waste = 2,056.94L per week (uncompacted)
- 12L/100m² of floor area per day recycling waste = 1,542.71L per week (uncompacted)

Waste Storage and Handling of Waste Streams

Based on the total waste generated by the development, the following Mobile Garbage Bins (MGBs) should be provided:

- 2 x 1100L General Waste MGB's collected and emptied once a week.
- 2 x 1100L Recycling Waste MGB's collected and emptied once a week.

NOTE: The building manager will collect the waste bins from within the commercial offices and ferry the bins to the basement where the building manager will use the 60L–240L Bin Lift to empty the bins into the 1100L MGB's

The following table illustrates the typical dimensions of the MGB's mentioned above.

Size (L)	Height (mm)	Width (mm)	Depth (mm)
240L	1,100	580	735
660L	1,250	1,370	850
1,100L	1,470	1,370	1,245

Table 2: Typical Measurements for Canterbury Bankstown (Mobile Garbage Bins) MGB's.





Figure 3: Guidelines for Waste Placement within the MGB's



The following figure illustrates the scaled diagram of the MGB's within the basement level waste storage room and placement on the ground level for collection.

Figure 4: Scaled Diagram of the Basement Waste Storage Room




Figure 5: Scaled Diagram of the Ground Level Waste Collection Point




Figure 6: Typical 60L - 240L Bin Lift





Figure 7: Typical Large Bin Tug

Waste collection should be provided by private waste contracted services.

To help ensure bin collection runs smoothly and enables drivers to pick up, empty and replace the bins safely, it's important to:

- Ensure the MGB's are not overfilled with the lids are shut to avoid spills and to protect it from bugs and animals.
- The building manager will use the bin tug to ferry the MGB's to the ground level collection point for collection on the day of collection.
- Once all the MGB's have been emptied the building manager will immediately return the MGB's to the basement waste room.

The waste collection vehicle will pull up within the ground level on-site waste collection area off Davis Lane and ferry the waste bins to/from the waste collection area and waste vehicle emptying the MGB's. Once all the MGB's have been emptied and returned to the waste collection area, the vehicle will leave in a forward motion.



Vehicle Type	Length	Design Width	Design Turning Radius	Clearance Travel Height	Swept Turning Circle
HRV (Rear Lift)	12.5m	2.5m	3.6m	4.5m	27.8m

Figure 8: Diagram of a Typical HRV Waste Collection Vehicle (Required by Council)

Noise

The only noise generated from the waste management at the property will be that of the MGB's being wheeled to / from the waste vehicle emptying the MGB's. Any other noise related to the waste management will be kept to a minimum.

Ventilation

The waste bin area will need ventilation.

Security & Communication Strategy

All MGB's will be secured within the waste storage area.

Management and Staff will receive detailed documentation detailing all necessary requirements for safe waste management and handling including all relevant contact information.

The building manager will collect the waste bins from within the commercial offices and ferry the bins to the basement where the building manager will use the 60L – 240L Bin Lift to empty the bins into the 1100L MGB's

Waste Storage Enclosures & Cleaning Facilities

Building management will be responsible for keeping the MGB's clean.

NOTE: The waste area should be enclosed and consist of; (1) Impervious solid impervious material walls and 75mm thick smooth even ground surface, ensuring the ground is graded to a Sydney approved drainage fitting. (2) Ceilings must be finished with a smooth faced, non-absorbent material capable of being cleaned. (3) Walls, ceilings and floors must be finished in a light colour. (4) Hot and cold water tap mixed through a centralised mixing valve with hose cock for use of cleaning the MGB's and waste area. (5) Doors must be at least 2m wide and be close fitting and self-closing and able to be opened from within the room. (6) Constructed to prevent the entry of vermin and birds with adequate light and ventilation. (7) Lighting must be controlled using switches located both inside and outside the room (8) Waste educational signage with building management contact details.

Prevention of Vermin

The occupants will be advised to not overfill the bins so that the lids are closed at all times. It is suggested to place rat traps in the corners of the waste storage areas.

Communal Composting Facility

Organic waste is a problem in landfill as it produces methane, a harmful greenhouse gas that is 25 times more potent than carbon dioxide. Turning it into compost reduces the impact on the environment and allows waste to become a usable product. Existing landfill sites are also nearing capacity and the creation of new sites can cause significant detrimental effects through land clearing, loss of habitat for local wildlife, and potential groundwater and soil contamination from the leaching of heavy metals and chemicals.

Management can decide to commit to improving waste management methods by choosing to add 2 x 240L Organic Waste bins collected at least once a week by a private organic waste contractor.

Internal Waste Storage

It is suggested that sufficient space, should be provided for interim storage of smaller bins in strategic areas for garbage and recyclables. Space should allow for separate storage of recyclables from the garbage streams. Ideally segregation of organics waste placed in a kitchen caddy for placement within the organic waste bin.

Organic (Food/Green) Waste

Food waste can be placed in the general waste bins. <u>*Please refer to Communal Composting Facility</u></u> <u><i>above*.</u> Green waste won't be required.</u>

Bulky Waste

If bulky hard waste collection is required management, should contact a private waste contracted service to organise collection.

E-Waste

Recyclable electronic goods include batteries, equipment containing printed circuit boards, computers, televisions, fluorescent tubes and smoke detectors. E-Waste is expected to be minimal therefore, all waste will be placed in a small impermeable surface container and management will organise for the E-Waste to be taken to a registered E-Waste Re-Processor as required.

APPENDIX A – SITE PLANS

