# PROPOSED TWO STOREY DWELLING WITH BASEMENT & POOL AT 50 CHASELING STREET, GREENACRE

- These drawings shall be read in conjunction with all architectural and other consultants drawings and specifications and with such other written instructions and sketches as may be issued during the course of the Contract. Any discrepancies shall be referred to the Superintendent before proceeding with any related works. Construction from these drawings, and their associated consultant's drawings is not to commence until approved by the Local Authorities.

- During construction the structure shall be maintained in a stable condition and no part shall be overstressed.

  Temporary bracing shall be provided by the builder/subcontractor to keep the works and excavations stable at all times.

- G7 Any substitution of materials shall be approved by the Engineer and included in any tender.
- G8 All services, or conduits for servicing shall be installed prior to commencement of pavement construction.
- The structural components detailed on these drawings have been designed in accordance with the relevant Standards Australia codes and Local Covernment Ordinances for the following loadings. Refer to the Architectural drawings for proposed floor usage. Refer to drawings for live loads and superimposed dead loads.

#### DRAINAGE NOTES

- All pits within the property are to be fitted with "weldlok" or approved equivalent grates: Light duty for landscaped areas Heavy duty where subjected to vehicular traffic


- D7 All pits in roadways are to be fitted with heavy duty grates with locking bolts and continuous hinge
- D8 Provide step irons to stormwater pits greater than 1200 in depth
- D10 Where a high early discharge (hed) pit is provided all pipes are to be connected to the hed pit, uno.
- D11 Down pipes shall be a minimum of dn100 sw grade upvc or 100 x100 colorbond/zincalume steel, uno.
- D13 Eaves gutters shall be a minimum of 125 wide x 100 deep (or of equivalent area) colorbond or zincalume
- D14 Subsoil drainage shall be provided to all retaining walls & embankments, with the lines feeding into the


#### **EROSION AND SEDIMENT CONTROL NOTES**

- The contractor shall implement all soil erosion and sediment control measures as necessary and to the satisfaction of the relevant local authority prior to the commencement of and during construction. No disturbance to the site shall be permitted other than in the immediate area of the works and no material shall be removed from the site without the relevant local authority approval. All erosion and sediment control devices to be installed and maintained in accordance with standards outlined in risw department of housing's "managing urban stormwater soils and constructions".
- Place straw bales length wise in a row as parallel as possible to the site contours, uno. Bale ends to be tightly butted. Bales are to be placed so that straws are parallel to the row. Bales are to be placed 1.5m to 2m downslope from the toe of the disturbed batter, uno.

- All drainage pipe inlets to be capped until: - pits constructed and protected with silt barrier
- E6 Provide and maintain silt traps around all surface inlet pits until catchment is revegetated or paved.

- The contractor shall implement dust control by regularly wetting down (but not saturating) disturbed area.
- Topsoil shall be stripped and stockpiled outside hazard areas such as drainage lines. This topsoil shall be respread later on areas to be revegetated and stabilised only, (i.e. all footpaths, batters, site regarding areas, basins and cathordrains). Topsoil shall not be respread on any other areas unless specifically instructed by the superintendent. If they are to remain for longer than one month stockpiles shall be protected from erosion by covering them with a mulch and hydroseeding and, if necessary, by locating banks or drains downstream of a stockpile to retard silt laden runoff.





LEGE	ND		
ALD AGE ARE BE	Australian height datum Ag-pipe (Sub soil drainage) Average recurrence interval Box Cutter Bottom water level Cover level Clean out inspection opening Discharge control pit Down pipe Dropper pipe Existing box qutter Existing box qutter Existing box qutter Existing eaves quiter Existing eaves guiter Existing eaves guiter Existing eaves guiter Fiber reinforced concrete Fiber reinforced concrete Fiber eniforced orange in the pipe of	SS SU TW TWL UIS VG UNO	Stainless steel Box gulfer sump Top of wall Top water level Underside of slab Vally gutter Unless noted otherwise

RECOMMENDED MAINTENAI	NCE SCHED	ULE	
DISCHARGE CONTROL PIT (DCP)	FREQUENCY	RESPONSIBILITY	PROCEDURE
Inspect flap valve and remove any blockage.	Six monthly	Owner	Remove grate. Ensure flap valve moves freely and remove any blockages or debris.
Inspect screen and clean.	Six monthly	Owner	Revove grate and screen if required and clean it.
Inspect & remove any blockage of orifice.	Six monthly	Owner	Remove grate & screen to inspect orifice. see plan for location of dcp.
Inspect dcp sump & remove any sediment-sludge.	Six monthly	Owner	Remove grate and screen. Remove sediment/sludge build-up and check orifice and flap valve clear.
Inspect grate for damage or blockage.	Six monthly	Owner	Check both sides of grate for corrosion, (especially corners and welds) damage or blockage.
Inspect return pipe from storage and return any blockage.	Six monthly	Owner	Remove grate and screen. ventilate underground storage if present. open flap valve and remove any blockages in return line. Check for sludge/debris on upstream side of return line.
Inspect outlet pipe and remove any blockage.	Six monthly	Maintenance Contractor	Remove grate and screen. ventilate underground storage if present. Check orifice and remove any blockages in outlet pipe. Flush outlet pipe to confirm it drains freely. Check for sludge/debris on upstream side of return line.
Check fixing of step irons is secure.	Six monthly	Maintenance Contractor	Remove grate and ensure fixings secure prior to placing weight on step iron.
Inspect overflow weir & remove any blockage.	Six monthly	Maintenance Contractor	Remove grate and open cover to ventilate underground storage if present, ensure weir clear of blockages.
Empty basket at overflow weir (if present).	Six monthly	Maintenance Contractor	Remove grate and ventilate underground storage chamber if present. Empty basket, check fixings secure and not corroded.
Check attachment of orifice plate to wall of pit (gaps less than 5 mm).	Annually	Maintenance Contractor	Remove grate and screen. ensure plate mounted securely, tighten fixings if required. seal gaps as required.
Check attachment of screen to wall of pit.	Annually	Maintenance Contractor	Remove grate and screen. ensure screen fixings secure. repair as required.
Check screen for corrosion.	Annually	Maintenance Contractor	Remove grate and examine screen for rust or corrosion, especially at corners or welds.
Check attachment of flap valve to wall of .	Annually	Maintenance Contractor	Remove grate. Ensure fixings of valve are secure.
Check flap valve seals against wall of pit.	Annually	Maintenance Contractor	Remove grate. fill pit with water and check that flap seals against side of pit with minimal leakage.
Check any hinges of flap valve move freely.	Annually	Maintenance Contractor	Remove grate. Test valve hinge by moving flap to full extent.
Inspect dcp walls (internal and external, if appropriate) for cracks or spalling.	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Check step irons for corrosion.	Annually	Maintenance Contractor	Remove grate. Examine step irons and repair any corrosion or damage.
Check orifice diameter correct and retains sharp edge.	Five yearly	Maintenance Contractor	Compare diameter to design (see work-as- executed) and ensure edge is not pitted or damaged.
STORAGE			
Inspect & remove any blockage of orifice.	Six monthly	Owner	Remove grate and screen. remove sediment/sludge build-up.
Check orifice diameter correct and retains sharp edge.	Six monthly	Owner	Remove blockages from grate and check if pit blocked.
Inspect screen and clean.	Six monthly	Owner	Remove debris and floatable material likely to be carried to grates.
Check attachment of orifice plate to wall of pit (gaps less than 5 mm).	Annually	Maintenance	Remove grate to inspect internal walls. repair as required. clear vegetation from external walls if necessary and repair as required.
Check attachment of screen to wall of pit.	Five yearly	Maintenance Contractor	Compare actual storage available with work-as executed plans. If volume loss is greater than 5%, arrange for reconstruction to replace the volume lost. Council to be notified of the proposal.
Check attachment of screen to wall of pit.	Five yearly	Maintenance Contractor	Check along drainage lines and at pits for subsidence likely to indicate leakages.

REVISION
Α

N						ĺ
	ı					l
	ľ					l
	ľ					l
		Α	16.01.2023	ISSUED FOR CDC	MT	l
_	ľ	REV	DATE	DESCRIPTION	BY	l

CODVDIGHT All rights reserved.
These drawings, plans and specifications and the copyright are the property of Nemco Design and must not be used, reproduced or copied wholly or in part without the written permission of

**NEMCO**DESIGN


A: SUITE 4, LEVEL 1, 402-410 CHAPEL RD, BANKSTOWN, NSW 2200 P: 9709 5556 M: 0422 606 228

PROPOSED TWO STOREY DWELLING
WITH BASEMENT & POOL
50 CHASELING ST, GREENACRE
LOT 75, DP 35156

STORMWATER - GENERAL NOTES

JOB NUMBER:	DWG NUMBER:	ORIGINAL SIZE:
22808	C00	A3
DESIGNED BY: A.N	DATE: 16.01.2023	
DRAWN BY: A.N	SCALE: AS SHOWN	

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE



#### **CONCEPT STORMWATER PLAN - ROOF PLAN**

- ALL DRAINAGE LINES SHALL BE uPVC (CLASS SH) STORMWATER DRAINAGE PIPE, U.N.O. ALL DRAINAGE LINES SHALL BE LAID @ 1% FALL MIN, U.N.O. MINIMUM EAVE GUTTER SIZE = 13400mm²

- ALL GUTTERS TO BE FITTED WITH GUTTER GUARD TO BUILDERS DETAIL
   MINIMUM EFFECTIVE EAVES GUTTER SLOPE = 1:200 U.N.O.
- THE FOLLOWING SYMBOLS & ABBREVIATIONS HAVE BEEN USED:

### **LEGEND**

DP = Ø100 OR 100 x 75 RECTANGULAR DOWN PIPE, U.N.O. DP/SP = DOWN PIPE + SPREADER



				A A
				th a
Α	16.01.2023	ISSUED FOR CDC	МТ	l w
REV	DATE	DESCRIPTION	BY	


COPYRIGHT
All rights reserved.
These drawings, plans and specifications and the copyright are the property of Nemco Design and must not be used, reproduced or copied wholly or in part without the written permission of



PROPOSED TWO STOREY D WITH BASEMENT & PC 50 CHASELING ST, GREENACE A: SUITE 4, LEVEL 1, 402-410 CHAPEL RD, BANKSTOWN, NSW 2200 P: 9709 5556 M: 0422 606 228 LOT 75, DP 35156 STORMWATER DRAINAGE P

**ROOF PLAN** 

OWELLING OOL CRE	JOB NUMBER: 22808	DWG NUMBER: C01	ORIGINAL SIZE:
/KL	DESIGNED BY: A.N	DATE: 16.01.2023	
PLAN -	DRAWN BY: A.N	SCALE: AS SHOWN	



#### **CONCEPT STORMWATER PLAN - BASEMENT PLAN**

- ALL DRAINAGE LINES SHALL BE uPVC (CLASS SH) STORMWATER DRAINAGE PIPE, U.N.O. ALL DRAINAGE LINES SHALL BE LAID @ 1% FALL MIN, U.N.O.

- MINIMUM EAVE GUTTER SIZE = 13400mm<sup>2</sup>
   ALL GUTTERS TO BE FITTED WITH GUTTER GUARD TO BUILDERS DETAIL
- MINIMUM EFFECTIVE EAVES GUTTER SLOPE = 1:200 U.N.O.
- THE FOLLOWING SYMBOLS & ABBREVIATIONS HAVE BEEN USED:

### **LEGEND**

DP = Ø100 OR 100 x 75 RECTANGULAR DOWN PIPE, U.N.O.



Α	16.01.2023	ISSUED FOR CDC	МТ	ĺ
REV	DATE	DESCRIPTION	BY	
				_


COPYRIGHT
All rights reserved.
These drawings, plans and specifications and the copyright are the property of Nemco Design and must not be used, reproduced or copied wholly or in part without the written permission of



A: SUITE 4, LEVEL 1, 402-410 CHAPEL RD, BANKSTOWN, NSW 2200 P: 9709 5556 M: 0422 606 228

PROPOSED TWO STOREY DWELLING WITH BASEMENT & POOL 50 CHASELING ST, GREENACRE	JOB NUMBER: 22808	DWG NUMBER: C02	ORIGINAL SIZE:
LOT 75, DP 35156	DESIGNED BY: A.N	DATE: 16.01.2023	
STORMWATER DRAINAGE PLAN - BASEMENT PLAN	DRAWN BY: A.N	SCALE: AS SHOWN	

NOTE: DO NOT SCALE OFF DRAWINGS, REFER TO ARCHITECTURAL PLANS, VERIFY DIMENSIONS ON SITE



TYPICAL SECTION(A) THROUGH PUMP PIT

SCALE 1:20

HEAVY DUTY CAST IRON OR FABRICATED GALVANISED STEEL GRATES SHALL BE PROVIDED ON ALL SURFACE INLET PITS IN AREAS WITH VEHICULAR TRAFFIC.

- TWO(2) PUMPS KWIKFLO SUBMERSIBLE PUMPS (415v OR 240v). ONE(1) PUMPS KWIK START CONTROL PANEL (CONTROL DESIGN TO ALTERNATE PUMPS ON START ON CONSECUTIVE START OPERATION).
- TWO(2) GATE VALVES )BRONZE).

ECIFIED TO MANUFACTURERS


TAIL AND CALCULATION SHEET

- TWO(2) CHECK VALVES (SWING TYPE) (BRONZE).
  TWO(2) SETS OF DISCHARGE HOSES WITH KAMLOK QUICK RELEASE COUPLINGS.
- ALL IN TANK PIT/PIPE AND PIPE FITTINGS, BRACKETS/SUPPORTS, HD GAL. CHAINS. FOUR(4) KWIK START KENRAHN MERCURY LEVEL FLOAT REGULATORS.

TANK PACKAGE/COVERS/MANHOLE, ALARM BELL, LOW LEVEL ALARM REGULATOR

MODEL	DIS. SIZE	MOTOR kw	POWER	Max Capacity	Max Head	Wt. kgs	CABLE m
KPSS 250	40mm BSP	0.25	240v	220 L/min	8 metres	17	5.2metre
KPSS 400	50mm BSP	0.40	240v	290 L/min	13 metres	19	5.2metre
KPSS 750	50mm BSP	0.75	240or415v	380 L/min	16 metres	20	5.2metre

# **PUMP SPECIFICATIONS**



# PUMP PERFORMANCE CURVES

#### **PUMP WELL DETAILS**


SUMP SIZE AND PUMP SIZE BASE ON 50 YEAR 2 HR STORM **INTENSITY IS 46.9mm/hr** AREA DRAINING TOWARDS SUMP IS UP TO 75m<sup>2</sup>  $Q=CIA/3600 = 0.95 \times 46.9 \times 75 / 3600 = 0.93 I/S$ VOLUME REQUIRED IS  $0.93 \times (2 \times 60 \times 60) = 6.7 \text{ m}^3$ STORAGE PROVIDED 2600 x 2600 x 1000 = 6.7 m<sup>3</sup>

PUMP OUT RATE BASED ON 50YR 5MIN. STORM = 219mm/hr Q=CIA/3600 = 1.0x219x100/3600 = 6.1I/s

### STANDARD PUMP-OUT NOTES

THE PUMP-OUT SYSTEM IS DESIGNED TO WORK IN THE FOLLOWING MANNER -

- 1. THE PUMPS SHALL BE PROGRAMMED TO WORK ALTERNATELY SO AS TO ALLOW BOTH PUMPS TO HAVE EQUAL OPERATION LOAD & PUMP LIFE.
- 2. A LOW LEVEL FLOAT SHALL BE PROVIDED TO ENSURE THAT THE MINIMUM REQUIRED WATER LEVEL IS MAINTAINED WITHIN THE SUMP AREA OF THE BELOW GROUND TANK. IN THIS REGARD THIS FLOAT WILL FUNCTION AS AN OFF SWITCH FOR THE PUMPS.
- 3. A SECOND FLOAT SHALL BE PROVIDED AT A HIGHER LEVEL, APPROXIMATELY 300mm ABOVE THE MINIMUM WATER LEVEL, WHEREBY ONE OF THE PUMPS WILL OPERATE & DRAIN THE TANK TO THE LEVEL OF THE LOW LEVEL FLOAT.
- 4. A THIRD FLOAT SHALL BE PROVIDED AT A HIGH LEVEL, WHICH IS APPROXIMATELY THE ROOF LEVEL OF THE BELOW GROUND TANK. THIS FLOAT SHOULD START THE OTHER PUMP THAT IS NOT OPERATING & ACTIVATE THE ALARM.
- 5. AN ALARM SYSTEM SHALL BE PROVIDED WITH A FLASHING STROBE LIGHT & A PUMP FAILURE WARNING SIGN WHICH ARE TO BE LOCATED AT THE DRIVEWAY ENTRANCE TO THE BASEMENT LEVEL. THE ALARM SYSTEM SHALL BE PROVIDED WITH A BATTERY BACK-UP IN CASE OF POWER FAILURE.



# TYPICAL SECTION THROUGH SUBSOIL HARD PIPE

STRUCTURAL ENGINEERING & ARCHITECTURAL DESIGN



A	16.01.2023	ISSUED FOR CDC	МТ
REV	DATE	DESCRIPTION	BY

COPYRIGHT All rights reserved.
These drawings, plans and specifications and the copyright are the property of Nemco Design and must not be used, reproduced or copied wholly or in part without the written permission


A: SUITE 4, LEVEL 1, 402-41 CHAPEL RD, BANKSTOWN, NSW 2200 P: 9709 5556 M: 0422 606 2 **NEMCO**DESIGN


	PROPOSED TWO STOREY DWELLIN
10	WITH BASEMENT & POOL
	50 CHASELING ST, GREENACRE
28	LOT 75, DP 35156
com.au	

**SECTION THROGH PUMP PIT & D** 

ELLING DL	JOB NUMBER: 22808	DWG NUMBER: C03	ORIGINAL SIZE:
	DESIGNED BY: A.N	DATE: 16.01.2023	
ETAILS	DRAWN BY: A.N	SCALE: AS SHOWN	

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE





'D'

100-150

225-300

TABLE A						
RAINWATER	METER	TYPE	TYPE OF			
TANK LOCATION	I SIZE (mm)	OF TAP	BACKFLOW PREVENTION			
ABOVE GROUND	20	BALL VALVE	DUAL CHECK VALVE			
			(COMBINED WITH METER)			
	25	BALL VALVE	DUAL CHECK VALVE			
	≥ 32	BALL VALVE	DUAL CHECK VALVE			
BELOW GROUND	20	BALL VALVE	TESTABLE DOUBLE CHECK VALVE			
	25	BALL VALVE	TESTABLE DOUBLE CHECK VALVE			
	≥ 32	BALL VALVE	TESTABLE DOUBLE CHECK VALVE			

# **LEGEND**

- PRESSURE VESSEL METER
- BALL VALVE RIGHT ANGLE TYPE ₽
- DUAL CHECK VALVE ⅎ PUMP
- **GARDEN TAP**
- DRINKING WATER SUPPLY PIPES RAINWATER SUPPLY PIPES
- --- DOWN PIPES

- DIAGRAM NOTES:
- DRAWING TO BE READ IN CONJUNCTION WITH SYDNEY WATER PLUMBING REQUIREMENTS
- 2 FOR TANKS 10,000 LITRES OR LESS, COUNCIL DEVELOPMENT CONSENT IS NOT REQUIRED, IF THEIR CONDITIONS FOR INSTALLATION ARE FOLLOWED.
- 3 FOR TANKS GREATER THAN 10,000 LITRES COUNCIL DEVELOPMENT CONSENT IS GENERALLY REQUIRED.
- 4 FOR TANKS MORE THAN 10,000 LITRES APPROVAL IS REQUIRED FOR BUILDING OVER SEWERS.
- 5 SYDNEY WATER'S APPROVAL IS REQUIRED FOR ANY TOP UP FROM DRINKING WATER SUPPLY, REGARDLESS OF TANK SIZE. NO DIRECT CONNECTION IS ALLOWED BETWEEN THE DRINKING WATER SUPPLY AND THE RAINWATER TANK SUPPLY.
- RAINWATER PIPEWORK IS SHOWN ON THE DIAGRAM AS SUPPLYING INTERNAL AND EXTERNAL RAINWATER USES. CUSTOMERS MAY WANT ONE OR THE OTHER.
- ANY DESIGNED ACCESS LID INTO RAINWATER RE-USE TANK IS TO HAVE A LOCKABLE LID. IF THE LID IS DESIGNED TO BE ACCESSED BY A MAINTENANCE PERSON, IT MUST BE AT LEAST 600 mm x 900 mm IN SIZE.

# UPVC PIPE

REFER TO PIPE LAYING


SPECIFICATION FOR

# TYPICAL PIPE LAYING DETAIL

DETAILS.

# **DUAL DRINKING WATER & RAINWATER SUPPLY DIAGRAM**

SSUED FOR CDC



NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

COPYRIGHT All rights reserved.
These drawings, plans and specifications and the copyright are the property of Nemco Design and must not be used, reproduced or copied wholly or in part without the written permission of

A: SUITE 4, LEVEL 1, 402-410 CHAPEL RD, BANKSTOWN, NSW 2200 P: 9709 5556 M: 0422 606 228 **NEMCO**DESIGN STRUCTURAL ENGINEERING & ARCHITECTURAL DESIGN

PROPOSED TWO STOREY DWELLING WITH BASEMENT & POOL LOT 75. DP 35156

STORMWATER DETAILS

C04 22808 A3 DESIGNED BY 16.01.2023 AS SHOWN

MIN

75

75

75

300

600