STORWATER MANAGEMENT PLAN

78-80A BENAROON ROAD, LAKEMBA, NSW 2195

GENERAL NOTES

- G1 ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE WITH COUNCIL'S REQUIREMENTS, BUILDING CODE OF AUSTRALIA, NSW CODE OF PRACTICE AND THE TO THE RELEVANT SERVICE CODES.
- THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL AND OTHER CONSULTANTS' DRAWINGS AND SPECIFICATIONS AND WITH SUCH OTHER WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ALL DISCREPANCIES SHALL BE REFERRED TO THE SUPERINTENDENT FOR DECISION BEFORE PROCEEDING WITH THE WORK.
- G3 ALL DIMENSIONS SHOWN ON THE DRAWINGS ARE IN MILLIMETERS IU.N.O.), DIMENSIONS SHALL NOT BE OBTAINED BY SCALING OF THESE DRAWINGS. USE FIGURED DIMENSIONS ONLY.
- BENCHMARKS HAVE BEEN ESTABLISHED WHERE INDICATED IN THE DRAWINGS. ALL LEVELS ARE TO AUSTRALIAN HEIGHT DATUM (A.H.D.). THE CONTRACTOR SHALL UNDERTAKE ALL NECESSARY SURVEY WORK TO ENSURE THAT THE WORKS ARE CONSTRUCTED TO DESIGN LINE AND LEVEL.
- G5 SETTING OUT DIMENSIONS AND LEVELS SHOWN ON THE DRAWINGS SHALL BE VERIFIED BY THE CONTRACTOR.
- G6 ALL MATERIALS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE RELEVANT AUSTRALIAN CODES AND THE BY-LAWS AND ORDINANCES OF THE RELEVANT BUILDING AUTHORITIES.
- G7 IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE ALL SAFETY FENCES. WARNING SIGNS. TRAFFIC DIVERSIONS AND THE LIKE DURING CONSTRUCTION. ALL WORKS TO COMPLY WITH WORK HEALTH AND SAFETY REQUIREMENTS AND OTHER RELEVANT AUTHORITY SAFETY REQUIREMENTS.
- G8 NO TREES SHALL BE REMOVED. CUTBACK OR RELOCATED WITHOUT THE WRITTEN INSTRUCTION FROM THE SUPERINTENDENT/COUNCIL.
- G9 WHERE NEW WORKS ABUT EXISTING THE CONTRACTOR SHALL ENSURE THAT A SMOOTH EVEN PROFILE, FREE FROM ABRUPT CHANGES IS OBTAINED.
- G10 ALL WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE DETAILS SHOWN ON THE DRAWINGS AND THESE SPECIFICATIONS.
- G11 DESIGN LEVELS GIVEN ARE TO FINISHED SURFACE LEVEL AND INCLUSIVE OF TOPSOIL. TOPSOIL DEPTH VARIES!
 G12 THE CONTRACTOR SHALL ARRANGE ALL SURVEY SETOUT TO BE
- CARRIED OUT BY A N.A.T.A. REGISTERED SURVEYOR.

 G13 CARE IS TO BE TAKEN WHEN EXCAVATING NEAR EXISTING SERVICES. NO MECHANICAL EXCAVATIONS ARE TO BE UNDERTAKEN OVER TELECOMMUNICATIONS OR ELECTRICAL

SERVICES. HAND EXCAVATE IN THESE AREAS.

- G14 THE LOCATIONS OF UNDERGROUND SERVICES SHOWN ON THE DRAWING HAVE BEEN PLOTTED FROM DIAGRAMS PROVIDED BY SER VICE AUTHORITIES. THIS INFORMATION HAS BEEN PREPARED SOLELY FOR THE AUTHORITIES OWN USE AND MAY NOT NECESSARILY BE UPDATED OR ACCURATE.
- G15 THE POSITION OF SER VICES AS RECORDED BY THE AUTHORITY AT THE TIME OF INSTALLATION MAY NOT REFLECT CHANGES IN THE PHYSICAL ENVIRONMENT SUBSEQUENT TO INSTALLATION.
- G16 HORIZON ENGINEERS DOES NOT GUARANTEE THAT THE SERVICES INFORMATION SHOWN ON THE DRAWING SHOWS MORE THAN THE PRESENCE OR ABSENCE OF SERVICES. AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SER VICES INFORMATION SHOWN FROM ANY CAUSE WHATSOEVER.
- G17 IT IS THE CONTRACTOR'S RESPONSIBILITY TO OBTAIN FROM THE UTILITY SERVICES AUTHORITIES A CURRENT COPY OF UNDERGROUND SERVICES SEARCH FOR THE LOCATION OF ALL EXISTING SERVICES PRIOR TO COMMENCEMENT OF ANY WORK AND NOTIFY ANY CONFLICT WITH THE DRAWINGS IMMEDIATELY. CLEARANCE SHALL BE OBTAINED FROM THE RELEVANT REGULATORY AUTHORITY.
 - CONTRACTOR TO KEEP COPY OF UNDERGROUND SERVICES SEARCH ON SITE AT ALL TIMES. ANY DAMAGES TO SERVICES OR SER VICES ADJUSTMENTS SHALL BE CARRIED OUT BY THE CONTRACTOR OR RELEVANT AUTHORITY AT THE CONTRACTOR'S EXPENSE.
- G18 VISIT THE SITE BEFORE SUBMITTING THE FINAL TENDER PRICE TO ASSESS "ON SITE' CONDITIONS. FAILURE TO DO SO WILL FORFEIT ANY CLAIM FOR NOT BEING AWARE OF CONDITIONS AFFECTING THE TENDER.
- G19 THE CONTRACTOR SHALL PREPARE ACCURATE
 WORK-AS-EXECUTED DRAWINGS FOLLOWING THE COMPLETION OF
 ALL WORKS.
- G20 IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE IN PLACE & MAINTAIN TRAFFIC FACILITIES AT ALL TIMES DURING CONSTRUCTION
- G21 GEOTEXTILE FABRIC MATERIAL TO BE BIDIM A14 OR APPROVED EQUIVALENT AND SHALL COMPLY WITH AS3TOS-1011"GEOTEXTILES- \$9 IDENTIFICATION, MARKING AND GENERAL DATA'.

RESTORATION

COMPACT AS SPECIFIED.

RI RESTORE ALL TRAFFIC AREAS TO PRE-EXISTING CONDITIONS.
R2 FOR ALL SURFACES OTHER THAN IN TRAFFIC AREAS RESTORE
DISTURBED SURFACES TO PRE-EXISTING CONDITIONS AND

APPROVALS

- API THE AS-BUILT WORKS SHALL BE INSPECTED BY THE ENGINEER. MINIMUM 48 HOURS NOTICE SHALL APPLY TO ALL INSPECTIONS.
- AP2 THE DESIGN PLANS HEREIN ARE SUBJECT TO LOCAL COUNCIL APPROVAL PRIOR TO CONSTRUCTION. OBTAIN EXPRESS IN WRITING ADVICE TO PROCEED FROM PROJECT SUPERINTENDENT PRIOR TO COMMENCEMENT.
- AP3 SUBMIT WORK-AS-EXECUTED DRAWINGS IN DWG FORMAT AND HARD COPY FORMAT UNDERTAKEN BY A REGISTERED SURVEYOR. VERIFY ALL CONSTRUCTION WORKS SHOWN HEREON.
- AP4 CERTIFY THAT THE AS-BUILT SYSTEM HAS BEEN BUILT IN ACCORDANCE WITH THE APPROVED PLANS ISSUED FOR CONSTRUCTION.
- AP5 ALLOW FOR SUB GRADE AND PAVEMENT THICKNESS TO BE VERIFIED BY THE GEOTECHNICAL ENGINEER AFTER INSPECTION OF PRELIMINARY BOXING.
- AP6 ALLOW FOR ANY SUB-GRADE REPLACEMENT WORK TO BE DETERMINED AS REQUIRED BY GEOTECHNICAL ENGINEER AT THE TIME OF PAVEMENT CONSTRUCTION.

KERB AND GUTTER

- KGI ALL KERB AND GUTTER SHALL COMPLY WITH AS2876-2000, CONCRETE KERBS AND CHANNELS-MANUALLY OR MACHINE PLACED".
- WITH THE CONCRETE NOTES.

 KG3 CONTROL JOINTS SHALL BE FORMED AT A MAXIMUM

KG2 CONCRETE CHARACTERISTICS SHALL BE IN ACCORDANCE

- KG3 CONTROL JOINTS SHALL BE FORMED AT A MAXIMUM SPACING OF 3m.
- KG4 THE CONTRACTOR SHALL LIAISE WITH RELEVANT AUTHORITIES TO DETERMINE THEIR REQUIREMENTS FOR THE KERBS AND GUTTERS.
- KG5 ALL KERB & GUTTER IS TO BE MACHINE LAID UNLESS OTHER WISE APPROVED BY THE SUPERINTENDENT

KERB INLET PITS

- KI COMPRESSIVE STRENGTH (F"c) FOR CAST IN SITU CONCRETE SHALL BE A MINIMUM 15MPa AT 18 DAYS.
- K2 100 DIA SUBSOIL DRAINAGE PIPE 3000mm LONG WRAPPED IN FABRIC SOCK SHALL BE PROVIDED ON THE UPSTREAM SIDE OF PIT, ADJACENT TO INLET PIPES.
- K3 ALL PITS SHALL BE PROVIDED WITH A LOCKING CLIP.
- K4 PIT GRATE SHALL BE "WELDLOCK" GULLY GRATE GGTB-SS OR EQUAL (APPROVED BY COUNCIL) WITH SKIRT FOR INDUSTRIAL ROADS. WITH 41xS EDGE BARS. GRATE TO BE CAST IRON HEAVY DUTY. THEFT RESISTANT SWING AND BICYCLE SAFE
- K5 DURING INSTALLATION OF GRATE & FRAME. CONTRACTOR SHALL ENSURE CLEARANCE BETWEEN LINTEL & OPENED GRATE

STORMWATER

- SI ALL WORK SHALL BE CARRIED OUT IN ACCORDANCE AS3500.3-2003 'STORMWATER DRAINAGE'.
- S2 FOR STORMWATER DRAINAGE PIPES THAT EXCEED 1:5 GRADE. REINFORCED CONCRETE ANCHOR BLOCKS SHALL BE INSTALLED. ANCHOR BLOCKS TO BE CONSTRUCTED TO SPECIFICATIONS SET OUT IN AS3500.3-2003 SECTION 8.10
- S3 EXISTING SERVICES SHOWN IN APPROXIMATE LOCATIONS ONLY.
- CONFIRM EXACT LOCATIONS ON SITE PRIOR TO COMMENCING WORK.

 S4 COORDINATE THE INSTALLATION OF NEW SERVICES WITH ALL NEW &
 EXISTING SER VICES & STRUCTURAL PROVISIONS AS
- DETERMINED ON SITE.

 S5 ALL PIPEWORK TO BE SUPPORTED IN ACCORDANCE WITH AS3500.3-2003.
- ALL PIPEWORK IS TO BE TESTED IN ACCORDANCE WITH THE REQUIREMENTS AS SET DOWN IN AS3500.3-2003. ALL IN-GROUND PIPEWORK TO BE INSPECTED BY THE SUPERINTENDENT UNDER TEST CONDITIONS PRIOR TO BACKFILLING.
- BACKFILLING AND BEADING TO AS3500.I-2003.

 S7 PIPES SHALL BE TRUE TO GRADES SHOWN AND ALIGNED SO THAT THE CENTER OF THE INLET PIPE INTERSECTS WITH THE CENTER OF THE OUTLET PIPE AT THE DOWNSTREAM FACE OF THE PIT.
- S8 BED ALL PIPES FIRMLY AND EVENLY WITH IMPORTED FILL ONLY. THICKNESS OF BEDDING LAYER SHALL BE 75mm IN SOIL AND 100mm IN ROCK.
- S9 LAY AND JOINT ALL PIPES IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND AS3725-2007, "DESIGN FOR INSTALLATION OF BURIED CONCRETE PIPES".
- SIO ALLOW TO TEST ALL PIPES AND PITS TO LOCAL AUTHORITY'S REQUIREMENTS.
- S11 EXCAVATE TRENCHES AND STOCKPILE ALL MATERIAL FOR INSPECTION WITH REGARD TO REUSE FOR TRENCH BACKFILL. REMAINING MATERIAL TO BE REMOVED FROM SITE.

- S12 BACKFILL PIPES WITH IMPORTED FILL. PROVIDE 200mm SIDE SUPPORT AND 150mm OVERLAY ABOVE PIPE CROWN. TRENCH FILL ABOVE THE EMBEDMENT ZONE TO THE UNDERSIDE OF THE ROAD PAVEMENT OR THE FOOTWAY SHALL BE AS FOLLOW,-
 - UNDER ROADWAY
 TRENCH FILL MATERIAL SHALL CONSIST OF IMPORTED FILL AS
 SPECIFIED HEREIN OF EITHER HIGH GRADE COMPACTION SAND OR
 APPROVED CRUSHED ROAD GRAVEL CONFORMING TO RMS QA
 SPECIFICATION 3051 OR SIMILAR.
 OTHER THAN ROADWAY
- TRENCH MATERIAL EXCAVATED SHALL CONSIST OF SELECT FILL AS SPECIFIED HEREIN AND SHALL NOT CONTAIN MORE THAN 10% OF STONES OF SIZE BETWEEN 25mm AND 75mm AND NONE LARGER THAN 75mm. PRIOR TO USE OF THE EXCAVATED MATERIAL IT SHALL BE INSPECTED AND APPROVED BY THE ENGINEER.
- S13 COMPACT BEDDING. EMBEDMENT AND TRENCH FILL MATERIALS ASFOLLOW,- EMBEDMENT;
- FOR GRANULAR FILL MATERIAL (NON-COHESIVE SOILS e.g. COARSE AGGREGATE FILL, THE DENSITY INDEX (ID) SHALL BE NOT LESS THAN 70%.
- TRENCH FILL,FOR GRANULAR MATERIAL (NON COHESIVE SOILS). THE DENSITY INDEX
 (ID) SHALL BE NOT LESS THAN 70%. FOR NON-GRANULAR FILL
 MATERIAL (COHESIVE SOILS). THE DRY DENSITY RATIO (RD) SHALL BE
 NOT LESS THAN 95%.
- SI4 EXISTING SERVICES
- UTILITY INFORMATION SHOWN ON THE PLANS IS NOT INTENDED TO DEPICT MORE THAN THE PRESENCE OF ANY SERVICES. ACTUAL LOCATIONS SHOULD BE VERIFIED BY HAND EXCAVATION PRIOR TO CONSTRUCTION.
- SI5 THE CONTRACTOR SHALL ALLOW FOR THE CAPPING OFF, EXCAVATION AND REMOVAL (IF REQUIRED) OF ALL EXISTING SERVICES IN AREAS AFFECTED BY THE WORKS.
- SI6 THE CONTRACTOR SHALL ENSURE THAT SER VICES TO ALL BUILDINGS NOT AFFECTED BY THE WORKS ARE NOT DISRUPTED AT ALL TIMES. THE CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES TO MAINTAIN EXISTING SUPPLY TO BUILDINGS REMAINING WHERE REQUIRED. ONCE THE WORKS ARE COMPLETE AND COMMISSIONED THE CONTRACTOR SHALL REMOVE ALL SUCH TEMPORARY SERVICES AND MAKE GOOD ALL DISTURBED AREAS.
- S17 DRAINAGE PIPES
 - EXISTING PIPES WHICH FORM NO PART OF THE DRAINAGE SYSTEM SHALL BE REMOVED OR SEALED AS INDICATED ON THE PLANS. PIPES UP TO 300mm DIAMETER SHALL BE SEWER GRADE uPVC WITH SOLVENT WELDED JOINTS (U.N.O.). ALL PIPE JUNCTIONS AND TAPERS SHALL BE VIA PURPOSE MADE FITTINGS.
- SI8 WHERE DOWNPIPES PASS UNDER FLOOR SLABS, SEWER GRADE uPVC WITH RUBBER RING JOINTS ARE TO BE USED.
- SI9 MINIMUM GRADE TO DRAINAGE PIPES TO BE 1% (U.N.0.), MIN. SIZE IOOmm DIAMETER (U.N.0.).
- S20 PIPES LARGER THAN OR EQUAL TO 300mm DIAMETER TO BE REINFORCED CONCRETE RUBBER RING JOINTED TYPE (CLASS 2) MANUFACTURED TO AS4058 (U.N.O.).
- S21 PIPE INSTALLATION UNDER TRAFFICABLE AREAS SHALL BE IN ACCORDANCE WITH CONCRETE PIPE ASSOCIATION OF AUSTRALIA PUBLICATION "CONCRETE PIPE SELECTION & INSTALLATION" TYPE HS3 SUPPORT.
- S22 EQUIVALENT STRENGTH FRC PIPES MAY BE USED SUBJECT TO AUTHORITY APPROVAL.
- S23 MINIMUM PIPE COVER TO BE 600mm UNDER TRAFFICABLE AREAS AND
- 300mm ELSEWHERE U.N.O.

 S24 CONTRACTOR TO SUPPLY AND INSTALL ALL FITTINGS AND SPECIALS INCLUDING VARIOUS PIPE ADAPTORS TO ENSURE PROPER CONNECTION BETWEEN DISSIMILAR PIPEWORKS.
- S25 STORMWATER DRAINAGE CONNECTIONS TO COUNCIL'S SYSTEM SHALL BE TO THE REQUIREMENTS AND THE SATISFACTION OF LOCAL COUNCIL
- S26 DRAINAGE PITS PITS DEEPER THAN 1200mm TO BE FITTED WITH STEP IRON AT 300 CENTRES TO AS1657-2013: 'FIXED PLATFORMS, WALKWAYS, STAIRWAYS AND LADDERS DESIGN, CONSTRUCTION AND INSTILLATION'
- S27 ALL EXPOSED EDGES TO BE ROUNDED WITH 20mm RADIUS, OR CHAMFERED 20mm X 20mm
- S28 PIT REINFORCEMENT MESH SL82 LAP TO BE 400mm MIN. CLEAR COVER 40 MIN. CAST AGAINST BLINDING OR FORMWORK.
- S30 BENCHING TO BE HALF OUTGOING PIPE DEPTH. CONCRETE FOR BENCHING TO BE 20MPa MASS CONCRETE.
- S31 APPROVED PRECAST PITS MAY BE USED.S32 100mm DIAMETER HOLE FOR SUBSOIL DRAINAGE OUTLET TO BE
- LOCATED 100mm ABOVE INVERT OF ALL INLET PIPES. SUBSOIL
 DRAINAGE TO EXTEND FOR A DISTANCE OF 3m UPSTREAM OF PIT (AT
 EACH INLET TRENCH) WITH THE UPSTREAM END SEALED.

 833 ALL CONNECTIONS TO EXISTING DRAINAGE PITS SHALL BE MADE IN
- S33 ALL CONNECTIONS TO EXISTING DRAINAGE PITS SHALL BE MADE IN TRADESMAN-LIKE MANNER AND THE INTERNAL WALL OF THE PIT AT THE POINT OF ENTRY SHALL BE CEMENT RENDERED TO ENSURE A SMOOTH FINISH.
- S34 PIT GRATE. FRAMES AND SOLID COVERS SHALL BE CLASS B IN NON TRAFFIC AREAS AND CLASS D IN TRAFFICABLE AREAS IN ACCORDANCE WITH AS3996.
- S35 ALL GRATES SHALL BE PROVIDED WITH A LOCKING CLIP.

- S36 MAXIMUM FRONT ENTRY PIPE,-STRAIGHT ENTRY- 750 DIAMETER SKEW ENTRY 45 DEGREES 525 DIAMETER
- S37 PIT GRATING TO BE GALVANISED STEEL TYPE "WELDLOK" OR APPROVED EQUIVALENT.
- S38 SUBSOIL DRAINAGE PIPES SHALL BE LAID AT A MIN GRADE OF 0.5% U.N.O.
- S39 ADDITIONAL SUBSOIL DRAINAGE SHALL BE LAID TO SUIT SITE CONDITIONS AND GROUNDWATER PRESENCE AS DIRECTED.
- S40 SUBSOIL PIPES SHALL BE LAID BEHIND KERBS IN CUT AREAS OF THE SITE.
- S41 SUBSOIL DRAINAGE SHALL CONSIST OF A SLOTTED IOOMM
 DIAMETER PLASTIC PIPE WRAPPED IN GEOTEXTILE AND PLACED
 A MINIMUM OF 650mm BELOW THE FINISHED SURFACE LEVEL
 AND COVERED WITH 500mm OF 20mm GRAVEL.
 PROVIDE A MINIMUM OF I50mm GRAVEL AROUND SUBSOIL PIPE.
 TRENCH TO BE LINED WITH GEOTEXTILE FABRIC TYPE BIDIM A24
- S42 GRATES TO PITS IN FOOTPATH AREAS SHALL BE HEEL SAFE COMPLYING WITH THE DISABLED ACCESS CODE

EROSION CONTROL

- ECI BEFORE EARTHWORKS CAN COMMENCE THE EROSION &
- SEDIMENT CONTROL MEASURES MUST BE IN PLACE.

 EC2 DURING THE CONSTRUCTION PERIOD, THESE CONTROL MEASURES WILL NEED TO BE INSPECTED & MAINTAINED REGULARLY. ESPECIALLY AFTER STORM EVENTS. BY THE CONTRACTOR.
- EC3 ALL WORK IS TO BE CARRIED OUT TO PREVENT EROSION.
 CONTAMINATION & SEDIMENTATION OF THE STORAGE SITE,
 SURROUNDING AREAS & DRAINAGE SYSTEMS.
- EC4 MINIMIZE DISTURBED AREA COVERED WITH NATURAL VEGETATION. ONLY THOSE AREAS DIRECTLY REQUIRED FOR
- CONSTRUCTION ARE TO BE DISTURBED.

 EC5 INSTALL EROSION/SEDIMENT CONTROL MEASURES PRIOR TO COMMENCEMENT OF CONSTRUCTION OR EXCAVA!ION
- EC6 PROVIDE SILT FENCE/STRAW BAIL BARRIERS TO THE LOW SIDE OF ALL EXPOSED EARTH EXCAVATIONS. TIE SEDIMENT FENCING MATERIAL TO CYCLONE WIRE SECURITY FENCE. SEDIMENT CONTROL FABRIC SHALL BE AN APPROVED MATERIAL (EG. HUMES PROPEX SILT STOP) STANDING 300mm ABOVE GROUND & EXTENDING 150mm BELOW GROUND.
- EC7 ISOLATE EXISTING STORMWATER PITS WITH STRAW BALES OR SILT TRAPS TO FILTER ALL INCOMING FLOWS.
- EC8 DO NOT STOCKPILE EXCAVATED MATERIAL ON THE ROAD WAY.
- EC9 DIVERT CLEAN WATER FROM UNDISTURBED AREAS AROUND THE WORKING AREAS.ECIO CONSTRUCTION ENTRY/EXIT SHALL BE VIA THE LOCATION
- NOTED ON THE DRAWING. CONTRACTOR SHALL ENSURE ALL DROPPABLE SOIL & SEDIMENT IS REMOVED PRIOR TO CONSTRUCTION TRAFFIC EXITING SITE. CONTRACTOR SHALL ENSURE ALL CONSTRUCTION TRAFFIC ENTERING AND LEAVING THE SITE DO SO IN A FORWARD DIRECTION.
- EC11 TREAT THE STORMWATER RUNOFF WITH SUSPENDED SOLIDS SO
 THE DISCHARGE WATER QUALITY TO COUNCIL STORMWATER
 DRAINAGE SYSTEM HAS A MAXIMUM CONCENTRATION OF
 SUSPENDED SOLIDS THAT DOES NOT EXCEED 50
 MILLIGRAMS PER LITTER IN ACCORDANCE WITH THE
 PROTECTION OF THE ENVIRONMENT OPERATION ACT (POED
- 1997) AND SHALL BE APPROVED BY LOCAL COUNCIL
 EC12 ADOPT TEMPORARY MEASURES AS MAY BE NECESSARY FOR
 EROSION AND SEDIMENT CONTROL, INCLUDING BUT NOT LIMITED
 TO THE FOLLOWING:-
 - DRAINS: TEMPORARY DRAINS AND CATCH DRAINS
 SPREADER BANKS OR OTHER STRUCTURES: TO DISPERSE
 CONCENTRATED RUNOFF
 SILT TRAPS: CONSTRUCTION AND MAINTENANCE OF SILT TRAPS
- DOWNSTREAM AREAS.
 EC13 AFTER RAIN, INSPECT, CLEAN AND REPAIR IF REQUIRED
 TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES.

TO PREVENT DISCHARGE OF SCOURED MATERIAL TO

- EC14 REMOVE TEMPORARY EROSION AND SEDIMENT CONTROL
 MEASURES WHEN THEY ARE NO LONGER REQUIRED.
- EC15 COMPLY WITH THE REQUIREMENTS OF LANDCOM'S
 MANAGEMENT URBAN STORMWATER
 SOIL AND CONSTRUCTION 'THE BLUE BOOK' LATEST EDITION
- EC16 THE EROSION AND SEDIMENT CONTROL PLAN PROVIDES IS ONLY INDICATIVE. THE CONTRACTOR SHOULD PREPARE A DETAILED ESCP SUITABLE FOR THE SPECIFIC SITE CONDITIONS.

<u>ABBREVIATIONS</u>

LEVELS

FFL FINISH FLOOR LEVEL
FSL FINISH SURFACE LEVEL
IL INVERT LEVEL
RL REDUCED LEVEL
H/L HIGH LEVEL
L/L LOW LEVEL

TOP OF KERB

HIGH POINT

VP VENT PIPE
RV RELIEF VENT
SW STORMWATER
SRM SEWER RISING MAIN
DTU DRAINAGE TURN UP
RWO RAIN WATER OUTLET
RWH RAIN WATER HEAD
O/F OVERFLOW

BALCONY OUTLET

PLANTER DRAIN OUTLET

STORMWATER SERVICES LEGEND

חוחבכ

PIPES —

SERVICE TYPE
SERVICE SIZE
DROPPER
STORMWATER

SUB SOIL DRAINAGE

1 DETAIL N

O. DETAIL REFERENCE

CAST-IN PIPES

SYMBOLS

CO CLEAR OUT

BEND RISER

BEND DROPPER

TEE RISER

TEE DROPPER

DIRECTION OF FLOW

RWO/PDO

SEALED JUNCTION PIT

GRATED INLET PIT

TRENCH GRATE

DRAWING SCHEDULE

| DWG NO. | DRAWING TITLE | REV. |
|---------|---------------------------------|------|
| W-00 | LEGEND & NOTES | 3 |
| W-01 | BASEMENT PLAN | 3 |
| W-01A | PUMP OUT PIT DETAIL | 3 |
| W-02 | GROUND FLOOR PLAN | 3 |
| W-02A | OSD PLAN AND SECTION | 3 |
| W-03 | EROSION & SEDIMENT CONTROL PLAN | 3 |
| | | |


W-03A | EROSION & SEDIMENT CONTROL DETAIL |


| 3 | S.U | 30/03/23 | H.N | 30/03/23 | RE-ISSUED FOR DA |
|------|------|----------|------|----------|------------------|
| 2 | S.U | 22/12/22 | H.N | 22/12/22 | ISSUED FOR DA |
| 1 | S.U | 20/12/22 | H.N | 20/12/22 | ISSUED FOR DA |
| REV. | DES. | DATE | VER. | DATE | DESCRIPTION |
| | | | | | |


ADDRESS: Suite 1, Level 2, 96 Phillip St, Parramatta NSW 2150 PHONE: 9635 9890



| DESIGNED | S.U | 30/03/2023 | ADDRESS | 78-80A BENAR | OON RD, | LAKEM | ВА | |
|-------------|-------|--|-------------|--------------|-------------|-------|----------|---|
| VERIFIED | H. N. | 30/03/2023 | SHEET TITLE | I FOEND 8 NO |)TEO | | | |
| DRAWN | S.U | SCALE @ A1 NTS | | LEGEND & NO | JIES | | | |
| PART OF THI | | GHT OF HORIZON ENGINEERS PTY. LTD. NO E REPRODUCED OR USED WITHOUT PRIOR RS PTY 1 TD | PROJECT NO. | 22235-W | DRAWING NO. | W-00 | REVISION | 3 |







| | 3 | S.U | 30/03/23 | H.N | 30/03/23 | RE-ISSUED FOR DA |
|---|-----|------|----------|------|----------|------------------|
| | 2 | S.U | 22/12/22 | H.N | 22/12/22 | ISSUED FOR DA |
| | 1 | S.U | 20/12/22 | H.N | 20/12/22 | ISSUED FOR DA |
| R | EV. | DES. | DATE | VER. | DATE | DESCRIPTION |


ADDRESS: Suite 1, Level 2, 96 Phillip St, Parramatta NSW 2150 PHONE: 9635 9890

WEBSITE: www.horizonengineers.com.au E-MAIL: info@horizonengineers.com.au



| DESIGNED | S.U | 30/03/2023 | ADDRESS | 78-80A BENAR | OON RD, | LAKEM | ВА | |
|--------------|-------|------------------------------------|-------------|--------------|-------------|-------|----------|---|
| VERIFIED | H. N. | 30/03/2023 | SHEET TITLE | DACEMENT D | I ANI | | | |
| | S.U | SCALE @ A1 1:100 | | BASEMENT P | LAN | | | |
| PART OF THIS | | TELLING COED ON COED WITHOUT THICK | PROJECT NO. | 22235-W | DRAWING NO. | W-01 | REVISION | 3 |

STREET



GALVANISED HEAVY DUTY GRATED ACCESS COVER AND FRAME RL 24.10 STEP IRON 300 CENTERS-@ ALL ACCESS POINTS **RISING MAIN** BOTH PUMPS ON TWL RL 23.26 AND ALARM SOUND NON-RETURN VALVE & ISOLATING VALVE - INLET 100mm ABOVE TWL L: 4.0m W: 2.0m PUMP ON EFFECTIVE DEPTH: 1.0m EFFECTIVE VOLUME: 8.0 m³ PUMP OFF RL 22.28 BASE AND WALLS STORMWATER PUMPS DUTY TO STRUCTURAL 10L/s @ 6m HEAD **ENGINEERING DETAILS**

STORMWATER PUMP OUT PIT SECTION
SCALE 1:20

1 W01A

PUMP WELL DETAILS

DRIVEWAY AREA DRAINING TO SUMP = $96.85m^2$


SUMP SIZE BASED ON 100YR 2 HR STORM, I = 39.5 mm/hr Q = CIA/3600 = 1 x 96.85 x 39.5/3600 = 1.063 L/sec VOLUME REQUIRED = $1.063x2x60x60 = 7654 L = 7.66 m^3$ STORAGE PROVIDED $4.0 \times 2.0 \times 1.0 = 8.00 m^3$

PUMP OUT RATE BASED ON 100YR 5 MIN STORM, I = 213 mm/hr (MIN.RATE REQUIRED AS PER AS 3500.3 is 10 L/sec)

Q = CIA/3600 = 1 x 213 x 96.85/3600 = 5.730 L/sec

SCALE 1:20

DUAL KS-30 PUMP OR EQUIVALENT TO BE INSTALLED IN SUMP AND CONNECTED TO CONTROL PANEL WHICH WILL ALLOW FOR THE PUMPS TO OPERATE ALTERNATIVELY ON HIGH LEVEL ALARMS AT 10L/sec(PER PUMP) AT 6 m HEAD



| | Out | ·nut | 0 | tlet | Rat | ted | Maxi | imum | Weigh | | Dimension | |
|--------|-------|------|-----|--------|--------|---------|------|----------|--------|-------|-------------|-------|
| Туре | Out | .put | Ou | uet | Head C | apacity | Head | Capacity | vveign | | Difficusion | l |
| | HP | kW | mm | Inch | M | LPM | M | LPM | Kg | L(mm) | W(mm) | H(mm) |
| KS-03 | 1/3 | 0.25 | 40 | 1 1/2" | 3 | 130 | 8 | 180 | 9 | 188 | 141 | 305 |
| KS-04 | 1/2 | 0.4 | 50 | 2" | 5 | 150 | 8 | 220 | 11 | 208 | 140 | 359 |
| KS-05 | 1/2 | 0.4 | 50 | 2" | 5 | 160 | 10 | 260 | 14 | 230 | 156 | 375 |
| KS-08 | 1 | 0.75 | 50 | 2" | 6 | 240 | 13 | 380 | 21 | 290 | 180 | 425 |
| KS-20 | 2 | 1.5 | 80 | 3" | 10 | 300 | 16 | 600 | 31 | 278 | 182 | 475 |
| KS-30 | 3 | 2.2 | 80 | 3" | 10 | 500 | 18 | 800 | 42 | 390 | 250 | 450 |
| KS-50 | 5 | 3.7 | 100 | 4'' | 10 | 800 | 21 | 1100 | 48 | 450 | 240 | 530 |
| KS-75 | 7 1/2 | 5.6 | 100 | 4" | 15 | 800 | 23 | 1300 | 60 | 550 | 310 | 590 |
| KS-100 | 10 | 7.5 | 150 | 6" | 18 | 900 | 25 | 1600 | 70 | 550 | 310 | 610 |





| S.U | 30/03/23 | H.N | 30/03/23 | RE-ISSUED FOR DA |
|------|------------|------------------------------|--------------------------------------|--|
| S.U | 22/12/22 | H.N | 22/12/22 | ISSUED FOR DA |
| S.U | 20/12/22 | H.N | 20/12/22 | ISSUED FOR DA |
| DES. | DATE | VER. | DATE | DESCRIPTION |
| | S.U S.U | S.U 22/12/22 S.U 20/12/22 | S.U 22/12/22 H.N S.U 20/12/22 H.N | S.U 22/12/22 H.N 22/12/22 S.U 20/12/22 H.N 20/12/22 |


ADDRESS: Suite 1, Level 2, 96 Phillip St, Parramatta NSW 2150 PHONE: 9635 9890



| DESIGNED | S.U | 30/03/2023 | ADDRESS | 78-80A BENAR | OON RD, LAKEM | ВА | |
|--------------|-------|--|-------------|---------------|-------------------|----------|---|
| VERIFIED | H. N. | 30/03/2023 | SHEET TITLE | PUMP OUT TA | ANK DETAII | | |
| DRAWN | S.U | SCALE © A1 AS SHOWN | | PUIVIP OUT 17 | AINN DETAIL | | |
| PART OF THIS | | GHT OF HORIZON ENGINEERS PTY. LTD. NO E REPRODUCED OR USED WITHOUT PRIOR PS PTY LTD. | PROJECT NO. | 22235-W | DRAWING NO. W-01A | REVISION | 3 |








NOTE: 1. DOWNPIPE FROM ROOF TO BE DIRECTED TO OSD TANK VIA DIA.225mm INLET.


| 3 | S.U | 30/03/23 | H.N | 30/03/23 | RE-ISSUED FOR DA |
|------|------|----------|------|----------|------------------|
| 2 | S.U | 22/12/22 | H.N | 22/12/22 | ISSUED FOR DA |
| 1 | S.U | 20/12/22 | H.N | 20/12/22 | ISSUED FOR DA |
| REV. | DES. | DATE | VER. | DATE | DESCRIPTION |

ADDRESS: Suite 1, Level 2, 96 Phillip St, Parramatta NSW 2150 PHONE: 9635 9890

| (HOF | ZIZON / ENGINEERS |
|------|----------------------|
| | |

| DESIGNED | S.U | 30/03/2023 | ADDRESS | 78-80A BENAR | OON RD, LAKEM | ВА | |
|--------------|-------|------------------------------------|-------------|--------------|------------------|----------|---|
| VERIFIED | H. N. | 30/03/2023 | SHEET TITLE | | | | |
| | S.U | SCALE @ A1 1:100 | | GROUND FLO | OR PLAN | | |
| PART OF THIS | | TELLING COED ON COED WITHOUT THICK | PROJECT NO. | 22235-W | DRAWING NO. W-02 | REVISION | 3 |





OSD CALCULATION (DRAINS MODELING)

 $= 984.6 \text{m}^2$ TOTAL SITE AREA $= 820.8 \text{ m}^2$ IMPERVIOUS AREA $= 163.8 \text{ m}^3 (16.6\%)$ AREA BYPASSING OSD


OSD TANK

= 49.42m2AREA AV.WATER DEPTH = 0.393m


VOLUME PROVIDED = 19.42m^3 VOLUME REQUIRED = 18.10m3 (BY DRAINS)

ORIFICE DIAMETER = 114mm


THEREFORE, OSD VOLUME IS SATISFACTORY




ORIFICE PLATE DETAIL



MULTI PURPOSE FILTER SCREEN









ON SITE STORMWATER DETENTION WARNING SIGN

NOTES:

1. SIGN SHALL BE PLACED IN A CLEAR AND VISIBLE LOCATION AT EACH DETENTION BASIN.

- TRIANGLE AND "WARNING" RED FIGURE AND LETTERING - BLACK

 3. SIGN TO BE MADE FROM COLOUR BONDED ALUMINIUM OR
- POLYPROPYLENE. 4. SIGN FIXED USING HILTI CHEMSETS OR EXPOXY


| DRAWN S.U | SCALE @ A1 AS SHOWN |
|----------------|---------------------|
| VERIFIED H. N. | 30/03/2023 |
| DESIGNED S.U | 30/03/2023 |

THIS IS AN **ON-SITE STORMWATER DETENTION SYSTEM** REQUIRED BY BURWOOD CITY COUNCIL IT IS AN OFFENCE TO REDUCE THE VOLUME OF THE 80mm TANK OR BASIN OR TO INTERFERE WITH THE ORIFICE PLATE THAT CONTROLS THE OUTFLOW THE BASE OF THE OUTLET CONTROL PIT AND THE DEBRIS SCREEN MUST BE CLEANED OF DEBRIS AND SEDIMENT ON A REGULAR BASIS BY THE OWNER

NOTES:
1. CORNERS SQUARE 2. COLOURS: ETCHED AND FILLED BLACK LEDGEND ON A NATURAL SILVER BACKGROUND.
3. CONSTRUCTED FROM ALUMINIUM 0.9mm MILL. 4. THIS SIGN SHALL BE PLACED IN A VISIBLE LOCATION NEAR A DISCHARGE CONTROL PIT OR AT THE ACCESS TO ONE. 5. SIGN FIXED USING HILTI CHEMSETS OR EXPOXY

THIS PLATE MUST NOT BE REMOVED


| © THIS DRAWING AND DESIGN IS THE COPYRIC PART OF THIS DRAWING OR DESIGN SHALL BE WRITTEN CONSENT FROM HORIZON ENGINEED | E REPRODUCED OR USED WITHOUT PRIOR | PROJECT NO. | 22235-W | DRAWING NO. W-02A | REVISION | 3 |
|--|------------------------------------|-------------|---------------------------|-------------------|----------|---|
| DRAWN S.U | SCALE @ A1 AS SHOWN | | OSD TANK PLAN AND SECTION | | | |
| VERIFIED H. N. | 30/03/2023 | SHEET TITLE | | | | |
| DESIGNED S.U | 30/03/2023 | ADDRESS | 78-80A BENAR | OON RD, LAKEM | ВА | |




ADDRESS: Suite 1, Level 2, 96 Phillip St, Parramatta NSW 2150 PHONE: 9635 9890



HVE



| | | LEGEND |
|-----|--------|--|
| TAG | SYMBOL | DESCRIPTION |
| 1 | | SEDIMENT FENCE. REFER TO SD 6-8 FOR DETAIL ON SHEET W-06A. |
| 2 | | SHAKER GRID. REFER TO DETAIL. |
| 3 | | MATERIAL STOCKPILE, REFER TO SD 4-1 FOR DETAIL ON SHEET W-06A. |
| 4 | | TEMPORARY TOILET AND BIN |
| 5 | | GRAVEL AND MESH FILTER. REFER TO SD 6-11 FOR DETAIL ON SHEET W-06A |
| 6 | | OVERLAND FLOW |
| 7 | | STRAW BALE SEDIMENT FILTER. REFER TO DETAIL ON SHEET W-06A. |
| 8 | < | EARTH BANK (LOW FLOW). REFER TO SD 5-5 FOR DETAIL ON SHEET W-06A. |
| 9 | | GEOTEXTILE INLET FILTER. REFER TO SD 6-12 FOR DETAIL ON SHEET W-07A. |
| | | |





| 3 | S.U | 30/03/23 | H.N | 30/03/23 | RE-ISSUED FOR DA |
|-----|------|----------|------|----------|------------------|
| 2 | S.U | 22/12/22 | H.N | 22/12/22 | ISSUED FOR DA |
| 1 | S.U | 20/12/22 | H.N | 20/12/22 | ISSUED FOR DA |
| REV | DES. | DATE | VER. | DATE | DESCRIPTION |

ADDRESS: Suite 1, Level 2, 96 Phillip St, Parramatta NSW 2150 PHONE: 9635 9890



| DESIGNED S.U | DATE 30/03/2023 | ADDRESS 78-80A BENAROON RD, LAKEMBA SHEET TITLE FROM CONTROL DIANI | | | |
|----------------|--|---|--|--|--|
| VERIFIED H. N. | DATE 30/03/2023 | | | | |
| DRAWN S.U | SCALE @ A1 1:100 | EROSION & SEDIMENT CONTROL PLAN | | | |
| | THE COPYRIGHT OF HORIZON ENGINEERS PTY. LTD. NO N SHALL BE REPRODUCED OR USED WITHOUT PRIOR N ENGINEERS PTY LTD. | PROJECT NO. 22235-W DRAWING NO. W-03 REVISION 3 | | | |






SEDIMENT FENCE

SD 6-8


MANUFACTURER.

6. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150 MM OVERLAP.




MESH AND GRAVEL FILTER


SD 6-11




GEOTEXTILE INLET FILTER

SD 6-12







| 3 | S.U | 30/03/23 | H.N | 30/03/23 | RE-ISSUED FOR DA |
|------|------|----------|------|----------|------------------|
| 2 | S.U | 22/12/22 | H.N | 22/12/22 | ISSUED FOR DA |
| 1 | S.U | 20/12/22 | H.N | 20/12/22 | ISSUED FOR DA |
| REV. | DES. | DATE | VER. | DATE | DESCRIPTION |

ADDRESS: Suite 1, Level 2, 96 Phillip St, Parramatta NSW 2150 PHONE: 9635 9890



| | DESIGNED S.U | | 30/03/2023 | ADDRESS | 78-80A BENAR(| OON RD, L | .AKEMI | 3 A | |
|--|--|--|----------------|-----------------------------------|----------------------|---------------|--------|----------|---|
| | VERIFIED H. N. | | 30/03/2023 | EROSION & SEDIMENT CONTROL DETAIL | | | | | |
| | DRAWN S.U | | SCALE @ A1 NTS | EROSION & SEDIMENT CONTROL DETAIL | | | | | |
| | © THIS DRAWING AND DESIGN IS THE COPYRIGHT OF HORIZON ENGINEERS PTY. LTD. NO PART OF THIS DRAWING OR DESIGN SHALL BE REPRODUCED OR USED WITHOUT PRIOR WRITTEN CONSENT FROM HORIZON ENGINEERS PTY. LTD. | | | PROJECT NO | [.] 22235-W | DRAWING NO. V | V-03A | REVISION | 3 |