Transcivic
Engineering

rimanw@yahoo.com.au

ABN 60 674 378 042 2 Vulcan Street, Guildford NSW 2161

Structural Report for the unauthorised work At 2/22 Warwick Street, Punchbowl

DATE:19/3/2022

PREPARED BY: WISSAM T. RIMAN

Senior Civil/Structural Engineer BSc (civil/structural) MIEAust. 560160 Mob: 0414381056

Introduction

Called to the property to inspect the new additional structures

Purpose

The purpose of this inspection is to provide the structural adequacy certificate for the Building Certificate

Inspection


The inspection was carried out on the 19th March 2022

The weather at the time was *sunny*.


Photographs were taken on the day of the inspection and have been included in this report.

Methodology


This report is based on a visual inspection only. No core drilling, testing or structural sampling has been carried out.



There is no bracing for the new brick work to the existing brick walls




Stormwater is connected to the existing




Single brick wall

Either a brick veneer or double brick or single engaged piers wall to be applied




Engaged pier are missing to tie up the corner





Strap for up lift wind pressure on each rafter

Engaged piers are missing



Missing Strap from brick pier to top plate as per AS1170

Conclusion

Main major Issues are:

- Brick wall to be up graded to brick veneer,
 Double brick or to single engaged piers wall.
- Missing straps from six coarse brick to the top plate for up lift pressure case.
- A certificate to be issued after the major rectifications done.

Storm water is adequate as it was connected to the existing stormwater pit. (certificate will be provided).

If you have any queries please contact undersigned

W. T. RIMAN

Senior Civil/Structural Engineer BSc (civil/structural) MIE Aust 560160