


2 Sunpath Analysis

1 : 500

Area Schedule	
Name	Area
Unit 1	
Alfresco	19.77 m ²
Balcony	12.11 m ²
Driveway	19.50 m ²
First Floor	71.33 m ²
Garage	16.53 m ²
Ground Floor	67.55 m ²
Landscape	133.45 m ²
Porch	6.68 m ²
POS	119.03 m ²
Site Area	278.47 m ²
Unit 2	
Alfresco	19.77 m ²
Balcony	10.08 m ²
Driveway	19.50 m ²
First Floor	71.33 m ²
Garage	15.93 m ²
Ground Floor	67.55 m ²
Landscape	132.70 m ²
Porch	6.68 m ²
POS	119.03 m ²
Site Area	278.47 m ²
Unit 1 Total TFA	138.88 m ²
Unit 1 FSR	0.50
Unit 2 Total TFA	138.88 m ²
Unit 2 FSR	0.50

NOTES AND SPECIFICATION


- These drawings are to be read in conjunction with the architectural drawings, structural drawings, and the specification.
- Prior to commencement of works the contractor shall satisfy himself of the correct location of existing services whether indicated or not on the plans. Any damage to existing services shall be rectified at the contractor's expense.
- Traffic management measures have to be implemented and maintained during construction, all in accordance with Council's requirements. The contractor shall maintain safe pedestrian access along the footpath.
- The contractor shall effect temporary drainage measures to avoid localised ponding of surface run-off.
- Refer to architect's drawings for all details (levels, grading, etc.) of driveways, concrete and paved areas, and retaining wall types and locations.
- Refer to landscape architect's drawings for details and extent of all landscaped areas.
- All SWD pipes are UPVC at 1.0% minimum grade.
- SWD pits can be pre-cast sized as follows: 450mm sq. up to 600mm deep 600mm sq. up to 1000mm deep
- All pits located in trafficable areas, (ie, driveways) to have medium-duty grated covers suitable for withstanding loads associated with small trucks.
- Provide step irons to all pits greater than 1.2m deep.
- The contractor shall implement all soil erosion and sediment control measures prior to commencement of works.
- Topsoil shall be stripped dn stockpile outside hazard areas such as drainage lines. This topsoil is to be respread later on are as to be revegetated.
- The contractor shall regularly maintain all sediment and erosion control devices and remove accumulated silt from such devices. All silt removed shall be disposed of as directed by the superintendent. The period for maintaining these devices shall be at least until all disturbed areas are revegetated and further as may be directed by the superintendent or Council.
- The contractor shall maintain dust control until final completion of works



Mahn Design © COPYRIGHT Reproduction of the whole or part of the document constitutes and infringes copyright. The information, ideas and concepts contained in this document is/are confidential. The recipient(s) of this document is/are prohibited from disclosing such information ideas and concepts to any person without prior written consent of the copyright holder. Contractor to check and verify all levels, datums & dimensions on site and shall report any discrepancies or omissions to this office prior to start of work & during the construction phase. This drawing is to be read and understood in conjunction with structural, mechanical, electrical and or any other consultant's documentation as may be applicable to the project prior to start of work & it's duration. Measurement scaling of this drawing shall only be permitted in its digital form.

REV	DATE	DESCRIPTION	INITIAL
A	06.11.23	Issued for Development Application	E.T.

DRAWING TITLE: Site Plan
DRAWN BY: E.T.
CHECKED BY: S.D.
LOT: 444 | **SEC:** | **DP:** 35899



SITE ADDRESS: 18 Treuer Parade, Yagoona NSW 2199
CLIENT: Ahmad AbdulWahed
PROJECT TYPE: Demolition of all existing improvements and construction of an Attached Dual Occupancy
DATE: Issue Date **REV:** A **SHEET NO:** A109
COUNCIL AREA: **SCALE:** As indicated

MAHN DESIGN ACCREDITED BUILDING DESIGNER
Suite 4/259 Northumberland St, Liverpool NSW 2170, Australia
Ph: 02 8319 9447 | info@mahn.com.au | www.mahn.com.au
PROJECT NO: 0001