REF: 6352WW VERSION [1.0] OCTOBER 19, 2023



SOIL AND SITE ASSESSMENT FOR ONSITE WASTEWATER DISPOSAL

759 Oura Road, Eunanoreenya, NSW

LGA: Wagga-Wagga

Lot 3 DP 751405

Owner: Scouts NSW

HARRIS ENVIRONMENTAL CONSULTING 6/1 MEMORIAL DRIVE, SHELLHARBOUR CBD, 2529 TEL: (02) 4236 0954

info@hec.eco

VERSION CONTROL

Title	Soil and Site	Soil and Site Assessment for Onsite Wastewater Disposal					
Site address	759 Oura Ro	759 Oura Road, Eunanoreenya, NSW					
Proposed development	Proposed ca	Proposed campsite upgrade					
Created By	Katherine Ro	ose Kilpatrick B. Sci (Geology) (UOW)					
Approved by:	Sean Harris	Msc Env Science (UOW), Grad dip Nat Res (UNE), BscAppSc, Agricultur	re (HAC)			
Date Created	Tuesday, 3 C	Tuesday, 3 October 2023					
Version Number	Modified By	Modifications Made	Date Modified	Status			
[0.1]	K.K.	Issue for client review	13/10/2023	Draft			
[1.0]	K.K.	Issue for client review	19/10/2023	Complete			

Limitations

The findings and recommendations in this report are based on the objectives and scope of work outlined above. Harris Environmental Consulting performed the services in a manner consistent with the normal level of care and expertise exercised by members of the environmental assessment profession. The report and conclusions are based on the information obtained at the time of the assessment. Changes to the site conditions may occur subsequent to the investigation described herein, through natural processes or through the intentional or accidental addition of contaminants, and these conditions may change with space and time. The results of this assessment are based upon site assessment conducted by HEC personnel and information provided by the client and site management. All conclusions regarding the property are the professional opinions of the HEC personnel involved with the project, subject to the qualifications made above. While normal assessments of data reliability have been made, HEC assumes no responsibility or liability for errors in any data obtained from regulatory agencies, information from sources outside of HEC, or developments resulting from situations outside the scope of this project.

Copyright

© Harris Environmental Consulting 2023

This report and accompanying plans were prepared for the exclusive use of Scouts NSW. No extract of text of this document may be reproduced, stored or transmitted in any form without the prior consent of Harris Environmental Consulting Pty. Plans accompanying this document may not be reproduced, stored or transmitted in any form unless this copyright note is included.

TABLE OF CONTENTS

1.	INT	RODUCTION	4
2.	PRO	OJECT DETAILS	5
3.	SIT	E INFORMATION	5
4.	SU	MMARY OF SOIL AND SITE CONSTRAINTS	9
5.	EXI	ISTING WASTEWATER INFRASTRUCTURE	9
6.	SYS	STEM DESIGN	
	5.1	Required capacity of a septic tank	
	5.2	OUTLET FILTER	
	5.3	Pipes	
7.		ING OF SOIL ABSORPTION BEDS	
8. 9.		MMARY FERENCES	
		FIGURES	
Fi	gure	Location of Property	.4
Fi	gure	2 Distribution box	14
		TABLES	
		IADLLO	
Ta	able 1	1 All waste septic tank operational capacities	10
Ta	able 2	2 Septic Tank Sizing for Different Source Locations	10
Ta	able 3	3 Minimum pipe diameter and grade calculations	12
Ta	able 4		
Ta	able 5	5 Dimensions for constructing soil absorption bed	13

APPENDICES

Appendix i	Flow Balancing Sheet	. 16
Appendix ii	Construction Of Soil Absorption Beds	. 18
Appendix iii	General Recommendations To Manage Water Quality And Quantity	.20
Appendix iv	Required Buffers	.21
Appendix v	Standard Drawing 9A - Upslope Diversion Drain	.23
Appendix vi	SITE PLAN - Sheet 1	. 24
Appendix vii	SITE PLAN - Sheet 2	. 25
Appendix viii	SITE PLAN - Sheet 3	. 26
Appendix ix	SITE PLAN - Sheet 4	. 27
Appendix x	SITE PLAN - Sheet 5	. 28
Appendix xi	SITE PLAN - Sheet 6	. 29
Appendix xii	STANDARD DRAWING Soil Absorption Beds	.30

1. INTRODUCTION

This Site and Soil Assessment for On-site Wastewater Management was prepared by Harris Environmental Consulting at the request of Scouts NSW. It relates to the proposed development to the campsite on Lot 3 DP 751405 at 759 Oura Road, Eunanoreenya, NSW.


Fieldwork was undertaken by Harris Environmental Consulting (HEC) on 12th September 2023. This plan is based on the primary investigation of the soils, topography and hydrology of the site observed on the day of inspection. Soil samples and photos of the site were taken for further analysis. This assessment was undertaken for a proposal to install 4 new septic tanks and retain 1 septic tank for wastewater treatment and the installation of 4 new soil absorption beds for wastewater disposal.

The assessment was prepared to assess compliance with related requirements described in:

- Wagga Wagga Development Control Plan (2010)
- Local Government Act 1993
- Australian Standard AS/NZS 3500 Plumbing and Drainage 2018
- Environment and Health Protection Guidelines (1998) On-site Sewage Management for Single Households (Department of Local Government)
- AS/NZ 1547:2012 On-site wastewater management (Standards Australia, 2012)
- Sydney Catchment Authority Neutral or Beneficial Effect (NorBE) on Water Quality Assessment Guideline (2011)

The location of the property is shown in Figure 1

FIGURE 1 LOCATION OF PROPERTY



Source: NSW Sixmaps

2. PROJECT DETAILS

6352WW					
Scouts NSW					
759 Oura Road, Eunanoreenya, NSW					
~13.2 ha					
Wagga-Wagga					
Tank					
No. of visitors per fortnight	100-200				
Expected Friday - Sunday					
Decision Montaverton = 5,900L -					
Design wastewater Generation	11,800L/day				
Daily Treatment Volume	3200L/day				
Septic tank	1				
Soil absorption bed					
12 September 2023					
13 October 2023					
Katherine Rose Kilpatrick B. Sci (Geology) (UOW)					
Msc Env Science (UOW), Gra BscAppSc, Agriculture (HAC)					
	Scouts NSW P: 0403 766 132 E: paul.mcintyre@nsw.scouts.com.au Lot 3 DP 751405 759 Oura Road, Eunanoreenya, NSW ~13.2 ha Wagga-Wagga Tank No. of visitors per fortnight Expected Friday - Sunday Design Wastewater Generation Daily Treatment Volume Septic tank Soil absorption bed 12 September 2023 13 October 2023 Katherine Rose Kilpatrick B. Sci (Geology) (U				

3. SITE INFORMATION

Method:	Mechanical augur/crowbar/shovel
Depth to bedrock (m):	1000mm to restrictive layer; minor limitation
Depth to high soil	No groundwater or subsoil mottling encountered at a depth of
watertable:	1000mm; minor limitation
Slope (%):	1-2 % Slope, minor limitation
Coarse (%):	No coarse rock fragments in subsoil, minor limitation
pH (soil/water):	pH 5.5-6; minor limitation
Electrical conductivity:	<4dSm, minor limitation
Salinity hazard:	No evidence of salinity was observed in area of existing soil
	absorption bed or within immediate vicinity; minor limitation
Domestic groundwater	The Department of Primary Industries Office of Water search of
use:	groundwater bores found there is no known groundwater bores
	within 100m of the proposed effluent management area.
Native vegetation and	No native vegetation or environmentally sensitive vegetation within
environmentally	1m of the proposed EMA.
sensitive vegetation	
Geological Unit	Alluvium 38485 – Channel and floodplain alluvium; gravel, sand, silt,
(From Geoscience	clay; may be locally calcreted.
Australia Portal)	
Soil Landscapes	Kurrajong Plain – moderately deep (80 – 150 cm) Eutrophic Brown
(From eSPADE by NSW	Dermosols and Eutrophic Brown Kandosols.
DPIE):	

Surface rock:	No surface rock in the proposed effluent management area						
Bulk density:	Moderate to well	Moderate to well-drained soil profile; minor limitation					
Soil profile, from two		Layer 1	DLR				
similar soil profiles in	Texture	Loam					
EMA:	Colour	Dark Brown					
	Depth	0-100mm	N/A				
	Structure	Moderately Structured					
	Coarse frag. N/A						
		DLR					
	Texture	Clay Loam					
	Colour	Brown					
	Depth	100-1000mm	10 mm/day				
	Structure	Moderately structured					
	Coarse frag.	N/A					

Photo 1 Onsite Soil Assessment.



Photo 2 Location of proposed soil absorption beds.



Photo 3 Location of proposed soil absorption beds (secondary view).



Photo 4 Existing septic tank located near northern amenities to be retained and refurbished.



Photo 5 Existing holding tank with a capacity of ~43,320L.



4. SUMMARY OF SOIL AND SITE CONSTRAINTS

There are no major soil or site constraints that would prevent the installation of new septic tanks and retention of one existing septic tank for wastewater treatment and soil absorption beds for wastewater disposal for the proposed development.

The proposed location of the new soil absorption beds is heavily vegetated and will need to be cleared to provide at least a 1m buffer around the proposed beds. Should the existing disposal area (to become reserve area) ever need to be used, the vegetation will need to be cleared.

This location for disposal has been chosen because it the highest point on the property and is a distance from land that will be used for camp sites and recreation. Furthermore, the existing wastewater infrastructure is located nearby to this proposed area and this assessment recommends the continued use of some of the infrastructure.

The proposed soil absorption beds are at a location that is compliant with the buffers and setback distances required by Wagga-Wagga Council and Water NSW. This includes:

- More than 100m from permanent watercourses, 40m from drainage depressions and dams
- 6m from downslope driveways/boundary lines
- 3m from upslope driveways/ boundary lines
- 6m from downslope buildings and 2m from upslope buildings

The clay loam subsoil has suitable permeability and nutrient absorption properties for this method of wastewater treatment and disposal.

5. EXISTING WASTEWATER INFRASTRUCTURE

On site at 759 Oura Road, Eunanoreenya, there are multiple pieces of wastewater infrastructure already installed and operational. These pieces include:

- 43,320L black holding tank located in the northwest of the property, north of the maintenance buildings.
- 1 septic tank and pumpwell located near the northern amenities.
- 1 septic tank and pumpwell located near the existing accommodation building, on the eastern side.
- 1 septic tank and pumpwell located near the existing amenities and office building on the western side.
- Existing ~30m long trench north of the existing holding tank

The existing trench is to be retained for reserve effluent disposal, in the event there is a power or pump failure that prevents the new beds from operating, and temporary relief is necessary. The new wastewater disposal area will be located east of this trench.

The septic tank and pumpwell located near the existing office and amenities block will be decommissioned, whereas the septic tank and pumpwell near the existing accommodation block can either be decommissioned or used as a junction for all southern pipework to merge before pumping north to the existing 43,320L holding tank.

6. SYSTEM DESIGN

6.1 REQUIRED CAPACITY OF A SEPTIC TANK

Septic tanks are to be sized in accordance with NSW Health Septic Tank and Collection Well Accreditation Guidelines (December 2001) Annexure 3:6-calculations 'Camping Grounds and/or Caravan Parks', as shown in Table 1.

TABLE 1 ALL WASTE SEPTIC TANK OPERATIONAL CAPACITIES

0	MD what had	07	4.10.000.007	5 Feet description
Camping Grounds	WC, urinal, basin	27	4 x No. of Sites x 27	Estimate 4 persons/site/day
and/or	WC, urinal, basin, kitchen	32	4 x No. of Sites x 32	A THE STATE OF THE
Caravan Parks	WC, urinal, basin, kitchen, & showers WC, urinal, basin,	59	4 x No. of Sites x 59	Septc tank capacity = daily flow + 1550 Litres
	kitchen, showers, & laundry	86	4 x No. of Sites x 86	

Septic Tank and Collection Well Accreditation Guideline December 2001 - Page 16

For the proposed development, numerous septic tanks are required to manage the effluent being generated around the campsite. The use of a septic tank and pumpwell at each effluent source will allow for the treatment of effluent before pumping the wastewater to the main existing holding tank. Table 2 explores the required size of each septic tank at each source, stating the minimum volume of the tank.

TABLE 2 SEPTIC TANK SIZING FOR DIFFERENT SOURCE LOCATIONS

	Section 1 - Northern	Section 2 - Southern	Section 3 - Duty Manager Cottage	Section 4 - Conference	Section 5 - Accommodation	Section 6 - Merritt Building
	Amenities	Amenities	0 0	Room	Cabins	5
Assumed WW Load (L)	-	-	59	27	59	59
People	-	-	2	138	60	16
Toilets	8	8	1	6	24	1
Showers	4	4	1	-	14	1
Septic Tank Calculations (L)				3,726	3,540	944
Sludge Allowance (L)	1,550	1,550	1,550	1,820	1,550	1,550
Minimum Septic Tank Size(L)	3,000	3,000	1,668	5,546	5,090	2,494
						6,034

From the above table, the septic tanks located near the northern amenities, southern amenities, Duty Manager Cottage, and the Merritt Buildings will need a 3000L minimum-sized tank. The Conference Room and Accommodation Cabins will require a septic tank of a minimum size of 5,600L. Furthermore, due to the close proximity of the Accommodation Hall and Merritt Buildings, if found to be preferable, only 1 septic tank and pumpwell may be installed to service the buildings. This source would require a 6,500L septic tank to service the 2 buildings, as seen in Table 2.

However, this assessment recommends each new septic tank be oversized to 10,000L to allow for surge capacity, as the usage of each amenities block can vary. All new and existing tanks should be fitted with alarms, that are both visual and audible, and that sound at 80% capacity.

With each new septic tank, an associated pumpwell is required to be installed to collect and transfer the treated effluent to the existing holding tank. Any existing septic tanks and pumps will need to be connected to the existing holding tank, if not already connected.

The collection/pump wells shall be fitted with a submersible vortex pump that pumps treated effluent to the disposal area when triggered by a float switch, with the installer to decide the

specifications of the required pumps, so as to be site-specific. NSW Health requires any pumpwell (also known as a collection tank) to be of a minimum capacity of 2000 litres. In the case of the septic tank and pumpwell being installed as separate units, the float switch will operate when the volume of wastewater in the tank reaches a certain volume. The installing plumber is to decide this volume, as to be site-specific. Should the pumpwell and septic tank be constructed as a single unit, this requirement may be unnecessary, given its purpose is to ensure the tank remains bedded.

The existing septic tank and pumpwell located near the northern amenities may be retained for wastewater treatment, conditional on the existing system being found in good working order.

The location of any new treatment system is to be located downslope of the source buildings. However, please note:

- The exact location of the septic tank is to be decided by the installer in consultation with the property owner.
- It is to be at least 1.5m from any building.
- Shall be located above the 1% AEP (1:100) flood contour.

6.2 OUTLET FILTER

An effluent filter is to be installed at the outlet of the septic tank.

- Outlet filters reduce TSS and BOD which are known to be the key factors in clogging soil-based absorption systems and resulting in hydraulic failure.
- Septic tank outlet filters provide a warning as to when maintenance of the system is required and involve the user in the oversight and maintenance of their systems.
- Manufacturers include Taylex, Everhard, XtraTreat, OSI FTi, Biotube, and Zoeller WW.

6.3 PIPES

The sewer pipes between the plumbing amenities, treatment system, and effluent disposal area must conform with 'AS/NZS 3500(Set):2018 Plumbing and Drainage Set' specifying the nominal pipe sizes and respective minimum grades. Table 3 contains these specifications.

In addition, where a sewer carrying untreated wastewater to a treatment system is longer than 60 metres, the minimum grade should be doubled, and inspection ports should be installed at least every 30 metres or at an angle or change of grade.

The sewer pipes between the plumbing amenities, septic tank, and effluent disposal area must be buried at a depth that provides protection against mechanical damage or deformation, in accordance with 'AS/NZS 3500(Set):2018 Plumbing and Drainage Set'. Table 4 shows the minimum pipe depth for trafficable areas.

TABLE 3 MINIMUM PIPE DIAMETER AND GRADE CALCULATIONS

Nominal pipe size (DN)	Minimum grade %	Minimum grade ratio
65	2.5	1:40
80	1.65	1:60
100	1.65*	1:60
125	1.25	1:80
150	1.00	1:100

^{*} Except for drains from septic tanks, sewage treatment plants and unvented discharge pipes from tundishes, which may have a minimum grade of 1%,

TABLE 4 MINIMUM PIPE DEPTH FOR TRAFFICABLE AREAS

Location	Minimum depth of cover (mm) for all materials other than cast iron
Where subject to vehicular traffic	500
Elsewhere	300
Source: 'AS/NZS 3500 (Parts 0-4):2018 Plumbing and drainage	ge Set'. Table 3.7.2 Minimum Cover for Buried Pipes'

Upon installation, if the installing plumber identifies a more efficient, site-specific means of installing the above-mentioned wastewater management systems and pipework, they may do so providing it meets all standards and required Council Guidelines, and tanks maintain their required capacities, as outlined in this report.

Source: 'AS/NZS 3500.2:2018 Plumbing and drainage Part 2 Sanitary plumbing and drainage' Table 3.4.1. NB: pipe grades are expressed as a percentage of vertical to horizontal distances.

7. SIZING OF SOIL ABSORPTION BEDS

The effluent disposal area will need to be sized for such a volume that the exiting holding tank is emptied before ethe following fortnights visitors. Appendix I shows a balance sheet that includes these calculations for differing event number and durations. Visitor numbers shown represent the capacity of the system. From the flow balancing, **the daily treatment volume has been calculated at 3,200L/day.**

The soil absorption bed can be constructed within the range of widths and depths shown in Table 5 (ASNZ1547, 2012). The bed can be no deeper than 600mm and no wider than 4m. For this site, the proposed base of the bed is 450mm below the ground surface (300mm aggregate and 150mm topsoil).

TABLE 5 DIMENSIONS FOR CONSTRUCTING SOIL ABSORPTION BED

	Typical dimensions (mm)	Maximum (mm)	Minimum (mm)			
Width	1000-4000	4000	1000			
Depth of aggregate	300-600	600	300			
Depth of topsoil	100-150	150	100			
Spacing between adjacent beds - NA 1000						
Source: 'AS/NZS 1547:2012 On-site domestic wastewater management						

The size of the soil absorption bed is calculated using the formulae in AS/NZ 1547(2012). It is based on design flow rate, design width, and Design Loading Rate (DLR), which is the amount of effluent that, over the long-term, be applied each day per area of an infiltrative surface without failure of the infiltrative surface. ASNZ1547(2012) recommends a DLR of 10mm/day for clay loam soils, receiving primary treated effluent.

The AS/NZ1547(2012) method for calculating bed size is as follows:

$$L = \frac{Q}{DLR \times W}$$

Where

L = Length in m

Q = Design daily flow in L/day (3200L/day)

W = Width in m (4m)

DLR = Design Loading Rate in mm/d (10mm/day)

Based on the above formulae and assumptions described in this report, the soil absorption beds must be 20m long, or 80m² each, with 4 beds being installed, for a total area of 320m².

page | 13

7.1 DISTRIBUTION BOX

A splitter distribution box is required to provide an even flow to each bed. Splitter boxes should be checked as part of performance monitoring inspections to confirm that an even flow of effluent is being directed to each distribution line. An example of a splitter box is shown in Figure 2.

FIGURE 2 DISTRIBUTION BOX





8. SUMMARY

The assessment was prepared for the proposed Camp Kurrajong developments. This assessment recommends the following:

- The installation of 4 new septic tanks and pumpwells, sized accordingly for the associated source building, as described in this report, and shown in site plans.
- Retention of the existing septic tank and pumpwell located near the northern amenities, if found to be in good working order.
- Retention of the existing 43,320L holding tank as a collection well for all treated effluent before disposal.
- This holding tank will transfer 3,200L/day to the absorption beds.
- Installation of 320m² of soil absorption bed as four (4), 20m long x 4m wide beds, as described in the Appendix and shown on the Site Plan.
- The beds need to receive a proportionate distribution of wastewater, which can be achieved manually using gate valves or similar.
- Retention of the existing trench for reserve effluent disposal in the event the primary system fails.

page | 14

9. REFERENCES

Department of Local Government (1998) On-site Sewage Management for Single *Households*. NSW Government.

Standards Australia (2012) Australian/New Zealand Standard 1547:2012 *On-site* domestic wastewater management. Standards Australia.

NSW Health Septic Tank Accreditation Guidelines (2001).

Hazelton, P.A and Murphy, B.W ed. (1992) What Do All the Numbers Mean? A Guide for the Interpretation of Soil Test Results. Department of Conservation and Land Management (incorporating the Soil Conservation Service of NSW), Sydney.

Sydney Catchment Authority Neutral or Beneficial Effect on Water Quality Assessment Guideline (2011).

Designing and Installing On Site Wastewater Systems. A Sydney Catchment Authority Current Recommended Practice (May 2012).

page | 15

APPENDIX I FLOW BALANCING SHEET

		beds = 59L		Total Occpancy		Volume (L)	Daily Net Change in Volume (L)	(
Week 1	Monday	0	0	0	0	3200		C
	Tuesday	0	0	0		3200		
	Wednesday	0	0	0	0	3200		(
	Thursday Friday	120	80	200	11800	3200 3200		8600
	Saturday	120	80	200		3200		17200
	Sunday	120	80	200	11800	3200		25800
Week 2	Monday	0	0	0		3200		22600
WCCK 2	Tuesday	0	0	0		3200		19400
	Wednesday	0	0	0		3200		16200
	Thursday	0	0	0	0			13000
	Friday	0	0	0	0	3200	-3200	9800
	Saturday	0	0	0	0	3200	-3200	6600
	Sunday	0	0	0	0	3200	-3200	3400
Week 3	Monday	0	0	0	0	3200	-3200	200
	Tuesday	0	0	0	0	3200	-3200	0
	Wednesday	0	0	0	0	3200	-3200	0
	Thursday	0	0	0		3200		0
	Friday	100	0	100	5900	3200		2700
	Saturday	100	0	100	5900	3200		5400
	Sunday	100	0	100	5900	3200		8100
Week 4	Monday	100	0		5900	3200		10800
	Tuesday	100	0		5900	3200		13500
	Wednesday	100 100	0	100 100	5900 5900	3200 3200		16200 18900
	Thursday Friday	100	0	100	5900	3200		21600
	Saturday	100	0	100	5900	3200		24300
	Sunday	100	0	100	5900	3200		27000
Week 5	Monday	100	0		5900	3200		29700
WCCK 5	Tuesday	100	0		5900	3200		32400
	Wednesday	100	0		5900	3200		35100
	Thursday	100	0		5900	3200		37800
	Friday	100	0	100	5900	3200		40500
	Saturday	100	0	100	5900	3200	2700	43200
	Sunday	0	0	0	0	3200	-3200	40000
Week 6	Monday	0	0	0	0	3200	-3200	36800
	Tuesday	0	0	0	0	3200	-3200	33600
	Wednesday	0	0				-3200	30400
	Thursday	0	0	0			-3200	27200
	Friday	0	0	0				24000
	Saturday	0	0	0	0	3200	-3200	20800

Week 7	Monday	0	0	0	0	3200	-3200	14400
	Tuesday	0	0	0	0	3200	-3200	11200
	Wednesday	0	0	0	0	3200	-3200	8000
	Thursday	0	0	0	0	3200	-3200	4800
	Friday	0	0	0	0	3200	-3200	1600
	Saturday	0	0	0	0	3200	-3200	0
	Sunday	0	0	0	0	3200	-3200	0
Week 8	Monday	0	0	0	0	3200	-3200	0
	Tuesday	0	0	0	0	3200	-3200	0
	Wednesday	0	0	0	0	3200	-3200	0
	Thursday	0	0	0	0	3200	-3200	0
	Friday	0	0	0	0	3200	-3200	0
	Saturday	0	0	0	0	3200	-3200	0
	Sunday	0	0	0	0	3200	-3200	0
Week 9	Monday	0	0	0	0	3200	-3200	0
	Tuesday	0	0	0	0	3200	-3200	0
	Wednesday	0	0	0	0	3200	-3200	0
	Thursday	0	0	0	0	3200	-3200	0
	Friday	120	80	200	11800	3200	8600	8600
	Saturday	120	80	200	11800	3200	8600	17200
	Sunday	120	80	200	11800	3200	8600	25800
Week 10	Monday	0	0	0	0	3200	-3200	22600
	Tuesday	0	0	0	0	3200	-3200	19400
	Wednesday	0	0	0	0	3200	-3200	16200
	Thursday	0	0	0	0	3200	-3200	13000
	Friday	0	0	0	0	3200	-3200	9800
	Saturday	0	0	0	0	3200	-3200	6600
	Sunday	0	0	0	0	3200	-3200	3400
Week 11	Monday	0	0	0	0	3200	-3200	200
	Tuesday	0	0	0	0	3200	-3200	0
	Wednesday	0	0	0	0	3200	-3200	0
	Thursday	0	0	0	0	3200	-3200	0
	Friday	100	0	100	5900	3200	2700	2700
	Saturday	100	0	100	5900	3200	2700	5400
	Sunday	100	0	100	5900	3200	2700	8100
Week 12	Monday	0	0	0	0	3200	-3200	4900
	Tuesday	0	0	0	0	3200	-3200	1700
	Wednesday	0	0	0	0	3200	-3200	0
	Thursday	0	0	0	0	3200	-3200	0
	Friday	0	0	0	0	3200	-3200	0
	Saturday	0	0	0	0	3200	-3200	0
	Sunday	0	0	0	0	3200	-3200	0

APPENDIX II CONSTRUCTION OF SOIL ABSORPTION BEDS

The following is a summary of construction notes from WaterNSW (2019) and should be read in conjunction with Standard Drawing attached. Refer to these documents if further clarification is required.

Step 1: Site Preparation

Obtain a copy of the council approved plans and conditions of consent. Accurately locate beds as shown on the site plans and according to the specified and approved design and/or any covenant. Check the location of all constructed beds against the approved site plans. If there is any change in their position from the site plans, a Section 96 application (from the *Environmental Planning and Assessment Act 1979*) must be made to the council to alter their position.

Step 2: Positioning

Build the beds along the contours and use laser leveling to ensure that the base is exactly level. If this does not happen, distribution will not be even and one part of the bed will be more heavily loaded. This could cause the most heavily loaded part of the bed to fail prematurely, with further creeping failure as the effluent is forced to more distant parts of the bed.

The basal area of the beds has been determined according to the procedures in AS/NZS 1547(2012) and WaterNSW (2019). This includes a minimum bed length to width ratio of 3:1, beds must be installed parallel to the site contours and beds must be of the same basal area if they are receiving the same volume of wastewater.

Always avoid cutting bed through existing weakened ground (e.g., through the alignments of former underground pipes, cables or conduits) as they may provide preferential pathways for the effluent to escape from the bed. If they cut downslope through the ground occupied by a series of bed, effluent may preferentially flow to the lowest bed causing it to fail or surcharge. Where it is unavoidable to cut into alignment or it happens accidentally, seal the weaknesses in the bed walls with cement or bentonite grout.

Step 3: Timing

Build beds during fine weather. If it rains before beds are completed, they should be covered to protect them from rain damage.

Once dug, complete the beds promptly to avoid foreign material being washed into the open bed. In particular, avoid puddling, where clay settles out at the bottom of a water filled trench exposed to rain, as clay settling on the base of the bed will reduce bed performance.



Step 4: Excavation

- Carefully excavate the base of any bed and level it with a dumpy or laser level. The
 bed must be level along and across the line of the bed. If there is a slope across the
 base of the bed, the effluent will drain to and preferentially load the downslope side of
 the bed, which may then fail or overflow.
- Where beds are dug along the contour on sloping ground by an excavator that does
 not have a pivoting bucket, the base of the bed will probably be cut parallel to the
 ground surface. In this case, the base of the bed will have a fall towards the downslope
 side. The bed should be further hand dug to level the base and stop excessive effluent
 accumulating against the downslope wall of the bed.
- Where beds are dug by excavator in clayey soils, any smearing of the bed walls and floor must be fixed by scarifying the surface.

Step 5 Construction

- Install arch drain (Reln) that complies with AS/NZS1547:2012.
- Ensure that the sides of beds are not damaged or caused to collapse when the beds are filled with gravel or sand.
- Beds can be filled with gravel (typically 20-40 millimetres).
- Lay geotextile filter cloth over the gravel and under the topsoil to ensure that the topsoil does not penetrate and block the bed.
- Test the beds with clean water before filling with gravel to ensure effective and even distribution of effluent.
- Apply 150 to 200 millimetres of topsoil to the top of the bed and leave it slightly
 mounded above ground level to allow it to settle and to encourage incident rainfall to
 be shed away from the top of the bed.
- The top of the absorption bed area should be turfed, or grass planted to establish vegetation cover promptly after construction. This ensures the best uptake of effluent by evapotranspiration. Ensure that larger deep-rooting plants are not planted close to bed to reduce the chance of root intrusion and clogging of the beds.
- A stormwater diversion berm/ drain should be built on sloping sites upslope of the absorption beds.

Step 6: Dosing

- Beds may be gravity-fed or pressure-dosed using pumps or dosing siphons. Raised pressure-dosed absorption beds are a possible alternative where there are shallow limiting layers present (e.g., bedrock, clay or water table) and not enough separation distance from that layer. The linear loading rate must be addressed in these situations.
- Install a hydraulically operated indexing valve that delivers effluent to a different trench / bed or set of laterals at each pump cut in.
- Checklist 10.1 details matters that should be checked when trenches or beds are installed. Plumbers/ installers and Council inspectors can use this checklist to ensure installation has been completed properly - see http://www.sca.nsw.gov.au/publications/publications/designing-and-installing-on-sitewastewater-systems



APPENDIX III GENERAL RECOMMENDATIONS TO MANAGE WATER QUALITY AND QUANTITY

Insinkerator style kitchen garbage disposal units should be avoided as they increase water consumption and raise the nutrient and BOD concentrations of household effluent.

Water conservation can reduce the volume of wastewater that needs to be treated and discharged on site. The residence should include appliances that are rated under the Water Efficiency Labelling and Standards (WELS) Scheme that includes:

- i. 4-star dual-flush toilets.
- ii. 3-star showerheads.
- iii. 4-star taps (for all taps other than bath outlets and garden taps).
- iv. 3-star urinals; and
- v. Water-efficient washing machines and dishwashers are to be specified and used wherever possible.

Chemical cleaning compounds and other chemicals that enter the treatment system should be low in phosphate and salt. Anti-bacterial chemical cleaning compounds and other chemicals that enter the treatment system should be avoided. This includes chlorine, disinfectants, bleaches etc.

APPENDIX IV REQUIRED BUFFERS

The following buffers must be applied when installing all onsite sewage management systems in accordance with WaterNSW (2019) and the Wagga-Wagga Council's Development Control Plan.

Table 2.6 – Buffer distances

Feature	Level of effluent treatment	Effluent application method	Buffer distance (minimum)	Achievable		
Buildings,	Primary	Subsoil	2.0m downslope and where flat, or 6.0m upslope of the feature	□ Yes	□ No	□N/A
retaining walls	Secondary (disinfected)	Subsurface and surface (including drip or trickle) irrigation	2-6m (<3m only for drip irrigation on low rate)	□ Yes	□ №	□ N/A
Premises boundaries, paths and	Primary	Subsoil	3.0m downslope and where flat, or 6.0m upslope of the feature; 15m to recreation areas, if by LPED irrigation	□ Yes	n No	□N/A
walkways, recreation areas	Secondary (disinfected)	Subsurface irrigation	3.0m downslope and where flat, or 4.0m upslope of the feature	□ Yes	□ No	□ N/A
		Surface irrigation	15m up- or downslope of the feature	□ Yes	п No	□ N/A
In ground potable water tanks,	Primary	Subsoil	15m and downslope from water tank or pool	□ Yes	□ No	□N/A
in ground swimming pools	Secondary (disinfected)	Subsurface and surface irrigation	4.0m - should not be located upslope of feature	□ Yes	n No	□ N/A
Watercourse , lakes and	Primary	Subsoil	100m from the high water level	□ Yes	п No	□N/A
the full supply level for all water supply reservoirs	Secondary (disinfected)	Subsurface and surface irrigation	100m from the high water level	□ Yes	п No	□N/A
Bore or well	Primary	Subsoil	100m	□ Yes	□ №	□ N/A
licenced for domestic^ consumption	Secondary (disinfected)	Subsurface and surface irrigation	100m	□ Yes	□ №	□N/A

Feature	Level of effluent treatment	Effluent application method	Buffer distance (minimum)	Achievable		
Drainage depressions,	Primary	Subsoil	40m from the high water level	□ Yes	□ №	□ N/A
farm dams and roadside drainage and lot scale stormwater quality improvemen t devices	Secondary (disinfected)	Subsurface and surface irrigation	40m from the high water level	□ Yes	□ No	□ N/A


^ If within 100 metres of a bore or well licenced for domestic consumption, a draw-down analysis is required using an appropriate methodology, such as Cromer, Gardner and Beavers, 2001 'An improved viral die-off method to estimate setback distances'. Domestic consumption is taken to mean for drinking, watering of edible plants etc.


APPENDIX V STANDARD DRAWING 9A - UPSLOPE DIVERSION DRAIN


111 300mm Clean local or imported soil and established grass cover Max. 2(H):1(V) batter grades Standard Drawing 9A - Upslope Diversion Drain Cross Section: Upslope Diversion Drain 10-40mm clean aggregate 100mm agricultural pipe Optional drain where significant subsoil run-on is likely. (not to scale) 1500mm Gradient of drain 1% to 5% 200 - 500mm Geotextile cloth 150mm Direction of Flow






















PLAN VIEW: TYPICAL BED





Issue:	Description:	Date	Drawn	Approved
Α	HEC Standard Drawing	28/09/2023	KK	SH



Harris Environmental Consulting PO Box 70 Jamberoo, NSW, 2533 T: 02 4236 0954 E: info@hec.eco

Wastewater | Bushfire | Stormwater

Drawing Title:
SOIL ABSORPTION BED WITH PUMP WELL
& HOLDING TANK STANDARD DRAWING
Drawn: Date: Scale: O.A. Check: Date

Drawn:	Date:	Scale:	Q.A. Check:	Date:
KK	28/09/2023	NTS		
Designed:	Our reference:	•	Dwg. No.	Issue:
SH				Α