







MM CONSULTING **ENGINEERS**

Schedule of Finishes

Address: 138 Haldon Street, Lakemba

Internal:	Floor:	<p>Ceramic Anti-Slip R10 Porcelain Tiles To be smooth and graded towards floor waste.</p> <p>Beig Colour</p>	
	Walls:	<p>Glazed Ceramic Tiles</p> <p>All existing and new walls to be of solid construction and finished with glossy ceramic tiles (Grout Epoxy)</p> <p>Off white Colour</p>	

	Ceiling:		
		<p>Painted Plaster (All Ceilings Except Coolroom)</p> <p>Ceiling to be Rigid, Non-Absorbent, Smoothed-Faced free from joints, cracks and crevices.</p> <p>Dulux – Vivid White Colour</p>	
		<p>Pre-Formed Panels</p> <p>Ceiling to be rigid, non-absorbent, smoothed-faced free from joints, cracks and crevices.</p> <p>White Colour</p>	
	Exhaust	<p>Steel Exhaust on the street same as already being used by other shop on the opposite side of the street.</p> <p>Shiny Steel</p>	

	Exterior Glazing /Door	Alluminium front door with clear glass , same as the existing one.	
--	-----------------------------------	---	---