



per BASIX requirements


BASIX requirements

CLOTHESLINE


location of rainwater tank as per

location of clothesline as per BASIX requirements











SHOP 1, 23-27 PATON STREET,				
MERRYLANDS WEST, NSW 2160				
(02) 9637 1111				
jack@dvyne.com.au				
www.dvyne.com.au				
DESIGN   CONSTRUCT   CONSUL				

JOB DESCRIPTION	DRAWING TITLE	D
Prop. SECONDARY DWELLING	FLOOR PLANS/ ELEVATIONS	
AT	CLIENT DETAILS	BETWI PR CONI
No 42 WOODBINE STREET, YAGOONA	JEREMY STEPHENS	DVYN

	LU
DO NOT SCALE THE DRAWINGS, READ ALL DIMENSIONS SHOWN.  ALL DIMENSIONS, NOTES ON ALL PLANS AND CONSENT	_ _ D
DOCUMENTS MUST BE CHECKED AND VERIFIED BY THE CONTRACTOR PRIOR TO ANY COMMENCEMENT OF ANY	С
BUILDING WORKS ON SITE, TO CLARIFY ANY DISCREPANCIES	S
BETWEEN ALL PLAN DRAWINGS AND DOCUMENTATION RELEVANT TO THE	$\vdash$
PROPOSAL / SITE WORKS. GROUND LEVELS MAY VARY DUE TO SITE CONDITIONS. COPYRIGHT - THESE DRAWINGS REMAIN THE PROPERTY OF	J(
DVYNE DESIGN JT PTY LTD AND CAN NOT BE ALTERED OR REPRODUCED WITHOUT WRITTEN CONSENT.	N
WIIIIOU WRITEN CONSENT.	

CB	ISSUE	AMENDMENT			BY	DATE
FEB 2024						
JACK	Α	DA SUBMISSION			СВ	FEB 2024
1/100						
23286-01						
A02						
A						
	FEB 2024 JACK 1/100 23286-01	FEB 2024  JACK  1/100  23286-01	FEB 2024  JACK  1/100  23286-01	FEB 2024  JACK	FEB 2024  JACK	FEB 2024  JACK





## 1 Landscape Plan 1:100

## **BASIX CERTIFICATE**

Water Commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check	Thermal Performance and Materials commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
Fixtures				Glazed windows, doors and skylights			
The applicant must install showerheads with a minimum rating of 4 star (> 4.5 but <= 6 L/min plus spray force and/or coverage tests) in all showers in the development.		~		The applicant must install the windows, glazed doors and shading devices described in the table below, in accordance with the specifications listed in the table. Relevant overshadowing specifications must be satisfied for each glazed window and door.	~	<b>✓</b>	~
The applicant must install a toilet flushing system with a minimum rating of 6 star in each toilet in the development.				The dwelling may have 1 skylight (<0.7 square metres) which is not listed in the table.	V	~	~
The applicant must install taps with a minimum rating of 5 star in the kitchen in the development.		<u> </u>	<u> </u>	The following requirements must also be satisfied in relation to each window and glazed door:	V		
The applicant must install basin taps with a minimum rating of 5 star in each bathroom in the development.				The applicant must install windows and glazed doors in accordance with the height and width, frame and glazing types listed in the table.		-	
		•		Each window and glazed door must have a U- value no greater than that listed and a Solar Heat Gain Coefficient (SHGC) within the			-
Thermal Performance and Materials commitments	Show on	Show on CC/CDC	Certifier	range listed. Total system U values and SHGC must be calculated in accordance with National Fenestration Rating Council (NFRC) conditions.		•	_
Do-it-yourself Method	DA plans	plans & specs	check	<ul> <li>Overshadowing buildings/vegetation must be of the height and distance from the centre and the base of the window and glazed door, as specified in the 'overshadowing' column.</li> </ul>	~	<b>~</b>	~
General features	-		-	The applicant must install the skylights described in the table below, in accordance with the specifications listed in the table. Total			
The dwelling must be a Class 1 dwelling according to the National Construction Code, and must not have more than 2 storeys.		T		skylight area must not exceed 3 square metres (the 3 square metre limit does not include the optional additional skylight of less than 0.7 square metres that does not have to be listed in the table).		•	•
The conditioned floor area of the duelling must not exceed 200 enurs matres	~	~	~		Shaw an	Shaw an GG/GDG	Contient
The conditioned floor area of the dwelling must not exceed 300 square metres.	~	~	~	Energy Commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
The dwelling must not contain open mezzanine area exceeding 25 square metres.	~	~	~	Hot water			
The dwelling must not contain third level habitable attic room.	~	~	~	The applicant must install the following hot water system in the development, or a system with a higher energy rating: gas instantaneous with a performance of 5 stars.	~	~	~
Floor, walls and ceiling/roof				Cooling system			
The applicant must construct the floor(s), walls, and ceiling/roof of the dwelling in accordance with the specifications listed in the table below.	~	<b>✓</b>	_	The applicant must install the following cooling system, or a system with a higher energy rating, in at least 1 living area: 1-phase airconditioning - non ducted; Energy rating: 5 star (average zone)		~	~
The applicant must adopt one of the options listed in the tables below to address thermal bridging in metal framed floor(s), walls and ceiling/roof of the dwelling.	~	~	~	The applicant must install the following cooling system, or a system with a higher energy rating, in at least 1 bedroom: 1-phase airconditioning - non ducted; Energy rating: 5 star (average zone)		~	~
The applicant must show through receipts that the materials purchased for construction are consistent with the specifications listed in				Heating system			
the tables below.				The applicant must install the following heating system, or a system with a higher energy rating, in at least 1 living area: 1-phase airconditioning - non ducted; Energy rating: 5 star (average zone)		V	
Thermal Performance and Materials commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier check	The applicant must install the following heating system, or a system with a higher energy rating, in at least 1 bedroom: 1-phase airconditioning - non ducted; Energy rating: 5 star (average zone)	2	~	~
Ceiling fans	_			Ventilation			
The applicant must install at least one ceiling fan in at least one daytime habitable space, such as living room.				The applicant must install the following exhaust systems in the development:		Ī	$\top$
The minimum number and diameter of ceiling fans in a daytime habitable space must be installed in accordance with the ABCB				At least 1 Bathroom: individual fan, open to façade; Operation control: manual switch on/off		<b>V</b>	
Housing Provisions (Part 13.5.2) of the National Construction Code .		•	•	Kitchen: individual fan, open to façade; Operation control: manual switch on/off		J	
				Laundry: individual fan, open to façade; Operation control: manual switch on/off			
				Artificial lighting		<u> </u>	
				The applicant must ensure that a minimum of 80% of light fixtures are fitted with fluorescent, compact fluorescent, or light-emitting-diode (LED) lamps.			
				Natural lighting	<u>.</u>	2	1,000
				The applicant must install a window and/or skylight in 1 bathroom(s)/toilet(s) in the development for natural lighting.		~	
				Fueran Commitments	Shower	Show on CO/ODS	Contific
				Energy Commitments	Show on DA plans	Show on CC/CDC plans & specs	Certifier
				Other			
				The applicant must install a gas cooktop & electric oven in the kitchen of the dwelling.		~	
				The applicant must install a fixed outdoor clothes drying line as part of the development.	1		+

	SHOP 1, 23-27 PATON STREE
	MERRYLANDS WEST, NSW 216
	(02) 9637 1111
	jack@dvyne.com.au
dvyne	www.dvyne.com.au
design	DESIGN   CONSTRUCT   CONS

JOB DESCRIPTION_	DRAWING TITLE
Prop. SECONDARY DWELLING	LANDSCPAE/ SECTION
AT	CLIENT DETAILS
No 42 WOODBINE STREET, YAGOONA	JEREMY STEPHENS

	DRA
DO NOT SCALE THE DRAWINGS, READ ALL DIMENSIONS SHOWN. ALL DIMENSIONS, NOTES ON ALL PLANS AND CONSENT	_DA1
DOCUMENTS MUST BE CHECKED AND VERIFIED BY THE CONTRACTOR PRIOR TO ANY COMMENCEMENT OF ANY	CHE
BUILDING WORKS ON SITE, TO CLARIFY ANY DISCREPANCIES BETWEEN ALL PLAN DRAWINGS AND DOCUMENTATION RELEVANT TO THE	SCA
PROPOSAL / SITE WORKS. GROUND LEVELS MAY VARY DUE TO SITE CONDITIONS. COPYRIGHT - THESE DRAWINGS REMAIN THE PROPERTY OF	JOB
DVYNE DESIGN JT PTY LTD AND CAN NOT BE ALTERED OR REPRODUCED WITHOUT WRITTEN CONSENT.	NUN
······································	

DRAWN	CB FEB 2024	ISSUE	AMENDMENT	BY	DATE
Date	I LD ZUZ4	_			
CHECKED	JACK	_ A	DA SUBMISSION	СВ	FEB 2024
SCALE	1/100				
JOB NUMBER	23286-01				
number in Set	A03				
ISSUE	A				