

Kosciuszko Thredbo Pty Ltd Proposed Access Track to Kareela Hutte

CLM CiViL Project No. V-333



	DRAWIN
Sheet No:	Des
1	Cover Sheet, Dra
2	Site Plan and Ac
3	Access Track Cr
4	Erosion and Sed
5	Erosion and Sed



NG LIST

escription rawing List and Locality Plan ccess Track Long Section Cross Sections diment Control plan diment Control Details

NOT FOR CONSTRUCTION

uszko Thredbo Pty Ltd				
Sheet Drawing List and	Client Re	view		
Locality Plan	GDA2020/AHD		Size	٨3
	V-333	1 of	5	D





 Rev
 Date
 Description

 A
 1/8/24
 First Issue
 First Issue
 CLM CiViL Engineering 205 Bobundara Road BERRIDALE NSW 2628 PH: 0427 886 623 E: greg@clmcivil.com.au
 Clert Kosciu

NOT FOR CONSTRUCTION			
uszko Thredbo Pty Ltd			
	Client Rev	view	
s Track Cross Sections	GDA2020/AHD Scale 1:200H	1:200V A3	
	V-333	3 of 5 D	

Ch 35.00 m

1811.149	1811.263	1811.113	1810.963	1810.052	
1811.149	1811.110	1810.700	1810.269	1810.052	1809.384
-1.73	-1.50	00.0	1.50	2.41	5.00

 \neg

Ch 40.00 m

	•				
1810.508	1810.699	1810.549	1810.399	1809.656	
1810.508	1810.423	1810.152	1809.867	1809.656	1808.989
-1.88	-1.50	00.0	1.50	2.24	5.00



ENVIRONMENTAL SITE MANAGEMENT

- 1. Implement soil and water management procedures to avoid erosion, contamination and sedimentation of the site, surrounding areas and drainage systems in accordance with the details provided in this drawing set, the Office of Environment and Heritage publication, 'Erosion and Sediment Control on Unsealed Roads, A Field Guide for Erosion and Sediment Control Maintenance Practices' and the 'Site Environmental Management Plan' prepared by Kosciuszko Thredbo.
- 2. Sediment and erosion controls must be in place prior to the commencement of any earthworks. The location of the final position of sediment and erosion control measures shall be determined on-site.
- 3. It is the responsibility of the contractor to ensure that all measures are taken during the course of construction to prevent sediment erosion and pollution of the downstream system. All sediment control structures shall be inspected after each rainfall event for structural damage and all trapped sediment to be removed to a nominated site. A sediment fence is to be placed downslope of all stockpiles.
- 4. Retain all vegetation wherever possible. Topsoil from all areas that will be disturbed is to be stripped and stockpiled at the nominated site.
- Disturbed areas are to be stablised as early as possible. All disturbed areas are 5. to be stablised within 14 days of disturbance.
- 6. All existing vegetation is to be retained unless shown otherwise on the approved drawings. Trees retained are to be protected with high visibility fence plus the flagging of individual trees as necessary.
- 7. All silt fences and barriers are to be maintained in good order and regularly desilted during the construction period.
- 8. The head contractor is to inform all site staff and sub-contractors of their obligations under the erosion and sediment control plan.

PH: 0427 886 623 E: greg@clmcivil.com.au

LEGEN	I <u>D:</u>	
HV Electrical Line	——— E ———	
Sewer main	S	
Gas main	—— GAS ——	
Downhill Mtn. bike track		
Contours		
Biodiversity Values Layer		
Proposed access track		
Access track centreline		
Straw bale filter		
Sediment fence	~~~~~	
	CLM CiVil Engineering	Client Kosc
CLM	205 Bobundara Road BERRIDALE NSW 2628	Erosic

NOT FOR CONSTRUCTION

uszko Thredbo Pty Ltd				
and Cadimont Control	Client Re	eview		
Plan	GDA2020/AHD	1:500	Size	\3
	V-333	4 of	5	D



•		
	Kareela	Hutte

