

Our ref: 7406-1-R1 Rev 1 4 October 2024

Suite 2.06 / 56 Delhi Road North Ryde NSW 2113 02 9878 6005 assetgeoenviro.com.au

Vail Resorts PO Box 42 Perisher Valley NSW 2624

Attention: Sophie Bellinger

Dear Sophie,

Eyre Kiosk Wastewater, Perisher NSW Geotechnical Assessment

1. Introduction

1.1 General

This report presents the results of a geotechnical assessment for the proposed Eyre Kiosk Wastewater at Perisher NSW (the Site). The assessment was commissioned on 26 October 2023 by Michael Fearnside of Vail Resorts.

Documents provided to us for this assessment comprised:

- Civil Engineering Plans (prepared by: CLM Civil Engineering; project: V-330; sheets: 1 to 6 of 6; revision: C; dated: 10 August 2024).
- Report on On-Site Sewage Management (prepared by: Southeast Engineering and Environmental; dated: 18 September 2024).
- Architectural Plans for Proposed Amenity Block (author: unknown; project number: unknown; drawing numbers: A00 to A11; dated: 24 September 2024).

Based on the above plans, we understand that the project involves a toilet block to be constructed next to an existing kiosk, installation of 3 x 60kL septic storage tanks adjacent to Kosciuszko Road, and piping of sewer from the toilet block to the septic tank. Minimal excavation (less than about 1m depth) is proposed for the amenity block and up to about 3m for the storage tanks.

The Site lies within the G-line as defined in DIPNR's "Geotechnical Policy – Kosciuszko Alpine Resorts", November 2003. However, given that the proposed works will likely be relatively minor, the development would fall under Minimal Impact criteria.



1.2 Scope of Work

The main objectives were to assess the surface and likely subsurface conditions and to provide comments and recommendations relating to Site Classification to AS2870–2011 "Residential Slabs and Footings", allowable bearing capacity, earthworks, and retaining.

The following scope of work was carried out to achieve the project objectives:

- A review of existing regional maps and reports relevant to the Site held within our files.
- Visual observations of surface features.
- Engineering assessment and reporting.

This report must be read in conjunction with the attached "Important Information about your Geotechnical Report" in Appendix A. Attention is drawn to the limitations inherent in site investigations and the importance of verifying the subsurface conditions inferred herein.

2. Site Description

The Site is located on the northern side of Kosciuszko Road about 830m southeast of Mount Perisher and about 2.1km southwest of the Perisher Valley Terminal, as shown in Plate 1.




Plate 1 – Site Locality

Topographically, the Site is at the base of a moderate to steep slope and at the head of a north easterly flowing watercourse. In the site vicinity, the slopes are estimated to be up to about 10°.



Selected photos of the site are attached.

The 1:250,000 Tallangatta Geological Map indicates the Site is underlain by Lower Devonian aged intrusive granites, micro-diorites and tonalites. This is locally weathered to produce core-stones and tor outcrops.

No granite outcrops were observed in the site vicinity, but scattered granite boulders were observed across the site. It is expected that variably weathered granite is located at relatively shallow depth below the ground surface to the north of the watercourse. Fill is expected to be encountered within the northern road shoulder on the southern flank of the watercourse, likely to have been placed as part of construction of Kosciuszko Road and is likely to comprise locally won materials from road cutting.

Localise seepage was observed to the west of the Kiosk (Photo 4), and local ponded surface was observed in a shallow depression in the northern road shoulder (Photo 1, 2).

3. Discussions & Recommendations

3.1 **Proposed Development**

It is understood that the development comprises:

- A toilet block to be constructed to the southwest of the Kiosk, with strip footings and posts to support a raised floor and a lower floor level.
- Wastewater to be piped adjacent to the access track down to 3 x 60 kL septic tanks, within a trench nominal 500mm deep. The trench will cross an 11,000-volt buried power line.
- Septic tanks 2.25m high buried up to 3m below ground level and sited about 12m to 18m from the road shoulder on the northern side of Kosciuszko Road.

3.2 Site Classification and Footings

In view of the landslide risk setting and likely site disturbance in the area including filling of variable depth and nature, the assessed site classification is Class P (Problem site).

Strip footing excavations for the toilet block are likely to encounter extremely weathered or better granite bedrock at relatively shallow depth, say less than about 1m, which would justify a less severe classification, Class A. It is expected that a conservative allowable bearing pressure of 150kPa would be achievable for footings on extremely weathered granite or very stiff natural clays or dense natural sands.

The septic tank excavation at 3m depth is likely to encounter natural soils or extremely weathered or better granite. Where the foundation material comprises stiff or better natural clays or medium dense or better natural sands or extremely weathered or better bedrock, an allowable bearing pressure of 150kPa should be available.



Inspection of footing excavations by a Geotechnical Engineer is required to verify the founding conditions. Further advise must be sought if deep fill is encountered, or if poorer quality subgrade is encountered.

3.3 Excavation Conditions and Batter Slopes

Excavations may encounter granite boulders that would require removal, or granite bedrock that would require blasting. Care should be taken to avoid disturbing adjacent services including the 11,000-volt power line.

Shallow excavations (not more than about 1m depth) could be dug with vertical sides. Deeper excavations (e.g., for the septic tank) should be excavated with a temporary batter slope no steeper than 1H:1V, or with 1m wide stepped benching at overall 1H:1V. If extremely weathered or better granite is encountered, this could be cut vertical. Inspection of the cut by a geotechnical engineer is recommended before allowing personnel to enter the excavation to construct the septic tank.

4. Limitations

In addition to the limitations inherent in geotechnical assessments and investigations (refer to the attached Information Sheets), it must be pointed out that the recommendations in this report are based on assessed subsurface conditions from limited observations. To confirm the assessed subsurface conditions in this report, further investigation would be required.

Asset accepts no liability where our recommendations are not followed or are only partially followed. The document "Important Information about your Geotechnical Report" in Appendix A provides additional information about the uses and limitations of this report.

 $\diamond \diamond \diamond$

Please do not hesitate to contact the undersigned if you have any questions regarding this report or if you require further assistance.

For and on behalf of AssetGeoEnviro

Mark Bartel

Mark Bartel BE, MEngSc, GMQ, CPEng, RPEQ/NER(Civil), DEP/PRE (NSW) Managing Director | Senior Principal Geotechnical Engineer

Encl: Site Photos Form 4 – Minimal Impact Certification Important Information about your Geotechnical Report Soil and Rock Explanation Sheets



Document Control

Distribution Register

Сору	Media	Recipient	Location
1	Secure PDF	Michael Fearnside	Vail Resorts
2	Secure PDF	Sophie Ballinger	Vail Resorts
2	Secure PDF	Mark Bartel	Asset Geotechnical Engineering

Document Status

Rev	Revision Details	Author	Reviewer		Approved for Issue		
			Name	Initials	Name	Initials	Date
0	Initial issue	M. Bartel			M. Bartel		30 November 2023
1	Updated plans	M. Bartel			M. Bartel		4 October 2024



Suite 2.06 / 56 Delhi Road North Ryde NSW 2113 02 9878 6005 assetgeoenviro.com.au

ISO 9001:2015 ISO 14001:2015 ISO 45001:2018 AS/NZS 4801:2001

© Copyright Asset Geotechnical Engineering Pty Ltd. All rights reserved.

AssetGeoEnviro is a registered business name of Asset Geotechnical Engineering Pty Ltd (Asset). This Report has been prepared by Asset for its Client in accordance with a contract between Asset and its Client. The Report may only be used for the purpose for which it was commissioned and is subject to the terms of contract including terms limiting the liability of Asset. Unauthorised use of this document in any form whatsoever is prohibited. Any third party who seeks to rely on this Report without the express written consent of Asset does so entirely at their own risk, and, to the fullest extent permitted by law, Asset accepts no liability whatsoever in respect of any loss or damage suffered by any such third party.



Site Photos



Photo 1

General view of Eyre Kiosk showing approach track from Kosciuszko Road. Services to be piped from Kiosk to septic tank on road shoulder (see Photo 2).





Photo 2

View of road shoulder where 3m deep septic tank proposed. Note ponded water in local depression. Road shoulder likely has been filled during construction of Kosciuszko Road.





Photo 3

Closeup view of Eyre Kiosk. Toilet block proposed to be constructed to left of Kiosk.





Photo 4

Closeup view of area where toilet block is proposed. Note seepage line.



Geotechnical Policy

Kosciuszko Alpine Resorts

Form 4 – Minimal Impact Certification

DA Number: _____

This form may be used where minor construction works which present minimal or no geotechnical impact on the site or related land are proposed to be erected within the "G" line area of the geotechnical maps.

A geotechnical engineer or engineering geologist must inspect the site and/or review the proposed development documentation to determine if the proposed development requires a geotechnical report to be prepared to accompany the development application. Where the geotechnical engineer determines that such a report is not required then they must complete this form and attach design recommendations where required. A copy of Form 4 with design recommendation, if required, must be submitted with the development application.

Please contact the Alpine Resorts Team in Jindabyne for further information - phone 02 6456 1733.

To complete this form, please place a cross in the appropriate boxes \Box and complete all sections.

1. Declaration made by geotechnical engineer or engineering geologist in relation to a nil or minimal geotechnical impact assessment and site classification

l, Mr 🗙	Ms 🗌	Mrs 🗌	Dr 🗌	Other		
First Na	me				Family Name	
Mark					Bartel	
						_

OF

Company/organisation

Asset Geotechnical Engineering Pty Ltd (trading as AssetGeoEnviro)

certify that I am a geotechnical engineer /engineering geologist as defined by the "Policy" and I have inspected the site and reviewed the proposed development known as

Eyre Kiosk Upgrades

As a result of my site inspection and review of the following documentation

(List of documentation reviewed)

Civil Engineering Plans (CLM Civil Engineering; project V-330; sheets 1 to 6 of 6; revision C; 10/8/24).

On-Site Sewage Management report (Southeast Engineering and Environmental; dated: 18/9/24).

Architectural Plans for Proposed Amenity Block (drawing numbers: A00 to A11; 24/9/24).

I have determined that;

- ☑ the current load-bearing capacity of the existing building will not be exceeded or adversely impacted by the proposed development, and
- ☑ the proposed works are of such a minor nature that the requirement for geotechnical advice in the form of a geotechnical report, prepared in accordance with the "Policy", is considered unnecessary for the adequate and safe design of the structural elements to be incorporated into the new works, and
- in accordance with AS 2870.1 Residential Slabs and Footings, the site is to be classified as a type

(insert classification type)

Class P (landslide risk setting, fill), Class A if founding on rock

and civil

☑ I have attached design recommendations to be incorporated in the structural design in accordance with this site classification. Refer report 7104-1-R1 Rev 1

I am aware that this declaration shall be used by the Department as an essential component in granting development consent for a structure to be erected within the "G" line area (as identified on the geotechnical maps) of Kosciuszko Alpine Resorts without requiring the submission of a geotechnical report in support of the development application.

2. Signatures

Signature	Chartered professional status
Mark Bartel	CPEng 35641 NER (Civil)
Name	Date
Mark Bartel	4 October 2024

3. Contact details

Alpine Resorts Team

Shop 5A, 19 Snowy River Avenue P O Box 36, JINDABYNE NSW 2627 Telephone: 02 6456 1733 Facsimile: 02 6456 1736 Email: alpineresorts@planning.nsw.gov.au

Important Information about your Geotechnical Report



Scope of Services

The geotechnical report ("the report") has been prepared in accordance with the scope of services as set out in the contract, or as otherwise agreed, between the Client and Asset Geotechnical Engineering Pty Ltd ("Asset"), for the specific site investigated. The scope of work may have been limited by a range of factors such as time, budget, access and/or site disturbance constraints.

The report should not be used if there have been changes to the project, without first consulting with Asset to assess if the report's recommendations are still valid. Asset does not accept responsibility for problems that occur due to project changes if they are not consulted.

Reliance on Data

Asset has relied on data provided by the Client and other individuals and organizations, to prepare the report. Such data may include surveys, analyses, designs, maps, and plans. Asset has not verified the accuracy or completeness of the data except as stated in the report. To the extent that the statements, opinions, facts, information, conclusions and/or recommendations ("conclusions") are based in whole or part on the data, Asset will not be liable in relation to incorrect conclusions should any data, information or condition be incorrect or have been concealed, withheld, misrepresented, or otherwise not fully disclosed to Asset.

Geotechnical Engineering

Geotechnical engineering is based extensively on judgment and opinion. It is far less exact than other engineering disciplines. Geotechnical engineering reports are prepared for a specific client, for a specific project and to meet specific needs, and may not be adequate for other clients or other purposes (e.g., a report prepared for a consulting civil engineer may not be adequate for a construction contractor). The report should not be used for other than its intended purpose without seeking additional geotechnical advice. Also, unless further geotechnical advice is obtained, the report cannot be used where the nature and/or details of the proposed development are changed.

Limitations of Site Investigation

The investigation program undertaken is a professional estimate of the scope of investigation required to provide a general profile of subsurface conditions. The data derived from the site investigation program and subsequent laboratory testing are extrapolated across the site to form an inferred geological model, and an engineering opinion is rendered about overall subsurface conditions and their likely behavior regarding the proposed development. Despite investigation, the actual conditions at the site might differ from those inferred to exist, since no subsurface exploration program, no matter how comprehensive, can reveal all subsurface details and anomalies.

The engineering logs are the subjective interpretation of subsurface conditions at a particular location and time, made by trained personnel. The actual interface between materials may be more gradual or abrupt than a report indicates.

Therefore, the recommendations in the report can only be regarded as preliminary. Asset should be retained during the project implementation to assess if the report's recommendations are valid and whether changes should be considered as the project proceeds.

Subsurface Conditions are Time Dependent

Subsurface conditions can be modified by changing natural forces or man-made influences. The report is based on conditions that existed at the time of subsurface exploration. Construction operations adjacent to the site, and natural events such as floods, or ground water fluctuations, may also affect subsurface conditions, and thus the continuing adequacy of a geotechnical report. Asset should be kept appraised of any such events and should be consulted to determine if any additional tests are necessary.

Verification of Site Conditions

Where ground conditions encountered at the site differ significantly from those anticipated in the report, either due to natural variability of subsurface conditions or construction activities, it is a condition of the report that Asset be notified of any variations and be provided with an opportunity to review the recommendations of this report. Recognition of change of soil and rock conditions requires experience, and it is recommended that a suitably experienced geotechnical engineer be engaged to visit the site with sufficient frequency to detect if conditions have changed significantly.

Reproduction of Reports

This report is the subject of copyright and shall not be reproduced either totally or in part without the express permission of this Company. Where information from the accompanying report is to be included in contract documents or engineering specification for the project, the entire report should be included to minimize the likelihood of misinterpretation from logs.

Report for Benefit of Client

The report has been prepared for the benefit of the Client and no other party. Asset assumes no responsibility and will not be liable to any other person or organization for or in relation to any matter dealt with or conclusions expressed in the report, or for any loss or damage suffered by any other person or organization arising from matters dealt with or conclusions expressed in the report (including without limitation matters arising from any negligent act or omission of Asset or for any loss or damage suffered by any other party relying upon the matters dealt with or conclusions expressed in the report). Other parties should not rely upon the report or the accuracy or completeness of any conclusions and should make their own inquiries and obtain independent advice in relation to such matters.

Data Must Not Be Separated from The Report

The report presents the site assessment and must not be copied in part or altered in any way.

Logs, figures, drawings, test results etc. included in our reports are developed by professionals based on their interpretation of field logs (assembled by field personnel) and laboratory evaluation of field samples. These data should not under any circumstances be redrawn for inclusion in other documents or separated from the report in any way.

Report Recommendations not Followed

Where the recommendations of the report are not followed or are only partially followed, there may be significant implications for the project (e.g., commercial loss, property loss or damage, personal injury, or loss of life). Consult Asset if you are not intending to follow all the report recommendations, to assess what the implications could be. Asset does not accept responsibility where the report recommendations have not been followed or have only been partially followed.

Other Limitations

Asset will not be liable to update or revise the report to consider any events or emergent circumstances or fact occurring or becoming apparent after the date of the report.



excavation logs



Other

Log Abbreviations & Notes

METHOD

borehol	e logs		
AS	auger screw *		
AD	auger drill *		
RR	roller / tricone		
W	washbore		
СТ	cable tool		
HA	hand auger		
D	diatube		
В	blade / blank bit		
V	V-bit		
Т	TC-bit		
* bit sho	wn by suffix e.g. ADV		

natural excavation NE HF hand excavation BH backhoe bucket ΕX excavator bucket DZ

- dozer blade ripper tooth
- R

coring

NMLC, NQ, PQ, HQ

SUPPORT

borehole logs		excav	ation logs
Ν	nil	N	nil
М	mud	S	shoring
С	casing	В	benched
NQ	NQ rods		

CORE-LIFT

- casing installed
- \square barrel withdrawn

NOTES, SAMPLES, TESTS

- disturbed D
- bulk disturbed В U50
- thin-walled sample, 50mm diameter ΗP hand penetrometer (kPa)
- shear vane test (kPa) S٧
- DCP dynamic cone penetrometer (blows per 100mm penetration)
- standard penetration test SPT
- SPT value (blows per 300mm) N*
- * denotes sample taken
- Nc SPT with solid cone
- R refusal of DCP or SPT

USCS SYMBOLS

- GW Gravel and gravel-sand mixtures, little or no fines.
- GP Gravel and gravel-sand mixtures, little or no fines, uniform gravels
- Gravel-silt mixtures and gravel-sand-silt mixtures. GΜ
- Gravel-clay mixtures and gravel-sand-clay mixtures. GC
- Sand and gravel-sand mixtures, little or no fines. SW SΡ
- Sand and gravel sand mixtures, little or no fines. SM
- Sand-silt mixtures. SC Sand-clay mixtures.
- ML Inorganic silt and very fine sand, rock flour, silty or clayey fine sand or silt with low plasticity.
- CL, CI Inorganic clays of low to medium plasticity, gravelly clays, sandy clays. Organic silts 0L
- MH Inorganic silts
- СН Inorganic clays of high plasticity.
- Organic clays of medium to high plasticity, organic silt ΟН
- ΡТ Peat, highly organic soils.

MOISTURE CONDITION


D	dry
М	moist
W	wet
αW	plastic limit

wi . liquid limit

CONSISTENCY **DENSITY INDEX**

VS	very soft	VL	very loose
S	soft	L	loose
F	firm	MD	medium dense
St	stiff	D	dense
VSt	very stiff	VD	very dense
н	hard		-

Gra	phic	Log
Gia	pine	LUY



Asphalt Concrete Brick Water Level Inflow Outflow (complete) Outflow (partial) **Boundaries** Known Probable Possible

WEATHERING

XW	extremely weathered
HW	highly weathered
MW	moderately weathered
SW	slightly weathered
FR	fresh

STRENGTH

very low

medium

very high

extremely high

low

high

VL

L

М

Н

VH

ΕH

RQD (%)

sum of intact core pieces > 2 x diameter x 100 total length of core run drilled

DEFECTS:

<u>type</u>		<u>coating</u>	
JT	joint	cl	clean
PT	parting	st	stained
SZ	shear zone	ve	veneer
SM	seam	CO	coating
<u>shape</u>		roughne	55
<u>shape</u> pl	planar	<i>roughne:</i> po	<u>ss</u> polished
•	planar curved	0	
pl .		ро	polished
pl cu	curved	po sl	polished slickensided
pl cu un	curved undulating	po sl sm	polished slickensided smooth

inclination

measured above axis and perpendicular to core

friable

Fb

Soil and Rock Explanation Sheets (2 of 2)



AS1726-2017

Soils and rock are described in the following terms, which are broadly in accordance with AS1726–2017.

Soil

MOISTURE CONDITION

Term Description

Dry	Looks and feels dry. Fine grained and cemented soils are hard, friable or pow-
	dery. Uncemented coarse grained soils run freely through hand.
Moist	Soil feels cool and darkened in colour. Fine grained soils can be moulded.
	Coarse soils tend to cohere.
Wet	As for moist, but with free water forming on hand.

CONSISTENCY OF FINE-GRAINED SOILS

Term	<u>Su (kPa)</u>	<u>Term</u>	<u>Su (kPa)</u>
Very soft	< 12	Very Stiff	>100 - ≤200
Soft	>12 - ≤25	Hard	> 200
Firm	>25 - ≤50	Friable	-
Stiff	>50 - ≤100		

RELATIVE DENSITY OF COARSE-GRAINED SOILS

<u>Term</u>	<u>Density Index (%)</u>	<u>Term</u>	<u>Density Index (%)</u>
Very Loose	< 15	Dense	65 – 85
Loose	15 – 35	Very Dense	>85
Medium Dense	35 – 65		

PARTICLE SIZE

Name	Subdivision	<u>Size (mm)</u>
Boulders		> 200
Cobbles		63 – 200
Gravel	coarse	19 – 63
	medium	6.7 – 19
	fine	2.36 - 6.7
Sand	coarse	0.6 - 2.36
	medium	0.21 - 0.6
	fine	0.075 - 0.21
Silt		0.002 - 0.075
Clay		< 0.075

MATERIAL DELINEATION

Sand or gravel>65% above 0.075mmClay or silt>35% below 0.075mm

MINOR COMPONENTS

<u>Term</u>	Proportion by Mass:	
	coarse grained	fine grained
Trace	≤ 5%	≤ 5%
With	>15% ≤ 30%	>5% – ≤12%

SOIL ZONING

Layers	Continuous across exposures or sample.
Lenses	Discontinuous, lenticular shaped zones.
Pockets	Irregular shape zones of different material.

SOIL CEMENTING

 Weakly
 Easily broken up by hand pressure in water or air.

 Moderately
 Effort is required to break up by hand in water or in air.

USCS SYMBOLS

<u>Symbol</u>	Description
---------------	--------------------

GW	Gravel and gravel-sand mixtures, little or no fines.
GP	Gravel and gravel-sand mixtures, little or no fines, uniform gravels.
GM	Gravel-silt mixtures and gravel-sand-silt mixtures.
GC	Gravel-clay mixtures and gravel-sand-clay mixtures.
SW	Sand and gravel-sand mixtures, little or no fines.
SP	Sand and gravel sand mixtures, little or no fines.
SM	Sand-silt mixtures.
SC	Sand-clay mixtures.
ML	Inorganic silt and very fine sand, rock flour, silty or clayey fine sand or silt
	with low plasticity.
CL, CI	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays.
OL	Organic silts
MH	Inorganic silts
CH	Inorganic clays of high plasticity.
OH	Organic clays of medium to high plasticity, organic silt
DT	Reat highly organic soils

```
PT Peat, highly organic soils.
```

Rock

Rock Type Conglomerate	COCK TYPE DEFINITI Definition (more that gravel sized (>2mm)	n 50% of rock consis	<u>ts of)</u>
Sandstone	sand sized (0.06 to 2	-	
Siltstone	silt sized (<0.06mm)	-	aminated.
Claystone	clay, rock is not lami		
Shale	silt or clay sized part	ticles, rock is laminate	d.
LAYERING			
<u>Term</u>	Description		
Massive	No layering appar		
Poorly Developed		e. Little effect on proper	
Well Developed	ing.	Rock breaks more eas	ny paraner to laye
STRUCTURE		_	
Term Thinly laminated	<u>Spacing (mm)</u> <6	<u>Term</u> Medium bedded	Spacing 200 – 600
Laminated	<0 6 – 20	Thickly bedded	200 – 800 600 – 2,000
Very thinly bedded	20 - 60	Very thickly bedded	
Thinly bedded	60 - 200	,,	
	E: Is50 = Point Load Str		
Term	<u>ls50 (MPa)</u>	<u>Term</u> High	<u>ls50 (MPa)</u>
Very Low Low	0.03 – 0.1 0.1 – 0.3	High Very High	1.0 – 3.0 3.0 – 10.0
Medium	0.3 – 1.0	Extremely High	>10.0
WEATHERING	Description		
<u>Term</u> Residual Soil	Description Material is weathered to	to an extent that it ha	s soil properties
	Rock structures are no	longer visible, but the	
Extremely	significantly transported. Material is weathered to the extent that it has soil properties. Mass structures, material texture & fabric of original rock is still visible.		
Highly	Rock strength is significa	ntly changed by weathe	ering; rock is discol-
	ored, usually by iron stai have weathered to clay r	0 0	e primary minerals
Moderately	Rock strength shows littl rock may be discolored.	e or no change of stren	gth from fresh rock
Slightly	Rock is partially discolor from fresh rock.	ed but shows little or no	o change of strength
Fresh	Rock shows no signs of	decomposition or sta	iining.
DEFECT DESCRI Type	PTION		
Joint	A surface or crack acro	ss which the rock has	little or no tensile
	strength. May be open		
Parting	A surface or crack acro strength. Parallel or su		
Sheared Zone	open or closed. Zone of rock substance	with roughly parallel	. near planar.
	curved or undulating b	oundaries cut by close	
Seam	sheared surfaces or ot Seam with deposited s		eathered insitu
	rock (XW), or disorienter rock (crushed).		
<u>Shape</u>	iock (crusheu).		
Planar	Consistent orientation.		
Curved	Gradual change in orie	ntation.	
Undulating	Wavy surface.	and allow a	
Stepped Irregular	One or more well defin Many sharp changes in		
Roughness	many snarp changes in		
Polished	Shiny smooth surface.		
Slickensided	Grooved or striated su		
Smooth	Smooth to touch. Few		
Rough	Many small surface irre Feels like fine to coarse		generally <1mm).
Very Rough	Many large surface irre Feels like very coarse s		generally >1mm.
Coating	e.s ince very course s		
Clean	No visible coating or di	scolouring.	
Stained	No visible coating but surfaces are discolored.		
Veneer	A visible coating of soil patchy		-
Costing	Visible coating -1mm t	is the interface of a set of the set of t	and a load a south shall a set

Visible coating =1mm thick. Thicker soil material described as seam.

Coating