


PROPOSED 3 RESIDENCES

at 28 Addison St Goulburn NSW 2580

for The Trustee for 28 Addison Property Trust

REF:22R019



CROSS SITE SECTION 1-1

SCALE - 1:100

PROJECT 28 Addison Street, Goulburn									
BASIX NOTES: DWELLING Lot 1									
ITEM	TYPE	INSULATION / RATING/ SIZE							
FLOOR-1	CONCRETE SLAB ON GROUND	NIL							
	TIMBER FRAMED	NIL							
EXTERNAL WALL	BRICK VENEER	R2.5							
	FIBRO CLAD FRAMED	R2.5							
ROOF	METAL DECK ROOF	R 1.3							
CEILING	FLAT	R 4.0							
WINDOWS	ALUMINUM FRAME -CLEAR GLASS								
	Aluminum B SG Clear	U VALUE	6.7	0.7					
	Aluminum A SG Clear	SHGC	6.7	0.57					
	FIXED WINDOW SG 638cmPacCf		3.91	0.62					
WATER	ALL SHOWER HEAD	3 STAR							
	ALL TOILET FLUSHING SYSTEMS	4 STAR							
	ALL KITCHEN TAPS	4 STAR							
	ALL BATH ROOM TAPS	4 STAR							
	RAINWATER TANK	1000 L							
ENERGY	HOT WATER SYSTEMS	GAS INSTANTANEOUS 6 STAR							
	AIR CONDITION	3 PHASE EER 2.5+							
	COOKING	INDUCTION COOKTOP ELECTRIC OVEN							
	LIGHTING	LED							
	PHOTOVOLTAIC SYSTEM	1.0KW MINIMUM							
PROJECT 28 Addison Street, Goulburn									
BASIX NOTES: DWELLING Lot 2									
ITEM	TYPE	INSULATION / RATING/ SIZE							
FLOOR-1	CONCRETE SLAB ON GROUND	NIL							
	TIMBER FRAMED	NIL							
EXTERNAL WALL	BRICK VENEER	R2.5							
	FIBRO CLAD FRAMED	R2.5							
ROOF	METAL DECK ROOF	R 1.3							
CEILING	FLAT	R 4.0							
WINDOWS	ALUMINUM FRAME -CLEAR GLASS								
	Aluminum B SG Clear	U VALUE	6.7	0.7					
	Aluminum A SG Clear	SHGC	6.7	0.57					
	FIXED WINDOW SG 638cmPacCf		3.91	0.62					
WATER	ALL SHOWER HEAD	3 STAR							
	ALL TOILET FLUSHING SYSTEMS	4 STAR							
	ALL KITCHEN TAPS	4 STAR							
	ALL BATH ROOM TAPS	4 STAR							
	RAINWATER TANK	1000 L							
ENERGY	HOT WATER SYSTEMS	GAS INSTANTANEOUS 6 STAR							
	AIR CONDITION	3 PHASE EER 1.5+							
	COOKING	INDUCTION COOKTOP ELECTRIC OVEN							
	LIGHTING	LED							
	PHOTOVOLTAIC SYSTEM	1.0KW MINIMUM							
PROJECT 28 Addison Street, Goulburn									
BASIX NOTES: DWELLING Lot 3									
ITEM	TYPE	INSULATION / RATING/ SIZE							
FLOOR-1	CONCRETE SLAB ON GROUND	NIL							
	TIMBER FRAMED	R2.5							
EXTERNAL WALL	BRICK VENEER	R2.5							
	FIBRO CLAD FRAMED	R2.5							
ROOF	METAL DECK ROOF	R 1.3							
CEILING	FLAT	R 5.0							
WINDOWS	ALUMINUM FRAME -CLEAR GLASS								
	Aluminum B SG Clear	U VALUE	6.7	0.7					
	Aluminum A SG Clear	SHGC	6.7	0.57					
	FIXED WINDOW SG 638cmPacCf		3.91	0.62					
	Aluminum B SG High Solar Gain Low-E		5.4	0.58					
WATER	ALL SHOWER HEAD	3 STAR							
	ALL TOILET FLUSHING SYSTEMS	4 STAR							
	ALL KITCHEN TAPS	4 STAR							
	ALL BATH ROOM TAPS	4 STAR							
	RAINWATER TANK	1000 L							
ENERGY	HOT WATER SYSTEMS	GAS INSTANTANEOUS 6 STAR							
	AIR CONDITION	3 PHASE EER 2.5+							
	COOKING	INDUCTION COOKTOP ELECTRIC OVEN							
	LIGHTING	LED							
	PHOTOVOLTAIC SYSTEM	1.0KW MINIMUM							

BASIX Certificate

Building Sustainability Index www.basix.nsw.gov.au

Multi Dwelling

Certificate number: 140223M_02

This certificate confirms that the proposed development will meet the NSW government's requirements for sustainability, if it is built in accordance with the commitments set out below. Terms used in this certificate, or in the commitments, have the meaning given by the document entitled "BASIX Definitions" dated 10/09/2020 published by the Department. This document is available at www.basix.nsw.gov.au.

This certificate is a revision of certificate number 140223M lodged with the consent authority or certifier on 10 August 2023 with application DA01020224.

It is the responsibility of the applicant to verify with the consent authority that the original, or any revised certificate, complies with the requirements of Schedule 1, Clause 2A, 4A or 6A of the Environment Planning and Assessment Regulation 2000.

Secretary
Date of issue: Wednesday, 27 November 2024
To be valid, this certificate must be lodged within 9 months of the date of issue.



BASIX Document of Planning, Housing and Infrastructure www.basix.nsw.gov.au Version 3.0/ DARWIN_01_01_0 Certificate No.: 140223M_02 Wednesday, 27 November 2024 page 1/13

Description of project

The tables below describe the dwellings and common areas within the project

Multi-dwelling houses

Dwelling no.	No. of bedrooms	Conditioned floor area (m²)	Unconditioned floor area (m²)	Area of gardens & lawn (m²)	Indigenous species (m² area m²)	Dwelling no.	No. of bedrooms	Conditioned floor area (m²)	Unconditioned floor area (m²)	Area of gardens & lawn (m²)	Indigenous species (m² area m²)
Lot1 44	153.70	12.80	87.00	0.00		Lot2 44	153.70	12.80	87.00	0.00	
Lot3 44	169.50	16.60	134.00								

Schedule of BASIX commitments

1. Commitments for single dwelling houses

2. Commitments for multi-dwelling houses

- (a) Dwellings
- (i) Water
- (ii) Energy
- (iii) Thermal Comfort

3. Commitments for common areas and central systems/facilities for the development (non-building specific)

- (a) Common areas and central systems/facilities
- (i) Water
- (ii) Energy

Schedule of BASIX commitments

The commitments set out below regulate how the proposed development is to be carried out. It is a condition of any development consent granted, or complying development certificate issued, for the proposed development, that BASIX commitments be complied with.

2. Commitments for multi-dwelling houses

(a) Dwellings

Dwelling no.	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(b) The applicant must comply with the commitments listed below in carrying out the development of a dwelling listed in a table below.			
(c) The applicant must plant indigenous or low water use species of vegetation throughout the area of land specified for the dwelling in the "Indigenous species" column of the table below, as private landscaping for that dwelling. (This area of indigenous vegetation is to be contained within the "Area of garden and lawn" for the dwelling specified in the "Description of Project" table).			
(d) If a rating is specified in the table below for a fixture or appliance to be installed in the dwelling, the applicant must ensure that each such fixture and appliance meets the rating specified for it.			
(e) The applicant must install an on demand hot water recirculation system which regulates all hot water use throughout the dwelling, where indicated for a dwelling in the "HW recirculation or diversion" column of the table below.			
(f) The applicant must install:			
(aa) a hot water diversion system to all showers, kitchen sinks and all basins in the dwelling, where indicated for a dwelling in the "HW recirculation or diversion" column of the table below; and			
(bb) a separate diversion tank (or tanks) connected to the hot water diversion systems of at least 100 litres. The applicant must connect the hot water diversion tank to all toilets in the dwelling.			
(g) The applicant must not install a private swimming pool or spa for the dwelling, with a volume exceeding that specified for it in the table below.			
(h) If specified in the table, that pool or spa (or both) must have a pool cover or shading (or both).			
(i) The pool or spa must be located as specified in the table.			
(j) The applicant must install, for the dwelling, each alternative water supply system, with the specified size, listed for that dwelling in the table below. Each system must be configured to collect run-off from the areas specified (excluding any area which supplies any other alternative water supply system), and to divert overflow as specified. Each system must be connected as specified.			

Fixtures		Appliances		Individual pool		Individual spa	
Dwelling no.	All shower-heads	All toilet flushing systems	All kitchen taps	All bathroom taps	HW recirculation or diversion	All clothes washers	All dish-washers
All dwellings	3 star (> 4.5 but <= 8 L/min)	4 star	4 star	4 star	no	-	-
Alternative water source							
Dwelling no.	Alternative water supply system	Size	Configuration	Landscape connection	Toilet connection (a)	Laundry connection	Pool top-up
All dwellings	Individual water tank (No. 1)	Tank size (min) 1000.00 litres	To collect run-off from at least: 100.00 square metres of roof area;	yes	yes	yes	no

(i) Energy	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) The applicant must comply with the commitments listed below in carrying out the development of a dwelling listed in a table below.			
(b) The applicant must install each hot water system specified for the dwelling in the table below, so that the dwelling's hot water is supplied by that system. If the table specifies a central hot water system for the dwelling, then the applicant must connect that central system to the dwelling, so that the dwelling's hot water is supplied by that central system.			
(c) The applicant must install, in each bathroom, kitchen and laundry of the dwelling, the ventilation system specified for that room in the table below. Each such ventilation system must have the operation control specified for it in the table.			
(d) The applicant must install the cooling and heating systems specified for the dwelling under the "Living areas" and "Bedroom areas" headings of the "Cooling" and "Heating" columns in the table below, in or at least 1 living/bedroom area of the dwelling. If no cooling or heating system is specified in the table for "Living areas" or "Bedroom areas", then no systems may be installed in any such areas. If the term "ceiling" is specified beside an air conditioning system, then the system must provide for daylight zoning between living areas and bedrooms.			
(e) This commitment applies to each room or area of the dwelling which is referred to in a heading to the "Artificial lighting" column of the table below (but only to the extent specified for that room or area). The applicant must ensure that the "primary type of artificial lighting" for each such room in the dwelling is fluorescent lighting or light emitting diode (LED) lighting. If the term "dedicated" is specified for a particular room or area, then the light fittings in that room or area must only be capable of being used for fluorescent lighting or light emitting diode (LED) lighting.			

(i) Energy	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) This commitment applies to each room or area of the dwelling which is referred to in a heading to the "Natural lighting" column of the table below (but only to the extent specified for that room or area). The applicant must ensure that each such room or area is fitted with a window and/or skylight.			
(b) This commitment applies if the applicant installs a water heating system for the dwelling's pool or spa. The applicant must:			
(aa) install the system specified for the pool in the "Individual Pool" column of the table below (or alternatively must not install any system for the pool). If specified, the applicant must install a timer, to control the pool's pump; and			
(bb) install the system specified for the spa in the "Individual Spa" column of the table below (or alternatively must not install any system for the spa). If specified, the applicant must install a timer to control the spa's pump.			
(c) The applicant must install in the dwelling:			
(aa) the kitchen cook-top and oven specified for that dwelling in the "Appliances & other efficiency measures" column of the table below;			
(bb) each appliance for which a rating is specified for that dwelling in the "Appliances & other efficiency measures" column of the table, and ensure that the appliance has that minimum rating; and			
(cc) any clothes drying line specified for the dwelling in the "Appliances & other efficiency measures" column of the table.			
(f) If specified in the table, the applicant must carry out the development so that each refrigerator space in the dwelling is "well ventilated".			
(g) The applicant must install the photovoltaic system specified for the dwelling under the "Photovoltaic system" heading of the "Alternative energy" column of the table below, and connect the system to that dwelling's electrical system.			

Hot water		Bathroom ventilation system		Kitchen ventilation system		Laundry ventilation system	
Dwelling no.	Hot water system	Each bathroom	Operation control	Each kitchen	Operation control	Each laundry	Operation control
All dwellings	gas instantaneous - 0 star	individual fan, not ducted	manual switch on/off	individual fan, not ducted	manual switch on/off	natural ventilation only, or no laundry	-

Cooling		Heating		Artificial lighting		Natural lighting	
Dwelling no.	Living areas	Bedroom areas	Living areas	Bedroom areas	No. of bedrooms &/or study	No. of living &/or diningroom	Main kitchen
All dwellings	3-phase air conditioning EER 2.5 - 3.0 (zoned)	3-phase air conditioning EER 2.5 - 3.0 (zoned)	3-phase air conditioning EER 2.5 - 3.0 (zoned)	3-phase air conditioning EER 2.5 - 3.0 (zoned)	4 (dedicated)	1 (dedicated)	yes (dedicated)

Individual pool		Individual spa		Appliances & other efficiency measures	
Dwelling no.	Pool heating system	Timer	Spa heating system	Timer	Kitchen cooktop/oven
All dwellings	-	-	-	-	Induction cooktop & electric oven

Alternative energy	
Dwelling no.	Photovoltaic system (min rated electrical output in peak kW)
All dwellings	1.00

(iii) Thermal Comfort	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) The applicant must attach the certificate referred to under "Assessor details" on the front page of this BASIX certificate (the "Assessor Certificate") to the development application and construction certificate application for the proposed development (or, if the applicant is applying for a complying development certificate for the proposed development, to that application). The applicant must also attach the Assessor Certificate to the application for a final occupation certificate for the proposed development.			
(b) The Assessor Certificate must have been issued by an Accredited Assessor in accordance with the Thermal Comfort Protocol.			
(c) The details of the proposed development on the Assessor Certificate must be consistent with the details shown in this BASIX Certificate, including the details shown in the "Thermal Loads" table below.			

(ii) Thermal Comfort	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(d) The applicant must show on the plans accompanying the development application for the proposed development, all matters which the Thermal Comfort Protocol requires to be shown on those plans. Those plans must bear a stamp of endorsement from the Accredited Assessor, to certify that this is the case.			
(e) The applicant must show on the plans accompanying the application for a construction certificate (or complying development certificate, if applicable), all thermal performance specifications set out in the Assessor Certificate, and all aspects of the proposed development which were used to calculate those specifications.			
(f) The applicant must construct the development in accordance with all thermal performance specifications set out in the Assessor Certificate, and in accordance with those aspects of the development application or application for a complying development certificate which were used to calculate those specifications.			
(g) Where there is an in-slab heating or cooling system, the applicant must:			
(aa) Install insulation with an R-value of not less than 1.0 around the vertical edges of the perimeter of the slab; or			
(bb) On a suspended floor, install insulation with an R-value of not less than 1.0 underneath the slab and around the vertical edges of the perimeter of the slab.			
(h) The applicant must construct the floors and walls of the development in accordance with the specifications listed in the table below.			

Thermal loads	
Dwelling no.	Area adjusted heating load (in MJ/m²/yr)
Lot1	170.20
Lot2	170.20
All other dwellings	170.20

Construction of floors and walls	
Dwelling no.	Concrete slab on ground (m²)
Lot1	155.00
Lot2	155.00
All other dwellings	155.00

3. Commitments for common areas and central systems/facilities for the development (non-building specific)

(a) Common areas and central systems/facilities

(i) Water	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) If, in carrying out the development, the applicant installs a showerhead, toilet, tap or clothes washer into a common area, then that item must meet the specifications listed for it in the table.			
(b) The applicant must install (or ensure that the development is serviced by) the alternative water supply system(s) specified in the "Central systems" column of the table below. In each case, the system must be sized, be configured, and be connected, as specified in the table.			
(c) A swimming pool or spa listed in the table must not have a volume (in kL) greater than that specified for the pool or spa in the table.			
(d) A pool or spa listed in the table must have a cover or shading if specified for the pool or spa in the table.			
(e) The applicant must install each fire sprinkler system listed in the table so that the system is configured as specified in the table.			
(f) The applicant must ensure that the central cooling system for a cooling tower is configured as specified in the table.			

Common areas	Showerheads rating	Toilets rating	Tap rating	Clothes washers rating
All common areas	no common facility	no common facility	no common facility	no common laundry facility

(i) Energy	Show on DA plans	Show on CC/CDC plans & specs	Certifier check
(a) If, in carrying out the development, the applicant installs a ventilation system to service a common area specified in the table below, then that ventilation system must be of the type specified for that common area, and must meet the efficiency measure specified.			
(b) In carrying out the development, the applicant must install, as the "primary type of artificial lighting" for each common area specified in the table below, the lighting specified for that common area. This lighting must meet the efficiency measure specified. The applicant must also install a centralised lighting control system or Building Management System (BMS) for the common area, where specified.			
(c) The applicant must install the systems and fixtures specified in the "Central energy systems" column of the table below. In each case, the system or fixture must be of the type, and meet the specifications, listed for it in the table.			

Central energy systems	Type	Specification
Other:	-	-

Notes

- In these commitments, "applicant" means the person carrying out the development.
- The applicant must identify each dwelling, building and common area listed in this certificate, on the plans accompanying any development application, and on the plans and specifications accompanying the application for a construction certificate / complying development certificate, for the proposed development, using the same identifying letter or reference as is given to that dwelling, building or common area in this certificate.
- This note applies if the proposed development involves the erection of a building for both residential and non-residential purposes (or the change of use of a building for both residential and non-residential purposes). Commitments in this certificate which are specified to apply to a "common area" of a building or the development, apply only to that part of the building or development to be used for residential purposes.
- If this certificate lets a central system as a commitment for a dwelling or building, and that system will also service any other dwelling or building within the development, then that system need only be installed once (even if it is separately listed as a commitment for that other dwelling or building).
- If a star or other rating is specified in a commitment, this is a minimum rating.
- All alternative water systems to be installed under these commitments (if any), must be installed in accordance with the requirements of all applicable regulatory authorities. NOTE: NSW Health does not recommend that stormwater, recycled water or private dam water be used to irrigate edible plants which are consumed raw, or that rainwater be used for human consumption in areas with potable water supply.

Legend

- Commitments identified with a "W" in the "Show on DA plans" column must be shown on the plans accompanying the development application for the proposed development (if a development application is to be lodged for the proposed development).
- Commitments identified with a "W" in the "Show on CC/CDC plans and specs" column must be shown in the plans and specifications accompanying the application for a construction certificate / complying development certificate for the proposed development.
- Commitments identified with a "C" in the "Certifier check" column must be certified by a certifying authority as having been fulfilled. (Note: a certifying authority must not issue an occupation certificate (either internal or final) for a building listed in this certificate, or for any part of such a building, unless it is satisfied that each of the commitments whose fulfillment it is required to monitor in relation to the building or part, has been fulfilled).