

STORMWATER MANAGEMENT PLAN

PROPOSED SINGLE DWELLING

No.29 GREENACRE ROAD, GREENACRE

GENERAL NOTES:

1.
- THESE PLANS REMAIN THE PROPERTY OF NY CIVIL ENGINEERING PTY LTD AND ARE SUBJECT TO COPYRIGHT
2.
- ALL DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE STATED. ALL REDUCED LEVELS (SURFACE LEVELS, INVERT LEVELS) AND CHAINAGES ARE IN METERS UNLESS OTHERWISE STATED. DO NOT SCALE OFF THE DRAWINGS, SCALES ARE AS SHOWN, USE FIGURED DIMENSIONS.
3.
- THIS PLAN IS TO BE READ IN JUNCTION WITH LATEST ARCHITECTURAL, STRUCTURAL, UTILITY AND LANDSCAPE PLANS IN ADDITION TO ANY RELEVANT GEOTECHNICAL, SOIL CLASSIFICATION OR REF/ENVIRONMENTAL REPORTS. ENGINEER IS TO BE NOTIFIED OF ANY DISCREPANCIES QUOTED ON THIS PLAN.
4.
- ALL WORKS SHALL BE CARRIED OUT TO LOCAL COUNCIL'S DEVELOPMENT CONTROL PLAN AND SPECIFICATIONS, AS/NZS 3500.3 AND B.C.A.
5.
- ALL LEVELS SHALL RELATE TO THE ESTABLISHED BM, PM AND/OR LM. ALL EXISTING SERVICES ARE TO BE VERIFIED FOR LOCATION AND DEPTH PRIOR TO COMMENCEMENT OF ANY WORK. CONTRACTOR TO NOTIFY DESIGNER OF ANY DISCREPANCIES OF SERVICE LEVELS QUOTED ON THIS PLAN. ALL SURVEY INFORMATION, BUILDING AND FINISHED SURFACE LEVELS SHOWN IN THESE DRAWINGS ARE BASED ON LEVELS OBTAINED FROM DRAWINGS BY OTHERS.
6.
- IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN ANY PRIOR APPROVAL REQUIRED FROM COUNCIL WITH RESPECT TO POTENTIAL IMPACT ON TREES FOR ANY WORKS SHOWN ON THIS DRAWING PRIOR TO THE COMMENCEMENT OF WORKS. NO TREES SHALL BE REMOVED WITHOUT THE WRITTEN PERMISSION OF COUNCIL.
7.
- THE CONTRACTOR SHALL TAKE ALL DUE CARE TO USE THE ABSOLUTE MINIMUM AREA FOR CONSTRUCTION AND THAT NO UNDUE DAMAGE IS DONE TO THE EXISTING VEGETATION.
8.
- THE CONTRACTOR SHALL COMPLY WITH CONDITIONS, AND SPECIFICATION OF COUNCIL AND ALL ACTS OF THE NSW EPA.
9.
- THE CONTRACTOR SHALL TAKE ALL REASONABLE CARE TO PROTECT EXISTING SERVICES. DAMAGED SERVICES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.
10.
- ALL NEW WORK IS TO MAKE A SMOOTH JUNCTION WITH EXISTING WORK.
11.
- SUITABLE WARNING SIGNS AND BARRICADES ARE TO BE PROVIDED IN ACCORDANCE WITH THE AUSTRALIAN STANDARDS AND AS DIRECTED BY THE RELEVANT AUTHORITY.
12.
- SERVICES SHOWN ARE INDICATIVE ONLY FROM AVAILABLE INFORMATION AND THE TIME OF SITE INVESTIGATION (IF ANY). THE BUILDER IS TO NOTIFY ENGINEER OF ANY DISCREPANCIES QUOTED ON THIS PLAN.
13.
- RESTORE ALL TRAFFIC AREAS TO PRE EXISTING CONDITION. FOR ALL SURFACES OTHER THAN IN TRAFFIC AREAS RESTORE DISTURBED SURFACES TO PRE-EXISTING CONDITION AND COMPACT AS SPECIFIED.
14.
- RESTORE ALL AUTHORITY OWNED AREAS TO COUNCIL AND/OR AUTHORITY STANDARD AND SPECIFICATION.
15.
- THE WORK AS CONSTRUCTED WORKS SHALL BE INSPECTED BY THE ENGINEER, MINIMUM 48 HOURS NOTICE SHALL BE PROVIDED FOR ALL INSPECTION REQUESTS.
16.
- THE DESIGN PLANS HEREIN ARE SUBJECT TO COUNCIL APPROVAL PRIOR TO CONSTRUCTION.
17.
- WORK AS CONSTRUCTED DRAWINGS TO BE REQUESTED AND RECEIVED IN CAD/DWG FILE TYPE AND HARD COPY 'RED LINE' MARKUP FROM CONSTRUCTOR FOR VERIFICATION AND CERTIFICATION.

ROOF STORMWATER DRAINAGE NOTES:

1.
- ALL DOWN PIPES TO BE MINIMUM DN90 OR 100x50MM FOR GUTTERS SLOPE 1:500 AND STEEPER AS PER AS 3500.3 - 3.7.8
2.
- ALL ROOF GUTTERS TO HAVE OVERFLOW PROVISION IN ACCORDANCE WITH AS 3500.3 AND SECTIONS 3.5.3, 3.7.5 AND APPENDIX G OF AS 3500.3.
3.
- ALL DOWNPIPES TO BE FITTED VERTICALLY TO THE SOLE OF EAVES GUTTERS, RAINHEAD AND/OR SUMP.
4.
- ALL DOWNPIPES TO DRAIN INTO RAINWATER TANK AND OR PIT PRIOR TO DISCHARGE OFFSITE UNLESS PRIOR APPROVAL IS OBTAINED FROM COUNCIL IN WRITING OR NOTED OTHERWISE ON THIS PLAN.
5.
- ALL EAVES GUTTERS TO BE SIZED FOR ARI 20 - AS PER AS 3500.3 - 3.5 AND APPENDIX H.
6.
- ROOF DRAINAGE INSTALLATION TO BE IN ACCORDANCE TO AS 3500.3 SECTION 4.

STORMWATER DRAINAGE NOTES:

- PIPE SIZE:
1.
- THE MINIMUM PIPE SIZE SHALL BE:
- 1.1.
- DN90 FOR ALL DOWNPIPES;
- 1.2.
- DN100 WHERE THE LINE ONLY RECEIVES ROOF STORMWATER RUNOFF, OR;
- 1.3.
- DN100 WHERE THE LINE RECEIVES RUNOFF FROM PAVED OR UNPAVED AREAS.
- PIPE GRADE:
1.
- THE MINIMUM PIPE GRADE SHALL BE:
- 1.1.
- FOR DN100 - DN150 - 1.00%
- 1.2.
- FOR DN225 - 0.50%
- 1.3.
- FOR DN300 - 0.45%
- 1.4.
- FOR DN375 - 0.35%
- STANDARD COVER:
1.
- MINIMUM PIPE COVER FOR PVC PIPES SHALL BE AS PER AS 3500.3 TABLE 6.2.5:
- 1.1.
- NOT SUBJECT TO VEHICULAR LOADING:
- 1.1.1.
- WITHOUT PAVEMENT SINGLE DWELLINGS - 100mm
- 1.1.2.
- WITHOUT PAVEMENT OTHER THAN SINGLE DWELLINGS - 300mm
- 1.1.3.
- WITH PAVEMENT (BRICK/PAVERS) AND/OR UNREINFORCED CONCRETE - 100mm
- 1.2.
- SUBJECT TO VEHICULAR LOADING:
- 1.2.1.
- ROADS (SEALED) - 600mm
- 1.2.2.
- ROADS (UNSEALED) - 750mm
- 1.2.3.
- OTHER THAN ROADS (WITH PAVEMENT) - 100mm
- 1.2.4.
- OTHER THAN ROADS (WITHOUT PAVEMENT) - 450mm

- PIPE INSTALLATION
1.
- PIPES AND FITTINGS FOR STORMWATER DRAINAGE SHALL BE AS FOLLOWS:
- 1.1.
- FOR PIPE SIZES UP TO DN225 - PVC WITH SOLVENT WELDED JOINTS (IN GROUND).
- 1.2.
- FOR PIPE SIZES GREATER THAN DN225 - RCP WITH RUBBER RING JOINTS.
- 1.3.
- FOR LARGER PIPE DEPTHS AS SPECIFIED IN AS 3500.3 - RCP WITH RUBBER RING JOINTS.
- 1.4.
- FOR PIPES AND FITTINGS FOR SUBSOIL DRAINAGE SHALL BE SLOTTED PVC WITH SOLVENT WELDED JOINTS MINIMUM DN150.
2.
- FOR GRATED DRAINS SHALL BE MINIMUM DN150 IN NON-TRAFFICABLE ZONES AND DN225 IN TRAFFICABLE ZONES.
3.
- LAY AND JOINT ALL PIPES IN ACCORDANCE WITH THE MANUFACTURING RECOMMENDATIONS AND:
- 3.1.
- AS 3725-1989 - LOADS ON BURIED CONCRETE PIPES
- 3.2.
- AS 2566 - 1988 - BURIED FLEXIBLE PIPELINES
- 3.3.
- AS 1597.2 - 1996 - PRECAST REINFORCED CONCRETE BOX CULVERTS
- 3.4.
- AS 3500 - 1990 NATIONAL PLUMBING AND DRAINAGE CODE - PART 2 SANITARY PLUMBING AND SANITARY DRAINAGE - SYDNEY WATER REQUIREMENTS.
4.
- ALLOW TO TEST ALL PIPES AND PITS TO MANUFACTURERS REQUIREMENTS.

CONNECTIONS TO STORMWATER SYSTEMS UNDER BUILDINGS:
IN ACCORDANCE WITH AS 3500.3 SECTION 6. TESTING IN ACCORDANCE WITH AS 3500.3 SECTION 9.2

CONNECTIONS TO COUNCIL STORMWATER SYSTEMS:
CONNECTION TO COUNCIL STORMWATER SYSTEM TO BE IN ACCORDANCE TO LOCAL COUNCIL DCP AND STANDARDS. NO CONNECTIONS TO BE MADE UNTIL PERMIT/APPROVALS ARE OBTAINED FROM LOCAL COUNCIL IN WRITING.

WARNING:
EXISTING SERVICES SHOWN ON THESE PLANS ARE NOT GUARANTEED COMPLETE OR CORRECT AND FURTHER INFORMATION IS REQUIRED FROM THE RELEVANT AUTHORITY AND FIELD INVESTIGATION AND ARE TO BE VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION.

LEGEND

SURFACE INLET PIT		GRATED TRENCH DRAIN	
SURFACE INLET PIT (WITH ENVIROPOD 200 MICRON)		ABSORPTION TRENCH	
ACCESS GRATE (WITH GROSS POLLUTANT TRAP)		PROPOSED ROOF GUTTER FALL	
450 SQUARE INTERVAL	450 X 450	PROPOSED DOWNPIPE SPREADER	
GRATE LEVEL = 75.50	SL 75.50	STORMWATER PIPE 100mm DIA. MIN. UNO	
INVERT LEVEL = RL 75.20	IL 75.20	SUBSOIL PIPE	
PROPOSED DOWNPIPE 90mm DIA. OR 100mm x 50mm MIN.		EXISTING STORMWATER PIPE	
NATURAL GROUND FINISHED DESIGN LEVEL	×	INSPECTION RISER	
		RAINWATER HEAD	

STORMWATER PIT/STRUCTURES NOTES:

- PIT SIZES AND DEPTHS:
1.
- PIT SIZES WILL BE AS FOLLOWS:
- | DEPTH (mm) | MIN. PIT SIZE (mm) |
|------------|---------------------------|
| UP TO 450 | 350x350 |
| 450 – 600 | 450x450 |
| 600 – 900 | 600x600 |
| 900 – 1200 | 600x900 |
| 1200+ | 900x900 (WITH STEP IRONS) |
- PIT DESIGNS:
1.
- TRENCH DRAINS: CONTINUOUS TRENCH DRAINS ARE TO BE MIN. DN150 AND MIN. 100mm DEPTH. THE BARS OF THE GRATE ARE TO BE PARALLEL TO THE DIRECTION OF SURFACE FLOW.
2.
- STEP IRONS: PITS BETWEEN 1.2m AND 6m ARE TO HAVE STEP IRONS IN ACCORDANCE WITH AS 1657. FOR PITS GREATER THAN 6m OTHER MEANS OF ACCESS MUST BE PROVIDED.
3.
- PLASTIC/PVC PITS: PVC PITS WILL ONLY BE PERMITTED IF THEY ARE MAX. 450x450 AND MAX. 450mm DEPTH AS WELL AS BEING HEAVY DUTY.
4.
- IN-SITU PITS: IN-SITU PITS ARE TO BE CONSTRUCTED ON A CONCRETE BED OF AT LEAST 150mm THICK. THE WALLS ARE TO BE DESIGNED TO MEET THE MINIMUM REQUIREMENTS OF CLAUSE 4.6.3 OF AS 3500.4. PITS DEEPER THAN 1.8m SHALL BE CONSTRUCTED WITH REINFORCED CONCRETE.
5.
- GRATES: GRATES ARE TO BE GALVANIZED STEEL GRID TYPE. GRATES ARE TO BE OF HEAVY-DUTY TYPE IN AREAS WHERE THEY MAY BE SUBJECT TO VEHICLE LOADING.
- INSTALLATION NOTES:
1.
- ALL PIPES INTO PITS TO BE CUT FLUSH WITH PIT WALL.
2.
- GRATED COVERS ON PITS GREATER THAN 600mm TO BE HINGED.
3.
- MINIMUM 20mm FALL TO BE PROVIDED ACROSS BASE OF PIT



APPROVED BY	REVISION	DRAWN	DESCRIPTION	DATE	DRAWING TITLE	SHEET SIZE A3	JOB REFERENCE
NADER ZAKI MIEAust CPEng NER	A	EM	ISSUED FOR DA	16.01.2024	DETAILS, NOTES & LEGEND	DESIGNED EM	E240659
						CHECKED NZ	DRAWING No. D1
0413 942 613						ISSUE A	No. IN SET
admin@nycivilengineering.com.au						SCALE -	8
www.nycivilengineering.com.au							
					PROJECT TITLE		
					PROPOSED SINGLE DWELLING No. 29 GREENACRE ROAD GREENACRE		

PUMP-OUT CALCULATIONS

PROPOSED RISING MAIN PIPE DIAMETER:
65mm DIA uPVC 'PRESSURE PIPE' CLASS "12"

HEAD LOSS

- STATIC = 2.4 m (approx)
- PIPE FRICTION = 0.5 m
- FITTINGS = 0.5 m
- TOTAL = 3.4 m

PUMP DUTY :
2 l/s AT 3.4 m HEAD

PUMP TYPE :
SUBMERSIBLE EQUAL TO DAVEY D75 750W, 240 V, OR
EQUIVALENT.

USE TWO (2) x PUMPS TO OPERATE

ALTERNATIVELY

AS PER AS3500.3.

PUMP CONTROL:

AUTOMATIC WITH FLOAT SWITCHES


PUMP OUT SYSTEM

- DESIGN STORM 100 ARI 2hr (I = 38.3mm/hr)
- AREA TO PUMP APPROX 27.4m²
- MAX FLOW $\frac{0.00274 \text{ Ha} \times 208 \text{ mm/hr}}{360} = 1.6\text{L/s}$
- DESIGN FLOW $\frac{0.00274 \text{ Ha} \times 38.3 \text{ mm/hr}}{360} = 0.29\text{L/s}$
- DESIGN VOLUME $0.29\text{L/s} \times 60\text{s} \times 120\text{min} = 2,088\text{L}$


THEREFORE PROVIDE MINIMUM 3.0m³ HOLDING TANK

PROVIDE DUAL PUMPS WITH MINIMUM DISCHARGE RATE OF 2 l/s EACH.
REFER TO DETAIL

CURVES



PUMP DESIGN



BASEMENT PLAN

1:200

Ø65 'CLASS 12' PUMP
OUT PIPE
CONTINUED ON D3

PLANS ARE FOR CONCEPT ONLY
AND NOT FOR CONSTRUCTION



APPROVED BY
NADER ZAKI
MIEAust CPEng NER


0413 942 613
admin@nycivilengineering.com.au
www.nycivilengineering.com.au

REVISION	DRAWN	DESCRIPTION	DATE
A	EM	ISSUED FOR DA	16.01.2024


STORMWATER MANAGEMENT PLAN

PROPOSED SINGLE DWELLING
No. 29 GREENACRE ROAD
GREENACRE

SHEET SIZE A3	JOB REFERENCE
DESIGNED EM	E240659
CHECKED NZ	DRAWING No.
ISSUE A	D2
SCALE 1:200	No. IN SET
	8




FIRST FLOOR PLAN
1:200



ROOF PLAN
1:200

- ROOF DRAINAGE
- GUTTERING - ACE HALF ROUND 150 OR EQUIVALENT GUTTER WITH CROSS SECTIONAL AREA GREATER THAN 6400mm²
 - DOWN PIPES - 90mm DIA PVC OR COLORBOND
- NOTE: ROOF DESIGNED TO 5% AEP INTENSITY 166 mm/hr




PLANS ARE FOR CONCEPT ONLY
AND NOT FOR CONSTRUCTION




APPROVED BY	REVISION	DRAWN	DESCRIPTION	DATE
NADER ZAKI MIEAust CPEng NER  0413 942 613 admin@nycivilengineering.com.au www.nycivilengineering.com.au	A	EM	ISSUED FOR DA	16.01.2024

DRAWING TITLE
STORMWATER MANAGEMENT FIRST FLOOR/ROOF PLAN
PROJECT TITLE
PROPOSED SINGLE DWELLING No. 29 GREENACRE ROAD GREENACRE


SHEET SIZE A3	JOB REFERENCE E240659
DESIGNED EM	DRAWING No. D4
CHECKED NZ	No. IN SET 8
ISSUE A	
SCALE 1:200	



	APPROVED BY	REVISION	DRAWN	DESCRIPTION	DATE	DRAWING TITLE		SHEET SIZE A3	JOB REFERENCE
	NADER ZAKI MIEAust CPEng NER	A	EM	ISSUED FOR DA	16.01.2024	STORMWATER DETAILS		DESIGNED EM	E240659
						PROJECT TITLE		CHECKED NZ	DRAWING No. D5
	0413 942 613					PROPOSED SINGLE DWELLING		ISSUE A	No. IN SET
	admin@nycivilengineering.com.au					No. 29 GREENACRE ROAD		SCALE AS NOTED	8
	www.nycivilengineering.com.au					GREENACRE			





	APPROVED BY	REVISION	DRAWN	DESCRIPTION	DATE	DRAWING TITLE		SHEET SIZE A3	JOB REFERENCE E240659
	NADER ZAKI MIEAust CPEng NER	A	EM	ISSUED FOR DA	16.01.2024	STORMWATER DETAILS		DESIGNED EM	
						PROJECT TITLE		CHECKED NZ	DRAWING No. D6
	0413 942 613					PROPOSED SINGLE DWELLING		ISSUE A	No. IN SET
	admin@nycivilengineering.com.au					No. 29 GREENACRE ROAD		SCALE AS NOTED	8
	www.nycivilengineering.com.au					GREENACRE			



APPROVED BY		REVISION	DRAWN	DESCRIPTION	DATE	DRAWING TITLE		SHEET SIZE A3	JOB REFERENCE
NADER ZAKI MIEAust CPEng NER		A	EM	ISSUED FOR DA	16.01.2024	SEDIMENT CONTROL PLAN		DESIGNED EM	E240659
						PROJECT TITLE		CHECKED NZ	DRAWING No. D7
0413 942 613						PROPOSED SINGLE DWELLING No. 29 GREENACRE ROAD GREENACRE		ISSUE A	No. IN SET
admin@nycivilengineering.com.au								SCALE 1:200	8
www.nycivilengineering.com.au									






SEDIMENT FENCE DETAIL

NTS

CONSTRUCTION NOTES:

1. CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENTS AREA OF ANY ONE SECTION. THE CATCHMENTS AREA SHOULD BE SMALL ENOUGH TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10 YEAR EVENT.
2. CUT A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
3. DRIVE 1.5m LONG STAR PICKETS INTO GROUND AT 2.5m INTERVALS (MAX) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.
4. FIX SELF-SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.
5. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH 150mm OVERLAP.
6. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.




MESH AND GRAVEL FILTER

NTS

CONSTRUCTION NOTES:

1. INSTALL FILTERS TO KERB INLETS ONLY AT SAG POINTS
2. FABRICATE A SLEEVE MADE FROM GEOTEXTILE OR WIRE MESH LONGER THAN THE LENGTH OF THE INLET PIT AND FILL IT WITH 25mm TO 50mm GRAVEL.
3. FORM AN ELLIPTICAL CROSS-SECTION ABOUT 150mm(h) x 400mm(w).
4. PLACE THE FILTER AT THE OPENING LEAVING AT LEAST 100mm SPACE BETWEEN IT AND THE KERB INLET. MAINTAIN THE OPENING WITH SPACER BLOCKS.
5. FORM A SEAL WITH THE KERB TO PREVENT SEDIMENT BYPASSING THE FILTER.
6. SANDBAGS FILLED WITH GRAVEL CAN SUBSTITUTE FOR THE MESH OR GEOTEXTILE PROVIDING THEY ARE PLACED SO THAT THEY FIRMLY ABUT EACH OTHER AND SEDIMENT-LADEN WATERS CANNOT PASS BETWEEN.




STOCKPILE

NTS

NOTE:

1. PLACE STOCKPILES MORE THAN 2 (PREFERABLY 5) METERS FROM EXISTING VEGETATION, CONCENTRATED WATER FLOW, ROADS AND HAZARD AREAS.
2. CONSTRUCT ON THE CONTOUR AS LOW, FLAT, ELONGATED MOUNDS.
3. WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2 METERS IN HEIGHT.
4. WHERE THEY ARE TO BE IN PLACE FOR MORE THAN 10 DAYS, STABILIZE FOLLOWING THE APPROVED ESCP OR SWMP TO REDUCE THE C-FACTOR TO LESS THAN 0.10.
5. CONSTRUCT EARTH BANKS (LOW FLOW) ON THE UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES AND SEDIMENT FENCES 1 TO 2 METERS ON THE DOWNSLOPE.




SEDIMENT BARRIER AROUND PIT

NTS

CONSTRUCTION NOTES:

1. FABRICATE A SEDIMENT BARRIER MADE FROM GEOTEXTILE OR STRAW BALES.
2. FOLLOW STRAW FILTER AND SEDIMENT FENCE FOR INSTALLATION PROCEDURES FOR THE STRAW BALES OR GEOFABRIC. REDUCE THE PICKET SPACING TO 1 METRE CENTRES.
3. IN WATERWAYS, ARTIFICIAL SAG POINTS CAN BE CREATED WITH SANDBAGS OR EARTH BANKS AS SHOWN IN THE DRAWING.
4. DO NOT COVER THE INLET WITH GEOTEXTILE UNLESS THE DESIGN IS ADEQUATE TO ALLOW FOR ALL WATERS TO BYPASS IT.



STABILIZED SITE ACCESS

NTS

CONSTRUCTION NOTES:

1. STRIP THE TOPSOIL, LEVEL THE SITE AND COMPACT THE SUBGRADE
2. COVER THE AREA WITH NEEDLE-PUNCHED GEOTEXTILE
3. CONSTRUCT A 200mm THICK PAD OVER THE GEOTEXTILE USING ROAD BASED OR 30mm AGGREGATE
4. ENSURE THE STRUCTURE IS AT LEAST 15m LONG OR TO BUILD ALIGNMENT AND AT LEAST 3 METERS WIDE.
5. WHERE A SEDIMENT FENCE JOINS ONTO THE STABILIZED ACCESS, CONSTRUCT A HUMP IN THE STABILIZED ACCESS TO DIVERT WATER TO THE SEDIMENT FENCE.



APPROVED BY
NADER ZAKI
MIEAust CPEng NER

0413 942 613
admin@nycivilengineering.com.au
www.nycivilengineering.com.au

REVISION	DRAWN	DESCRIPTION	DATE
A	EM	ISSUED FOR DA	16.01.2024

DRAWING TITLE
SEDIMENT CONTROL DETAILS
PROJECT TITLE
**PROPOSED SINGLE DWELLING
No. 29 GREENACRE ROAD
GREENACRE**

SHEET SIZE A3	JOB REFERENCE E240659
DESIGNED EM	
CHECKED NZ	DRAWING No. D8
ISSUE A	No. IN SET 8
SCALE AS NOTED	