| CALCULATIONS | |
|-----------------------------|----------------|
| EXISTING FLOOR AREA (FSR) | 94.sqm |
| PROPOSED FLOOR AREA (FSR) | 130.2sqm |
| SITE AREA | 301.9sqm |
| PROPOSED FSR | 0.43:1 |
| DEEP SOIL LANDSCAPE AREA | 55sqm (18%) |
| PROPOSED BUILDING FOOTPRINT | 130.2sqm |
| PROPOSED GARAGE FOOTPRINT | 24sqm |
| PROPOSED SITE COVERAGE | 154.2sqm (51%) |
| | |

BASIX COMMITMENTS

HOT WATER SYSTEM - GAS INSTANTANEOUS

THE APPLICANT MUST ENSURE A MINIMUM OF 40% OF NEW OR ALTERED LIGHT FIXTURES ARE FITTED WITH FLUORESCENT, COMPACT FLUORESCENT, OR LIGHT-EMITTING-DIODE (LED) LAMPS.

FIXTURES

THE APPLICANT MUST ENSURE NEW OR ALTERED SHOWERHEADS HAVE A FLOW RATE NO GREATER THAN 9 LITRES PER MINUTE OR A 3 STAR WATER RATING. THE APPLICANT MUST ENSURE NEW OR ALTERED TOILETS HAVE A FLOW RATE NO GREATER THAN 4 LITRES PER AVERAGE FLUSH OR A MINIMUM 3 STAR WATER RATING. THE APPLICANT MUST ENSURE NEW OR ALTERED TAPS HAVE A FLOW RATE NO GREATER THAN 9 LITRES PER MINUTE OR MINIMUM 3 STAR WATER RATING.


EXTERNAL WALL BRICK VENEER R1.16 OR R1.70 INCLUDING CONSTRUCTION

ROOF: FLAT CEILING, PITCHED ROOF: R1.45 (UP), ROOF: FOIL BACKED BLANKET (55mm), MEDIUM SOLAR ABSORPTANCE 0.475


PROPOSED WINDOWS & SKYLIGHTS: AS PER THE VALUES SHOWN IN THE TABLE IN BASIX CERTIFICATE


CONSTRUCTION NOTES

- FABRICATE A SEDIMENT BARRIER FROM GEOTEXTILE MATERIAL
- SUPPORT GEOTILE WITH MESH TIED TO POSTS AT 1m CTS.
- DO NOT COVER INLET WITH GEOTEXTILE




GRAVEL SAUSAGE - GUTTER PROTECTION





NB: PLACE GRAVEL SAUSAGE AROUND THE NEAREST DOWNSTREAM COUNCIL STORMWATER PIT IN THE STREET.



GEOTEXTILE INLET SEDIMENT TRAP

EROSION & SEDIMENT CONTROL DETAILS

0 ш

CONTAINMENT OF SITE WASTE

BUILDING MATERIALS MUST NOT BE BURIED ON SITE. DEMOLITION WASTE RESULTING FROM THE WORKS IS NOT TO BE STORED ON FOOTPATHS, STREET GUTTERS OR ROADWAYS ETC. ALL WASTE TO BE PLACED IN RUBBISH SKIPS OR CONTAINERS FOR COLLECTION.

VEHICLE MOVEMENTS

ALL VEHICLES VISITING THE SITE ARE TO COMPLY WITH THE PARKING REGULATIONS IN THE AREA. ALL VEHICLES ARE TO BE WASHED DOWN BEFORE LEAVING THE SITE. ALL POLLUTED WATERS ARE TO REMAIN ON SITE FOR TREATMENT. ALL TRUCKS AND UTILITIES MUST COVER THEIR LOADS. NO VEHICLE VISITING THE SITE IS TO IMPEDE LOCAL AREA TRAFFIC FLOWS. A LICENSED PERSON WILL DIRECT TRAFFIC AND PEDESTRIANS WHEN TRUCKS ENTER THE SITE.

OBJECTIVES

TO ENSURE THAT NECESSARY MEASURES ARE EMPLOYED ON THE SITE THAT PROTECT BOTH THE NEIGHBOURHOOD AMENITY AND THE SURROUNDING ENVIRONMENT AND MINIMISE SITE DEGRADATION. THE RECYCLING OF MATERIALS WILL REDUCE TIPPING COSTS.

RESPONSIBILITY

THE CONTRACTOR WILL BE RESPONSIBLE AND LIABLE FOR ALL WORKS CARRIED OUT ON THE SITE THIS INCLUDES ASSUMING RESPONSIBLITY FOR THE ACTIONS OF ALL THE SUBCONTRACTORS AS WELL AS ADVISING THEM OF COUNCIL'S REQUIREMENTS WHEN

IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE VIEWED ALL APPROVED PLANS PRIOR TO THE COMMENCEMENT OF DEMOLITION, EARTHWORKS AND CONSTRUCTION WORKS.

COUNCIL PROPERTY

COUNCIL PROPERTY IS NOT TO BE USED FOR CONSTRUCTION OR STORAGE ACTIVITIES UNLESS PRIOR WRITTEN APPROVAL HAS BEEN OBTAINED. COUNCIL PROPERTY IS NOT TO BE DAMAGED AND IS TO BE KEPT IN A CLEAN, SAFE AND FUNCTIONAL CONDITION BEFORE DURING AND ON COMPLETION OF THE WORKS.

SHOULD ANY COUNCIL PROPERTY INCLUDING FOOTPATHS BE INADVERTENTLY DAMAGED AS A RESULT OF THE WORKS, COUNCIL MUST BE NOTIFIED IMMEDIATELY.

OPERATING HOURS

TO MINIMISE UNDUE LOSS OF AMENITY, HOURS OF WORK FOR DEMOLITION / EXCAVATION / CONSTRUCTION ARE TO BE RESTRICTED ABSOLUTELY TO THE HOURS INDICATED IN THE CONDITIONS OF CONSENT, NO PLANT OR MACHINERY MAY MOVE ON OR OFF THE SITE OUTSIDE OF RESTRICTED HOURS OF OPERATION.

LARGE EXCAVATION VEHICLES WAITING TO COMMENCE WORK MUST BE REMOTELY LOCATED FROM THE SITE SO AS NOT TO AFFECT THE LOCAL AMENITY. THE CONTRACTOR IS REPONSIBLE FOR ANY CONTRAVENTION BY SUBCONTRACTORS OF THESE CONDITIONS.

ACCESS POINT

TO LIMIT DISTURBANCE TO THE SITE AND TRACKING OF MATERIAL ONTO THE STREET, ALL VEHICLES AND PLANT EQUIPMENT WILL USE A SINGLE ENTRY / EXIT POINT.

A SEDIMENT CONTROL DEVICE IS TO BE PLACED AT THE SITE ACCESS POINT TO PREVENT SEDIMENT DEPOSITION ON ADJOINING ROADS.

THE CONTRACTOR IS RESPONSIBLE TO REMOVE ANY MATERIAL DEPOSITED OFFSITE AS A RESULT OF SPILLAGE OR VEHICLE MOVEMENT. RESTORE AREA TO PREVIOUS STANDARD OR EQUAL. FORM VEHICLE CROSSING FROM 150x50 HARDWOOD PLANKS. CHAMFERED AT ENDS. LAY OVER 150mm ROAD BASE. TIE WITH HOOP IRON STRAPS AT 600 C/C.

HAZARDOUS MATERIALS

ASBESTOS CEMENT SHEETING IF ENCOUNTERED IS TO BE WRAPPED TIGHTLY IN PLASTIC TO COMPLY WITH THE AUSTRALIAN STANDARD AND WORK COVER AUTHORITIES REQUIREMENTS AND TAKEN TO AN APPROVED LANDFILL TIP.

BUILDING MATERIAL STOCKPILE

AT NO TIME MAY BUILDING MATERIALS OR STOCKPILES BE SITUATED ON A PUBLIC RESERVE, ROAD GUTTER OR FOOTPATH, THIS INCLUDES BUILDING OR DEMOLITION MATERIAL, WASTE CONTAINERS, PROTABLE SHEDS, PORTABLE TOILETS AND THE LIKE ALL BUILDING MATERAILS ARE TO BE STORED WITHIN THE SEDIMEN FENCE ENVELOPE OF THE SUBJECT SITE. ALL LOOSE MATERIAL TO BE COVERED WITH TARPAULINS.

A SUFFICIENT AREA MUST BE ALLOCATED WITHIN THE SITE FOR SUCH STORAGE OF BUILDING MATERIALS, DEMOLITION WASTE, WASTE CONTAINERS ETC. AS REQUIRED. THE FEASIBILITY OF THE NOMINATED SITE FOR THE STOCKPILE MUST BE CONFIRMED PRIOR TO COMMENCEMENT.

DUST CONTROL

APPROPRIATE METHODS ARE TO BE USED TO PREVENT WIND BLOWN DUST CREATING AN UNACCEPTABLE HAZARD OR NUISANCE ON THE SITE OR ADJOINING PROPERTIES. WHERE DUST IS CREATED AS A RESULT OF THE WORKS OR SOIL EXPOSURE. THE BARE SOIL AREAS ARE TO BE WATERED DURING THE DAY AND AT THE END OF DAY TO LAY THE DUST. AVOID EARTH MOVING ACTIVITIES WHEN THE WIND IS STRONG ENOUGH TO RAISE VISIBLE DUST.

AMENDMENTS 27.02.2025 A

REQUEST FOR INFORMATION

SITE PLAN

SCALE: 1:200

THE WORK IS TO BE COMPLETED WITH THE BUILDING CODE OF AUSTRALIA, SAA CODES AND RELEVANT BY-LAWS.

10.0M

THE BUILDING / MANUFACTURER SHALL CHECK AND VERIFY ALL DIMENSIONS, RL GROUNDLINES AND CONSTRUCTION METHODS PRIOR TO COMMENCEMENT OF WORK.

5.0M

200°14'35 39.625

THESE DRAWINGS HAVE BEEN PREPARED BY CORONA PROJECTS AND REMAIN THE PROPERTY OF THE ABOVE NAMED PART. THESE DRAWINGS ARE NOT TO BE USED IN ANY WAY WITHOUT THE PERMISSION OF CORONA PROJECTS AND ARE SUBJECT TO COMPRIGHE SUBJECT TO COPYRIGHT LAWS. A COPY OF THIS PLAN IS TO BE SUBMITTED BY THE

PROPRIETOR TO THE WATERBOARD FOR APPROVAL AS REQUIRED BY THE LOCAL COUNCIL.



PO BOX 1749 BONDI JUNCTION NSW 1355 PHONE: 0419 438 956 EMAIL: info@coronaprojects.com.au

DRAWING: SITE PLAN

PROJECT: **ALTERATIONS ADDITIONS**


SCALE:


1:200 @ A3


ADDRESS: 32 SECOND STREET **ASHBURY**

SHEET No: 01

DATE: FEB. 2025







Shadow Study 21 June at 1600h

| AME | ND | MENTS | |
|------------|----|-------------------------|--|
| 27.02.2025 | Α | REQUEST FOR INFORMATION | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

THE WORK IS TO BE COMPLETED WITH THE BUILDING CODE OF AUSTRALIA, SAA CODES AND RELEVANT BY-LAWS.

THE BUILDING / MANUFACTURER SHALL CHECK AND VERIFY ALL DIMENSIONS, RL GROUNDLINES AND CONSTRUCTION METHODS PRIOR TO COMMENCEMENT OF WORK.

THESE DRAWINGS HAVE BEEN PREPARED BY CORONA PROJECTS AND REMAIN THE PROPERTY OF THE ABOVE NAMED PART. THESE DRAWINGS ARE NOT TO BE USED IN ANY WAY WITHOUT THE PERMISSION OF CORONA PROJECTS AND ARE SUBJECT TO COPYRIGHT LAWS.

A COPY OF THIS PLAN IS TO BE SUBMITTED BY THE PROPRIETOR TO THE WATERBOARD FOR APPROVAL AS REQUIRED BY THE LOCAL COUNCIL.

| | Corona | projects | |
|---|--------|----------|--|
| 7 | | | |

| PO BOX 1749 BONDI JUNCTION NSW 1355 | |
|-------------------------------------|--|
| PHONE: 0419 438 956 | |
| EMAIL: info@coronaprojects.com.au | |

| DRAWING: SHADOW DIAGRAMS SHEET 5 | PROJECT: ALTERATIONS ADDITIONS | SHEET No: |
|-------------------------------------|-----------------------------------|-----------|
| SCALE: | ADDRESS: 32 SECOND STREET ASHBURY | DATE: |
| 1:200 @ A3 | | FEB. 2025 |