34 HIGHLAND AVENUE, BANKSTOWN STORMWATER MANAGEMENT PLANS

STORMWATER DESIGN NOTES

- 1. ALL DRAINAGE WORKS ARE TO BE IN ACCORDANCE WITH AS/NZS 3500.3 STORMWATER DRAINAGE, CANTERBURY-BANKSTOWN DEVELOPMENT CONTROL PLAN 2023.
- 2. THE SITE IS FLOOD AFFECTED BASED ON A DESKTOP ASSESSMENT OF COUNCILS STORMWATER SYSTEM REPORT.
- 3. THE SITE AREA = 1214 m2
- TOTAL SITE EXISTING IMPERVIOUS AREA = 288 m2 (24%)
- TOTAL SITE PROPOSED IMPERVIOUS AREA = 589 m2 (49%)
- 4. OSD IS NOT REQUIRED FOR THE DEVELOPMENT BASED ON A DESKTOP ASSESSMENT OF DUAL OCCUPANCY DEVELOPMENT WITH IMPERVIOUS AREA IS LESS THAN 66% OF SITE AREA.
- 5. RAINWATER TANK IS NOT REQUIRED FOR THE DEVELOPMENT BASED ON A DESKTOP ASSESSMENT OF THE LASTEST BASIX CERTIFICATE.
- 6. THE POINT OF DISCHARGE SHALL BE VIA NEW KERB AND GUTTER CONNECTION WITHIN STREET FRONTAGE.

ABBREVIATIONS

LEVELS

FFL FINISHED FLOOR LEVEL

IL INVERT LEVEL

RL REDUCED LEVEL

H/L HIGH LEVEL

L/L LOW LEVEL

+ NEW REDUCED LEVEL

X EXISTING LEVEL

AHD AUSTRALIAN HEIGHT DATUM

OFP OVERLAND FLOW PATH

SSL STRUCTURAL SLAB LEVEL

SRZ STRUCTURAL ROOT ZONE

TRZ TREE ROOT ZONE

UNO UNLESS NOTED OTHERWISE

FIXTURES

RWO RAINWATER OUTLET

SWP STORMWATER PIT (GRATE/SEALED)

PBO PLANTER BOX OUTLET


CO CLEAR OUT

GD GRATED TRENCH DRAIN

RWT RAINWATER TANK

KERB INLET PIT

SERVICES LEGEND





SITE LOCALITY PLAN

ROOF DRAINAGE FIXTURES

RHS RECTANGULAR HOLLOW SECTION

O/F OVERFLOW

SP SPREADER


DP DOWN PIPE

RH RAINWATER HEAD


BALCONY OUTLET

DRAWING LIST						
DRAWING NUMBER	DRAWING NAME					
2024H0048-SW01	COVER SHEET, NOTES & LEGEND					
2024H0048-SW02	SEDIMENT AND EROSION CONTROL PLAN					
2024H0048-SW03	CATCHMENT PLAN					
2024H0048-SW04	GROUND FLOOR PLAN					
2024H0048-SW05	DETAILS SHEET					

				STORMWATER MANAGEMENT PLANS	LISA LE	DESIGNER ENGINEER	T.N	DAT
				COVER SHEET, NOTES & LEGEND	PROJECT NAME 34 HIGHLAND AVENUE, BANKSTOWN	VERIFIER	L.N	SCA
P'	1 T.D	+	ISSUED FOR DA DESCRIPTION	DRAWING # 2024H0048-SW01 REVISION P1		© THIS DRAWING AND I PART OF THIS DRAWING WRITTEN CONSENT FRO	G OR DESIGN SHALL B	E REF








0

GEOTEXTILE INLET FILTER (FOR PITS WITHIN PAVEMENT AREAS)


MESH & GRAVEL INLET FILTER



CONSTRUCTION NOTES:

- PLACE STOCKPILES MORE THAN 2 (PREFERABLY S) METRES FROM EXISTING VEGETATION, CONCENTRATED WATER FLOW, ROADS AND HAZARD AREAS.
 CONSTRUCT ON THE CONTOUR AS LOW, FLAT, ELONGATED MOUNDS.
 WHERE THERE IS SUFFICIENT AREA, TOPSOIL STOCKPILES SHALL BE LESS THAN 2 METRES IN
- HEIGHT.
 WHERE THEY ARE TO BE IN PLACE FOR MORE THAN 10 DAYS, STABILISE FOLLOWING THE
 APPROVED ESCP OR SWMP TO REDUCE THE C-FACTOR TO LESS THAN 0.10.
- 5 CONSTRUCT FARTH BANKS (STANDARD DRAWING 5-5) ON THE UPSLOPE SIDE TO DIVERT WATER AROUND STOCKPILES AND SEDIMENT FENCES (STANDARD DRAWING 6-8) 1 TO 2 METRES

STOCK PILE DETAIL




GEOFABRIC MAY BE A WOVEN OR NEEDLE-PUNCHED PRODUCT WITH A MINIMUM CBR BURST STRENGTH (AS3706.4-90) OF 2500 N


CONSTRUCTION NOTES:

- 1. STRIP THE TOPSOIL, LEVEL THE SITE AND COMPACT THE SUBGRADE. 2. COVER THE AREA WITH NEEDLE-PUNCHED GEOTEXTILE. 3. CONSTRUCT A 200mm THICK PAD OVER THE GEOTEXTILE USING ROAD BASE OR 30mm AGGREGATE. . ENSURE THE STRUCTURE IS AT LEAST 15m LONG OR TO BUILDING ALIGNMENT AND AT LEAST 3m WIDE
- 5. WHERE A SEDIMENT FENCE JOINS ONTO THE STABILISED ACCESS, CONSTRUCT A HUMP IN THE STABILISED

STABILISED SITE ACCESS WITH SHAKER GRID DETAIL

NOT TO SCALE





- CONSTRUCTION NOTES:


 1. INSTALL FILTERS TO KERB INLETS ONLY AT SAG POINTS.

 2. FABRICATE A SLEEVE MADE FROM GEOTEXILE OR WIRE MESH LONGER THAN THE LENGTH OF THE INLET PIT AND FILL IT WITH 25mm TO 50mm GRAVEL.

 3. FORM AN ELLIPTICAL CROSS-SECTION ABOUT 150mm HIGH x 400mm WIDE.

- FORM AN ELLIP ILLA CROSS-SELION ABOUT 150mm HIGH x 400mm WIDE.
 PLACE THE FILTER AT THE OPENING LEAVING AT LEAST A 100mm SPACE
 BETWEEN IT AND THE KERB INLET. MAINTAIN THE OPENING WITH SPACER BLOCKS.
 FORM A SEAL WITH THE KERB TO PREVENT SEDIMENT BYPASSING THE FILTER.
 SANDBAGS FILLED WITH GRAVEL CAN SUBSTITUTE FOR THE MESH OR
 GEOTEXTILE PROVIDING THEY ARE PLACED SO THAT THEY FIRMLY ABUT EACH
 OTHER AND SEDIMENT-LADEN WATERS CANNOT PASS BETWEEN.

MESH AND GRAVEL INLET FILTER DETAIL



CONSTRUCTION NOTES:

- CONSTRUCTION NOT LES.

 1. CONSTRUCT SEDIMENT FENCES AS CLOSE AS POSSIBLE TO BEING PARALLEL TO THE CONTOURS OF THE SITE, BUT WITH SMALL RETURNS AS SHOWN IN THE DRAWING TO LIMIT THE CATCHMENT AREA OF ANY ONE SECTION. THE CATCHMENT AREA SHOULD BE SMALL ENDUGHT TO LIMIT WATER FLOW IF CONCENTRATED AT ONE POINT TO 50 LITRES PER SECOND IN THE DESIGN STORM EVENT, USUALLY THE 10-YEAR EVENT.

 2. CLIT A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTENDED.
- ENTRENCHED.
- ENTRENCHED.

 3. DRIVE 15, METRE LONG STAR PICKETS INTO THE GROUND AT 2.5 METRE INTERVALS (MAX) AT THE DOWNSLOPE EDGE OF THE TRENCH. ENSURE ANY STAR PICKETS ARE FITTED WITH SAFETY CAPS.

 4. FIX SELF SUPPORTING GEOTEXTILE TO THE UPSLOPE SIDE OF THE POSTS ENSURING IT GOES TO THE BASE OF THE TRENCH. FIX THE GEOTEXTILE WITH WIRE TIES OR AS RECOMMENDED BY THE MANUFACTURER. ONLY USE GEOTEXTILE SPECIFICALLY PRODUCED FOR SEDIMENT FENCING. THE USE OF SHADE CLOTH FOR THIS PURPOSE IS NOT SATISFACTORY.

 5. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150-DIM OVERLAP.
- 6. BACKFILL THE TRENCH OVER THE BASE OF THE FABRIC AND COMPACT IT THOROUGHLY OVER THE GEOTEXTILE.

SEDIMENT FENCE DETAIL

NOT TO SCALE


					STORMWATER MANAGEMENT PLAN	NS	
					SEDIMENT AND EROSION CONTROL	PLAN	
P1	T.D	04.11.2024	L.N	ISSUED FOR DA			
REV.	DES.	DATE	VER.	DESCRIPTION	DRAWING # 2024H0048-SW02	REVISION	P1

LISA LE 34 HIGHLAND AVENUE, BANKSTOWN


OJECT NORTH POINT

SIGNER	T.N	DATE CREATED 04.11.2024	THIS DRAWING IS NOT TO BE USED FOR TENDER/CONSTRUCTION UNLESS ENDORSED BELOW
GINEER	L.N	STATUS DA	PROJECT SUPERINTENDENT'S SIGNATURE: DATE:
RIFIER	L.N	SCALE @ A3 AS SHOWN	
		IGHT OF LEOPARD ENGINEERING GROUP. NO E REPRODUCED OR USED WITHOUT PRIOR	





PRE-DEVELOPED IMPERVIOUS CATCHMENT PLAN SCALE 1:250




POST-DEVELOPED IMPERVIOUS CATCHMENT PLAN


SCALE 1:250

	1				STORMWATER MANAGEMI	ENT PLANS		LISA LE	PROJECT NORTH POINT
P1	T.D.	04 11 2024	I.N	ISSUED FOR DA	CATCHMENT PLAN			34 HIGHLAND AVENUE, BANKSTOWN	
REV.	DES.	DATE		DESCRIPTION	DRAWING # 2024H0048-SW03	REVISION	P1		


DESIGNER	T.N	DATE CREATED 04.11.2024	THIS DRAWING IS NOT TO BE USED FOR TENDER/CONSTRUCTION UNLESS ENDORSED BELOW
ENGINEER	L.N	STATUS DA	PROJECT SUPERINTENDENT'S SIGNATURE: DATE:
VERIFIER	L.N	SCALE @ A3 AS SHOWN	
PART OF THIS I		IGHT OF LEOPARD ENGINEERING GROUP. NO E REPRODUCED OR USED WITHOUT PRIOR TING ENGINEERS GROUP	







TRENCH GRATE (200mm WIDE) CLASS D




ABOVE GROUND RAINWATER STORAGE TANK


								CLIENT					
					STORMWATER MANAGEMENT PLANS				T STORMWATER MANAGEMENT PLANS LISA LE				LISA LE
									PROJECT NAME				
\vdash	_				DETAILS SHEET				34 HIGHLAND AVENUE, BANKSTOWN				
\vdash	_		-		1 2	20 011221	ST THEREPARE TO THE PROPERTY OF THE PROPERTY O						
LF	1 T.D	04.11.2024	L.N	ISSUED FOR DA									
RI	V. DES.	DATE	VER.	DESCRIPTION	DRAWING #	2024H0048-SW05	REVISION	P1					

MAINTENANCE ACTION FREQUENCY RESPONSIBILITY PROCEDURE

SILT TRAP PIT MONTHLY AND AFTER HEAVY RAINFALL EVENTS OPEN GRATE AND REMOVE TRASH OR LEAF LITTER THAT HAS BEEN CAPTURED BY THE TRASH SCREEN. REMOVE ALL SILT IN SUMP AND DISPOSE IN GARDEN WASTE BIN. REMOVE ANY BLOCKAGES OVER WEEP HOLES IN BASE. ENSURE TRASH SCREEN IS SECURELY FIXED AND REPLACE GRATE CORRECTLY.



PROJECT NORTH POINT



SILT TRAP TRASH SCREEN DETAIL


N.T.S.

NOTES
1) PIT DIMENSIONS:
600 x 600 FOR < D ≤ 0.9
600 x 900 FOR 0.9 < D ≤ 1.2
900 x 900 FOR 1.2 < D (AS SHOWN ON PLAN)

2) PITS TO BE CONSTRUCTED FROM – CAST IN–SITU CONCRETE, PRECAST CONCRETE OF DOUBLE BRICK.

3) A SIGN SHALL BE CONSTRUCTED ADJACENT TO THE PIT STATING: "THIS SEDIMENT / SILT ARRESTOR PIT SHALL BE REGULARLY INSPECTED AND CLEANED".





TRENCH GRATE (100mm WIDE) CLASS B

DESIGNER	T.N	DATE CREATED 04.11.2024	THIS DRAWING IS NOT TO BE USED FOR TENDER/CONSTRUCTION UNLESS ENDORSED BELOW	
ENGINEER	L.N	STATUS DA	PROJECT SUPERINTENDENT'S SIGNATURE: DATE:	İ
VERIFIER	L.N	SCALE @ A3 AS SHOWN		CI
PART OF THIS DRA		GHT OF LEOPARD ENGINEERING GROUP. NO E REPRODUCED OR USED WITHOUT PRIOR TING ENGINEERS GROUP.		ABN E: i

