

PROPOSED SUBDIVISION

202 BUSHLAND DRIVE


TAREE

AJA DEVELOPMENTS

MIDCOAST COUNCIL

NOTES:

1. ALL DIMENSIONS OF EASEMENTS AND LOTS ARE SUBJECT TO REGISTRATION OF DEPOSITED PLAN.
2. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL'S STANDARD SPECIFICATIONS FOR ROADWORKS, WATER SUPPLY, SEWER, STORMWATER AND OTHER ASSOCIATED WORKS.
3. EROSION CONTROL DEVICES AND SILTATION TRAPS TO BE INSTALLED BEFORE SITE IS DISTURBED IN ACCORDANCE WITH THE ATTACHED SILTATION PLAN.
4. DENUDED AREAS TO BE REGRASSED ON COMPLETION OF WORKS.
5. ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS THE RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION & LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.
6. PAVEMENT THICKNESS TO BE IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE GEOTECHNICAL ENGINEER..
7. WORKING HOURS ON SITE SHALL BE IN ACCORDANCE WITH EPA & COUNCIL REQUIREMENTS.
8. VEHICULAR ACCESS AND ALL SERVICES ARE TO BE MAINTAINED AT ALL TIMES TO ADJOINING PROPERTIES AFFECTED BY CONSTRUCTION WORKS.
9. MAINTENANCE ON THE SEEDED AND TURFED AREAS SHALL BE OVER A 3 MONTH PERIOD. TURF THE FULL WIDTH OF ALL EARTH DISH DRAINS. WHERE NOT NOTED LAY 600mm WIDE TURF STRIPS TO EACH SIDE OF CONCRETE ACCESSWAYS, PATHWAYS, AT THE REAR OF ALL KERB AND GUTTERING AND AT THE TOP OF CUT BATTERS. MULCH (IF AVAILABLE FROM SITE CLEARING) AND SEED ALL OTHER DISTURBED AREAS, INCLUDING TRENCHES.
10. TRAFFIC CONTROL MEASURES TO BE IN ACCORDANCE WITH AS 1742.3-1996.
11. ALL LEVELS MUST BE OBTAINED FROM ESTABLISHED BENCH MARKS AS DIRECTED BY THE SUPERVISOR.
12. THE CONTRACTOR IS TO ENSURE THAT ALL THE NECESSARY SERVICE PIPE CONDUITS AND FITTINGS ARE IN PLACE PRIOR TO THE FINAL WEARING COURSE BEING LAID.
13. PROVIDE STREET NAME SIGNS AT ALL INTERSECTIONS, DOUBLE BLADED WHERE NECESSARY.
14. ALL SITE FILLING TO BE CONTROLLED FILL TO AS3798 WITH TESTING TO BE CARRIED OUT BY A NATA REGISTERED LABORATORY.
15. PAVEMENT PROOF ROLLING AND LEVEL CHECKS TO BE IN ACCORDANCE WITH STANDARD COUNCIL REQUIREMENTS.



DRAWING SCHEDULE JOB NUMBER HD336 DA2


DATE - 28.05.2025		DA ISSUE
DWG No.	SHEET TITLE	REV
S00	COVER SHEET	C6
S01	OVERALL SUBDIVISION PLAN	C6
S02	LOT 3 DEVELOPMENT OVERALL PLAN	C6
S03	LOT 3 DETAIL PLAN SHEET 1 OF 4	C6
S04	LOT 3 DETAIL PLAN SHEET 2 OF 4	C6
S05	LOT 3 DETAIL PLAN SHEET 3 OF 4	C6
S06	LOT 3 DETAIL PLAN SHEET 4 OF 4	C6
S07	BUSHLAND DRIVE INTERSECTION PLAN 1 OF 2	C6
S08	BUSHLAND DRIVE INTERSECTION PLAN 2 OF 2	C6
S09	ROUNDBABOUT PLAN SHEET	C6
S10	ROAD 1 LONGITUDINAL SECTION	C6
S11	ROAD 1 CROSS SECTIONS 1 OF 2	C6
S12	ROAD 1 CROSS SECTIONS 2 OF 2	C6
S13	TYPICAL SECTION	C6
S14	BASIN PLAN	C6
S15	CONSTRUCTION NOTES	C6
S16	HEADWALL AND BASE SLAB DETAILS	C6
S17	SEDIMENT AND EROSION CONTROL PLAN	C6
S18	SEDIMENT AND EROSION CONTROL NOTES 1 OF 3	C6
S19	SEDIMENT AND EROSION CONTROL NOTES 2 OF 3	C6
S20	SEDIMENT AND EROSION CONTROL NOTES 3 OF 3	C6
S21	ROUNDBABOUT TURNING MOVEMENTS 1 OF 2	C6
S22	ROUNDBABOUT TURNING MOVEMENTS 2 OF 2	C6
S23	BULK EARTHWORKS PLANS	C6

DA2 ISSUE



LEGEND

- PROPOSED INDUSTRIAL / COMMERCIAL LOTS
LOT 1 AND LOT 2
- PROPOSED COMMERCIAL LOT (BULKY GOODS)
LOT 3
- PROPOSED PUBLIC RESERVE
- PROPOSED PUBLIC ROAD
- PROPOSED EASEMENT FOR DRAINAGE
WITHIN LOT 3



LEGEND

- PROPOSED STORMWATER PIPE
- EXISTING SEWER MAIN
- EXISTING OVERHEAD POWER
- PROPOSED SEWER MANHOLE
- PROPOSED SAG PIT
- PROPOSED EKI PIT
- PROPOSED IAD PIT

- EXISTING WATER MAIN
- PROPOSED WATER MAIN
- EXISTING SEWER
- PROPOSED SEWER
- EXISTING OVERHEAD POWER

TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

SUBDIVISION PLAN

CLIENT: AJA DEVELOPMENTS

High Definition Design Pty Ltd

KEVIN URANE 0412009891

NOTE:

ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

0 10 20 30 40 50 m


1:500 (H)

Date: 11.04.23		Scale: 1:500 A1		Designed: KU		Project No	
Cad Ref: HD336 Civil COMMERCIAL R6						HD336	
C6	AMEND FLOOR LEVELS			KU	28.05.25	Drawing No	Revision
C5	DA ISSUE			KU	20.05.25	S01	C6
No	Amendment			Drawn	Date		



LEGEND

- PROPOSED STORMWATER PIPE
- EXISTING SEWER MAIN
- EXISTING SEWER MANHOLE
- EXISTING SEWER MAIN
- PROPOSED SEWER MANHOLE
- PROPOSED STORMWATER PIT
- PROPOSED SAG PIT
- PROPOSED EKI PIT
- PROPOSED WATER MAIN
- EXISTING WATER MAIN
- PROPOSED RETAINING WALLS
- PROPOSED DESIGN LEVELS
- PROPOSED STORMWATER INVERT LEVELS



TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

OVERALL PLAN

CLIENT: AJA DEVELOPMENTS

KEVIN URANE 0412009891

High Definition Design Pty Ltd

NOTE:

ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

0 10 20 30 40 50 m
1:500 (H)

Date: 10.05.25 Scale: 1:500 A1
Cad Ref: HD336 Civil COMMERCIAL R6

Designed: KU


Project No


HD336

C6	AMEND FLOOR LEVELS	KU	28.05.25
C5	DA ISSUE	KU	10.05.25
No	Amendment	Drawn	Date

Drawing No
S02

Revision
C6





LEGEND

--- PROPOSED STORMWATER PIPE

--- EXISTING SEWER MAIN

● EXISTING SEWER MANHOLE

--- EXISTING SEWER MAIN

● PROPOSED SEWER MANHOLE

■ PROPOSED STORMWATER PIT

■ PROPOSED SAG PIT

■ PROPOSED EKI PIT

--- PROPOSED WATER MAIN


--- EXISTING WATER MAIN

--- PROPOSED RETAINING WALLS

19.5 PROPOSED DESIGN LEVELS

IL15.8 PROPOSED STORMWATER INVERT LEVELS

EXISTING Ø375 SEWER MAIN




TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

PLAN SHEET 3 OF 4

CLIENT: AJA DEVELOPMENTS


KEVIN URANE 0412009891



NOTE:
ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.



Date: 20.02.25		Scale: 1:300 A1		Designed: KU		Project No	
Cad Ref: HD336 Civil COMMERCIAL R6						HD336-DA2	
C6	AMEND FLOOR LEVELS			KU	28.05.25	Drawing No S05	Revision C6
C5	DA ISSUE			KU	20.05.25		
No	Amendment			Drawn	Date		



LEGEND


- PROPOSED STORMWATER PIPE
- EXISTING SEWER MAIN
- EXISTING SEWER MANHOLE
- EXISTING SEWER MAIN
- PROPOSED SEWER MANHOLE
- PROPOSED STORMWATER PIT
- PROPOSED SAG PIT
- PROPOSED EKI PIT
- PROPOSED WATER MAIN
- EXISTING WATER MAIN
- PROPOSED RETAINING WALLS
- PROPOSED DESIGN LEVELS
- PROPOSED STORMWATER INVERT LEVELS

TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

PLAN SHEET 4 OF 4

CLIENT: AJA DEVELOPMENTS


KEVIN URANE 0412009891




NOTE:
ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.



Date:	20.02.25	Scale:	1:300 A1	Designed:	KU	Project No	HD336-DA2	
Cad Ref:	HD336 Civil COMMERCIAL R6					Drawing No	S06	Revision
C6	AMEND FLOOR LEVELS			KU	28.05.25	C6		
C5	DA ISSUE			KU	20.05.25			
No	Amendment			Drawn	Date			





TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE
INTERSECTION PLAN 2 OF 2
CLIENT: AJA DEVELOPMENTS


High Definition Design Pty Ltd

KEVIN URANE 0412009891

NOTE:
ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

0 10 20 30 40 50 m
1:500 (H)

Date: 20.02.25		Scale: 1:400 A1		Designed: KU		Project No	
Cad Ref: HD336 Civil		COMMERCIAL R6				HD336-DA2	
C6	AMEND FLOOR LEVELS			KU	28.05.25	Drawing No	Revision
C5	DA ISSUE			KU	20.05.25		
No	Amendment			Drawn	Date		
						S08	C6




LEGEND

- PROPOSED STORMWATER PIPE
- PROPOSED STORMWATER PIT
- PROPOSED STORMWATER ROAD PIT

NOTE:

ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.




TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

ROUNABOUT PLAN SHEET

CLIENT: AJA DEVELOPMENTS

High Definition Design Pty Ltd
KEVIN URANE 0412009891

Date: 20.02.25		Scale: 1:300 A1		Designed: KU		Project No	
Cad Ref: HD336 Civil		COMMERCIAL R6				HD336 DA2	
C6	AMEND FLOOR LEVELS			KU	28.05.25	Drawing No	Revision
C5	DA ISSUE			KU	20.05.25	S09	C6
No	Amendment			Drawn	Date		




ROAD 1 LONGITUDINAL SECTIONS

TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

ROAD 1 LONG SECTIONS

CLIENT: AJA DEVELOPMENTS











KEVIN URANE 0412009891

NOTE:
ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

0 10 20 30 40 50 m
1:500 (H)


Date: 20.02.25		Scale: 1:300 A1		Designed: KU		Project No	
Cad Ref: HD336 Civil		COMMERCIAL R6				HD336 DA2	
C6	AMEND FLOOR LEVELS			KU	28.05.25	Drawing No S10	Revision C6
C5	DA ISSUE			KU	20.05.25		
No	Amendment			Drawn	Date		



TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

ROAD 1 CROSS SECTIONS 1 OF 2





CLIENT: AJA DEVELOPMENTS







KEVIN URANE 0412009891

NOTE:
ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

Date:	11.04.23	Scale:	1:100 A1	Designed:	KU	Project No	HD336 DA2
Cad Ref:	HD336 Civil COMMERCIAL R6					Drawing No	S11
C6	AMEND FLOOR LEVELS			KU	28.05.25	Revision	C6
C5	DA ISSUE			KU	20.05.25		
No	Amendment			Drawn	Date		



Scale Horizontal 1:100 Vertical 1:100



TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE


ROAD 1 CROSS SECTIONS 2 OF 2

CLIENT: AJA DEVELOPMENTS

KEVIN URANE 0412009891

NOTE:

ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.



Date: 11.04.23 Scale: 1:100 A1
Cad Ref: HD336 Civil COMMERCIAL R6

Designed: KU

Project No	
------------	--

HD336 DA2

5	Drawing No
---	------------

Revision

5 S12

C6

	C6
--	----

AMEND FLOOR LEVELS

KU

	28.05.25
--	----------

	C5
--	----

DA ISSUE

KU


	20.05.25
--	----------

No


Amendment

Drawn


Date	
------	--



TYPICAL CROSS SECTION - ROAD 1 (13m WIDE PAVEMENT)
SCALE 1:50



TYPICAL CROSS SECTION - SWALE DRAIN 1
SCALE 1:25



TYPICAL CROSS SECTION - SWALE DRAIN 2
SCALE 1:25

TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

TYPICAL CROSS SECTION

CLIENT: AJAN DEVELOPMENTS

High Definition

Design Pty Ltd

KEVIN URANE 0412009891


NOTE:

ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

0 10 20 30 40 50 m

1:500 (H)

Date:	11.04.23	Scale:	1:50 A1	Designed:	KU	Project No	HD336
Cad Ref:	HD336 Civil COMMERCIAL R6					Drawing No	S13
C6	AMEND FLOOR LEVELS	KU	28.05.25			Revision	C6
C5	DA ISSUE	KU	20.05.25				
No	Amendment	Drawn	Date				



TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

BASIN PLAN

CLIENT: AJA DEVELOPMENTS

High Definition Design Pty Ltd

KEVIN URANE 0412009891

NOTE:
ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

0 4 8 12 16 20 m
1:200 (H)

Date: 11.04.23 Scale: 1:200 A1 Designed: KU
Cad Ref: HD336 Civil COMMERCIAL R6

C6	AMEND FLOOR LEVELS	KU	28.05.25
C5	DA ISSUE	KU	20.05.25
No	Amendment	Drawn	Date

Project No: HD336 DA2
Drawing No: S14 Revision: C6

EMBANKMENT FOUNDATION TREATMENT

BASED ON THE SUBSURFACE CONDITIONS ENCOUNTERED DURING THE INVESTIGATION IN THE PROPOSED BASIN ENVELOPES AND REVIEW OF THE DESIGN PLANS, EMBANKMENT FOUNDATION CONDITIONS ARE EXPECTED TO BE WITHIN THE RESIDUAL CLAY OR EXTREMELY WEATHERED MATERIAL.

THE FOLLOWING GENERAL FOUNDATION PREPARATION REQUIREMENTS MUST BE ADOPTED:

1. REMOVAL OF TOPSOIL AND WEAK, COMPRESSIBLE SOILS.
2. EXCAVATION TO DESIGN LEVELS AND STOCKPILING OF SUITABLE MATERIAL FOR REUSE AS ZONE 1 AND 2 FILL.
3. STATIC PROOF-ROLLING OF THE EXPOSED FOUNDATION AREA UNDER THE EMBANKMENT WITH A HEAVY (MINIMUM 10 TONNE) ROLLER. SOFT OR WEAK AREAS DETECTED DURING THE PROOF ROLLING SHALL BE EXCAVATED AND REPLACED WITH COMPACTED FILL COMPRISING LOW PERMEABILITY CLAY MEETING THE REQUIREMENTS OF ZONE 1 MATERIAL.
4. PROTECTION OF THE PREPARED FOUNDATION TO PREVENT EXCESSIVE WETTING OR DRYING PRIOR TO PLACEMENT OF EMBANKMENT FILL MATERIAL. TRAFFICKING OF THE EXPOSED FOUNDATION SHOULD BE LIMITED (OR AVOIDED WHERE POSSIBLE) TO PREVENT PERMANENT DEFORMATION.
5. INSPECTION OF CONTROLLED FILLING FOUNDATION BY AN EXPERIENCED GEOTECHNICAL CONSULTANT TO ASSESS POTENTIAL DEFECTS AND POTENTIAL SEEPAGE.

IMPOUNDMENT AREA

BASED ON THE EXCAVATED TEST PITS AND PROPOSED DESIGN LEVELS, THE ENTIRE IMPOUNDMENT AREA IS EXPECTED TO BE FORMED THROUGH EXCAVATIONS INTO THE RESIDUAL CLAY AND WEATHERED ROCK MATERIAL. DUE TO THE PRESENCE OF STILL-HARD RESIDUAL CLAYS AND EWM, IT IS EXPECTED A CLAY CORE WOULD NOT BE REQUIRED. INSTEAD, IT IS CONSIDERED THE APPLICATION OF A 500mm THICK CLAY LINER WOULD BE MORE SUITABLE FOR IMPOUNDMENT AREA TREATMENT TO PREVENT POTENTIAL SEEPAGE.

FOUNDATION PREPARATIONS FOR HE APPLICATION OF THE CLAY LINER WOULD COMPRISE:

- (A) EXCAVATION TO DESIGN LEVELS AND STOCKPILING OF SUITABLE MATERIAL FOR REUSE.
- (B) STATIC PROOF-ROLLING/ INSPECTION OF THE EXPOSED IMPOUNDMENT AREA BY A SUITABLE QUALIFIED GEOTECHNICAL CONSULTANT.
- (C) PROTECTION OF THE PREPARED FOUNDATION TO PREVENT EXCESSIVE WETTING OR DRYING PRIOR TO PLACEMENT OF CLAY LINER.
- (D) TRAFFICKING OF THE EXPOSED FOUNDATION SHOULD BE LIMITED (OR AVOIDED WHERE POSSBLE) TO PREVENT DEFORMATION.

FOLLOWING FOUNDATION PREPARATION, APPLICATION OF THE CLAY LINER WOULD THEN BE UNDERTAKEN. THIS WOULD COMPRISE:

- (A) COMPACTION OF THE CLAY MATERIAL TO SPECIFICATIONS OUTLINED IN TABLE 1-4 (REFER TO GEOTECHINCAL REPORT) WITHIN THE IMPOUNDMENT AREA.
- (B) CLAY IS TO BE ROLLED AND COMPACTED TO SPECIFIED LIMITS IN TWO (2) 250mm COMPACTED LAYERS UTILISING A PAD FOOT ROLLER.
- (C) SLIGHT OVERFILLING WILL BE REQUIRED SUCH THAT TRIMMING BACK TO SUITABLY COMPACTED CLAY IS UNDERTAKEN.
- (D) FOLLOWING TRIMMING WORKS, INSPECTION WILL BE REQUIRED BY A SUITABLY QUALIFIED GEOTECHNICAL CONSULTANT.

STORMWATER OUTLETS AND SEEPAGE COLLARS

A SEEPAGE COLLAR WILL BE REQUIRED TO BE CONSTRUCTED ALONG THE STORMWATER PIPES TRAVERSING THE DAM EMBANKMENT TO INCREASE THE LENGTH OF THE PERCOLATION PATH AND REDUCE THE RISK OF PIPING DEVELOPING AROUND THE STORMWATER PIPES.

SEEPAGE COLLARS ARE GENERALLY MADE OF CONCRETE WITH A REQUIRED WIDTH DEPENDING ON PIPE DIAMETER BUT ARE TYPICALLY THREE TIMES THE PIPE DIAMETER.

ON THE BASIS THAT THE PROPOSED BOX CULVERT INCLUDES WING WALLS ON EACH END AND THAT THE CONSTRUCTION INCLUDES A SUBSOIL DRAINAGE PIPE ON EACH SIDE EMBEDDED IN 10mm AGGREGATE, NO SEEPAGE COLLAR WOULD BE REQUIRED AS PART OF THE BOX CULVER CONSTRUCTION.

SURFACE EROSION CONTROL

TOPSOIL SHALL BE SPREAD OVER THE EXPOSED SURFACES OF THE EMBANKMENT TO A DEPTH OF AT LEAST 150MM AND SOWN WITH PASTURE GRASS TO ESTABLISH A GOOD COVER AS SOON AS PRACTICAL.

LARGE VEGETATION (TREES) WOULD BE CONSIDERED SUITABLE FOR THE FLATTER PORTIONS OF THE CENTRAL IMPOUNDMENT AREA, HOWEVER , SHALL NOT BE PLANTED ON BATTERS ASSOCIATED WITH THE BASIN. SHRUBS WOULD BE CONSIDERED A MORE SUITABLE OPTION FOR BATTERS OF THE BASIN.

ROCK RIP RAP SCOUR PROTECTION SHALL BE INCLUDED FOR EROSION CONTROL AT ALL INLET AND OUTLET POINTS INCLUDING EMERGENCY SPILLWAYS.

CONSTRUCTION SEQUENCING FOR BASIN SHALL BE AS FOLLOWS:

PHASE 1 - THE FACILITY SHALL BE CONSTRUCTED TO OPERATE AS SEDIMENT BASIN INITIALLY. ALL FINAL INLET AND OUTLET STRUCTURES SHALL BE INSTALLED AT THIS STAGE (UNLESS ALTERNATE ARRANGEMENTS HAVE BEEN MADE PRIOR WITH COUNCIL AGREEMENT). THE FACILITY SHALL BE MAINTAINED AS A SEDIMENT BASIN UNTIL THE CATCHMENTS DRAINING TO IT HAS BEEN SUBSTANTIALLY DEVELOPED.


PHASE 2- ONCE THE CATCHMENT HAS BEEN SUBSTANTIALLY DEVELOPED, THE SEDIMENT BASIN SHALL BE DECOMMISSIONED AND THE FINAL APPROVED FACILITY CONSTRUCTED AND LANDSCAPED. THIS WILL BE CONSTRUCTED AFTER STAGE 3 AND THE BASIN IS COMPLETED IN FULL


INSPECTION NOTES

1. CLAY LINER AND BASIN EMBAKMENT ARE NOT TO BE CONSTRUCTED UNTIL SURROUNDING SUBGRADE AREAS ARE INSPECTED AND APPROVED BY COUNCIL.
2. GEOTECHNICAL ENGINEER TO BE CONSULTED AND INSPECT BASIN EMBANKMENT







CONSTRUCTION NOTES FOR CULVERTS

1. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL ENGINEERING GUIDELINES
2. CONCRETE MINIMUM COMPRESSIVE STRENGTH TO BE 32 mpa AT 28 DAYS
CONCRETE MINIMUM FLEXURAL STRENGTH TO BE 4.25 mpA AT 28 DAYS
3. SPILLWAY SURFACE TO BE BROOMED AND RAKED FINISH
4. CULVERT INVERT SLAB SURFACE TO BE TROWELLED FINISH
5. CLEAR CONCRETE COVER SHALL BE AS NOTED IN THE DRAWINGS, WHERE COVER IS NOT NOTED IT SHALL COMPLY WITH AS3600
6. CONSTRUCTION OF JOINTS WHERE NOT SHOWN SHALL BE LOCATED TO THE APPROVAL OF THE ENGINEER
7. WELDING OF REINFORCEMENT SHALL NOT PERMITTED UNLESS SHOWN ON THE STRUCTURAL DRAWINGS OR APPROVED IN WRITING BY THE ENGINEER
8. REINFORCEMENT SYMBOLS
R- DENOTES GRADE 230R HOT ROLLED PLAIN BARS TO AS1302
N - DENOTES GRADE D500N TO AS/NZS 4671
SL - DENOTES WELDED MESH FABRIC TO AS/NZS 4671
9. ALL REINFORCEMENT FABRIC SHALL COMPLY WITH AS1303 AND AS1304 AD SHALL BE SUPPLIED AS FLAT SHEETS
10. REINFORCEMENT FABRIC FOR PAVEMENTS SHALL BE SUPPORTED ON CHAIRS AT MAXIMUM 1000 CENTRES IN BOTH DIRECTIONS UNO
11. ALL CONCRETE TO BE EFFICIENTLY COMPACTED WITH APPROVED VIBRATOR
12. ALL CONCRETE SHALL BE CURED IN ACCORDANCE WITH AS3600
13. FOR N12 BARS USE A LAP LENGTH OR 500mm MIN UNO
14. DOWELS ARE TO ACCURATELY ALIGNED PARALLEL TO THE PAVEMENT SURFACE AND THE PAVEMENT CENTRE LINE. ALL DOWELS AND JOINT FORMERS ARE TO BE GALVANISED
15. CONCRETE IS TO BE VIBRATED WITH 2 PASSES OF A VIBRATING SCREED IN ACCORDANCE WITH TNSW R83





- NOTE.**
1. BASE SLAB AND CULVERT CONSTRUCTION / INSTALLATION TO BE INACCORDANCE WITH AS1597.2 AND THE MANUFACTURES GUIDELINES.
 2. REFER TO AS1597.2 CLAUSE 5.4 FOR GROUTING AND MORTAR THICKNESS AND APPLICATION FOR BASE OF CULVERTS LEGS TO BASE SLAB AND ANY GAPS BETWEEN CULVERT LEGS AND BASE SLABS AFTER PLACEMENT.
 3. FOOTING OF BASE SLAB TO BE INSPECTED BY GEOTECHNICAL ENGINEER PRIOR TO PLACEMENT OF SLAB.
 4. MINIMUM BEARING CAPACITY 150kpa
 5. GEOTECHNICAL ENGINEER TO CONFIRM BEARING CAPACITY OF 150 KPa IS ACHIEVED. AREAS OF UNSUITABLE MATERIAL TO BE REMOVED AND REPLACED AT DIRECTION OF GEOTECHNICAL ENGINEER.
 6. MINIMUM STANDARD COMPACTION OF 95% TO BE ACHIEVED, GEOTECHNICAL ENGINEER TO CONFIRM PRIOR TO PLACEMENT OF CULVERT SLAB
 7. HEADWALLS AND BASE SLAB TO BE MINIMUM 32MPa @ 28 DAYS
 8. 50mm BLINDING LAYER TO UNDER HEADWALLS TO BE 5MPa
 9. ANY BARS THROUGH COL JOINTS REQUIRED TO BE GALVANISED
 10. SUBSOIL PIPE TO BE INSTALLED ON BOTH SIDE OF CULVERTS AND BACKFILL WITH 10MM AGGREGATE.
 11. HEADWALLS AND CULVERT BASE TO BE INSPECTED BY CIVIL/ STRUCTURAL ENGINEER AND COUNCIL PRIOR TO PLACEMENT OF CONCRETE



TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE


CULVERT DETAILS

CLIENT: AJA DEVELOPMENTS


KEVIN URANE 0412009891









High Definition Design Pty Ltd

NOTE:
ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.



Date:	11.04.23	Scale:	1:1000 A1	Designed:	KU	Project No	HD336 DA2	
Cad Ref:	HD336 Civil COMMERCIAL R6					Drawing No	S16	Revision
C6	AMEND FLOOR LEVELS			KU	28.05.25	C6		
C5	DA ISSUE			KU	20.05.25			
No	Amendment			Drawn	Date			





TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

EROSION AND SEDIMENT CONTROL DETAILS 1 OF 3

CLIENT: AJA DEVELOPMENTS

KEVIN URANE 0412009891

High Definition Design Pty Ltd

NOTE:
ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

0 10 20 30 40 50 m
1:500 (H)

Date:	11.04.23	Scale:	1:1000 A1	Designed:	KU	Project No	HD336 DA2	
Cad Ref:	HD336 Civil COMMERCIAL R6					Drawing No	S18	Revision
C6	AMEND FLOOR LEVELS							C6
C5	DA ISSUE							
No	Amendment					Drawn	Date	

Erosion and Sediment Control Notes

The following notes may not be relevant to each development.

General

- 1. ESCP refers to Erosion and Sediment Control Plan and SWMP refers to Soil and Water Management Plan.
- 2. ESC refers to erosion and sediment control.
- 3. Sediment, includes, but is not limited to, clay, silt, sand, gravel, soil, mud, cement, and ceramic waste.
- 4. Any reference to the Blue Book refers to Managing Urban Stormwater- Soils and Construction. Land com, 2004.
- 5. Any reference to the IECA White Books (2008) refers to IECA2008.Best Practice Erosion and Sediment Control. Books 1-6.InternationalErosion Control Association (Australasia). Picton NSW.
- 6. Any material deposited in any conservation area from works associated with the development shall be removed immediately by measures involving minimal ground and/or vegetation disturbance and no machinery, or following directions by Council and/or within a time frame advised by Council.

The ESCP

- 7. The ESCP and its associated ESC measures shall be constantly monitored, reviewed, and modified as required to correct deficiencies. Council has the right to direct changes if, in its opinion, the measures that are proposed or have been installed are inadequate to prevent pollution.
- 8.Prior to any activities on site, the responsible person(s) is to be nominated. The responsible person(s) shall be responsible for the ESC measures onsite. The name, address and 24 hour contact details of the person(s) shall be provided to Council in writing. Council shall be advised within 48 hours of any changes to the responsible person(s), or their contact details, in writing.
- 9. At least 14 days before the natural surface is disturbed in any new stage, the contractor shall submit to the Certifier, a plan showing ESC measures for that Stage. The degree of design detail shall be based on the disturbed area.
- 10. At any time, the ESC measures on site shall be appropriate for the area of disturbance and its characteristics including soils (in accordance with those required for the site as per DCP).
- 11. The implementation of the ESCP shall be supervised by personnel with appropriate qualifications and/or experience in ESC on construction sites.
- 12. The approved ESCP shall be available on-site for inspection by Council officers while work activities are occurring.
- 13. The approved ESCP shall be up to date and show a timeline of installation, maintenance and removal of ESC measures.
- 14. All ESC measure shall be appropriate for the Sediment Type(s) of the soils on site, in accordance with the Blue Book, IECA White Books or other current recognised industry standard for ESC for Australian conditions.
- 15. Adequate site data, including soil data from a NATA approved Laboratory, shall be obtained to allow the preparation of an appropriate ESCP, and allow the selection, design and specification of required ESC measures.
- 16. All works shall be carried out in accordance with the approved ESCP (as amended from time to time) unless circumstances arise where: a) compliance with the ESCP would increase the potential for environmental harm; or b) circumstances change during construction and those circumstances could not have been foreseen; or c) Council determines that unacceptable off-site sedimentation is occurring as a result of a land-disturbing activity. In either case, the person(s) responsible maybe required to take additional, or alternative protective action, and/or undertake reasonable restoration works within the timeframe specified by the Council.

- 17. Additional ESC measures hall be implemented, and a revised ESCP submitted for approval to the certifier(within five business days of any such amendments) in the event that:
 - a) there is a high probability that serious or material environmental harm may occur as a result of sediment leaving the site; or
 - b) the implemented works fail to achieve Council's water quality objectives specified in these conditions; or
 - c) site conditions significantly change; or
 - d) site inspections indicate that the implemented works are failing to achieve the "objective" of the ESCP.
 - 18. A copy of any amended ESCP shall be forwarded to an appropriate Council Officer, within five business days of any such amendments.
- Site establishment including clearing and mulching**
- 19. No land clearing shall be undertaken unless preceded by the installation of adequate drainage and sediment control measures, unless such clearing is required for the purpose of installing such measures, in which case, only the minimum clearing required to install such measures shall occur.
 - 20. Bulk tree clearing and grubbing of the sites shall be immediately followed by specified temporary erosion control measures (e.g. temporary grassing or mulching) prior to commencement of each stage of construction works.
 - 21. Trees and vegetation cleared from the site shall be mulchedonsitewithin7 days of clearing.
 - 22. Appropriate measures shall be undertaken to control any dust originating due to the mulching of vegetation onsite.
 - 23. All office facilities and operational activities shall be located such that any effluent, including wash-down water, can be totally contained and treated within the site.
 - 24. All reasonable and practicable measures shall be taken to ensure storm water runoff from access roads and stabilised entry/exit systems, drains to an appropriate sediment control device.
 - 25. Site exit points shall be appropriately managed to minimise the risk of sediment being tracked onto sealed, public roadways.
 - 26. Stormwater runoff from access roads and stabilised entry/exit points shall drain to an appropriate sediment control device.
 - 27. The Applicant shall ensure an adequate supply of ESC, and appropriate pollution clean-up materials are available on-site at all times.
 - 28. All temporary earth banks, flow diversion systems, and sediment basin embankments shall be machine-compacted, seeded and mulched within ten (10) days of formation for the purpose of establishing a vegetative cover, or lined appropriately.
 - 29. Sediment deposited off site as a result of on-site activities shall be collected and the area cleaned/rehabilitated as soon as reasonable and practicable.
 - 30. Concrete waste and chemical products, including petroleum and oil-based products, shall be prevented from entering any internal or external water body, or any external drainage system, excluding those on-site water bodies specifically designed to contain and/or treat such material. Appropriate measures shall be installed to trap these materials onsite.
 - 31. Brick, tile or masonry cutting shall be carried out on a pervious surface (e.g. grass or open soil) and in such a manner that any resulting sediment-laden run off is prevented from discharging into a gutter, drain or water. Appropriate measures shall be installed to trap these materials onsite.
 - 32. Newly sealed hard-stand areas (e.g. roads, driveways and car parks)shall be swept thoroughly as soon as practicable after sealing/surfacing to minimise the risk of components of the surfacing compound entering stormwater drains.
 - 33. Stockpiles of erodible material shall be provided with an appropriate protective cover (synthetic or organic) if the materials are likely to be stockpiled for more than 10 days.
 - 34. Stockpiles, temporary or permanent, shall not be located in areas identified as no-go

- zones (including, but not limited to, restricted access areas, buffer zones, or areas of non-disturbance) on the ESCP.
- 35. No more than 150mof a stormwater, sewer line or other service trench shall to be open at any one time.
- 36. Site spoil shall be lawfully disposed of in a manner that does not result in ongoing soil erosion or environmental harm.
- 37. Wherever reasonable and practicable, stormwater runoff entering the site from external areas, and non-sediment laden (clean) stormwater runoff entering a work area or area of soil disturbance, shall be diverted around or through that area in a manner that minimises soil erosion and the contamination of that water for all discharges up to the specified design storm discharge
- Erosion and Sediment Control Notes continued Site Management including Dust
- 38. Priority shall be given to the prevention, or at least the minimisation, of soil erosion, rather than the trapping of displaced sediment. Such a clause shall not reduce the responsibility to apply and maintain, at all times, all necessary ESC measures.
- 39. Measures used to control wind erosion shall be appropriate for the location and prevents oil erosion and emissions from site at all times, including working hours, out of hours, weekends, public holidays, and during any other shutdown periods.
- 40. The application of liquid or chemical-based dust suppression measures shall ensure that sediment-laden run off resulting from such measures does not create a traffic or environmental hazard.
- 41. All cut and fill earth batters less than 3m in elevation shall be topsoiled, and grass seeded/hydromulchedwithin10 days of completion of grading in consultation with Council.
- 42. All disturbed areas shall be stabilised in accordance with timelines in the Blue Book.
- 43. All reasonable and practicable measures shall be taken to prevent, or at least minimise, the release of sediment from the site.
- 44. Suitable all-weather maintenance access shall be provided to all sediment control devices.
- 45. Sediment control devices, other than sediment basins, shall be de-silted and made fully operational as soon as reasonable and practicable after a sediment-producing event, whether natural or artificial, if the device's sediment retention capacity falls below 75% of its design retention capacity.
- 46. All erosion and sediment control measures, including drainage control measures shall be maintained in proper working order at all times during their operational lives.
- 47. Washing/flushing of sealed road ways shall only occur where sweeping has failed to remove sufficient sediment and there is a compelling need to remove the remaining sediment (e.g. for safety reasons). In such circumstances, all reasonable and practicable sediment control measures shall be used to prevent, or at least minimise, the release of sediment into receiving waters. Only those measures that will not cause safety and property flooding issues shall be employed. Sediment removed from road ways shall be disposed of in a lawful manner that does not cause ongoing soil erosion or environmental harm.
- 48. Sediment removed from sediment traps and places of sediment deposition shall be disposed of in a lawful manner that does not cause ongoing soil erosion or environmental harm.
- Sediment Basins - installation, maintenance and removal including sediment traps**
- 49. As-Constructed plans shall be prepared for all constructed Sediment Basins and associated emergency spillways. Such plans shall verify the basin's dimensions, levels and volumes comply with the approved design drawings. These plans may be requested by the Certifier or Council.
- 50. Sediment basins shall be constructed and fully operational prior to any other soil disturbance in their catchment.
- 51. Install an internal gated valve, or similar, in any outlet pipe once pipes installed, or install a sacrificial pipe from basin through wall to external outlet point. The valve shall be connected to a riser made from slotted pipe in the basin. The valve maybe opened once captured water meets water quality requirements. The final setup for temporary internal


- outlet structures to be confirmed prior to construction with Council. This setup will enable discharge of treated water from site without need for pumping.
- 52. A sediment storage level marker post shall be with a cross member set just below the top of the sediment storage zone (as specified on the approved ESCP). At least a 75mmwidepost shall be firmly set into the basin floor.
- 53. The Site Manager shall obtain the relevant approvals from the relevant organisations to discharge treated water from any existing basins. Organisations may include, but not be limited to, Hunter Water, and Council.
- 54. Where more than one stage is to be developed at one time, or before the preceding stage is complete, the sediment basin(s) for these stages shall have sufficient capacity to cater for all area directed to the basin(s).
- 55. Prior to any forecast weather event likely to result in runoff, any basins/traps shall be dewatered to provide sufficient capacity to capture sediment laden water from the site.
- 56.Sufficient quantities of chemicals/agents to treat captured water shall be placed such that water entering the basin mix with the chemical/agents and is carried into the basin to speed up clarification.
- 57. Any basin shall be dewatered within the X-day rainfall depth used to calculate the capacity of the basin, after a rainfall event.
- 58. Sufficient quantities of chemicals/agents to treat turbid water shall be securely stored on-site to provide for at least three complete treatments of all basins requiring chemically treatment onsite.

TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

EROSION AND SEDIMENT CONTROL DETAILS 2 OF 3

CLIENT: AJA DEVELOPMENTS

KEVIN URANE 0412009891



NOTE:

ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

01020304050m

1:500 (H)

Date: 11.04.23		Scale: 1:1000 A1		Designed: KU		Project No	
Cad Ref: HD336 Civil COMMERCIAL R6						HD336DA2	
						Drawing No S19	Revision C6
C6	AMEND FLOOR LEVELS			KU	28.05.25		
C5	DA ISSUE			KU	20.05.25		
No	Amendment			Drawn	Date		

59. Prior to the controlled discharge (e.g. de-watering activities) from site including excavations and/or sediment basins, the following water quality objectives shall be achieved:

a) Total Suspended Solids (TSS) to a maximum 50 milligrams/L;

b) water pH between 6.5 and 8.5, unless otherwise required by the Council;

c) Turbidity (measured in NTUs) to a maximum of 60 NTU); and

d) EC levels no greater than background levels.

60. The Development Approval may require testing of additional water quality elements prior to discharge. E.g. including but not limited to metals, organic substances, chemicals or bacteriological indicators.

61. A sample of the released treated water shall be kept onsite in a clear container with the sample date recorded on it.

62. Water quality samples shall be taken at a depth no less than 200mm below the water surface of the basin.

63. No Aluminum based products may be used treat captured water onsite without the prior written permission from an appropriate Council Officer. The applicant shall have a demonstrated ability to use such products correctly and without environmental harm prior to any approval.

64. The chemical/agent used in Type D and Type F basins to treat captured water captured in the basin shall be applied in concentrations sufficient to achieve Council's water quality objectives within the X-day rainfall depth used to calculate the capacity of the basin, after a rainfall event.

65. All Manufacturers' Instructions shall be followed for any chemicals/agents used onsite, except where approved by the Responsible Person or an appropriate Council Officer.

66. The Applicant shall ensure that on each occasion a Type F or Type D basin was not de-watered prior to being surcharged by a following rainfall event, a report is presented to an appropriateCouncilofficerwithin5 days identifying the circumstances and proposed amendments, if any, to the basin's operating procedures.

67. Settled sediment shall be removed as soon as reasonable and practicable from any sediment basin if:

a) it is anticipated that the next storm event is likely to cause sediment to settle above the basin's sediment storage zone; or

b) the elevation of settled sediment is above the top of the basin's sediment storage zone; or

c) the elevation of settled sediment is above the basins sediment marker line.

68. Scour protection measures placed on sediment basin emergency spill ways shall appropriately protect the spillway chute and its side batters from scour, and shall extend a minimum of 3m beyond the downstream toe of the basin's embankment.

69. Suitable all-weather maintenance access shall be provided to all sediment control devices.

70. Materials, whether liquid or solid, removed from any ESC measure or excavation during maintenance or decommissioning, shall be disposed of in a manner that does not cause ongoing soil erosion, water pollution or environmental harm.

71. All sediment basins shall remain fully operational at all times until the basin's design catchment achieves 70% ground cover or surface stabilisation acceptable to Council.

72. The ESC measures installed during the decommissioning and rehabilitation of a sediment basin shall comply with same standards specified for the normal construction works.

73. A sediment basin shall not be decommissioned until all up-slope site stabilisation measures have been implemented and are appropriately working to control soil erosion and sediment runoff.

Erosion and Sediment Control Notes continued

74. Immediately prior to the construction of the permanent stormwater treatment device, appropriate flow by pass condition shall be established to prevent sediment-laden water entering the device. **Revegetation/Stabilisation**

75. Temporary Stabilisation maybe attained using vegetation, non rewettable soil polymers, or pneumatically applied erosion controls.

76. All cut and fill earth batters less than 3m in elevation shall be topsoiled, and grass seeded/hydromulchedwithin10 days of completion of grading in consultation with Council.

77. At the completion of formation in any section, all disturbed areas shall be stabilised in

accordance with time lines in the Blue Book.

78. The Maitland Council City Seed mix shall be used unless stated on the ESCP/SWMP.

79. The pH level of topsoil shall be appropriate to enable establishment and growth of specified vegetation prior to initiating the establishment of vegetation.

80. Non rewettable binder shall be used in all hydro mulch/ hydro seed/polymer mixes on slopes or works adjacent to a water course.

81. Soil ameliorants shall be added to the soil in accordance with an approved Landscape Plan, Vegetation Management Plan, and/or soil analysis.

82. Surface soil density, compaction and surface roughness shall be adjusted prior to seeding/planting in accordance with an approved Landscape Plan, Vegetation Management Plan, and/or soil analysis.

83. Procedures for initiating a site shutdown, whether programmed or un-programmed, shall incorporate revegetation of all soil disturbances unless otherwise approved by Council. The stabilisation works shall not rely upon the longevity of non-vegetated erosion control blankets, or temporary soil binders.

Site Monitoring and Maintenance

84. The Applicant shall ensure that appropriate procedures and suitably qualified personnel are engaged to plan and conduct site inspections and water quality monitoring throughout the construction and maintenance phase.

85. All ESC measures shall be inspected and any maintenance undertaken immediately:

a) at least daily (when work is occurring on-site); and

b) at least weekly (when work is not occurring on-site); and

c) within 24hrs of expected rainfall; and

d) within 18hrs of a rainfall event that causes runoff on the site.

86. Written records shall be kept onsite of ESC monitoring and maintenance activities conducted during the construction and maintenance periods, and be available to Council officers on request.


87. All environmentally relevant incidents shall be recorded in a field log that shall remain accessible to all relevant regulatory authorities.

88. All water quality data, including dates of rainfall, dates of testing, testing results and dates of water release, shall of testing, testing results and dates of water release, shall be kept in an on-site register. The register is to be maintained p to date for the duration of the approved works and be available on-site for inspection by all relevant regulatory authorities on request.

64. At nominated instream water monitoring sites, a minimum of 3 water samples shall be taken and analysed, and the average result used to determine quality. Instream Works 90. All instream works (including in or adjacent to watercourses natural or manmade, flowing or not) shall be carried out in accordance with the IECA White Books.

Instream Works

65. All instream works (including in or adjacent to water courses natural or manmade, flowing or not) shall be carried out in accordance with the IECA White Books.



TITLE: PROPOSED SUBDIVISION OF LOT 1 DP1228883 and LOT 1 DP430627
202 BUSHLAND DRIVE TAREE

ROUNABOUT PLAN SHEET 2 OF 2

CLIENT: AJA DEVELOPMENTS

High Definition Design Pty Ltd

KEVIN URANE 0412009891

NOTE:
ALL EXISTING UNDERGROUND SERVICES MUST BE LOCATED AND EXPOSED PRIOR TO EARTHWORKS COMMENCING AND IT IS RESPONSIBILITY OF THOSE PERSONS USING THIS PLAN TO CONFIRM BOTH POSITION AND LEVEL OF THESE UTILITIES IN CONJUNCTION WITH THE APPROPRIATE AUTHORITY.

0 10 20 30 40 50 m
1:500 (H)

Date: 20.02.25		Scale: 1:300 A1		Designed: KU		Project No	
Cad Ref: HD336 Civil		COMMERCIAL R6				HD336 DA2	
C6	AMEND FLOOR LEVELS			KU	28.05.25	Drawing No	
C5	DA ISSUE			KU	20.05.25	Revision	
					S22		C6
No	Amendment			Drawn	Date		

