

1 | SEDIMENT CONTROL

SCALE: 1:200

AFFORDABLE PLANS

EDIZ BOYACIOGLU
Architectural Draftsman
Director/Building Designer
Email: affordableplans2022@hotmail.com
Mob: 0416 052 155

NOT FOR CONSTRUCTION

REVISION

Issue for CDC 16/02/25 A

ADDRESS

LOT 11 DP16233 NO.76
LEOPOLD ST, ASHBURY NSW
2193

CLIENT

PROJECT NO 2025003

PROJECT

PROPOSED ALTERATION AND
ADDITION

CHK: FF


DSG: FF

DRW: FF

APR: FF

DRAWING TITLE

SEDIMENT CONTROL PLAN



GENERAL NOTES


1. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSPECTED AND MAINTAINED DAILY BY CONTRACTOR/SITE MANAGER.
2. MINIMISE DISTURBED AREAS.
3. ALL STOCKPILES TO BE CLEARED FROM DRAINS, GUTTERS AND FOOTPATHS.
4. DRAINAGE IS TO BE CONNECTED TO STORM WATER SYSTEM AS SOON AS POSSIBLE.
5. ROADS AND FOOTPATH TO BE SWEEP DAILY.
6. UNDER SECTION 16 OF THE CLEAN WATERS ACT HEAVY FINESSING/LIMING & SOOT ON THE SPOT FINE MAY BE IMPOSED IF A PERSON ALLOWS SOIL, CEMENT SLURRY OR OTHER BUILDING MATERIALS TO BE PUMPED, DRAINED OR ALLOWED TO ENTER THE STORM WATER SYSTEM.

SOIL EROSION NOTES

TOPSOIL SHALL BE STRIPPED AND STOCKPILED OUTSIDE HAZARD AREAS SUCH AS DRAINAGE LINES, THIS TOPSOIL IS TO BE RE-SPREAD LATER ON AREAS TO BE REVEGETATED AND STABILISED ONLY. (i.e. ALL FOOT-PATHS, BATTERS, SITE, RESERVING AREAS, DRAINAGE RESERVES AND CHANNELS). TOP SOIL SHALL NOT BE SPREAD ON ANY OTHER AREAS SPECIFICALLY INSTRUCTED BY THE SUPERINTENDENT. IF THEY ARE TO REMAIN FOR LONGER THAN ONE MONTH STOCKPILES SHALL BE PROTECTED FROM EROSION BY COVERING THEM WITH A MULCH AND HYDROSEEDING AND, IF NECESSARY, BY LOCATING BANKS OR DRAINS UPSLOPE TO DIVERT THE RUNOFF AROUND THEM. IN SOME CIRCUMSTANCES IT MAY BE NECESSARY TO PLACE BANKS OR DRAINS DOWNSTREAM OF A STOCKPILE TO RETARD SEDIMENT LADEN RUNOFF. THE CONTRACTOR SHALL REGULARLY MAINTAIN ALL SEDIMENT AND EROSION CONTROL DEVICES AND REMOVE ACCUMULATED SILT FROM SUCH DEVICES BEFORE NO MORE THAN 60% OF THEIR CAPACITY IS LOST. ALL THE SILT REMOVED SHALL BE DISPOSED OF AS DIRECTED BY THE SUPERINTENDENT. (NO SILT SHALL BE PLACED OUTSIDE THE LIMITS OF WORKS). THE PERIOD FOR MAINTAINING THESE DEVICES SHALL BE AT LEAST UNTIL ALL DISTURBED AREAS ARE REVEGETATED AND FURTHER AS MAY BE DIRECTED BY THE SUPERINTENDENT OR COUNCIL.

SEDIMENT NOTES

1. CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE AND PARALLEL TO THE CONTOURS OF THE SITE.
2. DRIVE 1.5 m LONG STAR PICKETS INTO GROUND Max 3 m Ctrs.
3. DIG A 150 mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
4. BACKFILL TRENCH OVER BASE OF FABRIC.
5. FIX SELF SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES OR AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
6. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A Min LAP OF 150 mm.



SEDIMENT CONTROL FENCE


NOT TO SCALE



PROVISIONAL AREA
FOR STOCKPILING OF
MATERIALS



GEOTEXTILE TRADE
WASTE RECEPTABLE



VC AND STABILISED ENTRY



SEDIMENT CONTROL FENCE

DRAWING NO.

SCALE @ A3As indicated

CDC15

DO NOT SCALE THE DRAWING. READ ALL DIMENSIONS FROM ALL DIMENSION LINES. NOTES ON ALL PLANS AND GENERAL DOCUMENTS MUST BE CHECKED AND VERIFIED BY THE CONTRACTOR PRIOR TO ANY COMMENCEMENT OF ANY WORK. ANY DISCREPANCY OR INCONSISTENCY ANY DIMENSIONS OR OTHER INFORMATION ON THE DRAWING OR ANY OTHER INFORMATION RELAYED TO THE PROPRIETOR, LETS WORKS, SHOULD BE IMMEDIATELY REPORTED TO THE CONTRACTOR.