# STORMWATER MANAGEMENT PLAN (FOR DA)

### PROPOSED RESIDENCE

### 5 WOLUMBA STREET CHESTER HILL NSW 2162

#### **GENERAL NOTES**

- 1. FINAL LOCATION OF NEW DOWNPIPES TO BE DETERMINED BY BUILDER/ARCHITECT AT TIME OF CONSTRUCTION.
- 2. THESE DRAWINGS TO BE READ IN CONJUNCTION WITH ARCHITECTS AND OTHER CONSULTANTS DRAWINGS. ANY DISCREPANCIES TO BE REFERRED TO THE ENGINEER BEFORE PROCEEDING WITH WORK.
- 3. ALL MATERIALS AND WORKMANSHIP TO BE IN ACCORDANCE WITH AS/NZS 3500.3:2003 STORMWATER DRAINAGE, BCA AND LOCAL COUNCIL POLICY/CONSENT/REQUIREMENTS.
- 4. ALL DIMENSIONS AND LEVELS TO BE VERIFIED BY BUILDER ON-SITE PRIOR TO COMMENCEMENT OF WORKS. THESE DRAWINGS ARE NOT TO BE SCALED FOR DIMENSIONS NOR TO BE USED FOR SETOUT PURPOSES
- 5. ALL SURVEY INFORMATION AND PROPOSED BUILDING AND FINISHED SURFACE LEVELS SHOWN IN THESE DRAWINGS ARE BASED ON LEVELS OBTAINED FROM DRAWINGS BY OTHERS.

- 6. ALL STORMWATER DRAINAGE PIPES ARE TO BE uPVC AT MINIMUM 1% GRADE UNLESS NOTED OTHERWISE.
- 7. IT IS THE CONTRACTORS RESPONSIBILITY TO LOCATE AND LEVEL ALL EXISTING SERVICES OR OTHER STRUCTURES WHICH MAY AFFECT/BE AFFECTED BY THIS DESIGN PRIOR TO COMMENCEMENT OF WORKS.
- 8. ALL PITS WITHIN DRIVEWAYS TO BE 150mm THICK CONCRETE OR EQUA
- 9. THIS PLAN IS THE PROPERTY OF DONOVAN ASSOCIATES AND MAY NOT BE USED OR REPRODUCED WITHOUT WRITTEN PERMISSION FROM DONOVAN ASSOCIATES.

#### PLAN SPECIFIC NOTES

- ROOF DRAINAGE NOTE: AS 3500 ROOF DRAINAGE REQUIRES EAVES GUTTERS TO BE SIZED FOR 20 YEAR 5 MIN. STORM = 205mm/hr. FOR EAVES GUTTERS, AS 3500.3:2003 THEN HAS THE FOLLOWING REQUIREMENTS: i) FOR TYPICAL STANDARD QUAD GUTTER WITH Ae = 6000mm<sup>2</sup> AND
- GUTTER SLOPE 1:500 AND STEEPER, THIS REQUIRES ONE DOWNPIPE PER 30m<sup>2</sup> ROOF AREA.
- SLOPE 1:500 AND STEPPER.
- iii) OVERFLOW METHOD TO FIGURE G1 OF AS 3500.3:2003 IT IS THE RESPONSIBILITY OF THE PLUMBER AND / OR BUILDER TO COMPLY WITH THIS. THIS DRAWING SHOWS PRELIMINARY LOCATIONS / NUMBERS OF DOWNPIPES ONLY WHICH ARE TO BE

**VERIFIED BY BUILDER / PLUMBER** 

- 2. TREE PRESERVATION: IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN ANY PRIOR APPROVAL REQUIRED FROM COUNCIL WITH RESPECT TO POTENTIAL IMPACT ON TREES FOR ANY WORKS SHOWN ON THIS DRAWING PRIOR TO THE COMMENCEMENT OF
- 3. ALL ROOF GUTTERS TO HAVE OVERFLOW PROVISION IN ACCORDANCE ii) DOWNPIPES TO BE MINIMUM 90mm DIA. OR 100 x 50mm FOR GUTTERS WITH AS 3500.3:2003 AND SECTIONS 3.5.3, 3.7.5 AND APPENDIX G OF AS 3500.3:2003
  - 4. THIS DRAWING IS NOT TO BE USED FOR SET-OUT PURPOSES REFER TO ARCHITECTURAL DRAWINGS
  - 5. LOCATION OF SURFACE STORMWATER GRATED INLET PITS MAY BE VARIED OR NEW PITS INSTALLED AT THE CONSTRUCTION STAGE PROVIDED DESIGN INTENT OF THIS DRAWING IS MAINTAINED

SURFACE INLET PIT		LEGEND GRATED TRENCH DRAIN	
SURFACE INLET PIT (WITH ENVIROPOD 200 MICRON)		ABSORPTION TRENCH	
ACCESS GRATE		PROPOSED ROOF GUTTER FALL	
(WITH ENVIROPOD 200 MICRON)		PROPOSED DOWNPIPE SPREADER	
450 SQUARE INTERVAL	450 x 450	STORMWATER PIPE 100mm DIA. MIN. UNO	
GRATE LEVEL = 75.50	SL 75.50	SUBSOIL PIPEaa	
INVERT LEVEL = RL 75.20	IL 75.20	EXISTING STORMWATER PIPE — sw — —	
PROPOSED DOWNPIPE 90mm DIA. OR 100mm x 50mm MIN.	•	INSPECTION RISER • IR	
NATURAL GROUND FINISHED DESIGN LEVEL	⊗ ■	RAINWATER HEAD RWH BOX GUTTER BG	

#### DRAINAGE NOTES

#### PIPE SIZE:

THE MINIMUM PIPE SIZE SHALL BE:

- 90mm DIA WHERE THE LINE ONLY RECEIVES ROOFWATER RUNOFF; OR
- · 100mm DIA WHERE THE LINE RECEIVES RUNOFF FROM PAVED OR UNPAVED AREAS ON THE PROPERTY

THE MINIMUM PIPE VELOCITY SHOULD BE 0.6 m/s AND A MAXIMUM PIPE VELOCITY OF 6.0 m/s DURING THE DESIGN STORM.

#### PIPE GRADE:

THE MINIMUM PIPE GRADE SHALL BE:

- 1.0% FOR PIPES LESS THAN 225mm DIA (UNO)
- · 0.5% FOR ALL LARGER PIPES (UNO)

PIPES WITH A GRADIENT GREATER THAN 20% WILL REQUIRE ANCHOR BLOCKS AT THE TOP AND BOTTOM OF THE INCLINED SECTION; AND AT INTERVALS NOT **EXCEEDING 3.0m** 

ANCHOR BLOCKS ARE DESIGNED ACCORDING TO CLAUSE 3.5.3 OF AS3500.3-1990

#### **DEPTH OF COVER FOR PVC PIPES:**

MINIMUM PIPE COVER SHALL BE AS FOLLOWS:

LOCATION	MINIMUM COVER
NOT SUBJECT TO VEHICLE LOADING	100mm SINGLE RESIDENTIAL
	300mm ALL OTHER DEVELOPMENTS
SUBJECT TO VEHICLE LOADING	450mm WHERE NOT IN A ROAD
UNDER A SEALED ROAD	600mm
UNSEALED ROAD	750mm
PAVED DRIVEWAY	100mm PLUS DEPTH OF CONCRETE

SEE AS2032 INSTALLATION OF UPVC PIPES FOR FURTHER INFORMATION.

CONCRETE PIPE COVER SHALL BE IN ACCORDANCE WITH AS3725-1989 LOADS ON BURIED CONCRETE PIPES, HOWEVER A MINIMUM COVER OF 450mm WILL APPLY.

WHERE INSUFFICIENT COVER IS PROVIDED. THE PIPE SHALL BE COVERED AT LEAST 50mm THICK OVERLAY AND SHALL THEN BE PAVED WITH AT LEAST:

· 75mm THICKNESS OF BRICK OR 100mm OF CONCRETE PAVING WHERE

150mm REINFORCED CONCRETE WHERE SUBJECT TO HEAVY VEHICLE

- SUBJECT TO LIGHT VEHICLE TRAFFIC: OR 50mm THICK BRICK OR CONCRETE PAVING WHERE NOT SUBJECT TO VEHICLE TRAFFIC.
- CONNECTIONS TO STORMWATER DRAINS UNDER BUILDINGS: SHALL BE CARRIED OUT IN ACCORDANCE WITH SECTION 3.10 OF AS3500.3-1990

#### CONNECTIONS TO COUNCIL SYSTEM:

IF PROPOSED DRAINAGE SYSTEM IS DESIGNED TO CONNECT TO COUNCIL'S DRAINAGE SYSTEM, IT IS ADVISED THAT A 'WORKS PERMIT' IS OBTAINED FROM THE RESPECTIVE COUNCIL PRIOR TO COMMENCEMENT OF WORKS

#### ABOVE GROUND PIPEWORK:

SHALL BE CARRIED OUT IN ACCORDANCE WITH SECTION 6 OF AS3500.3-1990

#### PIT SIZES AND DESIGN

DEPTH (mm)	MINIMUM PIT SIZE (mm)		
UP TO 450mm	450 x 450		
450mm TO to 600mm	600 x 600		
600mm TO 900mm	600 x 900		
900mm TO 1500mm	$900 \times 900$ (with step irons)		
1500mm TO 2000mm	1200 x 1200 (WITH STEP IRONS)		

ALL PIPES SHOULD BE CUT FLUSH WITH THE WALL OF THE PIT.

PITS GREATER THAN 600mm DEEP SHALL HAVE A MINIMUM ACCESS OPENING OF 600 x 600mm

THE GRATED COVERS OF PITS LARGER THAN 600 x 600mm ARE TO BE HINGED TO PREVENT THE GRATE FROM FALLING INTO THE PIT.

THE BASE OF THE DRAINAGE PITS SHOULD BE AT THE SAME LEVEL AS THE INVERT OF THE OUTLET PIPE. RAINWATER SHOULD NOT BE PERMITTED TO POND WITHIN THE STORMWATER SYSTEM

#### • TRENCH DRAINS:

CONTINUOUS TRENCH DRAINS ARE TO BE OF WIDTH NOT LESS THAN 150mm AND DEPTH NOT LESS THAN 100mm. THE BARS OF THE GRATING ARE TO BE PARALLEL TO THE DIRECTION OF SURFACE FLOW.

#### STEP IRONS:

PITS BETWEEN 1.2m AND 6m ARE TO HAVE STEP IRONS IN ACCORDANCE WITH AS1657. FOR PITS GREATER THAN 6m OTHER MEANS OF ACCESS MUST BE PROVIDED.

#### PVC PITS:

PVC PITS WILL ONLY BE PERMITTED IF THEY ARE NOT A GREATER SIZE THAN 450 x 450mm (MAXIMUM DEPTH 450mm) AND ARE HEAVY DUTY

#### IN-SITU PITS:

IN-SITU PITS ARE TO BE CONSTRUCTED ON A CONCRETE BED OF AT LEAST 150mm THICK. THE WALLS ARE TO BE DESIGNED TO MEET THE MINIMUM REQUIREMENTS OF CLAUSE 4.6.3 OF AS3500.4-1990. PITS DEEPER THAN 1.8m SHALL BE CONSTRUCTED WITH REINFORCED CONCRETE.

#### GRATES:

GRATES ARE TO BE GALVANISED STEEL GRID TYPE. GRATES ARE TO BE OF HEAVY-DUTY TYPE IN AREAS WHERE THEY MAY BE SUBJECT TO VEHICLE LOADING.


DRAWN	DATE	AMENDMENT.	REV.	
MH	23/06/2025	ISSUED FOR D.A.	А	



## L'EVEREST CONSULTING

STRUCTURAL&CIVIL CONSULTING job@levere stconsulting.com.au

FOR: XINYI CHEN	GENERAL NOTES	APPROVED BY:  JS	CHECKED:	ISSUE.
SITE ADDRESS: 5 WOLUMBA STREET CHESTER HILL NSW 2162	DEVELOPMENT APPLICATION	PROJECT CODE: 25G10035	REV.	DRAWING No



RAINWATER RE-USE TANK - RWT

(AS PER BASIX & COUNCIL REQUIREMENTS)

SIZE:

- OUTBUILDING: 1,500 LITRES (MIN)
- SECONDARY DWELLING: 1,500 LITRES (MIN) H2ENVIRO SLIMLINE COLORBOND TANK OR EQUIV. INSTALL TO MANUFACTURES SPECIFICATIONS, AS3500 AND

COUNCIL REQUIREMENTS

- FOR RE-USE AS SPECIFIED BY BASIX CERTIFICATE & COUNCIL REQUIREMENTS
- ENSURE TOP OF TANK IS MIN 0.6m BELOW ROOF GUTTERS
- TO ENSURE SUFFICIENT HEAD FOR THE SYSTEM

  TANK TO BE INSTALLED BY LICENSED PLUMBER

ACCORDANCE WITH AS/NZS 3500:2003 AND NSW CODE OF

PRACTICE PLUMBING AND DRAINAGE 2006

STORMWATER PLAN
1:100

NOTE: ALL THE THE
EXISTING SERVICES TO BE
CONFIRMED AT SITE BEFORE
COMMENCING CONSTRUCTION.
ANY DISCREPANCY TO BE
NOTIFIED TO THE ENGINEER

ALL CHARGE LINES TO BE WATERTIGHT UP TO THE TOP OF RAINWATER TANK LEVEL NOTE: ENSURE ANY
PROPOSED PAVING IS GRADED
SO THAT IT IS NOT IMPACTING
ADJOINING PROPERTIES

DRAWN	DATE	AMENDMENT.	REV.
MH	23/06/2025	ISSUED FOR D.A.	A



## L'EVEREST CONSULTING

STRUCTURAL&CIVIL CONSULTING job@levere stconsulting.com.au

FOR: XINYI CHEN	STORMWATER DRAINAGE PLAN	APPROVED BY:  JS	CHECKED:	ISSUE.
SITE ADDRESS: 5 WOLUMBA STREET CHESTER HILL NSW 2162	DEVELOPMENT APPLICATION	PROJECT CODE: 25G10035	REV.	DRAWING No.