



CASTLEREAGH TOURISM DEVELOPMENT

39-65 Old Castlereagh Road, Castlereagh NSW

Aboriginal Cultural Heritage Assessment

Final | September 2025

Prepared for Morson Group

PO Box 101, Pottsville NSW 2489 (02) 6676 4354 info@virtusheritage.com.au ABN 56 159 910 228



Cover image: Drone photography provided by Morson Group (2024)

Document Controls

Client:	Morson Group
Proponent:	Morson Group
Local Government Area:	City of Penrith Local Government Area
Local Aboriginal Land Council (LALC):	Deerubbin Local Aboriginal Land Council

Version History

Version	Date	Prepared by	Approved by	Comments
1	24 January 2025	Liam Clerke, Anya Graubard, Dr. Mary- Jean Sutton, Clare Anderson	Dr. Mary-Jean Sutton	Draft
2	23 July 2025	Liam Clerke	Dr. Mary-Jean Sutton	Draft
3	27 August 2025	Kate Morris and Liam Clerke	Dr. Mary-Jean Sutton	Final

September 2025 Page 2 of 61



Acknowledgement of Country

Virtus Heritage acknowledges the Traditional Custodians of the land on which this project was undertaken and pays respect to Elders past, present and emerging.

Content Warning

Aboriginal and Torres Strait Islander people are warned that this publication may contain names and images of deceased people, descriptions of traumatic historic events and parts of Country that have been impacted by development.

Disclaimer and cultural restrictions

This Report (including any enclosures and attachments) has been prepared by Virtus Heritage for the exclusive use and benefit of Morson Group and Morson Group for their use regarding the Project and solely for the purpose for which it is provided. Unless we provide express prior written consent, no part of this report should be reproduced, distributed or communicated to any third party. We do not accept any liability if this report is used for an alternative purpose from which it is intended, nor to any third party in respect of this report.

Information contained in the Report is current as at the date of the Report and may not reflect any event or circumstances which occur after the date of the Report.

All queries related to the content, or to any use of this report must be addressed to Dr Mary-Jean Sutton.

September 2025 Page 3 of 61



Executive Summary

Virtus Heritage Pty Limited (hereafter 'Virtus Heritage') was engaged by Morson Group, on behalf Morson Group (the Proponent), to prepare an Aboriginal Cultural Heritage Assessment (ACHA), including an Archaeological Assessment (AA) for (proposed impact areas for these works shown in Figure 1 and referred to hereafter as 'the project area' or whatever the client wants). The ACHA was compiled to accompany an Aboriginal Heritage Impact Permit (AHIP) application and Research Design and Methodology (RD&M). The objectives of the ACHA are to investigate and assess the impact of Castlereagh Tourism Development on known and potential Aboriginal objects, Aboriginal places and cultural heritage values within the project area as well as to provide appropriate management and mitigation strategies. This report has been compiled to meet the requirements of the *Guide to investigating, assessing and reporting on Aboriginal cultural heritage in NSW* (OEH 2011).

An Archaeological Assessment was also compiled to consider the scientific values of the project area, which is an Appendix (Appendix A), to the ACHA. The purpose of the Archaeological Assessment is to provide Morson Group, with archaeological advice on the potential impact of their proposal on Aboriginal archaeological sites and to meet the requirements of the *Code of Practice for Archaeological Investigation of Aboriginal Objects in New South Wales* (DECCW 2010) for Archaeological Reports – Requirements 1 to 11).

CONSULTATION

Consultation with the Registered Aboriginal Parties, including Deerubbin LALC, has been undertaken for this assessment and conducted in accordance with the Aboriginal cultural heritage consultation requirements for proponents 2010 (DECCW 2010b) (hereafter referred to as the "ACHRs"). The ACHA documents the process of investigation, consultation and assessment undertaken. The approach to the ACHA and AHIP also involved consultation with Heritage NSW's regional archaeologists (if relevant).

IMPACTS

The proposed scope of works as provided by Morson Group seeks approval for a tourism-oriented development comprising three (3) buildings across separate lots, including a hotel, an indoor recreation facility with two (2) drive-through restaurants, and a registered club. The proposal also includes associated vehicle access, on-grade and above-ground parking, and site infrastructure.

- Lot 12:
 - A seven (7) storey hotel with 147 rooms, restaurant, gym, spa, pool, and associated facilities.
 - Multi-level above-ground car parking.
- Lot 14:
 - A 5,713m² indoor recreation facility.
 - Two (2) restaurants with capacity for a drive-through.
 - Associated on-grade car parking.
- Lot 16:
 - A 5,177m² registered club building.
 - Associated on-grade car parking.

The project design is proposed to be submitted as a concept Development Application with DPHI, however the expected ground impacting activities will include:

- Archaeological investigations
- Demolition of existing structures
- Earth works including cut and fill, pilings/footings and service trenches across the project area;
- Construction of the three buildings on site;

September 2025 Page 4 of 61



- Installation of vehicle and pedestrian access;
- Heavy vehicle movement across the project area
- Landscaping works across the project area;
- Ancillary infrastructure and works

It is likely that excavations across the site will be part of the overall redevelopment works with most excavations anticipated to be up to 0.15 – 1.74 m below ground level (BGL), though excavation of stormwater systems and footings will also likely be required. Excavations in these areas are anticipated to be to a maximum depth of ~2.3 m BGL.

The proposed development is intended to be delivered in stages as outlined below:

- Early Works Stage: Demolition of existing dwellings and structures on the site and the installation of stormwater infrastructure, including partial construction of the stormwater system and a flood relief pipe at the rear of the site. No bulk earthworks are proposed in this stage.
- Stage 2: The construction of the hotel building on Lot 12,
- Stage 3: The construction of the indoor recreation facility and restaurants on Lot 14,
- Stage 4: The construction of the club building on Lot 16.

SIGNIFICANCE ASSESSMENT

Based upon numerous prior studies within Cranebrook Terrace (refer to **Appendix A**), the project area is situated within a culturally significant landscape.

The project area contains deposits of the Penrith Unit of the Cranebrook Terrace and a recorded Penrith Lakes 2025 background scatter with Aboriginal objects in 8 locations. Aboriginal objects in this unit provide an opportunity to further understand the geomorphic and archaeological value of the Penrith Unit of the Cranebrook Terrace and past Dharug land use on elevated terrain. Development in the local region has impacted the survival of Aboriginal objects in the Penrith Unit.

The proposed activity has the potential to harm Aboriginal objects associated with the Penrith Unit. Given the extent of information available on the Penrith Unit, the previous land-use of the project area, the identification of artefacts within surface exposures inside of the project area, and the homogeneity of topography and landforms within the project area,

Archaeological and cultural salvage are required to mitigate the impacts on the proposed development on Penrith Lakes 2025, background scatter

MANAGEMENT RECOMMENDATIONS

Management options and recommendations are outlined for this proposal in Section 10 and Section 11 of this report. Based on the description of project impacts provided by Morson Group, the results of the survey, Aboriginal consultation to date, and previous archaeological research, the following recommendations are made:

- a) An AHIP with community collection and archaeological salvage will be required prior to the commencement of ground disturbance works as Aboriginal objects will be harmed by the proposal.
- b) It is recommended that all site workers and personnel involved in site impact works should be **inducted and briefed** on the possible identification of Aboriginal sites and objects during construction and their responsibilities according to the provisions of the NPW Act 1974 and NPW Regulation 2019.

This induction package should be developed in consultation with DLALC, prior to works proceeding. The induction must include:

• An AHIP once issued as recommended by the results of this AA report.

September 2025 Page 5 of 61



- The contact phone numbers of the NSW Environment and Heritage regional archaeologist, EnviroLine 131 555, and DLALC.
- The relevant contact phone number Environmental Officer responsible for this project in case unknown objects or items are uncovered during excavation.
- The penalty for moving Aboriginal objects need to be made clear and given due consideration.
- An outline types of unexpected heritage objects, items & relics, and their legal protection
- The Unexpected Finds and Human Remains Procedures, as outlined in Recommendation 1 and 2.
- c) It is recommended that an **Unexpected Finds Procedure** be implemented for the duration of the project. In the event that a suspected Aboriginal object/s is identified the procedure should include the following:
 - Works are to stop immediately.
 - The area of the suspected find/s is to be fenced off with an appropriate buffer and protected.
 - A qualified archaeologist and representative of DLALC are to be contacted to inspect the area and the nature of the find and to advise if it can be collected within the provisions of an AHIP (if determined by HNSW).
 - Representative of DLALC to determine the find's significance, in consultation with a qualified archaeologist or NSW Environment and Heritage,.
 - Works are not to proceed until written advice is provided from the archaeologist or NSW Environment and Heritage on the appropriate management of the find.
- d) It is recommended that an Unexpected Human Remains procedure be implemented for the duration of the project. In the unlikely event that suspected Human Remains are identified the procedure should include the following:
 - Works are to stop immediately.
 - The area of the suspected Human Remains find is to be secured and cordoned off.
 - NSW Police are to be notified. No further works can be undertaken until the NSW Police provide written advice.
 - If these remains are deemed to require archaeological investigation by the NSW Police or NSW Coroner, then:
 - NSW Environment and Heritage and the relevant Aboriginal parties must be notified; and
 - a plan of management for the preservation of any identified Aboriginal human remains of for the salvage must be put in place or conducted under an AHIP methodology and variation developed in consultation with all relevant Aboriginal parties and the NSW Environment and Heritage.
 - Works are not to proceed until written advice is provided from the archaeologist or NSW Environment and Heritage.

September 2025 Page 6 of 61



Contents

1.	Introduction	12
1.1	Project Team and Qualifications	13
1.2	Acknowledgements	13
2.	Description of the Area	15
2.1	Location	15
2.2	Environmental Context	15
2.3	Aboriginal Heritage Context	19
2.3.1	1. Ethnohistory	19
2.3.2	2. Archaeological Context	2
3.	Consultation Process	28
3.1	Overview of the Consultation Process	28
3.2	Submissions/Comments on Methodology	34
3.3	Comments Made During Fieldwork	34
3.4 on Ca	Submissions/Comments on Draft ACHA and AA reports, AHIP Application and RD&M, and Gare and Control	
4.	Summary and Background Information	41
5.	Cultural Heritage Values and Statements of Significance	43
5.1	Assessment of Significance	43
5.2	Summary and Statement of Significance	45
6.	The Proposed Activity	46
6.1	Areas Where Objects will be Protected or Harmed	47
7.	Avoiding or Mitigating Harm	49
7.1.1.	Pre-lodgement consultation	49
7.1.2.	Consideration of Alternatives	50
7.2	Areas Where Objects will be Protected or Harmed	50
7.3	Justification of the Objectives of the Proposed Activity	50
7.4	Ecologically Sustainable Development (ESD)	51
8.	Recommendations	52
Refe	erences	54

Appendices

Appendix A Archae	ological Assessr	nent Report
-------------------	------------------	-------------

Appendix B Aboriginal Consultation Log

Appendix C Research Design and Methodology



Appendix D AHIMS Site Search and other Search Results

Appendix E Proposal Plans

Appendix F AHIMS Site Cards

Tables

Table 1: Soil profiles and depths from geotechnical investigations in Lot 14 (Morrow 2023: Table 2) Table 2. Summary of AHIMS Features within the Search Area												
						able 4: Aboriginal Parties/Individuals Registered Interest for this Project						
						Table 5: Compliance with the ACHRs						
Table 6: Comments Made During Fieldwork	34											
Table 7: Summary of Comments on Project Methodology, Draft ACHA and AA reports and Proposed												
Table 8: Assessment of the Burra Charter Values within the Project Area	43											
Table 9: Summary of Project Proposal.	46											
Table 10: Summary of Likely Harm	48											
Table 11: Summary of Likely Harm	50											
Figures												
Figure 1. Project area and locality	14											
Figure 2 Modified floodplain landform within the project area (Morson Group 2024)	15											
igure 3. A cross section of the Cranebrook Terrace with date ranges from Williams et al. 2017												
igure 4. Topography and Hydrology												
Figure 5. Identified Aboriginal Objects part of the Penrith Lakes 2025 Background Scatter within the Area												
Figure 6. AHIMS Sites, AHIPs, and Heritage Items within the Vicinity of the Project Area	27											

September 2025 Page 8 of 61



Definitions

DPC

DPIE

EP&A Act

September 2025

Abbreviations Description AAArchaeological Assessment ALR Act Aboriginal Land Rights Act 1983 **ACHA** Aboriginal Cultural Heritage Assessment **ACHCR** Aboriginal Cultural Heritage Consultation Requirements for Proponents 2010 (DECCW 2010) AHD Australian Heritage Database **AHIMS** Aboriginal Heritage Information Management System **AHIP** Aboriginal Heritage Impact Permit **AIATSIS** Australian Institute of Aboriginal and Torres Strait Islander Studies **ALRA** Aboriginal Land Rights Act 1976 AR Archaeological Report, Archaeological Assessment **ARDM** Archaeological Research Design and Methodology **BGL Below Ground Level** BP **Before Present CABAH** Australian Research Council Centre of Excellence for Australian Biodiversity and Heritage **CHMP** Cultural Heritage Management Plan CoP Code of Practice for Archaeological Investigation of Aboriginal Objects in New South Wales (DECCW 2010) DA **Development Application** DCCEEW/DCCEW NSW Department of Climate Change, the Environment and Water/ Department of Environment, Climate Change and Water DD Due Diligence DD Code, Due Due Diligence Code of Practice for the Protection of Aboriginal Objects in New Diligence Code South Wales (DECCW 2010) **DLALC** Deerubbin Local Aboriginal Land Council

NSW Department of Premier and Cabinet

NSW Department of Primary Industry and Environment

Page 9 of 61

Environmental Planning and Assessment Act 1979



EPBC Act Environment Protection and Biodiversity Conservation Act 1999

GIA Guide to investigating, assessing and reporting on Aboriginal Cultural heritage in

NSW (OEH 2011)

HNSW Heritage NSW

ILUA Indigenous Land Use Agreement

LALC Local Aboriginal Land Council

LEP Local Environmental Plan

LGA Local Government Area

NNTT National Native Title Tribunal

NPW Act National Parks and Wildlife Act 1974

NPW Reg National Parks and Wildlife Regulation 2019

NPWS NSW National Parks and Wildlife Service

NSW New South Wales

NSWALC NSW Aboriginal Land Council

NTA Native Title Act 1983

OEH NSW Office of Environment and Heritage (now Heritage NSW)

PAD Potential Archaeological Deposit s an area where sub-surface stone artefacts

and/or other cultural materials are likely to occur

PBC Prescribed Bodies Corporate

PLDC Penrith Lakes Development Corporation

RAP Registered Aboriginal Party

RAPs Registered Aboriginal Parties

RD&M Research Design and Methodology

REF Review of Environmental Factors

RNTBC Registered Native Title Body Corporate

S.139 Section 139 of the *National Parks and Wildlife Act 1974*

S.140 Section 140 of the *National Parks and Wildlife Act 1974*

S.170 Section 170 of the *National Parks and Wildlife Act 1974*

September 2025 Page 10 of 61



Glossary

Aboriginal object - A term used in the NPW Act legislation, meaning: '... any deposit, object or material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of the area that comprises NSW, being habitation before or concurrent with (or both) the occupation of that area by persons of non-Aboriginal extraction, and includes Aboriginal remains' (s.5 NPW Act).

Registered Aboriginal party – An individual or party who registers for Aboriginal consultation as part of the consultation and notification process following Aboriginal cultural heritage consultation requirements for proponents 2010 (NSW DECCW 2010b).

AHIP – An Aboriginal Heritage Impact Permit which is a document provided by Heritage NSW which provides a defence to the applicant to certain activities which constitute 'harm' to Aboriginal objects or Aboriginal places under Part 6 of the NPW Act. A proponent must prepare an application for an AHIP and other relevant documentation (including an ACHA) to obtain an AHIP from Heritage NSW in the Department of Premier and Cabinet.

Declared Aboriginal place - A term used in the NPW Act legislation, meaning any place declared to be an Aboriginal place (under s.84 of the NPW Act) by the Minister administering the NPW Act, by order published in the NSW Government Gazette, because the Minister is of the opinion that the place is or was of special significance with respect to Aboriginal culture. It may or may not contain Aboriginal objects.

Due Diligence assessment – Due diligence is taking reasonable and practical steps to determine whether a person's actions will harm an Aboriginal object and, if so, what measures can be taken to avoid that harm. A due diligence assessment will assess the potential for harm and provide recommendations to mitigate harm, generally in the form of an Aboriginal Cultural Heritage Assessment (ACHA), if Aboriginal objects or places are likely to be harmed by proposed works.

Harm - A term used in the NPW Act Amendments meaning '... any act or omission that destroys, defaces, damages an object or place or, in relation to an object - moves the object from the land on which it had been situated' (s.5 NPW Act).

Project area - Area proposed to be impacted as part of a specified activity or development proposal. These activities include indirect impact.

Place - An area of cultural value to Aboriginal people in the area (whether or not it is an Aboriginal place declared under s.84 of the Act).

Proponent - A person proposing an activity that may harm Aboriginal objects or declared Aboriginal places and who may apply for an AHIP under the NPW Act.

September 2025 Page 11 of 61



1. Introduction

Morson Group Consultants proposes to develop a tourism precinct at 39-65 Old Castlereagh Road, Castlereagh NSW (Lots 12, 14 and 16 DP793163, Figure 1). The project area is located within the Penrith Local Government Area (LGA), within the boundary of Deerubbin Local Aboriginal Land Council (DLALC).

The proposed scope of works as provided by Morson Group seeks approval for a tourism-oriented development comprising three (3) buildings across separate lots, including a hotel, an indoor recreation facility with two (2) drive-through restaurants, and a registered club. The proposal also includes associated vehicle access, on-grade and above-ground parking, and site infrastructure.

- Lot 12:
 - A seven (7) storey hotel with 147 rooms, restaurant, gym, spa, pool, and associated facilities.
 - Multi-level above-ground car parking.
- Lot 14:
 - A 5,713m² indoor recreation facility.
 - Two (2) restaurants with capacity for a drive-through.
 - Associated on-grade car parking.
- Lot 16
 - A 5,177m² registered club building.
 - Associated on-grade car parking.

It is likely that excavations across the site will be part of the overall redevelopment works with most excavations anticipated to be up to 0.15 - 1.74 m depth, though excavation of stormwater system and footings will also likely be required. Excavations in these areas are anticipated to be between 0.63 - 2.3 m depth.

AHIP CO001415 (AHIMS 3891), now expired, was previously issued over the project area. Previous Aboriginal cultural heritage assessments have identified that the project area may contain in-situ stratigraphy and low densities of Aboriginal objects associated with the alluvial Penrith Unit of the Cranebrook Terrace (PLDC 2011, Virtus Heritage 2024). The proposed works therefore have the potential to harm Aboriginal objects and/or places.

Virtus Heritage Pty Limited (hereafter 'Virtus Heritage') was engaged by Morson Group to prepare an Aboriginal Cultural Heritage Assessment (ACHA), including an Archaeological Assessment (AA) for the proposed development. The ACHA was compiled to accompany an Aboriginal Heritage Impact Permit (AHIP) with Archaeological Research Design and Methodology (ARDM). The objectives of the ACHA are to investigate and assess the impact of Castlereagh Tourism Development on known and potential Aboriginal objects, Aboriginal places, and cultural heritage values within the project area as well as to provide appropriate management and mitigation strategies. This report has been compiled to meet the requirements of the *Guide to investigating, assessing and reporting on Aboriginal cultural heritage in NSW* (OEH 2011).

An Archaeological Assessment was also compiled to consider the scientific values of the project area, which is an Appendix (Appendix A), to the ACHA. The purpose of the Archaeological Assessment is to provide Morson Group with archaeological advice on the potential impact of their proposal on Aboriginal archaeological sites and to meet the requirements of the *Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW* (DECCW 2010a) for Archaeological Reports – Requirements 1 to 11).

September 2025 Page 12 of 61



1.1 PROJECT TEAM AND QUALIFICATIONS

This report was originally compiled by Clare Anderson (Principal Archaeologist, Virtus Heritage, BA (Hons) Prehistoric and Historical Archaeology) with assistance from Anya Graubard (Anthropologist/Heritage Senior Consultant, Virtus Heritage, BA (Hons) Anthropology) and then updated Liam Clerke (Senior Geomorphologist/GIS Analyst, Virtus Heritage, MRes Paleohydrology, Macquarie University) and Dr Mary-Jean Sutton. GIS mapping was completed by Liam Clerke. Quality review was undertaken by Dr. Mary-Jean Sutton (Director, Virtus Heritage, PhD Archaeology, University of Queensland; B.Arts Hons, Archaeology, University of Sydney). Project information and description of works was provided by Peter Morson and Joshua West of the Morson Group.

1.2 ACKNOWLEDGEMENTS

We would like to acknowledge the assistance of the following individuals for the completion of this report:

- Steven Randall, Deerubbin Local Aboriginal Land Council
- Peter Morson, CEO, Morson Group
- Joshua West, Graduate Architect, Morson Group

September 2025 Page 13 of 61





Figure 1. Project area and locality

September 2025 Page 14 of 61



2. Description of the Area

The purpose of this section is to describe the geographic location of the project area, its environmental context, any known Aboriginal objects and places within the project area and surrounding locality and provide a summary of Aboriginal history within the locality. Much of this information is provided in detail in the attached AA (Appendix A) and only briefly summarised here.

2.1 LOCATION

The project area is located at 39-65 Old Castlereagh Road, Castlereagh NSW (Lots 12, 14 and 16 DP793163, Figure 1). The project area is situated within the Penrith Local Government Area (LGA), within the boundary of Deerubbin Local Aboriginal Land Council (DLALC).

2.2 ENVIRONMENTAL CONTEXT

A detailed description of the environmental context is provided in Section 3 of the AA (Appendix A).

The project area is situated within a modified landform on terrain elevated above the Nepean River and an unnamed tributary of Cranebrook Creek, now destroyed. The unnamed tributary of Cranebrook Creek, as well as a chains of ponds, were once present approximately 300 m north-east of the project area, with the Nepean River approximately 650m south-east and Cranebrook Creek 1.7 km west.



Figure 2. Modified floodplain landform within the project area (Morson Group 2024)

The temporary and permanent water sources in proximity to the project area would have provided suitable habitats for a vast range of plant and animal species with utility to Dharug-speaking people, with the availability of these resources changing over the last 40,000 years. Environmental shifts such as those indicated by Chalson and Martin (2008) can lead to changes in water channel and chain of ponds alignment, flooding regimes and resource availability. These in turn can lead to adaptation and changes in landscape use by Aboriginal people over time, resulting in patterns of land use and preservation of Aboriginal objects which may not be immediately apparent based on current environmental conditions.

September 2025 Page 15 of 61



The Penrith Lakes Scheme, inclusive of the project area, has previously been assessed as having a reasonable potential to contain Aboriginal objects. PLDC (2011) has previously stated that "flaked stone artefacts will be present within the soil across the Scheme in a consistently low-density distribution."

The project area contains silty sand/sandy silt topsoils to a depth of 0.6 m, followed by alluvial clayey sand/silty sand to depths between 3.3 and 6 m, characteristic of the Richmond soil landscape within the Penrith Unit of the Cranebrook Terrace. It has been theorised that Aboriginal objects would most likely been discarded on the surface of this older alluvium unit, with downward migration of artefacts over time as a result of bioturbation, disturbance and other geomorphic agents such as erosion and aggradation (Kohen 1997, 2004 see **Section 4**).




Figure 3. A cross section of the Cranebrook Terrace with date ranges from Williams et al. 2017.

Table 1: Soil profiles and depths from geotechnical investigations in Lot 14 (Morrow 2023: Table 2)

Approx. Depth Range of Uni			nge of Unit ¹ n	nBGL			
Unit	Material	BH1	BH2	ВН3	ВН4	ВН5	вн6
1	Topsoil	0.0 to 0.5 (24.2 to 23.7)	0.0 to 0.6 (23.8 to 23.2)	0.0 to 0.6 (24.0 to 23.4)	0.0 to 0.3 (24.0 to 23.7)	0.0 to 0.6 (24.1 to 23.5)	0.0 to 0.3 (24.1 to 23.8)
2	Medium Dense Sand	0.5 to 6.0 (23.7 to 18.2)	0.6 to 5.5 (23.2 to 18.3)	0.6 to 4.2 (23.4 to 20.0)	0.3 to 3.3 (23.7 to 20.7)	0.6 to 3.8 (23.5 to 20.3)	0.3 to 3.8 (23.8 to 20.3)
3	Alluvial Cobbles	6.0 to 13.9 (18.2 to 10.3)	5.5 + (sub 18.3)	4.2 + (sub 19.8)	3.3 + (sub 20.7)	3.8 + (20.7 to 20.3)	3.8 + (sub 20.3)
4	Shale Bedrock	13.9 to 14.6 (10.3 to 9.6)	-	-	-	-	
Notes:	Deurock	(

¹ Depths shown are based on material observed within test locations and will vary across the site.

September 2025 Page 16 of 61



This project area has been modified through agricultural activities, underground irrigation piping, the construction of residential structures, geotechnical investigations and ancillary infrastructure. The project area is also susceptible to flooding.

These activities may have removed Aboriginal objects in the topsoil but are more likely to have moved or displaced Aboriginal objects within the top 0.6 m of soil, resulting in low archaeological integrity in the topsoil. It is possible that intact archaeology has survived within the project area, particularly below the level of agricultural activities however, as noted by Kohen (1997, 2004), it is also possible that artefacts have moved through the soil profile as a result of bioturbation.

September 2025 Page 17 of 61






Figure 4. Topography and Hydrology

September 2025 Page 18 of 61



2.3 ABORIGINAL HERITAGE CONTEXT

This section is designed to provide a description of the Aboriginal heritage context as relevant to the proposed project. The Aboriginal heritage context includes a summary of Aboriginal history within the locality and material evidence of Aboriginal land use, which is a summary of information presented in much greater detail in the AA (refer to Appendix A, Sections 4, 5 and 6).

2.3.1. Ethnohistory

Historic information of Aboriginal people living on the land includes relevant archival, historic and ethnohistoric sources. This research will provide the historical narrative of the peoples who have and continue to live in the region.

Local histories often pay little attention to the Aboriginal history of the locality and can present Aboriginal people as invisible, unrelated to important local historical events, or passive victims of colonisation. So, while local historical information will provide important and valuable starting points, when investigating historic values involving Aboriginal people and obtaining oral history is important.

The project area is part of a broader Aboriginal cultural landscape of the Dharug-speaking peoples. The Penrith Lakes area is associated with the Boorooberongal and Mulgoa clans (PLDC 2011, Karskens 2007). The Blue Mountains, Cranebrook Escarpment and Nepean River connect with shared songlines between Dharug, Darkinjung and Gundungurra Nations (PLDC 2011, Blue Mountains City Council 2017).

The Penrith Lakes area was a traditional meeting place for Aboriginal people. Its river and rich soils provided abundant natural vegetation and wildlife which supported Aboriginal people for many generations (New South Wales State Heritage Register, Department of Planning & Environment. HO2009, 2024). Evidence of this history has been revealed through the many artefacts were collected during the 25 years of sand and gravel mining at Penrith Lakes, to the north, west and south of the project area (Kohen 1986, 1988–2004, 1997, EMGA 2001, Comber 2005, 2006, 2008, PLDC 2011, New South Wales State Heritage Register. Department of Planning & Environment. HO2009, 2024). In addition to the eight-five Aboriginal cultural heritage sites registered within a 4 km radius of the project area, there are additional Aboriginal cultural heritage sites were not recorded in AHIMS (ERM 2001, Insite Heritage 2005).

Substantial stone artefact workshops have been identified along the banks and terraces of Cranebrook Creek and the Nepean River, with many suitable stones for the manufacture of stone tools being sourced from the river and its creeks (Doelman et al 2015). Cranebrook Creek CC/1 (AHIMS 45–5–0281), listed as an artefact and Aboriginal Ceremony and Dreaming site, was located approximately 1.4 km to the north-west of the project area.

The first interactions recorded between Europeans and Aboriginal people along the Hawkesbury-Nepean (hereto referred to as 'Dyarubbin') Rivers was recorded by Governor Arthur Philips in 1791. The Aboriginal group identified themselves as 'Buruberongal' and spoke in a dialect of the Dharug language (Eco Logical 2021). These initial interactions were reportedly friendly (though recordings were undertaken by the colonists and therefore biased), but details of gift and food exchanging have been noted. Further colonisation, smallpox epidemics, bush warfare, over exploitation and destruction of natural resources led to the direct theft of Aboriginal children, the effects of which are still felt by the wider Aboriginal community now.

Main food sources in the project area would have included kangaroos, fruit bats, possums and small birds and freshwater mussels and yams growing along Dyarubbin River floodplains. However, by 1795 much of these yam beds had been destroyed and replaced with non-native crops (Eco Logical 2021). Nellie Nah

September 2025 Page 19 of 61



Doongh, or 'Black Nellie' was often referred to as the last of the 'Nepean tribe", living amongst colonists along the Yandhi. Karskens (2019) recounts how Nellie "was about 3 or 4 years old when white people appeared in her country, and the thing that she talked about was how the settlers shot all the game – the soundtrack of invasion was gunfire."

The colonisers' approach was extended beyond physical occupation to erasing the presence and identity of the Aboriginal people. In this context, the "unparalleled severities" (Karsens 2019) employed by colonisers can be seen as part of a deliberate strategy to annihilate the Aboriginal peoples' way of life, thereby facilitating the unchallenged appropriation of their land. The legacy of these actions is profound, having caused lasting trauma and disruption to Indigenous communities. Understanding this history is crucial for acknowledging the injustices faced by Aboriginal people and for addressing the ongoing impacts of colonisation (Karskens 2019).

However, it is also essential to recognise the resilience and agency of Aboriginal people (especially Western Sydney), where communities continue to assert their cultural identity. A prominent example of this resilience is embodied in the story of Colebee. The son of Chief Yarramundi, Colebee, acted as a guide to William Cox during his surveys and construction of a road across the Blue Mountains (Smith 2013). Mills (1997) notes that the remnants of the Aboriginal bands that had occupied the Cumberland Plain began to congregate on properties owned by sympathetic individuals, including William Cox. Colebee and Nurragingy were rewarded for their 'fidelity to Government and their recent good conduct' with a 30-acre land grant in 1819, two years after the establishment of the Parramatta Native Institution, a residential school in the area (Smith 2013). Governor Macquarie strategically settled Europeans known to Colebee and Nurragingy near Blacktown to assist with the assimilation process (GML 2018). The land was farmed by Nurragingy and his family until the closure of the Blacktown Native Institution in 1883. Colebee passed away in 1831, while Nurragingy was known to be living in the area by 1841, though his exact date of death is unknown (Brook and Kohen 1991:53). Despite extensive modifications and land use changes, the significance of the original Colebee and Nurragingy land grant endures.

To the north of the project area, near Hadley Park, the Nepean River was one of the many first contact places where local Aboriginal people were able to stay on their traditional lands by camping and working for the colonial settlers. It was a place of confrontation between Aboriginal people and colonial settlers before more peaceful relationships were established (New South Wales State Heritage Register. Department of Planning & Environment. HO2009, 2024).

These events highlight the resilience and agency of Aboriginal people with a connection to the project area, who navigated and utilised the colonial system to maintain a connection to their land and culture. Their efforts demonstrate the strength and adaptability of Aboriginal communities in the face of colonisation which continues today.

The Deerubbin Local Aboriginal Land Council (DLALC) continues to uphold its connections to and protect Country, with recent years marking several significant achievements for the council. A notable victory came after a three-year court battle, where the DLALC successfully won a land claim over the Parramatta Gaol and its surrounding areas. This site holds great cultural significance for the Dharug people, serving as an important area before the construction of the jail in 1841 (ABC News 2015).

Additionally, in 2021, the DLALC reached an agreement with the New South Wales (NSW) government to support the development and protection of land managed by the council. This agreement aims to safeguard 1,100 hectares of woodland on the Cumberland Plain, ensuring the preservation of this vital ecosystem (Mirage News 2021). Through these efforts, the DLALC demonstrates its ongoing commitment to preserving its cultural heritage and protecting the natural environment.

Aboriginal people, organisations and reference groups have continued to actively be involved in advocating for the protection of Aboriginal cultural heritage, archaeological assessment and care of Country across the local area, including the Penrith Lakes area (for example, Kohen 1988–2004, PLDC 2011, consultation for SEPP amendments 2023).

September 2025 Page 20 of 61



2.3.2. Archaeological Context

The detailed archaeological context including AHIMS and other heritage database searches, previous archaeological research, regional character, and predictive model, as well as mapping of previously recorded sites and landscape features, place, and natural resources of interest to Aboriginal people, are provided in Sections 4, 5 and 6 of the AA (Appendix A). A summary of this context is provided here.

An AHIMS search was completed on 10 July 2025 for search area (Client Service ID: 912988, GDA, Zone: 56, Eastings: 281848 – 289036, Northings: 6261482– 6270558, Appendix C). A total of eighty-seven Aboriginal cultural heritage sites were returned by the search (Table 2). No Aboriginal objects were recorded in the project area (Figure 6).

Table 2. Summary of AHIMS Features within the Search Area

Site Features	Frequency	Percentage (%) of Total
Art (Pigment or Engraved)	2	2.3%
Artefacts	74	85.1%
Artefact, Aboriginal Ceremony and Dreaming	1	1.1%
Artefact; Potential Archaeological Deposit (PAD)	7	8.0%
Potential Archaeological Deposit (PAD)	3	3.4%
Grand Total	87	100.0%

The nearest previously recorded Aboriginal cultural heritage site to the project area was "Andrews Road PAD 1" (AHIMS ID#45-5-5238), a PAD with stone artefacts associated. This site was destroyed in accordance with Aboriginal Heritage Impact Permit #4518 (Appendix B). This site is located approximately 1.1 km southeast of the project area.

The project area has previously been assessed for Aboriginal archaeological and cultural heritage values as part of the Penrith Lakes Development Scheme (Kohen 1981, Penrith Lakes Development Corporation (PLDC) 2011). This report consolidated previous archaeological assessments and survey coverage data up to 2011 and included consultation in accordance with the *Aboriginal community consultation requirements for proponents* (DECCW 2010). Volumes 1, 2 and 3 and Map 14 were not available to review for this assessment. Morson Group has requested this information from Heritage NSW and Penrith Lakes Development Corporation.

A model of past Aboriginal land use was developed for the Penrith Lakes Scheme. PLDC (2011) concluded that the Dharug speaking Aboriginal people who lived on the Cranebrook Terrace and associated landforms (such as the Smith Road conservation area ridge) hunted and gathered across the landscape with selection of elevated landforms as favoured camping locations. The assessment concluded that "it is assumed that flaked stone artefacts will be present within the soil across the Scheme in a consistently low-density distribution."

AHIP CO001415 (AHIMS 3891) was issued to PLDC over the project area between 15 November 2018 and 15 November 2023 to allow harm to known and unknown Aboriginal objects without mitigation of harm during vegetation works and erosion and sediment control works as described in Controlled Activity Approval 10 ERM 2011/0057 (Figure 6). This AHIP has expired.

An Aboriginal archaeological due diligence assessment was completed for the project (Virtus 2024) and included an archaeological survey with Virtus Heritage and Uncle Steven Randall (Deerubbin LALC). Survey coverage from this site inspection is presented in Section 6 of this report. No Aboriginal objects were identified in this initial survey. In a subsequent survey undertaken by 24 February 2025 with Dr Mary–Jean Sutton (Director) assisted by Anya Graubard (Virtus Heritage) and Tania Carroll (Murribigee), Vicky Slater

September 2025 Page 21 of 61



(Wurrumay) and Anika Jalomaki (Yulay) Aboriginal objects were identified in eight exposures within the project area. These exposures were identified within the project area. in one consistent landform and constitute one identified Aboriginal artefactual scatter, Penrith Lakes 2025 (PL2025) in the February 2025 survey. A background scatter of low density artefacts associated with the alluvial terrace/floodplain landform. Table 3 provides as summary of these exposures and the artefacts identified in Penrith Lakes 2025, recorded by Dr Sutton with RAPs.

Table 3. Aboriginal Objects (stone tools) within Penrith Lakes 2025 Recorded within the Project Area.

ĕ	· ·
Site and Object Recorded	Description Including Landform
PL 2025 - Retouched Flake	The object is a retouched meta-mudstone flake located along the fence line of a residential property (refer to Figure 5). It is a location heavily disturbed by generational agricultural and residential use. The object is located on an alluvial terrace. The object is situated along an exposure associated with the southern fence line of the project area. The exposure is approximately 1 meter wide and 100 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The tool is a tertiary flake with evidence of retouch and some patina and is a yellow – orange meta-mudstone 4 cm length x 2 cm width x 0.5 cm thick.
PL 2025 - Quartzite PF1	The object is a primary quartzite flake located along the fence line of a residential property (refer to Figure 5). It is a location heavily disturbed by generational agricultural and residential use. The object is located on an alluvial terrace. The object is situated along an exposure associated with the western fence line of the project area. The exposure is approximately 1 meter wide and 90 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. It is a primary flake with evidence of pitting and some patina and is a yellow – tan quartzite 6 cm length x 2.5 cm width x 1.5 cm thick.
PL 2025 – Meta-Mudstone SF1	The object is a secondary meta-mudstone flake located along the fence line of a residential property (refer to Figure 5). It is a location heavily disturbed by generational agricultural and residential use. The object is located on an alluvial terrace. The object is situated along an exposure associated with the southern fence line of the project area. The exposure is
	approximately 1 meters wide and 60 meters long. Visibility in

September 2025 Page 22 of 61

the exposure was 70% and outside the exposure was 1%. The object is a secondary flake with evidence of pitting and some patina and is a yellow – orange meta–mudstone 2 cm

length x 1.5 cm width x 0.5 cm thick.



Site and Object Recorded Description Including Landform

PL 2025 -Quartzite SF1



The object is a secondary quartzite flake located along the fence line of a residential property (refer to **Figure 5**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The site is situated along an exposure associated with the southern fence line of the project area. The exposure is approximately 1 meter wide and 60 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The object is a secondary flake with evidence of pitting and some patina and is a reddish orange quartzite 2.5 cm length x 2 cm width x 1.5 cm thick.

PL 2025 - AS1



The objects are part of a small scatter of at least one pink quartzite broken flake and three grey silcrete broken flakes and a red silcrete broken flake located along the fence line of a residential property (refer to **Figure 5**). Visibility in the exposure was 70% and outside the exposure was 1%. It is a location heavily disturbed by generational agricultural and residential use and erosion from heavy rain falls in February 2025.

The site is located on an alluvial terrace. The site is situated along an exposure associated with the southern fence line of the project area. The exposure is approximately 1 meter wide and 60 meters long.

PL 2025 – Basalt Hand Axe



The object recorded is a basalt hand axe located along the fence line of a residential property (refer to **Figure 5**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The site is situated along an exposure associated with the southern fence line of the project area. The exposure is approximately 1 meter wide and 100 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The object is a hand axe with evidence of flaking, pitting and some patina and is a greyish black basalt 7 cm length x 5 cm width x 2.5 cm thick. There is also evidence of blood as shown in the photograph on the tool or some kind of residue.

September 2025 Page 23 of 61



Site and Object Recorded

PL 2025 - Basalt PF1



The object is a primary basalt flake located along the fence line of a residential property (refer to **Figure 5**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The object is situated along an exposure associated with the northwestern fence line of the project area. The exposure is approximately 4 meter wide and 10 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The artefact is a tertiary flake with evidence of pitting and some patina and is a greyish black basalt 4.5 cm length x 3 cm width x 1 cm thick.





The object is a secondary basalt flake located along the fence line of a residential property (refer to **Figure 5**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The site is situated along an exposure associated with the northwestern fence line of the project area. The exposure is approximately 4 meter wide and 10 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The isolated object is a secondary flake with evidence of pitting and some patina and is a dark greyish black basalt 2.5 cm length x 2 cm width x 1 cm thick.

September 2025 Page 24 of 61





Figure 5. Identified Aboriginal Objects part of the Penrith Lakes 2025 Background Scatter within the Project Area

September 2025 Page 25 of 61



Ground surface visibility in the project area was extremely limited (<1%) due to the high level of non-native grass. All mature trees within the project area were identified as non-native species. The inspection confirmed that the project area had undergone ground disturbance associated with the construction of the existing houses, and landscaping works. Underground irrigation piping had been installed across the project area. On the basis of the previous assessment (PLDC 2011) and the presence of the Penrith Unit of the Cranebrook Terrace, the due diligence assessment considered that archaeological potential was present and community consultation and further impact assessment was required.

It is anticipated that the project area, as elevated terrain in proximity to water, was utilised by Aboriginal people in the past but not as intensively as other parts of the Penrith Lakes area as it is 300 m or greater from water. Stone artefacts are predicted to occur within the project area "in a consistently low-density distribution" to depths of 1.3 m (but often to 0.9 m). Artefacts may be manufactured of predominately silcrete and occasionally quartz, chert, quartzite, hornfels and basalt. Other site types and features are possible but unlikely to occur in the project area as they have not previously been identified within the project area during previous assessments and due to the degree of past land use and disturbance and a lack of suitable geology and vegetation.

Though Aboriginal objects were only identified within surface exposures over the project area, there exist numerous studies which appropriately characterise the distribution of Aboriginal objects within the Penrith Unit of the Cranebrook Terrace (see **Appendix A**).

September 2025 Page 26 of 61






Figure 6. AHIMS Sites, AHIPs, and Heritage Items within the Vicinity of the Project Area

September 2025 Page 27 of 61



3. Consultation Process

3.1 OVERVIEW OF THE CONSULTATION PROCESS

We acknowledge that Aboriginal people are the primary determinants of the cultural significance of their heritage. Aboriginal consultation for the ACHA was undertaken in compliance with the Aboriginal cultural heritage consultation requirements for proponents 2010 (DECCW 2010b) (hereafter referred to as the "ACHRs"). These consultation requirements are legal requirements that proponents must comply with during the ACHA process which are set out in Clause 60 of the National Parks and Wildlife Regulation (2019). Aboriginal consultation is crucial in the compilation of the ACHA in order to adequately assess and investigate Aboriginal cultural heritage.

Consultation is important with registered Aboriginal parties in this process in order to:

- · determine the cultural significance of a project area;
- · identify Aboriginal objects of cultural value within a project area; and
- identify places of Aboriginal cultural value (whether or not they are Aboriginal places declared under Section 84 of the NPW Act).

Twenty-two Aboriginal Parties/individuals registered interest for this project during the notification process (responded to the advertisements in the local newspapers or to an invitation to register in the project after their contact details were provided by notified organisations). The groups/individuals registered for consultation are listed in **Table 4**.

Table 4: Aboriginal Parties/Individuals Registered Interest for this Project

Deerubbin Local Aboriginal Land Council
Wailwan Aboriginal Group
Mura Gadi Aboriginal Corporation
Long Gully Cultural Services
Gadhungal Marring
Murra Bidgee Mullangari Aboriginal Corporation
Dharug Custodian Aboriginal Corporation
Wallanbah Aboriginal Site Conveyancing
Amanda Hickey Cultural Services
A1 Indigenous Services
Butucarbin Aboriginal Corporation
Kamilaroi Yankuntjatjara Working Group
Wurrumay Culture Heritage Consultants

September 2025 Page 28 of 61



Steven Hickey	Widescope Indigenous Group
Wendy Morgan	Guntawang Aboriginal Resources Incorporated
Pearl Depoma	Pearl Depoma (Individual)
Arika Jalomaki	Yulay Cultural Services
Thomas Dahlstrom	Thomas Dahlstrom (Individual)
Steven Johnson & Krystle Carroll	Ginninderra Aboriginal Corporation
Paul Webb	Paul Webb (Individual)
Robert Young	Konanggo Aboriginal Cultural Heritage Services
Undisclosed Registered Aboriginal Party	Undisclosed Registered Aboriginal Party

All consultation with Registered Aboriginal Parties undertaken by Morson Group and Virtus Heritage is documented in greater detail in **Appendix B**. Morson Group carried out the commercial engagement and selection of interested registered Aboriginal parties for fieldwork for this project Commercial engagement is stipulated in the ACHRs as separate to consultation and discussions between registered Aboriginal parties and Morson Group which are commercial in confidence will not be reiterated in the Aboriginal consultation log.

Table 5 provides a summary of compliance by this project with the ACHRs. It should be noted that consultation was undertaken through multiple forms of contact with registered Aboriginal parties for all correspondence including registered post via delivery confirmation, email (wherever possible), phone calls and SMS (where all other forms of contact were exhausted).

September 2025 Page 29 of 61



Table 5: Compliance with the ACHRs

Step #	Description of Step in the ACHRs	How this step of the ACHRS was complied with				
1: Notif	1: Notification of project proposal and registration of interest					
1a	Proponents must compile a list of Aboriginal people who have an interest in the proposed project area and hold knowledge relevant to determining the cultural significance of Aboriginal objects and/or places from reasonable sources of information which include writing to: The relevant Heritage NSW regional office; The relevant Local Aboriginal Land Council; The National Native Title Tribunal; Native Title Services Corporation; Relevant local council (s); and Relevant Local Land Services.	Letters were sent by Virtus Heritage to all of these relevant organisations (via email) requesting their input on the names and contact details of Aboriginal people who have an interest in the proposed project area and hold knowledge relevant to determining the cultural significance of Aboriginal objects and/or places within the locality of the project area on 24 September 2024.				
1b	 Proponent prepares a notification via newspaper which must include: The name and contact details of the proponent; A brief overview of the proposed project that may be the subject of an application for an AHIP, including the location of the proposed project; A statement that the purpose of community consultation with Aboriginal people is to assist the proposed applicant in preparing an application for an AHIP and to assist Heritage NSW in their consideration and determination of the application; An invitation for Aboriginal people who hold knowledge relevant to determining the cultural significance of Aboriginal object(s) and/or place(s) in the area of the proposed project to register an interest in a process of community consultation with the proposed applicant regarding the proposed activity; and A closing date for the registration of interests. 	A notification was placed in The Daily Telegraph in the Public Notices section on 27 September 2024 which complied with these requirements and is provided in Appendix B. A closing date of Wednesday 16 October 2024 was provided for registrations of interest.				
1c	Proponent writes to the Aboriginal people whose names were provided by organisations in Step 1a to notify them of the proposed project and opportunity to be involved in	Letters were sent to all Aboriginal people provided by organisations (unless they had registered interest already) via registered post with delivery confirmation and emailed				

September 2025 Page 30 of 61



	consultation and places notification in the local newspaper.	(wherever possible) on 2 nd October to comply with this step to invite them to be involved in consultation. Closing date for registrations was 21 st October 2024. Emails were made (wherever possible) to those who had not responded on 16 th October to remind people of closing date for registration.
1d	Proponent records names of Aboriginal people who have registered an interest in being involved in consultation – the 'Registered Aboriginal Parties'	Table 4 provides a list of the registered Aboriginal parties, who provided written registration of interest for this project.
1e	Proponent provides a copy of the notification and record of the Registered Aboriginal Parties to Heritage NSW and relevant LALC within 28 days of the closing date for registering an interest.	An email was sent to Heritage NSW and Deerubbin Local Aboriginal Land Council LALC to comply with this requirement on 4 th November 2024.
2 Pres	sentation of the information about the proposed p	project
2a	Proponent presents and/or provides project information to registered Aboriginal parties.	Project information package was presented via letter registered post with delivery confirmation and sent via email to all registered Aboriginal parties on 4th December 2024. This information included information from Virtus Heritage on the project proposal and the draft project methodology, requiring written responses/comments from registered Aboriginal parties by 20th January 2025. Virtus Heritage also included a separate letter requiring written response from registered Aboriginal parties for commercial engagement to be provided directly to Proponent. The invitation to discuss the project information with Virtus Heritage and Proponent was reiterated through phone calls and emails to the Registered Aboriginal Parties up to 20th January 2025.
2b	Proponent may create an opportunity for registered Aboriginal parties to visit the proposed project site.	22 registered Aboriginal parties were invited by Proponent to be involved in proposed fieldwork and to maintain an open dialogue on cultural knowledge and values. This invitation was sent out by Virtus Heritage by formal letter via email on 10th February 2025, with a date of 20th February 2025 scheduled for fieldwork.
2c	Proponent records or documents that information on the proposed project has been presented. The record or documentation should include any agreed outcomes and/or contentious issues that may require further discussion (where applicable). Proponent should provide a copy of this record or	Documentation of the information package is attached in the Aboriginal consultation log to this assessment. Copies of this correspondence were provided to Heritage NSW and RAPs with the draft ACHA.

September 2025 Page 31 of 61



documentation	to	registered	Aboriginal
parties.			

3 Gathering information about cultural significance

3a	Proponent presents and/or provides the
	proposed methodology (s) for the cultural
	heritage assessment to the registered
	Aboriginal parties for comment. registered
	Aboriginal parties have a minimum of 28 days
	after the proponent provides the methodology
	(s) to provide written or oral comment.

Project information package was presented via letter registered post with delivery confirmation and sent via email to all Registered Aboriginal Parties on 4th December 2024 with a closing date for comments set for 20th January 2025. Follow up phone calls were made on 7th January 2025.

Proponent considers input provided by registered Aboriginal parties and finalises methodology for implementation. Proponent documents how the input has been considered.

Project methodology was finalised and any comments from registered Aboriginal parties were taken into consideration where appropriate (refer to Section 3.1 for further discussion on implementation).

3c Proponent seeks information from registered Aboriginal parties to identify:

Whether there are any Aboriginal objects of cultural value; and

Whether there are places of cultural value (whether or not they are Aboriginal places declared under Section 84 of the NPW Act).

The presentation of project information and the draft proposed project methodology were provided to all registered Aboriginal parties via email and registered post on 4th December 2024 with a closing date of 20th January requesting information from registered Aboriginal parties in relation to this requirement.

An invitation to discuss the proposed methodology and cultural information on potential Aboriginal objects and places of cultural value with Virtus Heritage and the proponent was reiterated through phone calls and emails to the registered Aboriginal parties.

On 24 June 2024 by Steve Randall (DLALC), and Garth Thompson (Virtus Heritage), assisted by Anya Graubard (Virtus Heritage) carried out an initial survey for due diligence to discuss the project design and impacts as part of this project's Connecting with Country consultation process. A second survey was undertaken by 24 February 2025 with Dr Mary-Jean Sutton (Director) assisted by Anya Graubard (Virtus Heritage) and Tania Carroll (Murribigee), Vicky Slater (Wurrumay) and Anika Jalomaki (Yulay) and during both surveys these two questions were met in this requirement, as well as discussion of management inputs for the project for cultural values and Aboriginal cultural heritage to meet not only requirement 3a) but 3d) of the consultation process...

September 2025 Page 32 of 61



3d	Proponent seeks input from registered Aboriginal parties on potential management options	RAPs were provided with the presentation of project information and the draft proposed project methodology, which included the opportunity to provide input on potential management options within the project area via email and registered post on 4 th December 2024 with a closing date of 20 th January requesting information from registered Aboriginal parties in relation to this requirement. This request is reiterated again in the covering letter sent with this draft report for registered Aboriginal parties' comment and review
4 Revi	ew of draft cultural heritage assessment report	
4a	Proponent prepares draft cultural heritage assessment report and provides it to the registered Aboriginal parties for review and comment.	The draft AA and ACHA reports were provided to all registered Aboriginal parties via email on 28 th July 2025 with a closing date of 26 th August for comment.
		RAPs were provided the opportunity to a request hard copy to be sent via post.
4b	Registered Aboriginal parties have a minimum of 28 days after the proponent provides the draft report to review and provide written or oral comment.	The draft AA and ACHA reports were provided to all registered Aboriginal parties via email on 28 th July 2025 with a closing date of 26 th August for comment. An email reminder of the closing date of the review period was sent on 21 st August 2025 to RAPs who had not yet responded. A phone call reminder of the closing date of the review period occurred on 22 nd August 2025 to RAPs who had not yet responded. An email and SMS reminder of the closing date of the review period was sent on the morning of 26 th August 2025 to RAPs who had not yet
		responded.
4c	Proponent finalises cultural heritage assessment report. The final report is submitted to Heritage NSW for consideration with the proponent's AHIP application.	To be undertaken
4d	Proponent provides/makes available the final cultural heritage assessment report and AHIP application to the registered Aboriginal parties and relevant LALCs within 14 days of an AHIP application being made to Heritage NSW.	To be undertaken

September 2025 Page 33 of 61



3.2 SUBMISSIONS/COMMENTS ON METHODOLOGY

The purpose of this section of the report is to provide information on the submissions/comments raised about the proposed project methodology by registered Aboriginal parties and how these issues were addressed by the Proponent in order to comply with the ACHA guide (OEH 2011) and ACHRs (DECCW 2010b).

All registered Aboriginal parties were provided with the opportunity to provide comment on the methodology for this assessment, and to be involved in fieldwork. All submissions provided by the registered Aboriginal parties are provided in full in Appendix B and summarised in **Table 6** below. The finalised methodology is supplied in Appendix C.

3.3 COMMENTS MADE DURING FIELDWORK

Comments made by representatives from registered parties during fieldwork are summarised in Table 6.

Table 6: Comments Made During Fieldwork

Registered Party	Comments	Response		
Vicky Slater (Wurrumay Culture Heritage Consultants) Arika Jalomaki (Yulay Cultural Services) Tania Carroll (Murra Bidgee Mullungari Aboriginal Corporation)	 Values Importance of maintaining existing sightlines to the Blue Mountains from ground level (Blue Mountains visible). Emphasised significance of the area in all areas under Burra Charter, including contemporary ongoing connection to waterways near to the project area (the Penrith Lakes and Nepean River). Spoke of institutional homes such as Fern Hill Estate (12.5 km southwest of the project area). Spoke of matriarchal generational lines. 	Cultural values of sightlines and significance of waterways included in the significance assessment for this report.		
	Landscaping	Grass trees may be suitable for landscape inclusion are they are locally occurring. Kangaroo		

September 2025 Page 34 of 61



- Suggested planting of grey gums, grass trees and Kangaroo Paw trees.
- Northern terrace to meandering curves to the landscaped edge.
- Interested in use of macadamia and pecan nut trees by Aboriginal people, as various nut trees are currently within the project area (but are to be removed prior to construction).

Paws are native to Western Australia and therefore not an appropriate plan species for discussion.

Design

- Use of etched glass.
- Use of rooftop gardens.
- Tree canopy.
- Shadow play with perforated X.
- Supportive of potential access track.
 connecting project area to Penrith Lakes and nearby manmade waterways
- Usage of meandering curves rather than straight lines in design, including footpaths through the project area.
- Hesitant to limit use of solely Dharug language on any signage, as project are would have been utilised by various different Aboriginal groups, instead suggested signage refers to a "Shared Country" to be more inclusive, further to the fact that Penrith is a place for many different tribes that live together.
- Suggested colour palette be inspired by geological layers in project area.

Comments have been considered by Morson Group in the project co-design reporting for Connecting with Country and consultation. Cultural comment on Penrith being a place that many different tribes live together is included in the ACHA.

September 2025 Page 35 of 61



3.4 SUBMISSIONS/COMMENTS ON DRAFT ACHA AND AA REPORTS, AHIP APPLICATION AND RD&M, AND COMMENTS ON CARE AND CONTROL

A summary of submissions and comments on the draft project methodology, ACHA, AR and Research Design and Methodology are provided in **Table 7** once received.

Table 7: Summary of Comments on Project Methodology, Draft ACHA and AA reports and Proposed RD&M

Registered Aboriginal Stakeholder Group	Project Methodology	Draft ACHA and AA	Proposed RD&M	Care and Control	Additional Comments
Deerubbin Local Aboriginal Land Council	No comments.	No comment returned.	No comment returned.	No comment returned.	Stated that project area was very close to Aboriginal Lore grounds.
Wailwan Aboriginal Group	No comment returned.	No comment returned.	No comment returned.	No comment returned.	
Mura Gadi Aboriginal Corporation	No comment returned.	No comment returned.	No comment returned.	No comment returned.	
Long Gully Cultural Services	Supports draft project methodology.	No specific comment.	Supports the methodology and highly recommends and supports salvage, particularly around Penrith Lakes area because of its location and proximity to the mountains.	Would like artefacts collected to be reburied on the site because it is the right thing to do, and because of the repercussions of taking from Country, and emphasised that this is especially important because of the site's location.	Emphasised the importance of that area.

September 2025 Page 36 of 61



Gadhungal Marring	No comment returned.	No comment returned.	No comment returned.	No comment returned.	
Murra Bidgee Mullangari Aboriginal Corporation	Endorsed recommendations.	Endorsed recommendations.	Endorsed recommendations.	No specific comment.	
Dharug Custodian Aboriginal Corporation	Agrees with project methodology and recommendation for test excavations	Agrees with the recommendations.	Agrees with the recommendations.	No specific comment.	Stated this site is surrounded by sites and recommend testing on this site.
Wallanbah Aboriginal Site Conveyancing	No comment returned.	No comment returned.	No comment returned.	No comment returned.	
Amanda Hickey Cultural Services	Supports draft methodology.	Supports AA and ACHA.	Supports ARDM.	No specific comment.	
A1 Indigenous Services	Supports draft methodology.	Supports the information.	Supports the methodology.	No specific comment.	
Butucarbin Aboriginal Corporation	No comment returned.	No comment returned.	No comment returned.	No comment returned.	
Kamilaroi Yankuntjatjara Working Group	The study area is highly significant and sensitive to our people. Nepean River, which runs near Castlereagh, was an important water source & would have provided food such as fish and eels. It would have been used for hunting and gathering with	Agrees and supports the recommendations.	Agrees and supports the recommendations.	No specific comment.	Stated this area is highly significant and recommend testing on this site.

September 2025 Page 37 of 61



	river providing food sources & materials for tools and weapons. We agree and support your methodology and recommend further investigation in the way of test excavations before our culture is lost through development.				
Wurrumay Culture Heritage Consultants	Agrees with draft methodology.	Agrees with AA and ACHA.	Agrees with ARDM.	No specific comment.	The location of the area is significant to Aboriginal people on Dharug country + waterways with culture values holding spiritual connections
Widescope Indigenous Group	No comment returned.	"Nothing to add, everything's fine."	"Nothing to add, everything's fine."	Would like artefacts to be reburied on site as close to where they're found as possible depending on design.	
Guntawang Aboriginal Resources Incorporated	Supports draft methodology.	Agrees with the recommendations.	Agrees with the recommendations.	"We would like to recommend that any artefacts recovered from the excavation be displayed in the	Morson Group has no objection to this comment should artefacts be uncovered. This comment is included for RAP

September 2025 Page 38 of 61



				construction/ footpaths with a memorial of the first people of the land and information of what some of the artefacts were used for by our ancestors."	consultation in the Care strategy for the project in the Research Design and Methodology as well as this report for consideration.
Pearl Depoma	No comment returned.	No comment returned.	No comment returned.	No comment returned.	
Yulay Cultural Services	Agrees with draft methodology.	Agrees with AA and ACHA.	Agrees with ARDM.	No specific comment.	
Thomas Dahlstrom	No comment returned.	No specific comment.	Agrees with ARDM.	No specific comment.	
Ginninderra Aboriginal Corporation	No comment returned.	No comment returned.	No comment returned.	No comment returned.	
Paul Webb	No comment returned.	No comment returned.	No comment returned.	No comment returned.	
Konanggo Aboriginal Cultural Heritage Services	"KACHS has reviewed the draft presentation project information and the draft project methodology and acknowledged all processes in the project.	Cannot comment on the reports without having been on Country.	Cannot comment on the reports without having been on Country.	No specific comment.	Virtus Heritage emailed details of voluntary site inspection on 10 February 2025, set for 20th February and asked for RSVPs to be in by 18th Feb. On 10 February 2025, Robert rang Virtus Heritage and expressed concerns about lack of

September 2025 Page 39 of 61



	KACHS always suggests having an Elder and a Female or Male for their cultural knowledge through their cultural lens."				paid engagement, and declined to attend.
Undisclosed Registered Aboriginal Party	No comment returned.	No specific comment.	Happy with the ARDM but need to ensure AHIP works have equal number of men and women RAPs on field team, men's and women's toilets need to be separate and available onsite, and there should be a roster for RAPs on fieldwork so work can be spread equally across RAP groups.	Recommends reburial on Country with a smoking ceremony and elders as it provides them an opportunity to be involved in a capacity they are able to undertake. A tree planted on top, or some form of acknowledgement (plaque) could be placed at the reburial as an opportunity for tourist education.	

September 2025 Page 40 of 61



4. Summary and Background Information

As noted in **Section 4 of the AA**, the project area is part of a broader Aboriginal cultural landscape of the Dharug-speaking peoples and associated with the Boorooberongal and Mulgoa clans (PLDC 2011, Karskens 2007).

The Penrith Lakes area was a traditional meeting place for Aboriginal people (refer to Section 3 and RAP comments from Vicky Slater). Its river and rich soils provided abundant natural vegetation and wildlife which supported Aboriginal people for many generations (New South Wales State Heritage Register. Department of Planning & Environment. H02009, 2024). Evidence of this history has been revealed through the many artefacts were collected during the 25 years of sand and gravel mining at Penrith Lakes, to the north, west and south of the project area (Kohen 1986, 1988–2004, 1997, EMGA 2001, Comber 2005, 2006, 2008, PLDC 2011, New South Wales State Heritage Register. Department of Planning & Environment. H02009, 2024).

The survey results presented in **Section 6 of the AA**, indicate low surface visibility across the project area, with estimated effective coverage <1% and do not counteract the predictions of Aboriginal land use made in Section 5 of the AA which hypothesised that:

It is anticipated that the project area, as elevated terrain in proximity to water, will have been utilised by Aboriginal people in the past but not as intensively as other parts of the Penrith Lakes area as it is 300m or greater from water. Stone artefacts are predicted to occur within the project area "in a consistently low-density distribution" to depths of 1.3m (but often to 0.9m). Artefacts may be manufactured of predominately silcrete and occasionally quartz, chert, quartzite, hornfels and basalt. Other site types and features are possible but unlikely to occur in the project area as they have not previously been identified within the project area during previous assessments and due to the degree of past land use and disturbance and a lack of suitable geology and vegetation.

As the project area may contain in-situ geomorphology (PLDC 2011), relative to the surrounding Penrith Lakes area which has been significantly impacted from quarrying and past land use, the project area is considered to have moderate archaeological potential, particularly below the level of past agricultural activities to contain low densities of stone artefacts.

The project area contains deposits of the Penrith Unit of the Cranebrook Terrace which has experienced relatively less disturbance than other parts of the Penrith Lakes Scheme. This resource and opportunities to understand it are increasingly diminished by the amount of development in the region. Where Aboriginal objects survive in this profile, they have archaeological and geomorphic value due to their ability to support models of Aboriginal land use and archaeological preservation in the local area, particularly where excavations can be undertaken in a controlled manner to the current regulatory standards.

This assessment notes that across the Cranebrook Terrace and Penrith Lakes Scheme there has been a management trend towards area-wide AHIPs across the Penrith Lakes Scheme to manage the residual risk of Aboriginal objects irrespective of the identification of sites, particularly in those areas not historically impacted by sand quarrying (Kohen 1986–2004, AHIP COO01415, AHIP 1131345, Comber 2017).

Survey coverage and archaeological excavation coverage of the Penrith Unit of the Cranebrook Terrace across the project area (prior to 2018), was deemed to have been sufficient to allow for the issue of an AHIP COO01415 (AHIMS 3891), in order to harm known and unknown Aboriginal objects within the project area without mitigation.

We recommend that archaeological testing is not required. This is due to the volume of literature already available on the Penrith Unit of the Cranebrook Terrace, the previous land-use of the project area diminishing any research potential which could come from the distribution of in-situ Aboriginal objects, a lack of any topographic variability within the project area, and that a background scatter of artefacts have already been identified within limited surface exposures on-site, confirming that the project area is

September 2025 Page 41 of 61



archaeologically sensitive and likely consistent with previous site investigations close-by from within the Penrith Unit and can therefore expect a similar vertical distribution of Aboriginal objects.

With the classification of the project area as a site with background scatter, and the presence of Aboriginal objects in all identified exposures in 2025's survey, an AHIP with community collection and salvage for subsurface disturbances associated with site development works will be required.

September 2025 Page 42 of 61



5. Cultural Heritage Values and Statements of Significance

5.1 ASSESSMENT OF SIGNIFICANCE

The Burra Charter: the Australia ICOMOS Charter for Places of Cultural Significance, 2013 (Australia ICOMOS 2013, hereafter referred to as the 'Burra Charter') provides guidance for the conservation and management of places of cultural significance (cultural heritage places) and is based on the knowledge and experience of Australia ICOMOS members. Conservation is an integral part of the management of places of cultural significance and is an ongoing responsibility. The Burra Charter sets a standard of practice for those who provide advice, make decisions about, or undertake works to places of cultural significance, including owners, managers, and custodians. The Burra Charter defines cultural significance as the "aesthetic, historic, scientific, social or spiritual value for past, present or future generations. Cultural significance is embodied in the place itself, its fabric, setting, use, associations, meanings, records, related places and related objects" (Australia ICOMOS 2013:2).

Aboriginal cultural heritage sites are therefore assessed following the categories of significance developed under the Burra Charter (Table 8). See Section 8 of the AA (Appendix A) for detailed description of the categories of significance.

Table 8: Assessment of the Burra Charter Values within the Project Area

Categories of Significance	Statement of Values
Aesthetic	Although the natural aesthetics of the project area have been severely impacted by extensive urbanisation from past land use, views to the Blue Mountains are visible from within the project area and the Penrith Lakes will be viewable from a height of 27 m (or the third story in the proposed buildings onsite), We note that the views to Blue Mountains and also the Nepean River and nearby waterways are important to RAPs Vicky Slater (Wurrumay Culture Heritage Consultants), Arika Jalomaki (Yulay Cultural Services) and Tania Carroll (Murra Bidgee Mullungari Aboriginal Corporation).
Historic	The project area is situated within a broader cultural landscape with historic significance to the Aboriginal community. To date, there is no documented historical significance specific to the project area site, Aboriginal people of the region remain actively involved in continuing their culture and history, demonstrated within the project area through their advocacy to protect and manage Aboriginal cultural heritage affected by the Penrith Lakes Scheme and their involvement in this Aboriginal Cultural Heritage Assessment process. We note that RAPs have raised that the locality is an area where tribes come together (Vicky Slater, Wurrumay Cultural Heritage Consultants) and near areas of historical and cultural significance to DLALC.
Scientific/archaeological	There are no registered sites on AHIMS within the project area, though a new site with eight exposures containing artefacts were identified during a survey visit on 20 February 2025. The project area is situated on a portion of the Penrith Unit of the Cranebrook Terrace which has experienced relatively less disturbance than other parts of the Penrith Lakes Scheme.

September 2025 Page 43 of 61



This resource and opportunities to understand it are increasingly diminished by development.

The presence of Aboriginal objects demonstrate local Aboriginal land use and cultural history within the project area and surrounds. As more of the Cumberland Plain and Penrith Lakes area become urbanised there is less opportunity for conservation of Aboriginal occupation deposits. However, the artefacts of broken flakes and flakes within the project area are not unusual scientifically but have high cultural value. The hand axe and retouched flake are less common tool types in local assemblages.

The exposures of artefacts in Penrith Lakes 2025 background scatter are connected to the broader cultural landscape of Aboriginal land use of the Cumberland Plain. The site does have different tool types including a retouched flake, a broken hand axe, flakes and broken flakes. These tool types are **not rare in the locality** of the Cumberland Plain (and not in the State) surrounding the project area where there is not much variability in assemblages discussed in previous archaeological research.

Broken flakes and flakes are **not rare** in similar landscape contexts in the locality and the region and not rare.

The project area contains **moderate research potential** as it may provide an opportunity to further understand the geomorphic and archaeological value of the Penrith Unit of the Cranebrook Terrace and past Dharug land use on elevated terrain at a distance from an unnamed tributary of Cranebrook Creek, through analysis and salvage of the artefacts currently exposed and likely to be salvaged through further archaeological salvage.

The dating potential has been diminished by the degree of past land use disturbance in the minimum top 0.3 to 0.6m of deposit, making potential for chronology or dating in cultural history locally and at the State level unlikely and of low research potential.

The hand axe, retouched flake as well as the different artefact types and raw materials identified to date in Penrith Lakes 2025 have **moderate educational potential for teaching**. Residue analysis in particular and more detailed stone tool analysis could provide additional information about the hand axe to determine if there is blood or some other residue on the tool or starch or other residues on the retouched surface of the retouched flake. Residue analysis could provide some education and teaching potential for these two stone tools to contribute to the cultural story of the project area.

Social value - Cultural values

The project area contains moderate research potential as it may provide an opportunity to further understand the geomorphic and archaeological value of the Penrith Unit of the Cranebrook Terrace and past Dharug land use on elevated terrain at a distance from an unnamed tributary of Cranebrook Creek, through analysis and salvage of the artefacts currently exposed and likely to be salvaged through further archaeological salvage. The dating potential has been diminished by the degree of past land use disturbance in the minimum top 0.3 to 0.6 m of deposit, making potential for chronology or dating in cultural history locally and at the State level unlikely and of low research potential.

Spiritual value

The hand axe, retouched flake as well as the different artefact types and raw materials identified to date in Penrith Lakes 2025 have moderate educational potential for teaching. Residue analysis in particular and more

September 2025 Page 44 of 61



detailed stone tool analysis could provide additional information about the hand axe to determine if there is blood or some other residue on the tool or starch or other residues on the retouched surface of the retouched flake. Residue analysis could provide some education and teaching potential for these two stone tools to contribute to the cultural story of the project area.

5.2 SUMMARY AND STATEMENT OF SIGNIFICANCE

The project area holds cultural and archaeological value within a broader historic landscape of importance to the Aboriginal community, despite the impacts of urbanisation and land use that have altered its natural aesthetics. While no registered Aboriginal sites exist within the area, the proximity to the Nepean River near Castlereagh underscores its historical role as a vital resource for food, tools, and community sustenance. Subsurface deposits, particularly those associated with the Penrith Unit of the Cranebrook Terrace, retain moderate archaeological potential, offering opportunities for further research into Dharug land use and geomorphology. Although the topsoil exhibits low archaeological integrity due to past disturbances in the top 0.3 to 0.6 m, deeper deposits could remain relatively undisturbed, enhancing the area's research significance with moderate research potential. The study's findings will be refined following consultation with Registered Aboriginal Parties to ensure a comprehensive understanding of its cultural heritage.

The project area, identified as a site with background scatter, will require an AHIP with community collection and salvage. Currently, the archaeological significance of the project area specifically is unknown, however, the aesthetic and historic significance of the project area are low.

September 2025 Page 45 of 61



6. The Proposed Activity

Table 9 provides a summary of the history of previous impacts to the project area, the proposed impacts to the project area from the proposal, and a statement regarding potential harm of the proposal on Aboriginal objects within the project area. A full description category is provided in the relevant sections of the AA (Appendix A), as indicated in **Table 9**.

Table 9: Summary of Project Proposal.

Project Description	Summary			
Previous Impacts to the Project Area (AA – Section 3)	This project area has been modified through agricultural activities, underground irrigation piping, the construction of residential structures, geotechnical investigations and ancillary infrastructure. The project area is also susceptible to flooding.			
	These activities may have removed Aboriginal objects in the topsoil but are more likely to have moved or displaced Aboriginal objects within the top 0.3 to 0.6 m of soil, resulting in low archaeological integrity in the topsoil. It is possible that intact archaeology has survived within the project area, particularly below the level of agricultural activities however, as noted by Kohen (1997, 2004), it is also possible that artefacts have moved through the soil profile as a result of bioturbation.			
	AHIP CO001415 (AHIMS 3891), now expired, was previously issued over the project area.			
Proposed Impacts to the Project Area (AA – Section 2)	The proposed scope of works as provided by Morson Group includes a tourism development comprising of a 7-storey serviced apartment building with 65 dual key units, a 6 storey 4500sqm indoor recreation facility, 3 single-story fast-food outlets, a 5000sqm club, multiple shops, cafes and restaurants and a central community space. 1000 car parking spaces will be provided as multi-level above ground and on grade parking. The project design is still being undertaken; however, ground impacting activities include:			
	 Archaeological surface collection and salvage investigations Demolition of existing structures Earth works including cut and fill, pilings/footings and service trenches across the project area; Construction of the three buildings on site; Installation of vehicle and pedestrian access; Heavy vehicle movement across the project area Landscaping works across the project area; Ancillary infrastructure and works It is likely that excavations across the site will be part of the overall redevelopment works with most excavations anticipated to be up to 0.5 m depth, though excavation of stormwater system and footings will also likely be required. Excavations is these areas are anticipated to be ~1.5 m depth. 			

September 2025 Page 46 of 61



The following are the intended key program milestones for delivering this project:

- Concept DA Submission (mid-2025).
- Concept DA Approval (late-2025).
- Detailed DA submission (late-2026).
- Detailed DA Approval (mid-2027).
- Construction Certificate Phase (mid-2027 2028).
- Construction commences mid- to late-2028.

Potential Harm of Proposed Activity

Eight Aboriginal objects have been identified in the project area. No areas are currently proposed for conservation.

(AA – Sections 9 and 10)

The proposed activity will however directly impact on land predicted to have moderate archaeological sensitivity. Aboriginal objects are considered likely in low densities in this area.

Archaeological test excavations are not required to determine the presence or absence of Aboriginal objects, due to the volume of archaeological information available on the Penrith Unit, past land-use of the project area, a lack of any variability in topography or geomorphology within the project area, and a pre-existing background scatter of Aboriginal objects, confirming that the project area is archaeologically sensitive and likely consistent with previous site investigations within the Penrith Unit.

Many of the proposed impacts have been proposed to areas which are considered to have low archaeological integrity in the top 30 cm of the topsoil, with impacts proposed at depths exceeding 0.6m limited to piling/footings and service trenches. Morson Group are committed to cultural and archaeological salvage in areas of proposed impact and harm to Aboriginal objects.

The RAPs have communicated to date that surviving archaeological deposits and Aboriginal objects may retain cultural value to the Registered Aboriginal Parties irrespective of their archaeological integrity. The RAPs have been provided the draft report for review for comment on if they supports the development of management and mitigation measures for harm to Aboriginal heritage.

6.1 AREAS WHERE OBJECTS WILL BE PROTECTED OR HARMED

All Aboriginal objects are protected under the *National Parks and Wildlife Act 1974* and conservation is the preferred option for all objects. Consideration should be given to avoidance of and conservation of sites where possible. **Error! Reference source not found.**, required under the *Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW* (DECCW 2010), below lists all sites, places and PADs identified within the project area and summarises the type, level, and consequence of harm to these places.

All Aboriginal objects are protected under the *National Parks and Wildlife Act 1974* and conservation is the preferred option for all objects. Consideration should be given to avoidance of and conservation of sites where possible. **Error! Reference source not found.**1, required under the *Code of Practice for Archaeological*

September 2025 Page 47 of 61



Investigation of Aboriginal Objects in NSW (DECCW 2010), lists all sites, places and PADs identified within the project area and summarises the type, level, and consequence of harm to these places.

No areas are currently proposed for conservation. The proposed activity will however impact on land with recorded Aboriginal objects within background scatter Penrith Lakes 2025.

Table 10: Summary of Likely Harm

Site/Place/PAD		PAD	Type of Harm	Level of Harm	Consequence of Harm	
			(direct/indirect/ none)	(total/partial/none)	(total loss of value/partial loss of value/no loss of value)	
	enrith 2025	Lakes	Direct	Partial - based on project impacts	Partial loss of value based on mitigation of project impacts	

September 2025 Page 48 of 61



7. Avoiding or Mitigating Harm

7.1.1. Pre-lodgement consultation

A meeting with Heritage NSW was held on 22 November 2024 to discuss the assessment requirements for this project. Correspondence on the results of the survey in February 2025 were emailed to Heritage NSW on 18 March 2025 and update on changes of approach to salvage instead of testing and update on RAP comments from the survey, with an offer to meet to discuss with Heritage NSW, if required. Additional correspondence was emailed by Peter Morson to Heritage NSW regarding how to approach site definition with justifications for site definition were emailed to Kym McNamara, Heritage NSW on 20 June 2025 as well as an offer to discuss in a meeting before pre-lodgement. Sam Allen responded from Heritage NSW via email on 1 July 2025 stating that "Heritage NSW is supportive of the revised approach in registering the project area as a site with background scatter". This email to Ms McNamara by Peter Morson included this input from Virtus Heritage below (as emailed on 20 June 2025 to Heritage NSW)

- 1. The project area is situated on the Penrith Unit of the Cranebrook Terrace which has been demonstrated over numerous scientific studies and geotechnical investigations to be an archaeologically significant unit (e.g., Kohen, 1986; Nanson et al., 1987; Insite Heritage 2000; Williams et al., 2017; Comber Consultants, 2006, 2006).
 - 1. Given the age of the uppermost strata of the Penrith Unit (50,000 100,000 years old), these studies have reported that the vast majority of artefacts have been constrained within the top 0.6 m of soils (A horizon noted as deep as 1.3 m in some studies in topographic depressions) and exist at depth due to bioturbation and/or soil turnover from previous landuse (agriculture).
 - 2. Proposed excavations will be to a maximum of 2 m below ground level (BGL), with the majority between 0.6 and 1.2 m BGL. As such, proposed site works will impact the archaeologically significant portion of the Penrith Unit.
- 2. Based upon the high volume of studies within the Penrith Unit (a list with summaries will be provided along with a draft AA and ACHA within the next few weeks) and the identification of artefacts within fence line surface exposures during a site visit in February 2025, we expect to encounter Aboriginal objects within the A horizon of our project area (0.3 0.6 m deep based upon geotechnical surveys).
 - 1. The project area exhibits no distinct changes in topography and as such, there are no distinct landform units which can be mapped to provide insight over the possible distribution of artefacts. Due to the previous land-use of the project area (and broader landscape), any macro changes in topography were likely destroyed.
 - 2. The stratigraphy of the uppermost 0.6 m has also been disturbed as a result of past agricultural land-use. Therefore, any in-tact stratigraphy which could be used to inform us on the distribution of artefacts within the Penrith Unit (e.g., flood couplets) have been destroyed.
- 3. The project area is situated ~90-100 m away from the highly archaeologically sensitive Richmond Unit of the Penrith Terrace.

The project area previously had an AHIP granted in 2018 (#C0001415) which expired in 2023 and a future AHIP application will cover the same Lots as before (12, 14, and 16). With the topographic uniformity of the Penrith Unit, we could possibly link the project area to pre-existing site cards for works completed east of our site. Alternatively,... we can register the artefacts as a new site but given that there are no significant

September 2025 Page 49 of 61



landforms to constrain the project area to, the boundaries will not have any robust data to support their geographic placement.

HNSW have acknowledged emails and provided input which is included in this assessment.

7.1.2. Consideration of Alternatives

Morson Group between February 2025 to date have attempted to minimise and redesign project impacts and depths of development. Some redesign was possible to avoid Aboriginal occupation deposits if extant was considered with their design team. The opportunity to reuse existing service trenches for new services and to minimise all ground disturbance works is not possible for this project.

7.2 AREAS WHERE OBJECTS WILL BE PROTECTED OR HARMED

All Aboriginal objects are protected under the *National Parks and Wildlife Act 1974* and conservation is the preferred option for all objects. Consideration should be given to avoidance of and conservation of sites where possible. **Error! Reference source not found.**1, required under the *Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW* (DECCW 2010), lists all sites, places and PADs identified within the project area and summarises the type, level, and consequence of harm to these places.

No areas are currently proposed for conservation. The proposed activity will however impact on land with recorded Aboriginal objects within background scatter Penrith Lakes 2025.

Table 11: Summary of Likely Harm

Site/Place/PAD		Type of Harm	Level of Harm	Consequence of Harm	
		(direct/indirect/ none)	(total/partial/none)	(total loss of value/partial loss of value/no loss of value)	
Penrith 2025	Lakes	Direct	Partial - based on project impacts	Partial loss of value based on mitigation of project impacts	

7.3 JUSTIFICATION OF THE OBJECTIVES OF THE PROPOSED ACTIVITY

The project area is situated within an area zoned for the development of a tourism precinct within the Penrith Development Control Plans and State Environmental Planning Policy (SEPP). The design of this project has been undertaken with respect to Design Principles and in consideration of a framework (Government Architect NSW 2023).

Many of the proposed impacts have been proposed to areas which are considered to have low archaeological integrity in the top 30 cm of the topsoil, with impacts proposed at depths exceeding 0.6m limited to piling/footings and service trenches. Morson Group are committed to cultural and archaeological salvage in areas of proposed impact and harm to Aboriginal objects.

The RAPs have communicated to date that surviving archaeological deposits and Aboriginal objects may retain cultural value to the Registered Aboriginal Parties irrespective of their archaeological integrity. *The RAPs have been provided the draft report for review for comment on if they supports the development of management and mitigation measures for harm to Aboriginal heritage.*

September 2025 Page 50 of 61



7.4 ECOLOGICALLY SUSTAINABLE DEVELOPMENT (ESD)

Australia's National Strategy for Ecologically Sustainable Development (1992) defines ecologically sustainable development (ESD) as: 'using, conserving and enhancing the community's resources so that ecological processes, on which life depends, are maintained, and the total quality of life, now and in the future, can be increased' (Department of Agriculture Water and the Environment Website Ecologically Sustainable Development Webpage). These environmental considerations include cultural heritage. ESD can be applied to Aboriginal cultural heritage by considering intergenerational equity and the precautionary principle.

The **Principle of Intergenerational Equity** states that 'the present generation should make every effort to ensure the health, diversity and productivity of the environment – which includes cultural heritage – for the benefit of future generations' (OEH 2011). That is, by considering how will future generations be able to visit, see, experience and/or research Aboriginal objects. The Operational Policy: Protecting Aboriginal Cultural Heritage (DECCW 2009) states in terms of Aboriginal heritage, intergenerational equity can be considered in terms of the cumulative impacts to Aboriginal objects and places in a region.

A way of gauging what level of impact from development has occurred within a region, is to review how many Aboriginal Heritage Impact Permits (AHIPs) have been issued for that region. A review of the public register of AHIP) issued between 2010 and 2021, for Penrith LGA indicates that over 60 AHIPs were issued. The current AHIP Public Register for the Penrith LGA shows that five AHIPs has been issued, for the region. Though AHIMS tracking of AHIPs to sites is highly inaccurate, at least 32 of the 85 Aboriginal cultural heritage sites recorded in the AHIMS search (Section 4), have had AHIMS issued. Over 300 SSD projects and modifications have been initiated in the Penrith LGA.

Overall, there has been a relatively high cumulative impact to the Penrith region that includes the project area based on recent AHIPs and SSD projects. The project area has been subject to relatively less development with impacts from historical land use and natural processes discussed in Section 3. As noted in the significance assessment in Section 8, one Aboriginal background scatter, Penrith Lakes 2025 has been identified to date and much of the project area has low archaeological integrity in the top minimum 0.3m to maximum 0.6 m of topsoil, however where intact archaeological deposits survive, they are of moderate research value.

The **Precautionary Principle** states that if there are threats of serious or irreversible environmental damage, lack of full scientific certainty should not be used as a reason for postponing measures to prevent environmental degradation.

Inductions, cultural awareness training and further investigation through archaeological and cultural salvage are precautionary steps. Conservation is not possible in the project area and the proponent has attempted at least for now six months to redesign project impacts and attempt to avoid cultural deposits, if still extant associated with Penrith Lakes 2025.

Archaeological salvage and community collection, in addition to inductions and cultural awareness training will be required to mitigate the impacts of these works.

September 2025 Page 51 of 61



8. Recommendations

Management recommendations of this assessment consider all values as set out in The Burra Charter and the requirements of Heritage NSW. This assessment includes the recommendations for the Archaeological Survey Report (Archaeological Assessment). The ACHA includes management recommendations which consider the social (cultural), spiritual, aesthetic and historic values of The Burra Charter.

Based on the description of project impacts provided by Morson Group, the results of the survey, Aboriginal consultation to date, the limitations of this assessment and previous archaeological research, the following recommendations are made:

- 1. An AHIP with community collection and archaeological salvage will be required prior to the commencement of ground disturbance works as Aboriginal objects will be harmed by the proposal.
- It is recommended that all site workers and personnel involved in site impact works should be inducted and briefed on the possible identification of Aboriginal sites and objects during construction and their responsibilities according to the provisions of the NPW Act 1974 and NPW Regulation 2019.

This induction package should be developed in consultation with DLALC, prior to works proceeding. The induction must include:

- An AHIP once issued as recommended by the results of this AA report.
- The contact phone numbers of the NSW Environment and Heritage regional archaeologist, EnviroLine 131 555, and DLALC.
- The relevant contact phone number Environmental Officer responsible for this project in case unknown objects or items are uncovered during excavation.
- The penalty for moving Aboriginal objects need to be made clear and given due consideration.
- An outline types of unexpected heritage objects, items & relics, and their legal protection
- The Unexpected Finds and Human Remains Procedures, as outlined in Recommendation 1 and 2.
- It is recommended that an Unexpected Finds Procedure be implemented for the duration of the project. In the event that a suspected Aboriginal object/s is identified the procedure should include the following:
 - Works are to stop immediately.
 - The area of the suspected find/s is to be fenced off with an appropriate buffer and protected.
 - A qualified archaeologist and representative of DLALC are to be contacted to inspect the area and the nature of the find and to advise if it can be collected within the provisions of an AHIP (if determined by HNSW).
 - Representative of DLALC to determine the find's significance, in consultation with a qualified archaeologist or NSW Environment and Heritage,.
 - Works are not to proceed until written advice is provided from the archaeologist or NSW Environment and Heritage on the appropriate management of the find.
- 4. It is recommended that an **Unexpected Human Remains procedure** be implemented for the duration of the project. In the unlikely event that suspected Human Remains are identified the procedure should include the following:
 - Works are to stop immediately.
 - The area of the suspected Human Remains find is to be secured and cordoned off.
 - NSW Police are to be notified. No further works can be undertaken until the NSW Police provide written advice.
 - If these remains are deemed to require archaeological investigation by the NSW Police or NSW Coroner then:
 - NSW Environment and Heritage and the relevant Aboriginal parties must be notified; and

September 2025 Page 52 of 61



- a plan of management for the preservation of any identified Aboriginal human remains of for the salvage must be put in place or conducted under an AHIP methodology and variation developed in consultation with all relevant Aboriginal parties and the NSW Environment and Heritage.
- Works are not to proceed until written advice is provided from the archaeologist or NSW Environment and Heritage.

September 2025 Page 53 of 61



References

Artefact 2016, Jane Street and Mulgoa Road Infrastructure Upgrade, Penrith: Aboriginal Archaeological Survey Report.

Biosis 2018, Penrith Regatta Centre New Maintenance Shed Aboriginal Cultural Heritage Due Diligence Assessment. Report for Creative Planning Solutions on behalf of the Office of Sport. Authors: J Cole, Biosis Pty Ltd, Sydney. Project no. 27505.

Blue Mountains City Council 2017, Scenic Eastern Escarpment: Draft Master Plan.

Chalson, J.M. & Martin, H.A. 2008, A 38,000 year history of the vegetation at Penrith lakes, New South Wales, Proceedings of the Linnean Society of New South Wales, vol. 129, pp. 97–111.

DECCW 2010a, Due Diligence Code of Practice for the Protection of Aboriginal Objects in NSW and Archaeological Investigation of Aboriginal Objects Code of Practice.

DECCW 2010b, Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW.

DECCW 2010c, Aboriginal heritage consultation requirements for proponents 2010.

Department of Climate Change Energy the Environment and Water 2021, Register of the National Estate – archive. Accessed 27 July 2023 from http://www.dcceew.gov.au/parks-heritage/heritage/places/register-national-estate.

Department of Environment, Climate Change and Water 2010a, Due Diligence Code of Practice for the Protection of Aboriginal Objects in New South Wales 2010. Sydney, NSW.

Department of Environment, Climate Change and Water 2010b, Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW. Sydney, NSW.

Eco Logical Australia Pty Ltd 2020, Nepean Business Park, Penrith NSW – Aboriginal Cultural Heritage Assessment. Prepared for Great River NSW Pty Ltd.

Eco Logical Australia 2021, Nepean Business Park, Penrith, NSW Aboriginal Cultural Heritage Assessment. Report prepared for Great River NSW Pty Ltd.

Environment Australia 2001, Belt Forests in Queensland: Natural Heritage Trust Endangered Species Program Fact Sheet. Environment Australia, Canberra.

http://www.biodiversity.environment.gov.au/threaten/event/tsday2000/factsheets00/brigalow.html.

Environmental Planning and Assessment Act 1979.

ERM 2001, Penrith Lakes Scheme Cultural Heritage Management Study. Report prepared for Urban Pacific Pty Ltd. June 2001, 100488RP1.

GML Heritage Pty Ltd 2018, Blacktown Native Institution Heritage Impact Statement. Prepared for Landcom and the Museum of Contemporary Art.

ICOMOS Burra Charter 2013.

Isbell, R. 2002, The Australian Soil Classification. CSIRO publishing.

Karskens, G. 2019, "Nah Doongh's Song", Australian Book Review.

Karskens, G. et al. 2019, Traces in a Lost Landscape: Aboriginal archaeological sites, Dyarubbin/Nepean River and contiguous areas, NSW, Australia (Data Paper), Internet Archaeology 52. https://doi.org/10.11141/ia.52.8.

September 2025 Page 54 of 61



Mills, R. 1997, An Aboriginal Heritage Study for the Olympic Softball Venue and Aquilina Reserve, Blacktown. Report prepared for the Olympic Co-Ordination Authority.

Mitchell, P. 2002, Descriptions for NSW (Mitchell) Landscapes Version 2 online. Department of Environment and Climate Change NSW.

Morrow Geotechnics 2023, Geotechnical Investigation for Tourism Development: Lot 14, 47-65 Old Castlereagh Road, Castlereagh NSW.

National Parks and Wildlife Act 1974.

National Parks and Wildlife Regulation 2019.

New South Wales State Heritage Register. Department of Planning & Environment 2024, H02009.

NSW National Parks and Wildlife 2003, The Bioregions of New South Wales: Their Biodiversity, Conservation, and History. Hurstville: New South Wales National Parks and Wildlife Service.

Nanson, G., Young, R., & Stockton, R. 1987, 'Chronology and palaeoenvironment of the Cranebrook Terrace (near Sydney) containing artefacts more than 40,000 years old', Archaeology in Oceania, vol. 22, no. 2, pp. 72–78.

Office of Environment and Heritage (OEH) 2011, Guide to investigating, assessing and reporting on Aboriginal cultural heritage in NSW.

State Government of NSW and NSW Department of Climate Change, Energy, the Environment and Water 2023, Aboriginal Heritage Impact Permit Boundaries Dataset. Revision March 2024. Viewed 24 July 2024.

Williams, A., Burrow, A., Toms, P., Brown, O., Richards, M., & Bryant, T. 2017, 'The Cranebrook terrace revisited: recent excavations of an early Holocene alluvial deposit on the banks of the Nepean River, NSW, and their implications for the future work in the region', Australian Archaeology, vol. 83, no. 3, pp. 100–109.

September 2025 Page 55 of 61



Appendix A Archaeological Assessment Report

September 2025 Page 56 of 61





CASTLEREAGH TOURISM DEVELOPMENT 39-65 Old Castlereagh Road, Castlereagh NSW

Archaeological Assessment

Final | September 2025

Prepared for Morson Group

PO Box 101, Pottsville NSW 2489 (O2) 6676 4354 info@virtusheritage.com.au ABN 56 159 910 228



Cover image: Drone photography provided by Morson Group (2024)

Document controls

Client:	Morson Group
Local Government Area:	Penrith Local Government Area
Local Aboriginal Land Council (LALC):	Deerubbin Local Aboriginal Land Council

Version History

Version	Date	Prepared by	Approved by	Comments
1a	10 December 2024	Clare Anderson	Alice Buhrich	Draft
1e	3 July 2025	Liam Clerke and Anya Graubard	Dr. Mary-Jean Sutton	Client review
2a	23 July 2025	Liam Clerke	Dr. Mary-Jean Sutton	RAP review
3	27 August 2025	Kate Morris and Liam Clerke	Dr. Mary-Jean Sutton	Final

September 2025 Page 2 of 87



Acknowledgement of Country

Virtus Heritage acknowledges the Traditional Custodians of the land on which this project was undertaken and pays respect to Elders past, present and emerging.

Content Warning

Aboriginal and Torres Strait Islander people are warned that this publication may contain names and images of deceased people, descriptions of traumatic historic events and parts of Country that have been impacted by development.

Disclaimer and cultural restrictions

This Report (including any enclosures and attachments) has been prepared by Virtus Heritage for the exclusive use and benefit of Morson Group for their use regarding the Project and solely for the purpose for which it is provided. Unless we provide express prior written consent, no part of this report should be reproduced, distributed or communicated to any third party. We do not accept any liability if this report is used for an alternative purpose from which it is intended, nor to any third party in respect of this report.

Information contained in the Report is current as at the date of the Report and may not reflect any event or circumstances which occur after the date of the Report. Information in this Report may be considered sensitive and this Report cannot be distributed or made public, unless a redacted version is prepared.

All queries related to the content, or to any use of this report must be addressed to Dr Mary-Jean Sutton at info@virtusheritage.com.au.

September 2025 Page 3 of 87



Executive Summary

Morson Group Consultants proposes to develop a tourism precinct at 39-65 Old Castlereagh Road, Castlereagh NSW (Lots 12, 14 and 16 DP793163, Figure 1). The project area is located within the Penrith Local Government Area (LGA), within the boundary of Deerubbin Local Aboriginal Land Council (DLALC).

The proposed scope of works as provided by Morson Group seeks approval for a tourism-oriented development comprising three (3) buildings across separate lots, including a hotel, an indoor recreation facility with two (2) drive-through restaurants, and a registered club. The proposal also includes associated vehicle access, on-grade and above-ground parking, and site infrastructure.

- Lot 12:
 - A seven (7) storey hotel with 147 rooms, restaurant, gym, spa, pool, and associated facilities.
 - Multi-level above-ground car parking.
- Lot 14:
 - A 5,713m² indoor recreation facility.
 - Two (2) restaurants with capacity for a drive-through.
 - Associated on-grade car parking.
- Lot 16:
 - A 5,177m² registered club building.
 - Associated on-grade car parking.

It is likely that excavations across the site will be part of the overall redevelopment works with most excavations anticipated to be up to 0.15 – 1.74 m below ground level (BGL), though excavation of stormwater system and footings will also likely be required. Excavations in these areas are anticipated to be to a maximum depth of ~2.3 m BGL.

Aboriginal Heritage Impact Permit (AHIP) CO001415 (AHIMS 3891), now expired, was previously issued over the project area. Previous Aboriginal cultural heritage assessments have identified that the project area may contain in-situ stratigraphy and low densities of Aboriginal objects associated with the alluvial Penrith Unit of the Cranebrook Terrace (PLDC 2011, Virtus Heritage 2024). The proposed works therefore have the potential to harm Aboriginal objects.

Virtus Heritage Pty Limited (hereafter 'Virtus Heritage') was engaged by Morson Group to prepare an Aboriginal Cultural Heritage Assessment (ACHA), including an Archaeological Assessment (AA) for the proposed development.

This report is the Archaeological Assessment, which is an Appendix (**Appendix A**) to the ACHA. The purpose of this report is to provide Morson Group with archaeological advice on the potential impact of their proposal to Aboriginal archaeological sites and to meet the requirements of the *Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW* (DECCW 2010) for Archaeological Reports – (Requirements 1 to 11).

ENVIRONMENTAL CONTEXT

The project area is located in the floodplains associated with the Nepean River, within the Penrith Unit of the Cranebrook Terrace formation. The soils of the project area are consistent with the Richmond soil landscape. Aboriginal objects are known to occur within this soil landscape and in the Penrith Unit to depths of 1–2 m and generally in the top 0.9 m of deposit. Archaeological models across the Cumberland Plain indicate that Aboriginal objects can be found in any landform.

Stone artefacts tend to be found more frequently in proximity to key resources such as water and drainage lines, shelter and stone sources and decrease in frequency as distance from those resources increases. The

September 2025 Page 4 of 87



Nepean River is located a little over 650 m from the project area. The historic path of Cranebrook Creek is mapped approximately 1.7 km west of the project area. An unnamed tributary was located 300 m north-east of the project area. Previous potential chain of ponds and paleochannels were also identified by Groundtruth Consulting in proximity to the project area (Mitchell 2010). The proximity to the Nepean River, an unnamed tributary and potential ponds and paleochannels means there is the potential for stone artefacts in the project area.

The project area's alluvium topsoils have been disturbed by vegetation clearance, previous farming activity and the construction of the residential housing and irrigation infrastructure but does not appear to have been subject to sand mining. This past land use has impacted the A-horizon soils to at least 0.3 m to 0.6 m in depth.

ARCHAEOLOGICAL CONTEXT

An AHIMS extensive search (Client Service ID 912988) was undertaken on 10 July 2025. No Aboriginal cultural heritage sites were registered in, or close to the project area.

Previous archaeological assessments of the project area concluded that there was a reasonable potential for Aboriginal objects to occur within the project area. Aboriginal objects were predicted to be found at low frequencies and with low archaeological integrity to depths of a minimum of 0.3 m, with greater archaeological integrity possible below this depth given it's below the typical depth of plough zones (except for in areas of existing services trenches) (PLDC 2011, Virtus Heritage 2024).

SIGNIFICANCE AND IMPACT ASSESSMENT

The project area contains deposits of the Penrith Unit of the Cranebrook Terrace and a recorded Penrith Lakes 2025 background scatter with Aboriginal objects in 8 locations. Aboriginal objects in this unit provide an opportunity to further understand the geomorphic and archaeological value of the Penrith Unit of the Cranebrook Terrace and past Dharug land use on elevated terrain. Development in the local region has impacted the survival of Aboriginal objects in the Penrith Unit.

The proposed activity has the potential to harm Aboriginal objects associated with the Penrith Unit. Given the extent of information available on the Penrith Unit, the previous land-use of the project area, the identification of artefacts within surface exposures inside of the project area, and the homogeneity of topography and landforms within the project area,

Archaeological and cultural salvage are required to mitigate the impacts on the proposed development on Penrith Lakes 2025, background scatter

MANAGEMENT RECOMMENDATIONS

Management options and recommendations are outlined for this proposal in Section 10 and Section 11 of this report. Based on the description of project impacts provided by Morson Group, the results of the survey, Aboriginal consultation to date, and previous archaeological research, the following recommendations are made:

- 1. An AHIP with community collection and archaeological salvage will be required prior to the commencement of ground disturbance works as Aboriginal objects will be harmed by the proposal.
- It is recommended that all site workers and personnel involved in site impact works should be inducted and briefed on the possible identification of Aboriginal sites and objects during construction and their responsibilities according to the provisions of the NPW Act 1974 and NPW Regulation 2019.

This induction package should be developed in consultation with DLALC, prior to works proceeding. The induction must include:

September 2025 Page 5 of 87



- An AHIP once issued as recommended by the results of this AA report.
- The contact phone numbers of the NSW Environment and Heritage regional archaeologist, EnviroLine 131 555, and DLALC.
- The relevant contact phone number Environmental Officer responsible for this project in case unknown objects or items are uncovered during excavation.
- The penalty for moving Aboriginal objects need to be made clear and given due consideration.
- An outline types of unexpected heritage objects, items & relics, and their legal protection
- The Unexpected Finds and Human Remains Procedures, as outlined in Recommendation 1 and 2.
- 3. It is recommended that an **Unexpected Finds Procedure** be implemented for the duration of the project. In the event that a suspected Aboriginal object/s is identified the procedure should include the following:
 - Works are to stop immediately.
 - The area of the suspected find/s is to be fenced off with an appropriate buffer and protected.
 - A qualified archaeologist and representative of DLALC are to be contacted to inspect the area and the nature of the find and to advise if it can be collected within the provisions of an AHIP (if determined by HNSW).
 - Representative of DLALC to determine the find's significance, in consultation with a qualified archaeologist or NSW Environment and Heritage.
 - Works are not to proceed until written advice is provided from the archaeologist or NSW Environment and Heritage on the appropriate management of the find.
- 4. It is recommended that an Unexpected Human Remains procedure be implemented for the duration of the project. In the unlikely event that suspected Human Remains are identified the procedure should include the following:
 - Works are to stop immediately.
 - The area of the suspected Human Remains find is to be secured and cordoned off.
 - NSW Police are to be notified. No further works can be undertaken until the NSW Police provide written advice.
 - If these remains are deemed to require archaeological investigation by the NSW Police or NSW Coroner, then:
 - NSW Environment and Heritage and the relevant Aboriginal parties must be notified; and
 - a plan of management for the preservation of any identified Aboriginal human remains of for the salvage must be put in place or conducted under an AHIP methodology and variation developed in consultation with all relevant Aboriginal parties and the NSW Environment and Heritage.
 - Works are not to proceed until written advice is provided from the archaeologist or NSW Environment and Heritage.

September 2025 Page 6 of 87



Contents

1.	Introduction	14
1.1	Report Structure	16
1.2	Project Team and Acknowledgements	16
1.3	Project Limitations	17
2.	Description of the Project	18
2.1	Proposed Development	18
2.2	Project Description	18
2.3	Project Overview	19
2.3.1.	! Geotechnical Investigations	19
2.3.2	2. Trenching for Services and Utilities	19
2.3.3	3. Underground Tanks for Flood and Water Management	19
2.3.4	4. Pilings, Footings, Concrete Pavement Slabs and Concrete Floor Slabs	19
2.3.5	5. Landscaping and Fencing	20
2.3.6	6. Earthworks	20
2.4	Project Staging	21
2.5	Summary	21
3.	Environmental and Landscape Context	22
3.1	Topography, Landforms and Hydrology	22
3.2	Geology and Soils	23
3.3	Climate, Flora and Fauna	24
3.4	Previous Land Use History	24
3.5	Summary	27
4.	Archaeological Context	29
4.1	Statutory Heritage Register Searches	29
4.1.1.	Aboriginal Heritage Information Management System (AHIMS)	29
4.1.2.	P. Aboriginal Heritage Impact Permit (AHIP) Register	29
4.1.3.	Other Searches of Heritage Database	30
4.1.4.	l. Native Title Tribunal	32
4.2	Previous Archaeological Research	32
4.2.1.	1. Previous Assessments of the Project Area	32
4.2.2	2. Other relevant assessments in the region	33
4.3	Regional Character	37
4.4	Summary	39
5.	Predictive Model	40
5.1	Summary	42



6.	Survey and Results	44
6.1	Site Strategy	44
6.2	Site Survey	44
6.3	Survey Results	45
6.4	Landforms, Visibility and Effective Coverage	52
6.5	Summary	52
7.	Analysis and Discussion	54
8.	Scientific Values and Significance Assessment	56
8.1	Summary and Statement of Archaeological (Scientific) Values within the Project Area	58
9.	Impact Assessment	59
9.1	Background	61
9.1.1.	Pre-lodgement consultation	6i
9.1.2	Consideration of alternatives	62
9.2	Areas Where Objects will be Protected or Harmed	62
9.3	Justification of the Objectives of the Proposed Activity	62
9.4	Ecologically Sustainable Development (ESD)	63
10.	Management and Mitigation Measures	64
10.1	Legislative Context and Statutory Requirements	
10.1.	1. National Parks and Wildlife Act 1974	64
10.1.	2 Environmental Planning and Assessment Act (NSW) 1979	65
10.1.	3 Heritage Act (NSW) 1977	66
10.1.	4 Aboriginal Land Rights Act 1983	67
10.1.	5 Native Title Legislation	67
10.1.	6 Other Acts	68
10.2	Management Options	68
10.2	1 Conservation	68
10.2	2 Further Investigation – Testing Under the Code of Practice	68
10.2	3 Destruction Without Mitigation	68
10.2	.4 Destruction With Mitigation	69
11.	Recommendations	70
Legi	slation	72
	rences	

Appendices

Appendix A1 Archaeology Research Design Methodology

Appendix A2 Aboriginal Heritage Information Management System Search Result



Tables

Table 1. CoP Report Requirement and this Report's Relevant Report Section	16		
Table 2. Representatives of Registered Aboriginal Parties Involved in Fieldwork and Consultation			
Table 3: Soil profiles and depths from geotechnical investigations in Lot 14 (Morrow 2023: Table 2)	24		
Table 4. Summary of AHIMS Features within the Search Area	29		
Table 5: Previous Archaeological Investigations within the Locality	33		
Table 6. Predictive Model for Aboriginal Occupation within the Project Area	40		
Table 7. Definitions of Archaeological Potential	42		
Table 8. Aboriginal Objects (stone tools) within Penrith Lakes 2025 Recorded within the Project Area	ı47		
Table 9. Survey Coverage and Effective Visibility	52		
Table 10. Landform Summary – Sampled Areas	52		
Table 11. Assessment of the Burra Charter Values within the Project Area	57		
Table 12. Summary of Archaeological Value in the Project Area	58		
Table 13: Summary of Likely Harm	62		
Figures			
Figure 1. Locality Map and Project Area			
Figure 2. Modified floodplain landform within the project area (Morson Group 2024)	22		
Figure 3. 1942 Royal Australian Survey Corps topographic map of Windsor including the project ar unnamed creek			
Figure 4. A cross section of the Cranebrook Terrace with date ranges from Williams et al. 2017	23		
Figure 5: 1835 Castlereagh Parish Map	25		
Figure 6: 1947 Historic Aerial image	26		
Figure 7. 1955 Aerial Photograph	26		
Figure 8. 1965 Aerial Photograph	26		
Figure 9. 1978 Aerial Photograph	26		
Figure 10. 1986 Aerial Photograph. (Banksia EnviroSciences 2023)	26		
Figure 11: 1991 Historic Aerial Image	27		
Figure 12. 1998 Aerial Photograph	27		
Figure 13: 2013 Historic Aerial Image	27		
Figure 14. AHIPS and Heritage Items Within the Vicinity of the Project Area	31		
Figure 15. Cranebrook Terrace mapping from Nansen et al. 1987	38		
Figure 16. Soil exposure within the project area	45		
Figure 17. Exotic trees within the project area (right) compared to native trees outside project area (left).45		
Figure 18. Buildings present and levelled landscape from north-west corner of project area	46		



Figure 19. Building present and levelled landscape from north-east corner of project area	46
Figure 20. Irrigation tap identified in western project area	46
Figure 21. View to roofed-water tank in central project area	46
Figure 22. Identified Aboriginal Objects part of Penrith Lakes 2025 Background Scatter with Area	•
Figure 23. Areas of Subsurface Impact within the Project Area	60

September 2025 Page 10 of 87



Definitions

EP&A Act

Abbreviations Description AAArchaeological Assessment ALR Act Aboriginal Land Rights Act 1983 **ACHA** Aboriginal Cultural Heritage Assessment **ACHCR** Aboriginal Cultural Heritage Consultation Requirements for Proponents 2010 (DECCW 2010) **AHD** Australian Heritage Database **AHIMS** Aboriginal Heritage Information Management System AHIP Aboriginal Heritage Impact Permit **AIATSIS** Australian Institute of Aboriginal and Torres Strait Islander Studies **ALRA** Aboriginal Land Rights Act 1976 AR Archaeological Report, Archaeological Assessment **ARDM** Archaeological Research Design and Methodology **BGL** Below Ground Level BP Before Present **CABAH** Australian Research Council Centre of Excellence for Australian Biodiversity and Heritage **CHMP** Cultural Heritage Management Plan CoP Code of Practice for Archaeological Investigation of Aboriginal Objects in New South Wales (DECCW 2010) DA **Development Application** DCCEEW/DCCEW NSW Department of Climate Change, the Environment and Water/ Department of Environment, Climate Change and Water DD Due Diligence DD Code, Due Due Diligence Code of Practice for the Protection of Aboriginal Objects in New Diligence Code South Wales (DECCW 2010) **DLALC** Deerubbin Local Aboriginal Land Council **DPC** NSW Department of Premier and Cabinet **DPIE** NSW Department of Primary Industry and Environment

September 2025 Page 11 of 87

Environmental Planning and Assessment Act 1979



EPBC Act Environment Protection and Biodiversity Conservation Act 1999

GIA Guide to investigating, assessing and reporting on Aboriginal Cultural heritage in

NSW (OEH 2011)

HNSW Heritage NSW

ILUA Indigenous Land Use Agreement

LALC Local Aboriginal Land Council

LEP Local Environmental Plan

LGA Local Government Area

NNTT National Native Title Tribunal

NPW Act National Parks and Wildlife Act 1974

NPW Reg National Parks and Wildlife Regulation 2019

NPWS NSW National Parks and Wildlife Service

NSW New South Wales

NSWALC NSW Aboriginal Land Council

NTA Native Title Act 1983

OEH NSW Office of Environment and Heritage (now Heritage NSW)

PAD Potential Archaeological Deposit s an area where sub-surface stone artefacts

and/or other cultural materials are likely to occur

PBC Prescribed Bodies Corporate

PLDC Penrith Lakes Development Corporation

RAP Registered Aboriginal Party

RAPs Registered Aboriginal Parties

RD&M Research Design and Methodology

REF Review of Environmental Factors

RNTBC Registered Native Title Body Corporate

S.139 Section 139 of the *National Parks and Wildlife Act 1974*

S.140 Section 140 of the *National Parks and Wildlife Act 1974*

S.170 Section 170 of the *National Parks and Wildlife Act 1974*

SHI State Heritage Inventory

SHR State Heritage Register

SoHl Statement of Heritage Impact

September 2025 Page 12 of 87



SSD State Significant Development

SSI State Significant Infrastructure

The Burra Charter The Burra Charter: the Australia ICOMOS Charter for Places of Cultural Significance,

2013 (Australia ICOMOS 2013)

UNESCO United Nations Educational, Scientific and Cultural Organization

September 2025 Page 13 of 87



1. Introduction

Virtus Heritage was engaged by Morson Group, to prepare an Aboriginal Cultural Heritage Assessment (ACHA), including an Archaeological Assessment (AA) for a proposed tourism development located at 39-65 Old Castlereagh Road, Castlereagh, NSW (**Figure 1**, hereafter as 'the project area').

An ACHA was triggered due to the issue of Aboriginal Heritage Impact Permit (AHIP) C0001415 (Aboriginal Heritage Information Management System (AHIMS) 3891), now expired, over the project area, identified Aboriginal objects that may be harmed by the proposal in a survey in 2025 and the results of an Aboriginal Archaeological Due Diligence Assessment (Virtus Heritage 2024) of the proposal which identified archaeological potential associated with the underlying alluvial Penrith Unit of the Cranbrook Terrace. The proposed tourism development would impact these deposits and identified Aboriginal objects.

This report constitutes the AA component required for the ACHA process. The ACHA was compiled to accompany an AHIP. The objectives of the ACHA are to:

- 1. Investigate and assess the impacts of the proposed activity on Aboriginal objects, places and cultural heritage values within the project area.
- 2. Provide appropriate management and mitigation strategies.

This report has been compiled to meet Requirements 1 to 11 of the *Code of Practice for Archaeological Investigations of Aboriginal Objects in NSW* (hereafter referred to as CoP) (DECCW 2010) for Archaeological reports.

In general, the aims of this Archaeological Assessment are to:

- present an analysis of background data to assist in forming a predictive model and context to allow for the assessment of archaeological potential and archaeological significance of the project area;
- document the field investigations undertaken within the project area to best practice standards;
- describe the archaeological heritage values of the project area including a description and significance assessment of Aboriginal objects recorded;
- determine how the significance of the values of the project area would be affected by the proposal;
- consider potential harm from the proposal to Aboriginal objects and identified cultural heritage values within the project area;
- document measures to avoid, mitigate and/or manage harm to Aboriginal objects and identified cultural heritage values, where necessary; and
- detail any requirements for an AHIP or further archaeological investigation.

September 2025 Page 14 of 87





Figure 1. Locality Map and Project Area

September 2025 Page 15 of 87



1.1 REPORT STRUCTURE

Table 1 provides a summary of the reporting requirements outlined in the CoP and where these requirements are addressed in the structure of this report.

Table 1. CoP Report Requirement and this Report's Relevant Report Section

CoP Report Requirement		Where this Requirement is addressed in the Report
Requirement 1:	Review previous archaeological research	Section 4.2
Requirement 2:	Review the landscape context	Section 3.0
	Summarise and discuss the local and regional original land use and its material traces	Section 4.2 and Section 4.3
Requirement 4:	Predict the nature and distribution of evidence	Section 5.0
Requirement 5:	Archaeological survey	Section 6.0
Requirement 6:	Site definition	Section 5.0
Requirement 7:	Site recording	Section 6.4
Requirement 8:	Location information and geographic reporting	Section 3.0
Requirement 9:	Record survey coverage data	Section 6.3
Requirement 10:	Analyse survey coverage	Section 6.3
Requirement 11:	Archaeological Report content and format	Entire report

1.2 PROJECT TEAM AND ACKNOWLEDGEMENTS

This report was originally compiled by Clare Anderson (Principal Archaeologist, Bachelor of Arts (Prehistory and Historic Archaeology, University of Sydney) and reviewed by Dr Alice Buhrich (Principal Archaeologist, PhD Archaeology, James Cook University) and Dr Mary Jean Sutton (Director, PhD Archaeology, University of Queensland). The report was subsequently edited after the 2025 survey identifying Aboriginal objects by Dr Sutton and Liam Clerke (Senior Geomorphologist, MRes Paleohydrology, Macquarie University). GIS mapping was undertaken by Liam Clerke and Shaun Sewell (Senior GIS analyst; B.A. IT, Queensland University of Technology). Project information and description of works detailed in Section 2.0 was provided by Peter Morson (Morson Group).

The representatives of Registered Aboriginal Parties (RAPs) who were involved in fieldwork and consultation, which forms the basis of this assessment, are presented in **Table 2**.

Table 2. Representatives of Registered Aboriginal Parties Involved in Fieldwork and Consultation

Name of Contact	Registered Aboriginal Party
Uncle Steven Randall	Deerubbin Local Aboriginal Land Council
Philip Boney	Wailwan Aboriginal Group
Tiarna Bird	Mura Gadi Aboriginal Corporation

September 2025 Page 16 of 87



Ethan Trewlynn	Long Gully Cultural Services
Nigel Millgate	Gadhungal Marring
Darleen Johnson and Ryan Johnson	Murra Bidgee Mullangari Aboriginal Corporation
Justine Coplin	Dharug Custodian Aboriginal Corporation
Kelvin Boney	Wallanbah Aboriginal Site Conveyancing
Amanda Hickey	Amanda Hickey Cultural Services
Carolyn Hickey	A1 Indigenous Services
Jennifer Beale	Butucarbin Aboriginal Corporation
Phil Khan	Kamilaroi Yankuntjatjara Working Group
Kerrie Slater; Vicky Slater	Wurrumay Culture Heritage Consultants
Steven Hickey	Widescope Indigenous Group
Wendy Morgan	Guntawang Aboriginal Resources Incorporated
Pearl Depoma	Pearl Depoma (Individual)
Arika Jalomaki	Yulay Cultural Services
Thomas Dahlstrom	Thomas Dahlstrom (Individual)
Steven Johnson & Krystle Carroll	Ginninderra Aboriginal Corporation
Paul Webb	Paul Webb (Individual)
Robert Young	Konanggo Aboriginal Cultural Heritage Services
Undisclosed Registered Aboriginal Party	Undisclosed Registered Aboriginal Party

We would like to acknowledge the assistance of the following individuals for the completion of this report:

- Peter Morson, Morson Group.
- Uncle Steven Randall, Deerubbin Local Aboriginal Land Council

1.3 PROJECT LIMITATIONS

This report is limited to the assessment of project impacts described in information provided by Morson Group and mapped in this report. Virtus Heritage takes no responsibility for errors within Department of Premier and Cabinet's (DPC) Aboriginal Heritage Information Management Systems (AHIMS) data, Australian Heritage Database (AHD), Land and Property Information (LPI) Heritage data (State Heritage Register [SHR], curtilages and Heritage Conservation layers for relevant Local Government Areas (LGAs) and has assumed information provided by these agencies and government departments is accurate, however, we have made best efforts to ensure this information is verified and cross checked wherever possible. Requests have previously been made to Heritage NSW and PLDC for complete copies of reports associated with the Penrith Lakes Scheme and previous AHIPs, however not all components of reports were available for this assessment.

September 2025 Page 17 of 87



2. Description of the Project

Section 2 provides a description of proposed works based on information recorded during the survey and provided by Morson Group.

2.1 PROPOSED DEVELOPMENT

The proposed scope of works as provided by Morson Group seeks approval for a tourism-oriented development comprising three (3) buildings across separate lots, including a hotel, an indoor recreation facility with two (2) drive-through restaurants, and a registered club. The proposal also includes associated vehicle access, on-grade and above-ground parking, and site infrastructure.

- Lot 12:
 - A seven (7) storey hotel with 147 rooms, restaurant, gym, spa, pool, and associated facilities.
 - Multi-level above-ground car parking.
- Lot 14:
 - A 5,713m² indoor recreation facility.
 - Two (2) restaurants with capacity for a drive-through.
 - Associated on-grade car parking.
- Lot 16:
 - A 5,177m² registered club building.
 - Associated on-grade car parking.

The project design is proposed to be submitted as a concept Development Application with DPHI, however the expected ground impacting activities will include:

- Demolition of existing structures.
- Earth works including cut and fill, pilings/footings and service trenches across the project area.
- Construction of the three buildings on site.
- Installation of vehicle and pedestrian access.
- Heavy vehicle movement across the project area.
- · Landscaping works across the project area.
- Ancillary infrastructure and works.

Excavations across the site will be required as part of the overall redevelopment works. Most excavations are anticipated to be between 0.15 and 1.75 m below ground level (BGL). Deeper excavations to a maximum of 2.3 m BGL will be needed for stormwater infrastructure and footings.

The construction methodology with depths and dimensions of proposed works as represented in the Development Application for the proposal is provided below by Morson Group:

2.2 PROJECT DESCRIPTION

The proposed development is located on 39-65 Old Castlereagh Road, Castlereagh and includes the construction and operation of three (3) buildings comprising a hotel (Lot 12), an indoor recreation facility with two restaurants with capacity for drive-throughs (Lot 14) and a club (Lot 16) and associated infrastructure across all three lots.

The proposed development seeks consent for the following aspects of development:

September 2025 Page 18 of 87



- Site preparation and establishment works including bulk earthworks to create proposed site levels and in-ground building services and utility work;
- Removal and relocation of trees within the proposed development extent, where necessary;
- Construction and operation 3 of three (3) buildings comprising a hotel (Lot 12), an indoor recreation facility with two restaurants with capacity for drive-through (Lot 14), a club (Lot 14) and associated infrastructure across all three lots;
- A total gross floor area (GFA) of 21898 m² (Lot 12 9711 m², Lot 14 7010 m² and Lot 16 5177 m²);
- A maximum building height of 27 m;
- Three (3) vehicle crossovers to Old Castlereagh Road and internal access driveways;
- 491 off-street car parking spaces on grade and in multi-level above-ground carpark structures;
- Landscaping across the subject site;
- The proposed development is intended to be delivered in stages as outlined below:
 - Early Works Stage: Demolition of existing dwellings and structures on the site and the installation of stormwater infrastructure, including partial construction of the stormwater system and a flood relief pipe at the rear of the site. No bulk earthworks are proposed in this stage.
 - Stage 2: The construction of the hotel building on Lot 12,
 - Stage 3: The construction of the indoor recreation facility and restaurants on Lot 14,
 - Stage 4: The construction of the club building on Lot 16.

2.3 PROJECT OVERVIEW

2.3.1. Geotechnical Investigations

Further geotechnical investigations may occur to supplement further works as part of this project and would involve ground disturbance.

2.3.2. Trenching for Services and Utilities

Trenching and ground disturbance works will be required within the project area for the installation of services and utilities. The design and placement of these items have been allowed for and are further elaborated upon in **Section 9** of this report.

2.3.3. Underground Tanks for Flood and Water Management

Earthworks involving cut, fill and trenching will be required within the building footprint for the placement of underground onsite detention tanks, stormwater/sewer drains, services and utilities. The design and placement of these items have been allowed for and are further elaborated upon in **Section 9** of this report. All materials excavated onsite will be utilised elsewhere onsite in the landscaped area and underneath the pavement and ground level slabs where fill is required. Soils recovered to a depth of 1.3 m will be prioritised for use onsite to create the proposed swales, landscape berms, and provide the fill needed underneath the proposed floor level slabs, which are at a higher relative level than the existing ground surface. Any excess materials will be disposed of.

2.3.4. Pilings, Footings, Concrete Pavement Slabs and Concrete Floor Slabs

Piles

The design and placement of the concrete piles assumed to be required for this project have been allowed for and are further elaborated upon in **Section 9** of this report. However, the design and placement of these items is yet to be finalised and is yet to be confirmed by structural engineering at a construction certificate

September 2025 Page 19 of 87



phase of the project. The estimated dept of the piles is 12 - 13 m, and the pile diameter is estimated to be 600 mm.

Footings, Concrete Pavement Slabs and Concrete Floor Slabs

The proposed concrete floor slabs related to the parking area and internal areas on ground level are set at levels above natural ground level. The thickness of the concrete slabs and footings will not cause ground disturbance as they are located above the level of the natural ground level. However, there is likely to be a requirement to strip the existing grass and surficial topsoil below the areas of the car park and internal areas on ground level. The stripping depth will be about 150 mm below the natural surface level. These soils will be stockpiled and reused on site in the landscaped area to create swales and earth berms as indicated on the landscape architecture plans.

2.3.5. Landscaping and Fencing

The landscaped areas within the project area will be cultivated to a depth of 300 mm. These cultivated soils will not be removed from site and will be cultivated in place. Some trees in areas of the proposed construction have been shown to be removed and some existing trees have been shown to be transplanted and relocated on site. For further information, refer to **Section 9** of this report.

The sites rear and side boundaries already comprise existing fences, which will be retained or upgraded. The rear and western side boundary fences will be retained whereas the eastern side boundary fence will require an upgrade. Some new footings may be necessary to support the new fence; however, the design and placement of these footings are yet to be finalised.

2.3.6. Earthworks

For the purposes of this assessment, it has been assumed that earthworks will occur across the project area. The maximum depth and indicative areas of earthworks, including machinery used, are summarised below:

- A nominal 150 mm depth allowance to strip grass and topsoil under the pavement and building footprints;
- The cultivation of soils in the landscaped areas to a depth of 300 mm and the planting of landscaping;
- Trenches for reticulation of building services and drainage as detailed in Section 9 of this report;
- Excavation for OSD tanks as detailed in Section 9 of this report; and
- Drilling of foundation piles.

Machinery to be used to carry out the earthworks will include:

- Excavator;
- Backhoe;
- Bulldozer;
- Grader;
- Wheel tractor scraper;
- Trencher;
- Continuous Flight Auger Drilling Rig;
- Loader;
- B double tipper; and
- Haulage truck.

September 2025 Page 20 of 87



2.4 PROJECT STAGING

The following are the intended key program milestones for delivering this project:

- Concept DA Submission (mid-2025).
- Concept DA Approval (late-2025).
- Detailed DA submission (late-2026).
- Detailed DA Approval (mid-2027).
- Construction Certificate Phase (mid-2027 2028).
- Construction commences mid- to late-2028.

2.5 SUMMARY

The proposed activity has the potential to harm Aboriginal objects. Further discussion of potential project impacts to Aboriginal archaeological heritage and mapping of proposed impacts are presented in **Section 9** and **Section 10** of this report.

September 2025 Page 21 of 87



3. Environmental and Landscape Context

Section 3 provides a summary of the environmental and landscape context of the project area and the surrounding locality including soils, geology, landforms and hydrology, previous land use history and fauna and flora. Understanding the environmental and landscape context is important for understanding of the survival of any Aboriginal objects in the archaeological record and to predict landforms that were favourable for Aboriginal occupation.

3.1 TOPOGRAPHY, LANDFORMS AND HYDROLOGY

The project area is located on a modified, flat floodplain associated with the Quaternary terraces of the Nepean River. The slope of the project area has been modified as a result of past land use, but is on terrain elevated above nearby water courses and drainage lines.

Proximity to water is a key indicator for the presence of Aboriginal objects in the landscape. Many models of Aboriginal land use indicate a correlation between the frequency and diversity of Aboriginal objects present as proximity to water increases (see also **Section 4**).

The Nepean River is approximately 650m southeast of the project area. An unnamed manufactured lake is approximately 25 m north of the project area. The Sydney international Regatta Waterway is approximately 250 m north of the project area and is also manufactured.

Prior to extensive modifications to the landscape from the Penrith Lakes Scheme, the primary channel of Cranebrook Creek was 1.7 km west of the project area and an unnamed tributary to Cranebrook Creek was originally located approximately 300 m north-east. These watercourses and drainage lines are known to be associated with past Aboriginal land use and the presence of Aboriginal objects. Mitchell (2010) further mapped a number of potential paleochannels and chains-of-ponds to the north of the project area, indicating the project area could have had closer water resources available.

The project area is also likely to have been impacted by flooding over the years. Floods and rainfall can move, bury, and uncover Aboriginal objects.



Figure 2. Modified floodplain landform within the project area (Morson Group 2024).

September 2025 Page 22 of 87






Figure 3. 1942 Royal Australian Survey Corps topographic map of Windsor including the project area and unnamed creek.

3.2 GEOLOGY AND SOILS

The project area is within the Penrith Unit of the Cranebrook Terrace, a Quaternary alluvium geological landscape dominated by sand, silt and gravels derived from sandstone and shale. Sediment east of Cranebrook Creek's channel is modelled in the Penrith Unit and dated to a minimum of 40,000 years before present (Nanson et al 1987, Mitchell 2010, William et al 2017). Aboriginal objects have been identified within this unit through previous archaeological investigations (for example, Kohen 1997, 2004, PLDC 2011, Insite Heritage 2000). It has been theorised that Aboriginal objects would most likely been discarded on the surface of this older alluvium unit, with downward migration of artefacts over time as a result of bioturbation, disturbance and other geomorphic agents such as erosion and aggradation (Kohen 1997, 2004 see **Section 4**).

To the west of the project area, is the Richmond Unit of the Cranebrook Terrace. Sediment in the Richmond Unit to the west of Cranebrook Creek's channel has been dated to a minimum of 15,000 years before present (Williams et al 2017).




Figure 4. A cross section of the Cranebrook Terrace with date ranges from Williams et al. 2017.

September 2025 Page 23 of 87



The project area is within the Richmond soil landscape. A geotechnical assessment was conducted for this project, within the project area (Morrow 2023). This report found the project area to contain a topsoil of silty sand/sandy silt to a depth of 0.6 m, followed by alluvial clay sand/silty sand to depths between 3.3 and 6 m, suggesting variation in the topography and land formation within the project area. Alluvial cobbles are below this to a depth of 13.9 m after which a shale bedrock was identified. The soil profile is consistent with those previously observed in the Cranebrook Terrace (see **Section 4**).

Table 3. Soil profiles and depths from geotechnical investigations in Lot 14 (Morrow 2023: Table 2)

			Арр	rox. Depth Rai	nge of Unit ¹ n	nBGL	
Unit	Material	вн1	BH2	ВН3	BH4	ВН5	вн6
1	Topsoil	0.0 to 0.5 (24.2 to 23.7)	0.0 to 0.6 (23.8 to 23.2)	0.0 to 0.6 (24.0 to 23.4)	0.0 to 0.3 (24.0 to 23.7)	0.0 to 0.6 (24.1 to 23.5)	0.0 to 0.3 (24.1 to 23.8)
2	Medium Dense Sand	0.5 to 6.0 (23.7 to 18.2)	0.6 to 5.5 (23.2 to 18.3)	0.6 to 4.2 (23.4 to 20.0)	0.3 to 3.3 (23.7 to 20.7)	0.6 to 3.8 (23.5 to 20.3)	0.3 to 3.8 (23.8 to 20.3)
3	Alluvial Cobbles	6.0 to 13.9 (18.2 to 10.3)	5.5 + (sub 18.3)	4.2 + (sub 19.8)	3.3 + (sub 20.7)	3.8 + (20.7 to 20.3)	3.8 + (sub 20.3)
4	Shale Bedrock	13.9 to 14.6 (10.3 to 9.6)	-	-	-	-	-

1 Depths shown are based on material observed within test locations and will vary across the site

3.3 CLIMATE, FLORA AND FAUNA

The local area has experienced shifts in climate and the availability of water and flora and fauna resources.

Karskens (2007) identifies that the Penrith Lakes Scheme once contained black clay freshwater wetlands, remnant riverflat forest and Castlereagh Woodland. Studies of cores taken from the Nepean River indicate that during the 38,000–36,000 years BP, the vegetation of the Penrith Lakes area was likely an open sclerophyll forest with *Eucalyptus viminalis* and *Leptospermum polygalifolium* prominent (Chalson and Martin 2008). A 'spineless Asteraceae', thought to be *Cassinia Ercuate* was prominent in the understory. During the 27–16 k cal. Yr BP period, a shrubland of *Cassinia Ercuate* with some grasses was present. The lack of eucalypts during the height of the last glacial period suggests a cold, arid climate with less rainfall than today. In the period 6,000 years BP to present, a *Eucalyptus tereticornis* and *Leptospermum juniperinum* woodland with a grassy understorey occupied the site. When compared with other records in the Sydney Basin, the vegetation through the last glacial maximum at Penrith Lakes is the only one with a shrubland/grassland community (Chalson and Martin 2008).

Environmental shifts such as those indicated by Chalson and Martin (2008) and Karskens (2007) can lead to changes in water channel and chain of pond alignment, flooding regimes and resource availability. These in turn can lead to adaptation and changes in landscape use by Aboriginal people over time, resulting in patterns of land use and preservation of Aboriginal objects which may not be immediately apparent based on current environmental conditions.

The native vegetation within the project area has since been extensively cleared of open forest (as shown in **Figure 2**). Regrowth vegetation in the local area is dominated by Acacia species and Eucalypt species. During the site inspection no native vegetation was identified within the project area.

3.4 PREVIOUS LAND USE HISTORY

Understanding the previous land use history can help predict how the archaeological record has survived.

September 2025 Page 24 of 87



The earliest record for European use of the Penrith Lakes region is a 90-acre land grant to George Fieldhouse in 1803, which included the project area (Biosis 2018).

An unnamed tributary of Cranebrook Creek is visible in the 1942 survey of Windsor (Royal Australian Survey Corps 1942, **Figure 3**).

Historically, the area was used predominantly for farming due to the rich soils associated with the Nepean River. This is illustrated in historical imagery, particularly the 1947–1955 photographs, which show the project area as part of a larger context of fields (Figure 6, Figure 7). In the 1955 photographs one dwelling is present within the project area, with two other residential houses appearing by 1965 (Figure 8, Figure 9, Figure 12).

Sand quarrying took place near the project area from the 1960s until the 1990s but does not appear to have impacted on the project area directly (Figure 10). This is reflected in the PLDC (2011) mapping of soil disturbance which indicated the project area may have in-situ stratigraphy.

The region would be further developed in the 1990s, with the Sydney International Regatta Centre being developed 250 m north of the project area (see **Figure 9**, **Figure 10**). This development removed the previous unnamed tributary of Cranebrook Creek and small dams once visible northeast of the project area in the 1955–1978 aerial photographs (Figure 11). Underground irrigation piping was likely installed in the project area in 1998 (**Figure 12**).

The Nepean Business Park was developed just south of the project area across Old Castlereagh Road (Eco Logical Australia 2020). Geotechnical investigations and contamination investigations were undertaken in the project area in 2023 and 2024 (Morrow 2023, Banskia Envirosciences 2024).



Figure 5. 1835 Castlereagh Parish Map

September 2025 Page 25 of 87





Figure 6. 1947 Historic Aerial image



Figure 7. 1955 Aerial Photograph.



Figure 9. 1978 Aerial Photograph.



Figure 8. 1965 Aerial Photograph



Figure 10. 1986 Aerial Photograph. (Banksia EnviroSciences 2023)

While extensive ground works have been undertaken surrounding the project area, the project area itself appears to have only been disturbed by agricultural activities, underground irrigation piping, the construction of residential structures, geotechnical investigations and ancillary infrastructure. These activities may have removed Aboriginal objects in the topsoil but are more likely to have moved or displaced Aboriginal objects within a minimum depth of 0.3 m to 0.6 m of soil. It is possible that intact archaeology has survived within the project area, particularly below the level of agricultural activities.

September 2025 Page 26 of 87





Figure 11. 1991 Historic Aerial Image



Figure 12. 1998 Aerial Photograph.



Figure 13. 2013 Historic Aerial Image

3.5 SUMMARY

The project area is situated within a modified landform on terrain elevated above the Nepean River and an unnamed tributary of Cranebrook Creek, now destroyed. The unnamed tributary of Cranebrook Creek, as well as a chains of ponds, were once present approximately 300 m north-east of the project area, with the Nepean River approximately 650 m south-east and Cranebrook Creek 1.7 km west.

September 2025 Page 27 of 87



The temporary and permanent water sources near the project area would have provided suitable habitats for important plant and animal resources. The availability of these resources would have changed over the last 40,000 years since people have been using the local environment. Environmental shifts such as those indicated by Chalson and Martin (2008) can lead to changes in water channel and chain of pond alignment, flooding regimes and resource availability. These in turn can lead to adaptation in landscape use by Aboriginal people over time, resulting in patterns of land use and preservation of Aboriginal objects which may not be immediately apparent based on current environmental conditions.

The Penrith Lakes Scheme, inclusive of the project area, has previously been assessed as having a reasonable potential to contain Aboriginal objects. PLDC (2011) has previously stated that "flaked stone artefacts will be present within the soil across the Scheme in a consistently low-density distribution."

The project area contains silty sand/sandy silt topsoils to a depth of 0.6 m, followed by alluvial clayey sand/silty sand to depths between 3.3 and 6 m, characteristic of the Richmond soil landscape within the Penrith Unit of the Cranebrook Terrace. It has been theorised that Aboriginal objects would most likely been discarded on the surface of this older alluvium unit, with downward migration of artefacts over time as a result of bioturbation, disturbance and other geomorphic agents such as erosion and aggradation (Kohen 1997, 2004 see **Section 4**).

Although the project area has been modified it is possible that intact archaeology has survived within the project area, particularly below the level of agricultural activities, underground irrigation piping, the construction of residential structures, geotechnical investigations and ancillary infrastructure. The project area is also susceptible to flooding.

Previous land use may have moved or displaced Aboriginal objects within a minimum of 0.3 m to 0.6 m of soil, resulting in low archaeological integrity in a minimum of 0.3 m of the topsoil. It is possible that intact archaeology has survived within the project area, particularly below the level of agricultural activities (which would be at minimum 0.3 m based on ploughing impacts to topsoil). However, as noted by Kohen (1997, 2004), it is also possible that artefacts have moved through the soil profile as a result of bioturbation.

September 2025 Page 28 of 87



4. Archaeological Context

Section 4 presents the archaeological context of the project area and broader region. It provides a summary of known archaeological sites identified by previous archaeological investigations, and the understanding of Aboriginal heritage developed by analysis of previous work.

4.1 STATUTORY HERITAGE REGISTER SEARCHES

4.1.1. Aboriginal Heritage Information Management System (AHIMS).

The AHIMS is a database of registered Aboriginal sites within NSW, administered by the NSW Department of Climate Change, Environment, Energy and Water (DCCEEW). The limitation of the AHIMS cultural heritage database is that it contains only information that has been registered with the State and does not reflect all Aboriginal cultural sites that may exist. For example, additional stone artefacts not registered in AHIMS have been identified north and east of the project area (ERM 2011, Insite Heritage 2005). The AHIMS database is being continually updated and can contain errors.

The AHIMS search was completed on 10 July 2025 for the search area bounded by Eastings: 281848 – 289036, Northings: 6261482– 6270558 (GDA, Zone: 56), (Client Service ID: 912988, A2). A total of eighty-seven Aboriginal cultural heritage sites were returned by the search (Table 4). No Aboriginal objects were recorded in the search area (Figure 14).

The nearest previously recorded Aboriginal cultural heritage site to the project area was "Andrews Road PAD 1" (AHIMS ID#45-5-5238), a Potential Archaeological Deposit (PAD) with stone artefacts associated. This site was destroyed under AHIP #4518. This site is located approximately 1.1 km southeast of the project area.

Over 96% of the Aboriginal cultural heritage sites within the search area comprised of stone artefacts, including isolated finds and open artefact scatters with associated archaeological deposit (Table 4). The distribution of identified sites in AHIMS reflects the history of development and environmental impact assessment across the Penrith area. Many of the sites have been identified close to water sources.

Tal	rle 4	4. Si	umma	iry o	o f	^{c}AH	II	И.	S.	Features	wit	hin	the	Search	A	rea

Site Features	Frequency	Percentage (%) of Total
Art (Pigment or Engraved)	2	2.3%
Artefacts	74	85.1%
Artefact, Aboriginal Ceremony and Dreaming	1	1.1%
Artefact; Potential Archaeological Deposit (PAD)	7	8.0%
Potential Archaeological Deposit (PAD)	3	3.4%
Grand Total	87	100.0%

AHIMS also contains reports from previous archaeological assessments in the search area. These are considered further in **Section 4.2**.

4.1.2. Aboriginal Heritage Impact Permit (AHIP) Register.

Heritage NSW maintains a list of current and previous Aboriginal Heritage Impact Permits and is in the process of digitising this list. The Aboriginal Heritage Impact Permit Boundaries dataset (State Government

September 2025 Page 29 of 87



of NSW and NSW Department of Climate Change, Energy, the Environment and Water 2023) was searched on 20 May 2025.

AHIP CO001415 (AHIMS 3891) was issued to PLDC over the project area between 15 November 2018 and 15 November 2023 to allow harm to known and unknown Aboriginal objects without mitigation of harm during vegetation works and erosion and sediment control works as described in Controlled Activity Approval 10 ERM 2011/0057 (Figure 14). This AHIP has expired. It is not clear whether these works were undertaken in the project area.

4.1.3. Other Searches of Heritage Database

The following registers were searched:

- Australian Heritage Database: The Australian Heritage Database (AHD) is a Commonwealth
 administered heritage database that includes entries from the former Register for the National Estate
 and the current Commonwealth and National Heritage Lists and was searched on 17 July 2025:
 - National Native Title Tribunal: The search found no Native Title claims or agreements to be in place within or near the project area.
 - Indigenous Land Use Agreements (ILUAs): There are no ILUAs within or near the project area
 - World Heritage List: the search found no heritage items located within or near the project area.
 - National Heritage List: the search found no heritage items located within or near the project area.
 - Commonwealth Heritage list: the search found no heritage places located within or near the project area.
 - **Register of the National Estate:** the search found no heritage places located within near the project area.
- State Heritage Inventory and State Heritage Register: The State Heritage Inventory (SHI) is a heritage database administered by the NSW Environment and Heritage (Department of Planning and Environment) and was searched 17 July 2025. This database includes heritage listings from local and regional planning instruments and heritage studies and State significant heritage items. Information and items listed in the State Heritage Inventory come from a number of sources. This means that there may be several entries for the same heritage item in the database. Search results are divided into three sections.
 - Section 1 No Aboriginal Places were listed within the City of Penrith LGA.
 - Section 2 29 items listed under the Heritage Act are located within the City of Penrith LGA. None of these are within the project area.
 - Section 3 204 items were listed within the City of Penrith LGA. One heritage item, the
 Castlereagh Road Alignment, runs alongside the project area. The listing does not identify any
 Aboriginal history or cultural heritage values.
- The Penrith LEP 2010: The City of Penrith utilises the Penrith Local Environmental Plan (2010) to regulate land use and development within the City of Penrith LGA. Local Environmental Plans are planning instruments which contain provisions and listings of items of environmental heritage including heritage, conservation areas and archaeological sites within Schedule 5.
 - One heritage item, #261 Castlereagh Road Alignment, borders the project area to the south, but is not within the project area (Figure 14). No other heritage items, conservation areas or archaeological sites are within the project area.

September 2025 Page 30 of 87






Figure 14. AHIPS and Heritage Items Within the Vicinity of the Project Area.

September 2025 Page 31 of 87



4.1.4. Native Title Tribunal

A Native Title search was conducted of the National Native Title Tribunal (NNTT) webmap on 17 July 2025 of the project area to identify if any Native Title claims or Indigenous Land Use Agreements exist over the project area.

No claims or agreements were registered over the project area at the time of the search.

4.2 PREVIOUS ARCHAEOLOGICAL RESEARCH

A review of the AHIMS library and online searches was undertaken to obtain copies of previous Aboriginal heritage studies and archaeological investigations. **Section 4.2.1** summarises previous archaeological assessments of the project area while **Section 4.2.2** provides a summary of other relevant assessments in the region.

4.2.1. Previous Assessments of the Project Area

The project area has previously been assessed for Aboriginal archaeological and cultural heritage values as part of the Penrith Lakes Development Scheme (Kohen 1981, Penrith Lakes Development Corporation (PLDC) 2011). The PLDC report consolidated previous archaeological assessments and survey coverage data up to 2011 and included consultation in accordance with the Aboriginal community consultation requirements for proponents (DECCW 2010). Volumes 1.2 and 3 and Map 14 were not available to review for this assessment. Morson Group has requested this information from Heritage NSW and Penrith Lakes Development Corporation.

PLDC (2011) identifies that Kohen (1981) undertook archaeological survey of the Penrith Lakes Scheme to inform a Regional Environmental Study. According to the survey coverage in Kohen (1981a), the project area was surveyed, however no specific detail regarding land access, sampling or visibility. At this time, the project area does not appear to be part of any of the development applications associated with the Penrith Lakes Scheme. A supplementary report by Kohen (1981b) suggests that as a private property outside the scheme, the project area may not have been surveyed. No Aboriginal objects were identified (Kohen 1981).

The PLDC (2011) assessment noted archaeological monitoring and excavation has occurred in both the Penrith Unit and Richmond Unit of the Cranebrook Terrace within the Penrith Lakes Scheme, but there has been no archaeological monitoring or excavation within the current project area for the proposed Castlereagh Tourism Development. The project area was identified in the historic soil disturbance mapping as having agricultural disturbances with in-situ stratigraphy (PLDC 2011). No sand mining appears to have occurred in the project area. The predictive model mapping from that assessment was unavailable for this methodology. Efforts have been made to acquire this mapping from PLDC and Heritage NSW.

A model of past Aboriginal land use was developed for the Penrith Lakes Scheme. PLDC (2011) concluded that the Dharug speaking Aboriginal people who lived on the Cranebrook Terrace and associated landforms (such as the Smith Road conservation area ridge) hunted and gathered across the landscape with selection of elevated landforms as favoured camping locations. The assessment concluded that "it is assumed that flaked stone artefacts will be present within the soil across the Scheme in a consistently low-density distribution (PLDC 2011).

Based on this assessment, AHIP COO01415 (AHIMS 3891) was issued to PLDC over the project area between 15 November 2018 and 15 November 2023 to allow harm to known and unknown Aboriginal objects without mitigation of harm during vegetation works and erosion and sediment control works as described in Controlled Activity Approval 10 ERM 2011/0057. It is not clear whether these works were undertaken in the project area.

September 2025 Page 32 of 87



An Aboriginal archaeological due diligence assessment was completed for the project (Virtus 2024) and included an archaeological survey with Virtus Heritage and Uncle Steven Randall (Deerubbin LALC). Survey coverage from this site inspection is presented in Section 6 of this report. No Aboriginal objects were identified.

Ground surface visibility in the project area was extremely limited (<1%) due to the high level of non-native grass. All mature trees within the project area were identified as non-native species. The inspection confirmed that the project area had undergone ground disturbance associated with the construction of the existing houses, and landscaping works. Underground irrigation piping had been installed across the project area. On the basis of the previous assessment (PLDC 2011) and the presence of the Penrith Unit of the Cranebrook Terrace, the due diligence assessment considered that archaeological potential was present and community consultation and further impact assessment was required.

4.2.2. Other relevant assessments in the region

A large number of heritage assessments have occurred in the local region, particularly in association with the Penrith Lakes Scheme. A timeline and annotated bibliography of relevant reports reviewed for this assessment is provided in **Table 5** and synthesised in **Section 4.3**. **Section 4.4** and **Section 5**.

Table 5. Previous Archaeological Investigations within the Locality

Author and Year	AHIMS report number	Report Title and Relevance to Project Area
Kohen 1986b	1063	An additional archaeological survey of the Penrith Lakes Scheme: The DA2 area, at Total Survey Cranebrook and Upper Castlereagh [report prepared for Penrith Lakes Development Corporation]
		An archaeological survey of the DA 2 area that achieved 80-100% survey coverage. This did not include the project area and did not include assessment of the project area.
Kohen 1986c	1064	An archaeological survey of the Penrith Lakes scheme: The DA2 area, development area
		Selective survey of the DA2 area. This assessment and survey did not include the project area.
Nanson, Young and	-	Chronology and palaeoenvironment of the Cranebrook Terrace (near Sydney) containing artefacts more than 40,000 years old
Stockton 1987		A study of artefacts and the geological units associated with the Cranebrook Terrace in 1987 found natural sediment within the locality to have been deposited within three stages: a reworked overburden found between Cranebrook Creek and the Nepean River dating to 10–13,000 years BP, an original overburden dating to 40–45,000 years BP (Penrith Unit), and channel infill deposits dating to approximately 36,000 years BP (see Figure 4). The reworked overburden deposit (Richmond Unit) was identified as being deposited within the known habitation of Aboriginal populations in the Sydney area, and also as having an increased potential for archaeological deposits to its maximum depth of approximately 4 m. Within Nanson et al.'s mapping, the project area appears to be ~90 m of the border between the reworked overburden deposit associated with deeper archaeological potential (Richmond unit), and the original overfill burden deposit (Penrith Unit) (Nanson et al 1987, Figure 5). This model has subsequently been revised in Mitchell 2010 and Williams et al 2017.
Kohen 1988	-	The Penrith Lakes scheme: Routine inspection of quarrying operation
		The project area was not part of this assessment.
Kohen 1988- 2004	1433 4093	Inspections were initially conducted every six months. Monitoring of gravels within the quarrying continued until at least 1996 resulting in at least 13 reports without finding Aboriginal stone tools within the gravels. The regular inspections of gravels however observed artefacts exposed in the overburden sections around Cranebrook Creek.

September 2025 Page 33 of 87



		Monitoring was expanded to stripping of overburden. Monitoring of overburden stripping continued to around 2004. Artefacts from the monitoring were listed in each monitoring report by Kohen. Based on the mapping provided in PLDC (2011), the project area was not part of this monitoring. However, it provides additional information regarding the distribution of Aboriginal objects across the Penrith Lakes Scheme in both the Richmond and Penrith Unit.
Koettig and Hughes 1995	-	Excavations at RS1 Regentville (Koettig and Hughes 1995) found occasional artefacts to depths of O.8 m, providing an indication of depth of stone artefacts in similar soil profiles to the project area.
Valerie Smith and Associates	97515, 97527	Review of the Geomorphology of the Penrith Lakes Scheme Area and Context for Aboriginal Literature Survey Occupation by Valerie Smith & Associates
1996		This work was superseded by Mitchell 2010 and Williams et al 2017.
Kohen 1997	97700	Archaeological investigations in the DA4 area, Penrith Lakes Scheme [report prepared for Investigation Penrith Lakes Development Corporation] by Dr James Kohen
		Archaeological Assessments were completed by Kohen in 1997 for DA 4. This assessment did not include the project area.
		The first major subsurface investigation of the overburden took place in 1997 with the mechanical excavation by Kohen of two very large trenches within the Penrith Unit soil. Each trench was 7 m wide, and 100 m long dug by mechanical scraper. One major trench was dug by Cranebrook Creek to a depth of 4.6 m. A second trench was dug to a depth of 1.9 m by the paleochannel feature – a depressed band of clayey soil swamps near the base of the escarpment in the northeastern area of the Scheme. Kohen reports that 99% of artefacts were recovered within the top 1.3 m and European artefacts were recovered from the upper 90 cm at Cranebrook Creek and upper 60 cm at the paleochannel. The top 2 m of the soil were heavily bioturbated. The results suggested that artefacts had been mixed through the soil by bioturbation. The results suggested a low density of artefacts, although the recovery via 10 mm mechanical gravel screen would not have captured artefacts less than 10 mm wide. This assessment provides an indication of the likely depth and archaeological integrity of the Penrith Unit which is of relevance to the project area.
Insite Heritage 2000	-	In 2000, Insite Heritage undertook archaeological test pitting to the east of the project area near the boundary of the Penrith unit and Londonderry Terrace for a proposed development between Cranebrook Road and Andrew Road, A total of 75 artefacts were identified. Artefacts located I the sand terrace averaged around 1-3 artefacts per m³, with the majority located in the top 0.5 m. The report recommended the proponent apply for a consent to destroy with monitoring. This assessment contributes to an understanding of the archaeological potential of the Penrith Unit.
ERM 2001	-	ERM undertook a consolidation of information across the Penrith Lakes Scheme, including mapping the approximate distribution of Aboriginal objects recorded by Kohen prior to 2000 across the Penrith Lakes Scheme in both surface and subsurface contexts (ERM 2001: 2.15). The distribution of these sites notes the broader distribution of Aboriginal stone artefacts than indicated by the AHIMS data.
Comber Consultant 2005, 2006	105447	In 2005 nine Aboriginal stone artefacts had been identified eroding from the edges of a farm dam on a parcel of land previously owned by Camenzuli, located in the north of the scheme. An archaeological assessment was conducted by Comber resulting in the recording of 17 stone artefacts. Comber recommended archaeological salvage and consequently excavated a total of sixteen trenches, each 2 m by 3 m in area to a depth of 60 cm with all spoil dry sieved through 2.5 mm aperture screen. One artefact was recovered from the excavation. Comber's 2007 excavation of the PL9 area, located 1 km to the west of SB83, was conducted within the younger Richmond Unit and adopted total recovery wet–sieving approach. A series of 4 m by 1m trenches were dug by backhoe along three slightly elevated levees. Some of the trenches were expanded and a small number of additional 1 m x 1 m test pits were dug by hand. A total of 5,078 artefacts were recovered, with 52 backed artefacts extending to deeper spits within the undifferentiated alluvial deposits. These results indicate the presence of Holocene age technology bioturbated through a mixed alluvial deposit at least to the depth of excavation in many pits. In 2006,

September 2025 Page 34 of 87



		Comber prepared additional information This report recommends that the Section 90 permit with salvage be issued. One artefact was identified as a result of this work (Comber 2006).
Comber 2006	100211	Archaeological and Cultural Heritage Assessment Aboriginal Cultural Heritage Region in the area surrounding PL 9 Penrith Lakes Scheme
		This assessment did not include the project area.
Karskens 2007	-	Water Dreams, Earthen Histories: Exploring Urban Environmental History at the Penrith Lakes Scheme and Castlereagh, Sydney.
		Karskens (2007) provided a history of the Penrith Lakes Scheme and Castlereagh, noting historic sources relevant to Dharug life in the Penrith Lakes area.
Comber and Stening	101748	Aboriginal Archaeological & Cultural Heritage Assessment: Cranebrook Escarpment. Report prepared for Penrith Lakes Development Corporation
2008		This assessment did not include the project area and recommended further subsurface excavation to determine the nature and extent of two sites identified.
AHMS 2010	103762	Emu Plains Rail Stabling Yards – Section 87 #118047 Excavation Report
		This assessment identified stone artefacts within a levee landform adjacent a drainage line to the south of the Nepean River within the A Horizon soils, further demonstrating the potential for levee and terrace landforms to contain evidence of stone artefacts in proximity to water in the local area.
Mitchell 2010	-	Geomorphology and soils in relation in relation to archaeological investigations on the Cranebrook Terrace, Penrith Lakes. Report prepared by Groundtruth Consulting for Comber Consultants
		This report provides a summary of geomorphological investigations relevant to the project area, including additional interpretation on potential location of paleochannels and past drainage lines of Cranebrook Creek and its chains of ponds, indicating that water sources may have been around 300 m from the project area.
2010	-	The project area appears to have been incorporated into the Penrith Lakes Scheme.
November 2011	-	An area wide Penrith Lakes Scheme AHIP was lodged with the then Office of Environment and Heritage on 7 November 2011. This AHIP did not include the project area.
EMGA 2011	-	Aboriginal Heritage Assessment Report I Old Castlereagh Road and Quarantine Lake AHIP including results of test excavation of site PLSB83 (45–5–3991) under the Code of Practice for Archaeological Investigation of Aboriginal Object in NSW (DECCW 2010). Penrith Local Government Area. Prepared for Penrith Lakes Development Corporation
		The assessment states that "The Scheme land holds areas of high cultural significance with scientific value as representative landform with Aboriginal sites. The areas protected from quarrying contain Aboriginal stone artefacts in surface exposures and deep deposits. The deposits have research potential capacity to address questions of past Aboriginal land-use, certainly within the last 10,000 years, and possibly the late Pleistocene. The areas have Aboriginal socio-cultural values relating to their capacity to demonstrate past and current Aboriginal connection to the land." Baker hypothesised that "Based on the circumstances of initial discovery of PLSB83 and suggested land use model of Aboriginal behaviour it was initially assumed that flaked stone artefacts may be present within the upper 50 cm of soil in the AHIP area in an irregular very low-density distribution more than 300 m from Cranebrook Creek within the Penrith Unit soils. Within 300 m of Cranebrook Creek a higher concentration of Aboriginal flaked stone artefacts is anticipated. A very low-density artefact distribution may be present south of Cranebrook Creek within the Richmond Unit soils at an unknown depth". An archaeological test excavation of PLSB83 within the Penrith Lakes Scheme conducted in accordance with the Code of Practice for Archaeological Investigations and Aboriginal Objects in NSW (DECCW 2010) identified a low density of stone artefacts within the Richmond geomorphological unit, mainly on the eastern slightly higher ground close to the old Castlereagh Road. An AHIP was issued over part of the Penrith Lakes Scheme to support DA4, to the east of the project area with specific requirements to undertake salvage excavations across a number of geomorphic units including the Richmond Unit, the Penrith Unit and the boundaries of a tributary creek

September 2025 Page 35 of 87



		identified by Smith (1996). The applied for period was 2011-2018. DCAC noted a concern around the depth of excavation, and the lack of consideration of how the chains of ponds of Cranebrook Creek may have changed over 20,000 years.
EMGA 2011	105453	Aboriginal Heritage Assessment Report I 5B83, 5B73, 5B66 including results of test excavation of site PLSB83 (45-5-3991) under the Code of Practice for Archaeological Investigation of Aboriginal Object in NSW (DECCW 2010). Penrith Local Government Area. Prepared for Penrith Lakes Development Corporation I 21 June 2011
		This report does not appear to contain any additional information to that presented in the report above.
PDLC 2015	-	In July 2015, an application was made for an Aboriginal Heritage Impact Permit across part of the Penrith Lakes Scheme. This was subsequently amended in 2018 to include erosion works.
Artefact 2016		In more recent times, Artefact (2016) conducted an Aboriginal Archaeological Survey Report as part of a Review of Environmental Factors for infostructure works on Jane Street and Mulgoa Road, Penrith, approximately 2.3 km south of the project area. Artefact (2016) identified that artefact deposits have been found within the Cranebrook Terrace to a depth of 3.7 m, or 20.55 AHD, providing additional detail regarding of the archaeological potential in the region.
Williams et al 2017	-	In 2017 Williams et al. conducted excavations on the banks of Peach Tree Creek and created the most recent dating model for the Cranebrook Terrace (see Figure 7). This modelling identifies that the sandy clay sediment in areas west of the historic alignment of Cranebrook Creek, within the Richmond Unit, were deposited between 20–15,000 years ago to a depth of 3.5–3.9 m or 20.73–21.13 m AHD. This sedimentary layer is particularly sensitive for Aboriginal archaeological deposits, with flakes being identified by Williams et al. at the base of this layer. Sediment below this deposit are also sandy clays and date to approximately 50–40,000 years ago. Sediment east of the historic alignment of Cranebrook Creek dated to at least 50,000 years. Aboriginal objects are less likely to occur at depth to the east of Cranebrook Creek, with any Aboriginal objects most likely occurring in the reworked topsoils. Around 3 km east of Cranebrook Creek is and channel infill dating to between 50–75,000 years ago
Comber 2018	103872	Toga Penrith Aboriginal Archaeological Assessment
		An assessment of land within the Penrith Unit recommended further investigation, indicating a consistent interpretation that archaeological potential may exist in this unit.
Biosis Research 2018	-	In 2018 Biosis conducted an Aboriginal Cultural Heritage Due Diligence Assessment for the construction of a new maintenance shed at the Penrith Regatta Centre, 1.7 km west of the project area. Biosis noted that a high level of disturbance from sand mining and landscaping had been undertaken within the locality, which has impacted the potential for sites to be identified within its Richmond soils. No artefacts were identified in Biosis' site inspection.
Heritage NSW and PDLC	AHIP 1131345	AHIP 1131345 does not include the project area.
Karskens et al 2019	-	Traces in a Lost Landscape: Aboriginal archaeological sites, Dyarubbin/Nepean River and contiguous areas, NSW, Australia (Data Paper)
		This dataset provides a compilation of sites and reports relevant to the Dyarubbin and Penrith Lakes Scheme. Individual report where relevant are considered in this table.
Eco Logical Australia 2020	-	Nepean Business Park, Penrith, NSW Aboriginal Cultural Heritage Assessment Great River NSW Pty Ltd
2020		Eco Logical Australia (2020) conducted and Aboriginal Cultural Heritage Assessment in 2020 for the construction of the Nepean Business Park located 20 m south of the project area, on the other side of Old Castlereagh Road. This assessment identified stone artefacts to be the most common sites within the locality, though none were identified within their assessment area ERM (2001) indicates that Kohen possibly identified stone artefacts in or near this lot. Consultation with Aboriginal Parties in this report noted that burials had been identified in the broader Penrith Lakes region. However, the level of

September 2025 Page 36 of 87



		disturbance that has been undertaken in the locality due to sand mining indicated all Aboriginal objects to have a low potential within their assessment area. No Aboriginal artefacts or sites were identified in Eco Logical Australia's assessment.
Ecological	-	Regatta Park and River Road Reserve Test Excavation. Prepared for Penrith City Council
Australia 2020b		ELA was engaged by Penrith City Council to conduct a test excavation program and supporting Archaeological Technical Report (ATR) for the proposed upgrades in Regatta Park and River Road Reserve. In Regatta Park, there was low artefact density across the entirety of the site, with a majority of the artefacts found between 60 cm and 90 cm depth, 2.29 km south of the project area. This assessment provides additional supporting information regarding the archaeological potential of landscapes in the region.

4.3 REGIONAL CHARACTER

This section synthesises and discusses the previous archaeological research summarised in Section 4.2 and the environmental context of the region (presented in **Section 3**), in order to build a picture of the regional character of Aboriginal land use and potential archaeology, assist in predicting the types of sites that may be expected to be present in the project area (presented in **Section 5**), and help inform an analysis (presented in **Section 7**) of the survey results (**Section 6**).

The project area is part of a broader Aboriginal cultural landscape of the Dharug-speaking peoples. The Penrith Lakes area is associated with the Boorooberongal and Mulgoa clans (PLDC 2011, Karskens 2007). The Blue Mountains, Cranebrook Escarpment and Nepean River connect with shared songlines between Dharug, Darkinjung and Gundungurra Nations (PLDC 2011, Blue Mountains City Council 2017).

The Penrith Lakes area was a traditional meeting place for Aboriginal people. Its river and rich soils provided abundant natural vegetation and wildlife which supported Aboriginal people for many generations (New South Wales State Heritage Register. Department of Planning & Environment. HO2009, 2024). Evidence of this history has been revealed through the many artefacts were collected during the 25 years of sand and gravel mining at Penrith Lakes, to the north, west and south of the project area (Kohen 1986a, 1988–2004, 1997, EMGA 2001, Comber 2005, 2006, 2008, PLDC 2011, New South Wales State Heritage Register. Department of Planning & Environment. HO2009, 2024). In addition to the eighty-seven Aboriginal cultural heritage sites registered within a 4 km radius of the project area, there are additional Aboriginal cultural heritage sites were not recorded in AHIMS (ERM 2001, Insite Heritage 2005).

To the north of the project area, near Hadley Park, the Nepean River was one of the many first contact places where local Aboriginal people were able to stay on their traditional lands by camping and working for the colonial settlers. It was a place of confrontation between Aboriginal people and colonial settlers before more peaceful relationships were established (New South Wales State Heritage Register. Department of Planning & Environment. HO2009, 2024).

Substantial stone artefact workshops have been identified along the banks and terraces of Cranebrook Creek and the Nepean River, with many suitable stones for the manufacture of stone tools being sourced from the river and its creeks (Doelman et al 2015). Cranebrook Creek CC/1 (AHIMS 45–5–0281), listed as an artefact and Aboriginal Ceremony and Dreaming site, was located approximately 1.4 km to the north-west of the project area.

Aboriginal people, organisations and reference groups have continued to actively be involved in advocating for the protection of Aboriginal cultural heritage, archaeological assessment and care of Country across the local area, including the Penrith Lakes area (for example, Kohen 1988–2004, PLDC 2011, consultation for SEPP amendments 2023).

Kohen had previously hypothesised that a continuous scatter of artefacts at varying densities probably occur along all creeks in the Cumberland Plain (Kohen 1988) with the Nepean River and adjacent flood plain acted as focus of activity (Kohen 1988). Kohen thought that the Eastern bank and terraces of Nepean River

September 2025 Page 37 of 87



were likely to contain significant sites and possibly provided a focus of activity along bank of Cranebrook Creek (Kohen 1986a). Fauna and vegetation associated with Cranebrook Creek and its tributary streams would have played a major part in the selection of prehistoric sites (Kohen 1986a). Parts of the project area falls are approximately 300 m from an unnamed tributary of Cranebrook Creek. EMGA (2011) hypothesises that artefact densities will decrease at this distance and fall within the category of low-density artefact distribution

As noted in Section 4.2.1, a model of past Aboriginal land use was developed for the Penrith Lakes Scheme, synthesising Kohen's work. It hypothesised Dharug speaking Aboriginal people who lived on the Cranebrook Terrace and associated landforms (such as the Smith Road conservation area ridge) hunted and gathered across the landscape with selection of elevated landforms as favoured camping locations. The assessment concluded that "it is assumed that flaked stone artefacts will be present within the soil across the Scheme in a consistently low-density distribution.".

The age of artefacts and the age of archaeological deposits with the Cranebrook Terrace has been a source of debate over the years. A study of artefacts and the geological units associated with the Cranebrook Terrace in 1987 found natural sediment within the locality to have been deposited within three stages: a reworked overburden found between Cranebrook Creek and the Nepean River dating to 10-13,000 years BP (Richmond Unit), an original overburden dating to 40-45,000 years BP (Penrith Unit), and channel infill deposits dating to approximately 36,000 years BP (see Figure 15). The reworked overburden deposit was identified as being deposited within the known periods of habitation of Aboriginal populations in the Sydney area at the time of the study (1987), and also as having an increased potential for archaeological deposits to its maximum depth of approximately 4 m. This model has subsequently been revised in Mitchell 2010 and Williams et al 2017.

Within Nanson et al.'s mapping, the project area appears to be within 90 m of the border of these two units. This boundary was based on Walker's 1956 geological mapping at a 1-mile scale (Mitchell 2010) and localised variations may occur.




Figure 15. Cranebrook Terrace mapping from Nansen et al. 1987.

As noted in Section 4.2.2, the first major subsurface investigation of the alluvium overburden took place in 1997 with the mechanical excavation by Kohen of two trenches within the Penrith Unit soil. The excavation suggests that the Penrith Unit contained within the project area may retain Aboriginal objects to depths of 1.3 m and that these objects may have experienced bioturbation. It is important to note that the methods of sieving for this excavation used a larger size sieving mesh than is standard under the current Code of Practice for Archaeological Investigation in NSW, so artefact numbers in these deposits may have been higher than identified. The age of Aboriginal land use was not determined, though theorised to represent more recent occupation reworked into deposits laid down in the Pleistocene.

Additional excavations across Penrith Lakes Scheme, Castlereagh and the Nepean floodplain have identified stone artefacts buried within the topsoils and top 1.3 m of deposit within the Penrith Unit of the Cranebrook

September 2025 Page 38 of 87



Terrace (for example Insite Heritage 2005, Ecological Australia 2020), providing an indication of the potential depth of stone artefacts in the project area, and to greater depths in the Richmond unit (Comber 2006, 2008, Williams et al 2017). These assessments have further noted variation in the distribution of the Richmond and Penrith Unit to those originally hypothesised by Nanson et al (1987).

In 2017, Williams et al. conducted excavations on the banks of Peach Tree Creek and created the most recent dating model for the Cranebrook Terrace (see **Figure 7**). This modelling identifies that the sandy clay sediment in areas west of Cranebrook Creek, within the Richmond Unit were deposited between 20–15,000 years ago to a depth of 3.5–3.9 m or 20.73–21.13 m AHD. This sedimentary layer is particularly sensitive for Aboriginal archaeological deposits, with flakes being identified by Williams et al. at the base of this layer. Sediment below this deposit are also sandy clays and date to approximately 50–40,000 years ago. Sediment east of the historic alignment of Cranebrook Creek dates to at least 50,000 years. Aboriginal objects are less likely to occur at depth to the east of Cranebrook Creek, in areas such as the project area, with any Aboriginal objects most likely relating to a more recent time period and migrating through the topsoil, either through bioturbation, disturbance or other geomorphic agents.

With respect to the management of Aboriginal objects across the Penrith Lakes Scheme and local area, there appears to be a trend towards area-wide AHIPs to manage the residual risk of Aboriginal objects across both the Richmond and Penrith units of the Cranebrook Terrace irrespective of the identification of sites, particularly in those areas not historically impacted by sand quarrying (Kohen 1988–2004, Insite Heritage 2005, AHIP CO001415, AHIP 1131345, 2018, Ecological Australia 2020).

4.4 SUMMARY

The project area is situated within a modified landform on terrain elevated above the Nepean River, approximately 650 m south-east, and is approximately 300 m from an unnamed tributary of Cranebrook Creek, now destroyed.

The temporary and permanent water sources in proximity to the project area would have provided suitable habitats for a vast range of plant and animal species with utility to Dharug-speaking people, with the availability of these resources changing over the last 40,000 years. Environmental shifts such as those indicated by Chalson and Martin (2008) and Karskens (2007) can lead to changes in water channel and chain of pond alignment, flooding regimes and resource availability. These in turn can lead to adaptation and changes in landscape use by Aboriginal people over time, resulting in patterns of land use and preservation of Aboriginal objects which may not be immediately apparent based on current environmental conditions.

Based on the environmental context and archaeological context of the project area, Aboriginal objects (stone artefacts) are likely to occur within the project area "in a consistently low-density distribution" to depths of 1.3 m (but often to 0.6 - 0.9 m) based on archaeological excavations undertaken by Kohen (1997). Insite Heritage (2005), Comber Consultants (2006, 2008), Ecological Australia (2020) and synthesis undertaken by Williams et al (2017).

These Aboriginal objects are likely to have moved or displaced Aboriginal objects within the top 0.3 m to 0.6 m of soil as a result of past land use and disturbance, resulting in low archaeological integrity in the topsoil to a minimum of 0.3 m. It is possible that intact archaeology has survived within the project area, particularly below the level of agricultural activities. However, as noted by Kohen (1997, 2004), it is also possible that artefacts have moved through the soil profile as a result of bioturbation and other geomorphic agents.

September 2025 Page 39 of 87



5. Predictive Model

Based on the known archaeological, environmental and landscape context of the locality, a predictive model for evidence of Aboriginal occupation for the project area is presented below.

Table 6 describes the types of sites that may be encountered and their predicted relevance to the project area. The types of sites are not exhaustive but indicative of the main types of sites that could reasonably be expected to be found.

Table 7 provides the definitions of archaeological potential.

Table 6. Predictive Model for Aboriginal Occupation within the Project Area.

Description Relevance to the Project Area

Artefacts (Isolated artefacts and artefact scatters)

Isolated artefacts and artefact scatters (open camp sites) are the locations of discarded stone artefacts, often material that has been discarded as part of making stone tools or over frequent episodes of occupation/visitation of an area. These sites are most likely to be found within 200 m of a watercourse in well drained alluvial flats, alluvial terraces, lower slopes, and confluences where the landscape has not been heavily modified and on spurs, ridge lines and crests.

All of Australia has potential for discarded Aboriginal stone tools unless areas are heavily modified, and soils have been removed. Stone tools have been found in highly disturbed contexts and may retain value to community members.

Stone artefacts are likely to occur within the project area "in a consistently lowdensity distribution" to depths of 0.6 m, consistent with the maximum recorded depth of the A horizon.

Artefacts may be manufactured of predominately silcrete and occasionally quartz, chert, quartzite, hornfels and basalt.

Middens

Middens and shell mounds can be the accumulation of debris from fresh and saltwater fish, crustaceans, molluscs, and other shellfish (shells, fish bones) consumed as part of Aboriginal people's diet and may also contain charcoal, stone artefacts, bone and other types of material used by Aboriginal people. They are also known to contain cremated human remains or human burials, particularly in coastal environments. These places can have spiritual or ceremonial use and contain evidence of the early domestic practices. Middens are identified within sand dunes, beaches, terraces above watercourses, and inland, near lagoons and water holes.

Shell middens are rare but do occasionally occur along the Hawkesbury-Nepean Rivers (GML 2021). The soils in the project area are generally acidic and not conducive to the preservation of shell. It is possible, but unlikely, that shell midden may be present in the project area.

Burial Sites

Burial sites or Aboriginal ancestral remains may be found in a variety of landscapes throughout NSW, although most frequently they are found in middens, sand dunes, lunettes, bordering dunes, river terraces and other sandy or soft sedimentary soils, as well as defined cemeteries or burial grounds, mounds, rock shelters and caves. They may be marked with stones, carved trees, or found in association with other sites such as middens. These sites are rare and have a very special importance to Aboriginal people. There are numerous examples in Australian and NSW of burials being found in highly modified contexts such as Narrabeen carpark and foreshore for Narrabeen man and underneath houses at Nambucca.

Consultation for previous archaeological reports has noted a general potential for burial sites to occur within the Penrith Lakes area. No specific burial sites have been identified in the project area based on Aboriginal consultation to date and previous archaeological and historical research for this assessment.

Ceremonial/bora grounds, earthworks, and stone arrangements

Ceremonial or Bora grounds, earthworks and stone arrangements are rare site types and sometimes difficult to identify as they are generally low constructions, usually less than a metre high, and may range from being

There are no known bora grounds or stone arrangements within the project area based on Aboriginal consultation

September 2025 Page 40 of 87



very simple to more elaborate. They are made by the movement and mounding of earth or the arrangement of stones in circular, linear or figurative patterns, cairns and as paths. Bora grounds and stone arrangements are generally found on flat or gently sloping landforms but are known to exist in other contexts (e.g. cairns on hilltops and crests, or stone structures within rock shelters).

to date and previous archaeological and historical research for this assessment.

Story places, post-contact sites, songlines

These site types may or may not have tangible evidence of Aboriginal land use.

"The area is really close to Aboriginal Lore grounds" (Deerubbin LALC).

Other site types

Culturally modified trees Scarred trees and carved trees contain evidence of scars and carved patterns which can be attributed as having Aboriginal cultural origin. Scarred trees include the removal of bark from the trunk of the tree (usually with a stone axe) to make shields, canoes, implements and other types of items which leave a wound on the tree trunk. Carved trees are often found in association with ceremonial grounds, burials, or cultural sites. Carved trees are a very rare site type.

Petroglyphs (also referred to as Rock Engravings) are art sites where marks have been made in stone by Aboriginal people (for example, spirit figures, animals, implements and footprints).

Rock shelter sites with art rock overhangs used for shelter by Aboriginal people and where smooth surfaces on the walls of the shelter (sandstone surfaces) are painted with ochres and pigments. Rock shelters with floor deposits are closed sites perfect for Aboriginal occupation and evidence of burials, stone tools and midden material maybe subsurface or extant.

Aboriginal axe grinding grooves are grooves most often found in sandstone where Aboriginal people have sharpened or manufactured stone axes and other implements and, in some cases, ground seed and grains in the sandstone forming 'bowls'. This site type can occur where suitable geology is present.

Stone quarries Stone quarries for artefact manufacture, are most likely found in areas of exposed bedrock or gravel beds.

While these site types occur within the wider region, they are unlikely to occur within the project area due to an absence of mature native vegetation and an absence of suitable geology

Potential Archaeological Deposits

Soil profiles within landforms which are predicted to contain buried evidence of Aboriginal occupation. This buried evidence is most often stone artefact scatters which survive frequently in the archaeological record and may occur in both primary and secondary depositional environments. Nearly all soil landscapes and landform types in Australia are connected to Aboriginal occupation and have potential to contain evidence of such.

Artefacts are most commonly recorded in A unit soils (topsoils) and at great depth in B unit alluvial deposits. They occur also in other types of B unit subsoils and deposited between the cracks of C unit cracking clays, where artefacts have moved down the soil profile. of Evidence Aboriginal occupation occurs commonly in both natural secondary deposits as well as in many types of disturbed contexts. Due to the large number of environments and soils where artefacts can occur, deposits are considered to have archaeological potential unless the absence of artefacts is anticipated as a result of post-depositional factors.

September 2025 Page 41 of 87



Table 7. Definitions of Archaeological Potential

Archaeological Potential	Definition
Low to Zero	Landforms that have been totally modified and have low to zero potential for any remaining original soil profile or intact archaeological deposits. This category includes existing roads, quarry areas or any area where the original soil profile (topsoil – A horizon) has been stripped and the landform completely modified. This landform may also include areas where there is no intact A horizon soils due to high levels of erosion.
Low	Landforms that may have been utilised by Aboriginal people in the past, but at a lower intensity relative to all surrounding landforms, resulting in a lower artefact density than all surrounding landforms. This category also includes landscape areas of low terrain integrity, where geomorphic processes or human action may have redistributed artefacts from their deposited locations, such as stripping of soil to create levees or excavation to create culverts, dams or bridges, resulting in site disturbance or destruction.
Moderate	Landforms that are predicted to have been utilised by Aboriginal people in the past, but not intensively or repeatedly. There is therefore potential for artefactual deposition, but at a lower frequency and density than in areas of high archaeological potential. This category may also refer to landforms known to be sensitive for higher levels of Aboriginal occupation but where prior ground surface disturbances has decreased the archaeological integrity and potential of finding evidence of Aboriginal occupation (for example, creek confluences, alluvial terraces where stratigraphic integrity may have decreased due to previous land use).
High	Landscape areas predicted to have been intensively or repeatedly utilised by Aboriginal people in the past, such as creek confluences, Pleistocene terraces, floodplains or elevated landforms above major watercourses or floodplains. In these areas, site and artefact density are expected to be higher than the surrounding landscape, and sites in these areas may possibly be more complex. Terrain integrity in these areas may be variable although prior ground surface disturbance should be low or non-existent. An important characteristic of areas of high archaeological potential is the research potential or the capacity of sites to provide valuable information on past Aboriginal land use.

The project area is considered to have **moderate archaeological potential**, particularly below the level of past agricultural activities. This is because:

- As an elevated terrain in proximity to water, it is anticipated that the project area will have been utilised by Aboriginal people in the past.
- The project area is predicted to contain low densities of stone artefacts with low stratigraphic integrity in the top 0.6 m of soil and greater integrity below 0.6 m.
- The project area may contain in-situ stratigraphy, relative to the surrounding Penrith Lakes area which has been significantly impacted from quarrying and past land use.

Based on previous work in the area, stone artefacts are the most likely archaeological site type to be encountered.

5.1 SUMMARY

It is anticipated that the project area, as elevated terrain in proximity to water, will have been utilised by Aboriginal people in the past but not as intensively as other parts of the Penrith Lakes area as it is 300 m or greater from water. Stone artefacts are predicted to occur within the project area "in a consistently low-density distribution" to depths of 0.6 m, consistent with the maximum recorded depth of the A horizon. Artefacts may be manufactured of predominately silcrete and occasionally quartz, chert, quartzite, hornfels

September 2025 Page 42 of 87



and basalt. Other site types and features are possible but unlikely to occur in the project area. This is due to the degree of past land use and disturbance and a lack of suitable geology and vegetation.

September 2025 Page 43 of 87



6. Survey and Results

Section 6 provides a summary of the survey strategy for fieldwork, methods employed during fieldwork, the survey team and the results of the survey including sites and predictions for archaeological potential.

6.1 SITE STRATEGY

Two archaeological surveys were undertaken for this assessment. The first was a total pedestrian survey as part of a due diligence assessment report (Virtus Heritage 2024) and the second was a survey with RAPs.

A summary of the site survey undertaken for the due diligence assessment and survey coverage is represented here to meet the reporting requirements of the *Code of Practice for Archaeological Investigation of Aboriginal objects in NSW* (DECCW 2010). Additional information from the second survey conducted on 24 February 2025 is also summarised below.

Overall, the archaeological inspection aimed to:

- Confirm the desktop environment context (e.g. soils, geology, and vegetation, see above).
- Identify landscape features within the project area and record landscape elements that may have potential for cultural heritage.
- Confirm the past land use and disturbance history within the project area.
- Test the archaeological predictive model.
- Identify and assess any potential Aboriginal archaeological sites and/or cultural heritage constraints within the project area.

As the project area comprised one landform, the project area was surveyed as a single archaeological survey area, targeting areas of exposure (i.e. areas with adequate ground visibility).

Within the archaeological survey area, the different types of surface exposures (e.g. vehicle track, erosion scour), previous land use history and disturbance, natural features (e.g. presence of sandstone), soils, erosion, ground surface visibility, and geomorphic activity were recorded following the requirements of the *Code of Practice for Archaeological Investigation of Aboriginal objects in NSW* (DECCW 2010) and information or comments provided by Aboriginal parties involved in the survey.

The archaeological survey area was mapped and recorded using a handheld phone GPS and digital camera.

6.2 SITE SURVEY

Fieldwork was conducted as per the project methodology and survey strategy as outlined in Section 6.1.

A pedestrian survey of the project area was undertaken on 24 June 2024 by Steve Randall (DLALC), and Garth Thompson (Virtus Heritage), assisted by Anya Graubard (Virtus Heritage). The team were also met by Morson Group representatives Peter Morson, Joshua West, Joyce Ting to discuss the project design and impacts as part of this project's Connecting with Country consultation process. All survey areas and photographs were recorded using standardised recording forms based on the CoP requirements.

A second survey was undertaken by 24 February 2025 with Dr Mary-Jean Sutton (Director) assisted by Anya Graubard (Virtus Heritage) and Tania Carroll (Murribigee), Vicky Slater (Wurrumay) and Anika Jalomaki (Yulay). The survey included:

- Coverage of all environmental contexts within the project area.
- Focusing, where possible, on ground surfaces with higher archaeological visibility.
- Inspection of any mature trees for evidence of Aboriginal scarring (none present).

September 2025 Page 44 of 87



- Inspection of any stone outcrops for evidence of quarrying (none present).
- Inspection of any sandstone bedrock for evidence of grinding grooves (none present).
- Inspection of any places specifically requested by the Aboriginal parties within the project area.

6.3 SURVEY RESULTS

Twelve Aboriginal objects were identified within the project area across 8 locations, which constitute one identified Aboriginal artefactual scatter, Penrith Lakes 2025 (PL2025) in the February 2025 survey.

Soil exposures found around the proximity of the project area confirmed the soils to be a yellowish-brown clayey sand (see Figure 8). Exposures were particularly common along the fence line surrounding each of the properties and was consequently where all of the twelve artefacts were identified (see Figure 22 and Table 8). All mature trees within the project area were identified as non-native species (see Figure 9). The inspection confirmed that the project area had undergone extensive ground disturbance associated with the construction of the existing houses, and landscaping works that had levelled the project area in association with previous site developments (see Figures 10-13). Further impacts were identified in water piping associated with a protruding irrigation tap on the western lawn, and a water tank identified in the middle lawn (see Figures 12-13). These impacts also suggest underlying piping is present within the project area and impacts associated with their construction have previously taken place.

During the first survey, Steve Randall commented that the project area had been extensively disturbed by previous activities evident during the survey. Mr Randall also commented on sites being identified west, north and south of the project area, in association with sand lenses in close proximity to the Nepean River.

The impacts associated with the housing development, underlying infrastructure and landscaping works visible during the site inspection indicate a high level of disturbance has taken place within the A-horizon of soils throughout the project area. Deeper soils remain largely undisturbed. The likelihood of Aboriginal objects decreases with distance from water, with the nearest watercourses greater than 300 m away.








Figure 17. Exotic trees within the project area (right) compared to native trees outside project area (left).

September 2025 Page 45 of 87





Figure 18. Buildings present and levelled landscape from north-west corner of project area.



Figure 19. Building present and levelled landscape from north-east corner of project area.





Figure 20. Irrigation tap identified in western project area.

Figure 21. View to roofed-water tank in central project area.

One site was recorded within the project area, defined as a low density background scatter of twelve visible Aboriginal objects eroding out of exposures recorded in February 2025 as Penrith Lakes 2025. The site definition as the entire project area and justifications for site definition were emailed to Kym McNamara, Heritage NSW on 20 June 2025 and Sam Allen responded from Heritage NSW via email on 1 July 2025 stating that "Heritage NSW is supportive of the revised approach in registering the project area as a site with background scatter". The site is defined by the following (as emailed on 20 June 2025 to Heritage NSW)

- The project area is situated on the Penrith Unit of the Cranebrook Terrace which has been demonstrated over numerous scientific studies and geotechnical investigations to be an archaeologically significant unit (e.g., Kohen, 1986; Nanson et al., 1987; Insite Heritage 2000; Williams et al., 2017; Comber Consultants, 2006, 2006).
 - Given the age of the uppermost strata of the Penrith Unit (50,000 100,000 years old), these studies have reported that the vast majority of artefacts have been constrained within the top 0.6 m of soils (A horizon – noted as deep as 1.3 m in some studies in topographic depressions) and exist at depth due to bioturbation and/or soil turnover from previous landuse (agriculture).

September 2025 Page 46 of 87



- Proposed excavations will be to a maximum of 2.0 m below ground level (BGL), with the majority between 0.6 and 1.2 m BGL. As such, proposed site works will impact the archaeologically significant portion of the Penrith Unit.
- Based upon the high volume of studies within the Penrith Unit (a list with summaries will be provided along with a draft AA and ACHA within the next few weeks) and the identification of artefacts within fence line surface exposures during a site visit in February 2025, we expect to encounter Aboriginal objects within the A horizon of our project area (0.3 – 0.6 m deep based upon geotechnical surveys).
 - The project area exhibits no distinct changes in topography and as such, there are no distinct landform units which can be mapped to provide insight over the possible distribution of artefacts. Due to the previous land-use of the project area (and broader landscape), any macro changes in topography were likely destroyed.
 - o The stratigraphy of the uppermost 0.6 m has also been disturbed as a result of past agricultural land-use. Therefore, any in-tact stratigraphy which could be used to inform us on the distribution of artefacts within the Penrith Unit (e.g., flood couplets) have been destroyed.
- The project area is situated ~90-100 m away from the highly archaeologically sensitive Richmond Unit of the Penrith Terrace.

The project area previously had an AHIP granted in 2018 (#C0001415) which expired in 2023 and a future AHIP application will cover the same Lots as before (12, 14, and 16). With the topographic uniformity of the Penrith Unit, we could possibly link the project area to pre-existing site cards for works completed east of our site. Alternatively, we can register the artefacts as a new site but given that there are no significant landforms to constrain the project area to, the boundaries will not have any robust data to support their geographic placement.

It is worth noting that minor revisions of the proposed excavation depths were received on 17 July 2025 (see **Section 2**). Table 8 provides a summary of recorded exposures of Aboriginal objects in the February 2025 survey for the site, Penrith Lakes 2025 recorded by Dr Sutton with RAPs.

Table 8. Aboriginal Objects (stone tools) within Penrith Lakes 2025 Recorded within the Project Area.

PL 2025 -Retouched Flake

Recorded

Site and Object



Object Description Including Landform

The object is a retouched meta-mudstone flake located along the fence line of a residential property (refer to **Figure 22**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The object is situated along an exposure associated with the southern fence line of the project area. The exposure is approximately 1 meter wide and 100 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The tool is a tertiary flake with evidence of retouch and some patina and is a yellow – orange meta–mudstone 4 cm length x 2 cm width x 0.5 cm thick.

September 2025 Page 47 of 87



Site and Object Recorded Object Description Including Landform

PL 2025 -Quartzite PF1



The object is a primary quartzite flake located along the fence line of a residential property (refer to **Figure 22**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The object is situated along an exposure associated with the western fence line of the project area. The exposure is approximately 1 meter wide and 90 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. It is a primary flake with evidence of pitting and some patina and is a yellow – tan quartzite 6 cm length x 2.5 cm width x1.5 cm thick.

PL 2025 – Meta-Mudstone SF1



The object is a secondary meta-mudstone flake located along the fence line of a residential property (refer to **Figure 22**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The object is situated along an exposure associated with the southern fence line of the project area. The exposure is approximately 1 meter wide and 60 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The object is a secondary flake with evidence of pitting and some patina and is a yellow – orange meta–mudstone 2 cm length x 1.5 cm width x0.5 cm thick.

PL 2025 -Quartzite SF1



The object is a secondary quartzite flake located along the fence line of a residential property (refer to **Figure 22**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The site is situated along an exposure associated with the southern fence line of the project area. The exposure is approximately 1 meter wide and 60 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The object is a secondary flake with evidence of pitting and some patina and is a reddish orange quartzite 2.5 cm length x 2 cm width x1.5 cm thick.

September 2025 Page 48 of 87



Site and Object Recorded Object Description Including Landform

PL 2025 - AS1



The objects are part of a small scatter of at least one pink quartzite broken flake and three grey silcrete broken flakes and a red silcrete broken flake located along the fence line of a residential property (refer to **Figure 22**). Visibility in the exposure was 70% and outside the exposure was 1%. It is a location heavily disturbed by generational agricultural and residential use and erosion from heavy rain falls in February 2025.

The site is located on an alluvial terrace. The site is situated along an exposure associated with the southern fence line of the project area. The exposure is approximately 1 meter wide and 60 meters long.

PL 2025 – Basalt Hand Axe



The object recorded is a basalt hand axe located along the fence line of a residential property (refer to **Figure 22**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The site is situated along an exposure associated with the southern fence line of the project area. The exposure is approximately 1 meter wide and 100 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The object is a hand axe with evidence of flaking, pitting and some patina and is a greyish black basalt 7 cm length x 5 cm width x2.5 cm thick. There is also evidence of blood as shown in the photograph on the tool or some kind of residue.

PL 2025 - Basalt PF1



The object is a primary basalt flake located along the fence line of a residential property (refer to **Figure 22**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The object is situated along an exposure associated with the northwestern fence line of the project area. The exposure is approximately 4 meter wide and 10 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The artefact is a tertiary flake with evidence of pitting and some patina and is a greyish black basalt 4.5 cm length x 3 cm width x1 cm thick.

September 2025 Page 49 of 87



Site and Object Recorded Object Description Including Landform

PL 2025 - Basalt SF2



The object is a secondary basalt flake located along the fence line of a residential property (refer to **Figure 22**). It is a location heavily disturbed by generational agricultural and residential use.

The object is located on an alluvial terrace. The site is situated along an exposure associated with the northwestern fence line of the project area. The exposure is approximately 4 meter wide and 10 meters long. Visibility in the exposure was 70% and outside the exposure was 1%. The isolated object is a secondary flake with evidence of pitting and some patina and is a dark greyish black basalt 2.5 cm length x 2 cm width x1 cm thick.

September 2025 Page 50 of 87





Figure 22. Identified Aboriginal Objects part of Penrith Lakes 2025 Background Scatter within the Project Area.

September 2025 Page 51 of 87



6.4 LANDFORMS, VISIBILITY AND EFFECTIVE COVERAGE

Section 6.4 presents and discusses the landforms within the project area and the visibility and effective coverage of the survey. This information is important to demonstrate that the survey data provides sufficient evidence for an evaluation of the distribution of objects across the landscape, taking into account archaeological potential and recorded Aboriginal objects/site.

The general ground surface visibility and any exposures were recorded to enable survey coverage and effective visibility to be calculated. **Table 9** below details the survey coverage and effective visibility for each of the survey area and **Table 10** provides a landform summary.

Survey coverage was 100% of the project area, excluding cement driveways and built structures. Ground surface visibility and exposures in the project area were extremely limited (<1%) due to terrain modification and the high level of grass cover (see **Figures 9-10**). As result, effective survey coverage was low.

This assessment has therefore relied on the geotechnical borehole data, assumptions of disturbance based on documented and observed past land use disturbance and archaeological assessments in the local area to assess the archaeological potential within the project area.

Table 9. Survey Coverage and Effective Visibility

Survey Unit	Landfor m	Survey Unit Area (m²)	Visibilit y (%)	Visibility (m²)	Exposure (%)	Effective Coverage Area _† (m²)	Effective Coverage †† (%)
1	Modified alluvial terrace	34,000 m ²	1%	340 m ²	70%	266 m ²	<1%

^{† (=} survey unit area x visibility % x exposure %)

In **Table 9**, exposures where artefacts are recorded are detailed with archaeological visibility and exposure and also recorded on **Figure 22**.

Table 10. Landform Summary - Sampled Areas

Landfor m	Landform area (m²)	Effective Coverage m ²	% Landform Effectively Covered	Numbe r of sites	Site Description
Modified alluvial terrace	34,000 m ²	266 m ²	<1%	8	Low density background scatter, Penrith Lakes 2025 identified.

6.5 SUMMARY

100% of the project area was surveyed on foot. The survey indicated low surface visibility, with estimated effective coverage <1% across the project area and documented previous land use and disturbance, previously identified in **Section 3** of this report.

The literature review did not identify Aboriginal objects within the project area but found low visibility and a reasonable potential for Aboriginal objects to occur within the project area at low frequencies and with low

September 2025 Page 52 of 87

^{†† (=} effective coverage area/survey unit area x 100)



archaeological integrity to depths of around 0.6 m. This was supported by the survey inspection, which identified eight surface exposures with Aboriginal objects limited to fence lines recorded as background scatter, Penrith Lakes 2025 (refer to Table 8). Exposures surveyed as mapped in **Figure 22** were found to contain stone tools evidence of previous Aboriginal occupation. There is the potential for intact archaeological deposits below the depth of agricultural activities and additional Aboriginal stone artefacts within the modified layers of topsoil in a disturbed context. The proposed activity therefore has the potential to harm recorded Aboriginal objects.

September 2025 Page 53 of 87



7. Analysis and Discussion

As noted in **Section 4**, the project area is part of a broader Aboriginal cultural landscape of the Dharug-speaking peoples and associated with the Boorooberongal and Mulgoa clans (PLDC 2011, Karskens 2007).

The Penrith Lakes area was a traditional meeting place for Aboriginal people. Its river and rich soils provided abundant natural vegetation and wildlife which supported Aboriginal people for many generations (New South Wales State Heritage Register. Department of Planning & Environment. HO2009, 2024). Evidence of this history has been revealed through the many artefacts were collected during the 25 years of sand and gravel mining at Penrith Lakes, to the north, west and south of the project area (Kohen 1986a, 1988–2004, 1997, EMGA 2001, Comber 2005, 2006, 2008, PLDC 2011, New South Wales State Heritage Register. Department of Planning & Environment. HO2009, 2024).

The survey results presented in **Section 6** indicate low surface visibility across the project area, with estimated effective coverage <1%. This is consistent with the predictions of Aboriginal land use made in Section 5.

It is anticipated that the project area, as elevated terrain in proximity to water, will have been utilised by Aboriginal people in the past but not as intensively as other parts of the Penrith Lakes area as it is 300m or greater from water. Stone artefacts are predicted to occur within the project area "in a consistently low-density distribution" to depths of 1.3m (but often to 0.9m). Artefacts may be manufactured of predominately silcrete and occasionally quartz, chert, quartzite, hornfels and basalt. Other site types and features are possible but unlikely to occur in the project area as they have not previously been identified within the project area during previous assessments and due to the degree of past land use and disturbance and a lack of suitable geology and vegetation.

As the project area may contain in-situ geomorphology (PLDC 2011), relative to the surrounding Penrith Lakes area which has been significantly impacted from quarrying and past land use, the project area is considered to have moderate archaeological potential, particularly below the level of past agricultural activities to contain low densities of stone artefacts.

The project area contains deposits of the Penrith Unit of the Cranebrook Terrace which has experienced relatively less disturbance than other parts of the Penrith Lakes Scheme. This resource and opportunities to understand it are increasingly diminished by the amount of development in the region. Where Aboriginal objects survive in this profile, they have archaeological and geomorphic value due to their ability to support models of Aboriginal land use and archaeological preservation in the local area, particularly where excavations can be undertaken in a controlled manner to the current regulatory standards.

This assessment notes that across the Cranebrook Terrace and Penrith Lakes Scheme there has been a management trend towards area-wide AHIPs. These area-wide AHIPS aim to manage the residual risk of Aboriginal objects irrespective of the identification of sites, particularly in those areas not historically impacted by sand quarrying (Kohen 1988-2004, AHIP COO01415, AHIP 1131345, Comber 2017).

In 2018, previous survey and archaeological excavation coverage of the Penrith Unit of the Cranebrook Terrace was deemed to have been sufficient allow for the issue of an AHIP COO01415 (AHIMS 3891) to harm known and unknown Aboriginal objects within the project area without mitigation.

We recommend that archaeological testing is not required. This is due to the volume of literature already available on the Penrith Unit of the Cranebrook Terrace, the previous land-use of the project area diminishing any research potential which could come from the distribution of in-situ Aboriginal objects, a lack of any topographic variability within the project area, and that a background scatter of artefacts have already been identified within limited surface exposures on-site, confirming that the project area is archaeologically sensitive and likely consistent with previous site investigations close-by from within the Penrith Unit and can therefore expect a similar vertical distribution of Aboriginal objects.

September 2025 Page 54 of 87



With the classification of the project area as a site with background scatter, and the presence of Aboriginal objects in all identified exposures in 2025's survey, an AHIP with community collection and salvage for subsurface disturbances associated with site development works will be required.

September 2025 Page 55 of 87



8. Scientific Values and Significance Assessment

Section 8 assesses the scientific/archaeological values of Aboriginal archaeological sites and objects within the project area and references the other values identified by the Burra Charter, including the cultural values provided by RAPs.

Aboriginal cultural heritage sites are therefore assessed following these categories of significance developed under the Burra Charter:

- Aesthetic value refers to "the sensory, scenic, architectural and creative aspects of the place" and is often linked with social values (OEH 2011:9). This value may refer to the visual nature of the landscape and "smells and sounds associated with the place and its use" (OEH 2011:9).
- Historic value refers to "the associations of a place with a historically important person, event, phase
 or activity in an Aboriginal community", for example, post-contact places such as missions or reserves
 or massacre sites (OEH 2011:9).
- Scientific/archaeological value The Guide to investigating, assessing and reporting on Aboriginal cultural heritage in NSW (OEH, 2011) defines scientific values as:

This refers to the importance of a landscape, area, place or object because of its rarity, representativeness and the extent to which it may contribute to further understanding and information (Australian ICOMOS 1988).

This is further defined to the assessment of three criteria which Heritage NSW (2011) states "must be graded in terms that allow the significance to be described and compared; for example, as high, moderate or low" to

- 1. **Research potential**: does the evidence suggest any potential to contribute to an understanding of the area and/or region and/or state's natural and cultural history?
- 2. **Representativeness**: how much variability (outside and/or inside the subject area) exists, what is already conserved, how much connectivity is there?
- 3. Rarity: is the subject area important in demonstrating a distinctive way of life, custom, process, land-use, function or design no longer practised? Is it in danger of being lost or of exceptional interest?
- 4. **Education potential**: does the subject area contain teaching sites or sites that might have teaching potential?
- Spiritual value (can only be assessed by Aboriginal people) refers to the "the intangible values and
 meanings embodied in or evoked by a place which give it importance in the spiritual identity, or the
 traditional knowledge, art and practices of a cultural group. Spiritual value may also be reflected in the
 intensity of aesthetic and emotional responses or community associations and be expressed through
 cultural practices and related places" (ICOMOS 2013:4).
- Social value (can only be assessed by Aboriginal people) refers to the contemporary associations and
 attachments Aboriginal people have to an area or place. The guide to investigating, assessing, and
 reporting on Aboriginal cultural heritage in NSW notes that "Social or cultural value is how people express
 their connection with a place and the meaning that place has for them. Places of social or cultural value
 have associations with contemporary community identity. These places can have associations with
 tragic or warmly remembered experiences, periods, or events. Communities can experience a sense of

September 2025 Page 56 of 87



Category

Significance

loss should a place of social or cultural value be damaged or destroyed. There is not always a consensus about a place's social or cultural value" (OEH 2011:8).

Table 11 provides an assessment of these values within the project area.

Table 11. Assessment of the Burra Charter Values within the Project Area

Rarity: is the subject area
important in
demonstrating a
distinctive way of life,
custom, process, land-
use, function or design no
longer practised? Is it in

danger of being lost or of

exceptional interest?

Representativeness: how much variability (outside and/or inside the subject area) exists, what is already conserved, how much connectivity is there?

Statement of Values

There are no registered sites on AHIMS within the project area, though eight exposures with artefacts were identified during a survey visit on 20 February 2025. The project area is situated on a portion of the Penrith Unit of the Cranebrook Terrace which has experienced relatively less disturbance than other parts of the Penrith Lakes Scheme. This resource and opportunities to understand it are increasingly diminished by development.

The presence of Aboriginal objects demonstrate local Aboriginal land use and cultural history within the project area and surrounds. As more of the Cumberland Plain and Penrith Lakes area become urbanised there is less opportunity for conservation of Aboriginal occupation deposits. However, the artefacts of broken flakes and flakes within the project area are not unusual scientifically but have high cultural value. The hand axe and retouched flake are less common tool types in local assemblages.

The exposures of artefacts in Penrith Lakes 2025 background scatter are connected to the broader cultural landscape of Aboriginal land use of the Cumberland Plain. The site does have different tool types including a retouched flake, a broken hand axe, flakes and broken flakes. These tool types are not rare in the locality of the Cumberland Plain (and not in the State) surrounding the project area where there is not much variability in assemblages discussed in previous archaeological research.

Broken flakes and flakes are not unusual in similar landscape contexts in the locality and the region and not rare.

Research potential: does the evidence suggest any potential to contribute to an understanding of the area and/or region and/or state's natural and cultural history? The project area contains moderate research potential as it may provide an opportunity to further understand the geomorphic and archaeological value of the Penrith Unit of the Cranebrook Terrace and past Dharug land use on elevated terrain at a distance from an unnamed tributary of Cranebrook Creek, through analysis and salvage of the artefacts currently exposed and likely to be salvaged through further archaeological salvage.

The dating potential has been diminished by the degree of past land use disturbance in the minimum top 0.3 to 0.6m of deposit, making potential for chronology or dating in cultural history locally and at the State level unlikely and of low research potential.

Education potential: does the subject area contain teaching sites or sites that might have teaching potential? The hand axe, retouched flake as well as the different artefact types and raw materials identified to date in Penrith Lakes 2025 have moderate educational potential for teaching. Residue analysis in particular and more detailed stone tool analysis could provide additional information about the hand axe to determine if there is blood or some other residue on the tool or starch or other residues on the retouched surface of the retouched flake. Residue analysis could

September 2025 Page 57 of 87



provide some education and teaching potential for these two stone tools to contribute to the cultural story of the project area.

8.1 SUMMARY AND STATEMENT OF ARCHAEOLOGICAL (SCIENTIFIC) VALUES WITHIN THE PROJECT AREA

The project area has moderate archaeological values for research and educational and teaching potential as demonstrated by the assemblage of Penrith Lakes 2025. This scatter has no rarity and representativeness at the State level and low rarity and representativeness in the local level. The project area's soils are highly altered and impacted by agriculture and infrastructure to the minimum 0.3 m to 0.6 m in depth. Integrity is considered low at these depths but may have moderate potential below the disturbance zone.

The project area has moderate scientific values in its potential to yield information that will contribute to an understanding of the locality's natural and cultural history. Key areas of research include the Aboriginal settlement pattern and history and impacts of the last 237 years of European invasion and earlier evidence of Aboriginal cultural history relating to the use of stone tool types such as the broken axe and retouched flake and an understanding of potential residues as well as tool types use and manufacture.

Table 12 provides a summary of these criteria for scientific value against the recorded sites in the project area.

Table 12. Summary of Archaeological Value in the Project Area

Site	rarity (Local - L)	representativeness (Local - L)	research potential (Local – L)	educational and teaching (Local - L)
Penrith Lakes 2025 -	Local	Local	Local	Local
Background Scatter	Low	Low	Moderate	Moderate

September 2025 Page 58 of 87



9. Impact Assessment

All Aboriginal objects are protected under the *National Parks and Wildlife Act 1974*, irrespective of their context or past disturbance and displacement.

A summary of the proposed development with impacts that may cause harm to Aboriginal objects and likely Aboriginal objects was provided in **Section 2**. The following definitions of harm are reproduced from OEH (2011).

Direct harm/impact	Direct harm/impact may occur as the result of any activity which disturbs the ground including, but not limited to, site preparation activities, stripping of soils, clearing of shrubs, grass and contaminants, installation of services and infrastructure, roadworks, excavating detention ponds and other drainage or flood mitigation measures, and changes in water flows affecting the value of a cultural site.
Indirect harm/impact	Indirect harm/impact may affect sites or features located immediately beyond, or within, the area of the proposed activity. Examples of indirect impacts include, but are not limited to, cumulative impact on art in a rock shelter site from increased visitation, vibration impacts to sites from construction equipment, destruction from increased erosion and changes in access to wild food resources (OEH 2011).

For the purposes of this assessment three levels of impact were considered:

- **Significant impact** including topsoil stripping, cut and fill of areas. This would likely damage or remove all Aboriginal objects that might be located in the area of impact.
- Moderate impact minor topsoil stripping, no cut and fill majority of vegetation maintained. This would likely damage or disturb some Aboriginal objects that might be located in the specific areas of impact. Management measures could be put in place to protect individual known sites.
- Low impact no topsoil stripping, existing vegetation maintained. Sites in these areas could be subject to indirect impacts and would be managed via a management plan.

The proposal will involve significant impact in the project area to Penrith Lakes 2025, background scatter. Morson Group will be undertaking up to 2.3 metres of maximum depth of disturbance for excavation (refer to **Figure 23**) for services and the proposed development and Section 2 for description of construction activities.

September 2025 Page 59 of 87






Figure 23. Areas of Subsurface Impact within the Project Area

September 2025 Page 60 of 87



9.1 BACKGROUND

9.1.1. Pre-lodgement consultation

A meeting with Heritage NSW was held on 22 November 2024 to discuss the assessment requirements for this project. Correspondence on the results of the survey in February 2025 were emailed to Heritage NSW on 18 March 2025 and update on changes of approach to salvage instead of testing and update on RAP comments from the survey, with an offer to meet to discuss with Heritage NSW, if required. Additional correspondence was emailed by Peter Morson to Heritage NSW regarding how to approach site definition with justifications for site definition were emailed to Kym McNamara, Heritage NSW on 20 June 2025 as well as an offer to discuss in a meeting before pre-lodgement. Sam Allen responded from Heritage NSW via email on 1 July 2025 stating that "Heritage NSW is supportive of the revised approach in registering the project area as a site with background scatter". This email to Ms McNamara by Peter Morson included this input from Virtus Heritage below (as emailed on 20 June 2025 to Heritage NSW)

- The project area is situated on the Penrith Unit of the Cranebrook Terrace which has been demonstrated over numerous scientific studies and geotechnical investigations to be an archaeologically significant unit (e.g., Kohen, 1986; Nanson et al., 1987; Insite Heritage 2000; Williams et al., 2017; Comber Consultants, 2006, 2006).
 - o Given the age of the uppermost strata of the Penrith Unit (50,000 100,000 years old), these studies have reported that the vast majority of artefacts have been constrained within the top 0.6 m of soils (A horizon noted as deep as 1.3 m in some studies in topographic depressions) and exist at depth due to bioturbation and/or soil turnover from previous landuse (agriculture).
 - Proposed excavations will be to a maximum of 2 m below ground level (BGL), with the majority between 0.6 and 1.2 m BGL. As such, proposed site works will impact the archaeologically significant portion of the Penrith Unit.
- Based upon the high volume of studies within the Penrith Unit (a list with summaries will be provided along with a draft AA and ACHA within the next few weeks) and the identification of artefacts within fence line surface exposures during a site visit in February 2025, we expect to encounter Aboriginal objects within the A horizon of our project area (0.3 – 0.6 m deep based upon geotechnical surveys).
 - The project area exhibits no distinct changes in topography and as such, there are no distinct landform units which can be mapped to provide insight over the possible distribution of artefacts. Due to the previous land-use of the project area (and broader landscape), any macro changes in topography were likely destroyed.
 - The stratigraphy of the uppermost 0.6 m has also been disturbed as a result of past agricultural land-use. Therefore, any in-tact stratigraphy which could be used to inform us on the distribution of artefacts within the Penrith Unit (e.g., flood couplets) have been destroyed.
- The project area is situated ~90-100 m away from the highly archaeologically sensitive Richmond Unit of the Penrith Terrace.

The project area previously had an AHIP granted in 2018 (#COO01415) which expired in 2023 and a future AHIP application will cover the same Lots as before (12, 14, and 16). With the topographic uniformity of the Penrith Unit, we could possibly link the project area to pre-existing site cards for works completed east of our site. Alternatively, we can register the artefacts as a new site but given that there are no significant

September 2025 Page 61 of 87



landforms to constrain the project area to, the boundaries will not have any robust data to support their geographic placement.

HNSW have acknowledged emails and provided input which is included in this assessment.

9.1.2. Consideration of alternatives

Morson Group between February 2025 to date have attempted to minimise and redesign project impacts and depths of development. Some redesign was possible to avoid Aboriginal occupation deposits if extant was considered with their design team. The opportunity to reuse existing service trenches for new services and to minimise all ground disturbance works is not possible for this project.

9.2 AREAS WHERE OBJECTS WILL BE PROTECTED OR HARMED

All Aboriginal objects are protected under the *National Parks and Wildlife Act 1974* and conservation is the preferred option for all objects. Consideration should be given to avoidance of and conservation of sites where possible. Table 131, required under the *Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW* (DECCW 2010), lists all sites, places and PADs identified within the project area and summarises the type, level, and consequence of harm to these places.

No areas are currently proposed for conservation. The proposed activity will however impact on land with recorded Aboriginal objects within background scatter Penrith Lakes 2025.

Table 13: Summary of Likely Harm

Site/Place/PAD		Type of Harm	Level of Harm	Consequence of Harm	
		(direct/indirect/ none)	(total/partial/none)	(total loss of value/partial loss of value/no loss of value)	
Penrith 2025	Lakes	Direct	Partial - based on project impacts	Partial loss of value based on mitigation of project impacts	

9.3 JUSTIFICATION OF THE OBJECTIVES OF THE PROPOSED ACTIVITY

The project area is situated within an area zoned for the development of a tourism precinct within the Penrith Development Control Plans and State Environmental Planning Policy (SEPP). The design of this project has been undertaken with respect to Design Principles and in consideration of a framework (Government Architect NSW 2023).

Many of the proposed impacts have been proposed to areas which are considered to have low archaeological integrity in the top 30 cm of the topsoil, with impacts proposed at depths exceeding 0.6m limited to piling/footings and service trenches. Morson Group are committed to cultural and archaeological salvage in areas of proposed impact and harm to Aboriginal objects.

The RAPs have communicated to date that surviving archaeological deposits and Aboriginal objects may retain cultural value to the Registered Aboriginal Parties irrespective of their archaeological integrity. *The RAPs have been provided the draft report for review for comment on if they support the development of management and mitigation measures for harm to Aboriginal heritage.*

September 2025 Page 62 of 87



9.4 ECOLOGICALLY SUSTAINABLE DEVELOPMENT (ESD)

Australia's National Strategy for Ecologically Sustainable Development (1992) defines ecologically sustainable development (ESD) as: 'using, conserving and enhancing the community's resources so that ecological processes, on which life depends, are maintained, and the total quality of life, now and in the future, can be increased' (Department of Agriculture Water and the Environment Website Ecologically Sustainable Development Webpage). These environmental considerations include cultural heritage. ESD can be applied to Aboriginal cultural heritage by considering intergenerational equity and the precautionary principle.

The **Principle of Intergenerational Equity** states that 'the present generation should make every effort to ensure the health, diversity and productivity of the environment – which includes cultural heritage – for the benefit of future generations' (OEH 2011). That is, by considering how will future generations be able to visit, see, experience and/or research Aboriginal objects. The Operational Policy: Protecting Aboriginal Cultural Heritage (DECCW 2009) states in terms of Aboriginal heritage, intergenerational equity can be considered in terms of the cumulative impacts to Aboriginal objects and places in a region.

A way of gauging what level of impact from development has occurred within a region, is to review how many Aboriginal Heritage Impact Permits (AHIPs) have been issued for that region. A review of the public register of AHIP) issued between 2010 and 2021, for Penrith LGA indicates that over 60 AHIPs were issued. The current AHIP Public Register for the Penrith LGA shows that five AHIPs has been issued, for the region. Though AHIMS tracking of AHIPs to sites is highly inaccurate, at least 32 of the 85 Aboriginal cultural heritage sites recorded in the AHIMS search (Section 4), have had AHIMS issued. Over 300 SSD projects and modifications have been initiated in the Penrith LGA.

Overall, there has been a relatively high cumulative impact to the Penrith region that includes the project area based on recent AHIPs and SSD projects. The project area has been subject to relatively less development with impacts from historical land use and natural processes discussed in Section 3. As noted in the significance assessment in Section 8, one Aboriginal background scatter, Penrith Lakes 2025 has been identified to date and much of the project area has low archaeological integrity in the top minimum 0.3m to maximum 0.6 m of topsoil, however where intact archaeological deposits survive, they are of moderate research value.

The **Precautionary Principle** states that if there are threats of serious or irreversible environmental damage, lack of full scientific certainty should not be used as a reason for postponing measures to prevent environmental degradation.

Inductions, cultural awareness training and further investigation through archaeological and cultural salvage are precautionary steps. Conservation is not possible in the project area and the proponent has attempted at least for now six months to redesign project impacts and attempt to avoid cultural deposits, if still extant associated with Penrith Lakes 2025.

Archaeological salvage and community collection, in addition to inductions and cultural awareness training will be required to mitigate the impacts of these works.

September 2025 Page 63 of 87



10. Management and Mitigation Measures

Potential management and mitigation measures for the project area are discussed in this section within the broader context of state and federal legislation.

10.1 LEGISLATIVE CONTEXT AND STATUTORY REQUIREMENTS

The National Parks and Wildlife Act 1974 (NPW Act), the Environmental Planning and Assessment Act 1979 (EP&A Act) and the Heritage Act, 1977 are the relevant statutory controls protecting Aboriginal heritage within New South Wales. These acts and other relevant State and Commonwealth legislation are discussed below.

10.1.1. National Parks and Wildlife Act 1974

Under the provisions of the NPW Act, all Aboriginal objects are protected regardless of their significance or land tenure. Aboriginal objects are defined as 'any deposit, object or material evidence (not being a handicraft made for sale) relating to Aboriginal habitation of the area that comprises NSW, being habitation before or concurrent with the occupation of that area by persons of non-Aboriginal extraction and includes Aboriginal remains'.

Aboriginal objects are therefore limited to physical evidence and may also be referred to as 'Aboriginal sites', 'relics' or 'cultural material'. Aboriginal objects can include pre-contact features such as scarred trees, middens and artefact scatters, as well as physical evidence of post-contact use of the area such as Aboriginal built fencing or stockyards and missions.

The NPW Act also protects Aboriginal Places, which are defined as 'a place that is or was of special significance to Aboriginal culture. It may or may not contain Aboriginal objects'. Aboriginal Places can only be declared by the Minister administering the NPW Act. The NPW Act protects Aboriginal objects and Aboriginal places in NSW. Under the NPW Act, including the 2010 amendments, it is an offence to harm an Aboriginal object:

- Which the person knows is an Aboriginal object (a 'knowing offence').
- Whether or not a person knows it is an Aboriginal object (a 'strict liability offence').

The maximum penalty for a knowing offence is \$550,000 for an individual or \$1.1 million for a corporation and a 2-year gaol term. The maximum penalty for a strict liability offence is \$110,000 for an individual or \$220,000 for a corporation (DECCW 2010:5). A person or organisation who exercises due diligence in determining that their actions would not harm Aboriginal objects has a defence against prosecution for the strict liability offence if they later unknowingly harm an object without an AHIP (DECCW 2010:5). The due diligence defence is not available for activities which harm Aboriginal places. The *Due Diligence Code of Practice for the Protection of Aboriginal objects in NSW* (DECC 2010) sets out a procedure which, when followed, will satisfy the due diligence requirement. If a person or company can demonstrate that they exercised due diligence and determined that it was unlikely that Aboriginal objects would be harmed, then they have a defence to prosecution under the strict liability offence under Section 86(2) of the NPW Act (DECCW 2010:5).

Harm includes activities that destroy, deface or damage of Aboriginal object or Aboriginal Place, and in relation to an object, moving the object from the land on which it has been situated.

Under 89A (formerly Section 91) of the Act, the Chief Executive of the Office of Environment and Heritage (now regulated by Heritage NSW in the Department of Climate Change, Energy, the Environment and Water)

September 2025 Page 64 of 87



must be informed upon the identification of all Aboriginal objects. Failure to do this within a reasonable time is an offence under the Act.

Under Section 90 of the Act, it is an offence for a person to destroy, deface, damage, or desecrate an Aboriginal object or Aboriginal Place without the prior issue of an AHIP. AHIPs may only be obtained from Heritage NSW. If harm to Aboriginal objects and places is anticipated an AHIP is required.

The NPW Act also provides for stop-work orders under Part 6A Division 1 if an action is likely to significantly affect an Aboriginal object or Aboriginal Place. The order may require that an action is to cease or that no action is carried out in the vicinity of the Aboriginal object or Aboriginal Place for a period of up to 40 days.

The Guide to Investigating, Assessing and Reporting on Aboriginal Cultural Heritage, the Aboriginal community consultation requirements for proponents and Code of Practice for Archaeological Investigation of Aboriginal objects in NSW set out processes to demonstrate adequate assessment of the significance of and impacts to Aboriginal objects.

As the project area contains Aboriginal objects as part of Penrith Lakes 2025, further salvage is required to mitigate the proposed activities will impact Aboriginal objects.

10.1.2 Environmental Planning and Assessment Act (NSW) 1979

The project area is governed by the Chapter 5 Penrith Lakes Scheme of the State Environmental Planning Policy (Precincts – Western Parkland City) 2021 (the SEPP), version 28 June 2024.

The SEPP suspends covenants, agreements and instruments under certain conditions, such as conservation agreements under the NPW Act and heritage agreement or interim heritage orders within the meaning of the *Heritage Act 1977.*

Part 5.2 Development control requires that the consent authority shall take into consideration:

- (a) the Penrith Lakes Scheme Regional Environmental Study,
- (b) the recommendations, if any, of such technical working parties as may be established from time to time by the consent authority,
- (c) the statement of environmental effects accompanying the application,
 - (i) any item of the environmental heritage listed in Schedule 6,
 - (j) the effect upon a locality, place or building not listed in Schedule 6 having aesthetic, anthropological, archaeological, architectural, cultural, historical, scientific or social significance or other special value for present or future generations

This ACHA considers a and c of the above with respect to Aboriginal cultural heritage.

The project area is zoned for Tourism under the SEPP.

The miscellaneous provisions under Regulation 5.33 of the SEPP notes

- (1) The objectives are:
 - (a) to conserve the environmental heritage of Penrith,
 - (b) to conserve the heritage significance of heritage items and heritage conservation areas, including associated fabric, settings and views,

September 2025 Page 65 of 87



- (c) to conserve archaeological sites,
- (d) to conserve Aboriginal objects and Aboriginal places of heritage significance.

The Heritage Conservation provisions (2) and (3) note requirement for consent and conditions where development consent is not required.

Aboriginal objects are present, development consent will be required.

- (8) Aboriginal places of heritage significance. The consent authority must, before granting consent under this section to the carrying out of development in an Aboriginal place of heritage significance—
 - (a) consider the effect of the proposed development on the heritage significance of the place and any Aboriginal object known or reasonably likely to be located at the place by means of an adequate investigation and assessment (which may involve consideration of a heritage impact statement), and
 - (b) notify the local Aboriginal communities, in writing or in such other manner as may be appropriate, about the application and take into consideration any response received within 28 days after the notice is sent.

Penrith Lakes Development Control Plan Stage 1

This DCP applies to land zoned Employment and Tourism under Chapter 5 of the SEPP.

3.8 Aboriginal cultural heritage Objectives

- a) Preserve and enhance items and sites of Aboriginal cultural and archaeological significance located within Penrith Lakes.
- b) Ensure all development considers and addresses the potential impacts on Aboriginal cultural heritage significance and potential archaeological sites.

NSW Department of Planning and Environment | 17 Penrith Lakes Development Control Plan Controls:

- 1) All development is to be informed by an understanding of Country, through consultation with traditional owners.
- 2) All development is to be in accordance with the relevant provisions of the National Parks and Wildlife Act 1974 and the (former) Department of Environment, Climate Change and Water's Due Diligence Code of Practice for the Protection of Aboriginal Objects in New South Wales.

This assessment has been prepared in consultation with Registered Aboriginal Parties and in accordance with the National Parks and Wildlife Act 1974 and the (former) Department of Environment, Climate Change and Water's Due Diligence Code of Practice for the Protection of Aboriginal Objects in New South Wales.

10.1.3 Heritage Act (NSW) 1977

The Heritage Act 1977 (as amended in 2009) protects and aims to conserve the environmental heritage of New South Wales. Environmental heritage is broadly defined under Section 4 of the Heritage Act as consisting of "those places, buildings, works, relics, moveable objects, and precincts, of State or local heritage significance" (Heritage Branch DoP 2009: 1). Aboriginal places or objects that are recognised as having high cultural value (potentially of local and State significance) can be listed on the State Heritage Register and protected under the provisions the Heritage (NSW) 1977 of Act (http://www.heritage.nsw.gov.au/06_subnav_01.htm).

September 2025 Page 66 of 87



Amendments to the *Heritage Act (NSW) 1977* made in 2009 changed the definition of an archaeological 'relic', so that it is no longer based on age. A relic is now an archaeological deposit, resource or feature that has heritage significance at a local or State level. This significance-based approach to identifying 'relics' is consistent with the way other heritage items such as buildings, works, precincts or landscapes are identified and managed in NSW (Heritage Branch, DoP 2009:1). Section 4(1) of the *Heritage Act (NSW) 1977* (as amended 2009) defines 'relic' as follows:

Relic means any deposit, artefact, object or material evidence that:

- relates to the settlement of the area that comprises New South Wales, not being Aboriginal settlement, and
- is of State or local heritage significance (Heritage Branch, DoP, 2009:6).

10.1.4 Aboriginal Land Rights Act 1983

The NSW Aboriginal Land Rights Act 1983 (ALR Act), administered by the NSW Minister for the Public Service and Employee Relations, Aboriginal Affairs, and the Arts, establishes the NSW Aboriginal Land Council (NSWALC) and Local Aboriginal Land Councils (LALCs). The Act requires these bodies to:

- take action to protect the culture and heritage of Aboriginal persons in the council's area, subject to any other law
- promote awareness in the community of the culture and heritage of Aboriginal persons in the council's area.

These requirements recognise and acknowledge the statutory role and responsibilities of NSWALC and LALCs. The ALR Act also establishes the registrar whose functions include, but are not limited to, maintaining the Register of Aboriginal Land Claims and the Register of Aboriginal Owners.

Under the ALR Act, the registrar is to give priority to the entry in the register of the names of Aboriginal persons who have a cultural association with:

- lands listed in Schedule 14 to the NPW Act
- lands to which section 36A of the ALR Act applies.

10.1.5 Native Title Legislation

The (Commonwealth) Native Title Act 1993 (NTA) provides the legislative framework to:

- Recognise and protect native title.
- Establish ways in which future dealings affecting native title may proceed and to set standards for those
 dealings, including providing certain procedural rights for registered native title claimants and native title
 holders in relation to acts which affect native title.
- Establish a mechanism for determining claims to native title.
- Provide for, or permit, the validation of past acts invalidated because of the existence of native title.

The NSW *Native Title Act 1994* was introduced to make sure the laws of NSW are consistent with the Commonwealth's NTA on future dealings. It validates past and intermediate acts that may have been invalidated because of the existence of native title.

The National Native Title Tribunal has a number of functions under the NTA, including maintaining the Register of Native Title Claims, the National Native Title Register and the Register of Indigenous Land Use Agreements and mediating native title claims.

September 2025 Page 67 of 87



10.1.6 Other Acts

The (Commonwealth) Aboriginal and Torres Strait Islander Heritage Protection Act 1984 may be relevant if any item of Aboriginal heritage significance to an Aboriginal community is under threat of injury or desecration and state-based processes are unable to protect it. The Environment Protection and Biodiversity Conservation Act 1999 is relevant to projects where there are heritage values of national significance present.

10.2 MANAGEMENT OPTIONS

This section of the report provides a summary of available management and mitigation options for the proposal and the justification for the final recommendations provided in Section 11.

10.2.1 Conservation

Conservation is the best heritage outcome for preservation of threatened cultural sites and objects with cultural and scientific significance. Conservation through protection or further management should always be explored first before any other option for the management of threatened Aboriginal sites and objects.

Previous planning and Aboriginal Cultural Heritage Assessments have considered the project area when zoning the project area to tourism development, noting that other parts of the Penrith Lakes area hold greater conservation value.

Conservation is not possible in the project area and the proponent has attempted at least for now six months to redesign project impacts and attempt to avoid cultural deposits, if still extant associated with Penrith Lakes 2025.

Conservation may be relevant if Aboriginal heritage is found during test pit excavations, as discussed in Section 9 and below.

10.2.2 Further Investigation – Testing Under the Code of Practice

The Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW (DECCW 2010) (CoP) sets out a procedure for further archaeological investigations in areas assessed as having potential archaeological deposits. These investigations are regulated to be specific kinds of archaeological test excavation to a methodology specified in the CoP (DECCW 2010:24–28). The purpose of the test excavations are to assess the cultural heritage significance of the area, interpret the Aboriginal history of the area being investigated and inform future planning decisions (DECCW 2010:27).

Archaeological testing is not required as Aboriginal objects are recorded within the project area as a recorded background scatter, Penrith Lakes 2025.

Consultation has been undertaken with Heritage NSW regarding expectations for assessment and site definition.

10.2.3 Destruction Without Mitigation

Destruction without any form of mitigation could be a feasible management strategy if no Aboriginal sites or objects were identified; an area had low archaeological significance and cultural significance; and the strategy was agreed to by the Registered Aboriginal Parties/or approved native title claimants.

September 2025 Page 68 of 87



Previous AHIP have been issued over the project area without mitigation. This however is not considered appropriate given the indication that the project area contains Aboriginal objects with low archaeological integrity in the top 0.3 to 0.6 m of topsoil, as well as to areas with more potential past the agricultural disturbance zone. Consultation feedback with Registered Aboriginal Parties and Heritage NSW to date has indicated that Aboriginal objects within the project area have value and warrant further salvage.

10.2.4 Destruction With Mitigation

Destruction with mitigation refers to some form of archaeological or cultural salvage or investigation to mitigate the destruction of an Aboriginal object/s or sites. Destruction with mitigation would be recommended in areas where Aboriginal object/s and sites were identified, and/or in areas with moderate to high archaeological values with research potential that can contribute to a greater understanding of the cultural history of the project area and where conservation is not a viable management option. This may also be appropriate, if a project area has high cultural value to registered Aboriginal parties/or approved native title claimants for a project area.

Further salvage culturally and archaeologically is required as Aboriginal objects recorded within Penrith Lakes 2025 site are identified within the project area. Consultation feedback with Registered Aboriginal Parties and Heritage NSW to date has indicated that Aboriginal objects present within the project area they have value and warrant further salvage and mitigation.

Destruction with mitigation refers to some form of action taken to mitigate harm to Aboriginal objects and loss of heritage values. Examples of mitigation might include archival recording, archaeological excavations or cultural collection, designs and landscaping that enhance heritage values, interpretation, education and creating opportunities for Aboriginal people to continue to care for Country and Aboriginal cultural heritage. The focus for mitigation in the Archaeological Assessment is archaeological values and consideration of additional values is in the ACHA for other values under the Burra Charter (ICOMOS 2013) for Aboriginal cultural heritage.

Detailed site recording

Detailed site recording is recommended for all recorded Aboriginal cultural heritage sites. The information should be documented a report and in AHIMS site cards and Aboriginal Site Impact Recording Forms. This recording will include artefact analysis and consider use-wear and residue analysis of the retouched flake and broken hand axe.

Archaeological Surface Collection and Salvage Excavation

The following was considered for the project area:

- Archaeological salvage excavation considering a combination of mechanical methods for disturbed soil
 profiles and manual salvage for non-disturbed layers.
- Surface collection of Aboriginal objects in the eight exposures on site.

An Archaeological Research Design and Methodology will be developed in consultation with the RAPs.

Development of a Care and Control Strategy

For all collected and salvaged Aboriginal objects, consultation will be undertaken to develop a Care and Control Strategy i in consultation with RAPs to manage any artefacts in a manner acceptable to RAPs (for example, options that may be considered may include reburial, relocation on Country, Keeping Place, interpretation etc) and enable the cultural value of the artefacts to be documented and partially conserved.

September 2025 Page 69 of 87



11. Recommendations

Management recommendations of this assessment consider the archaeological (scientific values) as set out in The Burra Charter and the requirements of Heritage NSW for the Archaeological Survey Report (Archaeological Assessment). The ACHA to which this report is appended includes management recommendations which consider the social (cultural), spiritual, aesthetic and historic values. The proponent must consider the ACHA recommendations in conjunction with the recommendations of this Archaeological Assessment.

Based on the description of project impacts, the results of the survey, Aboriginal consultation to date, the limitations of this assessment and previous archaeological research, the following recommendations are made:

 An AHIP with community collection and salvage will be required prior to the commencement of ground disturbance works to adequately mitigate the project impacts and salvage Penrith Lakes 2025

2. Induction

It is recommended that all site workers and personnel involved in site impact works should be inducted and briefed on the possible identification of Aboriginal sites and objects during construction and their responsibilities according to the provisions of the NPW Act 1974 and NPW Regulation 2019.

This induction package should be developed in consultation with DLALC, prior to works proceeding. The induction must include:

- An AHIP once issued as recommended by the results of this AA report.
- The contact phone numbers of the NSW Environment and Heritage regional archaeologist, EnviroLine 131 555, and DLALC.
- The relevant contact phone number Environmental Officer responsible for this project in case unknown objects or items are uncovered during excavation.
- The penalty for moving Aboriginal objects need to be made clear and given due consideration.
- An outline types of unexpected heritage objects, items & relics, and their legal protection
- The Unexpected Finds and Human Remains Procedures, as outlined in Recommendation 1 and 2.

3. Unexpected Find Procedure

It is recommended that an Unexpected Finds Procedure be implemented for the duration of the project. In the event that a suspected Aboriginal object/s is identified the procedure should include the following:

- Works are to stop immediately.
- The area of the suspected find/s is to be fenced off with an appropriate buffer and protected.
- A qualified archaeologist and representative of DLALC are to be contacted to inspect the area and the nature of the find.
- Representative of DLALC to determine the find's significance, in consultation with a
 qualified archaeologist or NSW Environment and Heritage, and the requirement for an
 Aboriginal Heritage Impact Permit (AHIP).
- Works are not to proceed until written advice is provided from the archaeologist or NSW Environment and Heritage on the appropriate management of the find.

4. <u>Unexpected Human Remains Procedure</u>

It is recommended that an Unexpected Human Remains procedure be implemented for the duration of the project. In the unlikely event that suspected Human Remains are identified the procedure should include the following:

September 2025 Page 70 of 87



- Works are to stop immediately.
- The area of the suspected Human Remains find is to be secured and cordoned off.
- NSW Police are to be notified. No further works can be undertaken until the NSW Police provide written advice.
- If these remains are deemed to require archaeological investigation by the NSW Police or NSW Coroner, then:
- NSW Environment and Heritage and the relevant Aboriginal parties must be notified;
 and
- a plan of management for the preservation of any identified Aboriginal human remains of for the salvage must be put in place or conducted under an AHIP methodology and variation developed in consultation with all relevant Aboriginal parties and the NSW Environment and Heritage.
- Works are not to proceed until written advice is provided from the archaeologist or NSW Environment and Heritage.

September 2025 Page 71 of 87



Legislation

Aboriginal Land Rights Act 1983

Aboriginal and Torres Strait Islander Heritage Protection Act 1984

Environmental Planning and Assessment Act 1979

Environment Protection and Biodiversity Conservation Act 1999

Heritage Act 1977

National Parks and Wildlife Act 1974

National Parks and Wildlife Regulation 2019.

Native Title Act 1993

Native Title Act (NSW) 1994

September 2025 Page 72 of 87



References

Artefact (2016) Jane Street and Mulgoa Road Infrastructure Upgrade, Penrith: Aboriginal Archaeological Survey Report.

Australia ICOMOS (2013) *The Burra Charter: The Australia ICOMOS Charter for Places of Cultural Significance, 2013.* Australia ICOMOS Incorporated International Council on Monuments and Sites.

Biosis (2018) Penrith Regatta Centre New Maintenance Shed Aboriginal Cultural Heritage Due Diligence Assessment. Report for Creative Planning Solutions on behalf of the Office of Sport. Authors: J Cole, Biosis Pty Ltd, Sydney. Project no. 27505

Blue Mountains City Council (2017) Scenic Eastern Escarpment: Draft Master Plan.

Comber, J. (2005) Archaeological and cultural heritage assessment of Camenzufi Site 1, Penrith Lakes Scheme. Unpublished report for PLDC.

Comber, J. (2006) Archaeological and Cultural Heritage Assessment in the area surrounding PL9, Penrith Lakes Scheme. Unpublished report for PLDC.

Comber, J. (2007) Aboriginal Archaeological and Cultural Heritage Assessment: Russell Street Bridge, Penrith Lakes. Report to the Penrith Lakes Development Corporation.

Comber, J. (2018) Toga Penrith: Aboriginal Archaeological Assessment. Unpublished report prepared for Toga.

Comber, J. and T. Stening (2008) Aboriginal Archaeological and Cultural Heritage Assessment Cranebrook Escarpment. Report to Penrith Lakes Development Corporation.

Chalson, J.M. and H.A. Martin. (2008) A 38,000 year history of the vegetation at Penrith lakes, New South Wales. *Proceedings of the Linnean Society of New South Wales*, 129, Pp 97-111.

Deerubbin Local Aboriginal Land Council. (n.d.). *Deerubbin LALC* [Facebook]. Retrieved July 2, 2024, from https://www.facebook.com/DeerubbinLALC/

Department of Environment, Climate Change and Water (DECCW) (2009) Operational Policy: Protecting Aboriginal Cultural Heritage, Hurstville, NSW.

Department of Agriculture Water and the Environment Website Ecologically Sustainable Development Webpage. Accessed 23 September 2021 https://www.environment.gov.au/about-us/esd#:~:text=Australia's%20National%20Strategy%20for%20Ecologically,in%20the%20future%2C%20can%20be

Department of Environment, Climate Change and Water (DECCW) (2010) Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW, Hurstville, NSW.

Department of Climate Change Energy the Environment and Water (2021) Register of the National Estate – archive. Accessed 27 July 2023 from http://www.dcceew.gov.au/parks-heritage/heritage/places/register-national-estate

Eco Logical Australia Pty Ltd (2020) Nepean Business Park, Penrith NSW – Aboriginal Cultural Heritage Assessment. Prepared for Great River NSW Pty Ltd.

ERM (2001) Penrith Lakes Scheme Cultural Heritage Management Study. Report prepared for Urban Pacific Pty Ltd. June 2001 100488RP1.

September 2025 Page 73 of 87



EMGA (2011) Penrith Lakes Scheme Aboriginal Heritage Assessment Report I 5B83, 5B73, 5B66 I including results of test excavation of site PLSB83 (45-5-3991) under the Code of Practice for Archaeological Investigation of Aboriginal Object in NSW (DECCW 2010). Report to PLDC

GML (2021) Hawkesbury LGA Aboriginal Cultural Heritage Study. Report prepared for Hawkesbury City Council.

Government Architect New South Wales (2023). *Connecting with Country.* NSW Government. https://www.planning.nsw.gov.au/sites/default/files/2023-10/connecting-with-country.pdf

Karskens G. (2007) 'Water dreams, earthen histories: Exploring urban environmental history at the Penrith Lakes Scheme and Castlereagh, Sydney', *Environment and History*, 13, pp. 115 – 154.

Karskens, G. et al. (2019). *Traces in a Lost Landscape: Aboriginal archaeological sites, Dyarubbin/Nepean River and contiguous areas, NSW, Australia* (Data Paper). Internet Archaeology 52. https://doi.org/10.11141/ia.52.8.

Kohen, J.L. (1981) Report on an Archaeological Survey of the region proposed for the proposed Scheme. Report to Kinhill Stearns.

Kohen, J.L. (1986a) Prehistoric settlement in the western Cumberland Plain: resources, environment and technology. Unpublished PhD thesis, School of Earth Sciences, Macquarie University.

Kohen, J L. (1986b) An additional archaeological survey of The Penrith Lakes Scheme: The DA2 development area Unpublished report for PLDC.

Kohen, J L (1986c) An archaeological survey of The Penrith Lakes Scheme: the DA2 area at Cranebrook and Upper Castlereagh., Unpublished report for PLDC.

Kohen, J L. (1988a) Archaeological sites along Cranebrook Creek: Test excavations of open sites and monitoring after removal of topsoil., Unpublished report for PLDC.

Kohen, J L. (1988b) The Penrith Lakes Scheme: routine inspection of quarrying operation, August 1988, Unpublished report for PLDC.

Kohen, J L. (1989a) The Penrith lakes Scheme: routine inspection of quarrying operation, January 1989 Unpublished report for PLDC.

Kohen, J L. (1989b) The Penrith lakes Scheme: routine inspection of the quarrying operation, July 198 9 Unpublished report for PLDC.

Kohen, J L. (1989c) International Standard Rowing Course at Penrith: an archaeological survey Report prepared for Kinhill Engineers Pty Ltd.

Kohen, J L. (1990a) The Penrith Lakes Scheme: routine inspection of the quarrying operation, January 1990 Unpublished report for PLDC.

Kohen, J L. (1990b) The Penrith Lakes Scheme: routine inspection of quarrying operation, July 1990 Unpublished report for PLDC.

Kohen, J L. (1991a) The Penrith Lakes Scheme: routine inspection of quarrying operation, January 1991 Unpublished report for PLDC.

Kohen, J L. (1991b) The Penrith Lakes Scheme: routine inspection of quarrying operation July 1991 Unpublished report for PLDC.

September 2025 Page 74 of 87



Kohen, J L. (1992a) The Penrith Lakes Scheme: routine inspection of the quarrying operation January 1992 Unpublished report for PLDC.

Kohen, J L. (1992b) The Penrith Lakes Scheme: routine inspection of the quarrying operation July 1992 Unpublished report for PLDC.

Kohen, J.L. (1993a) The Darug and their neighbours. The traditional Aboriginal owners of the Sydney Region. Darug Link in association with Blacktown and District Historical Society, Blacktown.

Kohen, J L. (1993b) The Penrith lakes Scheme: routine inspection of the quarrying operation July 1993 Unpublished report for PLDC.

Kohen, J L. (1994a) The Penrith Lakes Scheme: routine inspection of the quarrying operation, July 1994 Unpublished report for PLDC.

Kohen, J L. (1994b) Archaeological survey at Cranebrook east of the Scheme., Unpublished report for PLDC.

Kohen, J L. (1994c) The Penrith Lakes Scheme: review of archaeological significance of the DA3 development area Unpublished report for PLDC.

Kohen, J L. (1995) The Penrith Lakes Scheme: routine inspection of the quarrying operation July 1995. Unpublished report for PLDC

Kohen, J L. {1996) The Penrith Lakes Scheme: routine inspection of the quarrying operation July 1996 Unpublished report for PLDC.

Kohen, J.L. (1997) Archaeological Investigations in the DA4 Area, Penrith Lakes Scheme. Unpublished report for PLDC.

Kohen, J.L. (1998a) Aboriginal Environmental Impacts in the Hawkesbury River Area. In J. Powell (Ed.). *The Improvers*' Legacy. *Environmental Studies of the Hawkesbury*. Deerubbin Press, Berowra Heights.

Kohen, J.L. (1998b) Supplementary notes to Archaeological Investigations in the DA4 Area, Penrith Lakes Scheme. Unpublished report for PLDC.

Kohen, J.L. (2004) Monitoring following surface stripping in the DA4 areas at Penrith Lakes 2001-2003. Unpublished report for PLDC.

Mitchell, P. (2010) Geomorphology and soils in relation to archaeological investigations on the Cranebrook Terrace, Penrith Lakes, NSW. Report to Comber Consultants for PLDC.

Morrow (2023) Geotechnical Investigation for Tourism Development: Lot 14, 47-65 Old Castlereagh Road, Castlereagh NSW.

Nanson G, Young R and Stockton R. (1987) 'Chronology and palaeoenvironment of the Cranebrook Terrace (near Sydney) containing artefacts more than 40,000 years old', in *Archaeology in Oceania*, 22(2) pp. 72-78.

New South Wales State Heritage Register. Department of Planning & Environment (2024) H02009.

NSW Department of Planning, Industry and Environment (2021). Penrith Lakes Draft Development Control Plan – Stage 1.

Office of Environment and Heritage (OEH) (2011) Guide to investigating, assessing and reporting on Aboriginal cultural heritage in NSW.

September 2025 Page 75 of 87



PLDC (2011) Penrith Lakes Scheme Area Aboriginal Heritage Assessment Report. Published by Penrith Lakes Development Corporation.

Smith, V. (1996) Review of the Geomorphology of the Scheme Area and context for Aboriginal Occupation Unpublished report for PLDC.

State Government of NSW and NSW Department of Climate Change, Energy, the Environment and Water 2023. Aboriginal Heritage Impact Permit Boundaries Dataset. Revision March 2024. Viewed 24 July 2024.

Virtus Heritage (2024). Aboriginal Archaeological Due Diligence Assessment for the Castlereagh Tourism Development. Report prepared for the Morson Group.

Williams A, A. Burrow, P. Toms, O. Brown, M. Richards and T. Bryant (2017) 'The Cranebrook terrace revisited: recent excavations of an early Holocene alluvial deposit on the banks of the Nepean River, NSW, and their implications for the future work in the region, *Australian Archaeology*, 83(3) pp. 100-109

September 2025 Page 76 of 87



Appendix A1. Archaeology Research Design Methodology

September 2025 Page 77 of 87





CASTLEREAGH TOURISM DEVELOPMENT

39-65 Old Castlereagh Road Castlereagh, NSW

Archaeological Research Design and Methodology

Final | September 2025

Prepared for Morson Group

PO Box 101, Pottsville NSW 2489 (O2) 6676 4354 info@virtusheritage.com.au ABN 56 159 910 228



Cover design: Cake

Cover image: Stock imagery (Microsoft Office 2022)

Document Controls

Client:	Enter Client
Proponent:	Morson Group
Local Government Area:	City of Penrith
Local Aboriginal Land Council (LALC):	Deerubbin Local Aboriginal Land Council

Version History

Version	Date	Prepared by	Approved by	Comments
1a - c	12 December 2024	Clare Anderson	Alice Buhrich Dr. Mary-Jean Sutton	Minor edits
1d	3 July 2025	Dr. Mary-Jean Sutton and Liam Clerke	Dr. Mary-Jean Sutton	Draft
2а – е	23 July 2025	Dr. Mary-Jean Sutton and Liam Clerke	Dr. Mary-Jean Sutton	Draft
3	27 August 2025	Kate Morris and Liam Clerke	Dr. Mary-Jean Sutton	Final

September 2025 Page 2 of 22



Acknowledgement of Country

Virtus Heritage acknowledges the Traditional Custodians of the land on which this project was undertaken and pays respect to Elders past, present and emerging.

Content Warning

Aboriginal and Torres Strait Islander people are warned that this publication may contain names and images of deceased people, descriptions of traumatic historic events and parts of Country that have been impacted by development.

Disclaimer and cultural restrictions

This Report (including any enclosures and attachments) has been prepared by Virtus Heritage for the exclusive use and benefit of Enter Client and Morson Group for their use regarding the Project and solely for the purpose for which it is provided. Unless we provide express prior written consent, no part of this report should be reproduced, distributed or communicated to any third party. We do not accept any liability if this report is used for an alternative purpose from which it is intended, nor to any third party in respect of this report.

Information contained in the Report is current as at the date of the Report and may not reflect any event or circumstances which occur after the date of the Report.

All queries related to the content, or to any use of this report must be addressed to Dr Mary-Jean Sutton.

September 2025 Page 3 of 22



Contents

1.	Introduction	7
1.1	Proposed Project Impacts	7
1.2	Aboriginal Consultation	10
1.3	Report Structure	11
2.	Summary of previous archaeological research	12
3.	Research Design	13
4.	Methodology	15
4.1	Impact and Mitigation Areas	15
4.2	Site Set Up	16
4.3	Surface Collection	16
4.4	Geotechnical Auger Hole and Trench	17
4.5	Manual (Hand) Salvage Excavation	17
4.6	Methodology for Controlled Subsurface Salvage – Mechanical Pits	18
4.7	Expansion or Placement of Additional Excavation Areas	19
4.8	Recording During Excavation and Sieving	19
4.9	Community Collection	19
4.10	Reporting	20
4.10	O.1. Attributes to be recorded for Stone Artefacts	20
4.11	Short and Long Term Care of Aboriginal Objects	20
4.12	Safety and Environmental Management	21
5.	References	22
Ta	bles	
Tabl	e 1 Aboriginal Site located within the AHIP Application Area	8
Tabl	e 2 Aboriginal Site located within the AHIP Application Area	10
Tabl	e 3. Proposed Impacts and Recommended Mitigation	15
Tabl	e 4: Attributes to be recorded	20
Fig	gures	
Figu	re 1: AHIP Application Area	9



Definitions

PAD

Abbreviations Description AAArchaeological Assessment **ACHA** Aboriginal Cultural Heritage Assessment **ACHCR** Aboriginal Cultural Heritage Consultation Requirements for Proponents 2010 (DECCW 2010a) **AHIMS** Aboriginal Heritage Information Management System **AHIP** Aboriginal Heritage Impact Permit **ARDM** Archaeology Research Design Methodology Code of Practice, Code of Practice for Archaeological Investigation of Aboriginal Objects in New South COP Wales (DECCW 2010b) **DLALC** Deerubbin Local Aboriginal Land Council LALC Local Aboriginal Land Council NPW ACT National Parks and Wildlife Act 1974 National Parks and Wildlife Regulation 2019 NPW Reg **OEH** NSW Office of Environment and Heritage (now Heritage NSW) **OSL** Optically stimulated luminescence

RAP Registered Aboriginal Party

Potential Archaeological Deposit

September 2025 Page 5 of 22



Glossary

Aboriginal object - A term used in the NPW Act legislation, meaning: '... any deposit, object or material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of the area that comprises NSW, being habitation before or concurrent with (or both) the occupation of that area by persons of non-Aboriginal extraction, and includes Aboriginal remains' (s.5 NPW Act).

Registered Aboriginal party – An individual or party who registers for Aboriginal consultation as part of the consultation and notification process following Aboriginal cultural heritage consultation requirements for proponents 2010 (NSW DECCW 2010a).

AHIP – An Aboriginal Heritage Impact Permit which is a document provided by Heritage NSW which provides a defence to the applicant to certain activities which constitute 'harm' to Aboriginal objects or Aboriginal places under Part 6 of the NPW Act. A proponent must prepare an application for an AHIP and other relevant documentation (including an ACHA) to obtain an AHIP from Heritage NSW in the Department of Premier and Cabinet.

Declared Aboriginal place - A term used in the NPW Act legislation, meaning any place declared to be an Aboriginal place (under s.84 of the NPW Act) by the Minister administering the NPW Act, by order published in the NSW Government Gazette, because the Minister is of the opinion that the place is or was of special significance with respect to Aboriginal culture. It may or may not contain Aboriginal objects.

Due Diligence assessment – Due diligence is taking reasonable and practical steps to determine whether a person's actions will harm an Aboriginal object and, if so, what measures can be taken to avoid that harm. A due diligence assessment will assess the potential for harm and provide recommendations to mitigate harm, generally in the form of an Aboriginal Cultural Heritage Assessment (ACHA), if Aboriginal objects or places are likely to be harmed by proposed works.

Harm - A term used in the NPW Act Amendments meaning '... any act or omission that destroys, defaces, damages an object or place or, in relation to an object – moves the object from the land on which it had been situated' (s.5 NPW Act).

Project area - Area proposed to be impacted as part of a specified activity or development proposal. These activities include indirect impact.

Place - An area of cultural value to Aboriginal people in the area (whether or not it is an Aboriginal place declared under s.84 of the Act).

Proponent - A person proposing an activity that may harm Aboriginal objects or declared Aboriginal places and who may apply for an AHIP under the NPW Act.

September 2025 Page 6 of 22



1. Introduction

Morson Group Consultants proposes to develop a tourism precinct at 39-65 Old Castlereagh Road, Castlereagh NSW (Lots 12, 14 and 16 DP793163, Figure 1). The project area is located within the Penrith Local Government Area (LGA), within the boundary of Deerubbin Local Aboriginal Land Council (DLALC).

The proposed scope of works as provided by Morson Group seeks approval for a tourism-oriented development comprising three (3) buildings across separate lots, including a hotel, an indoor recreation facility with two (2) drive-through restaurants, and a registered club. The proposal also includes associated vehicle access, on-grade and above-ground parking, and site infrastructure.

- Lot 12:
 - A seven (7) storey hotel with 147 rooms, restaurant, gym, spa, pool, and associated facilities.
 - Multi-level above-ground car parking.
- Lot 14:
 - A 5,713m² indoor recreation facility.
 - Two (2) restaurants with capacity for a drive-through.
 - Associated on-grade car parking.
- Lot 16:
 - A 5,177m² registered club building.
 - Associated on-grade car parking.

Virtus Heritage Pty Limited (hereafter 'Virtus Heritage') was engaged by Morson Group to prepare an Aboriginal Cultural Heritage Assessment (ACHA), including an Archaeological Assessment (AA) for the proposed development.

The proposed tourism development includes excavations anticipated to be up to 0.15 – 1.74 m depth, though excavation of stormwater system and footings will also likely be required. Excavations in these areas are anticipated to a maximum of 2.3 m depth.

AHIP COO01415 (AHIMS 3891), now expired, was previously issued over the project area. Previous Aboriginal cultural heritage assessments have identified that the project area may contain in-situ stratigraphy and low densities of Aboriginal objects associated with the alluvial Penrith Unit of the Cranebrook Terrace (PLDC 2011, Virtus Heritage 2024).

Where Aboriginal objects survive in this unit, they have research value as it may provide an opportunity to further understand the stratigraphy and archaeological value of the Penrith Unit of the Cranebrook Terrace and past Dharug land use on elevated terrain overlooking an unnamed tributary of Cranebrook Creek. This resource and opportunities to understand it are increasingly diminished by development in the local region.

The proposed activity has the potential to harm Aboriginal objects associated with this deposit. Given the extent of information available on the Penrith Unit, the previous land-use of the project area, the identification of artefacts within surface exposures inside of the project area, and the homogeneity of topography and landforms within the project area, archaeological testing is not necessary to determine the presence or absence of Aboriginal objects and archaeological deposits.

This document constitutes the Archaeological Research Design and Methodology (ARDM) to accompany an AHIP application to enable ground disturbance works associated with project development and salvage of an area of moderate archaeological potential within the project area.

1.1 PROPOSED PROJECT IMPACTS

Figure 1 shows the project impact area boundary which constitutes the application area for this AHIP application.

September 2025 Page 7 of 22



Table 1 outlines the proposed works and impacts to known sites and potential archaeological deposits (PAD) and indicates the level and type of harm.

Table 1 Aboriginal Site located within the AHIP Application Area

AHIMS # / PADs within Proposed Work Sites	Site Name	Site Type	Proposed Activity
	Penrith Lakes 2025, background scatter	Artefact scatter/Artefact (feature)	Salvage excavation Archaeological Surface
			Collection Community Collection

September 2025 Page 8 of 22





Figure 1: AHIP Application Area

September 2025 Page 9 of 22



1.2 ABORIGINAL CONSULTATION

As recognised by Heritage NSW, we acknowledge that Aboriginal people are the primary determinants of the cultural significance of their heritage. Aboriginal consultation for the ACHA was undertaken in compliance with the Aboriginal cultural heritage consultation requirements for proponents 2010 (NSW DECCW 2010a) (hereafter referred to as the "ACHCRs"). These consultation requirements are legal requirements that proponents must comply with during the ACHA process which are set out in Clause 80c of the NPW Regulation. Aboriginal consultation is crucial in the compilation of the ACHA in order to adequately assess and investigate Aboriginal cultural heritage.

Sixteen Aboriginal groups/individuals registered interest for this project during the notification process. Each interested party responded to advertisements in various newspapers or to an invitation to register in the project after their contact details were provided by notified organisations. The groups/individuals registered for consultation are listed in Table 2.

Table 2 Aboriginal Site located within the AHIP Application Area

Name of Contact	Registered Aboriginal Party
Steven Randall	Deerubbin Local Aboriginal Land Council
Philip Boney	Wailwan Aboriginal Group
Tiarna Bird	Mura Gadi Aboriginal Corporation
Ethan Trewlynn	Long Gully Cultural Services
Nigel Millgate	Gadhungal Marring
Darleen Johnson and Ryan Johnson	Murra Bidgee Mullangari Aboriginal Corporation
Justine Coplin	Dharug Custodian Aboriginal Corporation
Kelvin Boney	Wallanbah Aboriginal Site Conveyancing
Amanda Hickey	Amanda Hickey Cultural Services
Carolyn Hickey	A1 Indigenous Services
Jennifer Beale	Butucarbin Aboriginal Corporation
Phil Khan	Kamilaroi Yankuntjatjara Working Group
Kerrie Slater; Vicky Slater	Wurrumay Culture Heritage Consultants
Steven Hickey	Widescope Indigenous Group
Wendy Morgan	Guntawang Aboriginal Resources Incorporated
Undisclosed Registered Aboriginal Party	Undisclosed Registered Aboriginal Party

All registered Aboriginal parties have been provided with the opportunity to review, discuss and develop the ARDM presented in this document.

September 2025 Page 10 of 22



1.3 REPORT STRUCTURE

Section 1 provides an introduction and context to the project.

Section 2 of this research design and methodology summarises previous archaeological research which is relevant to the AHIP application for the site within the project area.

Section 3 details the research design that has been proposed for the project area.

Section 4 provides the methodology proposed for salvage for sites and areas within the project area.

Section 5 presents the attributes to be recorded during the analysis of artefacts recovered during salvage and collections.

Section 6 discusses the care of artefacts recovered during salvage and collections.

Section 7 lists the references cited within this document.

September 2025 Page 11 of 22



2. Summary of previous archaeological research

A review of the Heritage NSW Aboriginal Heritage Information Management System (AHIMS) library and online searches were undertaken to obtain copies of previous Aboriginal heritage studies and archaeological investigations within the locality of the project area, which relate to the AHIP application. Detailed summaries of all reports pertinent to the locality are provided in Section 4 of the Archaeological Assessment (Virtus Heritage 2024).

The project area is located on a floodplain terrace associated with the Nepean River, within the Penrith Unit of the Cranebrook Terrace formation. The soils of the project area are consistent with the Richmond soil landscape. Aboriginal objects are known to occur within this soil landscape and in the Penrith Unit to depths of 1–2 m and generally in the top 0.9 m of deposit. Archaeological models across the Cumberland Plain indicate that Aboriginal objects can be found in any landform, with stone artefacts tending to be found more frequently in proximity to key resources such as water and drainage lines, shelter and stone sources and decreasing in frequency as distance from those resources increases. The Nepean River is located a little over 650 m from the project area. The historic path of Cranebrook Creek is mapped approximately 1.7 km west of the project area. An unnamed tributary was located 300m north–east of the project area. Previous potential chain of ponds and paleochannels were also identified by Groundtruthing Consulting in proximity to the project area (Mitchell 2010).

The project area's alluvium topsoils have been disturbed by vegetation clearance, previous farming activity and the construction of the residential housing and irrigation infrastructure but does not appear to have been subject to sand mining. This past land use has impacted the A-horizon soils to at least 0.6 m in depth.

An AHIMS extensive search (Client Service ID 912988) was undertaken on 10 July 2025. No Aboriginal cultural heritage sites were registered in or in close proximity to the project area.

In 2017, Williams et al. conducted excavations on the banks of Peach Tree Creek and created the most recent dating model for the Cranebrook Terrace (Williams et al 2017) This modelling identifies that the sandy clay sediment in areas west of the historic alignment of Cranebrook Creek, within the Richmond Unit, were deposited between 20–15,000 years ago to a depth of 3.5–3.9 m or 20.73–21.13 m AHD. This sedimentary layer is particularly sensitive for Aboriginal archaeological deposits, with flakes being identified by Williams et al. at the base of this layer. Sediment below this deposit are also sandy clays and date to approximately 50–40,000 years ago. Sediment east of the historic alignment of Cranebrook Creek dated to at least 50,000 years. Aboriginal objects are less likely to occur at depth to the east of Cranebrook Creek, with any Aboriginal objects most likely occurring in the reworked topsoils, which is of particular relevance to the project area. Around 3km east of Cranebrook Creek is and channel infill dating to between 50–75,000 years ago.

Previous archaeological assessments of the project area concluded that there was a reasonable potential for Aboriginal objects to occur within the project area at low frequencies and with low archaeological integrity to depths of 0.3 m minimum to 0.6 m, with greater archaeological integrity below this depth within the Penrith Unit of the Cranebrook Terrace (PLDC 2011, Virtus Heritage 2024). Where Aboriginal objects survive in this unit, they have research value as it may provide an opportunity to further understand the stratigraphic and archaeological value of the Penrith Unit of the Cranebrook Terrace and past Dharug land use on elevated terrain overlooking an unnamed tributary of Cranebrook Creek. This resource and opportunities to understand it are increasingly diminished by development in the local region.

The proposed activity has the potential to harm Aboriginal objects identified in 8 exposures within the project area in the same landform defined in the Archaeological Assessment, as background scatter, Penrith Lakes 2025. An AHIP for salvage and collection is required as Aboriginal objects will be harmed by this proposal and require further mitigation and management.

September 2025 Page 12 of 22



3. Research Design

The research design has been developed in line with requirements of DECCW 2010a. Aboriginal heritage consultation requirements for proponents (DECCW 2010a), the Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW (DCEEW 2010b and Archaeological Investigation of Aboriginal Objects Code of Practice (DCEEW 2010c).

The past archaeological research within the vicinity of the project area and surrounds (refer to Section 2 of this document and Section 4.2 of the AA, Appendix 1 of the ACHA) indicates that there is potential for evidence of Aboriginal occupation to have survived impacts of previous land use.

The broad objective of this research design is to assist in further understanding how Aboriginal people utilised the project area in the past though archaeological investigation to determine the significance, extent, and integrity of any potential archaeological deposits and to analyse any artefacts recovered to document values.

Other research questions that will be investigated under the AHIP will be (and not limited to):

- Does the project area retain any evidence of natural land surfaces or intact archaeological deposits?
- Does the project area retain any evidence of Aboriginal land use?
- · What type of artefacts are present?
- What material evidence is there of former uses of the site?
- For Aboriginal objects and archaeological deposits in the project area,
 - What raw materials and technologies were in use at the site?
 - Do any of the artefacts retain evidence of use?
 - For the retouched flake and broken hand axe in the project area, is there any evidence of residue and for what types of usewear?
 - Is it possible to date the archaeological deposits?
 - If hearths/fire pits/heat treatment pits are located within the project area:
 - What can be inferred about technology choices for these features?
 - What can the features tell us about the chronology of land use in the project area?
 - Should faunal and/or shell material be located, which species present were utilised by Aboriginal people?
 - Can an inference be made as to a preference for marine or terrestrial resources?
 - Is there evidence of any change over time in these preferences or species utilised?
 - Is there evidence for the transport of resources within the environment?
- What does the artefact assemblages indicate about how Aboriginal people were utilising the local landscape?
- How does the results of the collection and artefact analysis compare to other analyses carried out in the locality and the region?
- Are Aboriginal people utilising the area less intensely than other parts of the Penrith Lakes area as
 predicted in ACHA in the predictive model, due to the distance of the project area from chain of ponds
 (in proximity to a water course). How does this pattern of landscape use compare to previous
 archaeological research in the locality and the region of Western Sydney?
- Are certain types of artefact types and artefact materials more prevalent within the project area than
 others as predicted in the ACHA in the predictive model? How do these results compare to previous
 archaeological research in the locality and the region?
- Is there any evidence of a change in occupation strategy over time?

September 2025 Page 13 of 22



• How have the descendants of the Traditional Aboriginal people and the broader Aboriginal community utilised this landscape through generations to the present day? Are there any dateable features (charcoal or hearths) that can provide information on the chronology of the midden or occupation deposit, if identified? What is the age of such features (e.g. Holocene or Pleistocene)? What is their significance within the broader cultural landscape?*

*We note that the AA has assessed that the identification of dateable features in the impact areas is at present considered unlikely.

September 2025 Page 14 of 22



4. Methodology

4.1 IMPACT AND MITIGATION AREAS

Table 3 sets out the proposed impacts and investigation in each works area.

Table 3. Proposed Impacts and Recommended Mitigation

Works Area	Proposed Impacts	Recommended Mitigation	Area proposed for excavation and collection	Estimated # of Days Archaeologists/Geomorphologist Representative Aboriginal Parties on Site
Clearing grass/levelling site	Depth – removal of grass less than <0.1 m	Archaeological Surface Collection during Works by at least two RAPs for topsoil disturbance during initial ground disturbing works	All of the impact area.	3 days Archaeologist (depending on machine size).3 days inclusion of at least one RAP representative.
Car parks	Excavations to depths <0.1 m	-	-	-
Stormwater Tanks	Excavation to depth of 2.3 m	Mechanical excavation to 0.6 m and if Aboriginal objects are identified and soil profiles with integrity and Aboriginal objects are identified with input from a geomorphologist on site, manual hand excavation will be required to depth of impact.	Mechanical excavation in controlled 5 cm spits and pits spaced every 5 m in 50 cm by 50 cm pits.	2 - 5 days with 1 excavation director and a supporting Archaeologist/Geomorphologist (depending on machine size). 2 - 5 days inclusion of at least two RAP representative.
Stormwater pipes (100 - 450 mm diameter) Sumps	Excavation to depth of 0.15 - 1.74 m	Mechanical excavation to 0.6 m for stormwater pipers over a	For pipes over 300 mm diameters, mechanical excavation in	5 - 10 days with 1 excavation director and a supporting Archaeologist/Geomorphologist (not including expansion areas).

September 2025 Page 15 of 22



		diameter of 300 mm and if Aboriginal objects are identified and soil profiles with integrity and Aboriginal objects are identified with input from a geomorphologist on site, manual hand excavation will be required to depth of impact.	controlled 10 cm spits and pits spaced every 5 m.	5 - 10 days inclusion of at least two RAP representative.
Piles	Excavations to depths ~1.5 m	Manual excavation, mechanical auger excavation	geotechnical trench/auger pits and if triggered expansion by manual investigations placed every 10 m in 1 m by 1 m pits	2 days with 1 Archaeologist and 1 Geomorphologist.2 days inclusion of at least two RAP representative.

Due to the cultural significance of the area and potential for out of context Aboriginal objects to occur despite past land use disturbance, the following methodologies have been prepared for a surface collection, community collection and triggers for manual salvage in the even that it is required.

4.2 SITE SET UP

The excavation will be staged within the project area to manage spoil, water and sieving progressively within the project area.

Where removal of concrete slabs/asphalt is required, an excavator would be used. This work would be monitored by a geomorphologist or archaeologist, and RAP representative(s).

4.3 SURFACE COLLECTION

A surface collection will be undertaken of any impact footprint, including machinery access and sample locations, including proposed carparks, sumps and water storage areas.

The proposed surface collection methodology is as follows:

- surface collection will be undertaken by one archaeologist and at least one representative from registered Aboriginal parties;
- surface artefacts will be flagged prior to collection. The flagged site will be photographed to record the spatial distribution of artefacts within the site;

September 2025 Page 16 of 22



- the location of each surface artefact will be recorded using a handheld GPS to record the spatial distribution of artefacts within the site; and
- artefacts will be individually bagged and labelled (including site name, date, and MGA co-ordinate).

4.4 GEOTECHNICAL AUGER HOLE AND TRENCH

Six initial auger pits will be drilled across the project area for proposed areas of piling to characterise the stratigraphic profile and may be expanded mechanically into accessible trenches to enable the safe access to collect soil samples, OSL dating samples and penetrometer readings.

The use of auger pits for the subsurface investigation salvage for piling of in the impact areas for the proposed works is designed to determine the extent and integrity of any PADs that are associated with the sensitive landform and provide a safe method of excavation in sandy profiles at depth.

We propose:

- Six initial auger pits will be excavated to characterise the soil profile.
- Initially auger pits in the impact areas will be excavated to determine confirm the extent and integrity of
 natural and cultural deposits, if extant and disturbance in the agricultural activity areas. The location of
 the auger pits will be guided by the proposed impact footprint.
 - 20 cm by 20 cm mechanical or manual auger pits will be excavated in the impact areas.
 - Fill (including concrete, bitumen, road base and imported fill) will be removed in bulk and not sieved (where concrete and bitumen is present a hole will be sawed for auger access).
 - Excavation of deposits under fill will be undertaken by auger in 20 cm spits.
 - Excavation will be undertaken to the maximum depth of impact from the proposed works.
 - All excavated soil from the primary sample (excluding fill) will be sieved (dry sieving preferably with wet sieving adopted if the deposit cannot be sieved effectively) through 5mm sieves.
 - Soil excavated to enable trench access will have a representative sample sieved.
 - Munsell and pH analysis will be undertaken for each stratigraphic unit within each pit.
 - Photographic records will be taken for each auger pit.
 - The location of each auger pit will be recorded using a handheld GPS to record the spatial distribution of artefacts within the areas.
 - Artefacts will be individually bagged and labelled (including site name, date, and MGA coordinate).
 - Excavations will cease if suspected human remains are encountered. If suspected human remains are uncovered during salvage excavations, the area of these suspected remains must be secured, and the NSW Police notified. If these remains are deemed to required archaeological investigation by the NSW Police or NSW Coroner, then Heritage NSW, and all Registered Aboriginal Parties must be notified.

During auger investigations, if intact deposits, or features such as artefact scatters, midden deposits, intact heat treatment pits, intact hearths, evidence of knapping events, and/or formal tool types in intact deposits (i.e., backed artefacts, retouched artefacts, scrapers, axes, or other tool types considered rarer in a local and/or regional context) are in intact deposits, manual test salvage excavation will be triggered.

4.5 MANUAL (HAND) SALVAGE EXCAVATION

Aboriginal archaeological salvage pits would be positioned approximately 5 m apart along each transect associated with proposed impacts.

The location of salvage pits would be dependent on-site conditions (proposed impacts, services, footings, existing structures):

• Excavation would be undertaken by hand.

September 2025 Page 17 of 22



- Excavation would be undertaken in 1 m x 1 m pits.
- The first pit will be excavated and documented in 5 cm spits.
- Based on the evidence of the first excavation unit, 10 cm spits or sediment profile/stratigraphic excavation (whichever is smaller) may then be implemented.
- Salvage excavation units will be excavated to the depth of the proposed impact or the depth of the
 artefact bearing layers, or the B horizon is reached, or at least two spits of culturally sterile deposit are
 reached, or groundwater is present, whichever is shallowest.
- If hearths are identified, these will be cross sectioned and a dating sample obtained if possible.

4.6 METHODOLOGY FOR CONTROLLED SUBSURFACE SALVAGE - MECHANICAL PITS

It may be necessary to use mechanical excavation to safely excavate salvage pits, notably in the stormwater tank areas or areas for proposed stormwater drainage and sumps.

The use of mechanical pits for salvage of the impact areas for the proposed works is designed to determine the extent and integrity of potential archaeological deposits.

- Initially mechanical excavation pits in the impact areas will be excavated to determine the extent and integrity of natural and cultural deposits, if extant.
 - 1 m by 1 m investigation pits (dimensions may be dictated by the size of excavator bucket) will be excavated in the impact areas.
 - Fill (including concrete, bitumen, road base and imported fill) will be removed in bulk and not sieved.
 - Excavation of deposits under fill will be undertaken by machine in 10 cm spits.
 - Excavation will be undertaken to the maximum depth of impact from the proposed works. Stepping, benching, or shoring of pits may be required to maintain integrity of the pit to depth.
 - All excavated soil from the primary sample unit (excluding fill) will be sieved (dry sieving preferably with wet sieving adopted if the deposit cannot be sieved effectively) through 5 mm
 - Soil excavated as a result of stepping, benching, or shoring will be sample sieved.
 - Munsell and pH analysis will be undertaken for each stratigraphic unit within each investigation pit.
 - A section drawing of at least one wall of the investigation pit will be completed for each investigation pit. Stepping, benching, or shoring of pits may be required to safely access the mechanical pits for section drawing.
 - Photographic records will be taken for each investigation pit.
 - The location of each investigation pit will be recorded using a handheld GPS to record the spatial distribution of artefacts within the areas.
 - Artefacts will be individually bagged and labelled (including site name, date, and MGA coordinate).
 - Excavations will cease if suspected human remains are encountered. If suspected human remains are uncovered during salvage excavations, the area of these suspected remains must be secured, and the NSW Police notified. If these remains are deemed to required archaeological investigation by the NSW Police or NSW Coroner, then Heritage NSW, and all Registered Aboriginal Parties must be notified.

During the excavation of pits, if features such as intact midden deposits, intact heat treatment pits, intact hearths, evidence of knapping events, and/or more than five formal tool types in intact deposits (i.e., backed artefacts, scrapers, axes, or other tool types considered rare in a local and/or regional context) are located in a 1 m x 1 m area in intact deposits, manual salvage will be triggered.

September 2025 Page 18 of 22



4.7 EXPANSION OR PLACEMENT OF ADDITIONAL EXCAVATION AREAS

Where certain triggers are met, additional excavation areas may be undertaken to salvage the extent of archaeological feature and artefacts and to understand the archaeological significance of the project area within the impact area.

During excavation works, certain features may trigger expansion of existing salvage areas, such as:

- If 10 or more artefacts (including conjoins) are located within a 50 cm square excavation pit.
- The presence of an intact midden deposit.
- The presence of an intact heat treatment pit or intact hearth.
- Evidence of stone artefacts in intact stratified deposit or clear feature.
- Evidence of early interaction between settlers and Aboriginal people such as knapped glass or ceramics (the presence of clear manual percussion including a dorsal scar or bulb of percussion would be required and glass/ceramic that dates to the early to mid-nineteenth century).
- The presence of rare or formal intact deposit, i.e. backed artefacts, scrapers, axes, elouera, grounded edge tools or other tool types considered rarer in a local and/or regional context.
- The expansion of the pit should continue until the full extent of the feature or deposit has been identified and recorded.

Excavation would cease once sufficient information was collected to salvage the extent, nature and significance of the archaeological deposits to mitigate the impact of development.

4.8 RECORDING DURING EXCAVATION AND SIEVING

The recording process will include:

- RTK, GPS or manual plotting of all excavation pits, in situ artefacts and cultural layers.
- Bagging any archaeological material identified during the excavation or sieving (such as stone artefacts, animal bone, shell, charcoal) and labelling with a unique number based on the relevant square and stratigraphic layer or unit.
- Where possible, collecting suitable samples for scientific dating and submitting to an appropriate facility for dating.
- Context numbers will be applied to features, deposit, cuts in the deposit, architecture, post-holes, and other archaeological features.
- Soil samples will be collected for each artefact-bearing stratigraphic unit.
- The location of the trenches/pits will be surveyed and photographed photogrammetrically for post-field planning. The exact location of the trenches/pits will be demarcated by the excavation director/s and recorded by a qualified archaeological surveyor. A full site plan showing the location of all trenches and excavated features (if any) will be created.
- The salvage excavation process will be recorded using digital photograph, and the final cross sections of each pit/trench will be illustrated, noting stratigraphy.

4.9 COMMUNITY COLLECTION

Community collection or opportunity to inspect areas for cultural salvage to RAPs would include ground disturbing works to the depth of topsoil removal, including proposed carparks, sumps and water storage areas, where safe to so and organised by Morson Group or the delegated Construction Manager and the RAPs.

The proposed community collection methodology is as follows:

September 2025 Page 19 of 22



- surface collection will be undertaken by at least two representatives from registered Aboriginal parties;
- surface artefacts will be flagged prior to collection. The flagged site will be photographed to record the spatial distribution of artefacts within the site;
- the location of each surface artefact will be recorded using a handheld GPS to record the spatial distribution of artefacts within the site; and
- artefacts will be individually bagged and labelled (including site name, date, and MGA co-ordinate).
- Repository on site would be with Morson Group in a secure locked container, unless nominated separately as part of RAP consultation for the AHIP.
- If archaeological assistance is required, it can be made on call.

4.10 REPORTING

Recording of artefacts will be undertaken in accordance with Requirement 26 of the *Code of Practice for Archaeological Investigation of Aboriginal objects in NSW.* Following completion of excavations, an Aboriginal Site Impact Recording form will be completed and submitted to the AHIMS Registrar as soon as practicable, for each AHIMS site that has been the subject of salvage in accordance with the requirements of the Code. The results of the excavations will be incorporated into an archaeological excavation report.

4.10.1. Attributes to be recorded for Stone Artefacts

The table below provides an indication of the attributes to be recorded for stone artefacts.

Table 4: Attributes to be recorded

General Attributes (All Artefacts)	Additional Attributes (Flakes)	Additional Attributes (Cores)
Artefact Type	Platforms (width, thickness, surface, overhang removal)	Rotated
Raw Material	Termination	Platform Preparation
Artefact Weight (g)	Retouch (Location and Type)	Scar Type
Artefact Measurements (Length, Width, Thickness)	Breakage	Exhausted
Cortex (Amount and Type)		
Heat Affect		

4.11 SHORT AND LONG TERM CARE OF ABORIGINAL OBJECTS

Options for Short Term Care of Aboriginal Objects

It is proposed that artefacts recovered through the salvage excavation program will be temporarily held by Virtus Heritage at their offices at Kingscliff or Sydney unless an alternative care arrangement is sought by Registered Aboriginal Parties. Where requested, Virtus Heritage will provide access to artefacts to the Registered Aboriginal Parties.

For community collection, without archaeological supervision, repository on site would be with Morson Group in a secure locked container, unless nominated separately as part of RAP consultation for the AHIP.

September 2025 Page 20 of 22



Opportunities for Registered Aboriginal Parties to participate in the cleaning and analysis of artefacts will be considered.

Options for Long Term Care of Aboriginal Objects

Options being considered for the long-term care of Aboriginal objects recovered from the archaeological test excavation under the AHIP application include:

- Lodgement of Aboriginal objects with Deerubbin Local Aboriginal Land Council or other Aboriginal organisation under a Care Agreement, for example at the Parramatta Gaol Keeping Place.
- Lodgement of the Aboriginal objects at the Parramatta Square/Phive Keeping Place
- On site display under a Care Agreement.
- On display for interpretation in the development or in another area publicly for a selection of objects as suggested a RAP.
- Other options identified by Registered Aboriginal Parties

4.12 SAFETY AND ENVIRONMENTAL MANAGEMENT

The following logistics will need to be arranged by the proponent for the excavation:

- A small to medium (5 14 tonne) excavator with a flat bucket of 1 m width or less for mechanical excavation.
- Auger and black case for auger for OSL sampling
- Removal of overburden and fill
- Toilet facilities (Men's and Women's).
- Where wet sieving is required:
 - A water source for the wet sieving of excavated soil (e.g. on-site water source or a water truck).
 - Watertight skip bins to capture sieve water and spoil with forklift capabilities.
 - Emptying of bins of water and sieved spoil 2-3 times a day, in accordance with EPA environmental management requirements.
 - Use of a forklift or Manitou to empty bins and a location to handle the volume of water runoff and spoil.
- Secure lockable storage for equipment and retrieved artefacts.
- · Contamination control if necessary.
- · Backfilling of excavated pits with clean fill.

September 2025 Page 21 of 22



5. References

DECCW (2010a) Aboriginal heritage consultation requirements for proponents 2010.

DECCW (2010b) Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW.

DECCW (2010c) Due Diligence Code of Practice for the Protection of Aboriginal Objects in NSW and Archaeological Investigation of Aboriginal Objects Code of Practice.

Mitchell, P. (2010) Geomorphology and soils in relation to archaeological investigations on the Cranebrook Terrace, Penrith Lakes, NSW. Report to Comber Consultants for PLDC.

PLDC (2011) Penrith Lakes Scheme Area Aboriginal Heritage Assessment Report. Published by Penrith Lakes Development Corporation.

Virtus Heritage (2024) Archaeological Assessment Castlereagh Tourism Development 39-65 Old Castlereagh Road, Castlereagh NSW. Report to Morson Group.

Williams A, A. Burrow, P. Toms, O. Brown, M. Richards and T. Bryant (2017) 'The Cranebrook terrace revisited: recent excavations of an early Holocene alluvial deposit on the banks of the Nepean River, NSW, and their implications for the future work in the region, *Australian Archaeology*, 83(3) pp. 100–109

September 2025 Page 22 of 22



Appendix A2. Aboriginal Heritage Information Management System Search Results

September 2025 Page 78 of 87

Your Ref/PO Number : 537

Client Service ID: 1022220

Date: 10 July 2025

Virtus Heritage Pty Ltd - Pottsville

38 Border Crescent

Pottsville New South Wales 2489


Attention: Kate Morris

Email: k.morris@virtusheritage.com.au

Dear Sir or Madam:

AHIMS Web Service search for the following area at Datum :GDA, Zone : 56, Eastings : 281848.0 - 289036.0, Northings : 6261482.0 - 6270558.0 with a Buffer of 0 meters, conducted by Kate Morris on 10 July 2025.

The context area of your search is shown in the map below. Please note that the map does not accurately display the exact boundaries of the search as defined in the paragraph above. The map is to be used for general reference purposes only.



A search of Heritage NSW AHIMS Web Services (Aboriginal Heritage Information Management System) has shown that:

87	Aboriginal sites are recorded in or near the above location.
0	Aboriginal places have been declared in or near the above location. *

If your search shows Aboriginal sites or places what should you do?

- You must do an extensive search if AHIMS has shown that there are Aboriginal sites or places recorded in the search area.
- If you are checking AHIMS as a part of your due diligence, refer to the next steps of the Due Diligence Code of practice.
- You can get further information about Aboriginal places by looking at the gazettal notice that declared it.
 Aboriginal places gazetted after 2001 are available on the NSW Government Gazette
 (https://www.legislation.nsw.gov.au/gazette) website. Gazettal notices published prior to 2001 can be
 obtained from Heritage NSW upon request

Important information about your AHIMS search

- The information derived from the AHIMS search is only to be used for the purpose for which it was requested. It is not be made available to the public.
- AHIMS records information about Aboriginal sites that have been provided to Heritage NSW and Aboriginal places that have been declared by the Minister;
- Information recorded on AHIMS may vary in its accuracy and may not be up to date. Location details are recorded as grid references and it is important to note that there may be errors or omissions in these recordings,
- Some parts of New South Wales have not been investigated in detail and there may be fewer records of Aboriginal sites in those areas. These areas may contain Aboriginal sites which are not recorded on AHIMS.
- Aboriginal objects are protected under the National Parks and Wildlife Act 1974 even if they are not recorded as a site on AHIMS.
- This search can form part of your due diligence and remains valid for 12 months.



Your Ref/PO Number: 537

Extensive search - Site list report Client Service ID: 1022221

<u>SiteID</u>	<u>SiteName</u>	<u>Datum</u>	Zone	Easting	Northing	<u>Context</u>	Site Status **	<u>SiteFeatures</u>	<u>SiteTypes</u>	<u>Reports</u>
45-5-0541	RP5 Penrith Leagues Club	AGD	56	285350	6262560	Open site	Valid	Artefact : -	Open Camp Site	102450,10315
										5,103360
	Contact	Recorders		abeth Rich	(0(1000	0 4	** 1. 1	Permits	0 0 0	4.000.400.455.4
45-5-0790	Jamison_and Blaikie Roads;	AGD	56	284750	6261800	Open site	Valid	Artefact : -	Open Camp Site	1633,103155,1 03360
	Contact	Recorders	Pam	Dean-Jones				<u>Permits</u>		03300
45-5-0493	Emu Plains (EP/1 P/3)	AGD		281830	6262460	Open site	Valid	Artefact : -	Open Camp Site	1018
	Contact	Recorders	lim I	Kohen		-		Permits Permits		
45-5-0222	Jamisons Creek Emu Plains	AGD		282220	6262184	Open site	Valid	Artefact : -	Open Camp Site	822
	Contact	Recorders	Iim I	Kohen				Permits		
45-5-5379	SMDS Basin I Area 06 PAD	GDA	,	288770	6265160	Open site	Valid	Artefact : -, Potential		
						•		Archaeological		
								Deposit (PAD) : -		
	Contact	Recorders			-	lls,Ms.Sophie Jenning		<u>Permits</u>	5411	
45-5-0333	Penrith Lakes 23	AGD	56	285375	6269289	Open site	Valid	Artefact : -	Open Camp Site	260,526,1018
	Contact	Recorders	,	Kohen				<u>Permits</u>	872	
45-5-0070	Lapstone Creek (Emu Plains)	AGD	56	282116	6262822	Open site	Valid	Artefact : -	Open Camp Site	527
	Contact	Recorders		Kohen				<u>Permits</u>		
45-5-3598	ADI: FF/30 (Springwood)	GDA	56	288835	6265442	Open site	Valid	Artefact : 1		102155,10245
										0
	Contact	Recorders	Io M	cDonald Cult	ural Heritage N	Janagement see GMI		Permits		
45-5-3599	Contact ADI: FF/31 (Springwood)	Recorders GDA	,			Management see GMI Open site		Permits Artefact : 19		102450
45-5-3599	ADI: FF/31 (Springwood)	GDA	56	288950	6265366	Open site	Valid	Artefact : 19		102450
	ADI: FF/31 (Springwood) <u>Contact</u>	GDA Recorders	56 Jo M	288950 cDonald Cult	6265366 ural Heritage N	Open site Management see GML	Valid _	Artefact : 19 Permits		
45-5-3599 45-5-5019	ADI: FF/31 (Springwood)	GDA	56 Jo M	288950	6265366	Open site	Valid	Artefact : 19		102450
	ADI: FF/31 (Springwood) <u>Contact</u>	GDA Recorders	56 Jo M	288950 cDonald Cult	6265366 ural Heritage N	Open site Management see GML	Valid _	Artefact : 19 Permits Potential		
	ADI: FF/31 (Springwood) <u>Contact</u>	GDA Recorders GDA Recorders	56 Jo M 56	288950 cDonald Cult 285850 .ber Consulta	6265366 ural Heritage M 6262985	Open site Management see GMI Open site	Valid Valid	Artefact : 19 Permits Potential Archaeological	4477	
	ADI: FF/31 (Springwood) Contact Union Street Penrith	GDA Recorders GDA	56 Jo M 56	288950 cDonald Cult 285850	6265366 ural Heritage M 6262985	Open site Management see GMI Open site	Valid Valid	Artefact : 19 Permits Potential Archaeological Deposit (PAD) : 1	4477	
45-5-5019	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact	GDA Recorders GDA Recorders	56 Jo M 56 Com 56	288950 cDonald Cult 285850 ber Consulta 285973	6265366 ural Heritage N 6262985 nts Pty Limited 6263538	Open site Management see GMI Open site d,Comber Consultant	Valid Valid s Pty Limited,Ms.A Valid n Anderson	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Artefact: - Permits	4477	
45-5-5019	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1	GDA Recorders GDA Recorders GDA	56 Jo M 56 Com 56 Kelle	288950 cDonald Cult 285850 ber Consulta 285973	6265366 ural Heritage N 6262985 nts Pty Limited 6263538	Open site Management see GMI Open site d,Comber Consultant Open site	Valid Valid Valid s Pty Limited,Ms.A	Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential	4477	
45-5-5019 45-5-5191	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact	GDA Recorders GDA Recorders GDA Recorders	56 Jo M 56 Com 56 Kelle	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting	6265366 ural Heritage N 6262985 nts Pty Limited 6263538 ale Consulting	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir	Valid Valid s Pty Limited,Ms.A Valid n Anderson	Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological	4477	
45-5-5019 45-5-5191	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS	GDA Recorders GDA Recorders GDA Recorders GDA	56 Jo M 56 Com 56 Kelle 56	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting 285284	6265366 ural Heritage M 6262985 nts Pty Limited 6263538 cale Consulting 6269516	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): -	4477	
45-5-5019 45-5-5191 45-5-4568	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact	GDA Recorders GDA Recorders GDA Recorders GDA Recorders	56 Jo M 56 Com 56 Kelle 56	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting 285284	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits		103872
45-5-5019 45-5-5191	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30	GDA Recorders GDA Recorders GDA Recorders GDA Recorders AGD	56 Jo M 56 Com 56 Kelle 56 GML	288950 cDonald Cult 285850 ober Consulta 285973 eher Nighting 285284 other Heritage Pty 284230	6265366 ural Heritage M 6262985 nts Pty Limited 6263538 cale Consulting 6269516	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: -	Open Camp Site	
45-5-5019 45-5-5191 45-5-4568 45-5-0591	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30 Contact	Recorders GDA Recorders GDA Recorders GDA Recorders GDA Recorders AGD Recorders	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim I	288950 cDonald Cult 285850 ober Consulta 285973 eher Nighting 285284 otheritage Pty 284230 Kohen	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516 Ltd - Surry Hi 6266400	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site lls,Doctor.Tim Owen Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: - Permits	Open Camp Site 28	103872
45-5-5019 45-5-5191 45-5-4568	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30	GDA Recorders GDA Recorders GDA Recorders GDA Recorders AGD	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim I	288950 cDonald Cult 285850 ober Consulta 285973 eher Nighting 285284 other Heritage Pty 284230	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: -	Open Camp Site	103872
45-5-5019 45-5-5191 45-5-4568 45-5-0591	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30 Contact	Recorders GDA Recorders GDA Recorders GDA Recorders GDA Recorders AGD Recorders	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim H 56	288950 cDonald Cult 285850 ober Consulta 285973 eher Nighting 285284 otheritage Pty 284230 Kohen	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516 Ltd - Surry Hi 6266400	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site lls,Doctor.Tim Owen Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: - Permits	Open Camp Site 28	103872 1064,102450 1018,102450,1
45-5-5191 45-5-4568 45-5-0591	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30 Contact Penrith P/1 (duplicate of 45-5-0290)	GDA Recorders GDA Recorders GDA Recorders GDA Recorders AGD Recorders	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim H 56	288950 cDonald Cult 285850 sber Consulta 285973 eher Nighting 285284 . Heritage Pty 284230 Kohen 285520	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516 Ltd - Surry Hi 6266400	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site lls,Doctor.Tim Owen Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: - Permits Artefact: - Permits Artefact: -	Open Camp Site 28 Open Camp Site	103872 1064,102450 1018,102450,1
45-5-5019 45-5-5191 45-5-4568 45-5-0591 45-5-0522	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30 Contact Penrith P/1 (duplicate of 45-5-0290) Contact	Recorders GDA Recorders GDA Recorders GDA Recorders AGD Recorders AGD Recorders	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim H 56	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting 285284 Heritage Pty 284230 Kohen 285520 Kohen 285400	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516 Ltd - Surry Hi 6266400 6263940	Open site Management see GMI Open site d,Comber Consultant: Open site Pty Ltd,Mr.Benjamir Open site lls,Doctor.Tim Owen Open site Open site Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: - Permits Artefact: - Permits Artefact: - Permits	Open Camp Site 28 Open Camp Site	103872 1064,102450 1018,102450,1 03155,103360

Report generated by AHIMS Web Service on 10/07/2025 for Kate Morris for the following area at Datum: GDA, Zone: 56, Eastings: 281848.0 - 289036.0, Northings: 6261482.0 - 6270558.0 with a Buffer of 0 meters.. Number of Aboriginal sites and Aboriginal objects found is 87



Extensive search - Site list report

Your Ref/PO Number: 537

Client Service ID: 1022221

<u>iteID</u>	<u>SiteName</u>	<u>Datum</u>	Zone	Easting	Northing	<u>Context</u>	Site Status **	<u>SiteFeature</u>	<u>s</u>	<u>SiteTypes</u>	<u>Reports</u>
5-5-5238	Andrews Road PAD 1	GDA	56	286905	6264763	Open site	Destroyed	Artefact : -			104180
	Contact	Recorders	Bios	is Pty Ltd - V	Vollongong,Bio	sis Pty Ltd - Woll	ongong,Mrs.Samantha	a Keats,Mrs.S	Permits Permits	4518	
5-5-2414	L1 (Penrith Lakeside Village)	GDA	56	286799	6266617	Open site	Valid	Artefact : -		Open Camp Site	102450,10418 0
	Contact	Recorders	Mar	y Dallas Cons	sulting Archaed	ologists (MDCA),B	Biosis Pty Ltd - Wollor	igong,Mrs.Sai	Permits	939,1694,1803	
5-5-0317	Penrith Lakes 3	AGD		284461	6269271	Open site	Valid	Artefact : -		Open Camp Site	256,260,526,10 18,105447
	Contact	Recorders	,	Kohen					<u>Permits</u>		07.00.00.00.00
-5-0318	Penrith Lakes 4	GDA		283031	6267186	Open site	Valid	Artefact : -		Open Camp Site	256,260,526,10 18,105447
	Contact	Recorders		Kohen					<u>Permits</u>	3891	
5-5-3816	Emu Plains Rail Stabling Yards	GDA	56	284015	6263583	Open site	Destroyed	Artefact : 1			
	<u>Contact</u>	Recorders	Doct	tor.Alan Will	iams,Doctor.Al	an Williams			<u>Permits</u>	3485,4823	
5-5-3817	Emu Plains Rail Stabling Yards1	GDA	56	284138	6263601	Open site	Destroyed	Artefact : 1			
	Contact	Recorders	Doct	or.Alan Will	iams,Doctor.Al	an Williams			<u>Permits</u>	3282,4823	
-5-4302	TNR-3	GDA	56	288545	6265150	Open site	Valid	Artefact : 1			
	Contact	Recorders	Doct	tor.Jo McDon	ald				Permits	3619	
-5-5730	Nepean River Trail 05	GDA	56	282938	6269016	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.N	Aichael Jacks	on,Jackson Wa	rd Archaeology P	ty Ltd		<u>Permits</u>		
5-5-5732	Nepean River Trail 07	GDA	56	282948	6269276	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.N	Michael Jacks	on,Jackson Wa	rd Archaeology P	ty Ltd		Permits Permits		
5-5-0052	Emu Plains F4-1	AGD	56	281800	6262200	Open site	Valid	Artefact : -		Open Camp Site	100450
	Contact	Recorders	Mar	y Dallas Cons	sulting Archaed	ologists (MDCA),E	Elizabeth Rich		<u>Permits</u>		
5-5-0592	Penrith Lakes 33	AGD	56	286200	6268200	Open site	Valid	Artefact : -		Open Camp Site	1064
	Contact	Recorders	Jim I	Kohen					Permits Permits	847,872,2174	
-5-0593	Penrith Lakes 32	AGD	•	286250	6267700	Open site	Valid	Artefact : -		Open Camp Site	11,526,1063
	Contact	Recorders	Iim I	Kohen					Permits	1067	
5-5-1026	ADI-25;	AGD		288880	6264930	Open site	Valid	Artefact : -		Isolated Find	102155,10245 0,102573
	Contact	Recorders	Doct	tor.Jo McDon	ald				Permits Permits	5411	
5-5-0323	Penrith Lakes 10	AGD	56	284461	6269271	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018, 05447
	Contact	Recorders	Jim I	Kohen					<u>Permits</u>	872	
5-5-0324	Penrith Lakes 11	AGD	56	285357	6270203	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018, 05447
	Contact	Recorders	•	Kohen					<u>Permits</u>		
5-5-0325	Penrith Lakes 12	AGD		283546	6269253	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018, 05447
	Contact	Recorders	Jim I	Kohen					<u>Permits</u>		



Extensive search - Site list report

Your Ref/PO Number: 537 Client Service ID: 1022221

<u>SiteID</u>	<u>SiteName</u>	<u>Datum</u>	Zone	Easting	Northing	<u>Context</u>	Site Status **	<u>SiteFeatur</u>	res	<u>SiteTypes</u>	<u>Reports</u>
45-5-0328	Penrith Lakes 17	AGD	56	283617	6265596	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018
	Contact	Recorders	Jim K	Kohen					<u>Permits</u>	28	
45-5-0330	Penrith Lakes 19	AGD	56	284496	6267442	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450
	Contact	Recorders	Jim k	Kohen					Permits	28	
45-5-0334	Penrith Lakes 24	AGD		287257	6266581	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450
45 5 0006	Contact	Recorders	,		(0(5(05	0 1	77 1: 1	A . C .	<u>Permits</u>	0 0 00	260 526 1010 1
45-5-0336	Penrith Lakes 27	AGD		288189	6265685	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450
	Contact	Recorders		Kohen	(O(##40		** 1. 1		<u>Permits</u>	7 1 1 170 1	400455 40045
45-5-1024	ADI-23	AGD	56	288700	6265510	Open site	Valid	Artefact : -		Isolated Find	102155,10245 0,102573,1054 76
	<u>Contact</u>	Recorders		•	ıld,Ms.Jenni Ba				<u>Permits</u>		
45-5-5020	Tench Reserve AFT 1	GDA	56	283626	6261646	Open site	Valid	Artefact : -			
	Contact	Recorders	Kelle	her Nighting	ale Consulting	Pty Ltd,Miss.Kristen	Taylor		<u>Permits</u>		
45-5-5685	170 Russell Street	GDA	56	282934	6263991	Open site	Valid	Artefact : -			104390
	Contact	Recorders	Com	ber Consulta	nts Pty Limited	l,Ms.Agata Calabrese	:		Permits		
45-5-5731	Nepean River Trail 06	GDA	56	282951	6269734	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.M	lichael Jackso	n,Jackson Wa	rd Archaeology Pty L	td		Permits		
45-5-0540	RP4 Peach Tree Creek	AGD	56	284960	6262120	Open site	Valid	Artefact : -		Open Camp Site	103155,10336 0
	Contact	Recorders		beth Rich					Permits		
45-5-0287	Emu Plains (Jamisons Creek)	AGD	56	283052	6261743	Open site	Partially Destroyed	Artefact : -		Open Camp Site	260,1018,1031 55,103360
	Contact	Recorders		Kohen					<u>Permits</u>	1423,1842	
45-5-0290	The Island (duplicate of 45-5-0522)	AGD	56	285661	6263989	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450,103155, 103360
	Contact	Recorders	,						<u>Permits</u>	5327	
45-5-3796	Cranebrook Escarpment 1 (CE1)	GDA	56	285600	6269450	Open site	Valid	Artefact : 1	10		101748
	Contact	Recorders	Com	ber Consulta	nts Pty Limited	l			<u>Permits</u>		
45-5-5389	SMDS Basin I AFT 16	GDA	56	288674	6265173	Open site	Valid	Artefact : -			
	<u>Contact</u>	Recorders	GML	Heritage Pty	Ltd - Surry Hi	lls,Ms.Sophie Jenning	gs		Permits	5411	
45-5-0327	Penrith Lakes 16	AGD	56	285428	6266546	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450,105447
	Contact	Recorders	Jim k	Kohen					<u>Permits</u>		
45-5-0366	Emu Plains Emu Plains 4	AGD	56	285107	6264253	Open site	Valid	Artefact : -		Open Camp Site	1018,102450,1 03155,103360



Extensive search - Site list report

Your Ref/PO Number: 537

Client Service ID: 1022221

SiteID	<u>SiteName</u>	<u>Datum</u>	<u>Zone</u>	Easting	Northing	Context	Site Status **	<u>SiteFeatures</u>		<u>SiteTypes</u>	<u>Reports</u>
	Contact	Recorders		Kohen					ermits		
45-5-3904	EPRSY 3(PAD)	GDA	56	284000	6263615	Open site	Destroyed	Artefact : -, Po	tential		103762
								Archaeologica			
	Contact	Recorders	Doct	or Alan Willi	iame Doctor Al-	an Williams,Ms.Geor	ria Rurnott	Deposit (PAD)	:- ermits	3485,4823	
45-5-5021	Tench Reserve IF 1	GDA		283452	6261519	Open site	Valid	Artefact : -	<u> </u>	3403,4023	
15 5 5021	Contact	Recorders				Pty Ltd,Miss.Krister			ermits	4528	
45-5-1025	ADI-24;	AGD		288540	6264980	Open site	Valid	Artefact : -	<u> </u>	Isolated Find	102155,10245
15 5 1025	101 21,	nab	30	200310	0201700	open site	vana	m telact.		isolated i ma	0
	Contact	Recorders	Doct	or.Jo McDon	ald			<u>Pe</u>	ermits	5411	
45-5-5484	Emu Plains Railway AFT	GDA	56	284068	6263560	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.M	latthew Barl	oer,NGH Herita	ge - Fyshwick		<u>Pe</u>	ermits		
45-5-5728	Nepean River Trail 03	GDA	56	282727	6267103	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.M	lichael Jacks	on,Jackson Wa	rd Archaeology Pty I	td	<u>Pe</u>	ermits		
45-5-5908	SummitCare Penrith PAD	GDA	56	285290	6261928	Open site	Valid	Potential			
								Archaeologica			
	Control	D	C) (I	11 to Do				Deposit (PAD)			
45-5-5390	Contact SMDS Basin I AFT 15	Recorders GDA		288860	y Lta - Surry Hi 6265155	lls,Mr.Jacob (GML) K Open site	valid	Artefact : -	<u>ermits</u>		
43-3-3390						•					
45-5-0319	Contact Penrith Lakes 5	Recorders GDA		283157	6268242	lls,Ms.Sophie Jenning	gs Valid	Artefact : -	ermits	Open Camp Site	260,526,1018,1
45-5-0519	Pennun Lakes 5	GDA	50	203137	0200242	Open site	valiu	Artelact : -		Open camp site	05447
	Contact	Recorders	Jim F	Kohen				<u>Pe</u>	ermits	3891	00117
45-5-0326	Penrith Lakes 15	AGD	56	285428	6266546	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1
											02450,105447
	Contact	Recorders		Kohen					<u>ermits</u>	28	
45-5-0331	Penrith Lakes 20	AGD	56	286325	6267478	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450
	Contact	Recorders	lim k	Kohen				Pe	ermits	28,1067	02450
45-5-5740	EPRSY 1	GDA	,	284199	6263600	Open site	Valid	Artefact : -	<u> </u>	20,1007	
	Contact	Recorders		ine Quinlan					ermits		
45-5-2491	Coreeen Ave 1	GDA		287199	6263429	Open site	Valid	Artefact : -	<u> </u>	Open Camp Site	98259,102450,
						~ p				~ p p	103155,10336
											0
	<u>Contact</u>	Recorders				/r.Matthew Barber,N			ermits	1367	
45-5-0281	Cranebrook Creek, CC/1	AGD	56	285150	6266723	Open site	Valid	Artefact : -,			260,526,1018,1
								Aboriginal Cer			02450
	Contact	Recorders	Jim F	Zohon .				and Dreaming	:- ermits	28	
	Contact	<u>Recorders</u>	Jun r	Konen				<u>Pt</u>	<u> </u>	40	



Extensive search - Site list report

Your Ref/PO Number: 537

Client Service ID: 1022221

<u>SiteID</u>	<u>SiteName</u>	<u>Datum</u>	Zone	Easting	Northing	<u>Context</u>	Site Status **	<u>SiteFeatures</u>	<u>SiteTypes</u>	<u>Reports</u>
45-5-3331	ADI/FF-30	AGD	56	288835	6265442	Open site	Valid	Artefact : 1		99635,102155, 102450,10257 3,103618
	<u>Contact</u> T Russell	Recorders	Jo M	cDonald Cult	ural Heritage l	Management see GM	L	<u>Perm</u>	<u>its</u> 3057	
45-5-3318	Western Sydney 6	GDA	56	287710	6264801	Open site	Valid	Artefact : 5		100554,10245 0
	<u>Contact</u> Searle	Recorders	Navi	n Officer Her	itage Consulta	nts Pty Ltd		Permi		
45-5-0314	Penrith Lakes 28	AGD		286325	6267478	Open site	Valid	Artefact : -	Open Camp Site	256,260,526,10 18,102450
	Contact	Recorders	,	Kohen	6060000		** 1. 1	Permi		0.00.404.0.4004
45-5-0340	Penrith Regional Art Gallery	AGD		284048	6262220	Open site	Valid	Art (Pigment or Engraved) : -	Rock Engraving	260,1018,1031 55,103360
45 4 0040	Contact	Recorders		les.D Power	6065450	0 "	77 1: 1	Permi		0446400450
45-1-0219	Penrith Lakes 39	AGD		284930	6267150	Open site	Valid	Artefact : -	Open Camp Site	2446,102450
	Contact	Recorders	,	Kohen				<u>Permi</u>	_	
45-5-3941	PL53	GDA	56	283676	6270056	Open site	Partially Destroyed	Artefact : -, Potent Archaeological Deposit (PAD) : -	ial	105454,10572 9
	Contact	Recorders	Com	ber Consulta	nts Pty Limite	d,Mr.Shaun Hooper,F	leritage Now - Bel	mont,Heritae Perm	<u>its</u> 5297	
45-5-5470	Andrews Road PAD 1 Reburial	GDA	56	287428	6264919	Open site	Valid	Artefact : -		
	Contact	Recorders	Bios	is Pty Ltd - W	ollongong,Mrs	s.Samantha Keats		Permi	<u>its</u>	
45-5-0051	Emu Plains	AGD		281883	6265379	Closed site	Valid	Art (Pigment or Engraved) : -	Shelter with Art	
	Contact	Recorders	Fred	McCarthy				<u>Permi</u>	<u>its</u>	
45-5-0589	Penrith Lakes 29	AGD	56	284300	6266280	Open site	Valid	Artefact : -	Open Camp Site	1064
	Contact	Recorders	Jim I	Kohen				<u>Permi</u>	<u>its</u> 28	
45-5-0530	Upper Castlereagh, UC/1	GDA	56	283035	6267149	Open site	Valid	Artefact : -	Open Camp Site	1018
	Contact	Recorders	Jim I	Kohen				Permi	its 3891	
45-5-2850	Vincent Road 1	AGD	56	287550	6268250	Open site	Valid	Artefact : -		
	Contact	Recorders	Doct	or.Susan (lef	t ahms) Mcint	vre-Tamwov		Permi	its 1599	
45-5-0329	Penrith Lakes 18	AGD		283617	6265596	Open site	Valid	Artefact : -	Open Camp Site	260,526,1018
	Contact	Recorders	lim I	Kohen		-		Permi	its 28	
45-5-0332	Penrith Lakes 21	AGD		284514	6266528	Open site	Valid	Artefact : -	Open Camp Site	260,526,1018,1 02450
	Contact	Recorders	Jim I	Kohen				<u>Permi</u>	<u>its</u> 28	
45-5-0288	Emu Plains	AGD	56	282030	6262546	Open site	Valid	Artefact : -	Open Camp Site	260,1018
	Contact	Recorders	Jim I	Kohen				Permi	<u>its</u>	
45-5-5311	River Road AS1	GDA		284756	6263365	Open site	Valid	Artefact : -, Potent: Archaeological Deposit (PAD) : -		



Extensive search - Site list report

Your Ref/PO Number: 537 Client Service ID: 1022221

SiteID Zone Northing Context Site Status ** SiteName Datum **Easting** SiteFeatures SiteTypes Reports Contact Recorders Biosis Pty Ltd - Wollongong, Eco Logical Australia Pty Ltd - Sydney - Individual user Permits 4634.4731 Potential 45-5-5902 Penrith Stadium PAD GDA 56 285738 6262322 Open site Valid Archaeological Deposit (PAD): -Contact Recorders Curio Projects Pty Ltd, Miss. Rebecca Agius **Permits** 5314 Nepean River Trail 04 GDA 45-5-5729 56 282884 6268421 Valid Artefact: -Contact Recorders Mr.Michael Jackson, Jackson Ward Archaeology Pty Ltd **Permits** 1018,103155,1 45-5-0539 RP3 Peach Tree Creek AGD 56 284920 6262050 Open site Valid Artefact: -Open Camp Site 03360 Contact Recorders Elizabeth Rich **Permits** 45-5-0282 Upper Castlereagh 56 282979 Valid Artefact: -Open Camp Site **GDA** 6267050 Open site 260.1018 **Permits Contact** Recorders Jim Kohen 3891 45-5-0590 Penrith Lakes 31 56 284610 6266550 Valid Artefact: -1064.102450 AGD Open site Open Camp Site Contact Recorders Iim Kohen **Permits** 28 1018.103155.1 45-5-0495 Jamisons Creek JC/2 Penrith AGD 56 282890 6261700 Open site Valid Artefact: -Open Camp Site 03360 Recorders Contact Jim Kohen **Permits** GDA 56 287679 Valid Artefact: 1 100554,10245 45-5-3317 Western Sydney 5 6264900 Open site 0 Contact Searle Recorders Navin Officer Heritage Consultants Pty Ltd **Permits** Artefact: 1. Potential 100554.10245 45-5-3319 Western Sydney 7 and PAD GDA 56 287450 6264725 Open site Valid Archaeological n Deposit (PAD): -Contact Searle Recorders Navin Officer Heritage Consultants Pty Ltd, Biosis Pty Ltd - Wollongong, Mrs. Samant Permits Artefact: -, Potential 103360 45-5-4361 Peachtree Creek PAD GDA 56 285590 6263560 Open site Valid Archaeological Deposit (PAD): -**Contact** Recorders Mr.Oliver Brown **Permits** 3664,3688 Penrith Lakes 2 256.260.526.10 45-5-0316 AGD 56 284443 6270186 Open site Valid Artefact: -Open Camp Site 18.103395.105 447 Contact Recorders Jim Kohen **Permits** 45-5-0335 Penrith Lakes 26 AGD 56 287274 6265667 Open site Valid Artefact: -Open Camp Site 260,526,1018,1 02450 Contact Recorders Iim Kohen **Permits** 45-5-2416 L-1:Penrith Lakeside Village: 6266617 Valid 102450 **GDA** 56 286799 Open site Artefact: -Open Camp Site **Contact** Recorders Mary Dallas Consulting Archaeologists (MDCA), Biosis Pty Ltd - Wollongong, Mrs. Sai Permits 45-5-5727 Nepean River Trail 02 GDA 56 282748 Artefact: -6270469 Open site Valid Contact Recorders 8 1 Mr. Michael Jackson, Jackson Ward Archaeology Pty Ltd **Permits**



Extensive search - Site list report

Your Ref/PO Number: 537 Client Service ID: 1022221

<u>SiteID</u> <u>SiteName</u> <u>Datum</u> <u>Zone</u> <u>Easting</u> <u>Northing</u> <u>Context</u> <u>Site Status **</u> <u>SiteFeatures</u> <u>SiteTypes</u> <u>Reports</u>

** Site Status

Valid - The site has been recorded and accepted onto the system as valid

Destroyed - The site has been completely impacted or harmed usually as consequence of permit activity but sometimes also after natural events. There is nothing left of the site on the ground but proponents should proceed with caution.

Partially Destroyed - The site has been only partially impacted or harmed usually as consequence of permit activity but sometimes also after natural events. There might be parts or sections of the original site still present on the ground

Not a site - The site has been originally entered and accepted onto AHIMS as a valid site but after further investigations it was decided it is NOT an aboriginal site. Impact of this type of site does not require permit but Heritage NSW should be notified

Search Results

50 results found.

ADI Site Western Precinct The Northern Rd	Llandilo, NSW, Australia	(<u>Place rejected for emergency</u> <u>listing</u>) National Heritage List
Agnes Banks Nature Reserve and Adjoining Areas Rickards Rd	Agnes Banks, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh Area	Upper Castlereagh, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh Cemetery Church St	Cranebrook, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh Jewel Beetle Habitat and Movement Corridor The Northern Rd	Berkshire Park, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh State Forest and Adjacent Area The Northern Rd	Berkshire Park, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Combewood, Outbuildings and Garden 306 RMB Castlereagh Rd	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only. no statutory basis) Register of the National Estate (Non-statutory archive)
Cranebrook Airservices Land Cranebrook Rd	Cranebrook, NSW, Australia	(<u>Ineligible place</u>) Commonwealth Heritage List

Emu Plains Community Arts Centre Great Western Hwy	Emu Plains, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Fernhill Mulgoa Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Fernhill Setting Mulgoa Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Former ADI Site The Northern Rd	Llandilo, NSW, Australia	(Nomination now ineligible for PPAL) National Heritage List
Glen Leigh and Outbuildings Mulgoa Rd	Regentville, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Glenmore Mulgoa Rd	Regentville, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Greater Blue Mountains Area Great Western Hwy	Katoomba, NSW, Australia	(<u>Declared property</u>) World Heritage List
Homestead Site & Windbreak Soling Cr	Mount Pleasant, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Indigenous Place	Blaxland, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)

Indigenous Place Yarramundi, NSW, (Indicative place before RNE Australia closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive) Jordan Hill Site North St Marys, NSW, (Destroyed before RNE closed. Australia Record for reference only, no statutory basis Register of the National Estate (Non-statutory archive) King Family Farm Sites and Trees Links Rd North St Marys, NSW, (Included place before RNE Australia closed. Record for reference only, no statutory basis Register of the National Estate (Non-statutory archive) King Family Farm Sites and Trees Links Rd North St Marys, NSW, (Ineligible place) Australia Commonwealth Heritage List King Family Farm Sites and Trees Links Rd St Marys, NSW, (Nomination now ineligible for Australia PPAL) National Heritage List St Clair, NSW, Mamre and Curtilage Mamre Rd (Included place before RNE Australia closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive) McGarvie Smith University Farm 124 Elizabeth Dve Badgerys Creek, NSW, (Nomination now ineligible for Australia PPAL) National Heritage List Minnaville Castlereagh Rd Castlereagh, NSW, (Indicative place before RNE Australia closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive) Mulgoa Group and Landscape Mulgoa Rd Mulgoa, NSW, (Included place before RNE Australia closed. Record for reference only, no statutory basis Register of the National Estate (Non-statutory archive)

Mulgoa Natural Area Sir John Jamison Cirt	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Museum of Fire Castlereagh Rd	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Nepean Park Castlereagh Rd	Castlereagh, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Orchard Hills Cumberland Plain Woodland The Northern Rd	Orchard Hills, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Orchard Hills Cumberland Plain Woodland The Northern Rd	Orchard Hills, NSW, Australia	(<u>Listed place</u>) Commonwealth Heritage List
Osborne Castlereagh Rd	Agnes Banks, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Penrith Courthouse (former) High St	Penrith, NSW, Australia	(Destroyed before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
St Mary Magdalene Anglican Church & Cemetery Great Western Hwy	St Marys, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)

J. 12 1 WI	Australian Hentage Database	
St Marys Permanent Cottage Area	St Marys, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
St Stephens Anglican Church & Graveyard 252 High St	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
St Thomas Anglican Church & Cemetery St Thomas Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
The Cottage St Thomas Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only. no statutory basis) Register of the National Estate (Non-statutory archive)
The Greater Blue Mountains Area Greater Western Hwy	Katoomba, NSW, Australia	(<u>Listed place</u>) National Heritage List
The Greater Blue Mountains Area - Additional Values and Areas Great Wester	rn Hwy Katoomba, NSW, Australia	(<u>Nominated place</u>) National Heritage List
The Lewers Bequest & Penrith Regional Art Gallery & Garden 86 River Rd	Emu Plains, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Thornton Hall & Surrounds 11 Mountain View Cr	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Thornton Hall & Surrounds 11 Mountain View Cr	Penrith, NSW, Australia	(Place removed from CHL) Commonwealth Heritage List
Thornton Hall and Surrounds (former Defence land) 11 Mountain View Co	r Penrith, NSW, Australia	(Place removed from CHL) Commonwealth Heritage List

J. 12 FW Au	Stratian rientage Database	
Upper Room Chapel, Hall and Cemetery 1727 Castlereagh Rd	Castlereagh, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
victoria Bridge Great Western Hwy	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
<u>Wara-n'hayara Plateau Area - part</u> Mount Kiera Rd	Wollongong, NSW, Australia	(<u>Place not included in NHL</u>) National Heritage List
Werrington House Rugby Street	Werrington County, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Western Sydney Shale Woodland St Marys Forrester Rd	St Marys, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Western Sydney Shale Woodland St Marys Forrester Rd	St Marys, NSW, Australia	(<u>Ineligible place</u>) Commonwealth Heritage List

Report Produced: Thu Jul 17 15:12:23 2025

Accessibility | Disclaimer | Privacy | © Commonwealth of Australia





Heritage Search Result

Date: 17/07/2025

Item Name	Location	LGA	SHR Id	Item Type	Record Owner
"Broadville", Victorian house	98 Station Street PENRITH NSW 2750	Penrith		Built	LGOV
"Bronte", villa	50 Gidley Street ST MARYS NSW 2760	Penrith		Built	LGOV
"Chestnut" dwelling, slab cottage, trees and garden	580-600 Castlereagh Road AGNES BANKS NSW 2753	Penrith		Built	LGOV
"Combewood", house, garden, trees and original entrance drive	234-256 Coreen Avenue PENRITH NSW 2750	Penrith		Complex / Group	LGOV
"Craithes", dwelling, trees, outbuildings and carriage loop	34-40 Borec Road PENRITH NSW 2750	Penrith		Built	LGOV
"Cram Place", coach house, well, pump and cast iron fence	338-340 High Street PENRITH NSW 2750	Penrith		Complex / Group	LGOV
"Dungarth" and remnant plantings site	4 Stockade Street EMU PLAINS NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
"Edinglassie", house	22 Bunyan Road LEONAY NSW 2750	Penrith		Built	LGOV
"Emu Hall", dwelling,outbuildings and trees	2-26 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
"Fairlight", homesteas,outbuildings and gardens	377-429 Fairlight Road MULGOA NSW 2745	Penrith		Complex / Group	LGOV
"Fernhill", curtilage	1147-1187 Mulgoa Road MULGOA NSW 2745	Penrith		Landscape	LGOV
"Fernhill", house, outbuildings, and landscape	1041-1117 Mulgoa Road MULGOA NSW 2745	Penrith		Complex / Group	LGOV
"Four Winds" - dwelling	568 Great Western Highway CLAREMONT MEADOWS NSW 2747	Penrith		Built	LGOV

"Glenleigh", estate	427-507 Mulgoa	Penrith	Built	LGOV
	Road MULGOA NSW 2745			
"Glenmore"	754-760 Mulgoa Road MULGOA NSW 2745	Penrith	Built	LGOV
"Gwandalan", dwelling and garden	35 Cary Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Huntington Hall", house and garden	48-52 Beach Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Kelvin Brae", Federation house	142 High Street PENRITH NSW 2750	Penrith	Built	LGOV
"Kenilworth", dwelling and trees	6-9 Tallowood Place CRANEBROOK NSW 2749	Penrith	Built	LGOV
"Kentucky", villa	146 Station Street PENRITH NSW 2750	Penrith	Built	LGOV
"Killeen", Federation House	34 Walkers Crescent EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Leo Buring" cottage, barn, glasshouse and memorial	3a Leonay Parade LEONAY NSW 2750	Penrith	Built	LGOV
"Lindfield"	182-188 Caddens Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
"Madang Park", farmhouse and trees	475-487 Jamison Road PENRITH NSW 2750	Penrith	Built	LGOV
"Margaret Farm", house, barn and tannery site	Pages Road, Barker, Wilson and Schleicher Streets ST MARYS NSW 2760	Penrith	Built	LGOV
"Mimosa", dwelling, fence and garden	13 Pages Road ST MARYS NSW 2760	Penrith	Built	LGOV
"Mimosa", stables (former)	11 Pages Road ST MARYS NSW 2760	Penrith	Built	LGOV
"Minnamurra", house	43 Warwick Street PENRITH NSW 2750	Penrith	Built	LGOV
"Mountain View" house	39 Grey Street EMU PLAINS NSW 2750	Penrith	Built	LGOV

"Mourilyan"	329-333 Great Western Highway ST MARYS NSW 2760	Penrith	Built	LGOV
"Orange Grove", cottage	15 Park Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Osborne", homestead,barn,outbuildings and plantings	580-600 Castlereagh Road AGNES BANKS NSW 2753	Penrith	Built	LGOV
"Passadena", house	45-61 Allan Road MULGOA NSW 2745	Penrith	Built	LGOV
"Seidler", house	31-33 Nepean Avenue PENRITH NSW 2750	Penrith	Built	LGOV
"The Cottage", dwelling and pine tree	39 Warwick Street PENRITH NSW 2750	Penrith	Built	LGOV
"Thompson's Tannery" site, tannery pits (former) and well	94 Saddington Street ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
"Torquay", house	555 Great Western Highway WERRINGTON NSW 2747	Penrith	Built	LGOV
"Tyreel" , dwelling and barn	626-652 Castlereagh Road AGNES BANKS NSW 2753	Penrith	Built	LGOV
"Werrington House", dwelling, driveway and garden	108 Rugby Street WERRINGTON COUNTY NSW 2747	Penrith	Built	LGOV
"Werrington Park House", garden and poplar avenue	653-729 Great Western Highway WERRINGTON NSW 2747	Penrith	Complex / Group	LGOV
"Westbank" house	2 Nepean Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Winbourne", house	1315 Mulgoa Road MULGOA NSW 2745	Penrith	Built	LGOV
"Yamba" , cottage	32 Nixon Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Yodalla" house and garden	28 Nepean Street EMU PLAINS NSW 2750	Penrith	Built	LGOV

1841 Tilley 5 inch Manual Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1869 Shand Mason 7" Manual Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1891 Shand Mason Steamer Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1898 Shand Mason Curricle Ladders - Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1916 Garford Type 64 Chain Drive Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1929 Ahrens Fox PS2 Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1939 Dennis Big 6 Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1942 Ford 21W Fire Brigade Mobile Canteen	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1949 Dennis F1 Fire Engine (Scout Car)	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
Above Ground Tank; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Aerial Tower Concrete Mounts (x4); Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Agnes Banks Nature Reserve	2 Geebung Close AGNES BANKS NSW 2753	Penrith		Landscape	LGOV
Agnes Banks Public School (former)	475-479 Castlereagh Road AGNES BANKS NSW 2753	Penrith		Built	LGOV
Ahrens Fox PS2 Fire Engine (1929)	1 Museum Drive PENRITH NSW 2750	Penrith	01717	Movable / Collection	HNSW
Antennae Concrete Base and Remnant Antennae Base; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV

Antennae Concrete Base, Mounts and Service Pit; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mount - Last; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mount Base and for Guy Wires and Services Pit; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts - Base and for Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts - Base and for Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts - Base and for Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts - Base and for Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts and Remnant; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts: Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Carnebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV

Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV

Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV

Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Remnant and Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Remnants; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV

Arms of Australia Inn	127 Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	LGOV
Australian Arms Hotel	359 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Australian Arms Inn (former)	113 Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	LGOV
Bank of NSW (former)	354-360 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Bayley Park - House	919-929 Mamre Road KEMPS CREEK NSW 2178	Penrith	Built	LGOV
Bellbird Reserve	29 Barina Crescent EMU PLAINS NSW 2750	Penrith	Landscape	LGOV
Bennett Wagon	Pioneer Park Great Western Highway ST MARYS NSW 2760	Penrith	Movable / Collection	LGOV
Bennetts Wagons	2151(a) Castlereagh Road PENRITH NSW 2750	Penrith	Movable / Collection	LGOV
Berkshire Park Homestead Site	844-848 Richmond Road BERKSHIRE PARK NSW 2765	Penrith	Archaeological- Terrestrial	LGOV
Brick cottage	73 Forbes Street EMU PLAINS NSW 2750	Penrith	Unknown	LGOV
Brick Cottage	406 Park Road LUDDENHAM NSW 2745	Penrith	Built	LGOV
Brick cottage	31-33 Pages Road ST MARYS NSW 2760	Penrith	Built	LGOV
Brick cottage	40 Gidley Street ST MARYS NSW 2760	Penrith	Built	LGOV
Brick cottage	38 Gidley Street ST MARYS NSW 2760	Penrith	Built	LGOV
Brick cottage	18 Princess Mary Street ST MARYS NSW 2760	Penrith	Built	LGOV

Brick cottage	100-104 Saddington Street ST MARYS NSW 2760	Penrith	Built	LGOV
Brick Cottage	Campbell Street LUDDENHAM NSW 2745	Penrith	Built	LGOV
Brick Cottage	21-55 Campbell Street LUDDENHAM NSW 2745	Penrith	Built	LGOV
Brick Farmhouse	282 Aldington Road KEMPS CREEK NSW 2178	Penrith	Built	LGOV
Brick Farmhouse	80-88 Caddens Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Brick farmhouse, trees and orchard	850-856 Castlereagh Road AGNES BANKS NSW 2753	Penrith	Built	LGOV
Brick house	565 Great Western Highway WERRINGTON NSW 2747	Penrith	Built	LGOV
Brick house	96-100 Greendale Road WALLACIA NSW 2745	Penrith	Built	LGOV
Brick house and garden	80 River Road EMU PLAINS NSW 2750	Penrith	Built	LGOV
Brick villa	318 - 320 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Building AA - Werrington Park House and Poplar Avenue	Great Western Highway WERRINGTON NSW 2747	Penrith	Built	SGOV
Building Foundations; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Building Foundations; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	 Built	SGOV
Bungalow	38 Greendale Road WALLACIA NSW 2745	Penrith	Complex / Group	LGOV

Canine Council Dwelling	391-395 Mamre Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Castlereagh Council Chambers (former)	1158-1160 Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Castlereagh General Cemetery and native vegetation	77-85 East Wilchard Road CRANEBROOK NSW 2749	Penrith	Archaeological- Terrestrial	LGOV
Castlereagh General Cemetery and native vegetation	132-156 Church Street CRANEBROOK NSW 2749	Penrith	Archaeological- Terrestrial	LGOV
Castlereagh Public School (former)	13-25 West Wilchard Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Castlereagh Road Alignment	Castlereagh Road AGNES BANKS NSW 2753	Penrith	Built	LGOV
Castlereagh Road Alignment	Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Unknown	LGOV
Christ Church Anglican Church	230-232 Church Lane CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Commissioner's Uniform (NSWFire Brigades) - Ian Mac Dougall	1 Museum Drive PENRITH NSW 2750	Penrith	Movable / Collection	SGOV
Concrete house	39a-43 Mackellar Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
Concrete Slabs; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Concrete, timber and steel remnants; Carnebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Cottage	169 Cox Avenue PENRITH NSW 2750	Penrith	Built	LGOV
Cottage	Seventh Avenue (Eastern end) LLANDILO NSW 2747	Penrith	Built	SGOV

Cottage	14 York Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Cottage	10-12 North Street PENRITH NSW 2750	Penrith		Built	LGOV
Cottage	1306 Mulgoa Road MULGOA NSW 2745	Penrith		Built	LGOV
Cottage	288 High Street PENRITH NSW 2750	Penrith		Built	LGOV
Cottage	3065-3067 The Northern Road LUDDENHAM NSW 2745	Penrith		Built	LGOV
Cottage and outbuildings	268 Seventh Avenue LLANDILO NSW 2747	Penrith		Complex / Group	LGOV
Cox's Cottage	1012-1046 Mulgoa Road MULGOA NSW 2745	Penrith		Built	LGOV
Cox's Cottage	2 St Thomas Road MULGOA NSW 2745	Penrith	00171	Landscape	HNSW
Craithes House	34-40 Borec Road PENRITH NSW 2750	Penrith	00378	Built	HNSW
Cranebrook Air Radio Receiving Station Ruins	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Complex / Group	SGOV
Cranebrook Public School (former)	216 Boundary Road CRANEBROOK NSW 2749	Penrith		Built	LGOV
Crushing Plant	280a Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	LGOV
Dennis Big 6 Fire Engine (1939)	1 Museum Drive PENRITH NSW 2750	Penrith	01718	Movable / Collection	HNSW
Dunheved Fire Station	50 Christie Street ST MARYS NSW 2760	Penrith		Built	LGOV
Dunheved Homestead Site	Links Road ST MARYS NSW 2760	Penrith		Archaeological- Terrestrial	LGOV
Edward Smith Headquarters Switchboard - 1909	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV

Edward Smith Headquarters Switchboard (1909)	1 Museum Drive PENRITH NSW 2750	Penrith	01901	Movable / Collection	HNSW
Edwardian cottage	46 Russell Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Edwardian cottage	2068 Castlereagh Road PENRITH NSW 2750	Penrith		Built	LGOV
Emu Plains (Nepean River) Underbridge	Off Bruce Neale Dr, Steel Trusses 1.3 Km Past Station PENRITH NSW 2750	Penrith	01830	Built	HNSW
Emu Plains (Nepean River) Underbridge	Off Bruce Neale Dr, Steel Trusses 1.3 Km Past Station PENRITH NSW 2750	Penrith		Built	SGOV
Emu Plains Assembly Hall	283 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Emu Plains Correctional Centre	Old Bathurst Road EMU PLAINS NSW 2750	Penrith		Built	SGOV
Emu Plains Correctional Centre - Manager of Industries Office	Old Bathurst Road EMU PLAINS NSW 2750	Penrith		Built	SGOV
Emu Plains Public School (former) and trees	207-219 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Emu Plains Railway Culvert	Lamrock Street EMU PLAINS NSW 2750	Penrith		Built	SGOV
Emu Plains Railway Station group	Main Western railway EMU PLAINS NSW 2750	Penrith	01136	Complex / Group	HNSW
Emu Plains Railway Station Group	Mackellar Street EMU PLAINS NSW 2750	Penrith		Built	SGOV
Emu Plains Railway Station group	Main Western Railway, Station Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Explorers Memorial	Memorial Avenue PENRITH NSW 2750	Penrith		Built	LGOV

Explosives storehouse	146 Dunheved Circuit ST MARYS NSW 2760	Penrith		Built	LGOV
Fairlight Homestead & Barn	Fairlight Road MULGOA NSW 2745	Penrith	00262	Landscape	HNSW
Farmhouse	361 Ninth Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
Farmhouse	170 Sixth Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
Farmhouse (collapsed) and outbuildings	2-22 Springwood Road AGNES BANKS NSW 2753	Penrith		Built	LGOV
Farmhouse,garden planting and natural vegetation	259A-263 Church Lane CASTLEREAGH NSW 2749	Penrith		Built	LGOV
Federation cottage	80 Woodriff Street PENRITH NSW 2750	Penrith		Built	LGOV
Federation farmhouse	330 Eighth Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
Federation farmhouse and trees	706 Castlereagh Road AGNES BANKS NSW 2753	Penrith		Built	LGOV
Federation House	9 Railway Row EMU PLAINS NSW 2750	Penrith		Built	LGOV
Federation house and garden	6 First Street KINGSWOOD NSW 2747	Penrith		Built	LGOV
Fernhill	Mulgoa Road MULGOA NSW 2745	Penrith	00054	Landscape	HNSW
Ferry crossing	Nepean River - Ferry Road PENRITH NSW 2750	Penrith		Built	LGOV
Ferry Crossing	Punt Road, Nepean River EMU PLAINS NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Fire and Rescue NSW Heritage Fleet	Museum Drive PENRITH NSW 2750	Penrith	01902	Movable / Collection	HNSW
Ford 21W Fire Brigade Mobile Canteen (1942)	Museum Drive PENRITH NSW 2750	Penrith	01900	Movable / Collection	HNSW
Former Penrith Brick Company - kiln and chimney	Copeland Street KINGSWOOD NSW 2747	Penrith		Archaeological- Terrestrial	LGOV

Fossil Collection	947-953 Londonderry Road LONDONDERR Y NSW 2753	Penrith	00971	Movable / Collection	HNSW
Four Winds	Great Western Highway WERRINGTON NSW 2747	Penrith		Built	SGOV
Fulton's Store (former)	413-423 High Street PENRITH NSW 2750	Penrith		Built	LGOV
Gateposts to Colesbrook	269-285 Mamre Road KEMPS CREEK NSW 2178	Penrith		Built	LGOV
Glenleigh Estate	427 Mulgoa Road REGENTVILLE NSW 2745	Penrith	00346	Landscape	HNSW
Glenmore	754-760 Mulgoa Road MULGOA NSW 2745	Penrith	00074	Landscape	HNSW
Gosling Street and Hessel Place Reserves	22 Gosling Street EMU HEIGHTS NSW 2750	Penrith		Landscape	LGOV
Gothic revival cottage	24 Princess Mary Street ST MARYS NSW 2760	Penrith		Built	LGOV
Government stockyard site	Hunter, Yodalla, Annette & Nepean Streets &River Road EMU PLAINS NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Governor Phillip Special Hospital - original building	64 Glebe Place PENRITH NSW 2750	Penrith		Built	LGOV
Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Hadley Park	14-278 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith	02009	Landscape	HNSW
Hadley Park	RMB 113 Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Landscape	GAZ
Hadley Park Homestead	14 -278 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	LGOV

High Street shop	538-540 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	550-556 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	371-375 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	377-381 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	383 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	387-389 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	391-393 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	425 - 427 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	449-451 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	542 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	437 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shops	361-365 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Archaeological- Terrestrial	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV

Hornseywood Avenue Conservation Area	Brown, Derby and Castlereagh Street, Penrith PENRITH NSW 2750	Penrith	Conservation Area	LGOV
House	43 Park Avenue KINGSWOOD NSW 2747	Penrith	Built	LGOV
House (Hall family)	13 Hessel Place EMU HEIGHTS NSW 2750	Penrith	Built	LGOV
International style house and garden	10 River Road EMU PLAINS NSW 2750	Penrith	Built	LGOV
Irrigation channel	Mulgoa Road, Queenshill Drive, Littlefields Road and The Northern Road MULGOA NSW 2745	Penrith	Archaeological- Terrestrial	LGOV
Johnson's Cottage	Nepean Street CRANEBROOK NSW 2749	Penrith	Built	LGOV
Kingswood Public School	46-54 Second Avenue KINGSWOOD NSW 2747	Penrith	Built	LGOV
Kingswood Public School - Building B00B	46-54 Second Avenue KINGSWOOD NSW 2747	Penrith	Built	SGOV
Landers Inn and Stone Stables Ruins	14 - 278 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Lawson Footbridge	East of Station At 94.93 Km, Old Overbridge LAWSON NSW 2783	Penrith	Built	SGOV
Leeholme Horse Stud Rotunda	391-395 Mamre Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Lemongrove Conservation Area	Lemongrove Road, Macquarie Avenue, Hemmings Street and The Crescent, Penrith PENRITH NSW 2750	Penrith	Conservation Area	LGOV
Lemongrove Lodge	22-24 Lemongrove Road PENRITH NSW 2750	Penrith	Built	LGOV

Lewers Bequest & Regional Art Gallery, houses and garden	84-88 River Road EMU PLAINS NSW 2750	Penrith		Built	LGOV
Little	EMU PLAINS NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Llandilo Community Hall	257C Seventh Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
Llandilo Public School	222 Seventh Avenue LLANDILO NSW 2747	Penrith		Unknown	LGOV
Llandilo Public School - Building B00F	222 Seventh Avenue LLANDILO NSW 2747	Penrith		Built	SGOV
Londonderry Cemetery	325-331 Londonderry Road LONDONDERR Y NSW 2753	Penrith		Archaeological- Terrestrial	LGOV
Luddenham Homestead site	1-9 Park Road WALLACIA NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Luddenham Progress Hall	3091-3095 The Northern Road LUDDENHAM NSW 2745	Penrith		Built	LGOV
Luddenham Road Alignment	Luddenham Road LUDDENHAM NSW 2745	Penrith		Built	LGOV
Luddenham Uniting Church and Cemetery	3097-3099 The Northern Road LUDDENHAM NSW 2745	Penrith		Complex / Group	LGOV
Luddenham Uniting Church Cemetery	The Northern Road LUDDENHAM NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Mamre	181-275 Mamre Road ORCHARD HILLS NSW 2748	Penrith		Complex / Group	LGOV
Mamre	Mamre Road ST MARYS NSW 2760	Penrith	00264	Landscape	HNSW
Mamre	Mamre Road ORCHARD HILLS NSW 2748	Penrith		Built	SGOV
Margaret Farm & Barn	Pages Road ST MARYS NSW 1790	Penrith		Built	SGOV
McCarthys Cemetery	McCarthys Lane CASTLEREAGH NSW 2749	Penrith		Archaeological- Terrestrial	GAZ

McCarthys Cemetery and Trees	Lot 82 McCarthys Lane CASTLEREAGH NSW 2749	Penrith	Archaeological- Terrestrial	LGOV
McCarthys Farm Archaeological remains (Demolished)	145-237 McCarthys Lane CRANEBROOK NSW 2749	Penrith	Complex / Group	LGOV
McGarvie-Smith Farm	1793-1951 Elizabeth Drive BADGERYS CREEK NSW 2555	Penrith	Built	LGOV
Melrose Hall	169 Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	LGOV
Memorial cairn	181-275 Mamre Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Memorial cairn	Luddenham Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Memorials and lamp stand, St Nicholas of Myra Catholic Church	332-338 High Street PENRITH NSW 2750	Penrith	Complex / Group	LGOV
Memorials- Smith Park	1151-1159 Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Memory Park	400 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Methodist Cemetery	CASTLEREAGH NSW 2749	Penrith	Complex / Group	GAZ
Methodist Church (former)	74 Henry Street PENRITH NSW 2750	Penrith	Built	LGOV
Milestone	Great Western Highway (between Marsden Road and Day Street) ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
Milestone	Great Western Highway CLAREMONT MEADOWS NSW 2747	Penrith	Built	LGOV
Milestone	Great Western Highway KINGSWOOD NSW 2747	Penrith	Built	LGOV

	1	1		1	
Milestone	Great Western Highway KINGSWOOD NSW 2747	Penrith		Built	LGOV
Milestone	Great Western Highway COLYTON NSW 2760	Penrith		Built	LGOV
Moore Cottage	8 Sainsbury Street ST MARYS NSW 2760	Penrith		Built	LGOV
Mulgoa Irrigation Company office and police station (former)	1298-1304 Mulgoa Road MULGOA NSW 2745	Penrith		Built	LGOV
Mulgoa Public School - Buildings B00A and B00C and Significant Trees	1189-1193 Mulgoa Road MULGOA NSW 2745	Penrith		Built	SGOV
Mulgoa Public School building, hall, residence and trees	1189-1193 Mulgoa Road MULGOA NSW 2745	Penrith		Complex / Group	LGOV
Mulgoa Road Alignment (former)	St Thomas Road MULGOA NSW 2745	Penrith		Built	LGOV
Mulgoa Road Conservation Area	1582-1586 & 1581-1587 Mulgoa Road WALLACIA NSW 2745	Penrith		Conservation Area	LGOV
Natural Area	Rickards Ave AGNES BANKS NSW 2753	Penrith		Landscape	SGOV
Natural Area	Rickards Avenue AGNES BANKS NSW 2753	Penrith	00649	Landscape	HNSW
Nepean Park	Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Landscape	GAZ
Nepean Park - Homestead,Garden and Trees	1404(a) Closed Road off Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	LGOV
North St Marys Staff Cottages Conservation Area	Forrester Road NORTH ST MARYS NSW 2760	Penrith		Conservation Area	LGOV
NSW Fire Brigades Heritage Fleet	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
NSW Fire Brigades No 10 Vehicle Number Plates	Castlereagh Road PENRITH NSW 2750	Penrith	01519	Movable / Collection	HNSW

NSWFB 'No. 10' Vehicle Number Plates	1 Museum Drive PENRITH NSW 2750	Penrith	Movable / Collection	SGOV
Old Police Station	Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	SGOV
Olive trees	68 Soling Crescent CRANEBROOK NSW 2749	Penrith	Complex / Group	LGOV
Orchard Hills Reservoir (WS 0083)	Castle Road ORCHARD HILLS NSW 2748	Penrith	Built	SGOV
Orchard Hills Uniting Church	3 Frogmore Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Original building	Glebe Place PENRITH NSW 2750	Penrith	Built	SGOV
Park Road Conservation Area	22-26 Park Road WALLACIA NSW 2745	Penrith	Conservation Area	LGOV
Parkers Slaughter Yard	Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Archaeological- Terrestrial	LGOV
Peach Tree Creek Bridge	Great Western Highway PENRITH NSW 2750	Penrith	Built	SGOV
Peachtree Creek Bridge	Peachtree Creek PENRITH NSW 2750	Penrith	Archaeological- Terrestrial	LGOV
Penrith Administrative Office - Building B00M	57 Henry Street PENRITH NSW 2750	Penrith	Built	SGOV
Penrith Ambulance Station	668-672 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Penrith Council Chambers (former)	129-133 Henry Street PENRITH NSW 2750	Penrith	Built	LGOV
Penrith General Cemetery	Land bounded by Copeland and Phillips Streets, Richmond Road and Cox Avenue KINGSWOOD NSW 2747	Penrith	Archaeological- Terrestrial	LGOV
Penrith Infants Department (1884 building)	57 Henry Street PENRITH NSW 2750	Penrith	Built	LGOV
Penrith Power Station (former)	1 Museum Drive PENRITH NSW 2750	Penrith	Built	LGOV

Penrith Public School - Building B00A and Significant Trees	194 High Street PENRITH NSW 2750	Penrith		Built	SGOV
Penrith Public School and palm trees	194 High Street PENRITH NSW 2750	Penrith		Complex / Group	LGOV
Penrith Railway Station group	Railway land, Jane Street PENRITH NSW 2750	Penrith		Built	LGOV
Penrith Railway Station group	Great Western Railway PENRITH NSW 2750	Penrith	01222	Complex / Group	HNSW
Penrith Railway Station Group and Residence	Station Street PENRITH NSW 2750	Penrith		Built	SGOV
Penrith School of Arts (former)	7 Castlereagh Street PENRITH NSW 2750	Penrith		Built	LGOV
Penrith Weir	Bruce Neale Drive PENRITH NSW 2750	Penrith		Built	SGOV
Petrology Collection	947-953 Londonderry Road LONDONDERR Y NSW 2753	Penrith	00973	Movable / Collection	HNSW
Pise House Ruins	198-202 Church Lane CASTLEREAGH NSW 2749	Penrith		Built	LGOV
Police station (Former)	30 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Police station residence (former)	4 Punt Road EMU PLAINS NSW 2750	Penrith		Built	LGOV
Poplars Garden (The)	Wrights Lane CRANEBROOK NSW 2749	Penrith		Landscape	LGOV
Poplars Pise House (The)	Wrights Lane CRANEBROOK NSW 2749	Penrith		Built	LGOV
Presbyterian manse (former)	154 Derby Street PENRITH NSW 2750	Penrith		Built	LGOV
Prospect Electricity building (former)	59 Station Street PENRITH NSW 2750	Penrith		Built	LGOV
Pumping station (former)	20 Memorial Avenue PENRITH NSW 2750	Penrith		Built	LGOV
Railway bridge	Over Nepean River PENRITH NSW 2750	Penrith		Complex / Group	LGOV

Rectory (former)	95 Glebe Place PENRITH NSW 2750	Penrith		Built	LGOV
Red Cow Hotel	569-595 High Street PENRITH NSW 2750	Penrith		Built	LGOV
Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith		Complex / Group	SGOV
Regentville Mansion (site) and vineyard terracing	460a-626 Mulgoa Road MULGOA NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Regentville Public School - Buildings B00A and B00K and Landscape	32-34 School House Road REGENTVILLE NSW 2745	Penrith		Built	SGOV
Regentville Public School, residence and garden	32-34 School House Road REGENTVILLE NSW 2745	Penrith		Built	LGOV
Regentville Windmill site	127-129 and 131 -135 Martin Street REGENTVILLE NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Regentville Workers' Terrace	1 Bundarra Road REGENTVILLE NSW 2745	Penrith		Built	LGOV
Remnants and Service Pit; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Rose Cottage and Early Slab Hut	Water Street WERRINGTON NSW 2747	Penrith	01392	Complex / Group	HNSW
Rose Cottage and early slab hut	Corner Water Street and Tennant Road WERRINGTON NSW 2747	Penrith		Complex / Group	LGOV
Rose Cottage and Slab Hut	Water Street WERRINGTON NSW 2747	Penrith		Built	SGOV
Rotunda	Luddenham Road NYAH VIC 3594	Penrith		Built	SGOV
Rowing course	Nepean River PENRITH NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Sandstone cottage	281 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV

Sandstone railway culvert	Lamrock Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Sawmill Precinct	ST MARYS NSW 2760	Penrith		Archaeological- Terrestrial	LGOV
Scarred tree and Aboriginal artefact scatter	Lot 2000 Bradley Street GLENMORE PARK NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Services Pit; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Shand Mason 7 inch Manual Fire Engine (1869)	1 Museum Drive PENRITH NSW 2750	Penrith	01898	Movable / Collection	HNSW
Shand Mason Curricle Ladders (1898)	1 Museum Drive PENRITH NSW 2750	Penrith	01899	Movable / Collection	HNSW
Shand Mason Fire Engine (1891)	Museum Drive PENRITH NSW 2750	Penrith	01716	Movable / Collection	HNSW
Shop	373 Great Western Highway ST MARYS NSW 2760	Penrith		Built	LGOV
Showground	428-452 Park Road LUDDENHAM NSW 2745	Penrith		Complex / Group	LGOV
Sir John Jamison Cemetery	14B Lilac Place JAMISONTOWN NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Site of Castlereagh township	East Wilchard Road and Church Lane CASTLEREAGH NSW 2749	Penrith		Landscape	LGOV
Site of Edinglassie	Lapstone Place LEONAY NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Site of Fulton's Church and School	184-194 Church Street CRANEBROOK NSW 2749	Penrith		Built	LGOV
Site of Mill; Neranie	Neranie Road Myall Lakes National Park BUNGWAHL NSW 2423	Penrith		Archaeological- Terrestrial	SGOV
Sites of Early Water Mills	CASTLEREAGH NSW 2749	Penrith		Built	LGOV

Slab Cottage & Buddladack	14-278 Old	Penrith	Built	LGOV
Slab Cottage & Puddledock (remains)	Castlereagh Road CASTLEREAGH NSW 2749			
Slab cottage site	1177-1187 Mulgoa Road MULGOA NSW 2745	Penrith	Archaeological- Terrestrial	LGOV
South Creek Bridge (Eastbound)	Great Western Highway ST MARYS NSW 2760	Penrith	Built	SGOV
St Andrew's Anglican Church (former)	25 Park Road WALLACIA NSW 2745	Penrith	Built	LGOV
St Aubyn's Terrace	255-265 High Street PENRITH NSW 2750	Penrith	Built	LGOV
St James Anglican Church and Cemetery	3101-3125 The Northern Road LUDDENHAM NSW 2745	Penrith	Complex / Group	LGOV
St Mary Magdalene Church, Hall, Cemetery and grounds	299-311 Great Western Highway ST MARYS NSW 2760	Penrith	Built	LGOV
St Marys Catholic Church	1262 - 1266 Mulgoa Road MULGOA NSW 2745	Penrith	Built	LGOV
St Marys Council Chambers (former)	2-6 Mamre Road ST MARYS NSW 2760	Penrith	Built	LGOV
St Marys General Cemetery	175-191 Great Western Highway ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
St Marys Public School	2-6 Princess Mary Street ST MARYS NSW 2760	Penrith	Built	LGOV
St Marys Public School - Building B00G, Residence, Grounds and Significant Trees	2-6 Princess Mary Street ST MARYS NSW 2760	Penrith	Built	SGOV
St Marys Railway Station	Corner Station and Queen Streets ST MARYS NSW 2760	Penrith	Complex / Group	LGOV
St Marys Railway Station Group	Queen Street ST MARYS NSW 2760	Penrith	Built	SGOV
St Pauls Anglican Cemetery	EMU PLAINS NSW 2750	Penrith	Archaeological- Terrestrial	LGOV

St Paul's Anglican Church and Emu Plains General Cemetery	Land bounded by Short, Mundy and Nixon Streets and Great Western Railway EMU PLAINS NSW 2750	Penrith		Complex / Group	LGOV
St Phillip's Anglican Church	32 Bringelly Road KINGSWOOD NSW 2747	Penrith		Built	LGOV
St Stephen's Anglican Church, Hall and Cemetery	258-280 High Street PENRITH NSW 2750	Penrith		Complex / Group	LGOV
St Thomas' Anglican Church (former) and Palm trees	540A-544A Cranebrook Road CRANEBROOK NSW 2749	Penrith		Landscape	LGOV
St Thomas' Anglican Church and Cemetery	43-57 St Thomas Road MULGOA NSW 2745	Penrith		Complex / Group	LGOV
St. David's Anglican Church (former)	257B Seventh Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
St. Mary Magdalene Cemetery	King Street ST MARYS NSW 1790	Penrith		Archaeological- Terrestrial	LGOV
St. Marys Railway Station Group	Great Western Railway ST MARYS NSW 2760	Penrith	01249	Complex / Group	HNSW
St. Marys Railway Station Parcels Office	Queen Street ST MARYS NSW 1790	Penrith		Built	LGOV
St. Stephens Cemetery	High Street PENRITH NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
St. Stephens Church Hall	High Street PENRITH NSW 2750	Penrith		Built	LGOV
St. Thomas Anglican Church	St Thomas Road MULGOA NSW 2745	Penrith	00426	Complex / Group	HNSW
State Records Movable Heritage - Furniture	143 O'Connell Street KINGSWOOD NSW 2747	Penrith		Movable / Collection	SGOV
State Records Movable Heritage - Memorials	143 O'Connell Street KINGSWOOD NSW 2747	Penrith		Movable / Collection	SGOV
Station Master's House (former)	Jane Street PENRITH NSW 2750	Penrith		Built	LGOV

Stone House	143 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Sydney Water Supply Canal	Camden Valley Way and Elizabeth Drive (between) LIVERPOOL NSW 2170	Liverpool		Complex / Group	GAZ
Table Rock Lookout	716-782 Fairlight Road MULGOA NSW 2745	Penrith		Landscape	LGOV
TAFE Building	115-119 Henry Street PENRITH NSW 2750	Penrith		Built	LGOV
TAFE NSW Penrith Campus	115-119 Henry Street PENRITH NSW 2750	Penrith		Built	SGOV
Teacher's residence (former)	56 Second Avenue KINGSWOOD NSW 2747	Penrith		Built	LGOV
The Fleurs Radio Telescope Site	885(a) Mamre Road KEMPS CREEK NSW 2178	Penrith		Unknown	LGOV
The Lodge	48-56 Leland Street PENRITH NSW 2750	Penrith		Built	LGOV
The Poplars - Old Slab Cottage, Pise House and Garden	108-110 Wrights Lane CASTLEREAGH NSW 2749	Penrith		Complex / Group	LGOV
The Willows - House	65 Mulgoa Road PENRITH NSW 2750	Penrith		Built	LGOV
Thompsons Tannery (Former)	ST MARYS NSW 2760	Penrith		Archaeological- Terrestrial	LGOV
Thompson's Tannery site (former)	Saddington Street ST MARYS NSW 2760	Penrith		Archaeological- Terrestrial	LGOV
Thornton Hall	Thornton House 33 Mountain View Crescent, Penrith PENRITH NSW 2750	Penrith		Built	LGOV
Torin building	26 Coombes Drive PENRITH NSW 2750	Penrith		Built	LGOV
Torin Building	26 Coombes Drive PENRITH NSW 2750	Penrith	01796	Built	HNSW


Torquay	555 Great Western Highway WERRINGTON NSW 2747	Penrith		Built	SGOV
Union Inn (former) and trees	36-42 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Uniting Church	5-7 Emerald Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Upper Castlereagh Methodist Church and Hall	CASTLEREAGH NSW 2749	Penrith		Built	GAZ
Upper Castlereagh Public School	Castlereagh Road CASTLEREAGH NSW 2749	Penrith	00339	Built	HNSW
Upper Castlereagh Public School and Residence	312 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	SGOV
Upper Castlereagh Public School and Residence	312-314 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	SGOV
Upper Castlereagh Public School Hall & Residence	312 -316 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Complex / Group	LGOV
Upper Castlereagh School and Residence	CASTLEREAGH NSW 2749	Penrith		Built	GAZ
Upper Castlereagh War Memorial	280a Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Archaeological- Terrestrial	LGOV
Victoria Bridge	Great Western Highway PENRITH NSW 2750	Penrith		Built	GAZ
Victoria Bridge	Great Western Highway PENRITH NSW 2750	Penrith		Built	LGOV
Victoria Bridge	Nepean River, Great Western Highway PENRITH NSW 2750	Penrith	01950	Built	HNSW
Victoria Bridge over Nepean River	Great Western Highway PENRITH NSW 2750	Penrith		Built	SGOV

Victoria Park and memorial	Boiunded by Great Western Highway, Pages Road, Putland and Princess Mary Streets ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
Victoria Park War Memorial	ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
Victorian cottage	163 Derby Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian cottage	194 Derby Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian farmhouse	46-54 Grays Lane CRANEBROOK NSW 2749	Penrith	Built	LGOV
Victorian Farmhouse	1188-1200 Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Victorian house	2083-2089 Castlereagh Road PENRITH NSW 2750	Penrith	Built	LGOV
Victorian house	6 Rawson Avenue PENRITH NSW 2750	Penrith	Built	LGOV
Victorian house	148 Station Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian house, dwelling and camphour laurel tree	50 Warwick Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian terrace and Interwar shop	219-221 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian villa	150 Lethbridge Street PENRITH NSW 2750	Penrith	Built	LGOV
Vineyard; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Archaeological- Terrestrial	SGOV
Wagon Wheel Hotel	449 Great Western Highway ST MARYS NSW 2760	Penrith	Built	LGOV
Wallacia Hotel	1590-1594 Mulgoa Road WALLACIA NSW 2745	Penrith	Built	LGOV

Wallacia Post Office	1589 Mulgoa Road WALLACIA NSW 2745	Penrith	Uı	nknown	LGOV
Wallacia Progress Association Hall	40 Greendale Road WALLACIA NSW 2745	Penrith	Uı	nknown	LGOV
Wallacia Public School	1573-1585 Mulgoa Road WALLACIA NSW 2745	Penrith	В	uilt	LGOV
Wallacia Public School - Building B00B and B00D	1573-1585 Mulgoa Road WALLACIA NSW 2745	Penrith	Ві	uilt	SGOV
Wallacia Weir	WALLACIA NSW 2745	Penrith		omplex / roup	GAZ
War Memorial, Emu Park	Great Western Highway, Lawson and Park Streets EMU PLAINS NSW 2750	Penrith	В	uilt	LGOV
Warwick Street Conservation Area	Warwick Street PENRITH NSW 2750	Penrith		onservation rea	LGOV
Water reservoir	197-207 Castle Road ORCHARD HILLS NSW 2748	Penrith	В	uilt	LGOV
Weatherboard cottage	410-450 Castlereagh Road AGNES BANKS NSW 2753	Penrith	В	uilt	LGOV
Weatherboard cottage	20 Princess Mary Street ST MARYS NSW 2760	Penrith	В	uilt	LGOV
Weatherboard cottage	22 Princess Mary Street ST MARYS NSW 2760	Penrith	В	uilt	LGOV
Weatherboard cottage	41-43 Camden Street PENRITH NSW 2750	Penrith	В	uilt	LGOV
Weatherboard cottage	24 Forbes Street EMU PLAINS NSW 2750	Penrith	В	uilt	LGOV
Weatherboard cottage	71 Parker Street PENRITH NSW 2750	Penrith	В	uilt	LGOV
Weatherboard Cottage	1296 Mulgoa Road MULGOA NSW 2745	Penrith		omplex / roup	LGOV

Weatherboard Cottage	3075 The Northern Road LUDDENHAM NSW 2745	Penrith	Built	LGOV
Weatherboard house	66-70 Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	LGOV
Weir	Bruce Neil Drive, Nepean River PENRITH NSW 2750	Penrith	Built	LGOV
Wool Pack Inn (ruin)	556 Great Western Highway ST MARYS NSW 2760	Penrith	Built	LGOV
Wool Pack Inn (Ruin)	556 Great Western Highway ST MARYS NSW 1790	Penrith	Built	SGOV
Workmen's Cottages	56-62 Mulgoa Road JAMISONTOWN NSW 2750	Penrith	Built	LGOV

537 - Penrith Lakes Native Title Vision Web Map



Sources: Esri, TomTom, Garmin, FAO, NOAA, USGS, \circledcirc OpenStreetMap contributors, and the GIS User Community, Esri, Geoscience Australia, NASA, NGA, USGS

0.2

0.1

0.4 km

Search Results

50 results found.

ADI Site Western Precinct The Northern Rd	Llandilo, NSW, Australia	(<u>Place rejected for emergency</u> <u>listing</u>) National Heritage List
Agnes Banks Nature Reserve and Adjoining Areas Rickards Rd	Agnes Banks, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh Area	Upper Castlereagh, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh Cemetery Church St	Cranebrook, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh Jewel Beetle Habitat and Movement Corridor The Northern Rd	Berkshire Park, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh State Forest and Adjacent Area The Northern Rd	Berkshire Park, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Combewood, Outbuildings and Garden 306 RMB Castlereagh Rd	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only. no statutory basis) Register of the National Estate (Non-statutory archive)
Cranebrook Airservices Land Cranebrook Rd	Cranebrook, NSW, Australia	(<u>Ineligible place</u>) Commonwealth Heritage List

Emu Plains Community Arts Centre Great Western Hwy	Emu Plains, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Fernhill Mulgoa Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Fernhill Setting Mulgoa Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Former ADI Site The Northern Rd	Llandilo, NSW, Australia	(Nomination now ineligible for PPAL) National Heritage List
Glen Leigh and Outbuildings Mulgoa Rd	Regentville, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Glenmore Mulgoa Rd	Regentville, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Greater Blue Mountains Area Great Western Hwy	Katoomba, NSW, Australia	(<u>Declared property</u>) World Heritage List
Homestead Site & Windbreak Soling Cr	Mount Pleasant, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Indigenous Place	Blaxland, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)

Indigenous Place Yarramundi, NSW, (Indicative place before RNE Australia closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive) Jordan Hill Site North St Marys, NSW, (Destroyed before RNE closed. Australia Record for reference only, no statutory basis Register of the National Estate (Non-statutory archive) King Family Farm Sites and Trees Links Rd North St Marys, NSW, (Included place before RNE Australia closed. Record for reference only, no statutory basis Register of the National Estate (Non-statutory archive) King Family Farm Sites and Trees Links Rd North St Marys, NSW, (Ineligible place) Australia Commonwealth Heritage List King Family Farm Sites and Trees Links Rd St Marys, NSW, (Nomination now ineligible for Australia PPAL) National Heritage List St Clair, NSW, Mamre and Curtilage Mamre Rd (Included place before RNE Australia closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive) McGarvie Smith University Farm 124 Elizabeth Dve Badgerys Creek, NSW, (Nomination now ineligible for Australia PPAL) National Heritage List Minnaville Castlereagh Rd Castlereagh, NSW, (Indicative place before RNE Australia closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive) Mulgoa Group and Landscape Mulgoa Rd Mulgoa, NSW, (Included place before RNE Australia closed. Record for reference only, no statutory basis Register of the National Estate (Non-statutory archive)

Mulgoa Natural Area Sir John Jamison Cirt	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Museum of Fire Castlereagh Rd	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Nepean Park Castlereagh Rd	Castlereagh, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Orchard Hills Cumberland Plain Woodland The Northern Rd	Orchard Hills, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Orchard Hills Cumberland Plain Woodland The Northern Rd	Orchard Hills, NSW, Australia	(<u>Listed place</u>) Commonwealth Heritage List
Osborne Castlereagh Rd	Agnes Banks, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Penrith Courthouse (former) High St	Penrith, NSW, Australia	(Destroyed before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
St Mary Magdalene Anglican Church & Cemetery Great Western Hwy	St Marys, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)

J. 12 1 WI	Australian Hentage Database	
St Marys Permanent Cottage Area	St Marys, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
St Stephens Anglican Church & Graveyard 252 High St	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
St Thomas Anglican Church & Cemetery St Thomas Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
The Cottage St Thomas Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only. no statutory basis) Register of the National Estate (Non-statutory archive)
The Greater Blue Mountains Area Greater Western Hwy	Katoomba, NSW, Australia	(<u>Listed place</u>) National Heritage List
The Greater Blue Mountains Area - Additional Values and Areas Great Wester	rn Hwy Katoomba, NSW, Australia	(<u>Nominated place</u>) National Heritage List
The Lewers Bequest & Penrith Regional Art Gallery & Garden 86 River Rd	Emu Plains, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Thornton Hall & Surrounds 11 Mountain View Cr	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Thornton Hall & Surrounds 11 Mountain View Cr	Penrith, NSW, Australia	(Place removed from CHL) Commonwealth Heritage List
Thornton Hall and Surrounds (former Defence land) 11 Mountain View Co	r Penrith, NSW, Australia	(Place removed from CHL) Commonwealth Heritage List


J. 12 FW Au	Stratian rientage Database	
Upper Room Chapel, Hall and Cemetery 1727 Castlereagh Rd	Castlereagh, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
victoria Bridge Great Western Hwy	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
<u>Wara-n'hayara Plateau Area - part</u> Mount Kiera Rd	Wollongong, NSW, Australia	(<u>Place not included in NHL</u>) National Heritage List
Werrington House Rugby Street	Werrington County, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Western Sydney Shale Woodland St Marys Forrester Rd	St Marys, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Western Sydney Shale Woodland St Marys Forrester Rd	St Marys, NSW, Australia	(<u>Ineligible place</u>) Commonwealth Heritage List

Report Produced: Thu Jul 17 15:12:23 2025

Accessibility | Disclaimer | Privacy | © Commonwealth of Australia



537 - Penrith Lakes Native Title Vision Web Map



Sources: Esri, TomTom, Garmin, FAO, NOAA, USGS, \circledcirc OpenStreetMap contributors, and the GIS User Community, Esri, Geoscience Australia, NASA, NGA, USGS

0.2

0.1

0.4 km

Penrith Local Environmental Plan 2010

Current version for 20 May 2024 to date (accessed 17 July 2025 at 14:57)

Schedule 5

Schedule 5 Environmental heritage

(Clause 5.10)

Part 1 Heritage items

Suburb	Item name	Address	Property description	Significance	e Item no
Agnes Banks	Castlereagh Road Alignment	Castlereagh Road		Local	261
Agnes Banks	Weatherboard cottage	410-450 Castlereagh Road	Lot 10, DP 792357	Local	660
Agnes Banks	Agnes Banks Public School (former)	475–479 Castlereagh Road	Lot 1, DP 776886	Local	3
Agnes Banks	"Osborne", homestead, barn, outbuildings and plantings	580–600 Castlereagh Road	Lot 1, DP 1155198	Local	6
Agnes Banks	"Chestnut", dwelling, slab cottage and trees	580–600 Castlereagh Road	Lot 1, DP 1155198	Local	8
Agnes Banks	"Tyreel", dwelling and barn	626-652 Castlereagh Road	Lot 1, DP 739177	Local	10
Agnes Banks	Federation farmhouse and trees	706 Castlereagh Road	Lot 4, DP 570547	Local	12
Agnes Banks	Brick farmhouse, trees and orchard	850-856 Castlereagh Road	Lot 1, DP 228165	Local	659
Agnes Banks	Agnes Banks Nature Reserve	2 Geebung Close, e and 36-62 and 66-88 Rickards Road	Lots 149 and 157-159, DP 752021; Lot 7302, DP 1151861; Lot 12 DP 1049319	State ,	15

Agnes Banks	Farmhouse (collapsed) and outbuildings	2-22 Springwood Road	Lot 930, DP 1129072	Local	2
Castlereagh	Castlereagh Road Alignment	Castlereagh Road		Local	261
Castlereagh	Memorials—Smith Park	1151-1159 Castlereagh Road	Lots 1-3, DP 3784; Part Lot 58, DP 752021	Local	19
Castlereagh	Castlereagh Council Chambers (former)	1158-1160 Castlereagh Road	Lot 1, DP 198257	Local	18
Castlereagh	Christ Church Anglican Church	230–232 Church Lane	Lot 27, DP 581747	Local	28
Castlereagh	Farmhouse, garden planting and natural vegetation	259A-263 Church Lane	Lot 1000, DP 1100451	Local	26
Castlereagh	Castlereagh Public School (former)	13-25 West Wilchard Road	Lot 2, DP 780559	Local	20
Claremont Meadows	Milestone	Great Western Highway	Fronting Lot 1, DP 1126991	Local	859
Claremont Meadows	"Four Winds", dwelling	568 Great Western Highway	Part Lot 11, Section 24, DP 111110	Local	321
Colyton	Milestone	Great Western Highway	Fronting Lot 1 DP 538063	Local	862
Cranebrook	Cranebrook Public School (former)	216 Boundary Road	Lot 22, DP 809521	Local	40
Cranebrook	Site of Fulton's Church and School	184-194 Church Street	Lot 287, DP 999655; Lot 288, DP 999656	Local	31
Cranebrook	St Thomas' Anglican Church (former) and Palm trees	5/11/0-5/1/1/0	Lots 12-17, Section A, DP 1613	Local	42
Cranebrook	Castlereagh General Cemetery and native vegetation	77-85 East Wilchard Road	Lot 281, DP 752021	Local	32
Cranebrook	Victorian farmhouse	46-54 Grays Lane	Lot 12, DP 825320	Local	35
Cranebrook	Johnson's Cottage	Nepean Street	Lots 18-20, Section A, DP 1613	Local	41
Cranebrook	Olive trees	68 Soling Crescent	Lot 104, DP 261535	Local	39
Cranebrook	"Kenilworth", dwelling and trees	6-9 Tallowood Place	Lot 26, DP 855247	Local	36

Emu Heights	Gosling Street and Hessel Place Reserves	22 Gosling Street	Lot 22, DP 1076016	Local	89
Emu Heights	House (Hall family)	13 Hessel Place	Lot 22, DP 250032	Local	88
Emu Plains	Bellbird Reserve	29 Barina Crescent	Lot 101, DP 577779	Local	90
Emu Plains	"Huntington Hall", house and garden	48-52 Beach Street	Lots 12, 13 and 15, DP 243048	Local	71
Emu Plains	Uniting Church	5-7 Emerald Street	Lot 1, DP 650543	Local	82
Emu Plains	Weatherboard cottage	24 Forbes Street	Lot 22, DP 253187	Local	664
Emu Plains	Brick cottage	73 Forbes Street	Lot 181, DP 575962	Local	669
Emu Plains	War Memorial, Emu Park	Great Western Highway, Lawson and Park Streets	Lot 7051, DP 1055094	Local	75
Emu Plains	"Emu Hall", dwelling, outbuildings and trees	2–26 Great Western Highway	Lot 2, DP 614436	Local	51
Emu Plains	Union Inn (former) and trees	36-42 Great Western Highway	Part Lots 1 and 2, DP 342116	Local	63
Emu Plains	Weatherboard house	66–70 Great Western Highway	Lot 17, SP 71124	Local	60
Emu Plains	Australian Arms Inn (former)	113 Great Western Highway	Lot 11, DP 1056135	Local	61
Emu Plains	Arms of Australia Inn	127 Great Western Highway	Lot 22, DP 242300	Local	327
Emu Plains	Stone house	143 Great Western Highway	Lot 111, DP 242913	Local	64
Emu Plains	Melrose Hall	169 Great Western Highway	Lot 7040, DP 751662	Local	73
Emu Plains	Emu Plains Public School (former) and trees	207-219 Great Western Highway	Part Lot 1, DP 650753	Local	76
Emu Plains	Sandstone cottage	281 Great Western Highway	Lot 110, DP 802233	Local	84
Emu Plains	Emu Plains Assembly Hall	283 Great Western Highway	Lot 1, DP 780531	Local	85
Emu Plains	"Mountain View" house	39 Grey Street	Lot 1, DP 203655	Local	837

Emu Plains	Sandstone railway culvert	Lamrock Street		Local	667
Emu Plains	Concrete house	39a-43 Mackellar Street	Lot 980, DP 810551	Local	58
Emu Plains	"Westbank", house	2 Nepean Street	Lot 1, DP 620712	Local	65
Emu Plains	"Gwandalan", dwelling and garden	11 Nepean Street and 35 Cary Street	Lots 121 and 123, DP 807462	Local	92
Emu Plains	"Yodalla", house and garden	28 Nepean Street	Lot 42, DP 524161	Local	66
Emu Plains	"Yamba", cottage	32 Nixon Street	Lot 116, DP 242303	Local	80
Emu Plains	"Orange Grove", cottage	15 Park Street	Lot 1, DP 703497	Local	74
Emu Plains	Ferry crossing	Punt Road, Nepean River		Local	147
Emu Plains	Police station residence (former)	4 Punt Road	Lot 7038, DP 94188	Local	52
Emu Plains	International style house and garden	10 River Road	Lot B, DP 33205	Local	666
Emu Plains	Brick house and garden	80 River Road	Lot 2, DP 1024616	Local	151
Emu Plains	Lewers Bequest and Regional Art Gallery, houses and garden	84-88 River Road,	Lot 34, DP 1114973	Local	69
Emu Plains	Edwardian cottage	46 Russell Street	Lot 10, DP 1097496	Local	83
Emu Plains	St. Paul's Anglican Church and Emu Plains General Cemetery	Land bounded by Short, Mundy and Nixon Streets and the Great Western Railway	Lot 1, DP 724148; Lot 1, DP 798650; Lot G, DP 751662	Local	78
Emu Plains	Emu Plains Railway Station group	Main Western Railway, Station Street	Lot 1, DP 1133099	State	59
Emu Plains	"Killeen", Federation house	34 Walkers Crescent	Lot 104, DP 1006488	Local	840
Emu Plains	Cottage	14 York Street	Lot 1, DP 563123	Local	55
Glenmore Park	Scarred tree and Aboriginal artefact scatter	Lot 2000 Bradley Street	Lot 2000, DP 1204777	Local	878

Jamisontown	Sir John Jamison Cemetery	14b and 14c Lilac Place	Lot 1, DP 724391; Lot 1, DP 723986	Local	269
Jamisontown	Workmens' cottages	56-62 Mulgoa Road	Lots 1-4, SP 39546	Local	94
Kingswood	St. Phillip's Anglican Church	32 Bringelly Road	Lot 64, DP 752022	Local	101
Kingswood	Penrith General Cemetery	Land bounded by Copeland and Phillips Streets, Richmond Road and Cox Avenue	Lots 1-28, DP 975352	Local	97
Kingswood	Federation house and garden	6 First Street	Lot 101, DP 1032987	Local	100
Kingswood	Milestone	Great Western Highway	Fronting Lot 1, DP 866081	Local	860
Kingswood	Milestone	Great Western Highway	Fronting Lot 10, DP 719064	Local	861
Kingswood	House	43 Park Avenue	Lot B, DP 409139	Local	672
Kingswood	Kingswood Public School	46-54 Second Avenue	Lot 172, DP 839785	Local	98
Kingswood	Teacher's residence (former)	56 Second Avenue	Lot 2, DP 1130750	Local	670
Leonay	"Edinglassie", house	22 Bunyan Road	Lot 185, DP 233104	Local	108
Leonay	"Leo Buring" cottage, barn, glasshouse and memorial	3a Leonay Parade	Lot 12, DP 818741	Local	109
Llandilo	Federation farmhouse	330 Eighth Avenue	Lot 330, DP 2147	Local	676
Llandilo	Farmhouse	361 Ninth Avenue	Lot 3, DP 231946	Local	677
Llandilo	Llandilo Public School	222 Seventh Avenue	Lot 222, DP 2147	Local	841
Llandilo	St David's Anglican Church (former)	257B Seventh Avenue	Lot 1, DP 724335	Local	673
Llandilo	Llandilo Community Hall	257C Seventh Avenue	Lot 11, DP 1092204	Local	675
Llandilo	Cottage and outbuildings	268 Seventh Avenue	Lot 269, DP 2147	Local	113
Llandilo	Farmhouse	170 Sixth Avenue	Lot A, DP 390397	Local	842

Londonderry	Londonderry Cemetery	325–331 Londonderry Road	Lot 100, DP 810236	Local	115
Luddenham	Luddenham Road Alignment	Luddenham Road		Local	843
Mulgoa	"Passadena", house	45-61 Allan Road	Lot 1, DP 227674	Local	132
Mulgoa	"Fairlight", homestead, outbuildings and gardens	377-429 Fairlight Road	Lot 22, DP 625510	State	140
Mulgoa	Table Rock Lookout	716-782 Fairlight Road	Lot A, DP 164835	Local	141
Mulgoa	"Glenleigh", estate	427–507 Mulgoa Road	Lot 2, DP 563748	State	273
Mulgoa	"Glenmore"	754-760 Mulgoa Road	Lot 3, DP 701949	State	124
Mulgoa	"Fernhill", house, outbuildings and landscape	1041-1117 Mulgoa Road	Lots 10 and 11, DP 615085; Lot 2, DP 541825	State	128
Mulgoa	"Fernhill", curtilage	1147–1187 Mulgoa Road and 10–156 Mayfair Road	Lot 100, DP 717549; Lot 1, DP 570484; Lot 6, DP 173159; Lot 5, DP 23781; Lot 12, DP 610186; Lot 2, DP 211795; Lots 1-4, DP 260373	Local	873
Mulgoa	Mulgoa Public School building, hall, residence and trees	1189-1193 Mulgoa Road	Lot 1, DP 853475	Local	130
Mulgoa	St Mary's Catholic Church	1262-1266 Mulgoa Road	Lot 10, Section E, DP 2121	Local	133
Mulgoa	Weatherboard cottage	1296 Mulgoa Road	Lot 2, DP 226343	Local	134
Mulgoa	Mulgoa Irrigation Company office and police station (former)	1298-1304 Mulgoa Road	Lot 32, DP 585921	Local	135
Mulgoa	Cottage	1306 Mulgoa Road	Lot 39, Section A, DP 2882	Local	136
Mulgoa	"Winbourne", house	1315 Mulgoa Road	Lot 4, DP 854076	Local	138

Mulgoa	St Thomas' Anglican Church and Cemetery	43-57 and 59-119 St Thomas Road	Lot 1, DP 996994; Lot 1, DP 1035490	State	126
Mulgoa	Cox's Cottage	1012-1046 Mulgoa Road and 2-24 St Thomas Road	Lots 2-4, DP 241971	State	125
Mulgoa	Mulgoa Road Alignment (former)	St Thomas Road		Local	844
Orchard Hills	Brick farmhouse	80-88 Caddens Road	Lot 6, DP 1344	Local	155
Orchard Hills	"Lindfield"	182-188 Caddens Road	Lot 1, DP 583439	Local	845
Orchard Hills	Water reservoir	197–207 Castle Road	Lot 1, DP 430473	Local	657
Orchard Hills	Orchard Hills Uniting Church	3 Frogmore Road	Lot 101, DP 128254	Local	156
Orchard Hills	Memorial cairn	Luddenham Road		Local	230
Orchard Hills	Mamre	181–275 Mamre Road	Lot 1, DP 530579	State	228
Orchard Hills	Memorial cairn	181-275 Mamre Road	Lot 1, DP 530579	Local	229
Orchard Hills	Leeholme Horse Stud Rotunda	391-395 Mamre Road	Lot 2, DP 547057	Local	232
Penrith	"Craithes", dwelling, trees, outbuildings and carriage loop	34-40 Borec Road	Lot 2, DP 802406	State	161
Penrith	Weir	Bruce Neale Drive, Nepean River		Local	848
Penrith	Weatherboard cottage	41-43 Camden Street	Lot 13, DP 712385	Local	695
Penrith	Edwardian cottage	2068 Castlereagh Road	Lot 3, DP 862636	Local	158
Penrith	Victorian house	2083-2089 Castlereagh Road	Lot 1, DP 623919	Local	160
Penrith	Bennetts Wagons	2151(a) Castlereagh Road	Lot 112 DP 774782	Local	829
Penrith	Penrith School of Arts (former)	7 Castlereagh Street	Lots 9-11, Section 1, DP 1582	Local	692
Penrith	Torin building	26 Coombes Drive	Lot 401-403, DP 1162312	State	827

Penrith	"Combewood", house, garden, trees and original entrance drive	234-256 Coreen Avenue	Lot 2, DP 654378; Lots 51-55, DP 237090	Local	163
Penrith	Cottage	169 Cox Avenue	Lot A, DP 984462	Local	853
Penrith	Thornton Hall	Thornton House 33 Mountain View Crescent, Penrith	Lot 2032, DP 1181618	Local	166
Penrith	Presbyterian manse (former)	154 Derby Street	Lot 4, DP 25106	Local	697
Penrith	Victorian cottage	163 Derby Street	Lot Y, DP 389668	Local	698
Penrith	Victorian cottage	194 Derby Street	Lot 1, DP 2363	Local	699
Penrith	Ferry crossing	Nepean River—Ferry Road		Local	870
Penrith	Governor Phillip Special Hospital—original building	64 Glebe Place	Lot 1, DP 213072	Local	174
Penrith	Rectory (former)	95 Glebe Place	Lots 5 and 5A, DP 39162	Local	173
Penrith	Victoria Bridge	Great Western Highway		State	146
Penrith	Penrith Infants Department (1884 building)	57 Henry Street	Lot 1, DP 724160	Local	177
Penrith	Methodist Church (former)	74 Henry Street	Lot 22, DP 586469	Local	179
Penrith	TAFE Building	115-119 Henry Street	Lot 111, DP 1028320	Local	689
Penrith	Penrith Council Chambers (former)	129-133 Henry Street	Lot 1123, DP 1106979	Local	189
Penrith	"Kelvin Brae", Federation house	142 High Street	Lot 1, DP 1127355	Local	854
Penrith	Penrith Public School and palm trees	194 High Street	Lot 2, DP 502608; Lots 2-4, Section 19, DP 2296	Local	210
Penrith	Victorian terrace and Interwar shop	219-221 High Street	Lot 2, DP 224062	Local	212
Penrith	St Aubyn's Terrace	255-265 High Street	Lot 3, DP 955837; Lot 4, DP 972	Local	209

Penrith	St Stephen's Anglican Church, Hall and Cemetery	258-280 High Street	Lots 101 and 102, DP 597910	Local	206
Penrith	Cottage	288 High Street	Lot 1, Section 3, DP 1582	Local	723
Penrith	Brick villa	318-320 High Street	Lot 4, Section 2, DP 1582	Local	711
Penrith	Memorials and lamp stand, St Nicholas of Myra Catholic Church	332–338 High Street	Lot 1, DP 782278	Local	688
Penrith	"Cram Place", coach house, well, pump and cast iron fence	338-340 High Street	Lot 11, DP 1013730	Local	201
Penrith	Bank of NSW (former)	354-360 High Street	Lot 10, SP 51611	Local	713
Penrith	Australian Arms Hotel	359 High Street	Lot 2, DP 513015	Local	196
Penrith	High Street shops	361-365 High Street	Lots 2 and 4, SP 13804	Local	714
Penrith	High Street shop	371-375 High Street	Lot 13, DP 616937	Local	715
Penrith	High Street shop	377-381 High Street	Lot 12, DP 616937	Local	716
Penrith	High Street shop	383 High Street	Lot 11, DP 616937	Local	717
Penrith	High Street shop	387-389 High Street	Lot 1, DP 774671	Local	718
Penrith	High Street shop	391-393 High Street	Lots 23 and 24, DP 236390	Local	719
Penrith	Memory Park	400 High Street	Lot 1, DP 198339	Local	200
Penrith	Fulton's Store (former)	413-423 High Street	Lot B, DP 322318	Local	197
Penrith	High Street shop	425-427 High Street	Lot A, DP 322318	Local	720
Penrith	High Street shop	437 High Street	Lot 2, DP 82325	Local	855
Penrith	High Street shop	449-451 High Street	Lot 12, DP 599349	Local	721
Penrith	High Street shop	538-540 High Street	Lot 1, DP 779550	Local	198
Penrith	High Street shop	542 High Street	Lot 2, DP 154388	Local	722
Penrith	High Street shop	550-556 High Street	Lot B, DP 152524	Local	199
Penrith	Red Cow Hotel	569-595 High Street	Lot 1, DP 1137699	Local	690

Penrith	Penrith Ambulance Station	668-672 High Street	Lot 12, DP 37829	Local	256
Penrith	"Madang Park", farmhouse and trees	475–487 Jamison Road	Lot 2, DP 567225	Local	95
Penrith	Station Master's House (former)	Jane Street	Lot 31, DP 1086586	State	187
Penrith	Penrith Railway Station group	Railway land, Jane Street	Lot 31, DP 1086586	State	188
Penrith	The Lodge	48-56 Leland Street	Lot 5, DP 1049780	Local	159
Penrith	Lemongrove Lodge	22-24 Lemongrove Road	Lot 1C, DP 162091	Local	172
Penrith	Victorian villa	150 Lethbridge Street	Lot 81, DP 526298	Local	214
Penrith	Explorers Memorial	Memorial Avenue		Local	258
Penrith	Pumping station (former)	20 Memorial Avenue	Lot 1, DP 233967	Local	144
Penrith	Penrith Power Station (former)	1 Museum Drive	Lot 1306, DP 1234327	Local	259
Penrith	"Seidler", house	31-33 Nepean Avenue	Lot 1, DP 14827	Local	685
Penrith	Rowing course	Nepean River		Local	148
Penrith	Railway bridge	Over Nepean River		State	668
Penrith	Weatherboard cottage	71 Parker Street	Lot 1, DP 996540	Local	175
Penrith	Peachtree Creek Bridge	Peachtree Creek		Local	257
Penrith	Victorian house	6 Rawson Avenue	Lot 2, DP 206095	Local	253
Penrith	Prospect Electricity building (former)	59 Station Street	Lot 10, DP 1025026	Local	701
Penrith	"Broadville", Victorian house	98 Station Street	Lot 910, DP 717451	Local	215
Penrith	"Kentucky", villa	146 Station Street	Lot 11, DP 715161	Local	216
Penrith	Victorian house	148 Station Street	Lot 80, DP 709313	Local	217
Penrith	"The Cottage", dwelling and pine tree	39 Warwick Street	Lot 11, DP 663880	Local	251

Penrith	"Minnamurra", house	43 Warwick Street	Lot 1, DP 173533	Local	696
Penrith	Victorian house, dwelling and camphor laurel tree	50 Warwick Street	Lot 1, DP 21745	Local	250
Penrith	Federation cottage	80 Woodriff Street	Lot 18, DP 2167	Local	847
Regentville	Regentville Workers' Terrace	1 Bundarra Road	Lots 1, 2 and 19, DP 16540	Local	276
Regentville	Regentville Public School, residence and garden	32-34 School House Road	Lot 1, DP 906651	Local	270
St Marys	Dunheved Fire Station	50 Christie Street	Lot 142, DP 31911	Local	655
St Marys	Explosives storehouse	146 Dunheved Circuit	Lot 131, DP 701610	Local	869
St Marys	Brick cottage	38 Gidley Street	Lot 1, DP 783200	Local	298
St Marys	Brick cottage	40 Gidley Street	Lot 1, DP 710777	Local	797
St Marys	"Bronte", villa	50 Gidley Street	Lot 4, DP 38617	Local	299
St Marys	Bennett Wagon	Pioneer Park, Great Western Highway	Lot B, DP 371329	Local	805
St Marys	Milestone	Great Western Highway (between Marsden Road and Day Street)		Local	304
St Marys	Victoria Park and memorial	Bounded by Great Western Highway, Pages Road, Putland and Princess Mary Streets	Lot 1, DP 1142771	Local	310
St Marys	St Marys General Cemetery	175-191 Great Western Highway	Lot 7300, DP 1141971	Local	303
St Marys	St Mary Magdalene Church, Hall, Cemetery and grounds	299-311 Great Western Highway	Lot 1, DP 1035601	Local	301
St Marys	"Mourilyan"	329–333 Great Western Highway	Lot 1, DP 997243	Local	300
St Marys	Shop	373 Great Western Highway	Lot 401, DP 601711	Local	806
St Marys	Wagon Wheel Hotel	449 Great Western Highway	Lot 102, DP 1031177	Local	308

St Marys	Wool Pack Inn (ruin)	556 Great Western Highway	Lot 1, DP 81099	Local	654
St Marys	St Marys Council Chambers (former)	2-6 Mamre Road	Lot 6, Section 1, DP 974985	Local	305
St Marys	"Margaret Farm", house, barn and tannery site	Pages Road, Barker, Wilson and Schleicher Streets	Lots 1-6, DP 30962	Local	226
St Marys	"Mimosa", stables (former)	11 Pages Road	Lot 1, DP 745809	Local	220
St Marys	"Mimosa", dwelling, fence and garden	13 Pages Road	Lot 40, DP 58974	Local	219
St Marys	Brick cottage	31-33 Pages Road	Lot 101, DP 833732	Local	801
St Marys	St Marys Public School	2-6 Princess Mary Street	Lot 1, DP 798964; Lot 1, DP 121443; Lot 1, DP 216092; Lot 1, DP 798965; Lot 2, DP 183835	Local	307
St Marys	Brick cottage	18 Princess Mary Street	Lot 104, DP 1037465	Local	309
St Marys	Weatherboard cottage	20 Princess Mary Street	Lot 13, DP 38418	Local	798
St Marys	Weatherboard cottage	22 Princess Mary Street	Lot 14, DP 38418	Local	799
St Marys	Gothic revival cottage	24 Princess Mary Street	Lot 15, DP 38418	Local	800
St Marys	"Thompson's Tannery" site, tannery pits (former) and well	94 Saddington Street	SP 73643; Lots 1-13, SP 73643	Local	235
St Marys	Brick cottage	100-104 Saddington Street	Lot 902, DP 1063929	Local	234
St Marys	Moore Cottage	8 Sainsbury Street	Lot 10, SP 72555	Local	221
St Marys	St Marys Railway Station	Corner Station and Queen Streets	Lot 1, DP 1040178	State	282
Wallacia	Bungalow	38 Greendale Road	Lot 60, DP 21083	Local	812
Wallacia	Wallacia Progress Association Hall	40 Greendale Road	Lot 61, DP 368083	Local	850
Wallacia	Brick house	96-100 Greendale Road	Lot 317, DP 808445	Local	811

Wallacia	Wallacia Public School	1573-1585 Mulgoa Road	Lot 50, DP 820512	Local	852
Wallacia	Wallacia Post Office	1589 Mulgoa Road	Lot 10, DP 1508	Local	851
Wallacia	Wallacia Hotel	1590-1594 Mulgoa Road	Part Lot A, DP 334601	Local	325
Wallacia	St Andrew's Anglican Church (former)	25 Park Road	Lot 1, DP 318587	Local	326
Werrington	"Torquay", house	555 Great Western Highway	Lot 11, DP 1170870	Local	319
Werrington	Brick house	565 Great Western Highway	Lot 565, DP 1121207	Local	810
Werrington	"Werrington Park House", garden and poplar avenue	653-729 Great Western Highway	Lot 101, DP 1140594	Local	315
Werrington	Rose Cottage and early slab hut	Corner of Water Street and Tennant Road	Lot 1, DP 827130	State	318
Werrington County	"Werrington House", dwelling, driveway and garden	108 Rugby Street	Lot 101, DP 605907	Local	248

Part 2 Heritage conservation areas

Name of heritage conservation area	Identification on Heritage Map	Significance
Hornseywood Avenue Conservation Area	Shown by an outline and identified as "HCA1"	Local
Lemongrove Conservation Area	Shown by an outline and identified as "HCA2"	Local
Warwick Street Conservation Area	Shown by an outline and identified as "HCA3"	Local
North St Marys Staff Cottages Conservation Area	Shown by an outline and identified as "HCA4"	Local
Mulgoa Road Conservation Area	Shown by an outline and identified as "HCA5"	Local
Park Road Conservation Area	Shown by an outline and identified as "HCA6"	Local

Part 3 Archaeological sites

Suburb	Item name	Address	Property description	Significance	Item no
Berkshire Park	Site of Berkshire Park homestead	844-848 Richmond Road	Lot 3, DP 1097876	Local	A662
Castlereagh	Site of Castlereagh township	East Wilchard Road and Church Lane	Various—see Heritage Map	Local	A30
Cranebrook	Castlereagh Genera Cemetery and native vegetation	132–156 Church Street, Cranebrook	Lot 245, DP 752021	Local	A880
Emu Plains	Police station (former)	30 Great Western Highway	Lot 8, DP 228204	Local	A53
Emu Plains	Government stockyard site	Hunter, Yodalla, Annett and Nepean Streets and River Road	Various—see Heritage Map	Local	A68
Emu Plains	"Dungarth" and remnant plantings site	4 Stockade Street	Lot 29, DP 250439	Local	A81
Leonay	Site of Edinglassie	Lapstone Place	Lot 102, DP 235829; Lot 2, DP 242718	Local	A112
Mulgoa	Irrigation canal	Mulgoa Road, Queenshill Drive, Littlefields Road and The Northern Road	Lots 5, 6, 8 and 9, DP 1046980; Lot 181, DP 230752; Lots 5 and 6, DP 718233	Local	A137
Mulgoa	Regentville Mansion (site) and vineyard terracing	460a-626 Mulgoa Road	Lot 40, DP 840788	Local	A271
Mulgoa	Slab cottage site	1177-1187 Mulgoa Road	Lot 6, DP 173159	Local	A858
Regentville	Regentville Windmill site	127–129 and 131–135 Martin Street	Lot 4, DP 249387; Lot 13, DP 633042	Local	A680
St Marys	Thompson's Tannery site (former)	Saddington Street	Various—see Heritage Map	Local	A236
Wallacia	Luddenham Homestead site	1-9 Park Road	Lots 1-3, DP 504928; Lots E-G, DP 390228	Local	A849

Penrith Local Environmental Plan 2010

Current version for 20 May 2024 to date (accessed 17 July 2025 at 14:57)

Schedule 5

Schedule 5 Environmental heritage

(Clause 5.10)

Part 1 Heritage items

Suburb	Item name	Address	Property description	Significance	e Item no
Agnes Banks	Castlereagh Road Alignment	Castlereagh Road		Local	261
Agnes Banks	Weatherboard cottage	410-450 Castlereagh Road	Lot 10, DP 792357	Local	660
Agnes Banks	Agnes Banks Public School (former)	475–479 Castlereagh Road	Lot 1, DP 776886	Local	3
Agnes Banks	"Osborne", homestead, barn, outbuildings and plantings	580–600 Castlereagh Road	Lot 1, DP 1155198	Local	6
Agnes Banks	"Chestnut", dwelling, slab cottage and trees	580–600 Castlereagh Road	Lot 1, DP 1155198	Local	8
Agnes Banks	"Tyreel", dwelling and barn	626-652 Castlereagh Road	Lot 1, DP 739177	Local	10
Agnes Banks	Federation farmhouse and trees	706 Castlereagh Road	Lot 4, DP 570547	Local	12
Agnes Banks	Brick farmhouse, trees and orchard	850-856 Castlereagh Road	Lot 1, DP 228165	Local	659
Agnes Banks	Agnes Banks Nature Reserve	2 Geebung Close, e and 36-62 and 66-88 Rickards Road	Lots 149 and 157-159, DP 752021; Lot 7302, DP 1151861; Lot 12 DP 1049319	State ,	15

Agnes Banks	Farmhouse (collapsed) and outbuildings	2-22 Springwood Road	Lot 930, DP 1129072	Local	2
Castlereagh	Castlereagh Road Alignment	Castlereagh Road		Local	261
Castlereagh	Memorials—Smith Park	1151-1159 Castlereagh Road	Lots 1-3, DP 3784; Part Lot 58, DP 752021	Local	19
Castlereagh	Castlereagh Council Chambers (former)	1158–1160 Castlereagh Road	Lot 1, DP 198257	Local	18
Castlereagh	Christ Church Anglican Church	230–232 Church Lane	Lot 27, DP 581747	Local	28
Castlereagh	Farmhouse, garden planting and natural vegetation	259A-263 Church Lane	Lot 1000, DP 1100451	Local	26
Castlereagh	Castlereagh Public School (former)	13-25 West Wilchard Road	Lot 2, DP 780559	Local	20
Claremont Meadows	Milestone	Great Western Highway	Fronting Lot 1, DP 1126991	Local	859
Claremont Meadows	"Four Winds", dwelling	568 Great Western Highway	Part Lot 11, Section 24, DP 111110	Local	321
Colyton	Milestone	Great Western Highway	Fronting Lot 1 DP 538063	Local	862
Cranebrook	Cranebrook Public School (former)	216 Boundary Road	Lot 22, DP 809521	Local	40
Cranebrook	Site of Fulton's Church and School	184-194 Church Street	Lot 287, DP 999655; Lot 288, DP 999656	Local	31
Cranebrook	St Thomas' Anglican Church (former) and Palm trees	5/11/0-5/1/1/0	Lots 12-17, Section A, DP 1613	Local	42
Cranebrook	Castlereagh General Cemetery and native vegetation	77-85 East Wilchard Road	Lot 281, DP 752021	Local	32
Cranebrook	Victorian farmhouse	46-54 Grays Lane	Lot 12, DP 825320	Local	35
Cranebrook	Johnson's Cottage	Nepean Street	Lots 18-20, Section A, DP 1613	Local	41
Cranebrook	Olive trees	68 Soling Crescent	Lot 104, DP 261535	Local	39
Cranebrook	"Kenilworth", dwelling and trees	6-9 Tallowood Place	Lot 26, DP 855247	Local	36

Emu Heights	Gosling Street and Hessel Place Reserves	22 Gosling Street	Lot 22, DP 1076016	Local	89
Emu Heights	House (Hall family)	13 Hessel Place	Lot 22, DP 250032	Local	88
Emu Plains	Bellbird Reserve	29 Barina Crescent	Lot 101, DP 577779	Local	90
Emu Plains	"Huntington Hall", house and garden	48-52 Beach Street	Lots 12, 13 and 15, DP 243048	Local	71
Emu Plains	Uniting Church	5-7 Emerald Street	Lot 1, DP 650543	Local	82
Emu Plains	Weatherboard cottage	24 Forbes Street	Lot 22, DP 253187	Local	664
Emu Plains	Brick cottage	73 Forbes Street	Lot 181, DP 575962	Local	669
Emu Plains	War Memorial, Emu Park	Great Western Highway, Lawson and Park Streets	Lot 7051, DP 1055094	Local	75
Emu Plains	"Emu Hall", dwelling, outbuildings and trees	2–26 Great Western Highway	Lot 2, DP 614436	Local	51
Emu Plains	Union Inn (former) and trees	36-42 Great Western Highway	Part Lots 1 and 2, DP 342116	Local	63
Emu Plains	Weatherboard house	66–70 Great Western Highway	Lot 17, SP 71124	Local	60
Emu Plains	Australian Arms Inn (former)	113 Great Western Highway	Lot 11, DP 1056135	Local	61
Emu Plains	Arms of Australia Inn	127 Great Western Highway	Lot 22, DP 242300	Local	327
Emu Plains	Stone house	143 Great Western Highway	Lot 111, DP 242913	Local	64
Emu Plains	Melrose Hall	169 Great Western Highway	Lot 7040, DP 751662	Local	73
Emu Plains	Emu Plains Public School (former) and trees	207-219 Great Western Highway	Part Lot 1, DP 650753	Local	76
Emu Plains	Sandstone cottage	281 Great Western Highway	Lot 110, DP 802233	Local	84
Emu Plains	Emu Plains Assembly Hall	283 Great Western Highway	Lot 1, DP 780531	Local	85
Emu Plains	"Mountain View" house	39 Grey Street	Lot 1, DP 203655	Local	837

Emu Plains	Sandstone railway culvert	Lamrock Street		Local	667
Emu Plains	Concrete house	39a-43 Mackellar Street	Lot 980, DP 810551	Local	58
Emu Plains	"Westbank", house	2 Nepean Street	Lot 1, DP 620712	Local	65
Emu Plains	"Gwandalan", dwelling and garden	11 Nepean Street and 35 Cary Street	Lots 121 and 123, DP 807462	Local	92
Emu Plains	"Yodalla", house and garden	28 Nepean Street	Lot 42, DP 524161	Local	66
Emu Plains	"Yamba", cottage	32 Nixon Street	Lot 116, DP 242303	Local	80
Emu Plains	"Orange Grove", cottage	15 Park Street	Lot 1, DP 703497	Local	74
Emu Plains	Ferry crossing	Punt Road, Nepean River		Local	147
Emu Plains	Police station residence (former)	4 Punt Road	Lot 7038, DP 94188	Local	52
Emu Plains	International style house and garden	10 River Road	Lot B, DP 33205	Local	666
Emu Plains	Brick house and garden	80 River Road	Lot 2, DP 1024616	Local	151
Emu Plains	Lewers Bequest and Regional Art Gallery, houses and garden	84-88 River Road,	Lot 34, DP 1114973	Local	69
Emu Plains	Edwardian cottage	46 Russell Street	Lot 10, DP 1097496	Local	83
Emu Plains	St. Paul's Anglican Church and Emu Plains General Cemetery	Land bounded by Short, Mundy and Nixon Streets and the Great Western Railway	Lot 1, DP 724148; Lot 1, DP 798650; Lot G, DP 751662	Local	78
Emu Plains	Emu Plains Railway Station group	Main Western Railway, Station Street	Lot 1, DP 1133099	State	59
Emu Plains	"Killeen", Federation house	34 Walkers Crescent	Lot 104, DP 1006488	Local	840
Emu Plains	Cottage	14 York Street	Lot 1, DP 563123	Local	55
Glenmore Park	Scarred tree and Aboriginal artefact scatter	Lot 2000 Bradley Street	Lot 2000, DP 1204777	Local	878

Jamisontown	Sir John Jamison Cemetery	14b and 14c Lilac Place	Lot 1, DP 724391; Lot 1, DP 723986	Local	269
Jamisontown	Workmens' cottages	56-62 Mulgoa Road	Lots 1-4, SP 39546	Local	94
Kingswood	St. Phillip's Anglican Church	32 Bringelly Road	Lot 64, DP 752022	Local	101
Kingswood	Penrith General Cemetery	Land bounded by Copeland and Phillips Streets, Richmond Road and Cox Avenue	Lots 1-28, DP 975352	Local	97
Kingswood	Federation house and garden	6 First Street	Lot 101, DP 1032987	Local	100
Kingswood	Milestone	Great Western Highway	Fronting Lot 1, DP 866081	Local	860
Kingswood	Milestone	Great Western Highway	Fronting Lot 10, DP 719064	Local	861
Kingswood	House	43 Park Avenue	Lot B, DP 409139	Local	672
Kingswood	Kingswood Public School	46-54 Second Avenue	Lot 172, DP 839785	Local	98
Kingswood	Teacher's residence (former)	56 Second Avenue	Lot 2, DP 1130750	Local	670
Leonay	"Edinglassie", house	22 Bunyan Road	Lot 185, DP 233104	Local	108
Leonay	"Leo Buring" cottage, barn, glasshouse and memorial	3a Leonay Parade	Lot 12, DP 818741	Local	109
Llandilo	Federation farmhouse	330 Eighth Avenue	Lot 330, DP 2147	Local	676
Llandilo	Farmhouse	361 Ninth Avenue	Lot 3, DP 231946	Local	677
Llandilo	Llandilo Public School	222 Seventh Avenue	Lot 222, DP 2147	Local	841
Llandilo	St David's Anglican Church (former)	257B Seventh Avenue	Lot 1, DP 724335	Local	673
Llandilo	Llandilo Community Hall	257C Seventh Avenue	Lot 11, DP 1092204	Local	675
Llandilo	Cottage and outbuildings	268 Seventh Avenue	Lot 269, DP 2147	Local	113
Llandilo	Farmhouse	170 Sixth Avenue	Lot A, DP 390397	Local	842

Londonderry	Londonderry Cemetery	325–331 Londonderry Road	Lot 100, DP 810236	Local	115
Luddenham	Luddenham Road Alignment	Luddenham Road		Local	843
Mulgoa	"Passadena", house	45-61 Allan Road	Lot 1, DP 227674	Local	132
Mulgoa	"Fairlight", homestead, outbuildings and gardens	377-429 Fairlight Road	Lot 22, DP 625510	State	140
Mulgoa	Table Rock Lookout	716-782 Fairlight Road	Lot A, DP 164835	Local	141
Mulgoa	"Glenleigh", estate	427–507 Mulgoa Road	Lot 2, DP 563748	State	273
Mulgoa	"Glenmore"	754-760 Mulgoa Road	Lot 3, DP 701949	State	124
Mulgoa	"Fernhill", house, outbuildings and landscape	1041-1117 Mulgoa Road	Lots 10 and 11, DP 615085; Lot 2, DP 541825	State	128
Mulgoa	"Fernhill", curtilage	1147–1187 Mulgoa Road and 10–156 Mayfair Road	Lot 100, DP 717549; Lot 1, DP 570484; Lot 6, DP 173159; Lot 5, DP 23781; Lot 12, DP 610186; Lot 2, DP 211795; Lots 1-4, DP 260373	Local	873
Mulgoa	Mulgoa Public School building, hall, residence and trees	1189-1193 Mulgoa Road	Lot 1, DP 853475	Local	130
Mulgoa	St Mary's Catholic Church	1262-1266 Mulgoa Road	Lot 10, Section E, DP 2121	Local	133
Mulgoa	Weatherboard cottage	1296 Mulgoa Road	Lot 2, DP 226343	Local	134
Mulgoa	Mulgoa Irrigation Company office and police station (former)	1298-1304 Mulgoa Road	Lot 32, DP 585921	Local	135
Mulgoa	Cottage	1306 Mulgoa Road	Lot 39, Section A, DP 2882	Local	136
Mulgoa	"Winbourne", house	1315 Mulgoa Road	Lot 4, DP 854076	Local	138

Mulgoa	St Thomas' Anglican Church and Cemetery	43-57 and 59-119 St Thomas Road	Lot 1, DP 996994; Lot 1, DP 1035490	State	126
Mulgoa	Cox's Cottage	1012-1046 Mulgoa Road and 2-24 St Thomas Road	Lots 2-4, DP 241971	State	125
Mulgoa	Mulgoa Road Alignment (former)	St Thomas Road		Local	844
Orchard Hills	Brick farmhouse	80-88 Caddens Road	Lot 6, DP 1344	Local	155
Orchard Hills	"Lindfield"	182-188 Caddens Road	Lot 1, DP 583439	Local	845
Orchard Hills	Water reservoir	197–207 Castle Road	Lot 1, DP 430473	Local	657
Orchard Hills	Orchard Hills Uniting Church	3 Frogmore Road	Lot 101, DP 128254	Local	156
Orchard Hills	Memorial cairn	Luddenham Road		Local	230
Orchard Hills	Mamre	181–275 Mamre Road	Lot 1, DP 530579	State	228
Orchard Hills	Memorial cairn	181-275 Mamre Road	Lot 1, DP 530579	Local	229
Orchard Hills	Leeholme Horse Stud Rotunda	391-395 Mamre Road	Lot 2, DP 547057	Local	232
Penrith	"Craithes", dwelling, trees, outbuildings and carriage loop	34-40 Borec Road	Lot 2, DP 802406	State	161
Penrith	Weir	Bruce Neale Drive, Nepean River		Local	848
Penrith	Weatherboard cottage	41-43 Camden Street	Lot 13, DP 712385	Local	695
Penrith	Edwardian cottage	2068 Castlereagh Road	Lot 3, DP 862636	Local	158
Penrith	Victorian house	2083-2089 Castlereagh Road	Lot 1, DP 623919	Local	160
Penrith	Bennetts Wagons	2151(a) Castlereagh Road	Lot 112 DP 774782	Local	829
Penrith	Penrith School of Arts (former)	7 Castlereagh Street	Lots 9-11, Section 1, DP 1582	Local	692
Penrith	Torin building	26 Coombes Drive	Lot 401-403, DP 1162312	State	827

Penrith	"Combewood", house, garden, trees and original entrance drive	234-256 Coreen Avenue	Lot 2, DP 654378; Lots 51-55, DP 237090	Local	163
Penrith	Cottage	169 Cox Avenue	Lot A, DP 984462	Local	853
Penrith	Thornton Hall	Thornton House 33 Mountain View Crescent, Penrith	Lot 2032, DP 1181618	Local	166
Penrith	Presbyterian manse (former)	154 Derby Street	Lot 4, DP 25106	Local	697
Penrith	Victorian cottage	163 Derby Street	Lot Y, DP 389668	Local	698
Penrith	Victorian cottage	194 Derby Street	Lot 1, DP 2363	Local	699
Penrith	Ferry crossing	Nepean River—Ferry Road		Local	870
Penrith	Governor Phillip Special Hospital—original building	64 Glebe Place	Lot 1, DP 213072	Local	174
Penrith	Rectory (former)	95 Glebe Place	Lots 5 and 5A, DP 39162	Local	173
Penrith	Victoria Bridge	Great Western Highway		State	146
Penrith	Penrith Infants Department (1884 building)	57 Henry Street	Lot 1, DP 724160	Local	177
Penrith	Methodist Church (former)	74 Henry Street	Lot 22, DP 586469	Local	179
Penrith	TAFE Building	115-119 Henry Street	Lot 111, DP 1028320	Local	689
Penrith	Penrith Council Chambers (former)	129-133 Henry Street	Lot 1123, DP 1106979	Local	189
Penrith	"Kelvin Brae", Federation house	142 High Street	Lot 1, DP 1127355	Local	854
Penrith	Penrith Public School and palm trees	194 High Street	Lot 2, DP 502608; Lots 2-4, Section 19, DP 2296	Local	210
Penrith	Victorian terrace and Interwar shop	219-221 High Street	Lot 2, DP 224062	Local	212
Penrith	St Aubyn's Terrace	255-265 High Street	Lot 3, DP 955837; Lot 4, DP 972	Local	209

Penrith	St Stephen's Anglican Church, Hall and Cemetery	258-280 High Street	Lots 101 and 102, DP 597910	Local	206
Penrith	Cottage	288 High Street	Lot 1, Section 3, DP 1582	Local	723
Penrith	Brick villa	318-320 High Street	Lot 4, Section 2, DP 1582	Local	711
Penrith	Memorials and lamp stand, St Nicholas of Myra Catholic Church	332–338 High Street	Lot 1, DP 782278	Local	688
Penrith	"Cram Place", coach house, well, pump and cast iron fence	338-340 High Street	Lot 11, DP 1013730	Local	201
Penrith	Bank of NSW (former)	354-360 High Street	Lot 10, SP 51611	Local	713
Penrith	Australian Arms Hotel	359 High Street	Lot 2, DP 513015	Local	196
Penrith	High Street shops	361-365 High Street	Lots 2 and 4, SP 13804	Local	714
Penrith	High Street shop	371-375 High Street	Lot 13, DP 616937	Local	715
Penrith	High Street shop	377-381 High Street	Lot 12, DP 616937	Local	716
Penrith	High Street shop	383 High Street	Lot 11, DP 616937	Local	717
Penrith	High Street shop	387-389 High Street	Lot 1, DP 774671	Local	718
Penrith	High Street shop	391-393 High Street	Lots 23 and 24, DP 236390	Local	719
Penrith	Memory Park	400 High Street	Lot 1, DP 198339	Local	200
Penrith	Fulton's Store (former)	413-423 High Street	Lot B, DP 322318	Local	197
Penrith	High Street shop	425-427 High Street	Lot A, DP 322318	Local	720
Penrith	High Street shop	437 High Street	Lot 2, DP 82325	Local	855
Penrith	High Street shop	449-451 High Street	Lot 12, DP 599349	Local	721
Penrith	High Street shop	538-540 High Street	Lot 1, DP 779550	Local	198
Penrith	High Street shop	542 High Street	Lot 2, DP 154388	Local	722
Penrith	High Street shop	550-556 High Street	Lot B, DP 152524	Local	199
Penrith	Red Cow Hotel	569-595 High Street	Lot 1, DP 1137699	Local	690

Penrith	Penrith Ambulance Station	668-672 High Street	Lot 12, DP 37829	Local	256
Penrith	"Madang Park", farmhouse and trees	475–487 Jamison Road	Lot 2, DP 567225	Local	95
Penrith	Station Master's House (former)	Jane Street	Lot 31, DP 1086586	State	187
Penrith	Penrith Railway Station group	Railway land, Jane Street	Lot 31, DP 1086586	State	188
Penrith	The Lodge	48-56 Leland Street	Lot 5, DP 1049780	Local	159
Penrith	Lemongrove Lodge	22-24 Lemongrove Road	Lot 1C, DP 162091	Local	172
Penrith	Victorian villa	150 Lethbridge Street	Lot 81, DP 526298	Local	214
Penrith	Explorers Memorial	Memorial Avenue		Local	258
Penrith	Pumping station (former)	20 Memorial Avenue	Lot 1, DP 233967	Local	144
Penrith	Penrith Power Station (former)	1 Museum Drive	Lot 1306, DP 1234327	Local	259
Penrith	"Seidler", house	31-33 Nepean Avenue	Lot 1, DP 14827	Local	685
Penrith	Rowing course	Nepean River		Local	148
Penrith	Railway bridge	Over Nepean River		State	668
Penrith	Weatherboard cottage	71 Parker Street	Lot 1, DP 996540	Local	175
Penrith	Peachtree Creek Bridge	Peachtree Creek		Local	257
Penrith	Victorian house	6 Rawson Avenue	Lot 2, DP 206095	Local	253
Penrith	Prospect Electricity building (former)	59 Station Street	Lot 10, DP 1025026	Local	701
Penrith	"Broadville", Victorian house	98 Station Street	Lot 910, DP 717451	Local	215
Penrith	"Kentucky", villa	146 Station Street	Lot 11, DP 715161	Local	216
Penrith	Victorian house	148 Station Street	Lot 80, DP 709313	Local	217
Penrith	"The Cottage", dwelling and pine tree	39 Warwick Street	Lot 11, DP 663880	Local	251

Penrith	"Minnamurra", house	43 Warwick Street	Lot 1, DP 173533	Local	696
Penrith	Victorian house, dwelling and camphor laurel tree	50 Warwick Street	Lot 1, DP 21745	Local	250
Penrith	Federation cottage	80 Woodriff Street	Lot 18, DP 2167	Local	847
Regentville	Regentville Workers' Terrace	1 Bundarra Road	Lots 1, 2 and 19, DP 16540	Local	276
Regentville	Regentville Public School, residence and garden	32-34 School House Road	Lot 1, DP 906651	Local	270
St Marys	Dunheved Fire Station	50 Christie Street	Lot 142, DP 31911	Local	655
St Marys	Explosives storehouse	146 Dunheved Circuit	Lot 131, DP 701610	Local	869
St Marys	Brick cottage	38 Gidley Street	Lot 1, DP 783200	Local	298
St Marys	Brick cottage	40 Gidley Street	Lot 1, DP 710777	Local	797
St Marys	"Bronte", villa	50 Gidley Street	Lot 4, DP 38617	Local	299
St Marys	Bennett Wagon	Pioneer Park, Great Western Highway	Lot B, DP 371329	Local	805
St Marys	Milestone	Great Western Highway (between Marsden Road and Day Street)		Local	304
St Marys	Victoria Park and memorial	Bounded by Great Western Highway, Pages Road, Putland and Princess Mary Streets	Lot 1, DP 1142771	Local	310
St Marys	St Marys General Cemetery	175-191 Great Western Highway	Lot 7300, DP 1141971	Local	303
St Marys	St Mary Magdalene Church, Hall, Cemetery and grounds	299-311 Great Western Highway	Lot 1, DP 1035601	Local	301
St Marys	"Mourilyan"	329–333 Great Western Highway	Lot 1, DP 997243	Local	300
St Marys	Shop	373 Great Western Highway	Lot 401, DP 601711	Local	806
St Marys	Wagon Wheel Hotel	449 Great Western Highway	Lot 102, DP 1031177	Local	308

St Marys	Wool Pack Inn (ruin)	556 Great Western Highway	Lot 1, DP 81099	Local	654
St Marys	St Marys Council Chambers (former)	2-6 Mamre Road	Lot 6, Section 1, DP 974985	Local	305
St Marys	"Margaret Farm", house, barn and tannery site	Pages Road, Barker, Wilson and Schleicher Streets	Lots 1-6, DP 30962	Local	226
St Marys	"Mimosa", stables (former)	11 Pages Road	Lot 1, DP 745809	Local	220
St Marys	"Mimosa", dwelling, fence and garden	13 Pages Road	Lot 40, DP 58974	Local	219
St Marys	Brick cottage	31-33 Pages Road	Lot 101, DP 833732	Local	801
St Marys	St Marys Public School	2-6 Princess Mary Street	Lot 1, DP 798964; Lot 1, DP 121443; Lot 1, DP 216092; Lot 1, DP 798965; Lot 2, DP 183835	Local	307
St Marys	Brick cottage	18 Princess Mary Street	Lot 104, DP 1037465	Local	309
St Marys	Weatherboard cottage	20 Princess Mary Street	Lot 13, DP 38418	Local	798
St Marys	Weatherboard cottage	22 Princess Mary Street	Lot 14, DP 38418	Local	799
St Marys	Gothic revival cottage	24 Princess Mary Street	Lot 15, DP 38418	Local	800
St Marys	"Thompson's Tannery" site, tannery pits (former) and well	94 Saddington Street	SP 73643; Lots 1-13, SP 73643	Local	235
St Marys	Brick cottage	100-104 Saddington Street	Lot 902, DP 1063929	Local	234
St Marys	Moore Cottage	8 Sainsbury Street	Lot 10, SP 72555	Local	221
St Marys	St Marys Railway Station	Corner Station and Queen Streets	Lot 1, DP 1040178	State	282
Wallacia	Bungalow	38 Greendale Road	Lot 60, DP 21083	Local	812
Wallacia	Wallacia Progress Association Hall	40 Greendale Road	Lot 61, DP 368083	Local	850
Wallacia	Brick house	96-100 Greendale Road	Lot 317, DP 808445	Local	811

Wallacia	Wallacia Public School	1573-1585 Mulgoa Road	Lot 50, DP 820512	Local	852
Wallacia	Wallacia Post Office	1589 Mulgoa Road	Lot 10, DP 1508	Local	851
Wallacia	Wallacia Hotel	1590-1594 Mulgoa Road	Part Lot A, DP 334601	Local	325
Wallacia	St Andrew's Anglican Church (former)	25 Park Road	Lot 1, DP 318587	Local	326
Werrington	"Torquay", house	555 Great Western Highway	Lot 11, DP 1170870	Local	319
Werrington	Brick house	565 Great Western Highway	Lot 565, DP 1121207	Local	810
Werrington	"Werrington Park House", garden and poplar avenue	653-729 Great Western Highway	Lot 101, DP 1140594	Local	315
Werrington	Rose Cottage and early slab hut	Corner of Water Street and Tennant Road	Lot 1, DP 827130	State	318
Werrington County	"Werrington House", dwelling, driveway and garden	108 Rugby Street	Lot 101, DP 605907	Local	248

Part 2 Heritage conservation areas

Name of heritage conservation area	Identification on Heritage Map	Significance
Hornseywood Avenue Conservation Area	Shown by an outline and identified as "HCA1"	Local
Lemongrove Conservation Area	Shown by an outline and identified as "HCA2"	Local
Warwick Street Conservation Area	Shown by an outline and identified as "HCA3"	Local
North St Marys Staff Cottages Conservation Area	Shown by an outline and identified as "HCA4"	Local
Mulgoa Road Conservation Area	Shown by an outline and identified as "HCA5"	Local
Park Road Conservation Area	Shown by an outline and identified as "HCA6"	Local

Part 3 Archaeological sites

Suburb	Item name	Address	Property description	Significance	Item no
Berkshire Park	Site of Berkshire Park homestead	844-848 Richmond Road	Lot 3, DP 1097876	Local	A662
Castlereagh	Site of Castlereagh township	East Wilchard Road and Church Lane	Various—see Heritage Map	Local	A30
Cranebrook	Castlereagh Genera Cemetery and native vegetation	132–156 Church Street, Cranebrook	Lot 245, DP 752021	Local	A880
Emu Plains	Police station (former)	30 Great Western Highway	Lot 8, DP 228204	Local	A53
Emu Plains	Government stockyard site	Hunter, Yodalla, Annett and Nepean Streets and River Road	Various—see Heritage Map	Local	A68
Emu Plains	"Dungarth" and remnant plantings site	4 Stockade Street	Lot 29, DP 250439	Local	A81
Leonay	Site of Edinglassie	Lapstone Place	Lot 102, DP 235829; Lot 2, DP 242718	Local	A112
Mulgoa	Irrigation canal	Mulgoa Road, Queenshill Drive, Littlefields Road and The Northern Road	Lots 5, 6, 8 and 9, DP 1046980; Lot 181, DP 230752; Lots 5 and 6, DP 718233	Local	A137
Mulgoa	Regentville Mansion (site) and vineyard terracing	460a-626 Mulgoa Road	Lot 40, DP 840788	Local	A271
Mulgoa	Slab cottage site	1177-1187 Mulgoa Road	Lot 6, DP 173159	Local	A858
Regentville	Regentville Windmill site	127–129 and 131–135 Martin Street	Lot 4, DP 249387; Lot 13, DP 633042	Local	A680
St Marys	Thompson's Tannery site (former)	Saddington Street	Various—see Heritage Map	Local	A236
Wallacia	Luddenham Homestead site	1-9 Park Road	Lots 1-3, DP 504928; Lots E-G, DP 390228	Local	A849



Appendix B Aboriginal Consultation Log

REDACTED

September 2025 Page 57 of 61



Appendix C Research Design and Methodology

September 2025 Page 58 of 61





CASTLEREAGH TOURISM DEVELOPMENT

39-65 Old Castlereagh Road Castlereagh, NSW

Archaeological Research Design and Methodology

Final | September 2025

Prepared for Morson Group

PO Box 101, Pottsville NSW 2489 (O2) 6676 4354 info@virtusheritage.com.au ABN 56 159 910 228



Cover design: Cake

Cover image: Stock imagery (Microsoft Office 2022)

Document Controls

Client:	Enter Client
Proponent:	Morson Group
Local Government Area:	City of Penrith
Local Aboriginal Land Council (LALC):	Deerubbin Local Aboriginal Land Council

Version History

Version	Date	Prepared by	Approved by	Comments
1a - c	12 December 2024	Clare Anderson	Alice Buhrich Dr. Mary-Jean Sutton	Minor edits
1d	3 July 2025	Dr. Mary-Jean Sutton and Liam Clerke	Dr. Mary-Jean Sutton	Draft
2а – е	23 July 2025	Dr. Mary-Jean Sutton and Liam Clerke	Dr. Mary-Jean Sutton	Draft
3	27 August 2025	Kate Morris and Liam Clerke	Dr. Mary-Jean Sutton	Final

September 2025 Page 2 of 22



Acknowledgement of Country

Virtus Heritage acknowledges the Traditional Custodians of the land on which this project was undertaken and pays respect to Elders past, present and emerging.

Content Warning

Aboriginal and Torres Strait Islander people are warned that this publication may contain names and images of deceased people, descriptions of traumatic historic events and parts of Country that have been impacted by development.

Disclaimer and cultural restrictions

This Report (including any enclosures and attachments) has been prepared by Virtus Heritage for the exclusive use and benefit of Enter Client and Morson Group for their use regarding the Project and solely for the purpose for which it is provided. Unless we provide express prior written consent, no part of this report should be reproduced, distributed or communicated to any third party. We do not accept any liability if this report is used for an alternative purpose from which it is intended, nor to any third party in respect of this report.

Information contained in the Report is current as at the date of the Report and may not reflect any event or circumstances which occur after the date of the Report.

All queries related to the content, or to any use of this report must be addressed to Dr Mary-Jean Sutton.

September 2025 Page 3 of 22



Contents

1.	Introduction	7	
1.1	Proposed Project Impacts	7	
1.2	Aboriginal Consultation	10	
1.3	Report Structure	11	
2.	Summary of previous archaeological research	12	
3.	Research Design	13	
4.	Methodology	15	
4.1	Impact and Mitigation Areas	15	
4.2	Site Set Up	16	
4.3	Surface Collection	16	
4.4	Geotechnical Auger Hole and Trench	17	
4.5	Manual (Hand) Salvage Excavation	17	
4.6	Methodology for Controlled Subsurface Salvage – Mechanical Pits	18	
4.7	Expansion or Placement of Additional Excavation Areas	19	
4.8	Recording During Excavation and Sieving	19	
4.9	Community Collection	19	
4.10	Reporting	20	
4.10	O.1. Attributes to be recorded for Stone Artefacts	20	
4.11	Short and Long Term Care of Aboriginal Objects	20	
4.12	Safety and Environmental Management	21	
5.	References	22	
Ta	bles		
Tabl	e 1 Aboriginal Site located within the AHIP Application Area	8	
Tabl	Table 2 Aboriginal Site located within the AHIP Application AreaArea		
Tabl	e 3. Proposed Impacts and Recommended Mitigation	15	
Tabl	e 4: Attributes to be recorded	20	
Fig	gures		
Figu	re 1: AHIP Application Area	9	



Definitions

PAD

Abbreviations Description AAArchaeological Assessment **ACHA** Aboriginal Cultural Heritage Assessment **ACHCR** Aboriginal Cultural Heritage Consultation Requirements for Proponents 2010 (DECCW 2010a) **AHIMS** Aboriginal Heritage Information Management System **AHIP** Aboriginal Heritage Impact Permit **ARDM** Archaeology Research Design Methodology Code of Practice, Code of Practice for Archaeological Investigation of Aboriginal Objects in New South COP Wales (DECCW 2010b) **DLALC** Deerubbin Local Aboriginal Land Council LALC Local Aboriginal Land Council NPW ACT National Parks and Wildlife Act 1974 National Parks and Wildlife Regulation 2019 NPW Reg **OEH** NSW Office of Environment and Heritage (now Heritage NSW) **OSL** Optically stimulated luminescence

RAP Registered Aboriginal Party

Potential Archaeological Deposit

September 2025 Page 5 of 22



Glossary

Aboriginal object - A term used in the NPW Act legislation, meaning: '... any deposit, object or material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of the area that comprises NSW, being habitation before or concurrent with (or both) the occupation of that area by persons of non-Aboriginal extraction, and includes Aboriginal remains' (s.5 NPW Act).

Registered Aboriginal party – An individual or party who registers for Aboriginal consultation as part of the consultation and notification process following Aboriginal cultural heritage consultation requirements for proponents 2010 (NSW DECCW 2010a).

AHIP – An Aboriginal Heritage Impact Permit which is a document provided by Heritage NSW which provides a defence to the applicant to certain activities which constitute 'harm' to Aboriginal objects or Aboriginal places under Part 6 of the NPW Act. A proponent must prepare an application for an AHIP and other relevant documentation (including an ACHA) to obtain an AHIP from Heritage NSW in the Department of Premier and Cabinet.

Declared Aboriginal place - A term used in the NPW Act legislation, meaning any place declared to be an Aboriginal place (under s.84 of the NPW Act) by the Minister administering the NPW Act, by order published in the NSW Government Gazette, because the Minister is of the opinion that the place is or was of special significance with respect to Aboriginal culture. It may or may not contain Aboriginal objects.

Due Diligence assessment – Due diligence is taking reasonable and practical steps to determine whether a person's actions will harm an Aboriginal object and, if so, what measures can be taken to avoid that harm. A due diligence assessment will assess the potential for harm and provide recommendations to mitigate harm, generally in the form of an Aboriginal Cultural Heritage Assessment (ACHA), if Aboriginal objects or places are likely to be harmed by proposed works.

Harm - A term used in the NPW Act Amendments meaning '... any act or omission that destroys, defaces, damages an object or place or, in relation to an object – moves the object from the land on which it had been situated' (s.5 NPW Act).

Project area - Area proposed to be impacted as part of a specified activity or development proposal. These activities include indirect impact.

Place - An area of cultural value to Aboriginal people in the area (whether or not it is an Aboriginal place declared under s.84 of the Act).

Proponent - A person proposing an activity that may harm Aboriginal objects or declared Aboriginal places and who may apply for an AHIP under the NPW Act.

September 2025 Page 6 of 22



1. Introduction

Morson Group Consultants proposes to develop a tourism precinct at 39-65 Old Castlereagh Road, Castlereagh NSW (Lots 12, 14 and 16 DP793163, Figure 1). The project area is located within the Penrith Local Government Area (LGA), within the boundary of Deerubbin Local Aboriginal Land Council (DLALC).

The proposed scope of works as provided by Morson Group seeks approval for a tourism-oriented development comprising three (3) buildings across separate lots, including a hotel, an indoor recreation facility with two (2) drive-through restaurants, and a registered club. The proposal also includes associated vehicle access, on-grade and above-ground parking, and site infrastructure.

- Lot 12:
 - A seven (7) storey hotel with 147 rooms, restaurant, gym, spa, pool, and associated facilities.
 - Multi-level above-ground car parking.
- Lot 14:
 - A 5,713m² indoor recreation facility.
 - Two (2) restaurants with capacity for a drive-through.
 - Associated on-grade car parking.
- Lot 16:
 - A 5,177m² registered club building.
 - Associated on-grade car parking.

Virtus Heritage Pty Limited (hereafter 'Virtus Heritage') was engaged by Morson Group to prepare an Aboriginal Cultural Heritage Assessment (ACHA), including an Archaeological Assessment (AA) for the proposed development.

The proposed tourism development includes excavations anticipated to be up to 0.15 – 1.74 m depth, though excavation of stormwater system and footings will also likely be required. Excavations in these areas are anticipated to a maximum of 2.3 m depth.

AHIP COO01415 (AHIMS 3891), now expired, was previously issued over the project area. Previous Aboriginal cultural heritage assessments have identified that the project area may contain in-situ stratigraphy and low densities of Aboriginal objects associated with the alluvial Penrith Unit of the Cranebrook Terrace (PLDC 2011, Virtus Heritage 2024).

Where Aboriginal objects survive in this unit, they have research value as it may provide an opportunity to further understand the stratigraphy and archaeological value of the Penrith Unit of the Cranebrook Terrace and past Dharug land use on elevated terrain overlooking an unnamed tributary of Cranebrook Creek. This resource and opportunities to understand it are increasingly diminished by development in the local region.

The proposed activity has the potential to harm Aboriginal objects associated with this deposit. Given the extent of information available on the Penrith Unit, the previous land-use of the project area, the identification of artefacts within surface exposures inside of the project area, and the homogeneity of topography and landforms within the project area, archaeological testing is not necessary to determine the presence or absence of Aboriginal objects and archaeological deposits.

This document constitutes the Archaeological Research Design and Methodology (ARDM) to accompany an AHIP application to enable ground disturbance works associated with project development and salvage of an area of moderate archaeological potential within the project area.

1.1 PROPOSED PROJECT IMPACTS

Figure 1 shows the project impact area boundary which constitutes the application area for this AHIP application.

September 2025 Page 7 of 22



Table 1 outlines the proposed works and impacts to known sites and potential archaeological deposits (PAD) and indicates the level and type of harm.

Table 1 Aboriginal Site located within the AHIP Application Area

AHIMS # / PADs within Proposed Work Sites	Site Name	Site Type	Proposed Activity
45-5-6025	Penrith Lakes 2025, background scatter	Artefact scatter/Artefact (feature)	Salvage excavation Archaeological Surface Collection
			Community Collection

September 2025 Page 8 of 22





Figure 1: AHIP Application Area

September 2025 Page 9 of 22



1.2 ABORIGINAL CONSULTATION

As recognised by Heritage NSW, we acknowledge that Aboriginal people are the primary determinants of the cultural significance of their heritage. Aboriginal consultation for the ACHA was undertaken in compliance with the Aboriginal cultural heritage consultation requirements for proponents 2010 (NSW DECCW 2010a) (hereafter referred to as the "ACHCRs"). These consultation requirements are legal requirements that proponents must comply with during the ACHA process which are set out in Clause 80c of the NPW Regulation. Aboriginal consultation is crucial in the compilation of the ACHA in order to adequately assess and investigate Aboriginal cultural heritage.

Sixteen Aboriginal groups/individuals registered interest for this project during the notification process. Each interested party responded to advertisements in various newspapers or to an invitation to register in the project after their contact details were provided by notified organisations. The groups/individuals registered for consultation are listed in Table 2.

Table 2 Aboriginal Site located within the AHIP Application Area

Name of Contact	Registered Aboriginal Party
Steven Randall	Deerubbin Local Aboriginal Land Council
Philip Boney	Wailwan Aboriginal Group
Tiarna Bird	Mura Gadi Aboriginal Corporation
Ethan Trewlynn	Long Gully Cultural Services
Nigel Millgate	Gadhungal Marring
Darleen Johnson and Ryan Johnson	Murra Bidgee Mullangari Aboriginal Corporation
Justine Coplin	Dharug Custodian Aboriginal Corporation
Kelvin Boney	Wallanbah Aboriginal Site Conveyancing
Amanda Hickey	Amanda Hickey Cultural Services
Carolyn Hickey	A1 Indigenous Services
Jennifer Beale	Butucarbin Aboriginal Corporation
Phil Khan	Kamilaroi Yankuntjatjara Working Group
Kerrie Slater; Vicky Slater	Wurrumay Culture Heritage Consultants
Steven Hickey	Widescope Indigenous Group
Wendy Morgan	Guntawang Aboriginal Resources Incorporated
Undisclosed Registered Aboriginal Party	Undisclosed Registered Aboriginal Party

All registered Aboriginal parties have been provided with the opportunity to review, discuss and develop the ARDM presented in this document.

September 2025 Page 10 of 22



1.3 REPORT STRUCTURE

Section 1 provides an introduction and context to the project.

Section 2 of this research design and methodology summarises previous archaeological research which is relevant to the AHIP application for the site within the project area.

Section 3 details the research design that has been proposed for the project area.

Section 4 provides the methodology proposed for salvage for sites and areas within the project area.

Section 5 presents the attributes to be recorded during the analysis of artefacts recovered during salvage and collections.

Section 6 discusses the care of artefacts recovered during salvage and collections.

Section 7 lists the references cited within this document.

September 2025 Page 11 of 22



2. Summary of previous archaeological research

A review of the Heritage NSW Aboriginal Heritage Information Management System (AHIMS) library and online searches were undertaken to obtain copies of previous Aboriginal heritage studies and archaeological investigations within the locality of the project area, which relate to the AHIP application. Detailed summaries of all reports pertinent to the locality are provided in Section 4 of the Archaeological Assessment (Virtus Heritage 2024).

The project area is located on a floodplain terrace associated with the Nepean River, within the Penrith Unit of the Cranebrook Terrace formation. The soils of the project area are consistent with the Richmond soil landscape. Aboriginal objects are known to occur within this soil landscape and in the Penrith Unit to depths of 1–2 m and generally in the top 0.9 m of deposit. Archaeological models across the Cumberland Plain indicate that Aboriginal objects can be found in any landform, with stone artefacts tending to be found more frequently in proximity to key resources such as water and drainage lines, shelter and stone sources and decreasing in frequency as distance from those resources increases. The Nepean River is located a little over 650 m from the project area. The historic path of Cranebrook Creek is mapped approximately 1.7 km west of the project area. An unnamed tributary was located 300m north–east of the project area. Previous potential chain of ponds and paleochannels were also identified by Groundtruthing Consulting in proximity to the project area (Mitchell 2010).

The project area's alluvium topsoils have been disturbed by vegetation clearance, previous farming activity and the construction of the residential housing and irrigation infrastructure but does not appear to have been subject to sand mining. This past land use has impacted the A-horizon soils to at least 0.6 m in depth.

An AHIMS extensive search (Client Service ID 912988) was undertaken on 10 July 2025. No Aboriginal cultural heritage sites were registered in or in close proximity to the project area.

In 2017, Williams et al. conducted excavations on the banks of Peach Tree Creek and created the most recent dating model for the Cranebrook Terrace (Williams et al 2017) This modelling identifies that the sandy clay sediment in areas west of the historic alignment of Cranebrook Creek, within the Richmond Unit, were deposited between 20–15,000 years ago to a depth of 3.5–3.9 m or 20.73–21.13 m AHD. This sedimentary layer is particularly sensitive for Aboriginal archaeological deposits, with flakes being identified by Williams et al. at the base of this layer. Sediment below this deposit are also sandy clays and date to approximately 50–40,000 years ago. Sediment east of the historic alignment of Cranebrook Creek dated to at least 50,000 years. Aboriginal objects are less likely to occur at depth to the east of Cranebrook Creek, with any Aboriginal objects most likely occurring in the reworked topsoils, which is of particular relevance to the project area. Around 3km east of Cranebrook Creek is and channel infill dating to between 50–75,000 years ago.

Previous archaeological assessments of the project area concluded that there was a reasonable potential for Aboriginal objects to occur within the project area at low frequencies and with low archaeological integrity to depths of 0.3 m minimum to 0.6 m, with greater archaeological integrity below this depth within the Penrith Unit of the Cranebrook Terrace (PLDC 2011, Virtus Heritage 2024). Where Aboriginal objects survive in this unit, they have research value as it may provide an opportunity to further understand the stratigraphic and archaeological value of the Penrith Unit of the Cranebrook Terrace and past Dharug land use on elevated terrain overlooking an unnamed tributary of Cranebrook Creek. This resource and opportunities to understand it are increasingly diminished by development in the local region.

The proposed activity has the potential to harm Aboriginal objects identified in 8 exposures within the project area in the same landform defined in the Archaeological Assessment, as background scatter, Penrith Lakes 2025. An AHIP for salvage and collection is required as Aboriginal objects will be harmed by this proposal and require further mitigation and management.

September 2025 Page 12 of 22



3. Research Design

The research design has been developed in line with requirements of DECCW 2010a. Aboriginal heritage consultation requirements for proponents (DECCW 2010a), the Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW (DCEEW 2010b and Archaeological Investigation of Aboriginal Objects Code of Practice (DCEEW 2010c).

The past archaeological research within the vicinity of the project area and surrounds (refer to Section 2 of this document and Section 4.2 of the AA, Appendix 1 of the ACHA) indicates that there is potential for evidence of Aboriginal occupation to have survived impacts of previous land use.

The broad objective of this research design is to assist in further understanding how Aboriginal people utilised the project area in the past though archaeological investigation to determine the significance, extent, and integrity of any potential archaeological deposits and to analyse any artefacts recovered to document values.

Other research questions that will be investigated under the AHIP will be (and not limited to):

- Does the project area retain any evidence of natural land surfaces or intact archaeological deposits?
- Does the project area retain any evidence of Aboriginal land use?
- · What type of artefacts are present?
- What material evidence is there of former uses of the site?
- For Aboriginal objects and archaeological deposits in the project area,
 - What raw materials and technologies were in use at the site?
 - Do any of the artefacts retain evidence of use?
 - For the retouched flake and broken hand axe in the project area, is there any evidence of residue and for what types of usewear?
 - Is it possible to date the archaeological deposits?
 - If hearths/fire pits/heat treatment pits are located within the project area:
 - What can be inferred about technology choices for these features?
 - What can the features tell us about the chronology of land use in the project area?
 - Should faunal and/or shell material be located, which species present were utilised by Aboriginal people?
 - Can an inference be made as to a preference for marine or terrestrial resources?
 - Is there evidence of any change over time in these preferences or species utilised?
 - Is there evidence for the transport of resources within the environment?
- What does the artefact assemblages indicate about how Aboriginal people were utilising the local landscape?
- How does the results of the collection and artefact analysis compare to other analyses carried out in the locality and the region?
- Are Aboriginal people utilising the area less intensely than other parts of the Penrith Lakes area as
 predicted in ACHA in the predictive model, due to the distance of the project area from chain of ponds
 (in proximity to a water course). How does this pattern of landscape use compare to previous
 archaeological research in the locality and the region of Western Sydney?
- Are certain types of artefact types and artefact materials more prevalent within the project area than
 others as predicted in the ACHA in the predictive model? How do these results compare to previous
 archaeological research in the locality and the region?
- Is there any evidence of a change in occupation strategy over time?

September 2025 Page 13 of 22



• How have the descendants of the Traditional Aboriginal people and the broader Aboriginal community utilised this landscape through generations to the present day? Are there any dateable features (charcoal or hearths) that can provide information on the chronology of the midden or occupation deposit, if identified? What is the age of such features (e.g. Holocene or Pleistocene)? What is their significance within the broader cultural landscape?*

*We note that the AA has assessed that the identification of dateable features in the impact areas is at present considered unlikely.

September 2025 Page 14 of 22



4. Methodology

4.1 IMPACT AND MITIGATION AREAS

Table 3 sets out the proposed impacts and investigation in each works area.

Table 3. Proposed Impacts and Recommended Mitigation

Works Area	Proposed Impacts	Recommended Mitigation	Area proposed for excavation and collection	Estimated # of Days Archaeologists/Geomorphologist Representative Aboriginal Parties on Site
Clearing grass/levelling site	Depth – removal of grass less than <0.1 m	Archaeological Surface Collection during Works by at least two RAPs for topsoil disturbance during initial ground disturbing works	All of the impact area.	3 days Archaeologist (depending on machine size).3 days inclusion of at least one RAP representative.
Car parks	Excavations to depths <0.1 m	-	-	-
Stormwater Tanks	Excavation to depth of 2.3 m	Mechanical excavation to 0.6 m and if Aboriginal objects are identified and soil profiles with integrity and Aboriginal objects are identified with input from a geomorphologist on site, manual hand excavation will be required to depth of impact.	Mechanical excavation in controlled 5 cm spits and pits spaced every 5 m in 50 cm by 50 cm pits.	2 - 5 days with 1 excavation director and a supporting Archaeologist/Geomorphologist (depending on machine size). 2 - 5 days inclusion of at least two RAP representative.
Stormwater pipes (100 - 450 mm diameter) Sumps	Excavation to depth of 0.15 - 1.74 m	Mechanical excavation to 0.6 m for stormwater pipers over a	For pipes over 300 mm diameters, mechanical excavation in	5 - 10 days with 1 excavation director and a supporting Archaeologist/Geomorphologist (not including expansion areas).

September 2025 Page 15 of 22



		diameter of 300 mm and if Aboriginal objects are identified and soil profiles with integrity and Aboriginal objects are identified with input from a geomorphologist on site, manual hand excavation will be required to depth of impact.	controlled 10 cm spits and pits spaced every 5 m.	5 - 10 days inclusion of at least two RAP representative.
Piles	Excavations to depths ~1.5 m	Manual excavation, mechanical auger excavation	geotechnical trench/auger pits and if triggered expansion by manual investigations placed every 10 m in 1 m by 1 m pits	2 days with 1 Archaeologist and 1 Geomorphologist.2 days inclusion of at least two RAP representative.

Due to the cultural significance of the area and potential for out of context Aboriginal objects to occur despite past land use disturbance, the following methodologies have been prepared for a surface collection, community collection and triggers for manual salvage in the even that it is required.

4.2 SITE SET UP

The excavation will be staged within the project area to manage spoil, water and sieving progressively within the project area.

Where removal of concrete slabs/asphalt is required, an excavator would be used. This work would be monitored by a geomorphologist or archaeologist, and RAP representative(s).

4.3 SURFACE COLLECTION

A surface collection will be undertaken of any impact footprint, including machinery access and sample locations, including proposed carparks, sumps and water storage areas.

The proposed surface collection methodology is as follows:

- surface collection will be undertaken by one archaeologist and at least one representative from registered Aboriginal parties;
- surface artefacts will be flagged prior to collection. The flagged site will be photographed to record the spatial distribution of artefacts within the site;

September 2025 Page 16 of 22



- the location of each surface artefact will be recorded using a handheld GPS to record the spatial distribution of artefacts within the site; and
- artefacts will be individually bagged and labelled (including site name, date, and MGA co-ordinate).

4.4 GEOTECHNICAL AUGER HOLE AND TRENCH

Six initial auger pits will be drilled across the project area for proposed areas of piling to characterise the stratigraphic profile and may be expanded mechanically into accessible trenches to enable the safe access to collect soil samples, OSL dating samples and penetrometer readings.

The use of auger pits for the subsurface investigation salvage for piling of in the impact areas for the proposed works is designed to determine the extent and integrity of any PADs that are associated with the sensitive landform and provide a safe method of excavation in sandy profiles at depth.

We propose:

- Six initial auger pits will be excavated to characterise the soil profile.
- Initially auger pits in the impact areas will be excavated to determine confirm the extent and integrity of
 natural and cultural deposits, if extant and disturbance in the agricultural activity areas. The location of
 the auger pits will be guided by the proposed impact footprint.
 - 20 cm by 20 cm mechanical or manual auger pits will be excavated in the impact areas.
 - Fill (including concrete, bitumen, road base and imported fill) will be removed in bulk and not sieved (where concrete and bitumen is present a hole will be sawed for auger access).
 - Excavation of deposits under fill will be undertaken by auger in 20 cm spits.
 - Excavation will be undertaken to the maximum depth of impact from the proposed works.
 - All excavated soil from the primary sample (excluding fill) will be sieved (dry sieving preferably with wet sieving adopted if the deposit cannot be sieved effectively) through 5mm sieves.
 - Soil excavated to enable trench access will have a representative sample sieved.
 - Munsell and pH analysis will be undertaken for each stratigraphic unit within each pit.
 - Photographic records will be taken for each auger pit.
 - The location of each auger pit will be recorded using a handheld GPS to record the spatial distribution of artefacts within the areas.
 - Artefacts will be individually bagged and labelled (including site name, date, and MGA coordinate).
 - Excavations will cease if suspected human remains are encountered. If suspected human remains are uncovered during salvage excavations, the area of these suspected remains must be secured, and the NSW Police notified. If these remains are deemed to required archaeological investigation by the NSW Police or NSW Coroner, then Heritage NSW, and all Registered Aboriginal Parties must be notified.

During auger investigations, if intact deposits, or features such as artefact scatters, midden deposits, intact heat treatment pits, intact hearths, evidence of knapping events, and/or formal tool types in intact deposits (i.e., backed artefacts, retouched artefacts, scrapers, axes, or other tool types considered rarer in a local and/or regional context) are in intact deposits, manual test salvage excavation will be triggered.

4.5 MANUAL (HAND) SALVAGE EXCAVATION

Aboriginal archaeological salvage pits would be positioned approximately 5 m apart along each transect associated with proposed impacts.

The location of salvage pits would be dependent on-site conditions (proposed impacts, services, footings, existing structures):

• Excavation would be undertaken by hand.

September 2025 Page 17 of 22



- Excavation would be undertaken in 1 m x 1 m pits.
- The first pit will be excavated and documented in 5 cm spits.
- Based on the evidence of the first excavation unit, 10 cm spits or sediment profile/stratigraphic excavation (whichever is smaller) may then be implemented.
- Salvage excavation units will be excavated to the depth of the proposed impact or the depth of the
 artefact bearing layers, or the B horizon is reached, or at least two spits of culturally sterile deposit are
 reached, or groundwater is present, whichever is shallowest.
- If hearths are identified, these will be cross sectioned and a dating sample obtained if possible.

4.6 METHODOLOGY FOR CONTROLLED SUBSURFACE SALVAGE - MECHANICAL PITS

It may be necessary to use mechanical excavation to safely excavate salvage pits, notably in the stormwater tank areas or areas for proposed stormwater drainage and sumps.

The use of mechanical pits for salvage of the impact areas for the proposed works is designed to determine the extent and integrity of potential archaeological deposits.

- Initially mechanical excavation pits in the impact areas will be excavated to determine the extent and integrity of natural and cultural deposits, if extant.
 - 1 m by 1 m investigation pits (dimensions may be dictated by the size of excavator bucket) will be excavated in the impact areas.
 - Fill (including concrete, bitumen, road base and imported fill) will be removed in bulk and not sieved.
 - Excavation of deposits under fill will be undertaken by machine in 10 cm spits.
 - Excavation will be undertaken to the maximum depth of impact from the proposed works. Stepping, benching, or shoring of pits may be required to maintain integrity of the pit to depth.
 - All excavated soil from the primary sample unit (excluding fill) will be sieved (dry sieving preferably with wet sieving adopted if the deposit cannot be sieved effectively) through 5 mm
 - Soil excavated as a result of stepping, benching, or shoring will be sample sieved.
 - Munsell and pH analysis will be undertaken for each stratigraphic unit within each investigation pit.
 - A section drawing of at least one wall of the investigation pit will be completed for each investigation pit. Stepping, benching, or shoring of pits may be required to safely access the mechanical pits for section drawing.
 - Photographic records will be taken for each investigation pit.
 - The location of each investigation pit will be recorded using a handheld GPS to record the spatial distribution of artefacts within the areas.
 - Artefacts will be individually bagged and labelled (including site name, date, and MGA coordinate).
 - Excavations will cease if suspected human remains are encountered. If suspected human remains are uncovered during salvage excavations, the area of these suspected remains must be secured, and the NSW Police notified. If these remains are deemed to required archaeological investigation by the NSW Police or NSW Coroner, then Heritage NSW, and all Registered Aboriginal Parties must be notified.

During the excavation of pits, if features such as intact midden deposits, intact heat treatment pits, intact hearths, evidence of knapping events, and/or more than five formal tool types in intact deposits (i.e., backed artefacts, scrapers, axes, or other tool types considered rare in a local and/or regional context) are located in a 1 m x 1 m area in intact deposits, manual salvage will be triggered.

September 2025 Page 18 of 22



4.7 EXPANSION OR PLACEMENT OF ADDITIONAL EXCAVATION AREAS

Where certain triggers are met, additional excavation areas may be undertaken to salvage the extent of archaeological feature and artefacts and to understand the archaeological significance of the project area within the impact area.

During excavation works, certain features may trigger expansion of existing salvage areas, such as:

- If 10 or more artefacts (including conjoins) are located within a 50 cm square excavation pit.
- The presence of an intact midden deposit.
- The presence of an intact heat treatment pit or intact hearth.
- Evidence of stone artefacts in intact stratified deposit or clear feature.
- Evidence of early interaction between settlers and Aboriginal people such as knapped glass or ceramics (the presence of clear manual percussion including a dorsal scar or bulb of percussion would be required and glass/ceramic that dates to the early to mid-nineteenth century).
- The presence of rare or formal intact deposit, i.e. backed artefacts, scrapers, axes, elouera, grounded edge tools or other tool types considered rarer in a local and/or regional context.
- The expansion of the pit should continue until the full extent of the feature or deposit has been identified and recorded.

Excavation would cease once sufficient information was collected to salvage the extent, nature and significance of the archaeological deposits to mitigate the impact of development.

4.8 RECORDING DURING EXCAVATION AND SIEVING

The recording process will include:

- RTK, GPS or manual plotting of all excavation pits, in situ artefacts and cultural layers.
- Bagging any archaeological material identified during the excavation or sieving (such as stone artefacts, animal bone, shell, charcoal) and labelling with a unique number based on the relevant square and stratigraphic layer or unit.
- Where possible, collecting suitable samples for scientific dating and submitting to an appropriate facility for dating.
- Context numbers will be applied to features, deposit, cuts in the deposit, architecture, post-holes, and other archaeological features.
- Soil samples will be collected for each artefact-bearing stratigraphic unit.
- The location of the trenches/pits will be surveyed and photographed photogrammetrically for post-field planning. The exact location of the trenches/pits will be demarcated by the excavation director/s and recorded by a qualified archaeological surveyor. A full site plan showing the location of all trenches and excavated features (if any) will be created.
- The salvage excavation process will be recorded using digital photograph, and the final cross sections of each pit/trench will be illustrated, noting stratigraphy.

4.9 COMMUNITY COLLECTION

Community collection or opportunity to inspect areas for cultural salvage to RAPs would include ground disturbing works to the depth of topsoil removal, including proposed carparks, sumps and water storage areas, where safe to so and organised by Morson Group or the delegated Construction Manager and the RAPs.

The proposed community collection methodology is as follows:

September 2025 Page 19 of 22



- surface collection will be undertaken by at least two representatives from registered Aboriginal parties;
- surface artefacts will be flagged prior to collection. The flagged site will be photographed to record the spatial distribution of artefacts within the site;
- the location of each surface artefact will be recorded using a handheld GPS to record the spatial distribution of artefacts within the site; and
- artefacts will be individually bagged and labelled (including site name, date, and MGA co-ordinate).
- Repository on site would be with Morson Group in a secure locked container, unless nominated separately as part of RAP consultation for the AHIP.
- If archaeological assistance is required, it can be made on call.

4.10 REPORTING

Recording of artefacts will be undertaken in accordance with Requirement 26 of the *Code of Practice for Archaeological Investigation of Aboriginal objects in NSW.* Following completion of excavations, an Aboriginal Site Impact Recording form will be completed and submitted to the AHIMS Registrar as soon as practicable, for each AHIMS site that has been the subject of salvage in accordance with the requirements of the Code. The results of the excavations will be incorporated into an archaeological excavation report.

4.10.1. Attributes to be recorded for Stone Artefacts

The table below provides an indication of the attributes to be recorded for stone artefacts.

Table 4: Attributes to be recorded

General Attributes (All Artefacts)	Additional Attributes (Flakes)	Additional Attributes (Cores)
Artefact Type	Platforms (width, thickness, surface, overhang removal)	Rotated
Raw Material	Termination	Platform Preparation
Artefact Weight (g)	Retouch (Location and Type)	Scar Type
Artefact Measurements (Length, Width, Thickness)	Breakage	Exhausted
Cortex (Amount and Type)		
Heat Affect		

4.11 SHORT AND LONG TERM CARE OF ABORIGINAL OBJECTS

Options for Short Term Care of Aboriginal Objects

It is proposed that artefacts recovered through the salvage excavation program will be temporarily held by Virtus Heritage at their offices at Kingscliff or Sydney unless an alternative care arrangement is sought by Registered Aboriginal Parties. Where requested, Virtus Heritage will provide access to artefacts to the Registered Aboriginal Parties.

For community collection, without archaeological supervision, repository on site would be with Morson Group in a secure locked container, unless nominated separately as part of RAP consultation for the AHIP.

September 2025 Page 20 of 22



Opportunities for Registered Aboriginal Parties to participate in the cleaning and analysis of artefacts will be considered.

Options for Long Term Care of Aboriginal Objects

Options being considered for the long-term care of Aboriginal objects recovered from the archaeological test excavation under the AHIP application include:

- Lodgement of Aboriginal objects with Deerubbin Local Aboriginal Land Council or other Aboriginal organisation under a Care Agreement, for example at the Parramatta Gaol Keeping Place.
- Lodgement of the Aboriginal objects at the Parramatta Square/Phive Keeping Place
- On site display under a Care Agreement.
- On display for interpretation in the development or in another area publicly for a selection of objects as suggested a RAP.
- Other options identified by Registered Aboriginal Parties

4.12 SAFETY AND ENVIRONMENTAL MANAGEMENT

The following logistics will need to be arranged by the proponent for the excavation:

- A small to medium (5 14 tonne) excavator with a flat bucket of 1 m width or less for mechanical excavation.
- Auger and black case for auger for OSL sampling
- Removal of overburden and fill
- Toilet facilities (Men's and Women's).
- Where wet sieving is required:
 - A water source for the wet sieving of excavated soil (e.g. on-site water source or a water truck).
 - Watertight skip bins to capture sieve water and spoil with forklift capabilities.
 - Emptying of bins of water and sieved spoil 2-3 times a day, in accordance with EPA environmental management requirements.
 - Use of a forklift or Manitou to empty bins and a location to handle the volume of water runoff and spoil.
- Secure lockable storage for equipment and retrieved artefacts.
- · Contamination control if necessary.
- · Backfilling of excavated pits with clean fill.

September 2025 Page 21 of 22



5. References

DECCW (2010a) Aboriginal heritage consultation requirements for proponents 2010.

DECCW (2010b) Code of Practice for Archaeological Investigation of Aboriginal Objects in NSW.

DECCW (2010c) Due Diligence Code of Practice for the Protection of Aboriginal Objects in NSW and Archaeological Investigation of Aboriginal Objects Code of Practice.

Mitchell, P. (2010) Geomorphology and soils in relation to archaeological investigations on the Cranebrook Terrace, Penrith Lakes, NSW. Report to Comber Consultants for PLDC.

PLDC (2011) Penrith Lakes Scheme Area Aboriginal Heritage Assessment Report. Published by Penrith Lakes Development Corporation.

Virtus Heritage (2024) Archaeological Assessment Castlereagh Tourism Development 39-65 Old Castlereagh Road, Castlereagh NSW. Report to Morson Group.

Williams A, A. Burrow, P. Toms, O. Brown, M. Richards and T. Bryant (2017) 'The Cranebrook terrace revisited: recent excavations of an early Holocene alluvial deposit on the banks of the Nepean River, NSW, and their implications for the future work in the region, *Australian Archaeology*, 83(3) pp. 100–109

September 2025 Page 22 of 22



Appendix D AHIMS Site Search and other Search Results

September 2025 Page 59 of 61

Your Ref/PO Number : 537

Client Service ID: 1022220

Date: 10 July 2025

Virtus Heritage Pty Ltd - Pottsville

38 Border Crescent

Pottsville New South Wales 2489


Attention: Kate Morris

Email: k.morris@virtusheritage.com.au

Dear Sir or Madam:

AHIMS Web Service search for the following area at Datum :GDA, Zone : 56, Eastings : 281848.0 - 289036.0, Northings : 6261482.0 - 6270558.0 with a Buffer of 0 meters, conducted by Kate Morris on 10 July 2025.

The context area of your search is shown in the map below. Please note that the map does not accurately display the exact boundaries of the search as defined in the paragraph above. The map is to be used for general reference purposes only.



A search of Heritage NSW AHIMS Web Services (Aboriginal Heritage Information Management System) has shown that:

87	Aboriginal sites are recorded in or near the above location.
0	Aboriginal places have been declared in or near the above location.*

If your search shows Aboriginal sites or places what should you do?

- You must do an extensive search if AHIMS has shown that there are Aboriginal sites or places recorded in the search area.
- If you are checking AHIMS as a part of your due diligence, refer to the next steps of the Due Diligence Code of practice.
- You can get further information about Aboriginal places by looking at the gazettal notice that declared it.
 Aboriginal places gazetted after 2001 are available on the NSW Government Gazette
 (https://www.legislation.nsw.gov.au/gazette) website. Gazettal notices published prior to 2001 can be
 obtained from Heritage NSW upon request

Important information about your AHIMS search

- The information derived from the AHIMS search is only to be used for the purpose for which it was requested. It is not be made available to the public.
- AHIMS records information about Aboriginal sites that have been provided to Heritage NSW and Aboriginal places that have been declared by the Minister;
- Information recorded on AHIMS may vary in its accuracy and may not be up to date. Location details are recorded as grid references and it is important to note that there may be errors or omissions in these recordings,
- Some parts of New South Wales have not been investigated in detail and there may be fewer records of Aboriginal sites in those areas. These areas may contain Aboriginal sites which are not recorded on AHIMS.
- Aboriginal objects are protected under the National Parks and Wildlife Act 1974 even if they are not recorded as a site on AHIMS.
- This search can form part of your due diligence and remains valid for 12 months.



Your Ref/PO Number: 537

Extensive search - Site list report Client Service ID: 1022221

<u>SiteID</u>	<u>SiteName</u>	<u>Datum</u>	Zone	Easting	Northing	<u>Context</u>	Site Status **	<u>SiteFeatures</u>	<u>SiteTypes</u>	<u>Reports</u>
45-5-0541	RP5 Penrith Leagues Club	AGD	56	285350	6262560	Open site	Valid	Artefact : -	Open Camp Site	102450,10315
										5,103360
	Contact	Recorders		abeth Rich	(0(1000	0 4	** 1. 1	Permits	0 0 0	4.000.400.455.4
45-5-0790	Jamison_and Blaikie Roads;	AGD	56	284750	6261800	Open site	Valid	Artefact : -	Open Camp Site	1633,103155,1 03360
	Contact	Recorders	Pam	Dean-Jones				<u>Permits</u>		03300
45-5-0493	Emu Plains (EP/1 P/3)	AGD		281830	6262460	Open site	Valid	Artefact : -	Open Camp Site	1018
	Contact	Recorders	lim I	Kohen		-		Permits Permits		
45-5-0222	Jamisons Creek Emu Plains	AGD		282220	6262184	Open site	Valid	Artefact : -	Open Camp Site	822
	Contact	Recorders	Iim I	Kohen		•		Permits		
45-5-5379	SMDS Basin I Area 06 PAD	GDA	,	288770	6265160	Open site	Valid	Artefact : -, Potential		
						•		Archaeological		
								Deposit (PAD) : -		
	Contact	Recorders			-	lls,Ms.Sophie Jenning		<u>Permits</u>	5411	
45-5-0333	Penrith Lakes 23	AGD	56	285375	6269289	Open site	Valid	Artefact : -	Open Camp Site	260,526,1018
	Contact	Recorders	,	Kohen				<u>Permits</u>	872	
45-5-0070	Lapstone Creek (Emu Plains)	AGD	56	282116	6262822	Open site	Valid	Artefact : -	Open Camp Site	527
	Contact	Recorders		Kohen				<u>Permits</u>		
45-5-3598	ADI: FF/30 (Springwood)	GDA	56	288835	6265442	Open site	Valid	Artefact : 1		102155,10245
										0
	Contact	Recorders	Io M	cDonald Cult	ural Heritage N	Janagement see GMI		Permits		
45-5-3599	Contact ADI: FF/31 (Springwood)	Recorders GDA	,			Management see GMI Open site		Permits Artefact : 19		102450
45-5-3599	ADI: FF/31 (Springwood)	GDA	56	288950	6265366	Open site	Valid	Artefact : 19		102450
	ADI: FF/31 (Springwood) <u>Contact</u>	GDA Recorders	56 Jo M	288950 cDonald Cult	6265366 ural Heritage N	Open site Management see GML	Valid _	Artefact : 19 Permits		
45-5-3599 45-5-5019	ADI: FF/31 (Springwood)	GDA	56 Jo M	288950	6265366	Open site	Valid	Artefact : 19		102450
	ADI: FF/31 (Springwood) <u>Contact</u>	GDA Recorders	56 Jo M	288950 cDonald Cult	6265366 ural Heritage N	Open site Management see GML	Valid _	Artefact : 19 Permits Potential		
	ADI: FF/31 (Springwood) <u>Contact</u>	GDA Recorders GDA Recorders	56 Jo M 56	288950 cDonald Cult 285850 .ber Consulta	6265366 ural Heritage M 6262985	Open site Management see GMI Open site	Valid Valid	Artefact : 19 Permits Potential Archaeological	4477	
	ADI: FF/31 (Springwood) Contact Union Street Penrith	GDA Recorders GDA	56 Jo M 56	288950 cDonald Cult 285850	6265366 ural Heritage M 6262985	Open site Management see GMI Open site	Valid Valid	Artefact : 19 Permits Potential Archaeological Deposit (PAD) : 1	4477	
45-5-5019	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact	GDA Recorders GDA Recorders	56 Jo M 56 Com 56	288950 cDonald Cult 285850 ber Consulta 285973	6265366 ural Heritage N 6262985 nts Pty Limited 6263538	Open site Management see GMI Open site d,Comber Consultant	Valid Valid s Pty Limited,Ms.A Valid n Anderson	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Artefact: - Permits	4477	
45-5-5019	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1	GDA Recorders GDA Recorders GDA	56 Jo M 56 Com 56 Kelle	288950 cDonald Cult 285850 ber Consulta 285973	6265366 ural Heritage N 6262985 nts Pty Limited 6263538	Open site Management see GMI Open site d,Comber Consultant Open site	Valid Valid Valid s Pty Limited,Ms.A	Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential	4477	
45-5-5019 45-5-5191	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact	GDA Recorders GDA Recorders GDA Recorders	56 Jo M 56 Com 56 Kelle	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting	6265366 ural Heritage N 6262985 nts Pty Limited 6263538 ale Consulting	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir	Valid Valid s Pty Limited,Ms.A Valid n Anderson	Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological	4477	
45-5-5019 45-5-5191	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS	GDA Recorders GDA Recorders GDA Recorders GDA	56 Jo M 56 Com 56 Kelle 56	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting 285284	6265366 ural Heritage M 6262985 nts Pty Limited 6263538 cale Consulting 6269516	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): -	4477	
45-5-5019 45-5-5191 45-5-4568	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact	GDA Recorders GDA Recorders GDA Recorders GDA Recorders	56 Jo M 56 Com 56 Kelle 56	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting 285284	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits		103872
45-5-5019 45-5-5191	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30	GDA Recorders GDA Recorders GDA Recorders GDA Recorders AGD	56 Jo M 56 Com 56 Kelle 56 GML	288950 cDonald Cult 285850 ober Consulta 285973 eher Nighting 285284 other Heritage Pty 284230	6265366 ural Heritage M 6262985 nts Pty Limited 6263538 cale Consulting 6269516	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: -	Open Camp Site	
45-5-5019 45-5-5191 45-5-4568 45-5-0591	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30 Contact	Recorders GDA Recorders GDA Recorders GDA Recorders AGD Recorders	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim H	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting 285284 Heritage Pty 284230 Kohen	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516 Ltd - Surry Hi 6266400	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site lls,Doctor.Tim Owen Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: - Permits	Open Camp Site 28	103872
45-5-5019 45-5-5191 45-5-4568	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30	GDA Recorders GDA Recorders GDA Recorders GDA Recorders AGD	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim H	288950 cDonald Cult 285850 ober Consulta 285973 eher Nighting 285284 other Heritage Pty 284230	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: -	Open Camp Site	103872
45-5-5019 45-5-5191 45-5-4568 45-5-0591	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30 Contact	Recorders GDA Recorders GDA Recorders GDA Recorders AGD Recorders	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim H 56	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting 285284 Heritage Pty 284230 Kohen	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516 Ltd - Surry Hi 6266400	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site lls,Doctor.Tim Owen Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: - Permits	Open Camp Site 28	103872 1064,102450 1018,102450,1
45-5-5191 45-5-4568 45-5-0591	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30 Contact Penrith P/1 (duplicate of 45-5-0290)	GDA Recorders GDA Recorders GDA Recorders GDA Recorders AGD Recorders	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim H 56	288950 cDonald Cult 285850 sber Consulta 285973 eher Nighting 285284 . Heritage Pty 284230 Kohen 285520	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516 Ltd - Surry Hi 6266400	Open site Management see GMI Open site d,Comber Consultant Open site Pty Ltd,Mr.Benjamir Open site lls,Doctor.Tim Owen Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: - Permits Artefact: - Permits Artefact: -	Open Camp Site 28 Open Camp Site	103872 1064,102450 1018,102450,1
45-5-5019 45-5-5191 45-5-4568 45-5-0591 45-5-0522	ADI: FF/31 (Springwood) Contact Union Street Penrith Contact Museum Drive Penrith AFT 1 Contact Escarpment 01 AS Contact Penrith Lakes 30 Contact Penrith P/1 (duplicate of 45-5-0290) Contact	Recorders GDA Recorders GDA Recorders GDA Recorders AGD Recorders AGD Recorders	56 Jo M 56 Com 56 Kelle 56 GML 56 Jim H 56	288950 cDonald Cult 285850 ber Consulta 285973 eher Nighting 285284 Heritage Pty 284230 Kohen 285520 Kohen 285400	6265366 ural Heritage M 6262985 Ints Pty Limited 6263538 Tale Consulting 6269516 Ltd - Surry Hi 6266400 6263940	Open site Management see GMI Open site d,Comber Consultant: Open site Pty Ltd,Mr.Benjamir Open site lls,Doctor.Tim Owen Open site Open site Open site	Valid Valid s Pty Limited,Ms.A Valid n Anderson Valid Valid	Artefact: 19 Permits Potential Archaeological Deposit (PAD): 1 Alandra Tasir Permits Artefact: - Permits Artefact: -, Potential Archaeological Deposit (PAD): - Permits Artefact: - Permits Artefact: - Permits Artefact: - Permits	Open Camp Site 28 Open Camp Site	103872 1064,102450 1018,102450,1 03155,103360

Report generated by AHIMS Web Service on 10/07/2025 for Kate Morris for the following area at Datum: GDA, Zone: 56, Eastings: 281848.0 - 289036.0, Northings: 6261482.0 - 6270558.0 with a Buffer of 0 meters.. Number of Aboriginal sites and Aboriginal objects found is 87



Extensive search - Site list report

Your Ref/PO Number: 537

Client Service ID: 1022221

<u>iteID</u>	<u>SiteName</u>	<u>Datum</u>	Zone	Easting	Northing	<u>Context</u>	Site Status **	<u>SiteFeature</u>	<u>s</u>	<u>SiteTypes</u>	<u>Reports</u>
5-5-5238	Andrews Road PAD 1	GDA	56	286905	6264763	Open site	Destroyed	Artefact : -			104180
	Contact	Recorders	Bios	is Pty Ltd - V	Vollongong,Bio	sis Pty Ltd - Woll	ongong,Mrs.Samantha	a Keats,Mrs.S	Permits Permits	4518	
5-5-2414	L1 (Penrith Lakeside Village)	GDA	56	286799	6266617	Open site	Valid	Artefact : -		Open Camp Site	102450,10418 0
	Contact	Recorders	Mar	y Dallas Cons	sulting Archaed	ologists (MDCA),B	Biosis Pty Ltd - Wollor	igong,Mrs.Sai	Permits	939,1694,1803	
5-5-0317	Penrith Lakes 3	AGD		284461	6269271	Open site	Valid	Artefact : -		Open Camp Site	256,260,526,10 18,105447
	Contact	Recorders	,	Kohen					<u>Permits</u>		07.00.00.00.00
-5-0318	Penrith Lakes 4	GDA		283031	6267186	Open site	Valid	Artefact : -		Open Camp Site	256,260,526,10 18,105447
	Contact	Recorders		Kohen					<u>Permits</u>	3891	
5-5-3816	Emu Plains Rail Stabling Yards	GDA	56	284015	6263583	Open site	Destroyed	Artefact : 1			
	<u>Contact</u>	Recorders	Doct	tor.Alan Will	iams,Doctor.Al	an Williams			<u>Permits</u>	3485,4823	
5-5-3817	Emu Plains Rail Stabling Yards1	GDA	56	284138	6263601	Open site	Destroyed	Artefact : 1			
	Contact	Recorders	Doct	or.Alan Will	iams,Doctor.Al	an Williams			<u>Permits</u>	3282,4823	
-5-4302	TNR-3	GDA	56	288545	6265150	Open site	Valid	Artefact : 1			
	Contact	Recorders	Doct	tor.Jo McDon	ald				Permits	3619	
-5-5730	Nepean River Trail 05	GDA	56	282938	6269016	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.N	Aichael Jacks	on,Jackson Wa	rd Archaeology P	ty Ltd		<u>Permits</u>		
5-5-5732	Nepean River Trail 07	GDA	56	282948	6269276	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.N	Michael Jacks	on,Jackson Wa	rd Archaeology P	ty Ltd		Permits Permits		
5-5-0052	Emu Plains F4-1	AGD	56	281800	6262200	Open site	Valid	Artefact : -		Open Camp Site	100450
	Contact	Recorders	Mar	y Dallas Cons	sulting Archaed	ologists (MDCA),E	Elizabeth Rich		<u>Permits</u>		
5-5-0592	Penrith Lakes 33	AGD	56	286200	6268200	Open site	Valid	Artefact : -		Open Camp Site	1064
	Contact	Recorders	Jim I	Kohen					Permits Permits	847,872,2174	
-5-0593	Penrith Lakes 32	AGD	•	286250	6267700	Open site	Valid	Artefact : -		Open Camp Site	11,526,1063
	Contact	Recorders	Iim I	Kohen					Permits	1067	
5-5-1026	ADI-25;	AGD		288880	6264930	Open site	Valid	Artefact : -		Isolated Find	102155,10245 0,102573
	Contact	Recorders	Doct	tor.Jo McDon	ald				Permits Permits	5411	
5-5-0323	Penrith Lakes 10	AGD	56	284461	6269271	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018, 05447
	Contact	Recorders	Jim I	Kohen					<u>Permits</u>	872	
5-5-0324	Penrith Lakes 11	AGD	56	285357	6270203	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018, 05447
	Contact	Recorders	•	Kohen					<u>Permits</u>		
5-5-0325	Penrith Lakes 12	AGD		283546	6269253	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018, 05447
	Contact	Recorders	Jim I	Kohen					<u>Permits</u>		



Extensive search - Site list report

Your Ref/PO Number: 537 Client Service ID: 1022221

<u>SiteID</u>	<u>SiteName</u>	<u>Datum</u>	Zone	Easting	Northing	<u>Context</u>	Site Status **	<u>SiteFeatur</u>	res	<u>SiteTypes</u>	<u>Reports</u>
45-5-0328	Penrith Lakes 17	AGD	56	283617	6265596	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018
	Contact	Recorders	Jim K	Kohen					<u>Permits</u>	28	
45-5-0330	Penrith Lakes 19	AGD	56	284496	6267442	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450
	Contact	Recorders	Jim k	Kohen					Permits	28	
45-5-0334	Penrith Lakes 24	AGD		287257	6266581	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450
45 5 0006	Contact	Recorders	,		(0(5(05	0 11	77 1: 1	A . C .	<u>Permits</u>	0 0 00	260 526 1010 1
45-5-0336	Penrith Lakes 27	AGD		288189	6265685	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450
	Contact	Recorders		Kohen	(O(##40		** 1. 1		<u>Permits</u>	7 1 1 170 1	400455 40045
45-5-1024	ADI-23	AGD	56	288700	6265510	Open site	Valid	Artefact : -		Isolated Find	102155,10245 0,102573,1054 76
	<u>Contact</u>	Recorders		•	ıld,Ms.Jenni Ba				<u>Permits</u>		
45-5-5020	Tench Reserve AFT 1	GDA	56	283626	6261646	Open site	Valid	Artefact : -			
	Contact	Recorders	Kelle	her Nighting	ale Consulting	Pty Ltd,Miss.Kristen	Taylor		<u>Permits</u>		
45-5-5685	170 Russell Street	GDA	56	282934	6263991	Open site	Valid	Artefact : -			104390
	Contact	Recorders	Com	ber Consulta	nts Pty Limited	l,Ms.Agata Calabrese	:		Permits		
45-5-5731	Nepean River Trail 06	GDA	56	282951	6269734	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.M	lichael Jackso	n,Jackson Wa	rd Archaeology Pty L	td		Permits		
45-5-0540	RP4 Peach Tree Creek	AGD	56	284960	6262120	Open site	Valid	Artefact : -		Open Camp Site	103155,10336 0
	Contact	Recorders		beth Rich					Permits		
45-5-0287	Emu Plains (Jamisons Creek)	AGD	56	283052	6261743	Open site	Partially Destroyed	Artefact : -		Open Camp Site	260,1018,1031 55,103360
	Contact	Recorders		Kohen					<u>Permits</u>	1423,1842	
45-5-0290	The Island (duplicate of 45-5-0522)	AGD	56	285661	6263989	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450,103155, 103360
	Contact	Recorders	,						<u>Permits</u>	5327	
45-5-3796	Cranebrook Escarpment 1 (CE1)	GDA	56	285600	6269450	Open site	Valid	Artefact : 1	10		101748
	Contact	Recorders	Com	ber Consulta	nts Pty Limited	l			<u>Permits</u>		
45-5-5389	SMDS Basin I AFT 16	GDA	56	288674	6265173	Open site	Valid	Artefact : -			
	<u>Contact</u>	Recorders	GML	Heritage Pty	Ltd - Surry Hi	lls,Ms.Sophie Jenning	gs		Permits	5411	
45-5-0327	Penrith Lakes 16	AGD	56	285428	6266546	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450,105447
	Contact	Recorders	Jim k	Kohen					<u>Permits</u>		
45-5-0366	Emu Plains Emu Plains 4	AGD	56	285107	6264253	Open site	Valid	Artefact : -		Open Camp Site	1018,102450,1 03155,103360



Extensive search - Site list report

Your Ref/PO Number: 537

Client Service ID: 1022221

SiteID	<u>SiteName</u>	<u>Datum</u>	<u>Zone</u>	Easting	Northing	Context	Site Status **	<u>SiteFeatures</u>		<u>SiteTypes</u>	<u>Reports</u>
	Contact	Recorders		Kohen					ermits		
45-5-3904	EPRSY 3(PAD)	GDA	56	284000	6263615	Open site	Destroyed	Artefact : -, Po	tential		103762
								Archaeologica			
	Contact	Recorders	Doct	or Alan Willi	iame Doctor Al-	an Williams,Ms.Geor	ria Rurnott	Deposit (PAD)	:- ermits	3485,4823	
45-5-5021	Tench Reserve IF 1	GDA		283452	6261519	Open site	Valid	Artefact : -	<u> </u>	3403,4023	
15 5 5021	Contact	Recorders				Pty Ltd,Miss.Krister			ermits	4528	
45-5-1025	ADI-24;	AGD		288540	6264980	Open site	Valid	Artefact : -	<u> </u>	Isolated Find	102155,10245
15 5 1025	101 21,	nab	30	200310	0201700	open site	vana	m telact.		isolated i ma	0
	Contact	Recorders	Doct	or.Jo McDon	ald			<u>Pe</u>	ermits	5411	
45-5-5484	Emu Plains Railway AFT	GDA	56	284068	6263560	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.M	latthew Barl	oer,NGH Herita	ge - Fyshwick		<u>Pe</u>	ermits		
45-5-5728	Nepean River Trail 03	GDA	56	282727	6267103	Open site	Valid	Artefact : -			
	Contact	Recorders	Mr.M	lichael Jacks	on,Jackson Wa	rd Archaeology Pty I	td	<u>Pe</u>	ermits		
45-5-5908	SummitCare Penrith PAD	GDA	56	285290	6261928	Open site	Valid	Potential			
								Archaeologica			
	Control	D	C) (I	11 to Do				Deposit (PAD)			
45-5-5390	Contact SMDS Basin I AFT 15	Recorders GDA		288860	y Lta - Surry Hi 6265155	lls,Mr.Jacob (GML) K Open site	valid	Artefact : -	<u>ermits</u>		
43-3-3390						•					
45-5-0319	Contact Penrith Lakes 5	Recorders GDA		283157	6268242	lls,Ms.Sophie Jenning	gs Valid	Artefact : -	ermits	Open Camp Site	260,526,1018,1
45-5-0519	Pennun Lakes 5	GDA	50	203137	0200242	Open site	valiu	Artelact : -		Open camp site	05447
	Contact	Recorders	Jim F	Kohen				<u>Pe</u>	ermits	3891	00117
45-5-0326	Penrith Lakes 15	AGD	56	285428	6266546	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1
											02450,105447
	Contact	Recorders		Kohen					<u>ermits</u>	28	
45-5-0331	Penrith Lakes 20	AGD	56	286325	6267478	Open site	Valid	Artefact : -		Open Camp Site	260,526,1018,1 02450
	Contact	Recorders	lim k	Kohen				Pe	ermits	28,1067	02450
45-5-5740	EPRSY 1	GDA	,	284199	6263600	Open site	Valid	Artefact : -	<u> </u>	20,1007	
	Contact	Recorders		ine Quinlan					ermits		
45-5-2491	Coreeen Ave 1	GDA		287199	6263429	Open site	Valid	Artefact : -	<u> </u>	Open Camp Site	98259,102450,
						~ p				~ p p	103155,10336
											0
	<u>Contact</u>	Recorders				/r.Matthew Barber,N			ermits	1367	
45-5-0281	Cranebrook Creek, CC/1	AGD	56	285150	6266723	Open site	Valid	Artefact : -,			260,526,1018,1
								Aboriginal Cer			02450
	Contact	Recorders	Jim F	Zohon.				and Dreaming	:- ermits	28	
	Contact	<u>Recorders</u>	Jun r	Konen				<u>Pt</u>	<u> </u>	40	



Extensive search - Site list report

Your Ref/PO Number: 537

Client Service ID: 1022221

<u>SiteID</u>	<u>SiteName</u>	<u>Datum</u>	Zone	Easting	Northing	<u>Context</u>	Site Status **	<u>SiteFeatures</u>	<u>SiteTypes</u>	<u>Reports</u>
45-5-3331	ADI/FF-30	AGD	56	288835	6265442	Open site	Valid	Artefact : 1		99635,102155, 102450,10257 3,103618
	<u>Contact</u> T Russell	Recorders	Jo M	cDonald Cult	ural Heritage l	Management see GM	L	<u>Perm</u>	<u>its</u> 3057	
45-5-3318	Western Sydney 6	GDA	56	287710	6264801	Open site	Valid	Artefact : 5		100554,10245 0
	<u>Contact</u> Searle	Recorders	Navi	n Officer Her	itage Consulta	nts Pty Ltd		Permi		
45-5-0314	Penrith Lakes 28	AGD		286325	6267478	Open site	Valid	Artefact : -	Open Camp Site	256,260,526,10 18,102450
	Contact	Recorders	,	Kohen	6060000		** 1. 1	Permi		0.00.404.0.4004
45-5-0340	Penrith Regional Art Gallery	AGD		284048	6262220	Open site	Valid	Art (Pigment or Engraved) : -	Rock Engraving	260,1018,1031 55,103360
45 4 0040	Contact	Recorders		les.D Power	6065450	0 "	77 1: 1	Permi		0446400450
45-1-0219	Penrith Lakes 39	AGD		284930	6267150	Open site	Valid	Artefact : -	Open Camp Site	2446,102450
	Contact	Recorders	,	Kohen				<u>Permi</u>	_	
45-5-3941	PL53	GDA	56	283676	6270056	Open site	Partially Destroyed	Artefact : -, Potent Archaeological Deposit (PAD) : -	ial	105454,10572 9
	Contact	Recorders	Com	ber Consulta	nts Pty Limite	d,Mr.Shaun Hooper,F	leritage Now - Bel	mont,Heritae Perm	<u>its</u> 5297	
45-5-5470	Andrews Road PAD 1 Reburial	GDA	56	287428	6264919	Open site	Valid	Artefact : -		
	Contact	Recorders	Bios	is Pty Ltd - W	ollongong,Mrs	s.Samantha Keats		Permi	<u>its</u>	
45-5-0051	Emu Plains	AGD		281883	6265379	Closed site	Valid	Art (Pigment or Engraved) : -	Shelter with Art	
	Contact	Recorders	Fred	McCarthy				<u>Permi</u>	<u>its</u>	
45-5-0589	Penrith Lakes 29	AGD	56	284300	6266280	Open site	Valid	Artefact : -	Open Camp Site	1064
	Contact	Recorders	Jim I	Kohen				<u>Permi</u>	<u>its</u> 28	
45-5-0530	Upper Castlereagh, UC/1	GDA	56	283035	6267149	Open site	Valid	Artefact : -	Open Camp Site	1018
	Contact	Recorders	Jim I	Kohen				Permi	its 3891	
45-5-2850	Vincent Road 1	AGD	56	287550	6268250	Open site	Valid	Artefact : -		
	Contact	Recorders	Doct	or.Susan (lef	t ahms) Mcint	vre-Tamwov		Permi	its 1599	
45-5-0329	Penrith Lakes 18	AGD		283617	6265596	Open site	Valid	Artefact : -	Open Camp Site	260,526,1018
	Contact	Recorders	lim I	Kohen		-		Permi	its 28	
45-5-0332	Penrith Lakes 21	AGD		284514	6266528	Open site	Valid	Artefact : -	Open Camp Site	260,526,1018,1 02450
	Contact	Recorders	Jim I	Kohen				<u>Permi</u>	<u>its</u> 28	
45-5-0288	Emu Plains	AGD	56	282030	6262546	Open site	Valid	Artefact : -	Open Camp Site	260,1018
	Contact	Recorders	Jim I	Kohen				Permi	<u>its</u>	
45-5-5311	River Road AS1	GDA		284756	6263365	Open site	Valid	Artefact : -, Potent: Archaeological Deposit (PAD) : -		



Extensive search - Site list report

Your Ref/PO Number: 537 Client Service ID: 1022221

SiteID Zone Northing Context Site Status ** SiteName Datum **Easting** SiteFeatures SiteTypes Reports Contact Recorders Biosis Pty Ltd - Wollongong, Eco Logical Australia Pty Ltd - Sydney - Individual user Permits 4634.4731 Potential 45-5-5902 Penrith Stadium PAD GDA 56 285738 6262322 Open site Valid Archaeological Deposit (PAD): -Contact Recorders Curio Projects Pty Ltd, Miss. Rebecca Agius **Permits** 5314 Nepean River Trail 04 GDA 45-5-5729 56 282884 6268421 Valid Artefact: -Contact Recorders Mr.Michael Jackson, Jackson Ward Archaeology Pty Ltd **Permits** 1018,103155,1 45-5-0539 RP3 Peach Tree Creek AGD 56 284920 6262050 Open site Valid Artefact: -Open Camp Site 03360 Contact Recorders Elizabeth Rich **Permits** 45-5-0282 Upper Castlereagh 56 282979 Valid Artefact: -Open Camp Site **GDA** 6267050 Open site 260.1018 **Permits Contact** Recorders Jim Kohen 3891 45-5-0590 Penrith Lakes 31 56 284610 6266550 Valid Artefact: -1064.102450 AGD Open site Open Camp Site Contact Recorders Iim Kohen **Permits** 28 1018.103155.1 45-5-0495 Jamisons Creek JC/2 Penrith AGD 56 282890 6261700 Open site Valid Artefact: -Open Camp Site 03360 Recorders Contact Jim Kohen **Permits** GDA 56 287679 Valid Artefact: 1 100554,10245 45-5-3317 Western Sydney 5 6264900 Open site 0 Contact Searle Recorders Navin Officer Heritage Consultants Pty Ltd **Permits** Artefact: 1. Potential 100554.10245 45-5-3319 Western Sydney 7 and PAD GDA 56 287450 6264725 Open site Valid Archaeological n Deposit (PAD): -Contact Searle Recorders Navin Officer Heritage Consultants Pty Ltd, Biosis Pty Ltd - Wollongong, Mrs. Samant Permits Artefact: -, Potential 103360 45-5-4361 Peachtree Creek PAD GDA 56 285590 6263560 Open site Valid Archaeological Deposit (PAD): -**Contact** Recorders Mr.Oliver Brown **Permits** 3664,3688 Penrith Lakes 2 256.260.526.10 45-5-0316 AGD 56 284443 6270186 Open site Valid Artefact: -Open Camp Site 18.103395.105 447 Contact Recorders Jim Kohen **Permits** 45-5-0335 Penrith Lakes 26 AGD 56 287274 6265667 Open site Valid Artefact: -Open Camp Site 260,526,1018,1 02450 Contact Recorders Iim Kohen **Permits** 45-5-2416 L-1:Penrith Lakeside Village: 6266617 Valid 102450 **GDA** 56 286799 Open site Artefact: -Open Camp Site **Contact** Recorders Mary Dallas Consulting Archaeologists (MDCA), Biosis Pty Ltd - Wollongong, Mrs. Sai Permits 45-5-5727 Nepean River Trail 02 GDA 56 282748 Artefact: -6270469 Open site Valid Contact Recorders 8 1 Mr. Michael Jackson, Jackson Ward Archaeology Pty Ltd **Permits**



Extensive search - Site list report

Your Ref/PO Number: 537 Client Service ID: 1022221

<u>SiteID</u> <u>SiteName</u> <u>Datum</u> <u>Zone</u> <u>Easting</u> <u>Northing</u> <u>Context</u> <u>Site Status **</u> <u>SiteFeatures</u> <u>SiteTypes</u> <u>Reports</u>

** Site Status

Valid - The site has been recorded and accepted onto the system as valid

Destroyed - The site has been completely impacted or harmed usually as consequence of permit activity but sometimes also after natural events. There is nothing left of the site on the ground but proponents should proceed with caution.

Partially Destroyed - The site has been only partially impacted or harmed usually as consequence of permit activity but sometimes also after natural events. There might be parts or sections of the original site still present on the ground

Not a site - The site has been originally entered and accepted onto AHIMS as a valid site but after further investigations it was decided it is NOT an aboriginal site. Impact of this type of site does not require permit but Heritage NSW should be notified

Search Results

50 results found.

ADI Site Western Precinct The Northern Rd	Llandilo, NSW, Australia	(<u>Place rejected for emergency</u> <u>listing</u>) National Heritage List
Agnes Banks Nature Reserve and Adjoining Areas Rickards Rd	Agnes Banks, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh Area	Upper Castlereagh, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh Cemetery Church St	Cranebrook, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh Jewel Beetle Habitat and Movement Corridor The Northern Rd	Berkshire Park, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Castlereagh State Forest and Adjacent Area The Northern Rd	Berkshire Park, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Combewood, Outbuildings and Garden 306 RMB Castlereagh Rd	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only. no statutory basis) Register of the National Estate (Non-statutory archive)
Cranebrook Airservices Land Cranebrook Rd	Cranebrook, NSW, Australia	(<u>Ineligible place</u>) Commonwealth Heritage List

Emu Plains Community Arts Centre Great Western Hwy	Emu Plains, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Fernhill Mulgoa Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Fernhill Setting Mulgoa Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Former ADI Site The Northern Rd	Llandilo, NSW, Australia	(Nomination now ineligible for PPAL) National Heritage List
Glen Leigh and Outbuildings Mulgoa Rd	Regentville, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Glenmore Mulgoa Rd	Regentville, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Greater Blue Mountains Area Great Western Hwy	Katoomba, NSW, Australia	(<u>Declared property</u>) World Heritage List
Homestead Site & Windbreak Soling Cr	Mount Pleasant, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Indigenous Place	Blaxland, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)

Indigenous Place Yarramundi, NSW, (Indicative place before RNE Australia closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive) Jordan Hill Site North St Marys, NSW, (Destroyed before RNE closed. Australia Record for reference only, no statutory basis Register of the National Estate (Non-statutory archive) King Family Farm Sites and Trees Links Rd North St Marys, NSW, (Included place before RNE Australia closed. Record for reference only, no statutory basis Register of the National Estate (Non-statutory archive) King Family Farm Sites and Trees Links Rd North St Marys, NSW, (Ineligible place) Australia Commonwealth Heritage List King Family Farm Sites and Trees Links Rd St Marys, NSW, (Nomination now ineligible for Australia PPAL) National Heritage List St Clair, NSW, Mamre and Curtilage Mamre Rd (Included place before RNE Australia closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive) McGarvie Smith University Farm 124 Elizabeth Dve Badgerys Creek, NSW, (Nomination now ineligible for Australia PPAL) National Heritage List Minnaville Castlereagh Rd Castlereagh, NSW, (Indicative place before RNE Australia closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive) Mulgoa Group and Landscape Mulgoa Rd Mulgoa, NSW, (Included place before RNE Australia closed. Record for reference only, no statutory basis Register of the National Estate (Non-statutory archive)

Mulgoa Natural Area Sir John Jamison Cirt	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Museum of Fire Castlereagh Rd	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Nepean Park Castlereagh Rd	Castlereagh, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Orchard Hills Cumberland Plain Woodland The Northern Rd	Orchard Hills, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Orchard Hills Cumberland Plain Woodland The Northern Rd	Orchard Hills, NSW, Australia	(<u>Listed place</u>) Commonwealth Heritage List
Osborne Castlereagh Rd	Agnes Banks, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Penrith Courthouse (former) High St	Penrith, NSW, Australia	(Destroyed before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
St Mary Magdalene Anglican Church & Cemetery Great Western Hwy	St Marys, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)

J. 12 1 WI	Australian Hentage Database	
St Marys Permanent Cottage Area	St Marys, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
St Stephens Anglican Church & Graveyard 252 High St	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
St Thomas Anglican Church & Cemetery St Thomas Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
The Cottage St Thomas Rd	Mulgoa, NSW, Australia	(Included place before RNE closed. Record for reference only. no statutory basis) Register of the National Estate (Non-statutory archive)
The Greater Blue Mountains Area Greater Western Hwy	Katoomba, NSW, Australia	(<u>Listed place</u>) National Heritage List
The Greater Blue Mountains Area - Additional Values and Areas Great Wester	rn Hwy Katoomba, NSW, Australia	(<u>Nominated place</u>) National Heritage List
The Lewers Bequest & Penrith Regional Art Gallery & Garden 86 River Rd	Emu Plains, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Thornton Hall & Surrounds 11 Mountain View Cr	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Thornton Hall & Surrounds 11 Mountain View Cr	Penrith, NSW, Australia	(Place removed from CHL) Commonwealth Heritage List
Thornton Hall and Surrounds (former Defence land) 11 Mountain View Co	Penrith, NSW, Australia	(Place removed from CHL) Commonwealth Heritage List

J. 12 FW Au	Stratian rientage Database	
Upper Room Chapel, Hall and Cemetery 1727 Castlereagh Rd	Castlereagh, NSW, Australia	(Indicative place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
victoria Bridge Great Western Hwy	Penrith, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
<u>Wara-n'hayara Plateau Area - part</u> Mount Kiera Rd	Wollongong, NSW, Australia	(<u>Place not included in NHL</u>) National Heritage List
Werrington House Rugby Street	Werrington County, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Western Sydney Shale Woodland St Marys Forrester Rd	St Marys, NSW, Australia	(Included place before RNE closed. Record for reference only, no statutory basis) Register of the National Estate (Non-statutory archive)
Western Sydney Shale Woodland St Marys Forrester Rd	St Marys, NSW, Australia	(<u>Ineligible place</u>) Commonwealth Heritage List

Report Produced: Thu Jul 17 15:12:23 2025

Accessibility | Disclaimer | Privacy | © Commonwealth of Australia





Heritage Search Result

Date: 17/07/2025

Item Name	Location	LGA	SHR Id	Item Type	Record Owner
"Broadville", Victorian house	98 Station Street PENRITH NSW 2750	Penrith		Built	LGOV
"Bronte", villa	50 Gidley Street ST MARYS NSW 2760	Penrith		Built	LGOV
"Chestnut" dwelling, slab cottage, trees and garden	580-600 Castlereagh Road AGNES BANKS NSW 2753	Penrith		Built	LGOV
"Combewood", house, garden, trees and original entrance drive	234-256 Coreen Avenue PENRITH NSW 2750	Penrith		Complex / Group	LGOV
"Craithes", dwelling, trees, outbuildings and carriage loop	34-40 Borec Road PENRITH NSW 2750	Penrith		Built	LGOV
"Cram Place", coach house, well, pump and cast iron fence	338-340 High Street PENRITH NSW 2750	Penrith		Complex / Group	LGOV
"Dungarth" and remnant plantings site	4 Stockade Street EMU PLAINS NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
"Edinglassie", house	22 Bunyan Road LEONAY NSW 2750	Penrith		Built	LGOV
"Emu Hall", dwelling,outbuildings and trees	2-26 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
"Fairlight", homesteas,outbuildings and gardens	377-429 Fairlight Road MULGOA NSW 2745	Penrith		Complex / Group	LGOV
"Fernhill", curtilage	1147-1187 Mulgoa Road MULGOA NSW 2745	Penrith		Landscape	LGOV
"Fernhill", house, outbuildings, and landscape	1041-1117 Mulgoa Road MULGOA NSW 2745	Penrith		Complex / Group	LGOV
"Four Winds" - dwelling	568 Great Western Highway CLAREMONT MEADOWS NSW 2747	Penrith		Built	LGOV

"Glenleigh", estate	427-507 Mulgoa	Penrith	Built	LGOV
	Road MULGOA NSW 2745			
"Glenmore"	754-760 Mulgoa Road MULGOA NSW 2745	Penrith	Built	LGOV
"Gwandalan", dwelling and garden	35 Cary Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Huntington Hall", house and garden	48-52 Beach Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Kelvin Brae", Federation house	142 High Street PENRITH NSW 2750	Penrith	Built	LGOV
"Kenilworth", dwelling and trees	6-9 Tallowood Place CRANEBROOK NSW 2749	Penrith	Built	LGOV
"Kentucky", villa	146 Station Street PENRITH NSW 2750	Penrith	Built	LGOV
"Killeen", Federation House	34 Walkers Crescent EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Leo Buring" cottage, barn, glasshouse and memorial	3a Leonay Parade LEONAY NSW 2750	Penrith	Built	LGOV
"Lindfield"	182-188 Caddens Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
"Madang Park", farmhouse and trees	475-487 Jamison Road PENRITH NSW 2750	Penrith	Built	LGOV
"Margaret Farm", house, barn and tannery site	Pages Road, Barker, Wilson and Schleicher Streets ST MARYS NSW 2760	Penrith	Built	LGOV
"Mimosa", dwelling, fence and garden	13 Pages Road ST MARYS NSW 2760	Penrith	Built	LGOV
"Mimosa", stables (former)	11 Pages Road ST MARYS NSW 2760	Penrith	Built	LGOV
"Minnamurra", house	43 Warwick Street PENRITH NSW 2750	Penrith	Built	LGOV
"Mountain View" house	39 Grey Street EMU PLAINS NSW 2750	Penrith	Built	LGOV

"Mourilyan"	329-333 Great Western Highway ST MARYS NSW 2760	Penrith	Built	LGOV
"Orange Grove", cottage	15 Park Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Osborne", homestead,barn,outbuildings and plantings	580-600 Castlereagh Road AGNES BANKS NSW 2753	Penrith	Built	LGOV
"Passadena", house	45-61 Allan Road MULGOA NSW 2745	Penrith	Built	LGOV
"Seidler", house	31-33 Nepean Avenue PENRITH NSW 2750	Penrith	Built	LGOV
"The Cottage", dwelling and pine tree	39 Warwick Street PENRITH NSW 2750	Penrith	Built	LGOV
"Thompson's Tannery" site, tannery pits (former) and well	94 Saddington Street ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
"Torquay", house	555 Great Western Highway WERRINGTON NSW 2747	Penrith	Built	LGOV
"Tyreel" , dwelling and barn	626-652 Castlereagh Road AGNES BANKS NSW 2753	Penrith	Built	LGOV
"Werrington House", dwelling, driveway and garden	108 Rugby Street WERRINGTON COUNTY NSW 2747	Penrith	Built	LGOV
"Werrington Park House", garden and poplar avenue	653-729 Great Western Highway WERRINGTON NSW 2747	Penrith	Complex / Group	LGOV
"Westbank" house	2 Nepean Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Winbourne", house	1315 Mulgoa Road MULGOA NSW 2745	Penrith	Built	LGOV
"Yamba" , cottage	32 Nixon Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
"Yodalla" house and garden	28 Nepean Street EMU PLAINS NSW 2750	Penrith	Built	LGOV

1841 Tilley 5 inch Manual Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1869 Shand Mason 7" Manual Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1891 Shand Mason Steamer Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1898 Shand Mason Curricle Ladders - Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1916 Garford Type 64 Chain Drive Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1929 Ahrens Fox PS2 Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1939 Dennis Big 6 Fire Engine	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1942 Ford 21W Fire Brigade Mobile Canteen	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
1949 Dennis F1 Fire Engine (Scout Car)	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
Above Ground Tank; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Aerial Tower Concrete Mounts (x4); Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Agnes Banks Nature Reserve	2 Geebung Close AGNES BANKS NSW 2753	Penrith		Landscape	LGOV
Agnes Banks Public School (former)	475-479 Castlereagh Road AGNES BANKS NSW 2753	Penrith		Built	LGOV
Ahrens Fox PS2 Fire Engine (1929)	1 Museum Drive PENRITH NSW 2750	Penrith	01717	Movable / Collection	HNSW
Antennae Concrete Base and Remnant Antennae Base; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV

Antennae Concrete Base, Mounts and Service Pit; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mount - Last; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mount Base and for Guy Wires and Services Pit; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts - Base and for Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts - Base and for Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts - Base and for Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts - Base and for Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts and Remnant; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts: Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Carnebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV

Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV

Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV

Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Remnant and Concrete Mounts; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Antennae Remnants; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV

Arms of Australia Inn	127 Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	LGOV
Australian Arms Hotel	359 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Australian Arms Inn (former)	113 Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	LGOV
Bank of NSW (former)	354-360 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Bayley Park - House	919-929 Mamre Road KEMPS CREEK NSW 2178	Penrith	Built	LGOV
Bellbird Reserve	29 Barina Crescent EMU PLAINS NSW 2750	Penrith	Landscape	LGOV
Bennett Wagon	Pioneer Park Great Western Highway ST MARYS NSW 2760	Penrith	Movable / Collection	LGOV
Bennetts Wagons	2151(a) Castlereagh Road PENRITH NSW 2750	Penrith	Movable / Collection	LGOV
Berkshire Park Homestead Site	844-848 Richmond Road BERKSHIRE PARK NSW 2765	Penrith	Archaeological- Terrestrial	LGOV
Brick cottage	73 Forbes Street EMU PLAINS NSW 2750	Penrith	Unknown	LGOV
Brick Cottage	406 Park Road LUDDENHAM NSW 2745	Penrith	Built	LGOV
Brick cottage	31-33 Pages Road ST MARYS NSW 2760	Penrith	Built	LGOV
Brick cottage	40 Gidley Street ST MARYS NSW 2760	Penrith	Built	LGOV
Brick cottage	38 Gidley Street ST MARYS NSW 2760	Penrith	Built	LGOV
Brick cottage	18 Princess Mary Street ST MARYS NSW 2760	Penrith	Built	LGOV

Brick cottage	100-104 Saddington Street ST MARYS NSW 2760	Penrith	Built	LGOV
Brick Cottage	Campbell Street LUDDENHAM NSW 2745	Penrith	Built	LGOV
Brick Cottage	21-55 Campbell Street LUDDENHAM NSW 2745	Penrith	Built	LGOV
Brick Farmhouse	282 Aldington Road KEMPS CREEK NSW 2178	Penrith	Built	LGOV
Brick Farmhouse	80-88 Caddens Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Brick farmhouse, trees and orchard	850-856 Castlereagh Road AGNES BANKS NSW 2753	Penrith	Built	LGOV
Brick house	565 Great Western Highway WERRINGTON NSW 2747	Penrith	Built	LGOV
Brick house	96-100 Greendale Road WALLACIA NSW 2745	Penrith	Built	LGOV
Brick house and garden	80 River Road EMU PLAINS NSW 2750	Penrith	Built	LGOV
Brick villa	318 - 320 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Building AA - Werrington Park House and Poplar Avenue	Great Western Highway WERRINGTON NSW 2747	Penrith	Built	SGOV
Building Foundations; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Building Foundations; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Bungalow	38 Greendale Road WALLACIA NSW 2745	Penrith	Complex / Group	LGOV

Canine Council Dwelling	391-395 Mamre Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Castlereagh Council Chambers (former)	1158-1160 Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Castlereagh General Cemetery and native vegetation	77-85 East Wilchard Road CRANEBROOK NSW 2749	Penrith	Archaeological- Terrestrial	LGOV
Castlereagh General Cemetery and native vegetation	132-156 Church Street CRANEBROOK NSW 2749	Penrith	Archaeological- Terrestrial	LGOV
Castlereagh Public School (former)	13-25 West Wilchard Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Castlereagh Road Alignment	Castlereagh Road AGNES BANKS NSW 2753	Penrith	Built	LGOV
Castlereagh Road Alignment	Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Unknown	LGOV
Christ Church Anglican Church	230-232 Church Lane CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Commissioner's Uniform (NSWFire Brigades) - Ian Mac Dougall	1 Museum Drive PENRITH NSW 2750	Penrith	Movable / Collection	SGOV
Concrete house	39a-43 Mackellar Street EMU PLAINS NSW 2750	Penrith	Built	LGOV
Concrete Slabs; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Concrete, timber and steel remnants; Carnebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith	Built	SGOV
Cottage	169 Cox Avenue PENRITH NSW 2750	Penrith	Built	LGOV
Cottage	Seventh Avenue (Eastern end) LLANDILO NSW 2747	Penrith	Built	SGOV

Cottage	14 York Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Cottage	10-12 North Street PENRITH NSW 2750	Penrith		Built	LGOV
Cottage	1306 Mulgoa Road MULGOA NSW 2745	Penrith		Built	LGOV
Cottage	288 High Street PENRITH NSW 2750	Penrith		Built	LGOV
Cottage	3065-3067 The Northern Road LUDDENHAM NSW 2745	Penrith		Built	LGOV
Cottage and outbuildings	268 Seventh Avenue LLANDILO NSW 2747	Penrith		Complex / Group	LGOV
Cox's Cottage	1012-1046 Mulgoa Road MULGOA NSW 2745	Penrith		Built	LGOV
Cox's Cottage	2 St Thomas Road MULGOA NSW 2745	Penrith	00171	Landscape	HNSW
Craithes House	34-40 Borec Road PENRITH NSW 2750	Penrith	00378	Built	HNSW
Cranebrook Air Radio Receiving Station Ruins	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Complex / Group	SGOV
Cranebrook Public School (former)	216 Boundary Road CRANEBROOK NSW 2749	Penrith		Built	LGOV
Crushing Plant	280a Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	LGOV
Dennis Big 6 Fire Engine (1939)	1 Museum Drive PENRITH NSW 2750	Penrith	01718	Movable / Collection	HNSW
Dunheved Fire Station	50 Christie Street ST MARYS NSW 2760	Penrith		Built	LGOV
Dunheved Homestead Site	Links Road ST MARYS NSW 2760	Penrith		Archaeological- Terrestrial	LGOV
Edward Smith Headquarters Switchboard - 1909	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV

Edward Smith Headquarters Switchboard (1909)	1 Museum Drive PENRITH NSW 2750	Penrith	01901	Movable / Collection	HNSW
Edwardian cottage	46 Russell Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Edwardian cottage	2068 Castlereagh Road PENRITH NSW 2750	Penrith		Built	LGOV
Emu Plains (Nepean River) Underbridge	Off Bruce Neale Dr, Steel Trusses 1.3 Km Past Station PENRITH NSW 2750	Penrith	01830	Built	HNSW
Emu Plains (Nepean River) Underbridge	Off Bruce Neale Dr, Steel Trusses 1.3 Km Past Station PENRITH NSW 2750	Penrith		Built	SGOV
Emu Plains Assembly Hall	283 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Emu Plains Correctional Centre	Old Bathurst Road EMU PLAINS NSW 2750	Penrith		Built	SGOV
Emu Plains Correctional Centre - Manager of Industries Office	Old Bathurst Road EMU PLAINS NSW 2750	Penrith		Built	SGOV
Emu Plains Public School (former) and trees	207-219 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Emu Plains Railway Culvert	Lamrock Street EMU PLAINS NSW 2750	Penrith		Built	SGOV
Emu Plains Railway Station group	Main Western railway EMU PLAINS NSW 2750	Penrith	01136	Complex / Group	HNSW
Emu Plains Railway Station Group	Mackellar Street EMU PLAINS NSW 2750	Penrith		Built	SGOV
Emu Plains Railway Station group	Main Western Railway, Station Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Explorers Memorial	Memorial Avenue PENRITH NSW 2750	Penrith		Built	LGOV

Explosives storehouse	146 Dunheved Circuit ST MARYS NSW 2760	Penrith		Built	LGOV
Fairlight Homestead & Barn	Fairlight Road MULGOA NSW 2745	Penrith	00262	Landscape	HNSW
Farmhouse	361 Ninth Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
Farmhouse	170 Sixth Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
Farmhouse (collapsed) and outbuildings	2-22 Springwood Road AGNES BANKS NSW 2753	Penrith		Built	LGOV
Farmhouse,garden planting and natural vegetation	259A-263 Church Lane CASTLEREAGH NSW 2749	Penrith		Built	LGOV
Federation cottage	80 Woodriff Street PENRITH NSW 2750	Penrith		Built	LGOV
Federation farmhouse	330 Eighth Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
Federation farmhouse and trees	706 Castlereagh Road AGNES BANKS NSW 2753	Penrith		Built	LGOV
Federation House	9 Railway Row EMU PLAINS NSW 2750	Penrith		Built	LGOV
Federation house and garden	6 First Street KINGSWOOD NSW 2747	Penrith		Built	LGOV
Fernhill	Mulgoa Road MULGOA NSW 2745	Penrith	00054	Landscape	HNSW
Ferry crossing	Nepean River - Ferry Road PENRITH NSW 2750	Penrith		Built	LGOV
Ferry Crossing	Punt Road, Nepean River EMU PLAINS NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Fire and Rescue NSW Heritage Fleet	Museum Drive PENRITH NSW 2750	Penrith	01902	Movable / Collection	HNSW
Ford 21W Fire Brigade Mobile Canteen (1942)	Museum Drive PENRITH NSW 2750	Penrith	01900	Movable / Collection	HNSW
Former Penrith Brick Company - kiln and chimney	Copeland Street KINGSWOOD NSW 2747	Penrith		Archaeological- Terrestrial	LGOV

Fossil Collection	947-953 Londonderry Road LONDONDERR Y NSW 2753	Penrith	00971	Movable / Collection	HNSW
Four Winds	Great Western Highway WERRINGTON NSW 2747	Penrith		Built	SGOV
Fulton's Store (former)	413-423 High Street PENRITH NSW 2750	Penrith		Built	LGOV
Gateposts to Colesbrook	269-285 Mamre Road KEMPS CREEK NSW 2178	Penrith		Built	LGOV
Glenleigh Estate	427 Mulgoa Road REGENTVILLE NSW 2745	Penrith	00346	Landscape	HNSW
Glenmore	754-760 Mulgoa Road MULGOA NSW 2745	Penrith	00074	Landscape	HNSW
Gosling Street and Hessel Place Reserves	22 Gosling Street EMU HEIGHTS NSW 2750	Penrith		Landscape	LGOV
Gothic revival cottage	24 Princess Mary Street ST MARYS NSW 2760	Penrith		Built	LGOV
Government stockyard site	Hunter, Yodalla, Annette & Nepean Streets &River Road EMU PLAINS NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Governor Phillip Special Hospital - original building	64 Glebe Place PENRITH NSW 2750	Penrith		Built	LGOV
Guy Wires; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Hadley Park	14-278 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith	02009	Landscape	HNSW
Hadley Park	RMB 113 Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Landscape	GAZ
Hadley Park Homestead	14 -278 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	LGOV

High Street shop	538-540 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	550-556 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	371-375 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	377-381 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	383 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	387-389 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	391-393 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	425 - 427 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	449-451 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	542 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shop	437 High Street PENRITH NSW 2750	Penrith	Built	LGOV
High Street shops	361-365 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Archaeological- Terrestrial	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV
Historic Ruin; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Built	SGOV

Hornseywood Avenue Conservation Area	Brown, Derby and Castlereagh Street, Penrith PENRITH NSW 2750	Penrith	Conservation Area	LGOV
House	43 Park Avenue KINGSWOOD NSW 2747	Penrith	Built	LGOV
House (Hall family)	13 Hessel Place EMU HEIGHTS NSW 2750	Penrith	Built	LGOV
International style house and garden	10 River Road EMU PLAINS NSW 2750	Penrith	Built	LGOV
Irrigation channel	Mulgoa Road, Queenshill Drive, Littlefields Road and The Northern Road MULGOA NSW 2745	Penrith	Archaeological- Terrestrial	LGOV
Johnson's Cottage	Nepean Street CRANEBROOK NSW 2749	Penrith	Built	LGOV
Kingswood Public School	46-54 Second Avenue KINGSWOOD NSW 2747	Penrith	Built	LGOV
Kingswood Public School - Building B00B	46-54 Second Avenue KINGSWOOD NSW 2747	Penrith	Built	SGOV
Landers Inn and Stone Stables Ruins	14 - 278 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Lawson Footbridge	East of Station At 94.93 Km, Old Overbridge LAWSON NSW 2783	Penrith	Built	SGOV
Leeholme Horse Stud Rotunda	391-395 Mamre Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Lemongrove Conservation Area	Lemongrove Road, Macquarie Avenue, Hemmings Street and The Crescent, Penrith PENRITH NSW 2750	Penrith	Conservation Area	LGOV
Lemongrove Lodge	22-24 Lemongrove Road PENRITH NSW 2750	Penrith	Built	LGOV

Lewers Bequest & Regional Art Gallery, houses and garden	84-88 River Road EMU PLAINS NSW 2750	Penrith		Built	LGOV
Little	EMU PLAINS NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Llandilo Community Hall	257C Seventh Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
Llandilo Public School	222 Seventh Avenue LLANDILO NSW 2747	Penrith		Unknown	LGOV
Llandilo Public School - Building B00F	222 Seventh Avenue LLANDILO NSW 2747	Penrith		Built	SGOV
Londonderry Cemetery	325-331 Londonderry Road LONDONDERR Y NSW 2753	Penrith		Archaeological- Terrestrial	LGOV
Luddenham Homestead site	1-9 Park Road WALLACIA NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Luddenham Progress Hall	3091-3095 The Northern Road LUDDENHAM NSW 2745	Penrith		Built	LGOV
Luddenham Road Alignment	Luddenham Road LUDDENHAM NSW 2745	Penrith		Built	LGOV
Luddenham Uniting Church and Cemetery	3097-3099 The Northern Road LUDDENHAM NSW 2745	Penrith		Complex / Group	LGOV
Luddenham Uniting Church Cemetery	The Northern Road LUDDENHAM NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Mamre	181-275 Mamre Road ORCHARD HILLS NSW 2748	Penrith		Complex / Group	LGOV
Mamre	Mamre Road ST MARYS NSW 2760	Penrith	00264	Landscape	HNSW
Mamre	Mamre Road ORCHARD HILLS NSW 2748	Penrith		Built	SGOV
Margaret Farm & Barn	Pages Road ST MARYS NSW 1790	Penrith		Built	SGOV
McCarthys Cemetery	McCarthys Lane CASTLEREAGH NSW 2749	Penrith		Archaeological- Terrestrial	GAZ

McCarthys Cemetery and Trees	Lot 82 McCarthys Lane CASTLEREAGH NSW 2749	Penrith	Archaeological- Terrestrial	LGOV
McCarthys Farm Archaeological remains (Demolished)	145-237 McCarthys Lane CRANEBROOK NSW 2749	Penrith	Complex / Group	LGOV
McGarvie-Smith Farm	1793-1951 Elizabeth Drive BADGERYS CREEK NSW 2555	Penrith	Built	LGOV
Melrose Hall	169 Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	LGOV
Memorial cairn	181-275 Mamre Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Memorial cairn	Luddenham Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Memorials and lamp stand, St Nicholas of Myra Catholic Church	332-338 High Street PENRITH NSW 2750	Penrith	Complex / Group	LGOV
Memorials- Smith Park	1151-1159 Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Memory Park	400 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Methodist Cemetery	CASTLEREAGH NSW 2749	Penrith	Complex / Group	GAZ
Methodist Church (former)	74 Henry Street PENRITH NSW 2750	Penrith	Built	LGOV
Milestone	Great Western Highway (between Marsden Road and Day Street) ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
Milestone	Great Western Highway CLAREMONT MEADOWS NSW 2747	Penrith	Built	LGOV
Milestone	Great Western Highway KINGSWOOD NSW 2747	Penrith	Built	LGOV

	1	1		1	
Milestone	Great Western Highway KINGSWOOD NSW 2747	Penrith		Built	LGOV
Milestone	Great Western Highway COLYTON NSW 2760	Penrith		Built	LGOV
Moore Cottage	8 Sainsbury Street ST MARYS NSW 2760	Penrith		Built	LGOV
Mulgoa Irrigation Company office and police station (former)	1298-1304 Mulgoa Road MULGOA NSW 2745	Penrith		Built	LGOV
Mulgoa Public School - Buildings B00A and B00C and Significant Trees	1189-1193 Mulgoa Road MULGOA NSW 2745	Penrith		Built	SGOV
Mulgoa Public School building, hall, residence and trees	1189-1193 Mulgoa Road MULGOA NSW 2745	Penrith		Complex / Group	LGOV
Mulgoa Road Alignment (former)	St Thomas Road MULGOA NSW 2745	Penrith		Built	LGOV
Mulgoa Road Conservation Area	1582-1586 & 1581-1587 Mulgoa Road WALLACIA NSW 2745	Penrith		Conservation Area	LGOV
Natural Area	Rickards Ave AGNES BANKS NSW 2753	Penrith		Landscape	SGOV
Natural Area	Rickards Avenue AGNES BANKS NSW 2753	Penrith	00649	Landscape	HNSW
Nepean Park	Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Landscape	GAZ
Nepean Park - Homestead,Garden and Trees	1404(a) Closed Road off Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	LGOV
North St Marys Staff Cottages Conservation Area	Forrester Road NORTH ST MARYS NSW 2760	Penrith		Conservation Area	LGOV
NSW Fire Brigades Heritage Fleet	1 Museum Drive PENRITH NSW 2750	Penrith		Movable / Collection	SGOV
NSW Fire Brigades No 10 Vehicle Number Plates	Castlereagh Road PENRITH NSW 2750	Penrith	01519	Movable / Collection	HNSW

NSWFB 'No. 10' Vehicle Number Plates	1 Museum Drive PENRITH NSW 2750	Penrith	Movable / Collection	SGOV
Old Police Station	Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	SGOV
Olive trees	68 Soling Crescent CRANEBROOK NSW 2749	Penrith	Complex / Group	LGOV
Orchard Hills Reservoir (WS 0083)	Castle Road ORCHARD HILLS NSW 2748	Penrith	Built	SGOV
Orchard Hills Uniting Church	3 Frogmore Road ORCHARD HILLS NSW 2748	Penrith	Built	LGOV
Original building	Glebe Place PENRITH NSW 2750	Penrith	Built	SGOV
Park Road Conservation Area	22-26 Park Road WALLACIA NSW 2745	Penrith	Conservation Area	LGOV
Parkers Slaughter Yard	Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Archaeological- Terrestrial	LGOV
Peach Tree Creek Bridge	Great Western Highway PENRITH NSW 2750	Penrith	Built	SGOV
Peachtree Creek Bridge	Peachtree Creek PENRITH NSW 2750	Penrith	Archaeological- Terrestrial	LGOV
Penrith Administrative Office - Building B00M	57 Henry Street PENRITH NSW 2750	Penrith	Built	SGOV
Penrith Ambulance Station	668-672 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Penrith Council Chambers (former)	129-133 Henry Street PENRITH NSW 2750	Penrith	Built	LGOV
Penrith General Cemetery	Land bounded by Copeland and Phillips Streets, Richmond Road and Cox Avenue KINGSWOOD NSW 2747	Penrith	Archaeological- Terrestrial	LGOV
Penrith Infants Department (1884 building)	57 Henry Street PENRITH NSW 2750	Penrith	Built	LGOV
Penrith Power Station (former)	1 Museum Drive PENRITH NSW 2750	Penrith	Built	LGOV

Penrith Public School - Building B00A and Significant Trees	194 High Street PENRITH NSW 2750	Penrith		Built	SGOV
Penrith Public School and palm trees	194 High Street PENRITH NSW 2750	Penrith		Complex / Group	LGOV
Penrith Railway Station group	Railway land, Jane Street PENRITH NSW 2750	Penrith		Built	LGOV
Penrith Railway Station group	Great Western Railway PENRITH NSW 2750	Penrith	01222	Complex / Group	HNSW
Penrith Railway Station Group and Residence	Station Street PENRITH NSW 2750	Penrith		Built	SGOV
Penrith School of Arts (former)	7 Castlereagh Street PENRITH NSW 2750	Penrith		Built	LGOV
Penrith Weir	Bruce Neale Drive PENRITH NSW 2750	Penrith		Built	SGOV
Petrology Collection	947-953 Londonderry Road LONDONDERR Y NSW 2753	Penrith	00973	Movable / Collection	HNSW
Pise House Ruins	198-202 Church Lane CASTLEREAGH NSW 2749	Penrith		Built	LGOV
Police station (Former)	30 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Police station residence (former)	4 Punt Road EMU PLAINS NSW 2750	Penrith		Built	LGOV
Poplars Garden (The)	Wrights Lane CRANEBROOK NSW 2749	Penrith		Landscape	LGOV
Poplars Pise House (The)	Wrights Lane CRANEBROOK NSW 2749	Penrith		Built	LGOV
Presbyterian manse (former)	154 Derby Street PENRITH NSW 2750	Penrith		Built	LGOV
Prospect Electricity building (former)	59 Station Street PENRITH NSW 2750	Penrith		Built	LGOV
Pumping station (former)	20 Memorial Avenue PENRITH NSW 2750	Penrith		Built	LGOV
Railway bridge	Over Nepean River PENRITH NSW 2750	Penrith		Complex / Group	LGOV

Rectory (former)	95 Glebe Place PENRITH NSW 2750	Penrith		Built	LGOV
Red Cow Hotel	569-595 High Street PENRITH NSW 2750	Penrith		Built	LGOV
Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith		Complex / Group	SGOV
Regentville Mansion (site) and vineyard terracing	460a-626 Mulgoa Road MULGOA NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Regentville Public School - Buildings B00A and B00K and Landscape	32-34 School House Road REGENTVILLE NSW 2745	Penrith		Built	SGOV
Regentville Public School, residence and garden	32-34 School House Road REGENTVILLE NSW 2745	Penrith		Built	LGOV
Regentville Windmill site	127-129 and 131 -135 Martin Street REGENTVILLE NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Regentville Workers' Terrace	1 Bundarra Road REGENTVILLE NSW 2745	Penrith		Built	LGOV
Remnants and Service Pit; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Rose Cottage and Early Slab Hut	Water Street WERRINGTON NSW 2747	Penrith	01392	Complex / Group	HNSW
Rose Cottage and early slab hut	Corner Water Street and Tennant Road WERRINGTON NSW 2747	Penrith		Complex / Group	LGOV
Rose Cottage and Slab Hut	Water Street WERRINGTON NSW 2747	Penrith		Built	SGOV
Rotunda	Luddenham Road NYAH VIC 3594	Penrith		Built	SGOV
Rowing course	Nepean River PENRITH NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Sandstone cottage	281 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV

Sandstone railway culvert	Lamrock Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Sawmill Precinct	ST MARYS NSW 2760	Penrith		Archaeological- Terrestrial	LGOV
Scarred tree and Aboriginal artefact scatter	Lot 2000 Bradley Street GLENMORE PARK NSW 2745	Penrith		Archaeological- Terrestrial	LGOV
Services Pit; Cranebrook	Cranebrook Road Wianamatta Nature Reserve CRANEBROOK NSW 2749	Penrith		Built	SGOV
Shand Mason 7 inch Manual Fire Engine (1869)	1 Museum Drive PENRITH NSW 2750	Penrith	01898	Movable / Collection	HNSW
Shand Mason Curricle Ladders (1898)	1 Museum Drive PENRITH NSW 2750	Penrith	01899	Movable / Collection	HNSW
Shand Mason Fire Engine (1891)	Museum Drive PENRITH NSW 2750	Penrith	01716	Movable / Collection	HNSW
Shop	373 Great Western Highway ST MARYS NSW 2760	Penrith		Built	LGOV
Showground	428-452 Park Road LUDDENHAM NSW 2745	Penrith		Complex / Group	LGOV
Sir John Jamison Cemetery	14B Lilac Place JAMISONTOWN NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Site of Castlereagh township	East Wilchard Road and Church Lane CASTLEREAGH NSW 2749	Penrith		Landscape	LGOV
Site of Edinglassie	Lapstone Place LEONAY NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
Site of Fulton's Church and School	184-194 Church Street CRANEBROOK NSW 2749	Penrith		Built	LGOV
Site of Mill; Neranie	Neranie Road Myall Lakes National Park BUNGWAHL NSW 2423	Penrith		Archaeological- Terrestrial	SGOV
Sites of Early Water Mills	CASTLEREAGH NSW 2749	Penrith		Built	LGOV

Slab Cottage & Buddladack	14-278 Old	Penrith	Built	LGOV
Slab Cottage & Puddledock (remains)	Castlereagh Road CASTLEREAGH NSW 2749			
Slab cottage site	1177-1187 Mulgoa Road MULGOA NSW 2745	Penrith	Archaeological- Terrestrial	LGOV
South Creek Bridge (Eastbound)	Great Western Highway ST MARYS NSW 2760	Penrith	Built	SGOV
St Andrew's Anglican Church (former)	25 Park Road WALLACIA NSW 2745	Penrith	Built	LGOV
St Aubyn's Terrace	255-265 High Street PENRITH NSW 2750	Penrith	Built	LGOV
St James Anglican Church and Cemetery	3101-3125 The Northern Road LUDDENHAM NSW 2745	Penrith	Complex / Group	LGOV
St Mary Magdalene Church, Hall, Cemetery and grounds	299-311 Great Western Highway ST MARYS NSW 2760	Penrith	Built	LGOV
St Marys Catholic Church	1262 - 1266 Mulgoa Road MULGOA NSW 2745	Penrith	Built	LGOV
St Marys Council Chambers (former)	2-6 Mamre Road ST MARYS NSW 2760	Penrith	Built	LGOV
St Marys General Cemetery	175-191 Great Western Highway ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
St Marys Public School	2-6 Princess Mary Street ST MARYS NSW 2760	Penrith	Built	LGOV
St Marys Public School - Building B00G, Residence, Grounds and Significant Trees	2-6 Princess Mary Street ST MARYS NSW 2760	Penrith	Built	SGOV
St Marys Railway Station	Corner Station and Queen Streets ST MARYS NSW 2760	Penrith	Complex / Group	LGOV
St Marys Railway Station Group	Queen Street ST MARYS NSW 2760	Penrith	Built	SGOV
St Pauls Anglican Cemetery	EMU PLAINS NSW 2750	Penrith	Archaeological- Terrestrial	LGOV

St Paul's Anglican Church and Emu Plains General Cemetery	Land bounded by Short, Mundy and Nixon Streets and Great Western Railway EMU PLAINS NSW 2750	Penrith		Complex / Group	LGOV
St Phillip's Anglican Church	32 Bringelly Road KINGSWOOD NSW 2747	Penrith		Built	LGOV
St Stephen's Anglican Church, Hall and Cemetery	258-280 High Street PENRITH NSW 2750	Penrith		Complex / Group	LGOV
St Thomas' Anglican Church (former) and Palm trees	540A-544A Cranebrook Road CRANEBROOK NSW 2749	Penrith		Landscape	LGOV
St Thomas' Anglican Church and Cemetery	43-57 St Thomas Road MULGOA NSW 2745	Penrith		Complex / Group	LGOV
St. David's Anglican Church (former)	257B Seventh Avenue LLANDILO NSW 2747	Penrith		Built	LGOV
St. Mary Magdalene Cemetery	King Street ST MARYS NSW 1790	Penrith		Archaeological- Terrestrial	LGOV
St. Marys Railway Station Group	Great Western Railway ST MARYS NSW 2760	Penrith	01249	Complex / Group	HNSW
St. Marys Railway Station Parcels Office	Queen Street ST MARYS NSW 1790	Penrith		Built	LGOV
St. Stephens Cemetery	High Street PENRITH NSW 2750	Penrith		Archaeological- Terrestrial	LGOV
St. Stephens Church Hall	High Street PENRITH NSW 2750	Penrith		Built	LGOV
St. Thomas Anglican Church	St Thomas Road MULGOA NSW 2745	Penrith	00426	Complex / Group	HNSW
State Records Movable Heritage - Furniture	143 O'Connell Street KINGSWOOD NSW 2747	Penrith		Movable / Collection	SGOV
State Records Movable Heritage - Memorials	143 O'Connell Street KINGSWOOD NSW 2747	Penrith		Movable / Collection	SGOV
Station Master's House (former)	Jane Street PENRITH NSW 2750	Penrith		Built	LGOV

Stone House	143 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Sydney Water Supply Canal	Camden Valley Way and Elizabeth Drive (between) LIVERPOOL NSW 2170	Liverpool		Complex / Group	GAZ
Table Rock Lookout	716-782 Fairlight Road MULGOA NSW 2745	Penrith		Landscape	LGOV
TAFE Building	115-119 Henry Street PENRITH NSW 2750	Penrith		Built	LGOV
TAFE NSW Penrith Campus	115-119 Henry Street PENRITH NSW 2750	Penrith		Built	SGOV
Teacher's residence (former)	56 Second Avenue KINGSWOOD NSW 2747	Penrith		Built	LGOV
The Fleurs Radio Telescope Site	885(a) Mamre Road KEMPS CREEK NSW 2178	Penrith		Unknown	LGOV
The Lodge	48-56 Leland Street PENRITH NSW 2750	Penrith		Built	LGOV
The Poplars - Old Slab Cottage, Pise House and Garden	108-110 Wrights Lane CASTLEREAGH NSW 2749	Penrith		Complex / Group	LGOV
The Willows - House	65 Mulgoa Road PENRITH NSW 2750	Penrith		Built	LGOV
Thompsons Tannery (Former)	ST MARYS NSW 2760	Penrith		Archaeological- Terrestrial	LGOV
Thompson's Tannery site (former)	Saddington Street ST MARYS NSW 2760	Penrith		Archaeological- Terrestrial	LGOV
Thornton Hall	Thornton House 33 Mountain View Crescent, Penrith PENRITH NSW 2750	Penrith		Built	LGOV
Torin building	26 Coombes Drive PENRITH NSW 2750	Penrith		Built	LGOV
Torin Building	26 Coombes Drive PENRITH NSW 2750	Penrith	01796	Built	HNSW


Torquay	555 Great Western Highway WERRINGTON NSW 2747	Penrith		Built	SGOV
Union Inn (former) and trees	36-42 Great Western Highway EMU PLAINS NSW 2750	Penrith		Built	LGOV
Uniting Church	5-7 Emerald Street EMU PLAINS NSW 2750	Penrith		Built	LGOV
Upper Castlereagh Methodist Church and Hall	CASTLEREAGH NSW 2749	Penrith		Built	GAZ
Upper Castlereagh Public School	Castlereagh Road CASTLEREAGH NSW 2749	Penrith	00339	Built	HNSW
Upper Castlereagh Public School and Residence	312 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	SGOV
Upper Castlereagh Public School and Residence	312-314 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Built	SGOV
Upper Castlereagh Public School Hall & Residence	312 -316 Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Complex / Group	LGOV
Upper Castlereagh School and Residence	CASTLEREAGH NSW 2749	Penrith		Built	GAZ
Upper Castlereagh War Memorial	280a Old Castlereagh Road CASTLEREAGH NSW 2749	Penrith		Archaeological- Terrestrial	LGOV
Victoria Bridge	Great Western Highway PENRITH NSW 2750	Penrith		Built	GAZ
Victoria Bridge	Great Western Highway PENRITH NSW 2750	Penrith		Built	LGOV
Victoria Bridge	Nepean River, Great Western Highway PENRITH NSW 2750	Penrith	01950	Built	HNSW
Victoria Bridge over Nepean River	Great Western Highway PENRITH NSW 2750	Penrith		Built	SGOV

Victoria Park and memorial	Boiunded by Great Western Highway, Pages Road, Putland and Princess Mary Streets ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
Victoria Park War Memorial	ST MARYS NSW 2760	Penrith	Archaeological- Terrestrial	LGOV
Victorian cottage	163 Derby Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian cottage	194 Derby Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian farmhouse	46-54 Grays Lane CRANEBROOK NSW 2749	Penrith	Built	LGOV
Victorian Farmhouse	1188-1200 Castlereagh Road CASTLEREAGH NSW 2749	Penrith	Built	LGOV
Victorian house	2083-2089 Castlereagh Road PENRITH NSW 2750	Penrith	Built	LGOV
Victorian house	6 Rawson Avenue PENRITH NSW 2750	Penrith	Built	LGOV
Victorian house	148 Station Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian house, dwelling and camphour laurel tree	50 Warwick Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian terrace and Interwar shop	219-221 High Street PENRITH NSW 2750	Penrith	Built	LGOV
Victorian villa	150 Lethbridge Street PENRITH NSW 2750	Penrith	Built	LGOV
Vineyard; Regentville	Mulgoa Nature Reserve REGENTVILLE NSW 2745	Penrith	Archaeological- Terrestrial	SGOV
Wagon Wheel Hotel	449 Great Western Highway ST MARYS NSW 2760	Penrith	Built	LGOV
Wallacia Hotel	1590-1594 Mulgoa Road WALLACIA NSW 2745	Penrith	Built	LGOV

Wallacia Post Office	1589 Mulgoa Road WALLACIA NSW 2745	Penrith	Uı	nknown	LGOV
Wallacia Progress Association Hall	40 Greendale Road WALLACIA NSW 2745	Penrith	Uı	nknown	LGOV
Wallacia Public School	1573-1585 Mulgoa Road WALLACIA NSW 2745	Penrith	В	uilt	LGOV
Wallacia Public School - Building B00B and B00D	1573-1585 Mulgoa Road WALLACIA NSW 2745	Penrith	Ві	uilt	SGOV
Wallacia Weir	WALLACIA NSW 2745	Penrith		omplex / roup	GAZ
War Memorial, Emu Park	Great Western Highway, Lawson and Park Streets EMU PLAINS NSW 2750	Penrith	В	uilt	LGOV
Warwick Street Conservation Area	Warwick Street PENRITH NSW 2750	Penrith		onservation rea	LGOV
Water reservoir	197-207 Castle Road ORCHARD HILLS NSW 2748	Penrith	В	uilt	LGOV
Weatherboard cottage	410-450 Castlereagh Road AGNES BANKS NSW 2753	Penrith	В	uilt	LGOV
Weatherboard cottage	20 Princess Mary Street ST MARYS NSW 2760	Penrith	В	uilt	LGOV
Weatherboard cottage	22 Princess Mary Street ST MARYS NSW 2760	Penrith	В	uilt	LGOV
Weatherboard cottage	41-43 Camden Street PENRITH NSW 2750	Penrith	В	uilt	LGOV
Weatherboard cottage	24 Forbes Street EMU PLAINS NSW 2750	Penrith	В	uilt	LGOV
Weatherboard cottage	71 Parker Street PENRITH NSW 2750	Penrith	В	uilt	LGOV
Weatherboard Cottage	1296 Mulgoa Road MULGOA NSW 2745	Penrith		omplex / roup	LGOV

Weatherboard Cottage	3075 The Northern Road LUDDENHAM NSW 2745	Penrith	Built	LGOV
Weatherboard house	66-70 Great Western Highway EMU PLAINS NSW 2750	Penrith	Built	LGOV
Weir	Bruce Neil Drive, Nepean River PENRITH NSW 2750	Penrith	Built	LGOV
Wool Pack Inn (ruin)	556 Great Western Highway ST MARYS NSW 2760	Penrith	Built	LGOV
Wool Pack Inn (Ruin)	556 Great Western Highway ST MARYS NSW 1790	Penrith	Built	SGOV
Workmen's Cottages	56-62 Mulgoa Road JAMISONTOWN NSW 2750	Penrith	Built	LGOV

537 - Penrith Lakes Native Title Vision Web Map



Sources: Esri, TomTom, Garmin, FAO, NOAA, USGS, \circledcirc OpenStreetMap contributors, and the GIS User Community, Esri, Geoscience Australia, NASA, NGA, USGS

0.2

0.1

0.4 km

Penrith Local Environmental Plan 2010

Current version for 20 May 2024 to date (accessed 17 July 2025 at 14:57)

Schedule 5

Schedule 5 Environmental heritage

(Clause 5.10)

Part 1 Heritage items

Suburb	Item name	Address	Property description	Significance	e Item no
Agnes Banks	Castlereagh Road Alignment	Castlereagh Road		Local	261
Agnes Banks	Weatherboard cottage	410-450 Castlereagh Road	Lot 10, DP 792357	Local	660
Agnes Banks	Agnes Banks Public School (former)	475-479 Castlereagh Road	Lot 1, DP 776886	Local	3
Agnes Banks	"Osborne", homestead, barn, outbuildings and plantings	580–600 Castlereagh Road	Lot 1, DP 1155198	Local	6
Agnes Banks	"Chestnut", dwelling, slab cottage and trees	580–600 Castlereagh Road	Lot 1, DP 1155198	Local	8
Agnes Banks	"Tyreel", dwelling and barn	626-652 Castlereagh Road	Lot 1, DP 739177	Local	10
Agnes Banks	Federation farmhouse and trees	706 Castlereagh Road	Lot 4, DP 570547	Local	12
Agnes Banks	Brick farmhouse, trees and orchard	850–856 Castlereagh Road	Lot 1, DP 228165	Local	659
Agnes Banks	Agnes Banks Nature Reserve	2 Geebung Close, e and 36–62 and 66–88 Rickards Road	Lots 149 and 157-159, DP 752021; Lot 7302, DP 1151861; Lot 12, DP 1049319	State	15

Agnes Banks	Farmhouse (collapsed) and outbuildings	2–22 Springwood Road	Lot 930, DP 1129072	Local	2
Castlereagh	Castlereagh Road Alignment	Castlereagh Road		Local	261
Castlereagh	Memorials—Smith Park	1151-1159 Castlereagh Road	Lots 1-3, DP 3784; Part Lot 58, DP 752021	Local	19
Castlereagh	Castlereagh Council Chambers (former)	1158–1160 Castlereagh Road	Lot 1, DP 198257	Local	18
Castlereagh	Christ Church Anglican Church	230–232 Church Lane	Lot 27, DP 581747	Local	28
Castlereagh	Farmhouse, garden planting and natural vegetation	259A-263 Church Lane	Lot 1000, DP 1100451	Local	26
Castlereagh	Castlereagh Public School (former)	13-25 West Wilchard Road	Lot 2, DP 780559	Local	20
Claremont Meadows	Milestone	Great Western Highway	Fronting Lot 1, DP 1126991	Local	859
Claremont Meadows	"Four Winds", dwelling	568 Great Western Highway	Part Lot 11, Section 24, DP 111110	Local	321
Colyton	Milestone	Great Western Highway	Fronting Lot 1 DP 538063	Local	862
Cranebrook	Cranebrook Public School (former)	216 Boundary Road	Lot 22, DP 809521	Local	40
Cranebrook	Site of Fulton's Church and School	184-194 Church Street	Lot 287, DP 999655; Lot 288, DP 999656	Local	31
Cranebrook	St Thomas' Anglican Church (former) and Palm trees	540A-544A Cranebrook Road	Lots 12-17, Section A, DP 1613	Local	42
Cranebrook	Castlereagh General Cemetery and native vegetation	77–85 East Wilchard Road	Lot 281, DP 752021	Local	32
Cranebrook	Victorian farmhouse	46-54 Grays Lane	Lot 12, DP 825320	Local	35
Cranebrook	Johnson's Cottage	Nepean Street	Lots 18-20, Section A, DP 1613	Local	41
Cranebrook	Olive trees	68 Soling Crescent	Lot 104, DP 261535	Local	39
Cranebrook	"Kenilworth", dwelling and trees	6-9 Tallowood Place	Lot 26, DP 855247	Local	36

Emu Heights	Gosling Street and Hessel Place Reserves	22 Gosling Street	Lot 22, DP 1076016	Local	89
Emu Heights	House (Hall family)	13 Hessel Place	Lot 22, DP 250032	Local	88
Emu Plains	Bellbird Reserve	29 Barina Crescent	Lot 101, DP 577779	Local	90
Emu Plains	"Huntington Hall", house and garden	48-52 Beach Street	Lots 12, 13 and 15, DP 243048	Local	71
Emu Plains	Uniting Church	5-7 Emerald Street	Lot 1, DP 650543	Local	82
Emu Plains	Weatherboard cottage	24 Forbes Street	Lot 22, DP 253187	Local	664
Emu Plains	Brick cottage	73 Forbes Street	Lot 181, DP 575962	Local	669
Emu Plains	War Memorial, Emu Park	Great Western Highway, Lawson and Park Streets	Lot 7051, DP 1055094	Local	75
Emu Plains	"Emu Hall", dwelling, outbuildings and trees	2–26 Great Western Highway	Lot 2, DP 614436	Local	51
Emu Plains	Union Inn (former) and trees	36-42 Great Western Highway	Part Lots 1 and 2, DP 342116	Local	63
Emu Plains	Weatherboard house	66–70 Great Western Highway	Lot 17, SP 71124	Local	60
Emu Plains	Australian Arms Inn (former)	113 Great Western Highway	Lot 11, DP 1056135	Local	61
Emu Plains	Arms of Australia Inn	127 Great Western Highway	Lot 22, DP 242300	Local	327
Emu Plains	Stone house	143 Great Western Highway	Lot 111, DP 242913	Local	64
Emu Plains	Melrose Hall	169 Great Western Highway	Lot 7040, DP 751662	Local	73
Emu Plains	Emu Plains Public School (former) and trees	207-219 Great Western Highway	Part Lot 1, DP 650753	Local	76
Emu Plains	Sandstone cottage	281 Great Western Highway	Lot 110, DP 802233	Local	84
Emu Plains	Emu Plains Assembly Hall	283 Great Western Highway	Lot 1, DP 780531	Local	85
Emu Plains	"Mountain View" house	39 Grey Street	Lot 1, DP 203655	Local	837

Emu Plains	Sandstone railway culvert	Lamrock Street		Local	667
Emu Plains	Concrete house	39a-43 Mackellar Street	Lot 980, DP 810551	Local	58
Emu Plains	"Westbank", house	2 Nepean Street	Lot 1, DP 620712	Local	65
Emu Plains	"Gwandalan", dwelling and garden	11 Nepean Street and 35 Cary Street	Lots 121 and 123, DP 807462	Local	92
Emu Plains	"Yodalla", house and garden	28 Nepean Street	Lot 42, DP 524161	Local	66
Emu Plains	"Yamba", cottage	32 Nixon Street	Lot 116, DP 242303	Local	80
Emu Plains	"Orange Grove", cottage	15 Park Street	Lot 1, DP 703497	Local	74
Emu Plains	Ferry crossing	Punt Road, Nepean River		Local	147
Emu Plains	Police station residence (former)	4 Punt Road	Lot 7038, DP 94188	Local	52
Emu Plains	International style house and garden	10 River Road	Lot B, DP 33205	Local	666
Emu Plains	Brick house and garden	80 River Road	Lot 2, DP 1024616	Local	151
Emu Plains	Lewers Bequest and Regional Art Gallery, houses and garden	84-88 River Road,	Lot 34, DP 1114973	Local	69
Emu Plains	Edwardian cottage	46 Russell Street	Lot 10, DP 1097496	Local	83
Emu Plains	St. Paul's Anglican Church and Emu Plains General Cemetery	Land bounded by Short, Mundy and Nixon Streets and the Great Western Railway	Lot 1, DP 724148; Lot 1, DP 798650; Lot G, DP 751662	Local	78
Emu Plains	Emu Plains Railway Station group	Main Western Railway, Station Street	Lot 1, DP 1133099	State	59
Emu Plains	"Killeen", Federation house	34 Walkers Crescent	Lot 104, DP 1006488	Local	840
Emu Plains	Cottage	14 York Street	Lot 1, DP 563123	Local	55
Glenmore Park	Scarred tree and Aboriginal artefact scatter	Lot 2000 Bradley Street	Lot 2000, DP 1204777	Local	878

Jamisontown	Sir John Jamison Cemetery	14b and 14c Lilac Place	Lot 1, DP 724391; Lot 1, DP 723986	Local	269
Jamisontown	Workmens' cottages	56-62 Mulgoa Road	Lots 1-4, SP 39546	Local	94
Kingswood	St. Phillip's Anglican Church	32 Bringelly Road	Lot 64, DP 752022	Local	101
Kingswood	Penrith General Cemetery	Land bounded by Copeland and Phillips Streets, Richmond Road and Cox Avenue	Lots 1-28, DP 975352	Local	97
Kingswood	Federation house and garden	6 First Street	Lot 101, DP 1032987	Local	100
Kingswood	Milestone	Great Western Highway	Fronting Lot 1, DP 866081	Local	860
Kingswood	Milestone	Great Western Highway	Fronting Lot 10, DP 719064	Local	861
Kingswood	House	43 Park Avenue	Lot B, DP 409139	Local	672
Kingswood	Kingswood Public School	46-54 Second Avenue	Lot 172, DP 839785	Local	98
Kingswood	Teacher's residence (former)	56 Second Avenue	Lot 2, DP 1130750	Local	670
Leonay	"Edinglassie", house	22 Bunyan Road	Lot 185, DP 233104	Local	108
Leonay	"Leo Buring" cottage, barn, glasshouse and memorial	3a Leonay Parade	Lot 12, DP 818741	Local	109
Llandilo	Federation farmhouse	330 Eighth Avenue	Lot 330, DP 2147	Local	676
Llandilo	Farmhouse	361 Ninth Avenue	Lot 3, DP 231946	Local	677
Llandilo	Llandilo Public School	222 Seventh Avenue	Lot 222, DP 2147	Local	841
Llandilo	St David's Anglican Church (former)	257B Seventh Avenue	Lot 1, DP 724335	Local	673
Llandilo	Llandilo Community Hall	257C Seventh Avenue	Lot 11, DP 1092204	Local	675
Llandilo	Cottage and outbuildings	268 Seventh Avenue	Lot 269, DP 2147	Local	113
Llandilo	Farmhouse	170 Sixth Avenue	Lot A, DP 390397	Local	842

Londonderry	Londonderry Cemetery	325–331 Londonderry Road	Lot 100, DP 810236	Local	115
Luddenham	Luddenham Road Alignment	Luddenham Road		Local	843
Mulgoa	"Passadena", house	45-61 Allan Road	Lot 1, DP 227674	Local	132
Mulgoa	"Fairlight", homestead, outbuildings and gardens	377-429 Fairlight Road	Lot 22, DP 625510	State	140
Mulgoa	Table Rock Lookout	716-782 Fairlight Road	Lot A, DP 164835	Local	141
Mulgoa	"Glenleigh", estate	427–507 Mulgoa Road	Lot 2, DP 563748	State	273
Mulgoa	"Glenmore"	754-760 Mulgoa Road	Lot 3, DP 701949	State	124
Mulgoa	"Fernhill", house, outbuildings and landscape	1041-1117 Mulgoa Road	Lots 10 and 11, DP 615085; Lot 2, DP 541825	State	128
Mulgoa	"Fernhill", curtilage	1147–1187 Mulgoa Road and 10–156 Mayfair Road	Lot 100, DP 717549; Lot 1, DP 570484; Lot 6, DP 173159; Lot 5, DP 23781; Lot 12, DP 610186; Lot 2, DP 211795; Lots 1-4, DP 260373	Local	873
Mulgoa	Mulgoa Public School building, hall, residence and trees	1189-1193 Mulgoa Road	Lot 1, DP 853475	Local	130
Mulgoa	St Mary's Catholic Church	1262-1266 Mulgoa Road	Lot 10, Section E, DP 2121	Local	133
Mulgoa	Weatherboard cottage	1296 Mulgoa Road	Lot 2, DP 226343	Local	134
Mulgoa	Mulgoa Irrigation Company office and police station (former)	1298-1304 Mulgoa Road	Lot 32, DP 585921	Local	135
Mulgoa	Cottage	1306 Mulgoa Road	Lot 39, Section A, DP 2882	Local	136
Mulgoa	"Winbourne", house	1315 Mulgoa Road	Lot 4, DP 854076	Local	138

Mulgoa	St Thomas' Anglican Church and Cemetery	43-57 and 59-119 St Thomas Road	Lot 1, DP 996994; Lot 1, DP 1035490	State	126
Mulgoa	Cox's Cottage	1012-1046 Mulgoa Road and 2-24 St Thomas Road	Lots 2-4, DP 241971	State	125
Mulgoa	Mulgoa Road Alignment (former)	St Thomas Road		Local	844
Orchard Hills	Brick farmhouse	80-88 Caddens Road	Lot 6, DP 1344	Local	155
Orchard Hills	"Lindfield"	182-188 Caddens Road	Lot 1, DP 583439	Local	845
Orchard Hills	Water reservoir	197–207 Castle Road	Lot 1, DP 430473	Local	657
Orchard Hills	Orchard Hills Uniting Church	3 Frogmore Road	Lot 101, DP 128254	Local	156
Orchard Hills	Memorial cairn	Luddenham Road		Local	230
Orchard Hills	Mamre	181–275 Mamre Road	Lot 1, DP 530579	State	228
Orchard Hills	Memorial cairn	181-275 Mamre Road	Lot 1, DP 530579	Local	229
Orchard Hills	Leeholme Horse Stud Rotunda	391-395 Mamre Road	Lot 2, DP 547057	Local	232
Penrith	"Craithes", dwelling, trees, outbuildings and carriage loop	34-40 Borec Road	Lot 2, DP 802406	State	161
Penrith	Weir	Bruce Neale Drive, Nepean River		Local	848
Penrith	Weatherboard cottage	41-43 Camden Street	Lot 13, DP 712385	Local	695
Penrith	Edwardian cottage	2068 Castlereagh Road	Lot 3, DP 862636	Local	158
Penrith	Victorian house	2083-2089 Castlereagh Road	Lot 1, DP 623919	Local	160
Penrith	Bennetts Wagons	2151(a) Castlereagh Road	Lot 112 DP 774782	Local	829
Penrith	Penrith School of Arts (former)	7 Castlereagh Street	Lots 9-11, Section 1, DP 1582	Local	692
Penrith	Torin building	26 Coombes Drive	Lot 401-403, DP 1162312	State	827

Penrith	"Combewood", house, garden, trees and original entrance drive	234-256 Coreen Avenue	Lot 2, DP 654378; Lots 51-55, DP 237090	Local	163
Penrith	Cottage	169 Cox Avenue	Lot A, DP 984462	Local	853
Penrith	Thornton Hall	Thornton House 33 Mountain View Crescent, Penrith	Lot 2032, DP 1181618	Local	166
Penrith	Presbyterian manse (former)	154 Derby Street	Lot 4, DP 25106	Local	697
Penrith	Victorian cottage	163 Derby Street	Lot Y, DP 389668	Local	698
Penrith	Victorian cottage	194 Derby Street	Lot 1, DP 2363	Local	699
Penrith	Ferry crossing	Nepean River—Ferry Road		Local	870
Penrith	Governor Phillip Special Hospital—original building	64 Glebe Place	Lot 1, DP 213072	Local	174
Penrith	Rectory (former)	95 Glebe Place	Lots 5 and 5A, DP 39162	Local	173
Penrith	Victoria Bridge	Great Western Highway		State	146
Penrith	Penrith Infants Department (1884 building)	57 Henry Street	Lot 1, DP 724160	Local	177
Penrith	Methodist Church (former)	74 Henry Street	Lot 22, DP 586469	Local	179
Penrith	TAFE Building	115-119 Henry Street	Lot 111, DP 1028320	Local	689
Penrith	Penrith Council Chambers (former)	129-133 Henry Street	Lot 1123, DP 1106979	Local	189
Penrith	"Kelvin Brae", Federation house	142 High Street	Lot 1, DP 1127355	Local	854
Penrith	Penrith Public School and palm trees	194 High Street	Lot 2, DP 502608; Lots 2-4, Section 19, DP 2296	Local	210
Penrith	Victorian terrace and Interwar shop	219-221 High Street	Lot 2, DP 224062	Local	212
Penrith	St Aubyn's Terrace	255-265 High Street	Lot 3, DP 955837; Lot 4, DP 972	Local	209

Penrith	St Stephen's Anglican Church, Hall and Cemetery	258–280 High Street	Lots 101 and 102, DP 597910	Local	206
Penrith	Cottage	288 High Street	Lot 1, Section 3, DP 1582	Local	723
Penrith	Brick villa	318-320 High Street	Lot 4, Section 2, DP 1582	Local	711
Penrith	Memorials and lamp stand, St Nicholas of Myra Catholic Church	332-338 High Street	Lot 1, DP 782278	Local	688
Penrith	"Cram Place", coach house, well, pump and cast iron fence	338-340 High Street	Lot 11, DP 1013730	Local	201
Penrith	Bank of NSW (former)	354-360 High Street	Lot 10, SP 51611	Local	713
Penrith	Australian Arms Hotel	359 High Street	Lot 2, DP 513015	Local	196
Penrith	High Street shops	361-365 High Street	Lots 2 and 4, SP 13804	Local	714
Penrith	High Street shop	371-375 High Street	Lot 13, DP 616937	Local	715
Penrith	High Street shop	377-381 High Street	Lot 12, DP 616937	Local	716
Penrith	High Street shop	383 High Street	Lot 11, DP 616937	Local	717
Penrith	High Street shop	387-389 High Street	Lot 1, DP 774671	Local	718
Penrith	High Street shop	391-393 High Street	Lots 23 and 24, DP 236390	Local	719
Penrith	Memory Park	400 High Street	Lot 1, DP 198339	Local	200
Penrith	Fulton's Store (former)	413-423 High Street	Lot B, DP 322318	Local	197
Penrith	High Street shop	425-427 High Street	Lot A, DP 322318	Local	720
Penrith	High Street shop	437 High Street	Lot 2, DP 82325	Local	855
Penrith	High Street shop	449-451 High Street	Lot 12, DP 599349	Local	721
Penrith	High Street shop	538-540 High Street	Lot 1, DP 779550	Local	198
Penrith	High Street shop	542 High Street	Lot 2, DP 154388	Local	722
Penrith	High Street shop	550-556 High Street	Lot B, DP 152524	Local	199
Penrith	Red Cow Hotel	569-595 High Street	Lot 1, DP 1137699	Local	690

Penrit	:h	Penrith Ambulance Station	668-672 High Street	Lot 12, DP 37829	Local	256
Penrit	:h	"Madang Park", farmhouse and trees	475–487 Jamison Road	Lot 2, DP 567225	Local	95
Penri	:h	Station Master's House (former)	Jane Street	Lot 31, DP 1086586	State	187
Penrit	:h	Penrith Railway Station group	Railway land, Jane Street	Lot 31, DP 1086586	State	188
Penri	:h	The Lodge	48-56 Leland Street	Lot 5, DP 1049780	Local	159
Penrit	:h	Lemongrove Lodge	22-24 Lemongrove Road	Lot 1C, DP 162091	Local	172
Penrit	:h	Victorian villa	150 Lethbridge Street	Lot 81, DP 526298	Local	214
Penri	:h	Explorers Memorial	Memorial Avenue		Local	258
Penrit	:h	Pumping station (former)	20 Memorial Avenue	Lot 1, DP 233967	Local	144
Penrit	:h	Penrith Power Station (former)	1 Museum Drive	Lot 1306, DP 1234327	Local	259
Penri	:h	"Seidler", house	31-33 Nepean Avenue	Lot 1, DP 14827	Local	685
Penri	:h	Rowing course	Nepean River		Local	148
Penri	:h	Railway bridge	Over Nepean River		State	668
Penrit	:h	Weatherboard cottage	71 Parker Street	Lot 1, DP 996540	Local	175
Penrit	:h	Peachtree Creek Bridge	Peachtree Creek		Local	257
Penri	:h	Victorian house	6 Rawson Avenue	Lot 2, DP 206095	Local	253
Penrit	:h	Prospect Electricity building (former)	59 Station Street	Lot 10, DP 1025026	Local	701
Penrit	:h	"Broadville", Victorian house	98 Station Street	Lot 910, DP 717451	Local	215
Penri	:h	"Kentucky", villa	146 Station Street	Lot 11, DP 715161	Local	216
Penrit	:h	Victorian house	148 Station Street	Lot 80, DP 709313	Local	217
Penri	:h	"The Cottage", dwelling and pine tree	39 Warwick Street	Lot 11, DP 663880	Local	251

Penrith	"Minnamurra", house	43 Warwick Street	Lot 1, DP 173533	Local	696
Penrith	Victorian house, dwelling and camphor laurel tree	50 Warwick Street	Lot 1, DP 21745	Local	250
Penrith	Federation cottage	80 Woodriff Street	Lot 18, DP 2167	Local	847
Regentville	Regentville Workers' Terrace	1 Bundarra Road	Lots 1, 2 and 19, DP 16540	Local	276
Regentville	Regentville Public School, residence and garden	32-34 School House Road	Lot 1, DP 906651	Local	270
St Marys	Dunheved Fire Station	50 Christie Street	Lot 142, DP 31911	Local	655
St Marys	Explosives storehouse	146 Dunheved Circuit	Lot 131, DP 701610	Local	869
St Marys	Brick cottage	38 Gidley Street	Lot 1, DP 783200	Local	298
St Marys	Brick cottage	40 Gidley Street	Lot 1, DP 710777	Local	797
St Marys	"Bronte", villa	50 Gidley Street	Lot 4, DP 38617	Local	299
St Marys	Bennett Wagon	Pioneer Park, Great Western Highway	Lot B, DP 371329	Local	805
St Marys	Milestone	Great Western Highway (between Marsden Road and Day Street)		Local	304
St Marys	Victoria Park and memorial	Bounded by Great Western Highway, Pages Road, Putland and Princess Mary Streets	Lot 1, DP 1142771	Local	310
St Marys	St Marys General Cemetery	175-191 Great Western Highway	Lot 7300, DP 1141971	Local	303
St Marys	St Mary Magdalene Church, Hall, Cemetery and grounds	299-311 Great Western Highway	Lot 1, DP 1035601	Local	301
St Marys	"Mourilyan"	329-333 Great Western Highway	Lot 1, DP 997243	Local	300
St Marys	Shop	373 Great Western Highway	Lot 401, DP 601711	Local	806
St Marys	Wagon Wheel Hotel	449 Great Western Highway	Lot 102, DP 1031177	Local	308

St Marys	Wool Pack Inn (ruin)	556 Great Western Highway	Lot 1, DP 81099	Local	654
St Marys	St Marys Council Chambers (former)	2-6 Mamre Road	Lot 6, Section 1, DP 974985	Local	305
St Marys	"Margaret Farm", house, barn and tannery site	Pages Road, Barker, Wilson and Schleicher Streets	Lots 1-6, DP 30962	Local	226
St Marys	"Mimosa", stables (former)	11 Pages Road	Lot 1, DP 745809	Local	220
St Marys	"Mimosa", dwelling, fence and garden	13 Pages Road	Lot 40, DP 58974	Local	219
St Marys	Brick cottage	31-33 Pages Road	Lot 101, DP 833732	Local	801
St Marys	St Marys Public School	2-6 Princess Mary Street	Lot 1, DP 798964; Lot 1, DP 121443; Lot 1, DP 216092; Lot 1, DP 798965; Lot 2, DP 183835	Local	307
St Marys	Brick cottage	18 Princess Mary Street	Lot 104, DP 1037465	Local	309
St Marys	Weatherboard cottage	20 Princess Mary Street	Lot 13, DP 38418	Local	798
St Marys	Weatherboard cottage	22 Princess Mary Street	Lot 14, DP 38418	Local	799
St Marys	Gothic revival cottage	24 Princess Mary Street	Lot 15, DP 38418	Local	800
St Marys	"Thompson's Tannery" site, tannery pits (former) and well	94 Saddington Street	SP 73643; Lots 1-13, SP 73643	Local	235
St Marys	Brick cottage	100-104 Saddington Street	Lot 902, DP 1063929	Local	234
St Marys	Moore Cottage	8 Sainsbury Street	Lot 10, SP 72555	Local	221
St Marys	St Marys Railway Station	Corner Station and Queen Streets	Lot 1, DP 1040178	State	282
Wallacia	Bungalow	38 Greendale Road	Lot 60, DP 21083	Local	812
Wallacia	Wallacia Progress Association Hall	40 Greendale Road	Lot 61, DP 368083	Local	850
Wallacia	Brick house	96-100 Greendale Road	Lot 317, DP 808445	Local	811

Wallacia	Wallacia Public School	1573-1585 Mulgoa Road	Lot 50, DP 820512	Local	852
Wallacia	Wallacia Post Office	1589 Mulgoa Road	Lot 10, DP 1508	Local	851
Wallacia	Wallacia Hotel	1590-1594 Mulgoa Road	Part Lot A, DP 334601	Local	325
Wallacia	St Andrew's Anglican Church (former)	25 Park Road	Lot 1, DP 318587	Local	326
Werrington	"Torquay", house	555 Great Western Highway	Lot 11, DP 1170870	Local	319
Werrington	Brick house	565 Great Western Highway	Lot 565, DP 1121207	Local	810
Werrington	"Werrington Park House", garden and poplar avenue	653–729 Great Western Highway	Lot 101, DP 1140594	Local	315
Werrington	Rose Cottage and early slab hut	Corner of Water Street and Tennant Road	Lot 1, DP 827130	State	318
Werrington County	"Werrington House", dwelling, driveway and garden	108 Rugby Street	Lot 101, DP 605907	Local	248

Part 2 Heritage conservation areas

Name of heritage conservation area	Identification on Heritage Map	Significance
Hornseywood Avenue Conservation Area	Shown by an outline and identified as "HCA1"	Local
Lemongrove Conservation Area	Shown by an outline and identified as "HCA2"	Local
Warwick Street Conservation Area	Shown by an outline and identified as "HCA3"	Local
North St Marys Staff Cottages Conservation Area	Shown by an outline and identified as "HCA4"	Local
Mulgoa Road Conservation Area	Shown by an outline and identified as "HCA5"	Local
Park Road Conservation Area	Shown by an outline and identified as "HCA6"	Local


Part 3 Archaeological sites


Suburb	Item name	Address	Property description	Significance	Item no
Berkshire Park	Site of Berkshire Park homestead	844-848 Richmond Road	Lot 3, DP 1097876	Local	A662
Castlereagh	Site of Castlereagh township	East Wilchard Road and Church Lane	Various—see Heritage Map	Local	A30
Cranebrook	Castlereagh Genera Cemetery and native vegetation	132–156 Church Street, Cranebrook	Lot 245, DP 752021	Local	A880
Emu Plains	Police station (former)	30 Great Western Highway	Lot 8, DP 228204	Local	A53
Emu Plains	Government stockyard site	Hunter, Yodalla, Annett and Nepean Streets and River Road	Various—see Heritage Map	Local	A68
Emu Plains	"Dungarth" and remnant plantings site	4 Stockade Street	Lot 29, DP 250439	Local	A81
Leonay	Site of Edinglassie	Lapstone Place	Lot 102, DP 235829; Lot 2, DP 242718	Local	A112
Mulgoa	Irrigation canal	Mulgoa Road, Queenshill Drive, Littlefields Road and The Northern Road	Lots 5, 6, 8 and 9, DP 1046980; Lot 181, DP 230752; Lots 5 and 6, DP 718233	Local	A137
Mulgoa	Regentville Mansion (site) and vineyard terracing	460a-626 Mulgoa Road	Lot 40, DP 840788	Local	A271
Mulgoa	Slab cottage site	1177-1187 Mulgoa Road	Lot 6, DP 173159	Local	A858
Regentville	Regentville Windmill site	127–129 and 131–135 Martin Street	Lot 4, DP 249387; Lot 13, DP 633042	Local	A680
St Marys	Thompson's Tannery site (former)	Saddington Street	Various—see Heritage Map	Local	A236
Wallacia	Luddenham Homestead site	1-9 Park Road	Lots 1-3, DP 504928; Lots E-G, DP 390228	Local	A849





Appendix E Proposal Plans

September 2025 Page 60 of 61











Appendix F AHIMS Site Cards

September 2025 Page 61 of 61



Aboriginal Site Recording Form Manager, Information Systems

Locked Bag 5020, Parramatta 2124 NSW

AHIMS site II	D: 45-5-6025			Date recorded:	02-09-2025
014-1					
	n Information				
Site name:	Penrith Lakes 2	025 - AS1			
Easting:	285811	Northing: 6	265488	Coordinates must be	e in GDA94 (MGA)
Horizontal A	ccuracy (m):				
		<u></u>	-1		
Zone: 56			Phone GPS		
Recorder Inf (The person responsil	ormation ble for the completion and s	ubmission of this form)			
Title	Surname			First name	
Ms. Morr	is		Kate		
Organisation:	Virtus Heritage				
Address:	Suite 17/11-13	Pearl St, King	scliff NSW		
Phone: 0266	764354 E-m	ail: k.morris@	virtusherita	ge.com.au	
Site Context	Information				
Land Form Pattern:	Floodplain		Land Use:	Residential	
Land Form Unit:	Terrace		Vegetation	Cleared	
Distance to Water (m):	Prima Repor	. IATEUR DELI	tage ACHA 2	025	
How to get to the site:	Castlereagh, al	ong the northe	rn side of t	of 65 Old Castlereagh the road on exposures north-west corner	
Other site information:	any extent subs soil as a resul and other struc	urface artefact t of past land tures are presonant Ang	ts may have use and dis ent near the	es associated with fen moved within the top sturbance. Residential e scatter and PAD. Si on 24 Feb 2025, enter	0.3-0.6m of buildings te recorded

Site location map



Site plan



Site contents information	open/closed site: Open	Site condition: Disturbed
Features: 1. Artefact Feature condition: Disturbed Description:	Number of feature(s) feature(s) extent (m) 12 Length of width of feature(s) feature (s) extent (m) 150 100	Scarred Trees Scar Depth Regrowth (cm) (cm) Scar shape Tree Species
Artefact scatter comprising 12 a cm and 2x1.5x0.5 cm) Two tan qu quartzite broken flake One red flakes One greyish black basalt (4.5x3x1 cm and 2.5x2x1 cm)	artzite flakes (6x2.5x1.5 silcrete broken flake Thr	cm and 2.5x2x1.5 cm) One pink ree grey silcrete broken
Features: 2. Feature condition: Description:	Number of Length of Width of features extent (m) extent (m)	Scarred Trees Scar Depth Regrowth (cm) (cm) Scar shape Tree Species
Features: 3. Feature condition: Description:	Number of feature(s) feature (s) extent (m) extent (m)	Scarred Trees Scar Depth Regrowth (cm) (cm) Scar shape Tree Species

Features: 4. Feature condition: Description:	Number of feature(s) feature (s) extent (m) Number of feature(s) feature (s) extent (m)	Scarred Trees Scar Depth Regrowth (cm) (cm) Scar shape Tree Species
Feature condition: Description:	Number of feature(s) feature (s) extent (m) Length of width of feature (s) feature (s) extent (m)	Scarred Trees Scar Depth Regrowth (cm) Scar shape Tree Species

Site photographs



Description: Artefact detail, ventral surface of mudstone flake



Description: Artefact detail, basalt hand axe





Site restrict Do you want Restrict this	to	Gender General Location				
		. type: [-1/12]				
Why is this site	restricted?: 					
urther infor	mation contact					
Title	Surname	First name				
Ms. Mon	ris	Kate				
Organisation:	Virtus Heritage					
Address:	gscliff 2487 NSW					
Phone: 026	6764354 E-mail: k.morris@vi	irtusheritage.com.au				
- 11011e.	E-IIIaii.	ireasiierreage.com.aa				
Cita intonnu	-4-4:					
Site interp	etation and community statem	nent				
Site interpo	etation and community statem	nent				
Site interpr	etation and community statem	nent				
Site interpr	etation and community statem	nent				
Site interp	etation and community statem	nent				
Site interp	retation and community statem	nent				
Site interpr	etation and community statem	nent				
Site interpr	etation and community statem	nent				

v1.4 June 2022 5